

LEE'S SUMMIT FIRE DEPARTMENT

FIRE HEADQUARTERS
207 SE DOUGLAS STREET
LEE'S SUMMIT, MISSOURI 64063-2372
(816) 969-1300
FAX (816) 969-1313
TDD (816) 969-7407

PLANS REVIEW CONDITIONS

Permit No:	PRCOM20115556	Date: March 15, 2012
Project Title:	OUR LADY OF THE PRESENTATION	Applicant:
Location:	130 NW MURRAY RD.	Progressive Electronics
	LEES SUMMIT, MO 64081	6102 Arlington
Type of Work:		Raytown, MO 64133
Occupancy Group:	A-3	(816) 765-5750
Description:	INTERIOR REMODEL	
Construction Type:	Type IIB (Unprotected)	
Map Page:	195E	

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review

Reviewed By: Jim Eden

Released for Construction

1. 2006 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Action required: Call (816) 969-1300 to schedule a test.

2. The exterior horn strobe shall activate for water flow only. Verified at inspection.