

SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements.  
 Specific Requirements: Reach info: Bill Coday 816-803-4924 [/wc7681@att.com](mailto:wc7681@att.com). Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

## Project Number: A0592D2

<b>Project Name:</b>	FDR KSCYMO412118PA A0592D2
<b>Estimated In-Service Date:</b>	30-Jun-2026
<b>Project Description:</b>	AC IWM IFP* FEEDER, KSCYMO41 - (PSA KSCYMO412118PA)
<b>Mod Code:</b>	AAJUT 100%
<b>GEO LOC:</b>	EE4160
<b>FRC:</b>	845C
<b>Project Notes:</b>	<p>What: THIS PROJECT AUTHORIZES THE NECESSARY EXPENDITURES FOR ALL F1 WORK REQUIRED TO PROVIDE FOR IFP FTTP SERVICE AS PART OF THE 2025 IFP FTTP BUILD. (DISTRIBUTION WORK ON PROJECT A0592D3)</p> <p>Where: WIRECENTER KSCYMO41 PSA KSCYMO412118PA          06/04/2025, WP7253, PLANNING SUBMITTAL          KSCYMO41-EE4160-IFP*-905 SE 5TH TER-KSCYMO412118PA</p> <p>WHAT:</p> <p>THIS PROJECT PROVIDES FACILITIES FOR IFP PFP AT 905 SE 5TH TER</p> <p>MAJOR ITEMS OF WORK CONSIST OF:</p> <p>PLACE 1845 FEET OF 144 FIBER CABLE</p> <p>(3) SPLITTER(S) OF 1X64 USING SPLITTERS # ( )</p> <p>1845 FEET OF INNER-DUCT</p> <p>THE FIELD ENGINEER WILL SPECIFY SITE REQUIREMENTS AND HAS THE OPTION TO CHANGE EQUIPMENT TYPE AS NECESSARY.</p> <p>FIBERS ASSIGNED ARE:</p> <p>L2014, 409-411</p> <p>FIBERS ALLOCATED ARE:</p> <p>L2014, 412-420</p> <p>OLT INFO:</p> <p>OLT CLLI: KSCYMO41OL0010125121</p> <p>OLT JOB #:</p> <p>OLT TID:</p> <p>OLT RR:</p> <p>OLT SLOT: 10</p> <p>OLT PORTS:</p> <p>WHERE:</p> <p>PFP ADDRESS: 905 SE 5TH TER</p> <p>PSA ID: 2118PA</p> <p>WIRE CENTER: KSCYMO41</p> <p>Why: THE IFP FTTP PROGRAM MANAGEMENT TEAM HAS IDENTIFIED THIS WIRE CENTER AND PSA TO BE INCLUDED IN THE 2025 BUILD PROGRAM. THIS JOB WAS AUTO-CREATED FROM IWM.</p> <p>Why this way: THIS PROJECT WAS PLANNED ACCORDING TO THE IFP FTTP GUIDELINES.</p> <p>Why now: THIS PSA HAS BEEN ADDED TO THE IFP FTTP BUILD AND IS SCHEDULED FOR TURN-UP FOR IFP FTTP SERVICE IN 2025. ALL WORK NEEDS TO BE COMPLETED IN CONJUNCTION WITH THE CURRENT IFP FTTP SCHEDULE.</p>