SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements. Specific Requirements: Reach info: Bill Coday 816-803-4924 /wc7681@att.com. Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

Project Number: A05B7XB

<u> </u>	
Project Name:	EE4160-PFP* A05B7XB
Estimated In- Service Date:	26-Feb-2026
Project Description:	PFP*-KSCYMO41-250 NE Alura Way 15644224-KSCYMO411215PA
Mod Code:	FPPFP 100%
GEO LOC:	EE4160
FRC:	845C, 85C
Project Notes:	ADDENDUM 1: WP7253 10/1/25 ADDING \$20K TO JOB DUE TO MORE FOOTAGE THAN ORIGINALLY ESTIMATED. WHAT: THIS PROJECT PROVIDES FOR GREENFIELD - MDU AT TBD NEAR HH FID 15644224 MAJOR ITEMS OF WORK CONSIST OF: PLACING: 300 FEET OF 288 FIBER CABLE, PLACING (1) PFP SIZE 864, PLACE (6) 1X64 SPLITTER(S) USING SPLITTERS # (1-6), 300 FEET OF INNER-DUCT. THE FIELD ENGINEER WILL SPECIFY SITE REQUIREMENTS AND HAS THE OPTION TO CHANGE EQUIPMENT TYPE AS NECESSARY. FIBERS ASSIGNED: L2015, 1-6. FIBERS ALLOCATED: L2015, 7-24. SIX SPLITTERS DUE TO ESTIMATED 700 LU. WHERE: PFP ADDRESS: TBD NEAR HH FID 15644224 PSA ID: 1215PA WIRE CENTER: KSCYMO41. WHY: THIS WORK IS TRIGGERED BY KSCYMO411215PA DEVLOG 321906. PER ENG, APPROX 700 LU. WHY THIS WAY: LEES SUMMIT IS AN FTTP APPROVED WIRE CENTER AND THIS IS TRANSMITTED ONLY ON A FIBER MEDIUM. LEGACY T FIBERS WERE CONSIDERED BUT NOT USED FOR THIS PROJECT. IT HAS BEEN DETERMINED THAT THE CLOSEST ACCESS POINT TO ANY LEGACY T FIBERS WOULD MAKE THIS PROJECT MORE COSTLY THAN UTILIZING EXISTING LOOP FIBERS. THIS PFP IS SIZED TO PROVIDE SERVICE FOR 300 LIVING UNITS AND 40 BUSINESS UNITS. THIS PROJECT HAS BEEN PREPARED IN ACCORDANCE WITH THE CURRENT CLRS. THIS JOB DEPENDS ON THE COMPLETION OF BACKBONE JOB FOR ROUTE 1 A058ACY. WHY NOW: THE ESTIMATED IN SERVICE DATE IS 2026-02-26. PM TO DETERMINE FINAL OSP DUE DATE. PUBLIC NOTIFICATION OF NETWORK CHANGE IS NOT REQUIRED. THIS IS A COMPLETE
	WHY THIS WAY: LEES SUMMIT IS AN FTTP APPROVED WIRE CENTER AND THIS IS TRANSMITTED ONLY ON A FIBER MEDIUM. LEGACY T FIBERS WERE CONSIDERED BUT NOT USED FOR THIS PROJECT. IT HAS BEEN DETERMINED THAT THE CLOSEST ACCESS POINT TO ANY LEGACY T FIBERS WOULD MAKE THIS PROJECT MORE COSTLY THAN UTILIZING EXISTING LOOP FIBERS. THIS PFP IS SIZED TO PROVIDE SERVICE FOR 300 LIVING UNITS AND 40 BUSINESS UNITS. THIS PROJECT HAS BEEN PREPARED IN ACCORDANCE WITH THE CURRENT CLRS. THIS JOB DEPENDS ON THE COMPLETION OF BACKBONE JOB FOR ROUTE 1 A058ACY. WHY NOW: THE ESTIMATED IN SERVICE DATE IS 2026-02-26. PM TO DETERMINE FINAL OSP DUE