


# LEGACY LAKE DREDGING

## PARKS AND RECREATION DEPARTMENT

### CITY OF LEE'S SUMMIT, MISSOURI

#### PROJECT NO. 2025-PR-006



## VICINITY MAP

**11"x17" PLOT WILL BE  
HALF SCALE UNLESS  
OTHERWISE NOTED**

## SHEET INDEX

## GENERAL


|      |                   |
|------|-------------------|
| G001 | COVER SHEET       |
| G002 | LEGENDS AND NOTES |
| G003 | SOIL BORINGS      |
| G004 | SOIL BORINGS      |

## SITE PLANS

|      |                        |
|------|------------------------|
| C100 | OVERVIEW AND KEY MAP   |
| C101 | DREDGING PLAN          |
| C102 | SEDIMENT DISPOSAL      |
| C103 | DREDGING HEAT MAP      |
| C104 | SURFACE CROSS SECTIONS |

## DETAIL SHEETS

|      |         |
|------|---------|
| C501 | DETAILS |
| C502 | DETAILS |



PROJECT LOCATION  
LEGACY LAKE

**UTILITY COMPANIES**  
**BEFORE EXCAVATING CALL: 1 (800) DIG**

**BEFORE EXCAVATING CALL: 1 (800) DIG-RITE**

**GAS**  
**SPIRE ENERGY**  
**RICHI GARCIA**  
**(816) 507-0713**  
richi.garcia@spireenergy.com

**ELECTRICITY**  
**EVERGY**  
**RON DEJARNETTE**  
**(816) 347-4316**  
1105 SE US HWY 40  
**BLUE SPRINGS, MO 64014**  
ron.dejarnette@evergy.com

**TELEPHONE**  
**AT&T**  
**CRAIG PERKINS**  
**(816) 275-2721 500**  
East 8th Street, Room 1152  
Kansas City, MO 64106  
CP0772@att.com

**WATER & WASTEWATER**  
**LEE'S SUMMIT WATER UTILITIES**  
**(816) 969-1940**  
1200 SE HAMBLEN RD.  
**LEE'S SUMMIT, MO 64081**

**STREETS & STORMWATER**  
**PUBLIC WORKS OPERATIONS**  
**DIVISION**  
**(816) 969-1870**  
1971 SE HAMBLEN RD.  
**LEE'S SUMMIT, MO 64082**

**SCHOOLS**  
**LS R-7 SCHOOL DISTRICT**  
**TRANSPORTATION**  
**KEITH HENRY**  
**(816) 986-2405**

**LS R-7 SCHOOL DISTRICT**  
**FIBER OPTICS**  
**KINZIE WOODERSON**  
**(816) 986-105**

**CABLE**  
**COMCAST**  
**JIM DUFF**  
**(816) 795-2257**  
3400 NW DUNCAN RD.  
**BLUE SPRINGS, MO 64015**  
james\_duff@cable.comcast.com

**GOOGLE FIBER**  
**ANDREA SAKLA**  
**(415) 736-9962**  
908 BROADWAY BLVD.  
**KANSAS CITY, MO 64105**  
kc-google-uc@google.com

**SPECTRUM**  
**(816) 508-7287**  
**TROY PREWITT, STEVE BAXTER**  
8221 WEST 119TH STREET  
**OVERLAND PARK, KS 66213**  
troy@cablem.com  
steve.baxter@twcable.com



**NOTE:** KNOWN UNDERGROUND UTILITIES IN THE VICINITY OF THE WORK ARE SHOWN ON THESE PLANS, ALTHOUGH OTHERS MAY EXIST. THE LOCATIONS SHOWN ARE BELIEVED TO BE REASONABLY CORRECT, BUT DO NOT PURPORT TO BE ABSOLUTELY SO. BEFORE STARTING WORK, THE CONTRACTOR SHALL GIVE NOTICE TO AND OBTAIN INFORMATION FROM EACH OWNER AND OPERATOR OF EXISTING UNDERGROUND FACILITIES IN ACCORDANCE WITH THE MISSOURI UNDERGROUND FACILITY SAFETY AND DAMAGE PREVENTION STATUTE (RSMO CHAPTER 319.015 - 319.050).


[illegible]

**LEE'S SUMMIT**  
MISSOURI

PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

LEGACY LAKE DREDGING  
PROJECT NO. 2025-PR-006  
MMIT, JACKSON COUNTY, MISSOURI

COVER SHEET



|             |            |
|-------------|------------|
| DRAWN BY:   | DEO        |
| CHECKED BY: | WAW        |
| DATE:       | 05/12/2025 |
| PROJECT #:  | 10415715   |

**G001**

1. ALL WORK SHALL CONFORM TO AND BE PERFORMED IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REQUIREMENTS AND COMPLY WITH ALL APPLICABLE CODES AND ORDINANCES.
2. CONTRACTOR SHALL VISIT THE SITE AND INSPECT THE PROJECT AREA AND THOROUGHLY FAMILIARIZE THEMSELVES WITH THE ACTUAL JOB CONDITIONS PRIOR TO BIDDING AND THE START OF WORK. FAILURE TO VISIT THE PROJECT SITE SHALL NOT RELIEVE THE CONTRACTOR FROM PERFORMING THE WORK IN ACCORDANCE TO THE PLANS, SPECIFICATIONS, SPECIAL PROVISIONS AND CONTRACT.
3. CONTRACTOR SHALL THOROUGHLY REVIEW AND BECOME FAMILIAR WITH THE PROJECT PLANS, SPECIFICATIONS AND ANY SPECIAL CONDITIONS OF THE CONTRACT DOCUMENTS PRIOR TO BEGINNING CONSTRUCTION ON THE PROJECT.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS, PAYING ALL FEES AND FOR OTHERWISE COMPLYING WITH ALL APPLICABLE REGULATIONS GOVERNING THE WORK.
5. THE MEANS OF THE WORK AND SAFETY OF THE CONTRACTOR'S EMPLOYEES ARE SOLELY THE RESPONSIBILITY OF THE CONTRACTOR.
6. ANY WORK REQUIRED TO COMPLETE THE SCOPE OF THIS PROJECT BUT NOT SPECIFICALLY CALLED OUT, SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED FOR THE COMPLETION OF THIS WORK.
7. WORK WHICH DOES NOT CONFORM TO THE REQUIREMENTS OF THE CONTRACT WILL BE CONSIDERED UNACCEPTABLE. UNACCEPTABLE WORK, WHETHER THE RESULT OF POOR WORKMANSHIP, USE OF DEFECTIVE MATERIALS, DAMAGE THROUGH CARELESSNESS OR ANY OTHER CAUSE, FOUND TO EXIST PRIOR TO THE FINAL ACCEPTANCE OF THE WORK, SHALL BE REMOVED AND REPLACED IN AN ACCEPTABLE MANNER, AS REQUIRED BY THE OWNER AT THE CONTRACTOR'S EXPENSE.
8. NO WORK SHALL BE PERFORMED BEYOND THE PROJECT LIMITS WITHOUT PRIOR AUTHORIZATION FROM THE OWNER'S REPRESENTATIVE.
9. DO NOT RESTRICT DRAINAGE CHANNELS. CONTRACTOR SHALL BE AWARE OF EXISTING DRAINAGE CONDITIONS AND FACILITIES AND SHALL ENSURE DRAINAGE IS MAINTAINED DURING ALL PHASES OF CONSTRUCTION.
10. CONTRACTOR SHALL NOT BE ALLOWED TO WORK WEEKENDS OR HOLIDAYS WITHOUT REQUESTING PRIOR APPROVAL FROM THE OWNER THREE WORKING DAYS IN ADVANCE.
11. CONTRACTOR MUST MAINTAIN THRU TRAFFIC AT ALL TIMES. IF ONE LANE IS TEMPORARILY CLOSED, CONTRACTOR SHALL PROVIDE FLAGGERS AND SIGNAGE PER THE REQUIREMENTS OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
12. ALL WORK SHALL BE WITHIN EXISTING CITY LEE'S SUMMIT PARKS AND RECREATION (LSPR) PROPERTY, UTILITY EASEMENTS OR TEMPORARY EASEMENTS.
13. ALL EXISTING UTILITIES INDICATED ON THE DRAWINGS ARE ACCORDING TO THE BEST INFORMATION AVAILABLE TO THE ENGINEER; HOWEVER ALL UTILITIES ACTUALLY EXISTING MAY NOT BE SHOWN. UTILITIES DAMAGED THROUGH THE NEGLIGENCE OF THE CONTRACTOR TO OBTAIN THE EXACT LOCATION OF SAME SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT THEIR EXPENSE. CONTRACTOR SHALL HAVE EACH UTILITY MARKED BY MISSOURI-ONE-CALL.
14. CONTRACTOR SHALL NOTIFY LEES SUMMIT WATER UTILITIES DEPARTMENT AND LSPR OPERATIONS STAFF AT LEAST 48 HOURS IN ADVANCE OF ANY WORK INVOLVING CLOSING OR OPENING OF ANY WATER VALVES.
15. CONTRACTOR SHALL NOTIFY UTILITY OWNERS AT LEAST 48 HOURS IN ADVANCE OF ANY WORK BEING PERFORMED ACROSS AND/OR ADJACENT TO UTILITIES.
16. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING, AND IF DAMAGED, RESTORING EXISTING FACILITIES (CONCRETE, UTILITIES, FENCES, ETC.) TO PRE-CONSTRUCTION CONDITION OR EQUAL. NO PAYMENT WILL BE MADE FOR THIS RESTORATION UNLESS LISTED IN THE CONTRACT UNIT PRICES.
17. ALL DISTURBED AREAS, INCLUDING ACCESS AND HAUL ROADS, ARE TO BE REWORKED TO THEIR EXISTING CONDITIONS AND SEEDED. REFER TO SPECIFICATIONS FOR SEEDING REQUIREMENTS.
18. CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING SURVEY MONUMENTS WHICH INCLUDE RIGHT OF WAY MARKERS AND PROPERTY PINS. THE CONTRACTOR WILL BE REQUIRED TO REESTABLISH SURVEY MONUMENTS WHICH ARE DAMAGED OR DESTROYED BY CONSTRUCTION OPERATIONS. MONUMENTS SHALL BE REESTABLISHED BY A MISSOURI LICENSED LAND SURVEYOR IN ACCORDANCE WITH MISSOURI STATE LAWS AT CONTRACTOR'S EXPENSE.
19. CONTRACTOR SHALL AVOID DAMAGING TREES DURING THE PROJECT. ANY WORK THAT MAY DAMAGE TREES WILL BE ADDRESSED ON A CASE BY CASE BASIS.

1. EFFLUENT DISCHARGED FROM THE SEDIMENT CONTAINMENT BASIN SHALL BE NO GREATER THAN 25 NTU ABOVE THE AVERAGE LAKE TURBIDITY. CONTRACTOR SHALL ADJUST SEDIMENT CONTAINMENT BASIN OUTLET OR PROVIDE FLOATING TURBIDITY CURTAINS AS NECESSARY.
2. EFFLUENT TESTING SHALL BE DONE ON A DAILY BASIS AND LAKE TURBIDITY TESTED WEEKLY.
3. EFFLUENT TESTING SHALL BE TAKEN FROM DISCHARGE PIPE. LAKE TURBIDITY TESTING SHALL BE WITHIN THE VICINITY OF THE LAKE SPILLWAY.

1. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEPARTMENT OF NATURAL RESOURCES (DNR) NPDES PERMIT AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) REQUIREMENTS AND REQUIRED CONTAINMENT STRUCTURES. THE CONTRACTOR SHALL IMPLEMENT, MAINTAIN, COMPLETE REQUIRED INSPECTIONS, AND UPDATE THE SWPPP AS REQUIRED TO MEET ALL LOCAL, STATE, AND FEDERAL REQUIREMENTS.
2. CONTRACTORS SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMPs) AS REQUIRED BY THIS PLAN AND SWPPP.
3. BMPs AND CONTROLS SHALL CONFIRM CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.
4. CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL OR AS REQUIRED BY THE GENERAL PERMIT. CLEARING SHALL NOT OCCUR OUTSIDE THE PROJECT LIMITS SHOWN ON THE CONSTRUCTION PLANS UNLESS APPROVED BY THE OWNER IN WRITING.
5. EROSION AND SEDIMENT CONTROL (ESC) SHALL BE THE CONTRACTOR'S RESPONSIBILITY INCLUDING MAINTAINING ESC SYSTEMS, REPLACING DAMAGED OR FAILED ESC DEVICES, AND INSPECTING THE SITE IN ORDER TO REPAIR THE ESC SYSTEM WITHIN 24 HOURS AFTER A 1/2-INCH RAIN EVENT.
6. CONTRACTOR SHALL PROVIDE ADEQUATE ESC TO PREVENT SOIL AND/OR DEBRIS FROM ENTERING PAVEMENT, DITCHES, CREEKS, YARDS OR SURFACE WATERS. REPAIR OR DREDGE SURFACE WATERS THAT RECEIVE STORM WATER RUNOFF FROM THE PROJECT SITES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
7. STAGING LOCATION FOR CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE COORDINATED WITH AND APPROVED BY THE OWNER.
8. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLotation BOOMS SHALL BE MAINTAINED ON SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
9. DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
10. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEaled CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
11. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE INITIATED AS SOON AS PRACTICABLE.
12. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE SEEDDED BY THE CONTRACTOR. THESE AREAS SHALL BE SEEDDED NO LATER THAN 14 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS.
13. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
14. ON-SITE AND OFFSITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATION SHALL BE NOTED ON THE SITE MAP AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.
15. SLOPES SHALL BE LEFT IN ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.
16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURE (SILT FENCES, STRAW WATTLES, ETC.) TO PREVENT EROSION THROUGH THE DURATION OF THE PROJECT.
17. ALL CONSTRUCTION SHALL BE ESTABLISHED AT THE END OF EACH WORKING DAY. THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.
18. AN UPDATED COPY OF THE SWPPP SHALL BE KEPT ONSITE FOR THE DURATION OF THE PROJECT.
19. ALL SUBCONTRACTORS ENGAGED IN ACTIVITIES AT THE CONSTRUCTION SITE THAT COULD IMPACT STORM WATER MUST BE IDENTIFIED AND COMPLETE A CERTIFICATION STATEMENT PRIOR TO CONSTRUCTION.
20. CONTRACTOR SHALL BE RESPONSIBLE FOR STABILIZING ALL AREAS DISTURBED BY BASIN CONSTRUCTION INCLUDING ACCESS ROUTES, STAGING AREAS, AND STOCKPILE AREAS.
21. THIS PLAN SHOWS THE LOCATION AND DETAILS OF BMPs TO BE INSTALLED. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING EROSION AND DISCHARGE OF SEDIMENT AND OTHER POLLUTANTS FROM THE SITE AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE NECESSARY BMPs DURING ALL PHASES OF CONSTRUCTION REGARDLESS OF WHETHER THEY ARE SPECIFICALLY NOTED ON THIS PLAN, INCLUDING BMP ADDITIONS OR CHANGES APPROVED BY THE PROJECT MANAGER, AND SHALL MAINTAIN AND REPLACE CONTROLS AS NECESSARY DURING CONSTRUCTION TO CONTROL EROSION AND MINIMIZE THE DISCHARGE OF SEDIMENT AND OTHER POLLUTANTS FROM THE SITE.
22. SEDIMENT REMOVED FROM BMPs AND FACILITIES SHALL NOT BE PLACED ON STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES AND SHALL BE IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES. THE CONTRACTOR IS RESPONSIBLE FOR THE TEMPORARY PROTECTION AND STABILIZATION OF ALL SOIL STOCKPILES ON SITE AS WELL AS OFF-SITE BORROW AND FILL AREAS.
23. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT DEPOSITION, THE CONTRACTOR SHALL IMPLEMENT APPROPRIATE BMPs TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT DEPOSITION.
24. AFTER FINAL STABILIZATION HAS BEEN ACHIEVED WITH 70% PLANT DENSITY OVER 100% (WITH THE WATER QUALITY INSPECTORS APPROVAL) OF THE SITE OR OTHER PERMANENT MATERIALS, TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS SHALL BE STABILIZED IMMEDIATELY. THE CONTRACTOR OR THEIR REPRESENTATIVE MUST NOTIFY THE WATER QUALITY INSPECTOR TO SCHEDULE A MEETING AT THE SITE TO REVIEW FINAL STABILIZATION MEASURES AND REMOVAL OF THE SEDIMENT AND EROSION CONTROLS.

|        |                                  |
|--------|----------------------------------|
| APPROX | APPROXIMATELY                    |
| ARV    | AIR RELEASE VALVE                |
| BFV    | BUTTERFLY VALVE                  |
| BM     | BENCHMARK                        |
| BOL    | BEGINNING OF LINE                |
| DEPT   | DEPARTMENT                       |
| DI     | DUCTILE IRON                     |
| DIA    | DIAMETER                         |
| DND    | DO NOT DISTURB                   |
| E      | EAST                             |
| EA     | EACH                             |
| ESMT   | EASEMENT                         |
| ELEC   | ELECTRIC                         |
| EL     | ELEVATION                        |
| EOL    | END OF LINE                      |
| ENGR   | ENGINEER                         |
| ESC    | EROSION AND SEDIMENT CONTROL     |
| FO     | FIBER OPTIC                      |
| GV     | GATE VALVE                       |
| HDPE   | HIGH DENSITY POLYETHYLENE        |
| HOR    | HORIZONTAL                       |
| LN     | LANE                             |
| LF     | LINEAR FOOT                      |
| LS     | LUMP SUM                         |
| MODOT  | MISSOURI DEPT. OF TRANSPORTATION |
| MJ     | MECHANICAL JOINT                 |
| N      | NORTH                            |
| NTS    | NOT TO SCALE                     |
| PE     | POLYETHYLENE                     |
| PVC    | POLYVINYL CHLORIDE               |
| PC     | POWER & CABLE POLE               |
| PT     | POWER & TELEPHONE POLE           |
| PTC    | POWER, TELEPHONE, & CABLE POLE   |
| PROJ   | PROJECT                          |
| RJ     | RESTRAINED JOINT                 |
| R/W    | RIGHT OF WAY                     |
| S      | SOUTH                            |
| SF     | SILT FENCE                       |
| SS     | SANITARY SEWER                   |
| SSC    | SOLID SLEEVE COUPLING            |
| ST     | STORM SEWER                      |
| SW     | SOUTHWEST                        |
| SY     | SQUARE YARD                      |
| STA    | STATION                          |
| T/E    | TRASH ENCLOSURE                  |
| U.E.   | UTILITY ENCLOSURE                |
| UTIL   | UTILITY                          |
| W      | WEST                             |

| EXISTING                                                                            |                            | PROPOSED                                                                            |
|-------------------------------------------------------------------------------------|----------------------------|-------------------------------------------------------------------------------------|
|  | WATER VALVE                |  |
|  | WATER METER                |  |
|  | SANITARY SEWER MANHOLE     |                                                                                     |
|  | POWER/TRAFFIC SIGNAL POLE  |                                                                                     |
|  | FIRE HYDRANT               |  |
|  | TREE/LARGE BRUSH           |                                                                                     |
|  | STORM INLET/JUNCTION BOX   |                                                                                     |
|  | GAS METER                  |                                                                                     |
|  | MAIL BOX                   |                                                                                     |
|  | POWER POLE                 |                                                                                     |
|  | POWER ANCHOR               |                                                                                     |
|  | SIDEWALK                   |                                                                                     |
|  | UNDERGROUND UTILITY MARKER |                                                                                     |
|  | OVERHEAD ELECTRIC          |                                                                                     |
|  | UNDERGROUND ELECTRIC       |                                                                                     |
|  | SANITARY SEWER             |                                                                                     |
|  | WATER LINE                 |  |
|  | STORM SEWER                |                                                                                     |
|  | UNDERGROUND GAS LINE       |                                                                                     |
|  | UNDERGROUND TELEPHONE      |                                                                                     |
|  | UNDERGROUND FIBER OPTIC    |                                                                                     |
|  | UNDERGROUND CABLE TV       |                                                                                     |
|  | SECTION LINE               |                                                                                     |
|  | RIGHT-OF-WAY LINE          |                                                                                     |
|  | LOT LINE                   |                                                                                     |
|  | PERMANENT EASEMENT LINE    |                                                                                     |
|  | TEMPORARY EASEMENT LINE    |                                                                                     |
|                                                                                     | SECTION VIEW               |  |

[illegible]



Surface Elevation 971Completion Date: 10/28/24

Datum NAVD88

DEPTH IN FEET

DESCRIPTION OF MATERIAL

ROOT ZONE - 12 inches

CLAY - brown, stiff, fat - CH

Auger refusal at 11.5 feet.

GRAPHIC LOG

DRY UNIT WEIGHT (pcf)  
SPT BLOW COUNTS  
CORE RECOVERY/ROD

SAMPLES

3-4-6 SS1

4-4-6 SS2

SHEAR STRENGTH, tsf

STANDARD PENETRATION RESISTANCE (ASTM D 1586)

WATER CONTENT, %

GROUNDWATER DATA

DRILLING DATA

U.S. Environmental Protection Agency

Legacy Park Lake Dredge  
Lee's Summit, Missouri

LOG OF BORING: B- 6

Project No. J046831.01

Surface Elevation 977Completion Date: 10/28/24

Datum NAVD88

DEPTH IN FEET

DESCRIPTION OF MATERIAL

ROOT ZONE - 12 inches

CLAY - brown and gray to yellow brown and gray, stiff and very stiff, fat - CH

shaley, some gravel

Auger refusal at 12.5 feet.

GRAPHIC LOG

DRY UNIT WEIGHT (pcf)  
SPT BLOW COUNTS  
CORE RECOVERY/ROD

SAMPLES

6-8-8 SS1

4-6-9 SS2

SHEAR STRENGTH, tsf

STANDARD PENETRATION RESISTANCE (ASTM D 1586)

WATER CONTENT, %

GROUNDWATER DATA

DRILLING DATA

U.S. Environmental Protection Agency

Legacy Park Lake Dredge  
Lee's Summit, Missouri

LOG OF BORING: B- 7

Project No. J046831.01

Surface Elevation 983Completion Date: 10/28/24

Datum NAVD88

DEPTH IN FEET

DESCRIPTION OF MATERIAL

ROOT ZONE - 12 inches

CLAY - red brown to yellow brown and gray, medium stiff and stiff, fat - CH

some gravel

Weathered SHALE

Auger refusal at 16.5 feet.

GRAPHIC LOG

DRY UNIT WEIGHT (pcf)  
SPT BLOW COUNTS  
CORE RECOVERY/ROD

SAMPLES

5-6-6 SS1

2-3-4 SS2

8-17-24 SS3

SHEAR STRENGTH, tsf

STANDARD PENETRATION RESISTANCE (ASTM D 1586)

WATER CONTENT, %

GROUNDWATER DATA

DRILLING DATA

U.S. Environmental Protection Agency

Legacy Park Lake Dredge  
Lee's Summit, Missouri

LOG OF BORING: B- 8

Project No. J046831.01

Surface Elevation 968Completion Date: 10/28/24

Datum NAVD88

DEPTH IN FEET

DESCRIPTION OF MATERIAL

ROOT ZONE - 12 inches

CLAY - brown to reddish brown, medium stiff and stiff, fat - CH

weathered limestone fragments

Auger refusal at 10.5 feet.

GRAPHIC LOG

DRY UNIT WEIGHT (pcf)  
SPT BLOW COUNTS  
CORE RECOVERY/ROD

SAMPLES

4-7-6 SS1

3-4-3 SS2

SHEAR STRENGTH, tsf

STANDARD PENETRATION RESISTANCE (ASTM D 1586)

WATER CONTENT, %

GROUNDWATER DATA

DRILLING DATA

U.S. Environmental Protection Agency

Legacy Park Lake Dredge  
Lee's Summit, Missouri

LOG OF BORING: B- 9

Project No. J046831.01

Surface Elevation 973Completion Date: 10/28/24

Datum NAVD88

DEPTH IN FEET

DESCRIPTION OF MATERIAL

ROOT ZONE - 12 inches

CLAY - brown to yellow brown, stiff, fat - CH

Auger refusal at 11.5 feet.

GRAPHIC LOG

DRY UNIT WEIGHT (pcf)  
SPT BLOW COUNTS  
CORE RECOVERY/ROD

SAMPLES

4-5-6 SS1

2-4-6 SS2

SHEAR STRENGTH, tsf

STANDARD PENETRATION RESISTANCE (ASTM D 1586)

WATER CONTENT, %

GROUNDWATER DATA

DRILLING DATA

U.S. Environmental Protection Agency

Legacy Park Lake Dredge  
Lee's Summit, Missouri

LOG OF BORING: B-10

Project No. J046831.01

DATE

DESCRIPTION

REV


LEE'S SUMMIT  
MISSOURI

PROJECT: LEGACY LAKE DREDGING  
PROJECT NO. 2025-PR-006  
LEE'S SUMMIT, JACKSON COUNTY, MISSOURI  
SHEET NAME: SOIL BORINGS

WESLEY A. WEIMER  
NUMBER  
PE-2019017908  
DRAWN BY: DEO  
CHECKED BY: WAW  
DATE: 05/12/2025  
PROJECT #: 10415715

G004





|                     |                                                                                     |     |
|---------------------|-------------------------------------------------------------------------------------|-----|
| EXISTING CONTOURS   |  | 965 |
| PROPOSED CONTOURS   |  | 965 |
| EDGE OF WATER       |  |     |
| 100 YEAR FLOOD LINE |  |     |
| 500 YEAR FLOOD LINE |  |     |
| CONTROL POINT       |  |     |
| BENCHMARK           |  |     |
| AREA OF INTEREST    |  |     |

1. CONTRACTOR TO COORDINATE STAGING AREA WITH LEE'S SUMMIT PARKS AND RECREATION (LSPR) AT PRE-CONSTRUCTION MEETING.
2. LAYDOWN AND STAGING OF EQUIPMENT IS NOT ALLOWED IN EXISTING PARKING LOTS.
3. CONTRACTOR TO PROVIDE CONTINUOUS ACCESS TO PARK FACILITIES DURING PARK HOURS.
4. 48 HOURS NOTICE SHOULD BE GIVEN TO LSPR PRIOR TO DELIVERIES OF EQUIPMENT AND MATERIALS. CONTACT BROOKE CHESTNUT AT PHONE NUMBER (816) 969-1575

1. CONTRACTOR TO COORDINATE LOCATION OF BOAT RAMP WITH LSPR AT PRE-CONSTRUCTION MEETING.
2. CONTRACTOR SHALL PROTECT EXISTING PAVEMENT WITH MATS. ANY CRACKED OR DAMAGED PAVEMENT WILL BE REPAIRED AT CONTRACTOR'S EXPENSE.

1. DREDGING SHALL COMMENCE AT THE NORTH END OF THE DREDGING AREA AND PROGRESS TOWARDS THE SOUTH. COORDINATE WITH LSPR.
2. THE PLANS PROVIDE THE DREDGING TEMPLATE AND INDICATE PROPOSED DREDGING ELEVATIONS AND DEPTHS. ELECTRONIC FILES WILL BE MADE AVAILABLE FOR THE CONTRACTOR'S USE UPON REQUEST. A  $\pm 12"$  DREDGING TOLERANCE OR DEVIATION FROM THE PROPOSED DREDGING TEMPLATE IS ALLOWED. REFER TO PROJECT SPECIFICATIONS.
3. SURVEYS FOR MEASUREMENT/PAYMENT AND PROJECT ACCEPTANCE WILL BE PROVIDED BY THE CONTRACTOR. REFER TO PROJECT SPECIFICATIONS.
4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO TRACK PROGRESS AND STOP WORK WHEN THE ALLOWABLE REMOVAL QUANTITY HAS BEEN ACHIEVED. REFER TO THE PROJECT SPECIFICATIONS.
5. REFER TO THE PROJECT SPECIFICATIONS FOR RETURN WATER QUALITY REQUIREMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING WATER QUALITY AND ADJUSTING OPERATIONS AS REQUIRED TO MEET STANDARDS. REFER TO PROJECT SPECIFICATIONS.

1. DREDGING TO REMOVE 50,000 CY OF IN SITU MATERIAL.
2. NO DREDGING SHALL OCCUR WITHIN 20' OF ANY EXISTING STRUCTURE.
3. DREDGING SHALL BE COMPLETED TO REMOVE ACCUMULATED SEDIMENT TO THE PROPOSED ELEVATIONS. A SIDE SLOPE OF 1H:1V FROM DREDGING LIMITS IS ANTICIPATED.
4. ESTIMATED REMOVAL DEPTHS ARE NOTED ON SHEET C103.
5. LEGACY LAKE IS SUBJECT TO WATER LEVEL FLUCTUATIONS INFLUENCED BY GROUNDWATER INTERACTION, EVAPORATION, AND PRECIPITATION. REFER TO PLANS FOR OBSERVED WATER SURFACE ELEVATION AT TIME OF SURVEY.
6. LEGACY LAKE IS EQUIPPED WITH AN IRRIGATION INTAKE. CONTRACTOR TO AVOID DAMAGE TO THE IRRIGATION SYSTEM AND COORDINATE PHASING OF WORK WITH OWNER.


[illegible]

**LEE'S SUMMIT**  
MISSOURI

**PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063**

CT: LEGACY LAKE DREDGING  
PROJECT NO. 2025-PR-006  
LEE'S SUMMIT, JACKSON COUNTY, MISSOURI

## DREDGING PLAN




|                    |                   |
|--------------------|-------------------|
| <b>DRAWN BY:</b>   | <b>DEO</b>        |
| <b>CHECKED BY:</b> | <b>WAW</b>        |
| <b>DATE:</b>       | <b>05/27/2025</b> |
| <b>PROJECT #:</b>  | <b>10415715</b>   |

# C101







[illegible]


**LS** **LEE'S SUMMIT**  
MISSOURI

PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

PROJECT: LEGACY LAKE DREDGING  
PROJECT NO. 2025-PR-006  
LEE'S SUMMIT, JACKSON COUNTY, MISSOURI



**SHEET NAME:**

## DETAILS




|             |            |
|-------------|------------|
| DRAWN BY:   | DEO        |
| CHECKED BY: | WAW        |
| DATE:       | 05/27/2025 |
| PROJECT #:  | 10415715   |

# C501



- STOCKPILE PROTECTION MAINTENANCE NOTES:**
1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
  2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
  3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
  4. IF PERIMETER PROTECTION MUST BE MOVED TO ACCESS SOIL STOCKPILE, REPLACE PERIMETER CONTROLS BY THE END OF THE WORKDAY.
  5. STOCKPILE PERIMETER CONTROLS CAN BE REMOVED ONCE ALL THE MATERIAL FROM THE STOCKPILE HAS BEEN USED.

[illegible]

**LS** **LEE'S SUMMIT**  
MISSOURI


PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

LEGACY LAKE DREDGING  
PROJECT NO. 2025-PR-006  
MMIT, JACKSON COUNTY, MISSOURI

LEE'S SUMMIT, JACKSON COUNTY, MISSOURI

**SHEET NAME:**

## DETAILS



|                    |                   |
|--------------------|-------------------|
| <b>DRAWN BY:</b>   | <b>DEO</b>        |
| <b>CHECKED BY:</b> | <b>WAW</b>        |
| <b>DATE:</b>       | <b>05/12/2025</b> |
| <b>PROJECT #:</b>  | <b>10415715</b>   |

# C502