

RE: Roof - 8 Inch Heel -

Site Information:

Project Customer: Clayton Properties Project Name: Carolina Modern Prairie 3 Car

Lot/Block: 0370

Subdivision: BAILEY FARMS

Model: Carolina Modern Prairie 3 Car

Address: 1126 SE RANGLAND

City: LEE'S SUMMIT

State: MO

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2018/TPI2014

Wind Code: ASCE 7-16

Wind Speed: 115 mph

Roof Load: 45.0 psf

Mean Roof Height (feet): 35

Design Program: MiTek 20/20 8.6

Design Method: MWFRS (Envelope)/C-C hybrid Wind ASCE 7-16

Floor Load: N/A psf

Exposure Category: C

MiTek, Inc.

16023 Swingley Ridge Rd.
Chesterfield, MO 63017
314.434.1200

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I75763731	A1	8/20/25	35	I75763765	J4	8/20/25
2	I75763732	A2	8/20/25	36	I75763766	J5	8/20/25
3	I75763733	A3	8/20/25	37	I75763767	J6	8/20/25
4	I75763734	A4	8/20/25	38	I75763768	J7	8/20/25
5	I75763735	A5	8/20/25	39	I75763769	M1	8/20/25
6	I75763736	A6	8/20/25	40	I75763770	M2	8/20/25
7	I75763737	A7	8/20/25	41	I75763771	M3	8/20/25
8	I75763738	A8	8/20/25	42	I75763772	M4	8/20/25
9	I75763739	A9	8/20/25	43	I75763773	M5	8/20/25
10	I75763740	A10	8/20/25	44	I75763774	M6	8/20/25
11	I75763741	A11	8/20/25	45	I75763775	M7	8/20/25
12	I75763742	A12	8/20/25	46	I75763776	V1	8/20/25
13	I75763743	A13	8/20/25	47	I75763777	V2	8/20/25
14	I75763744	A14	8/20/25				
15	I75763745	A15	8/20/25				
16	I75763746	A16	8/20/25				
17	I75763747	A17	8/20/25				
18	I75763748	A18	8/20/25				
19	I75763749	B1	8/20/25				
20	I75763750	B2	8/20/25				
21	I75763751	B3	8/20/25				
22	I75763752	C1	8/20/25				
23	I75763753	CG1	8/20/25				
24	I75763754	CG2	8/20/25				
25	I75763755	CG3	8/20/25				
26	I75763756	D1	8/20/25				
27	I75763757	D2	8/20/25				
28	I75763758	HG1	8/20/25				
29	I75763759	HG2	8/20/25				
30	I75763760	HG3	8/20/25				
31	I75763761	HG4	8/20/25				
32	I75763762	J1	8/20/25				
33	I75763763	J2	8/20/25				
34	I75763764	J3	8/20/25				

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision based on the parameters
provided by Premier Building Supply (Springhill, KS)20300 W 207th Street.


Truss Design Engineer's Name: Lu, Jie

My license renewal date for the state of Missouri is December 31, 2026.

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:54 Page: 1
ID:KAaTahamYSUzEEtzV7quzbFH -RfC?PsB70Hg3NSgPqnL8w3ulTXbGKWrCdoi7J4zJC?f

[illegible]

- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Unbalanced roof live loads have been considered for this design.
- 4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCdL=6.0psf, BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) Interior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 5-11-4, Exterior(2R) 5-11-4 to 13-0-2, Interior (1) 13-0-2 to 24-0-12, Exterior(2E) 24-0-12 to 30-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) All bearings are assumed to be SPF No.2 crushing capacity of 425 psi.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 749 lb uplift at joint 2 and 748 lb uplift at joint 8.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 11) "NAILED" indicates Girder: 3-16d (0.162" x 3.5") toenails per NDS guidelines.
- 12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 420 lb down and 109 lb up at 5-11-4, and 420 lb down and 109 lb up at 24-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15,
Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-70, 3-7=-70, 7-9=-70, 2-8=-20
Concentrated Loads (lb)
Vert: 3=-131 (B), 5=-131 (B), 14=-39 (B), 15=-420
(B), 10=-420 (B), 7=-131 (B), 11=-39 (B), 13=-39 (B),
12=-39 (B), 4=-131 (B), 6=-131 (B), 17=-131 (B),
18=-131 (B), 20=-131 (B), 22=-131 (B), 23=-131 (B),
25=-39 (B), 26=-39 (B), 27=-39 (B), 28=-39 (B)

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x3 - 1 row at 0-9-0 oc.



August 20, 2025

 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

WARNING – Verify design parameters and READ NOTES ON THIS and INCLUDED LITERATURE REFERENCE (see MP14743 rev. 12/2022) BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

Mitek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
16023 Swinley Ridge Rd
Crested Butte, MO 68016
402.414.0200 MitekUS
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:32


Job	Truss	Truss Type	Qty	Ply	175763732
Roof - 8 Inch Heel	A2	Hip	1	1	Job Reference (optional)

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:55

Page: 1

ID:oM8ro1bOJl3LBmpQQg0MM5zbfGz-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRcDOI7J4zJC?f



Scale = 1:56.6

Plate Offsets (X, Y): [2:0-3-13,0-1-5], [9:0-3-13,0-1-5]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.25	12	>999	240	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.96	Vert(CT)	-0.48	12-14	>755	180	
BCLL	0.0	Rep Stress Incr	YES	WB	0.69	Horz(CT)	0.15	9	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							
Weight: 124 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E *Except* 4-7:2x4 SP No.2
 BOT CHORD 2x4 SP No.2
 WEBS 2x3 SPF No.2
 SLIDER Left 2x4 SP No.2 -- 4-1-2, Right 2x4 SP No.2 -- 4-1-2

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-2-2 oc purlins, except 2-0-0 oc purlins (2-6-7 max.): 4-7.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

REACTIONS

(size) 2=0-5-8, 9=0-5-8
 Max Horiz 2=-54 (LC 13)
 Max Uplift 2=-319 (LC 8), 9=-319 (LC 9)
 Max Grav 2=1411 (LC 1), 9=1411 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-5/0, 2-4=-2973/757, 4-5=-2691/750, 5-6=-3468/916, 6-7=-2691/750, 7-9=-2973/756, 9-10=-5/0
 BOT CHORD 2-14=-611/2710, 12-14=-829/3404, 11-12=-836/3404, 9-11=-614/2710
 WEBS 4-14=-59/697, 7-11=-58/697, 5-12=0/188, 5-14=-991/269, 6-12=0/188, 6-11=-991/269

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 7-11-4, Exterior(2R) 7-11-4 to 15-0-2, Interior (1) 15-0-2 to 22-0-12, Exterior(2R) 22-0-12 to 29-1-10, Interior (1) 29-1-10 to 30-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip
- Provide adequate drainage to prevent water ponding.
- All plates are 3x4 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 319 lb uplift at joint 2 and 319 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:32


Job	Truss	Truss Type	Qty	Ply	175763733
Roof - 8 Inch Heel	A3	Hip	1	1	Job Reference (optional)

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:55

Page: 1

ID:klGcDiderNJ2Q4zpY52qRWzbfGx-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:56.6

Plate Offsets (X, Y): [2:0-3-13,0-1-5], [10:0-3-13,0-1-5], [10:Edge,0-0-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.85	Vert(LL)	-0.20	13	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.44	Vert(CT)	-0.43	2-15	>843	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.09	10	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 128 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP 2400F 2.0E
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 2-8-3, Right 2x4 SP No.2 -- 2-8-3

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except 2-0-0 oc purlins (3-1-1 max.): 5-7.
BOT CHORD Rigid ceiling directly applied or 9-5-0 oc bracing.

REACTIONS

(size) 2=0-5-8, 10=0-5-8
Max Horiz 2=-67 (LC 13)
Max Uplift 2=-310 (LC 8), 10=-310 (LC 9)
Max Grav 2=1411 (LC 1), 10=1411 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-5/0, 2-4=-2968/878, 4-5=-2701/736, 5-6=-2878/866, 6-7=-2878/866, 7-8=-2701/736, 8-10=-2968/878, 10-11=-5/0
BOT CHORD 2-15=-762/2691, 13-15=-568/2531, 12-13=-564/2531, 10-12=-758/2691
WEBS 5-15=0/351, 5-13=-187/569, 6-13=-448/226, 7-13=-187/569, 7-12=0/351, 4-15=-199/232, 8-12=-199/232

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 9-11-4, Exterior(2R) 9-11-4 to 17-0-2, Interior (1) 17-0-2 to 20-0-12, Exterior(2R) 20-0-12 to 27-1-10, Interior (1) 27-1-10 to 30-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SP 2400F 2.0E crushing capacity of 805 psi.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 310 lb uplift at joint 2 and 310 lb uplift at joint 10.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:32


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A4	Hip	1	1	175763734
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:55

Page: 1

ID:Cxq_Q2eGcgRv2EY?6oa3_kzbfGw-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4JC?f



Scale = 1:56.7

Plate Offsets (X, Y): [2:0-3-13,0-1-5], [9:0-3-13,0-1-5]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.20	14-15	>999	240	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(CT)	-0.38	12-14	>945	180	197/144
BCLL	0.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.13	9	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							
Weight: 129 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 3-2-0, Right 2x4 SP No.2 -- 3-2-0

BRACING

TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (2-2-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 6-10-7 oc bracing.

REACTIONS

(size) 2=0-5-8, 9=0-5-8
Max Horiz 2=79 (LC 12)
Max Uplift 2=-298 (LC 8), 9=-298 (LC 9)
Max Grav 2=1411 (LC 1), 9=1411 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-5/0, 2-4=-3028/823, 4-5=-2489/736, 5-6=-2306/761, 6-7=-2490/758, 7-9=-3027/850, 9-10=-5/0
BOT CHORD 2-15=-709/2752, 14-15=-709/2752, 12-14=-535/2305, 11-12=-731/2752, 9-11=-731/2752
WEBS 4-15=0/228, 4-14=-517/211, 5-14=-9/365, 5-12=-221/222, 6-12=-11/365, 7-12=-517/212, 7-11=0/227

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8,
Interior (1) 4-1-8 to 11-11-4, Exterior(2E) 11-11-4 to
18-0-12, Exterior(2R) 18-0-12 to 25-1-10, Interior (1)
25-1-10 to 30-10-8 zone; cantilever left and right
exposed ; end vertical left and right exposed;C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SP No.2 crushing
capacity of 565 psi.
- 6) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 298 lb uplift at
joint 2 and 298 lb uplift at joint 9.
- 7) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A5	Roof Special	1	1	175763735
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:56

Page: 1

ID:uQhwP9vZHkQCOF6WEGVXhazbfJ9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:59.5

Plate Offsets (X, Y): [7:0-3-13,0-1-5], [11:0-2-4,0-3-0], [13:0-2-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.18	12-13	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.80	Vert(CT)	-0.37	12-13	>948	180		
BCLL	0.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.10	7	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 131 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E *Except* 3-4:2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Right 2x4 SP No.2 -- 3-6-0

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-5-11 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-7 max.): 1-2, 3-4.
BOT CHORD Rigid ceiling directly applied or 7-7-1 oc bracing.

WEBS 1 Row at midpt 5-10

REACTIONS (size) 7=0-5-8, 14= Mechanical
Max Horiz 14=-99 (LC 17)
Max Uplift 7=-278 (LC 9), 14=-244 (LC 8)
Max Grav 7=1387 (LC 1), 14=1324 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-14=-1262/386, 1-2=-2653/672,
2-3=-2190/583, 3-4=-2005/596,
4-5=-2194/584, 5-7=-2970/709, 7-8=-5/0
BOT CHORD 13-14=-52/135, 12-13=-554/2613,
10-12=-379/1994, 9-10=-593/2712,
7-9=-593/2712

WEBS 2-12=-703/185, 3-12=-9/331, 3-10=-208/251,
4-10=-60/373, 5-10=-797/263, 5-9=0/290,
2-13=-913/361, 1-13=-706/2805

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-1-4 to 5-1-4,
Interior (1) 5-1-4 to 13-5-12, Exterior(2E) 13-5-12 to
15-7-4, Exterior(2R) 15-7-4 to 20-7-4, Interior (1) 20-7-4
to 30-5-0 zone; cantilever left and right exposed ; end
vertical left and right exposed; C-C for members and
forces & MWFRS for reactions shown; Lumber
DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 5) Bearings are assumed to be: , Joint 7 SP No.2 crushing
capacity of 565 psi.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 244 lb uplift at
joint 14 and 278 lb uplift at joint 7.
- 8) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard




August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A6	Roof Special	1	1	175763736
Job Reference (optional)					



Scale = 1:59.6

Plate Offsets (X, Y): [5:0-2-8,0-3-4], [8:0-3-13,0-1-5], [13:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.99	Vert(LL)	-0.20	10-11	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.86	Vert(CT)	-0.46	10-11	>764	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.97	Horz(CT)	0.11	8	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 128 lb	FT = 20%

LUMBER			2) Wind: ASCE 7-16; Vult=115mph (3-second gust)		
TOP CHORD	2x4 SP No.2		Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;		
BOT CHORD	2x4 SP No.2		Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)		
WEBS	2x3 SPF No.2		exterior zone and C-C Exterior(2E) 0-1-4 to 5-1-4,		
SLIDER	Right 2x4 SP No.2 -- 2-6-7		Interior (1) 5-1-4 to 14-6-8, Exterior(2R) 14-6-8 to		
BRACING			19-6-8, Interior (1) 19-6-8 to 30-5-0 zone; cantilever left		
TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (3-6-14 max.): 1-3.		and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip		
BOT CHORD	Rigid ceiling directly applied or 7-8-11 oc bracing.		DOL=1.60		
WEBS	1 Row at midpt	2-14	3) Provide adequate drainage to prevent water ponding.		
REACTIONS (size)			4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.		
	8=0-5-8, 14= Mechanical		5) Bearings are assumed to be: , Joint 8 SP No.2 crushing capacity of 565 psi.		
	Max Horiz 14=-115 (LC 10)		6) Refer to girder(s) for truss to truss connections.		
	Max Uplift 8=-268 (LC 9), 14=-239 (LC 8)		7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 14 and 268 lb uplift at joint 8.		
	Max Grav 8=1387 (LC 1), 14=1324 (LC 1)		8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.		
FORCES (lb) - Maximum Compression/Maximum Tension			9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.		
TOP CHORD	1-14=-124/71, 1-2=-84/67, 2-3=-2519/624, 3-4=-2039/525, 4-6=-2793/664, 6-8=-2935/680, 8-9=-5/0		LOAD CASE(S) Standard		
BOT CHORD	13-14=-292/1474, 11-13=-486/2496, 10-11=-511/2509, 8-10=-565/2647				
WEBS	4-11=-114/820, 5-11=-781/272, 5-10=0/313, 6-10=-51/111, 3-13=-644/245, 3-11=-756/204, 2-13=-253/1307, 2-14=-1834/528				
NOTES					
1) Unbalanced roof live loads have been considered for this design.					



August 20,2025


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A7	Roof Special	1	1	175763737
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:56

Page: 1

ID:8JxkrkfW8lhHdHXiODDcX39zbfGu-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:57.9

Plate Offsets (X, Y): [10:0-3-13,0-1-5], [16:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-0.18	12-13	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(CT)	-0.37	12-13	>950	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.56	Horz(CT)	0.10	10	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 137 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2 *Except* 17-1:2x4 SP No.2
SLIDER Right 2x4 SP No.2 -- 2-9-6

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-0-11 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-5 max.); 2-4.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 3-16

REACTIONS (size) 10=0-5-8, 17= Mechanical
Max Horiz 17=123 (LC 8)
Max Uplift 10=265 (LC 9), 17=240 (LC 8)
Max Grav 10=1385 (LC 1), 17=1322 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-695/211, 2-3=-652/213, 3-4=-2316/596, 4-5=-1989/532, 5-6=-1987/544, 6-8=-2713/641, 8-10=-2955/717, 10-11=-5/0, 1-17=-1351/325

BOT CHORD 16-17=-103/181, 15-16=-320/1676, 13-15=-431/2301, 12-13=-454/2304, 10-12=-600/2678

WEBS 2-16=-29/91, 4-15=-467/186, 1-16=-298/1271, 5-13=-202/977, 4-13=-650/181, 6-13=-680/239, 6-12=-24/399, 8-12=-229/191, 3-15=-158/867, 3-16=-1395/411

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 2-7-4 to 4-7-4, Exterior(2R) 4-7-4 to 9-7-4, Interior (1) 9-7-4 to 17-0-0, Exterior(2R) 17-0-0 to 22-0-0, Interior (1) 22-0-0 to 32-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearings are assumed to be: , Joint 10 SP No.2 crushing capacity of 565 psi.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 240 lb uplift at joint 17 and 265 lb uplift at joint 10.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	A8	Roof Special	1	1	


I75763738

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:56

Page: 1

ID:8JxkrkfW8lhHdHXIODDcX39zbfGu-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrcDoi7J4zJC?f



Scale = 1:60.2

Plate Offsets (X, Y): [2:0-1-8,0-2-0], [11:0-3-13,0-1-5]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	-0.18	13-15	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.38	13-15	>926	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.76	Horz(CT)	0.10	11	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 141 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2 *Except* 18-1:2x4 SP No.2
SLIDER Right 2x4 SP No.2 -- 2-6-6

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-11-10 oc purlins, except end verticals, and 2-0-0 oc purlins (4-1-14 max.): 2-3, 4-5.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

WEBS 1 Row at midpt 3-17

REACTIONS (size) 11=0-5-8, 18= Mechanical
Max Horiz 18=123 (LC 8)
Max Uplift 11=264 (LC 9), 18=240 (LC 8)
Max Grav 11=1385 (LC 1), 18=1322 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-816/245, 2-3=-771/254, 3-4=-2094/577, 4-5=-1943/543, 5-6=-1970/567, 6-7=-1987/546, 7-9=-2729/640, 9-11=-2932/704, 11-12=-5/0, 1-18=-1331/365

BOT CHORD 17-18=-105/179, 16-17=-386/2011, 15-16=-390/2081, 13-15=-511/2395, 11-13=-587/2652

WEBS 2-17=-140/143, 1-17=-350/1300, 6-15=-221/1003, 3-16=-221/131, 4-16=-142/557, 5-16=-331/114, 5-15=-554/179, 3-17=-1482/425, 7-15=-725/245, 7-13=0/357, 9-13=-167/166

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 2-7-4 to 5-0-10, Exterior(2R) 5-0-10 to 10-0-10, Interior (1) 10-0-10 to 12-7-4, Exterior(2E) 12-7-4 to 14-7-4, Interior (1) 14-7-4 to 17-0-0, Exterior(2R) 17-0-0 to 22-0-7, Interior (1) 22-0-7 to 32-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearings are assumed to be: , Joint 11 SP No.2 crushing capacity of 565 psi.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 240 lb uplift at joint 18 and 264 lb uplift at joint 11.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A9	Roof Special	1	1	175763739
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:56

Page: 1

ID: dWV724g9vbpUvhHanx7mcMzbfGt-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f




Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A10	Roof Special	1	1	175763740
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:56

Page: 1

ID:5i3VGQhngvXLXrsmLee?8azbfGs-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWwCDoi7J4zJC?f



Scale = 1:58.5

Plate Offsets (X, Y): [4:0-2-0,Edge], [7:0-3-13,0-1-5]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.20	11-12	>999	240	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.47	Vert(CT)	-0.42	7-9	>850	180	197/144
BCLL	0.0	Rep Stress Incr	YES	WB	0.65	Horz(CT)	0.07	7	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							
Weight: 123 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP 2400F 2.0E *Except* 1-2:2x4 SP No.2
BOT CHORD	2x4 SP 2400F 2.0E
WEBS	2x3 SPF No.2
SLIDER	Right 2x4 SP No.2 -- 4-2-14

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS 1 Row at midpt 2-12

REACTIONS	(size) 7=0-5-8, 12= Mechanical
	Max Horiz 12=-114 (LC 17)
	Max Uplift 7=-277 (LC 9), 12=-228 (LC 8)
	Max Grav 7=1387 (LC 1), 12=1324 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-12=-118/72, 1-2=-81/51, 2-3=-2085/486, 3-5=-2565/643, 5-7=-2870/687, 7-8=-5/0

BOT CHORD 11-12=-441/1920, 9-11=-293/1737, 7-9=-549/2619

WEBS 2-12=-2197/632, 2-11=-182/219, 3-11=0/396, 3-9=-184/910, 5-9=-522/301

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-4 to 4-7-2, Interior (1) 4-7-2 to 13-6-8, Exterior(2R) 13-6-8 to 18-6-8, Interior (1) 18-6-8 to 30-5-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearings are assumed to be: , Joint 7 SP 2400F 2.0E crushing capacity of 805 psi.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 228 lb uplift at joint 12 and 277 lb uplift at joint 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A11	Common	1	1	Job Reference (optional)
					I75763741

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:56

Page: 1

ID:gssx3aRENmQB7mKwARHJKMzbfHA-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRCDoi7J4zJC?f



Scale = 1:57.8

Plate Offsets (X, Y): [2:0-3-13,0-1-5], [5:0-2-0,Edge], [7:0-2-0,Edge], [10:0-3-13,0-1-5], [13:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.19	13-14	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.94	Vert(CT)	-0.38	13-14	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.15	10	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 136 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E
 BOT CHORD 2x4 SP No.2
 WEBS 2x3 SPF No.2
 SLIDER Left 2x4 SP No.2 -- 4-4-4, Right 2x4 SP No.2 -- 4-4-4

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-5-15 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

WEBS 1 Row at midpt 8-13, 4-13

REACTIONS (size) 2=0-5-8, 10=0-5-8
 Max Horiz 2=108 (LC 12)
 Max Uplift 2=-299 (LC 8), 10=-293 (LC 9)
 Max Grav 2=1510 (LC 1), 10=1501 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
 TOP CHORD 1-2=-2/0, 2-4=-3196/723, 4-6=-2271/585, 6-8=-2271/586, 8-10=-3198/725, 10-11=-5/0
 BOT CHORD 2-14=-592/2920, 12-14=-595/2921, 10-12=-595/2921
 WEBS 6-13=-118/852, 8-13=-988/308, 8-12=0/334, 4-13=-986/306, 4-14=0/334

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -1-0-0 to 4-0-0, Interior (1) 4-0-0 to 16-0-0, Exterior(2R) 16-0-0 to 21-0-0, Interior (1) 21-0-0 to 32-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 299 lb uplift at joint 2 and 293 lb uplift at joint 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
 RELEASE FOR CONSTRUCTION
 AS NOTED ON PLANS REVIEW
 DEVELOPMENT SERVICES
 LEE'S SUMMIT, MISSOURI
 11/20/2025 4:00:33

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	A12	Common	1	1	


I75763742

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:57

Page: 1

ID:gssx3aRENmQB7mKwARHJKMzbfHA-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWwCDoi7J4zJC?f



Scale = 1:56.3

Plate Offsets (X, Y): [1:0-3-13,0-1-5], [4:0-2-0,Edge], [6:0-2-0,Edge], [9:0-3-13,0-1-5], [12:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.19	11-12	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.38	11-12	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.15	9	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 134 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 4-4-4, Right 2x4 SP No.2 -- 4-4-4

BRACING

TOP CHORD Structural wood sheathing directly applied or 4-5-10 oc purlins.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

WEBS 1 Row at midpt 7-12, 3-12

REACTIONS (size) 1=0-5-8, 9=0-5-8
Max Horiz 1=109 (LC 12)
Max Uplift 1=-252 (LC 8), 9=-293 (LC 9)
Max Grav 1=1439 (LC 1), 9=1502 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-3=-3206/750, 3-5=-2274/595,
5-7=-2274/587, 7-9=-3201/728, 9-10=-5/0
BOT CHORD 1-13=-613/2930, 11-13=-613/2930,
9-11=-603/2924
WEBS 5-12=-126/854, 7-12=-988/307, 7-11=0/334,
3-12=-994/309, 3-13=0/336

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-0-0 to 5-0-0,
Interior (1) 5-0-0 to 16-0-0, Exterior(2R) 16-0-0 to
21-0-0, Interior (1) 21-0-0 to 32-10-8 zone; cantilever left
and right exposed; end vertical left and right
exposed; C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60

- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 252 lb uplift at joint 1 and 293 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:57 Page: 1
ID:qssx3aRENmQB7mKwARHJKMzbFHA-RfC?PsB70Hq3NSaPanL8w3uITXbGKWRcDai7J4zJC?f




Plate Offsets (X, Y): [5:0-2-0,Edge], [8:0-3-13,0-1-5], [11:0-4-0,0-3-0], [12:0-2-8,0-2-0], [13:Edge,0-5-8]

NUMBER
TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2 *Except* 13-1:2x4 SP No.2
SLIDER Right 2x4 SP No.2 -- 4-4-4

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-2-11 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 1 Row at midpt 6-11, 2-11

REACTIONS (size) 8=0-5-8, 13= Mechanical
Max Horiz 13=-107 (LC 13)
Max Uplift 8=-290 (LC 9), 13=-245 (LC 8)
Max Grav 8=1475 (LC 1), 13=1412 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-2980/704, 2-4=-2197/579,
4-6=-2193/569, 6-8=-3126/712, 8-9=-5/0,
1-13=-1328/397
BOT CHORD 12-13=-193/627, 10-12=-588/2855,
8-10=-588/2855
WEBS 4-11=-119/822, 6-11=-993/308, 6-10=0/333,
2-11=-895/288, 2-12=-16/212,
1-12=-444/2129

- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Bearings are assumed to be: , Joint 8 SP No.2 crushing capacity of 565 psi.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 245 lb uplift at joint 13 and 290 lb uplift at joint 8.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-7-4 to 5-7-4,
Interior (1) 5-7-4 to 16-0-0, Exterior(2R) 16-0-0 to
21-0-0, Interior (1) 21-0-0 to 32-10-8 zone; cantilever left
and right exposed ; end vertical left and right
exposed;C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60



August 20, 2025




Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria**, and **DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

Mitek
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:33

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A14	Hip	1	1	175763744
Job Reference (optional)					

ID:5RX4hcT6ghol_E2Vrar0y_zbfH7-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWCrDoi7J4zJC?f



Scale = 1:59.8									
Plate Offsets (X, Y): [7:0-3-13,0-1-5], [13:0-2-8,0-2-0], [14:Edge,0-6-8]									
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in (loc)	l/defl	L/d
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.97	Vert(LL)	-0.20 12-13	>999	240
TCDL	10.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.40 12-13	>948	180
BCLL	0.0	Rep Stress Incr	YES	WB	0.99	Horz(CT)	0.12 7	n/a	n/a
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S					
Weight: 137 lb FT = 20%									
PLATES MT20 GRIP 197/144									

LUMBER	
TOP CHORD	2x4 SP No.2 *Except* 4-8:2x4 SP 2400F 2.0E
BOT CHORD	2x4 SP No.2
WEBS	2x3 SPF No.2 *Except* 14-1:2x4 SP No.2
SLIDER	Right 2x4 SP No.2 -- 3-8-5
BRACING	
TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (3-8-9 max.): 3-4.
BOT CHORD	Rigid ceiling directly applied or 6-10-11 oc bracing.
REACTIONS (size) 7=0-5-8, 14= Mechanical	
Max Horiz 14=-93 (LC 13)	
Max Uplift 7=-305 (LC 9), 14=-260 (LC 8)	
Max Grav 7=1475 (LC 1), 14=1412 (LC 1)	
FORCES (lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-2991/789, 2-3=-2424/705, 3-4=-2246/727, 4-5=-2443/719, 5-7=-3182/845, 7-8=-5/0, 1-14=-1335/418
BOT CHORD	13-14=-151/487, 12-13=-669/2775, 10-12=-474/2220, 9-10=-721/2908, 7-9=-721/2908
WEBS	2-13=-85/146, 2-12=-647/235, 3-12=-26/361, 3-10=-187/248, 4-10=-40/366, 5-10=-751/257, 5-9=0/292, 1-13=-573/2297

NOTES
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-7-4 to 5-7-4,
Interior (1) 5-7-4 to 13-11-4, Exterior(2E) 13-11-4 to
18-0-12, Exterior(2R) 18-0-12 to 24-11-2, Interior (1)
24-11-2 to 32-10-8 zone; cantilever left and right
exposed ; end vertical left and right exposed;C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 5) Bearings are assumed to be: , Joint 7 SP No.2 crushing
capacity of 565 psi.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 260 lb uplift at
joint 14 and 305 lb uplift at joint 7.
- 8) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A15	Hip	1	1	175763745
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:57

Page: 1

ID:cE_hUGTUvNguM4TJHsKnQnzbH8-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:59.7

Plate Offsets (X, Y): [7:0-3-13,0-1-5], [13:0-2-8,0-2-0], [14:Edge,0-6-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.93	Vert(LL)	-0.20	9-10	>999	240	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.86	Vert(CT)	-0.46	10-12	>826	180	197/144
BCLL	0.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.12	7	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 134 lb FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2 *Except* 3-4:2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2 *Except* 14-1:2x4 SP No.2
SLIDER Right 2x4 SP No.2 -- 3-2-0

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 6-9-3 oc bracing.
WEBS 1 Row at midpt 3-10

REACTIONS (size) 7=0-5-8, 14= Mechanical
Max Horiz 14=-80 (LC 13)
Max Uplift 7=-317 (LC 9), 14=-273 (LC 8)
Max Grav 7=1475 (LC 1), 14=1412 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-2934/808, 2-3=-2644/759, 3-4=-2507/785, 4-5=-2683/781, 5-7=-3188/871, 7-8=-5/0, 1-14=-1336/419
BOT CHORD 13-14=-120/438, 12-13=-704/2726, 10-12=-568/2451, 9-10=-750/2898, 7-9=-750/2898
WEBS 2-13=-166/137, 2-12=-337/195, 3-12=0/371, 3-10=-195/296, 4-10=0/383, 5-10=-453/214, 5-9=0/208, 1-13=-611/2300

NOTES

1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-7-4 to 5-7-4, Interior (1) 5-7-4 to 11-11-4, Exterior(2R) 11-11-4 to 19-0-2, Interior (1) 19-0-2 to 20-0-12, Exterior(2R) 20-0-12 to 27-1-10, Interior (1) 27-1-10 to 32-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Bearings are assumed to be : Joint 7 SP No.2 crushing capacity of 565 psi.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 273 lb uplift at joint 14 and 317 lb uplift at joint 7.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	A16	Hip	1	1	175763746
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:57

Page: 1

ID:82QJHwSs83Y2lvw7j9oYtZzbFh9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:59.7

Plate Offsets (X, Y): [1:Edge,0-2-4], [8:0-3-13,0-1-5], [11:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.25	11-12	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.94	Vert(CT)	-0.46	12-13	>812	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.12	8	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 133 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except* 11-8:2x4 SP 2400F 2.0E
WEBS 2x3 SPF No.2 *Except* 13-1:2x4 SP 2400F 2.0E
SLIDER Right 2x4 SP No.2 -- 2-8-3

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

WEBS 1 Row at midpt 2-13

REACTIONS (size) 8=0-5-8, 13= Mechanical
Max Horiz 13=67 (LC 13)
Max Uplift 8=327 (LC 9), 13=284 (LC 8)
Max Grav 8=1475 (LC 1), 13=1412 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-506/97, 2-3=-2803/761, 3-4=-3187/936, 4-5=-3187/936, 5-6=-2887/772, 6-8=-3131/910, 8-9=-5/0, 1-13=-308/123
BOT CHORD 12-13=-727/2616, 10-12=-599/2710, 8-10=-788/2841
WEBS 3-12=0/293, 3-11=-228/800, 4-11=-534/261, 5-11=-213/708, 5-10=0/344, 2-13=-2408/779, 2-12=-33/266, 6-10=-162/231

NOTES

1) Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-7-4 to 5-7-4, Interior (1) 5-7-4 to 9-11-4, Exterior(2R) 9-11-4 to 17-0-2, Interior (1) 17-0-2 to 22-0-12, Exterior(2R) 22-0-12 to 29-1-10, Interior (1) 29-1-10 to 32-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearings are assumed to be : Joint 8 SP 2400F 2.0E crushing capacity of 805 psi.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 327 lb uplift at joint 8 and 284 lb uplift at joint 13.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:57 Page: 1
ID:V0DCKeW?zcAKrh4W0jadzbfH4-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWRcD0i7J4ZC?c




Plate Offsets (X, Y): [8:0-3-13,0-1-5], [11:0-3-0,0-3-4], [13:Edge,0-6-8]

LUMBER
TOP CHORD 2x4 SP 2400F 2.0E *Except* 2-4,4-6:2x4 SP No.2
BOT CHORD 2x4 SP 2400F 2.0E
WEBS 2x3 SPF No.2 *Except* 13-1:2x4 SP No.2
SLIDER Right 2x4 SP No.2 -- 4-1-2

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-8-4 oc purlins, except end verticals, and 2-0-0 oc purlins (2-7-4 max.): 2-6.
BOT CHORD Rigid ceiling directly applied or 8-8-13 oc bracing.
WEBS 1 Row at midpt 3-12, 5-10

REACTIONS (size) 8=0-5-8, 13= Mechanical
Max Horiz 13=-55 (LC 17)
Max Uplift 8=-335 (LC 9), 13=-293 (LC 8)
Max Grav 8=1475 (LC 1), 13=1412 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-2978/772, 2-3=-2735/774,
3-5=-3828/989, 5-6=-2867/783,
6-8=-3161/791, 8-9=-5/0, 1-13=-1331/427
BOT CHORD 12-13=-236/700, 10-12=-911/3781,
8-10=-646/2888
WEBS 2-12=-24/570, 6-10=-47/704,
1-12=-413/2057, 3-11=0/256,
3-12=-1236/325, 5-11=0/195, 5-10=-1178/312

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCFL=6.0psf; BCFL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-7-4 to 5-7-4,
Interior (1) 5-7-4 to 7-11-4, Exterior(2R) 7-11-4 to 15-0-2,
Interior (1) 15-0-2 to 24-0-12, Exterior(2R) 24-0-12 to
31-1-10, Interior (1) 31-1-10 to 32-10-8 zone; cantilever
left and right exposed ; end vertical left and right
exposed;C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 5) Bearings are assumed to be : Joint 8 SP 2400F 2.0E
crushing capacity of 805 psi.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 293 lb uplift at
joint 13 and 335 lb uplift at joint 8.
- 8) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.

LOAD CASE(S) Standard

NOTES

- 1) Unbalanced roof live loads have been considered for this design.



August 20, 2025



WARNING – Verify design parameters and READ NOTES on this and INCLUDED WITH REFERENCE PAGE #4743 (rev. 12/2023) BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpiinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
16923 Swinley Ridge Rd
Chesapeake, MD 20805
410.429.1100
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	175763748
Roof - 8 Inch Heel	A18	Hip Girder	1	2	Job Reference (optional)

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:58

Page: 1

ID:1pfq6IVNCl2TDYCuY_tU1PzbFH5-RfC?PsB70Hq3NSgPqnL8w3uTXbGKWRcDoi7J4zJC?f



Scale = 1:59.6

Plate Offsets (X, Y): [1:Edge,0-1-12], [9:0-0-11,0-1-8], [12:0-2-8,0-1-8], [13:0-4-0,0-4-8], [14:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.97	Vert(LL)	-0.38	13	>988	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.68	13	>550	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.68	Horz(CT)	0.08	9	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 306 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP 2400F 2.0E *Except* 8-10:2x4 SP No.2
BOT CHORD 2x6 SP 2400F 2.0E
WEBS 2x3 SPF No.2
WEDGE Right: 2x4 SP No.3
SLIDER Left 2x4 SP No.2 -- 2-8-8

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-6-8 oc purlins, except 2-0-0 oc purlins (5-0-12 max.): 3-8.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1= Mechanical, 9=0-5-8
Max Horiz 1=42 (LC 17)
Max Uplift 1=-746 (LC 8), 9=-792 (LC 9)
Max Grav 1=2733 (LC 1), 9=2793 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-3=-6505/1929, 3-4=-9530/2823, 4-5=-10500/3057, 5-7=-10500/3057, 7-8=-9573/2797, 8-9=-6910/1997, 9-10=0/1
BOT CHORD 1-15=-1718/6010, 14-15=-1718/5992, 12-14=-2701/9568, 11-12=-1784/6349, 9-11=-1787/6377
WEBS 3-15=0/446, 8-11=-48/587, 3-14=-1091/3941, 8-12=-1002/3605, 4-14=-1338/551, 4-13=-302/1102, 5-13=-657/351, 7-13=-293/1055, 7-12=-1255/528

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x3 - 1 row at 0-9-0 oc.

- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-5-8 to 5-5-8, Interior (1) 5-5-8 to 5-11-4, Exterior(2R) 5-11-4 to 13-0-2, Interior (1) 13-0-2 to 26-0-12, Exterior(2E) 26-0-12 to 32-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearings are assumed to be: , Joint 9 SP 2400F 2.0E crushing capacity of 805 psi.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 746 lb uplift at joint 1 and 792 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates Girder: 3-16d (0.162" x 3.5") toe-nails per NDS guidelines.

- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 420 lb down and 109 lb up at 5-11-4, and 420 lb down and 109 lb up at 26-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-70, 3-8=-70, 8-10=-70, 1-9=-20
Concentrated Loads (lb)
Vert: 3=-131 (F), 6=-131 (F), 15=-420 (F), 11=-420 (F), 8=-131 (F), 13=-39 (F), 5=-131 (F), 17=-131 (F), 18=-131 (F), 19=-131 (F), 21=-131 (F), 23=-131 (F), 24=-131 (F), 25=-131 (F), 27=-39 (F), 28=-39 (F), 29=-39 (F), 30=-39 (F), 31=-39 (F), 32=-39 (F), 33=-39 (F), 34=-39 (F)



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34


Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:58 Page: 1
ID:Cxa Q2eGcaRv2EY?6oa3 kzbfgw-RfC?PsB70Hq3NSqPanL8w3ulTXbGKWrCDoi7J4zJC?f



- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8,
Interior (1) 4-1-8 to 5-11-4, Exterior(2E) 5-11-4 to 14-4-8
zone; cantilever left and right exposed ; end vertical left
and right exposed;C-C for members and forces &
MWFRS for reactions shown; Lumber DOL=1.60 plate
grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 5) All bearings are assumed to be SPF No.2 crushing
capacity of 425 psi.

- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 352 lb uplift at joint 2 and 352 lb uplift at joint 5.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 9) "NAILED" indicates Girder: 3-16d (0.162" x 3.5") toe-nails per NDS guidelines.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 420 lb down and 109 lb up at 5-11-4, and 420 lb down and 109 lb up at 7-6-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

1) Dead + Roof Live (balanced): Lumber Increase=1.15,
Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-70, 3-4=-70, 4-6=-70, 2-5=-20
Concentrated Loads (lb)
Vert: 3=-131 (F), 4=-131 (F), 8=420 (F), 7=420 (F)



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria**, and **DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
16023 Swinley Ridge Rd
Crestfield, MO 68017
Development Services
Lee's Summit, Missouri
64420 MiTek US
11/20/2025 4:00:34

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:58 Page: 1
ID:CgIzSeQccSIKvdlckcm4o8zbFHB-RfC?PsB70Hg3NSgPqnL8w3ulTXbGKWRCDoi7J4zJC?f



LUMBER		5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 147 lb uplift at joint 2 and 147 lb uplift at joint 6.
TOP CHORD	2x4 SP No.2	
BOT CHORD	2x4 SP No.2	6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
WEBS	2x3 SPF No.2	
SLIDER	Left 2x4 SP No.2 -- 3-6-5, Right 2x4 SP No.2 -- 3-6-5	
BRACING		LOAD CASE(S) Standard

TOP CHORD	Structural wood sheathing directly applied or 4-8-11 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-3-8, 6=0-5-8
 Max Horiz 2=-48 (LC 13)
 Max Uplift 2=-147 (LC 8), 6=-147 (LC 9)
 Max Grav 2=669 (LC 1), 6=669 (LC 1)

	Tension
TOP CHORD	1-2=-5/0, 2-4=-998/439, 4-6=-997/439, 6-7=-5/0
BOT CHORD	2-8=-303/863, 6-8=-303/863
WEBS	4-8=0/307

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) -0-10-7 to 4-1-9,
Interior (1) 4-1-9 to 6-9-0, Exterior(2R) 6-9-0 to 11-9-0,
Interior (1) 11-9-0 to 14-4-9 zone; cantilever left and right
exposed ; end vertical left and right exposed; C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 4) All bearings are assumed to be SP No.2 crushing
capacity of 565 psi.



 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

WARNING – Verify design parameters and READ NOTES ON THIS and INCLUDED WITH REFERENCE FILE MP14743 Rev. 12/2022 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
16923 Swinley Ridge Rd
Chesapeake, MD 20805
Tel: 410-220-1100
Lee's Summit, Missouri
11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	B3	Common Girder	1	2	
Job Reference (optional)					I75763751

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:58

Page: 1

ID:ROLzJXFVDQ24?xTe7QBf2zbH2-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:34.8

Plate Offsets (X, Y): [1:0-4-0,0-2-6], [5:0-4-0,0-2-6], [7:0-5-0,0-5-12]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.68	Vert(LL)	-0.11	6-7	>999	240	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.19	6-7	>825	180	
BCLL	0.0	Rep Stress Incr	NO	WB	0.82	Horz(CT)	0.03	5	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							
Weight: 142 lb FT = 20%											

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x8 SP 2400F 2.0E
WEBS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-2-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=0-5-8, 5=0-5-8
Max Horiz 1=-46 (LC 17)
Max Uplift 1=-1122 (LC 8), 5=-1278 (LC 9)
Max Grav 1=5519 (LC 1), 5=5463 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-9626/2352, 2-3=-8069/2064, 3-4=-8067/2064, 4-5=-10353/2704
BOT CHORD 1-8=-2116/8849, 7-8=-2116/8849, 6-7=-2443/9521, 5-6=-2443/9521
WEBS 2-8=-250/1594, 2-7=-1394/336, 3-7=-1150/4795, 4-7=-2143/698, 4-6=-544/2205

NOTES


- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-4-0 oc.
Web connected as follows: 2x3 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.

- Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-2-13 to 5-2-13,
Interior (1) 5-2-13 to 6-9-0, Exterior(2R) 6-9-0 to 11-9-0,
Interior (1) 11-9-0 to 13-3-5 zone; cantilever left and right
exposed; end vertical left and right exposed; C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SP 2400F 2.0E crushing
capacity of 805 psi.
- Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 1122 lb uplift at
joint 1 and 1278 lb uplift at joint 5.
- This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- Use Simpson Strong-Tie LUS28 (6-SD9112 Girder, 4-
SD912 Truss, Single Ply Girder) or equivalent spaced
at 2-0-0 oc max. starting at 1-0-0 from the left end to
9-0-0 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails
per NDS guidelines.
- Hanger(s) or other connection device(s) shall be
provided sufficient to support concentrated load(s) 2713
lb down and 758 lb up at 10-11-3, and 133 lb down and
25 lb up at 13-3-5 on bottom chord. The design/
selection of such connection device(s) is the
responsibility of others.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15,
Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-70, 3-5=-70, 1-5=-20
Concentrated Loads (lb)

Vert: 5=-133 (B), 7=-1392 (B), 13=-1394 (B),
14=-1392 (B), 15=-1392 (B), 16=-1392 (B),
17=-2713 (B)



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	C1	Hip Girder	1	2	Job Reference (optional)
					I75763752

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:58

Page: 1

ID:nnCjQAChMd9osWzWfFeY1PymG1K-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:44.6

Plate Offsets (X, Y): [2:0-2-8,Edge], [3:0-2-13,0-2-0], [5:0-2-13,0-2-0], [6:0-2-8,Edge], [9:0-6-0,0-8-0], [10:0-6-0,0-8-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	-0.07	9-10	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.81	Vert(CT)	-0.13	9-10	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.82	Horz(CT)	0.01	8	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 155 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x10 HF No.2
WEBS 2x3 SPF No.2 *Except* 11-2,8-6:2x4 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 8=0-3-8, 11=0-3-8
Max Horiz 11=76 (LC 10)
Max Uplift 8=1117 (LC 9), 11=1212 (LC 8)
Max Grav 8=4427 (LC 1), 11=4729 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/23, 2-3=-3452/978, 3-4=-3203/937, 4-5=-3217/928, 5-6=-3468/968, 6-7=0/25, 2-11=-4814/1404, 6-8=-4849/1393
BOT CHORD 10-11=-108/139, 9-10=-1062/3413, 8-9=-45/68
WEBS 3-10=-177/968, 5-9=-197/984, 2-10=-1261/4753, 6-9=-1234/4776, 4-10=-267/233, 4-9=-252/250

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-4-0 oc.
Web connected as follows: 2x3 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-2-6, Exterior(2R) 2-2-6 to 9-3-4, Interior (1) 9-3-4 to 9-7-0, Exterior(2E) 9-7-0 to 12-9-7 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- Bearing at joint(s) 11, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1212 lb uplift at joint 11 and 1117 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Use Simpson Strong-Tie HUS28 (22-10d Girder, 4-10d Truss, Single Ply Girder) or equivalent spaced at 6-0-0 oc max. starting at 0-8-0 from the left end to 10-8-0 to connect truss(es) to back face of bottom chord.
- Use Simpson Strong-Tie HUS26 (14-16d Girder, 4-16d Truss) or equivalent spaced at 2-0-0 oc max. starting at 4-8-0 from the left end to 6-8-0 to connect truss(es) to back face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 74 lb down and 172 lb up at 2-2-6, and 74 lb down and 134 lb up at 9-6-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-70, 2-3=-70, 3-5=-70, 5-6=-70, 6-7=-70, 8-11=-20
Concentrated Loads (lb)
Vert: 10=-74 (F), 9=-74 (F), 16=-1309 (B), 17=-1304 (B), 19=-1302 (B), 21=-1302 (B), 23=-1302 (B), 24=-1304 (B)



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	CG1	Diagonal Hip Girder	6	1	Job Reference (optional)
					I75763753

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:59

ID: 82QJHwSs83Y2lw7j9oYtZzbFH9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:37											
Plate Offsets (X, Y): [2:0-4-6,Edge]											
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.94	Vert(LL)	-0.22	2-5	>454	240	GRIP
TCDL	10.0	Lumber DOL	1.15	BC	0.53	Vert(CT)	-0.43	2-5	>227	180	MT20
BCLL	0.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	0.00	5	n/a	n/a	197/144
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 35 lb FT = 20%

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E

BOT CHORD 2x4 SP 2400F 2.0E

WEBS 2x3 SPF No.2

SLIDER Left 2x4 SP No.2 -- 4-1-15

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-7-6, 5= Mechanical

Max Horiz 2=103 (LC 9)

Max Uplift 2=-149 (LC 8), 5=-115 (LC 12)

Max Grav 2=484 (LC 1), 5=410 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-6/0, 2-4=-140/82, 4-5=-315/306

BOT CHORD 2-5=-47/51

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) -1-2-14 to 5-10-0, Exterior(2R) 5-10-0 to 8-2-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) Bearings are assumed to be: Joint 2 SP 2400F 2.0E crushing capacity of 805 psi.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 115 lb uplift at joint 5 and 149 lb uplift at joint 2.
 - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

- 7) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
 - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
- LOAD CASE(S)** Standard
- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (lb/ft)
- Vert: 1-4=-70, 2-5=-20
- Concentrated Loads (lb)
- Vert: 7=-53 (F=-26, B=-26), 10=-19 (F=-10, B=-10)



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

RELEASE FOR CONSTRUCTION

AS NOTED ON PLANS REVIEW

DEVELOPMENT SERVICES

LEE'S SUMMIT, MISSOURI

11/20/2025 4:00:34


Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	CG2	Diagonal Hip Girder	2	1	I75763754

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,


Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:59

Page: 1

ID:F7?GvPrBo0EUhKAU_4CLPkbfdU-RFC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	CG3	Diagonal Hip Girder	2	1	175763755
					Job Reference (optional)



Scale = 1:36.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	0.00	4-5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	4-5	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.06	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 18 lb	FT = 20%

LUMBER **LOAD CASE(S)** Standard

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or
2-11-13 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.

REACTIONS (size) 4= Mechanical, 5=0-7-0
Max Horiz 5=135 (LC 9)
Max Uplift 4=-79 (LC 9), 5=-118 (LC 8)
Max Grav 4=102 (LC 1), 5=241 (LC 1)

FORCES (lb) - Maximum Compression/Maximum
Tension

TOP CHORD 2-5=-221/322, 1-2=0/22, 2-3=-73/66,
3-4=-86/101

BOT CHORD 4-5=-226/160
WEBS 2-4=-146/241

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Corner (3) zone; cantilever left
and right exposed; end vertical left and right
exposed; C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
 - 3) Bearings are assumed to be: Joint 5 SP No.2 crushing
capacity of 565 psi.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 118 lb uplift at joint
5 and 79 lb uplift at joint 4.
 - 6) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	D1	Hip Girder	1	2	I75763756
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:02:59

Page: 1

ID:sz05NLa7o8pdxTg2JF_uHgzbH?-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrCdoi7J4zJC?f



Scale = 1:71.3

Plate Offsets (X, Y): [5:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.97	Vert(LL)	-0.08	18-19	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.15	18-19	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	1.00	Horz(CT)	0.05	11	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 340 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SPF No.2
WEBS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-9.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

WEBS 1 Row at midpt 5-16

REACTIONS (size) 2=0-3-8, 11=0-5-8, 16=0-5-8
Max Horiz 2=-54 (LC 17)
Max Uplift 2=-453 (LC 8), 11=-426 (LC 9), 16=-1475 (LC 8)
Max Grav 2=1609 (LC 25), 11=1493 (LC 26), 16=5356 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/1, 2-3=-3473/1044, 3-4=-3481/995, 4-5=-2042/618, 5-6=-610/2195, 6-8=-610/2195, 8-9=-1613/497, 9-10=-3103/888, 10-11=-3115/944, 11-12=0/1

BOT CHORD 2-19=-918/3149, 18-19=-853/3254, 16-18=-513/2037, 14-16=-365/1608, 13-14=-725/2891, 11-13=-818/2811

WEBS 4-19=-107/920, 9-13=-115/918, 6-16=-1093/565, 4-18=-1376/420, 5-16=-4593/1347, 5-18=0/936, 9-14=-1471/444, 8-14=-4/924, 8-16=-4175/1230, 3-19=-230/391, 10-13=-218/357

NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x3 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 3-11-2, Interior (1) 3-11-2 to 7-11-4, Exterior(2R) 7-11-4 to 15-0-2, Interior (1) 15-0-2 to 31-4-12, Exterior(2R) 31-4-12 to 38-5-10, Interior (1) 38-5-10 to 40-2-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- All bearings are assumed to be SPF No.2 crushing capacity of 425 psi.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 453 lb uplift at joint 2, 1475 lb uplift at joint 16 and 426 lb uplift at joint 11.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates Girder: 3-16d (0.162" x 3.5") toe-nails per NDS guidelines.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 226 lb down and 148 lb up at 7-11-4, 202 lb down and 148 lb up at 10-0-0, 202 lb down and 148 lb up at 12-0-0, 202 lb down and 148 lb up at 14-0-0, 202 lb down and 148 lb up at 16-0-0, 202 lb down and 148 lb up at 18-0-0, 202 lb down and 148 lb up at 19-8-0, 202 lb down and 148 lb up at 21-4-0, 202 lb down and 148 lb up at 23-4-0, 202 lb down and 148 lb up at 25-4-0, 202 lb down and 148 lb up at 27-4-0, and 202 lb down and 148 lb up at 29-4-0, and 226 lb down and 148 lb up at 31-4-12 on top chord, and 752 lb down and 191 lb up at 7-11-4, and 752 lb down and 191 lb up at 31-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



August 20,2025

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35

Job	Truss	Truss Type	Qty	Ply	I75763756
Roof - 8 Inch Heel	D1	Hip Girder	1	2	
Job Reference (optional)					

Uniform Loads (lb/ft)
Vert: 1-4=-70, 4-9=-70, 9-12=-70, 2-11=-20
Concentrated Loads (lb)
Vert: 4=-202 (F), 17=-59 (F), 19=-752 (F), 13=-752 (F), 18=-59 (F), 5=-202 (F), 9=-202 (F), 15=-59 (F), 21=-202 (F), 22=-202 (F), 24=-202 (F), 25=-202 (F), 26=-202 (F), 27=-202 (F), 28=-202 (F), 30=-202 (F), 31=-202 (F), 32=-202 (F), 34=-59 (F), 35=-59 (F), 36=-59 (F), 37=-59 (F), 38=-59 (F), 39=-59 (F), 40=-59 (F), 41=-59 (F)


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	D2	Monopitch Girder	1	1	Job Reference (optional)
					I75763757

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00

Page: 1

ID:tfFU26Yd3PwbgghSod77zqzbevo-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:30.9

Plate Offsets (X, Y): [3:Edge,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.63	Vert(LL)	0.07	1-3	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.65	Vert(CT)	-0.13	1-3	>661	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 27 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x6 SPF No.2
WEBS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

(size) 1=0-3-8, 3= Mechanical
Max Horiz 1=128 (LC 9)
Max Uplift 1=-110 (LC 8), 3=-274 (LC 12)
Max Grav 1=430 (LC 1), 3=615 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-183/102, 2-3=-246/327
BOT CHORD 1-3=-55/60

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-1-12 to 5-1-12,
Interior (1) 5-1-12 to 7-2-4 zone; cantilever left and right
exposed; end vertical left and right exposed; C-C for
members and forces & MWFRS for reactions shown;
Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 3) Bearings are assumed to be: Joint 1 SPF No.2 crushing
capacity of 425 psi.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 110 lb uplift at joint
1 and 274 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.

7) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails
per NDS guidelines.

8) Hanger(s) or other connection device(s) shall be
provided sufficient to support concentrated load(s) 123
lb down and 88 lb up at 7-2-4 on bottom chord. The
design/selection of such connection device(s) is the
responsibility of others.

9) In the LOAD CASE(S) section, loads applied to the face
of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15,
Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-70, 1-3=-20
Concentrated Loads (lb)
Vert: 3=-123 (B), 6=-61 (B), 7=-113 (B), 8=-113 (B)




August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00 Page: 1
ID:uQhwP9vZHKQCOF6WEGVXhazbfJ9-RfC?PsB70Ha3NSaPqnL8w3uTXbGKWRcDoi7J4zJC?f



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.22	Horiz(TL)	0.01	11	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							Weight: 94 lb	FT = 20%

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x3 SPF No.2

2-19=-184/156, 3-18=-184/158,
4-17=-211/181, 5-16=-137/59, 7-15=-118/43,
8-14=-211/185, 9-13=-184/157,
10-12=-184/156

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) 0-4-1 to 5-4-1,
Interior (1) 5-4-1 to 8-11-12, Exterior(2R) 8-11-12 to
13-11-12, Interior (1) 13-11-12 to 17-7-7 zone; cantilever
left and right exposed ; end vertical left and right
exposed;C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss
only. For studs exposed to wind (normal to the face),
see Standard Industry Gable End Details as applicable,
or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 1.5x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 2-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 8) All bearings are assumed to be SP No.2 crushing
capacity of 565 psi.
- 9) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 108 lb uplift at
joint 1, 87 lb uplift at joint 11, 138 lb uplift at joint 19, 132
lb uplift at joint 18, 158 lb uplift at joint 17, 35 lb uplift at
joint 16, 19 lb uplift at joint 15, 161 lb uplift at joint 14,
132 lb uplift at joint 13 and 138 lb uplift at joint 12.
- 10) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size)		
		1=17-11-0, 11=17-11-0, 12=17-11-0, 13=17-11-0, 14=17-11-0, 15=17-11-0, 16=17-11-0, 17=17-11-0, 18=17-11-0, 19=17-11-0
	Max Horiz	1=-258 (LC 8)
	Max Uplift	1=-108 (LC 10), 11=-87 (LC 11), 12=-138 (LC 13), 13=-132 (LC 13), 14=-161 (LC 13), 15=-19 (LC 13), 16=-35 (LC 12), 17=-158 (LC 12), 18=-132 (LC 12), 19=-138 (LC 12)
	Max Grav	1=301 (LC 12), 11=287 (LC 13), 12=209 (LC 20), 13=204 (LC 20), 14=216 (LC 20), 15=159 (LC 20), 16=177 (LC 19), 17=212 (LC 19), 18=205 (LC 19), 19=209 (LC 19)

FORCES	(lb) - Maximum Compression/Maximum Tension
TOP CHORD	1-2=-432/307, 2-3=-305/203, 3-4=-173/111, 4-5=-117/68, 5-6=-77/63, 6-7=-77/61, 7-8=-94/47, 8-9=-155/98, 9-10=-287/202, 10-11=-414/306
BOT CHORD	1-19=-226/312, 18-19=-226/312, 17-18=-226/312, 15-17=-227/312, 14-15=-226/312, 13-14=-226/312, 12-13=-226/312, 11-12=-226/312



WARNING – Verify design parameters and READ NOTES on this and INCLUDED WITH REFERENCE PAGE #4743 (rev. 12/2023) BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcscomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	HG2	Lay-In Gable	1	1	175763759
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00

Page: 1

ID:GHAoRZPL5r2cGJbLUJkcjzbfHD-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:62.8

Plate Offsets (X, Y): [16:0-2-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.06	Vert(TL)	n/a	-	n/a	999	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.28	Horiz(TL)	0.01	11	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							
Weight: 110 lb FT = 20%											

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
OTHERS	2x3 SPF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 6-16

REACTIONS (size)	1=19-11-0, 11=19-11-0, 12=19-11-0, 13=19-11-0, 14=19-11-0, 15=19-11-0, 16=19-11-0, 17=19-11-0, 18=19-11-0, 19=19-11-0, 20=19-11-0
Max Horiz	1=-288 (LC 8)
Max Uplift	1=-131 (LC 10), 11=-88 (LC 11), 12=-138 (LC 13), 13=-135 (LC 13), 14=-143 (LC 13), 15=-127 (LC 13), 17=-131 (LC 12), 18=-141 (LC 12), 19=-135 (LC 12), 20=-138 (LC 12)
Max Grav	1=283 (LC 12), 11=255 (LC 13), 12=209 (LC 20), 13=206 (LC 20), 14=207 (LC 20), 15=213 (LC 20), 16=231 (LC 13), 17=215 (LC 19), 18=206 (LC 19), 19=206 (LC 19), 20=209 (LC 19)

FORCES

TOP CHORD	(lb) - Maximum Compression/Maximum Tension 1-2=-408/250, 2-3=-281/193, 3-4=-177/143, 4-5=-150/134, 5-6=-194/199, 6-7=-193/184, 7-8=-105/93, 8-9=-134/85, 9-10=-243/149, 10-11=-370/251
-----------	---

BOT CHORD	1-20=-186/281, 19-20=-187/281, 18-19=-187/281, 17-18=-187/281, 15-17=-187/282, 14-15=-187/282, 13-14=-187/282, 12-13=-187/282, 11-12=-187/282
WEBS	2-20=-181/155, 3-19=-185/160, 4-18=-191/165, 5-17=-176/155, 6-16=-207/148, 7-15=-176/152, 8-14=-191/166, 9-13=-185/160, 10-12=-181/155

NOTES

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-1 to 5-4-1, Interior (1) 5-4-1 to 9-11-12, Exterior(2R) 9-11-12 to 14-11-12, Interior (1) 14-11-12 to 19-7-7 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 1.5x4 MT20 unless otherwise indicated.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 2-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.

- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 131 lb uplift at joint 1, 88 lb uplift at joint 11, 138 lb uplift at joint 20, 135 lb uplift at joint 19, 141 lb uplift at joint 18, 131 lb uplift at joint 17, 127 lb uplift at joint 15, 143 lb uplift at joint 14, 135 lb uplift at joint 13 and 138 lb uplift at joint 12.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard




August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	HG3	Lay-In Gable	1	1	Job Reference (optional)
					I75763760



Scale = 1:72									
Plate Offsets (X, Y): [5:0-3-8,Edge], [8:Edge,0-1-7]									
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	PLATES
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.14	Vert(LL)	n/a	-	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.07	Vert(CT)	n/a	-	GRIP
BCLL	0.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	11	197/144
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S					Weight: 73 lb FT = 20%

LUMBER		WEBS	3-19=669/571, 4-18=211/171, 5-17=280/247, 6-16=141/68, 7-14=151/72, 8-13=122/38, 9-12=206/176	13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
TOP CHORD	2x4 SP No.2			
BOT CHORD	2x4 SP No.2			
WEBS	2x3 SPF No.2			
OTHERS	2x3 SPF No.2			
BRACING		NOTES		LOAD CASE(S) Standard
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-8.	1) Unbalanced roof live loads have been considered for this design.		
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.	2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-3 to 5-0-2, Interior (1) 5-0-2 to 11-0-2, Exterior(2E) 11-0-2 to 14-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60		
REACTIONS	(size)	3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.		
	2=14-5-11, 11=14-5-11, 12=14-5-11, 13=14-5-11, 14=14-5-11, 15=14-5-11, 16=14-5-11, 17=14-5-11, 18=14-5-11, 19=14-5-11	4) Provide adequate drainage to prevent water ponding.		
Max Horiz	2=-310 (LC 13)	5) All plates are 1.5x4 MT20 unless otherwise indicated.		
Max Uplift	2=-484 (LC 13), 11=-6 (LC 12), 12=-167 (LC 13), 13=-13 (LC 9), 14=-51 (LC 9), 15=-26 (LC 8), 16=-46 (LC 9), 17=-225 (LC 13), 18=-150 (LC 13), 19=-298 (LC 11)	6) Gable requires continuous bottom chord bearing.		
Max Grav	2=200 (LC 11), 11=77 (LC 20), 12=218 (LC 20), 13=163 (LC 26), 14=183 (LC 26), 15=39 (LC 11), 16=179 (LC 1), 17=211 (LC 20), 18=233 (LC 20), 19=764 (LC 13)	7) Gable studs spaced at 2-0-0 oc.		
FORCES	(lb) - Maximum Compression/Maximum Tension	8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.		
TOP CHORD	1-2=-7/0, 2-3=-466/513, 3-4=-372/399, 4-5=-251/273, 5-6=-149/160, 6-7=-149/161, 7-8=-149/160, 8-9=-182/185, 9-10=-56/56, 10-11=-70/49	9) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.		
BOT CHORD	2-19=-50/36, 18-19=-111/110, 17-18=-107/108, 16-17=-80/85, 15-16=-73/85, 14-15=-45/52, 13-14=-45/52, 12-13=-45/53, 11-12=-45/53	10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 6 lb uplift at joint 11, 484 lb uplift at joint 2, 26 lb uplift at joint 15, 298 lb uplift at joint 19, 150 lb uplift at joint 18, 225 lb uplift at joint 17, 46 lb uplift at joint 16, 51 lb uplift at joint 14, 13 lb uplift at joint 13 and 167 lb uplift at joint 12.		
		11) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2, 19, 18, 17, 16.		
		12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.		




Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	HG4	Lay-In Gable	1	1	
Job Reference (optional)					I75763761

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00

Page: 1

ID:r7YXrg_mromV4b0Ghmo5mOymG1d-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:42.1

Plate Offsets (X, Y): [1:0-0-10,0-1-8], [4:0-2-7,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(TL)	n/a	-	n/a	999	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.06	Horiz(TL)	0.00	7	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-S							
										Weight: 44 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x3 SPF No.2
OTHERS	2x3 SPF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-4.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 1-12.

REACTIONS

(size)	1=9-2-12, 7=9-2-12, 8=9-2-12, 9=9-2-12, 10=9-2-12, 11=9-2-12, 12=9-2-12
Max Horiz	1=-154 (LC 13)
Max Uplift	1=-21 (LC 9), 7=-15 (LC 8), 8=-152 (LC 13), 9=-10 (LC 9), 10=-15 (LC 8), 11=-51 (LC 9), 12=-40 (LC 13)
Max Grav	1=58 (LC 1), 7=75 (LC 20), 8=214 (LC 20), 9=154 (LC 1), 10=28 (LC 11), 11=183 (LC 1), 12=175 (LC 1)

FORCES

(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-159/169, 2-3=-159/169, 3-4=-159/168, 4-5=-191/192, 5-6=-59/58, 6-7=-72/53
BOT CHORD	1-12=-50/51, 11-12=-49/55, 10-11=-38/54, 9-10=-24/31, 8-9=-24/31, 7-8=-24/31
WEBS	4-9=-119/32, 3-11=-148/72, 2-12=-133/62, 5-8=-211/170

NOTES

- 1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-4-1 to 5-4-1, Interior (1) 5-4-1 to 5-10-0, Exterior(2E) 5-10-0 to 9-4-14 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Provide adequate drainage to prevent water ponding.
- 5) All plates are 1.5x4 MT20 unless otherwise indicated.
- 6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 7) Gable studs spaced at 2-0-0 oc.
- 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 9) All bearings are assumed to be SP No.2 crushing capacity of 565 psi.
- 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 1, 15 lb uplift at joint 7, 15 lb uplift at joint 10, 10 lb uplift at joint 9, 51 lb uplift at joint 11, 40 lb uplift at joint 12 and 152 lb uplift at joint 8.
- 11) N/A
- 12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)


MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	J1	Jack-Open	13	1	
Job Reference (optional)					I75763762

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00
ID:T9mP6MuCjYyKtaMX3mpbNnzbfGP-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWRCdoi7J4zJC?f

Page: 1



Scale = 1:30.3

Plate Offsets (X, Y): [2:0-1-8,0-0-5]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	-0.23	2-5	>410	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.46	2-5	>205	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.03	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 32 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
SLIDER Left 2x4 SP No.2 -- 4-2-7

6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-2-10 oc bracing.

REACTIONS (size) 2=0-3-8, 4= Mechanical, 5= Mechanical
Max Horiz 2=128 (LC 12)
Max Uplift 2=-95 (LC 8), 4=-148 (LC 12)
Max Grav 2=419 (LC 1), 4=272 (LC 1), 5=157 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-5/0, 2-4=-129/68
BOT CHORD 2-5=0/0

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 7-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Bearings are assumed to be: , Joint 2 SP No.2 crushing capacity of 565 psi.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 148 lb uplift at joint 4 and 95 lb uplift at joint 2.



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	J2	Jack-Open	4	1	


I75763763

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00

Page: 1

ID:bkA06210eR9r5126IHmb9szbfff8-RfC?PsB70Hq3NSgPqnL8w3uITxbGKWrcDoi7J4zJC?f



Scale = 1:28.9

Plate Offsets (X, Y): [2:0-1-8,0-0-5]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.07	2-5	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.43	Vert(CT)	-0.13	2-5	>516	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.02	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 24 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
SLIDER Left 2x4 SP No.2 -- 3-1-4

6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING

TOP CHORD Structural wood sheathing directly applied or 5-10-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-3-8, 4= Mechanical, 5= Mechanical
Max Horiz 2=97 (LC 12)
Max Uplift 2=-80 (LC 8), 4=-110 (LC 12)
Max Grav 2=326 (LC 1), 4=198 (LC 1), 5=116 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-5/0, 2-4=-104/49
BOT CHORD 2-5=0/0

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 5-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Bearings are assumed to be: , Joint 2 SP No.2 crushing capacity of 565 psi.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 4 and 80 lb uplift at joint 2.




August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:35

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:00 Page: 1
ID:XgLdgMjB9VhkPZo1PqP1dSzbea-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRcDoi7J4zJC?f



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	-0.01	2-5	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	-0.02	2-5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.01	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 16 lb	FT = 20%

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vesd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
K=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) zone; cantilever left
and right exposed ; end vertical left and right
exposed; C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 3) Bearings are assumed to be : Joint 2 SP No.2 crushing
capacity of 565 psi.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 73 lb uplift at joint
4 and 67 lb uplift at joint 2.



WARNING – Verify design parameters and READ NOTES ON THIS and INCLUDED MEMBER REFERENCE (see MP17475 rev. 12/2022) BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
16023 Swinley Ridge Rd
Chesapeake, MD 20805
Tel: 410.620.1100
Lee's Summit, Missouri
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	J4	Jack-Open	16	1	I75763765
Job Reference (optional)					

ID:fAdYOpTl5VKuTZIWg384fCzbfN-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWwCDoi7J4zJC?f

-0-10-8	1-10-3
0-10-8	1-10-3



Scale = 1:26.8

Plate Offsets (X, Y): [2:0-1-8,0-0-5]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	0.00	2-5	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	2-5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 9 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
SLIDER Left 2x4 SP No.2 -- 1-5-8

6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

BRACING

TOP CHORD Structural wood sheathing directly applied or 1-10-3 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 4= Mechanical, 5= Mechanical
Max Horiz 2=40 (LC 12)
Max Uplift 2=-57 (LC 8), 4=-35 (LC 12)
Max Grav 2=158 (LC 1), 4=50 (LC 1), 5=37 (LC 3)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-5/0, 2-4=-43/16
BOT CHORD 2-5=0/0

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Bearings are assumed to be: , Joint 2 SP No.2 crushing capacity of 565 psi.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 2 and 35 lb uplift at joint 4.



August 20,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	J5	Jack-Open	23	1	

I75763766



Scale = 1:28.9											
Plate Offsets (X, Y): [2:0-1-8,0-0-5]											
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.07	2-5	>987	240	GRIP
TCDL	10.0	Lumber DOL	1.15	BC	0.44	Vert(CT)	-0.14	2-5	>493	180	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.02	4	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 24 lb FT = 20%

LUMBER		6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
TOP CHORD	2x4 SP No.2	
BOT CHORD	2x4 SP No.2	
SLIDER	Left 2x4 SP No.2 -- 3-1-13	
BRACING		LOAD CASE(S) Standard
TOP CHORD	Structural wood sheathing directly applied or 5-11-4 oc purlins.	
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.	
REACTIONS	(size)	2=0-5-8, 4= Mechanical, 5= Mechanical
	Max Horiz	2=99 (LC 12)
	Max Uplift	2=-81 (LC 8), 4=-111 (LC 12)
	Max Grav	2=330 (LC 1), 4=201 (LC 1), 5=118 (LC 3)
FORCES	(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-5/0, 2-4=-105/50	
BOT CHORD	2-5=0/0	

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 4-1-8, Interior (1) 4-1-8 to 5-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 3) Bearings are assumed to be: , Joint 2 SP No.2 crushing capacity of 565 psi.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 111 lb uplift at joint 4 and 81 lb uplift at joint 2.



August 20,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	J6	Jack-Open	6	1	

I75763767



Scale = 1:33.5

Plate Offsets (X, Y): [2:0-3-0,0-1-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.65	Vert(LL)	0.01	4-5	>999	240	MT18HS	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.32	Vert(CT)	0.01	4-5	>999	180	MT20	197/144
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.12	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-R							Weight: 10 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

WEBS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-6 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical, 5=0-5-8

Max Horiz 5=83 (LC 9)

Max Uplift 3=-47 (LC 12), 4=-26 (LC 9), 5=-41 (LC 8)

Max Grav 3=55 (LC 1), 4=40 (LC 3), 5=176 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 2-5=-156/150, 1-2=0/22, 2-3=-53/25

BOT CHORD 4-5=0/0

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

2) All plates are MT20 plates unless otherwise indicated.

3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

4) Bearings are assumed to be: , Joint 5 SP No.2 crushing capacity of 565 psi.

5) Refer to girder(s) for truss to truss connections.

6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 41 lb uplift at joint 5, 47 lb uplift at joint 3 and 26 lb uplift at joint 4.



August 20,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	M1	Half Hip	1	1	Job Reference (optional)
					I75763769



Scale = 1:25.8

Plate Offsets (X, Y): [1:0-2-4,0-0-10]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	6	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	6	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 14 lb	FT = 20%

LUMBER			7) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 1.
TOP CHORD	2x4 SP No.2		8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 1 and 36 lb uplift at joint 5.
BOT CHORD	2x4 SP No.2		9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
WEBS	2x3 SPF No.2		10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
SLIDER	Left 2x4 SP No.2 -- 1-3-4		
BRACING			LOAD CASE(S) Standard
TOP CHORD	Structural wood sheathing directly applied or 3-5-5 oc purlins, except 2-0-0 oc purlins: 3-4.		
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.		
REACTIONS (size) 1=0-2-2, 5= Mechanical			
Max Horiz 1=41 (LC 12)			
Max Uplift 1=-24 (LC 8), 5=-36 (LC 8)			
Max Grav 1=139 (LC 1), 5=139 (LC 1)			
FORCES (lb) - Maximum Compression/Maximum Tension			
TOP CHORD 1-3=-154/90, 3-4=-116/111			
BOT CHORD 1-6=-97/110, 5-6=0/0			
WEBS 3-6=-41/95, 4-5=-124/129, 4-6=-126/134			

- NOTES**
- 1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

3) Provide adequate drainage to prevent water ponding.

4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

5) Bearings are assumed to be: Joint 1 SP No.2 crushing capacity of 565 psi.

6) Refer to girder(s) for truss to truss connections.



August 20,2025


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	M2	Roof Special	1	1	175763770
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 E Aug 30 2023 Print: 8.630 E Aug 30 2023 MiTek Industries, Inc. Wed Aug 20 14:14:51

Page: 1

ID:WISb?PUUFtGdVvpU04XyGnzbevt-ajpKxV_1iBfUD_zkZzE9rf2GS7L9vS98LQREGym5UK



Scale = 1:24.3									
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	L/d
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	0.00	4-5	>999 240
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	4-5	>999 180
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	4	n/a n/a
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P					
					PLATES		GRIP		
					MT20		197/144		
					Weight: 14 lb		FT = 20%		

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 3-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 1-2.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS

All bearings 0-1-8.
(lb) - Max Horiz 5=64 (LC 9)
Max Uplift All uplift 100 (lb) or less at joint(s) 1, 3, 4, 5
Max Grav All reactions 250 (lb) or less at joint (s) 1, 3, 4, 5

FORCES

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-4 to 1-8-10, Interior (1) 1-8-10 to 3-0-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 1, 3, 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard



August 20,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	M3	Monopitch	1	1	

I75763771



Scale = 1:21.1												
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	0.00	3-4	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	3-4	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 14 lb	FT = 20%

LUMBER **LOAD CASE(S)** Standard

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2

BRACING
TOP CHORD 2'-0" oc purlins: 1-2, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=-70 (LC 8)
Max Uplift 3=-49 (LC 9), 4=-49 (LC 8)
Max Grav 3=133 (LC 1), 4=133 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-4=-103/193, 1-2=-35/38, 2-3=-103/157
BOT CHORD 3-4=-98/101
WEBS 1-3=-72/72

- NOTES**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Corner (3) zone; cantilever left
and right exposed ; end vertical left and right
exposed;C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
 - 2) Provide adequate drainage to prevent water ponding.
 - 3) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 49 lb uplift at joint
4 and 49 lb uplift at joint 3.
 - 6) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
 - 7) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.



August 20,2025


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	M4	Monopitch	1	1	

I75763772



Scale = 1:23.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	0.00	3-4	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	3-4	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 16 lb	FT = 20%

LUMBER LOAD CASE(S) Standard

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2

BRACING
TOP CHORD 2-0-0 oc purlins: 1-2, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=97 (LC 9)
Max Uplift 3=-68 (LC 9), 4=-68 (LC 8)
Max Grav 3=133 (LC 1), 4=133 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-4=-124/227, 1-2=-49/53, 2-3=-103/157
BOT CHORD 3-4=-136/140
WEBS 1-3=-112/112

- NOTES
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Corner (3) zone; cantilever left
and right exposed ; end vertical left and right
exposed;C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
 - 2) Provide adequate drainage to prevent water ponding.
 - 3) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 68 lb uplift at joint
4 and 68 lb uplift at joint 3.
 - 6) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
 - 7) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®


RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36

Job	Truss	Truss Type	Qty	Ply	175763773
Roof - 8 Inch Heel	M5	Monopitch	1	1	Job Reference (optional)

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:01
ID:WISb?PUUFtGdVvpU04XyGnzbevt-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 1



Scale = 1:25.2

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.00	3-4	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	3-4		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	3		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P				n/a		
									Weight: 16 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2

LOAD CASE(S) Standard

BRACING

TOP CHORD 2-0-0 oc purlins: 1-2, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 3= Mechanical, 4= Mechanical
Max Horiz 4=113 (LC 9)
Max Uplift 3=-82 (LC 9), 4=-82 (LC 8)
Max Grav 3=133 (LC 1), 4=133 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-4=-149/251, 1-2=-57/62, 2-3=-103/157
BOT CHORD 3-4=-158/163
WEBS 1-3=-139/139

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Corner (3) zone; cantilever left
and right exposed; end vertical left and right
exposed; C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 82 lb uplift at joint
4 and 82 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.
- 7) Graphical purlin representation does not depict the size
or the orientation of the purlin along the top and/or
bottom chord.



August 20, 2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:36


Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	M6	Half Hip	1	1	I75763774
Job Reference (optional)					

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:01

Page: 1

ID:2WuDn3TsUZ8mtEISN0jjZzbevu-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:27.6											
Plate Offsets (X, Y): [2:Edge,0-0-0]											
Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	0.00	7	>999	240	GRIP
TCDL	10.0	Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	2-7	>999	180	MT20
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	6	n/a	n/a	197/144
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 16 lb
											FT = 20%

LUMBER	
TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x3 SPF No.2
SLIDER	Left 2x4 SP No.2 -- 1-6-6
BRACING	
TOP CHORD	Structural wood sheathing directly applied or 3-5-9 oc purlins, except end verticals, and 2-0-0 oc purlins: 4-5.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
REACTIONS	
(size)	2=0-5-7, 6= Mechanical
Max Horiz	2=41 (LC 9)
Max Uplift	2=-76 (LC 8), 6=-30 (LC 8)
Max Grav	2=221 (LC 1), 6=143 (LC 1)
FORCES	
(lb) - Maximum Compression/Maximum Tension	
TOP CHORD	1-2=-5/0, 2-4=-172/98, 4-5=-123/117, 5-6=-128/128
BOT CHORD	2-7=-108/130, 6-7=-19/20
WEBS	4-7=-41/96, 5-7=-124/143

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Bearings are assumed to be: Joint 2 SP No.2 crushing capacity of 565 psi.
 - Refer to girder(s) for truss to truss connections.

- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 30 lb uplift at joint 6 and 76 lb uplift at joint 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:37

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
Roof - 8 Inch Heel	M7	Monopitch	4	1	


I75763775

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083,

Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:01

Page: 1

ID:WiSb?PUUFtGdVvpU04XyGnzbevt-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f



Scale = 1:27.1

Plate Offsets (X, Y): [2:Edge,0-0-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	-0.01	2-5	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	-0.02	2-5	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 16 lb	FT = 20%

LUMBER

LOAD CASE(S) Standard

TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x3 SPF No.2
SLIDER Left 2x4 SP No.2 -- 1-8-12

BRACING

TOP CHORD Structural wood sheathing directly applied or
3-5-9 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc
bracing.

REACTIONS (size) 2=0-5-7, 5= Mechanical
Max Horiz 2=69 (LC 9)
Max Uplift 2=-72 (LC 8), 5=-37 (LC 12)
Max Grav 2=221 (LC 1), 5=143 (LC 1)

FORCES (lb) - Maximum Compression/Maximum
Tension

TOP CHORD 1-2=-5/0, 2-4=-90/54, 4-5=-109/175
BOT CHORD 2-5=-31/33

NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft;
Ke=1.00; Cat. II; Exp C; Enclosed; MWFRS (envelope)
exterior zone and C-C Exterior(2E) zone; cantilever left
and right exposed; end vertical left and right
exposed; C-C for members and forces & MWFRS for
reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom
chord live load nonconcurrent with any other live loads.
- 3) Bearings are assumed to be: Joint 2 SP No.2 crushing
capacity of 565 psi.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to
bearing plate capable of withstanding 37 lb uplift at joint
5 and 72 lb uplift at joint 2.
- 6) This truss is designed in accordance with the 2018
International Residential Code sections R502.11.1 and
R802.10.2 and referenced standard ANSI/TPI 1.




August 20,2025

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:37

Premier Building Supply (Springhill, KS), Spring Hills, KS - 66083, Run: 8.63 S Sep 26 2024 Print: 8.630 S Sep 26 2024 MiTek Industries, Inc. Tue Aug 19 16:03:01 Page: 1
ID:82QJHwSs83Y2lw7j9oYtZzbIH9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKwRCdo7J4zJC?f




LOAD CASE(S) Standard



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria**, and **DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:37

Job	Truss	Truss Type	Qty	Ply	
Roof - 8 Inch Heel	V2	Valley	1	1	Job Reference (optional)
					I75763777



Scale = 1:19.8

Plate Offsets (X, Y): [2:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	25.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	n/a	-	n/a	999	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.14	Vert(TL)	n/a	-	n/a	999	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 13 lb FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-3-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=5-1-8, 3=5-1-8
Max Horiz 1=11 (LC 16)
Max Uplift 1=-27 (LC 8), 3=-27 (LC 9)
Max Grav 1=152 (LC 1), 3=152 (LC 1)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-198/239, 2-3=-198/243
BOT CHORD 1-3=-200/173

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=35ft; Ke=1.00; Cat. II; Exp C; Endosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 4-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - All bearings are assumed to be SP No.2 crushing capacity of 565 psi.

- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 1 and 27 lb uplift at joint 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



August 20,2025



WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcsccomponents.com)

MiTek®
RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:37

Symbols

PLATE LOCATION AND ORIENTATION




For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

PLATE SIZE


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.


BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:
ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:
ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.
Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
11/20/2025 4:00:37