



GENERAL DEMOLITION NOTES:

1. THE INTENT OF THESE DEMOLITION DRAWINGS IS TO DEFINE A GENERAL SCOPE OF DEMOLITION WORK. THESE DRAWINGS MAY NOT IDENTIFY EVERY INDIVIDUAL ITEM TO BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING ALL ITEMS WHICH MUST BE REMOVED TO FACILITATE NEW CONSTRUCTION.
2. REFER TO KEYED NOTES FOR SPECIFIC ITEMS TO BE REMOVED IN DRAWINGS. NOT ALL ITEMS TO BE REMOVED ARE DESCRIBED BY A KEYED NOTE.
3. ITEMS DRAWN DASHED TO BE REMOVED.
4. REMOVE ALL ABANDONED PIPING, ELECTRICAL CONDUIT, MISCELLANEOUS HANGARS, MISCELLANEOUS DUCTWORK, AND ALL OTHER ABANDONED ITEMS UNLESS OTHERWISE NOTED.
5. THE CONTRACTOR SHALL SHORE ANY AREAS AFFECTED OR COMPROMISED BY DEMOLITION ACTIVITIES AS REQUIRED.
6. PROTECT ITEMS NOT SLATED FOR REMOVAL. REPAIR ANY AND ALL DAMAGE TO EXISTING CONDITIONS THAT OCCUR AS PART OF THE DEMOLITION / NEW CONSTRUCTION PROCESS.
7. COORDINATE ALL REMOVAL AND LOCATION OF WALL AND FLOOR PENETRATIONS WITH NEW CONSTRUCTION.
8. DEMOLITION CONTRACTOR SHALL COORDINATE WITH THE MECHANICAL AND ELECTRICAL CONTRACTOR FOR LOCATION OF SAW CUTS AND CONCRETE FLOOR DEMOLITION.
9. HIBAY LIGHTING TO BE SALVAGED UNLESS OTHERWISE NOTED.
10. ALL LOWER CEILINGS AND LIGHTING TO BE REMOVED. THIS INCLUDES BUT IS NOT LIMITED TO THE CEILING ABOVE THE RESTROOMS AND THE CEILING ABOVE THE BREAK ROOM.
11. REMOVE ALL EXISTING LIGHT FIXTURES AND ANY CONDUIT ASSOCIATED WITH THEM THAT ARE DIRECTLY ABOVE ANY SPACE THAT WILL RECEIVE A NEW CEILING, OR ABOVE ANY CLOUD ELEMENTS, UNLESS OTHERWISE NOTED.

DEMO KEYED NOTES:

1. REMOVE EXIST. WINDOW / STOREFRONT AND FRAME
2. REMOVE EXIST. DOOR AND FRAME
3. PREP EXISTING CONCRETE SLAB AS REQUIRED FOR NEW FLOORING
4. REMOVE EXIST. PLUMBING FIXTURES, CUT AND CAP BELOW CONC. FLOOR
5. REMOVE EXIST. TOILET / SHOWER ACCESSORIES
6. REMOVE EXIST. CERAMIC FLOOR TILE, GROUT, AND MORTAR BED
7. REMOVE EXIST. CARPET
8. REMOVE EXIST. VINYL / RUBBER FLOORING
9. REMOVE EXIST. STAIR AND MEZZANINE AREA ABOVE; EXISTING EQUIPMENT TO BE RELOCATED; COORD. W/ MEP
10. EXISTING BOLLARDS TO REMAIN; PREP FOR NEW BOLLARD SLEEVE
11. EXISTING SLAB SHOWN AS ~~EXISTING~~ TO BE SAWCUT FOR FUTURE PLUMBING AND ELECTRICAL COORD. EXACT LOCATIONS W/ FLOOR PLANS AND MEP DRAWINGS
12. REMOVE EXIST. CABINET / MILLWORK
13. REMOVE EXISTING WALL SHELVING UNIT AND ALL ELEMENTS ASSOCIATED WITH IT
14. REMOVE EXIST. OVERHEAD DOOR, TRACK & OPERATOR
15. REMOVE EXISTING CEILING DOOR ABOVE AND ANY ASSOCIATED TRACK, MECHANISM, AND STRUCTURE
16. REMOVE EXISTING DOCK LEVELER AND ANY EQUIPMENT ASSOCIATED WITH IT; SEE SECTIONS FOR MORE INFORMATION
17. REMOVE EXIST. HANDRAIL; PREP CONCRETE SLAB TO BE FILLED TO FIRST FLOOR ELEVATION AND SAWCUT AS NECESSARY
18. REMOVE EXIST. WALL
19. REMOVE EXISTING TOILET PARTITIONS
20. EXISTING WALL TO REMAIN; PATCH AND REPAIR GWS AS NECESSARY
21. EXISTING ALUMINUM SLIDING DOOR TO BE RELOCATED; REMOVE FROM CURRENT LOCATION WITHOUT DAMAGING ASSEMBLY
22. EXISTING LADDER AND CAGE ABOVE; CUT OFF BOTH AT 10'-0" A.F.F.
23. CHASE FOR ROOF DRAIN TO REMAIN; PATCH AND REPAIR GWS AS NECESSARY
24. REMOVE EXISTING MERCHANDISE ALARM GATE AND ALL ASSOCIATED ELECTRICAL EQUIPMENT
25. SAW CUT CONCRETE SLAB AND PREP FOR FUTURE POWER TO TREADMILLS; COORD. TREADMILL LAYOUT W/ A.I.T.; COORD. W/ MEP DRAWINGS FOR MORE INFORMATION
26. EXISTING ELEVATED TRASH DOOR TO REMAIN

RELEASED FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
CODES ADMINISTRATION
LEE'S SUMMIT, MISSOURI

BY *[Signature]*
DATE 5-18-12

ALLEY-POYNER
MACCHIETTO
ARCHITECTURE 1516 Cuming Street
Omaha, NE 68102
Ph: 402.341.1544
Fax: 402.341.4735
alleepoyner.com

MECHANICAL ENGINEER
1516 Cuming Street
Omaha, NE 68102
Ph: 402.341.1544
Fax: 402.341.4735
alleepoyner.com



REVISION DATE
PROJECT NUMBER: 12012
DATE: 05/01/2012
COPYRIGHT © 2012
ALLEY-POYNER MACCHIETTO ARCHITECTURE, P.C.

DEMO FLOOR PLAN

AD1.1

R1 DEMO FLOOR PLAN

2011 SCALE: 1/8" = 1'-0"