

LEE'S SUMMIT FIRE DEPARTMENT

FIRE HEADQUARTERS
207 SE DOUGLAS STREET
LEE'S SUMMIT, MISSOURI 64063-2372
(816) 969-1300
FAX (816) 969-1313
TDD (816) 969-7407

PLANS REVIEW CONDITIONS

Permit No:	PRCOM20130108	Date:	March 26, 2013
Project Title:	SALON AMI	Applicant:	
Location:	930 NW BLUE PKWY, Unit:J, LEES SUMMIT, MO 64086	ABSOLUTE FIRE INC 5899 RAYTOWN ROAD RAYTOWN, MO 64133--3384	
Type of Work:			
Occupancy Group:	B		
Description:	TENANT FINISH FOR NEW HAIR SALON	Primary:	(816) 737-9991
Construction Type:	Type IIB (Unprotected)		
Map Page:	195A		

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Brian Austerman

Released for Construction

1. 2006 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call 969-1300 to schedule flow test in conjunction with alarm test

2. Sprinkler control valve in corridor needs to be marked with the appropriate suite designation. Verified at inspection

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.