

FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

Permit No: PRCOM20132419 Date: Project Title: LEES SUMMIT VOLKSWAGEN Location: 2225 NE INDEPENDENCE AVE, LEES SUMMIT, MO FIRE & SECURITY SOLUTIONS GROUP INC 64064 Type of Work: Occupancy Group: B/S1 Description: BUILDING FOR NEW CAR DEALERSHIP. Construction Type: Type VB (Unprotected) Map Page:

Applicant: 6025 MARTWAY STE 104 MISSION, KS 66202 (913) 789-7160

August 12, 2014

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review

Reviewed By: Brian Austerman

Released for Construction

1. 1. Unless the ambient condition warrants the necessity change the heat detectors to smoke detectors in the elevator shaft

2. Outside horn srtobe is to activate on a waterflow alarm only

3. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call (816) 969-1300 to schedule alarm testing

The applicant understands that the requirements listed above must be corrected to conform to applicable **City Codes and Ordinances.**