



## FIRE DEPARTMENT

### PLANS REVIEW CONDITIONS

Permit No:	PRCOM20141908	Date:	November 06, 2014
Project Title:	JOHN KNOX VILLAGE RESIDENTIAL CARE FACILITY	Applicant:	
Location:	400 NW MURRAY RD, LEES SUMMIT, MO 64081	NATIONAL FIRE SUPPRESSION INC 501 SUNSHINE ROAD KANSAS CITY, KS 66115--1294	
Type of Work:			
Occupancy Group:	R-2		
Description:	REPLACE EXISTING FIRE SUPPRESSION SYSTEM	Primary:	(913) 321-9208
Construction Type:	Not Applicable		
Map Page:			

**Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.**

#### **Sprinkler Plan Review**

**Reviewed By: Brian Austerman**

**Released for Construction**

1. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call (816) 969-1300 to schedule hydrostatic and flow testing

#### **Sprinkler Plan Review**

**Reviewed By: Brian Austerman**

**Released for Construction**

1. Provide label on FDC clearly stating which building it serves

2. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call (816) 969-1300 to schedule hydrostatic and flow testing

3. Mark interior riser room doors

4. Main drain needs to be routed to the exterior or to a drain capable of handling the flow

**The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.**