



PLANS REVIEW CONDITIONS

Permit No:	PRCOM20142004	Date:	April 14, 2015
Project Title:	LBP V-B	Applicant:	
Location:	2884 NE INDEPENDENCE AVE, LEES SUMMIT, MO 64064		BLUE SPRINGS ELECTRICAL SERVICE 3402 LAKE SHORE DR BLUE SPRINGS, MO 64014
Type of Work:			
Occupancy Group:	MIX		
Description:	SHELL BUILDING FOR OFFICE AND WAREHOUSE USE	Primary:	(816) 224-9911
Construction Type:	Type IIB (Unprotected)		
Map Page:	175R		

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review

Reviewed By: Brian Austerman

Released for Construction

1. Provide smoke detectors within 10' of the FACP and NAC panels
2. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

Call (816) 969-1300 to schedule alarm testing prior to final
3. "Silencing" the system shall terminate all horns and strobes
4. Outside horn strobe shall activate on a waterflow alarm only

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.