



LEE'S SUMMIT
MISSOURI



FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

Permit No: PRCOM20151735 Date: November 25, 2015
Project Title: LEE'S SUMMIT MEDICAL CENTER Applicant:
O.R. ADDITION REMODEL
Location: 2100 SE BLUE PKWY, LEES AMERICAN FIRE SPRINKLER CORPORATION
SUMMIT, MO 64063 PO BOX 958
MISSION, KS 66201
Type of Work: Primary: (913) 722-6900
Occupancy Group: I-2
Description: OPERATING ROOM ADDITION AND
INTERIOR ALTERATIONS
Construction Type: Type IB
Map Page:

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Joe Dir

Released for Construction

1. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.
FIELD TESTING REQUIRED FOR THE NEW INSTALLATION. TO SCHEDULE A TEST CONTACT THE FIRE DEPARTMENT AT 816-969-1300. INFORMATION PURPOSES

2. 2012 IFC 901.6- Inspection, testing and maintenance. Fire detection, alarm and extinguishing systems shall be maintained in an operative condition at all times, and shall be replaced or repaired where defective. Not required fire protection systems and equipment shall be inspected, tested and maintained or removed.
THE ORIGINAL SPRINKLER SYSTEM SHALL BE CURRENT ON THE ANNUAL SERVICE. CURRENT SERVICE TAG TO BE LOCATED ON THE RISER. VERIFIED AT INSPECTION.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.