

PR COM 2016 2278
off: a

August 12, 2016

Jeff Thorn
City of Lee's Summit, Missouri
220 SE Green Street
Lee's Summit, MO 64063

Re: Tudor Road Pump Station – Flood Work Electrical

R.F. Fisher Electric Company, LLC is pleased to offer the following proposal for the electrical portion of the aforementioned project. Our proposal is as follows:

Proposal #1: Flood Damage

1. Demo out high bay, fluorescent and exit light fixtures
2. Demo out conduits on walls submerged and fittings; safe off and pull out wire
3. Run rigid conduit, fittings, boxes to replace exposed conduits for outlets and switches to mirror those demoed out; pull in new wire
4. Demo out outlets and switches affected; replace and pull new wire
5. Provide (7) hibay lights with gripple aircraft cable safety hanger; (18) 4' fluorescent lights vaportite LED fixtures; (3) emergency exit light LED with battery backup, all installed in exact same locations
6. Provide elevator shaft fixture, vaportite jelly jar, and pump outlet
7. Provide (2) double duplex receptacle at ferric pumps
8. Wire in new sump pump control panel (furnished and installed by others;) check operation; label panel and wiring
9. All work to be performed during normal working hours; no overtime included in scope of work
10. Not included in RFF Scope of Work, to be performed by others as directed: parts under water, dual sumps controller; pressure switches; RTD's; valve accuator position switches; solenoid valves vibration sensors; and elevator controls; all stated items by others as directed.

PRICE PROPOSAL #1:

\$54,450.00

Fifty-Four Thousand Four Hundred Fifty Dollars and 0/100 cents

Proposal #2: Flow Meter Control Pipe

1. Horizontal power bore from control cabinet area into pit as directed 1" HDTP
2. At controller end excavate and turn into cabinet with 1" rigid rag roy coated pipe
3. Furnish and install 3-wire shielded cable from controller to pit; tie into controller flow meter by others as directed
4. All work to be performed during normal working hours; no overtime included in scope of work

PRICE PROPOSAL #2:

\$5,070.00

Five Thousand Seventy Dollars and 0/100 cents

Thank you for the opportunity to bid on this project. Feel free to call me at (913) 261-0616 if there are any questions.

Sincerely,

R. F. Fisher Electric Company, Inc.

Sam Valenti

Sam Valenti

Joe Frogge

From: Jeff Thorn
Sent: Wednesday, September 07, 2016 4:05 PM
To: Joe Frogge
Subject: FW: Tudor Road Pump Station permit

From: Brent Boice
Sent: Wednesday, September 07, 2016 4:02 PM
To: Jeff Thorn
Subject: RE: Tudor Road Pump Station permit

Please use 500 83 200 054 – 7306. If they could identify the charges as TUDOR ROAD PUMP STATION – EMERGENCY that would be helpful.

Yours Truly,

Brent Boice | Assistant Director of Support Service
220 SE Green Street | Lee's Summit, MO 64063
816.969.1920 | lswater.net | Brent.Boice@cityofls.net



From: Jeff Thorn
Sent: Wednesday, September 07, 2016 3:51 PM
To: Brent Boice
Subject: FW: Tudor Road Pump Station permit

We need account # to send to Joe for Tudor Elec Permit for Fisher.

Yours Truly,

Jeff Thorn, P.E. | Assistant Director of Engineering Services
220 SE Green Street | Lee's Summit, MO 64063
816.969.1922 | lswater.net | Jeff.Thorn@cityofls.net



From: Joe Frogge
Sent: Wednesday, September 07, 2016 3:27 PM
To: Jeff Thorn
Subject: Tudor Road Pump Station permit

Jeff,
Permit is ready to go. My off the hip estimate was way off. \$372.49