



# LEE'S SUMMIT MISSOURI

Central Building Services Department

220 S.E. Green St.

LEE'S SUMMIT, MISSOURI 64063

12-14-16

**Project:** Install new Replacement Unit Heater & bring current wiring to unit up to code

**SCOPE OF WORK:** Electrical project will be done in Hanger #1 at Air Charter facility located at 2525 NE Douglas RD. LSMO 64064. CBS Staff will provide labor and materials for the work as outlined in the following specification. CBS Staff will install one 60amp three pole disconnect to new hanging heater (480 volt three phase).

**SITE WORK:** CBS Staff will furnish all equipment and labor to complete the project.

**ELECTRICAL:** CBS Staff will furnish all labor and materials necessary to complete the electrical work relating to this project, as shown on the submitted plan, and outlined below. This will include:

1. Install one – 60amp disconnect to new replacement unit heater - 480 volt / 3 phase
2. Install 6AWG gauge to new replacement heater unit
3. Install new liquid tight metal flex conduit to new replacement heater unit
4. All circuits will originate from the 480v panel 3phase from north west corner of building

Total Project Evaluation \$ 1,500.00

Ron Johnson (CBS Supervisor)

