



LEE'S SUMMIT
MISSOURI



FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

| | | | |
|--------------------|---|---------------------------|-------------------|
| Permit No: | PRCOM20161179 | Date: | December 19, 2016 |
| Project Title: | JOHN KNOX VILLAGE - MEADOWS | Applicant: | |
| Location: | 1820 NW OBRIEN RD, LEES SUMMIT, MO 64081 | NATIONAL FIRE SUPPRESSION | |
| Type of Work: | | 501 SUNSHINE RD | |
| Occupancy Group: | R-2 | KANSAS CITY, KS 66115 | |
| Description: | BUILDING B - 3 STORY INDEPENDENT LIVING UNIT BUILDING | Primary: | (913) 321-9208 |
| Construction Type: | Type VA (1 hour) | | |
| Map Page: | 194D | | |

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Joe Dir

Released for Construction

1. PROVIDE UPDATED PLANS SHOWING STANDPIPE CONNECTIONS ON ALL FLOORS IN STAIRWAY #5.
2. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test. FIELD AND ACCEPTANCE TESTING OF THE FIRE SPRINKLER SYSTEM WILL BE REQUIRED PRIOR TO THE FINAL OCCUPANCY INSPECTION. TO SCHEDULE A TEST CONTACT THE FIRE DPEARTMENT AT 816-969-1300.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.