



LEE'S SUMMIT
MISSOURI



FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

Permit No:	PRCOM20161058	Date:	January 18, 2017
Project Title:	WATER UTILITIES FACILITY (HAMBLER RD)	Applicant:	
Location:	1200 SE HAMBLER RD, LEES SUMMIT, MO 64081	ADVANTAGE FIRE PROTECTION SYSTEMS INC 404 B NW 11TH ST BLUE SPRINGS, MO 64015	
Type of Work:		Primary:	(816) 224-3400
Occupancy Group:	S-1		
Description:	NEW WATER UTILITIES FACILITY		
Construction Type:	Type IIB (Unprotected)		
Map Page:	195R		

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Joe Dir

Released for Construction

1. PLANS SHOW THE FIRE DEPARTMENT CONNECTION AS A SIEMENSE CONNECTION. FIRE DEPARTMENT CONNECTION SHALL BE A 4 INCH STORTZ FITTING WITH A 30 DEGREE ELBOW. MAKE THE NEEDED CORRECTIONS.

2. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test. FIELD AND ACCEPTANCE TESTS OF THE SYSTEM ARE REQUIRED PRIOR TO THE FINAL OCCUPANCY INSPECTION. TO SCHEDULE A TEST CONTACT THE FIRE DEPARTMENT AT 816-969-1300.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.