

FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

Permit No: PRCOM20162583

SAINT LUKES HOSPITAL - CATH

LAB EXPANSION

Location:

Project Title:

20 NE SAINT LUKES BLVD, LEES

SUMMIT, MO 64086

Type of Work:

Occupancy Group: I-2

Description: CATH LAB EXPANSION

Construction Type: Type IA Map Page: 175X Date: January 27, 2017

Applicant:

SHAW ELECTRIC COMPANY

3600 FULLER

KANSAS CITY, MO 64129

Primary: (816) 921-0033

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review Reviewed By: Joe Dir Released for Construction

1. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

ALL NEW OR RELOCATED ALARM SYSTEM NOTIFICATION AND ACTIVATION DEVICES SHALL BE TESTED PRIOR TO THE FINAL OCCUPANCY INSPECTION. ALL CARD READERS, OR ELECTRONICALLY LOCKED ACCESS DOORS WILL DROP OFF ON THE ACTIVATION OF A FIRE ALARM OR POWER LOSS.TO SCHEDULE A TEST CONTACT THE FIRE DPEARTMENT AT 816-969-1300. (VERIFIED AT INSPECTION)

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.