

FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

Permit No: Project Title: Location:	PRCOM20170499 BROW THREADING	Date: June 08, 2017 Applicant:
Type of Work:	910 NW BLUE PKWY, Unit:D, LEES SUMMIT, MO 64086	ABSOLUTE FIRE INC 13906 CENTURY LN GRANDVIEW, MO 64030
Occupancy Group:		
1 2	TENANT FINISH FOR PERSONAL CARE SALON - FACIALS, WAXING, ETC	Primary: (816) 737-9991
	***NEW CONTACT PERSON- JUAN JUAREZ-816-738-4019. PRIMARY CONTACT POINT FOR JOB. ype: Type IIB (Unprotected) 195A	

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Joe Dir

Released for Construction

1. 2006 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test. ACTION REOUIRED:

The systems flow and tamper switches shall be tested prior to final occupancy inspection.

2. 2012 IFC 901.6- Inspection, testing and maintenance. Fire detection, alarm and extinguishing systems shall be maintained in an operative condition at all times, and shall be replaced or repaired where defective. Not required fire protection systems and equipment shall be inspected, tested and maintained or removed.

ACTION REQUIRED:(veriifed at inspection)

The existing fire sprinkler riser shall be current with all required serving and maintenence. A current service tag shall be posted on the systems riser.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.