



Skeens Consulting Services, LLC

Engineering, Inspections & Design Build

Michael H. Skeens, PE

mike@skeensconsulting.com

423 N. Winnebago Drive

Ph: (816) 806-9719




Lake Winnebago, MO 64034

Project: Stairway header required for
minimum headroom clearances

Location: 1324
~~1324~~ Brandywine Road, L.S. MO

Client: Pfeifer Homes, Inc.


Date: Sept 11, 2017 pg. 1 of 1



EDGE REINFORCEMENT
MAINTAIN CODE REQUIRED CLEARANCES

1 piece(s) 2 x 10 Douglas Fir-Larch No. 2

Overall Length: 4' 4"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	242 @ 2"	1434 (2.25")	Passed (17%)	--	1.0 D + 1.0 L (All Spans)
Shear (lbs)	208 @ 1' 3/4"	1665	Passed (12%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	276 @ 2' 7"	1765	Passed (16%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.004 @ 2' 1 11/16"	0.100	Passed (L/999+)	--	1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.005 @ 2' 1 3/4"	0.200	Passed (L/999+)	--	1.0 D + 1.0 L (All Spans)

System : Floor
Member Type : Flush Beam
Building Use : Residential
Building Code : IBC 2012
Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Top Edge Bracing (Lu): Top compression edge must be braced at 4' 2" o/c unless detailed otherwise.
- Bottom Edge Bracing (Lu): Bottom compression edge must be braced at 4' 2" o/c unless detailed otherwise.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)			Accessories
	Total	Available	Required	Dead	Floor Live	Total	
1 - Beam - SPF	3.50"	2.25"	1.50"	77	169	246	1 1/4" Rim Board
2 - Beam - SPF	3.50"	2.25"	1.50"	77	131	208	1 1/4" Rim Board

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Comments
0 - Self Weight (PLF)	1 1/4" to 4' 2 3/4"	N/A	3.5		
1 - Uniform (PSF)	0 to 4' 4" (Front)	2' 8"	12.0	-	Residential - Living Areas
2 - Point (lb)	1' 3" (Front)	N/A	-	150	
3 - Point (lb)	2' 7" (Front)	N/A	-	150	


Member Notes

1321 Brandywine Road
Lees Summit, MO
Pfeiffer Homes Inc.
Rick Holbrooke

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC E5 under technical reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator



<p>Forfe Software Operator</p> <p>Michael Steens</p> <p>Steens Consulting Services, LLC</p> <p>(816) 805-9719</p> <p>msteens@steensconsulting.com</p>	<p>Job Notes</p>
---	------------------

9/11/2017 1:28:24 AM
Forte v5.3, Design Engineer V7.0 0.5