



LEE'S SUMMIT
MISSOURI



FIRE DEPARTMENT

PLANS REVIEW CONDITIONS

Permit No:	PRCOM20172360	Date:	February 09, 2018
Project Title:	HARBOR FREIGHT TOOLS	Applicant:	
Location:			
	300 SW BLUE PKWY, Unit:A, LEES	FORD ENTERPRISES	
	SUMMIT, MO 64063	3809 PINNACLE CIR	
Type of Work:		LAWRENCE, KS 66049	
Occupancy Group:	M		
Description:	TENANT FINISH FOR TOOL SALES	Primary:	(913) 568-2459

**invite planner to final to verify screening
Construction Type: Type IIB (Unprotected)
Map Page: 195K

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review

Reviewed By: Joe Dir

Released for Construction

1. 2012 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

ACTION REQUIRED:

Acceptance testing of the system will be required prior to the final occupancy inspection. contact the fire department to schedule testing. (816)969-1300.

2. Notification devices.

ACTION REQUIRED:

Install strobe notification devices in the restrooms as per the revised attached sheet.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.