

October 24, 2018

**Kevin Higdon Construction** PO Box 847 Lee's Summit, MO 64063

Re:

Permit #: PRRES20181851 1531 SW Blackstone PI Lee's Summit, MO 64082

Apex Engineers, Inc. has been asked to address comments from the city rough-in inspection for the house at the address above.

Provide engineers report on cut LVL in master bedroom.

The (2) 1 3/4"x18" LVL has a tapered notch at each end. There is 9" of remaining member depth at the notch, measured at the bearing wall at each end of the beam. After computations, the (2) 1 34"x18" LVL adequately supports the design loads.

Our firm recommends approval of this structural issue. Please call if Apex Engineers, Inc. can be of further assistance.

#### LIMITATIONS

The scope of our services includes only those items specifically addressed herein. No attempt was made to design or check the design of any structural members other than those specifically addressed herein. All other items are outside the scope of this inspection; including but not limited to, any environmental assessment (such as, but not limited to mold, mildew, presence of hazardous or toxic materials in the soil, surface water, ground water, etc.).

In addition, the scope of our services does not include any evaluation of the building or site for job-site safety and/or hazardous conditions. All construction shall be performed in compliance with IRC and OSHA standards at all times. Our firm has not been retained to examine the site or building for any of these conditions. In addition, the contractor shall retain sole responsibility for the quality of work, for adhering to plans, specifications, appropriate codes, and, for repairing defects, deficiencies or omission, regardless of when they are found.

Best Regards, Apex Engineers, Inc.

Joshua M. Jensen, E.I.T.

Project Engineer

Apex Engineers 1625 Locust St Kansas City, Missouri 64108 www.apex-engineers.com Title Block" selection.

Project Title: Engineer: Project ID: Project Descr:

Title Block Line 6
Wood Beam

SW Blackstone Place\_Lot 1531 Napa Valley\_LSMO\2018.10.24\_Struct\_Kevin Higdon Homes\Eng\text{beam calcs.ec6}

Lic. # : KW-06005244

Description : LVL Over Master Bedroom

Licensee: APEX ENGINEERS INC


**CODE REFERENCES** 

Calculations per NDS 2015, IBC 2015, CBC 2016, ASCE 7-10

Load Combination Set : IBC 2012

**Material Properties** 

Analysis Method: Allowable Stress Design	Fb+	2600 psi	E : Modulus of Elasti	city
Load Combination 1BC 2012	Fb-	2600 psi	Ebend- xx	1900 ksi
	Fc - Prll	2510 psi	Eminbend - xx	965.71 ksi
Wood Species : Trus Joist	Fc - Perp	750 <b>psi</b>		
Wood Grade : MicroLam LVL 1.9 E	Fv .	285 <b>psi</b>		
Hood Olddo , Miorocam Eve 1.0 E	Ft	1555 <b>ps</b> i	Density	42 pcf
Beam Bracing : Beam is Fully Braced against lateral-tors	sional buckling	,	,	



Span = 21.50 ft

**Applied Loads** 

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loads

Uniform Load: D = 0.0050, L = 0.010 ksf, Tributary Width = 8.0 ft, (Ceiling Load)

Point Load: D = 0.860, L = 1.720 k @ 10.0 ft, (Points Load From Ridge Above)

Point Load: D = 0.1020, L = 0.2040 k @ 7.50 ft, (Point Load From Roof Hip)

Point Load: D = 0.0510, L = 0.1020 k @ 1.0 ft

DESIGN SUMMARY						Desig	n OK
Maximum Bending Stress Ratio Section used for this span fb : Actual	=	0.562 1 2-1.75x18 1,461.48psi	Maximum Shear Stress F Section used for this fv : Actual		=	2-1.7	.238 : 1
FB : Allowable	=	2,600.00 <b>psi</b>	Fv : Allowable	<b>)</b>	=		5.00 <b>psi</b>
Load Combination Location of maximum on span Span # where maximum occurs	=	+D+L+H 9.965 <b>ft</b> Span # 1	Load Combination Location of maximum on Span # where maximum		S OF M	+[	+L+H 0.000 <b>ft</b> an # 1
Maximum Deflection Max Downward Transient Deflect Max Upward Transient Deflection Max Downward Total Deflection Max Upward Total Deflection		0.331 in Rat 0.000 in Rat 0.525 in Rat 0.000 in Rat	io = 0 < 360 io = 491 >= 180	PARO	CLAYTO HESS NOMB PE-20020	n Z poque	
Maximum Forces & Stresses	s for Loa	ad Combinations			SIONA	ENCHAR	
Load Combination Max Stress	Ratios		Mo	ment Values	THE PERSON NAMED IN	Sh	ear Values
Segment Length Span # M	γ (	Cd C <sub>F/V</sub> Ci Cr	C <sub>m</sub> C <sub>t</sub> C <sub>L</sub> M	fb	F'b	٧	fv F'
+D+H					0.00	0.00	0.00 0.0

Apex Engineers 1625 Locust St Kansas City, Missouri 64108 www.apex-engineers.com Title Block" selection. Title Block Line 6 Project Title: Engineer: Project ID: Project Descr:

**Wood Beam** 

+0.60D+0.60W+0.60H

+0.60D+0.70E+0.60H

D Only

Lr Only L Only

S Only W Only E Only H Only SW Blackstone Place\_Lot 1531 Napa Valley\_LSMO\2018.10.24\_Struct\_Kevin Higdon Homes\Eng\beam calcs.ec6

Lic. # : KW-060	005244	Licensee : APEX ENGINEERS INC
Description:	LVL Over Master Bedroom	

Load Combination		Max Stress	s Ratios								Mor	ment Values			Shear Va	alues
Segment Length	Span #	М	V	$C_d$	C <sub>F/V</sub>	Сį	Cr	C <sub>m</sub>	Ct	CL	М	fb	F'b	V	fv	F'v
Length = 21.50 ft	1	0.227	0.099	0.90	1.000	1.00	1.00	1.00	1.00	1.00	8.38	531.86	2340.00	1.06	25.35	256.50
+D+L+H					1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.562	0.238	1.00	1.000	1.00	1.00	1.00	1.00	1.00	23.02	1,461.48	2600.00	2.85	67.94	285.00
+D+Lr+H					1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.164	0.071	1.25	1.000	1.00	1.00	1.00	1.00	1.00	8.38	531.86	3250.00	1.06	25.35	356.25
+D+S+H					1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.178	0.077	1.15	1.000	1.00	1.00	1.00	1.00	1.00	8.38	531.86	2990.00	1.06	25.35	327.75
+D+0.750Lr+0.750L+H					1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.378	0.161	1.25	1.000	1.00	1.00	1.00	1.00	1.00	19.36	1,229.08	3250.00	2.41	57.29	356.25
+D+0.750L+0.750S+H					1.000	1.00	1.00	1.00	1.00	1.00		•	0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.411	0.175	1.15	1.000	1.00	1.00	1.00	1.00	1.00	19.36	1,229.08	2990.00	2.41	57.29	327.75
+D+0.60W+H					1.000	1.00	1.00	1.00	1.00	1.00		•	0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.128	0.056	1.60	1.000	1.00	1.00	1.00	1.00	1.00	8.38	531.86	4160.00	1.06	25.35	456.00
+D+0.70E+H					1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.128	0.056	1.60	1.000	1.00	1.00	1.00	1.00	1.00	8.38	531.86	4160.00	1.06	25.35	456.00
+D+0.750Lr+0.750L+0.4	50W+H				1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.295	0.126	1.60	1.000	1.00	1.00	1.00	1.00	1.00	19.36	1,229.08	4160.00	2.41	57.29	456.00
+D+0.750L+0.750S+0.45	60W+H				1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.295	0.126	1.60	1.000	1.00	1.00	1.00	1.00	1.00	19.36	1,229.08	4160.00	2.41	57.29	456.00
+D+0.750L+0.750S+0.52	250E+H				1.000	1.00	1.00	1.00	1.00	1.00		•	0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.295	0.126	1.60	1.000	1.00	1.00	1.00	1.00	1.00	19.36	1,229.08	4160.00	2.41	57.29	456.00
+0.60D+0.60W+0.60H					1.000	1.00	1.00	1.00	1.00	1.00		.,	0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.077	0.033	1.60	1.000	1.00	1.00	1.00	1.00	1.00	5.03	319.12	4160.00	0.64	15.21	456.00
+0.60D+0.70E+0.60H					1.000	1.00	1.00	1.00	1.00	1.00			0.00	0.00	0.00	0.00
Length = 21.50 ft	1	0.077	0.033	1.60	1.000	1.00	1.00	1.00	1.00	1.00	5.03	319.12	4160.00	0.64	15.21	456.00

Overall Maximum Deflection Load Combination Sp	ns Max. "-" Defl Location in S	Span Load Combination	Max. "+" Defl	Location in Span
→ むれ出	1 0.5247 10.59	3	0.0000	0.000
Vertical Reactions	M M	Support notation : Far left is #1	Values in KIPS	
Load Combination	Support 1 Support	2	101	
Overall MAXimum	3.213 2.80	o1 \( \frac{1}{2} \)		
Overall MINimum	2.010 1.73	36 )		
WOHL WHEEL .	1.202	35		
+D+L+H	3.213 2.80	01		
+D+Lr+H	1.203 1.06	65		
+D+S+H	1.203 1.06	65		
+D+0.750Lr+0.750L+H	2.710 2.36	57		
+D+0.750L+0.750S+H	2.710 2.36	57		
+D+0.60W+H	1.203 1.06	65		
+D+0.70E+H	1.203 1.06	65		
+D+0.750Lr+0.750L+0.450W+H	2.710 2.36	67		
+D+0.750L+0.750S+0.450W+H	2.710 2.36	57		
+D+0.750L+0.750S+0.5250E+H	2.710 2.36	67		

0.639

0.639

1.065

1.736

0.722

0.722


1.203

2.010



Project: 1531 SW Blackstone PI Client: Kevin Higdon Homes

Engineer: JMJ
Date: 10/25/2018
Description: Notched LVL



# **NOTCHED/TAPERED BEAM CALCULATIONS**

## Input (to find shear value):

	1
Location =	North End
Type of notch =	Tapered Beam
Type of lumber =	LVL
b =	3.50 in
d =	18.00 in
d <sub>n</sub> =	9.00 in
L=	21.60 ft
V =	2810 lb
C <sub>D</sub> =	1.15
f <sub>v</sub> =	134 psi
F' <sub>v</sub> =	328 psi
Pass or Fail	Pass

The shear force in the member at the notch is calculated as:

The actual shear stress in the member at the notch is calculated as:

For notched members:  $f_v = \frac{3V}{2bd_n} \left[ \frac{d}{d_n} \right]^2$ 

For tapered members:  $f_v = \frac{3V}{2bd_n}$ 

The adjusted design value of the allowable shear stress is calculated as:

 $F_{v}' = F_{v}C_{D}$ 

### Nomenclature:

b = Width of Member

d = Depth of Member (Unnotched)

d<sub>n</sub> = Depth of Member at Notch (Measured Perpendicular to the Longitudinal Axis)

L = Span Length of Member

V = Shear Force in Member at Notch

C<sub>D</sub> = Load Duration Factor (From NDS Table 2.3.2)

f<sub>v</sub> = Actual Shear Stress in Member at Notch

F<sub>v</sub> = Reference design value for allowable shear stress (from manufacturers data)


F'<sub>v</sub> = Allowable Shear Stress





Project: 1531 SW Blackstone Pl Client: Kevin Higdon Homes

Engineer: JMJ
Date: 10/25/2018
Description: Notched LVL



# **NOTCHED/TAPERED BEAM CALCULATIONS**

# Input (to find shear value):

_	
	1
Location =	South End
Type of notch =	Tapered Beam
Type of lumber =	LVL
b =	3.50 in
d =	18.00 in
d <sub>n</sub> =	9.00 in
L =	21.60 ft
V =	3210 lb
C <sub>D</sub> =	1.15
f <sub>v</sub> =	153 psi
F' <sub>v</sub> =	328 psi
Pass or Fail	Pass

The shear force in the member at the notch is calculated as:

The actual shear stress in the member at the notch is calculated as:

For notched members:  $f_v = \frac{3V}{2bd_n} \left[ \frac{d}{d_n} \right]^2$ 

For tapered members:  $f_v = \frac{3V}{2bd_n}$ 

The adjusted design value of the allowable shear stress is calculated as:

 $F_{v}' = F_{v}C_{D}$ 

#### Nomenclature:

b = Width of Member

d = Depth of Member (Unnotched)

d<sub>n</sub> = Depth of Member at Notch (Measured Perpendicular to the Longitudinal Axis)

L = Span Length of Member

V = Shear Force in Member at Notch

C<sub>D</sub> = Load Duration Factor (From NDS Table 2.3.2)

f<sub>v</sub> = Actual Shear Stress in Member at Notch

F<sub>v</sub> = Reference design value for allowable shear stress (from manufacturers data)

F'<sub>v</sub> = Allowable Shear Stress

