PLAN REVIEW CONDITIONS

May 02, 2019

ACI BOLAND 1421 EAST 104TH ST; SUITE 100 KANSAS CITY, MO 64131

Permit No: PRCOM20191072

Project Title: SAINT LUKES HOSPITAL - ED WAITING ROOM AND NURSE STATION

Project Address: 80 NE SAINT LUKES BLVD, LEES SUMMIT, MO 64086

Parcel Number: 52440044000000000

Location: SAINT LUKES HOSPITAL OF LEES SUMMIT LOTS 1 & 2---LOT 1

Type of Work: ALTERATION COMMERCIAL
Occupancy Group: INSTITTIONAL, INCAPACITATED

Description: INTERIOR ALTERATIONS - ED WAITING ROOMS AND NURSE STATION REMODEL

The following is a list of requirements from the City of Lee's Summit that have not been satisfactorily addressed in the plans and specifications. Please contact the appropriate department regarding clarification of comments.

Development Services Department (816) 969-1200

Fire Department (816) 969-1300

Building Plan Review

Reviewed By: Joe Frogge

Approved

1. A License Tax application completed by the contractor must be submitted to the City of Lee's Summit, Codes Administration Department, and any applicable License Tax paid prior to issuing a building permit.

Action required: Comment is for informational purposes.

Fire Plan Review Reviewed By: Joe Dir Approved with Conditions

1. 2018 IFC 907.1.1- Construction documents. Construction documents for fire alarm systems shall be submitted for review and approval prior to system installation. Construction documents shall include, but not be limited to, all of the following: 1. A floor plan which indicates the use of all rooms. 2. Locations of alarm-initiating and notification appliances. 3. Alarm control and trouble signaling equipment. 4. Annunciation. 5. Power connection. 6. Battery calculations. 7. Conductor type and sizes. 8. Voltage drop calculations. 9. Manufacturers, model numbers and listing information for equipment, devices and materials. 10. Details of ceiling height and construction. 11. The interface of fire safety control functions. ACTION REQUIRED: (information purposes)

Have the fire alarm system contractor provide three sets of PE stamped shop drawings of any modifications to be done to the fire alarm system.

2. 2018 IFC 901.2- Construction documents. The fire code official shall have the authority to require construction documents and calculations for all fire protection systems and to require permits be issued for the installation, rehabilitation or modification of any fire protection system. Construction documents for fire protection systems shall be submitted for review and approval prior to system installation. ACTION REQUIRED: (information purposes)

Have the fire sprinkler system contractor provide three sets of PE stamped shop drawings of any modifications to be done to the fire sprinkler system

3. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

ACTION REQUIRED:(information purposes)

Any modification done to the fire alarm system will be required to be tested prior to the final occupancy inspection. Contact the fire department to schedule testing.(816)969-1300

4. Med Gas

ACTION REQUIRED: (information purposes)

Any med gas lines and or pressure monitoring devices relocated or installed new will require a pressure test on the system. Documentation of the testing shall be provided to the fire department at the conclusion of testing prior to the final occupancy inspection.

The approval of plans and specifications does not permit the violation of any section of the Building Codes or other City Ordinances or State Law.

The review conducted by the City of Lee's Summit Development Services Department shall not be construed as a structural review of the project.