



PLANS REVIEW CONDITIONS

Permit No:	PRCOM20190589	Date:	June 28, 2019
Project Title:	OUR LADY OF PRESENTATION - CLASSROOM ADDITION	Applicant:	
Location:	150 NW MURRAY RD, LEES SUMMIT, MO 64081	PROGRESSIVE ELECTRONICS INC	
Type of Work:		6102 ARLINGTON AVE	
Occupancy Group:	E	RAYTOWN, MO 64133	
Description:	ADDITION OF 2ND AND 3RD FLOOR CLASSROOMS TO EXISTING CHURCH	Primary: (816) 765-5750	
Construction Type:	Type IIB (Unprotected)		
Map Page:	195E		

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

1. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Action Required)

Call (816)969-1300 to schedule a test. Test must be conducted before a final occupancy inspection.

2. (Action Required)

Three smoke detectors added to second floor corridor. (See additional plan sheet attached to plans.)

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.