

PLANS REVIEW CONDITIONS

Permit No: PRCOM20190274 Date: June 30, 2019
Project Title: LEES SUMMIT SURGICAL CENTER Applicant:
Location: 2801 NE INDEPENDENCE AVE, LEES SUMMIT, MO 64064 JAYHAWK FIRE SPRINKLER CO INC
Type of Work: 12030 S HEDGE LANE TERRACE
Occupancy Group: B OLATHE, KS 66061
Description: NEW SHELL BUILDING FOR
OUTPATIENT SURGICAL, SPORTS TRAINING, AND SPORTS REHAB Primary: (913) 422-3770
RE:PRCOM20190276 FOR FOUNDATION PERMIT
Construction Type: Type IIB (Unprotected)
Map Page: 175R

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

1. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Action Required)

Call (816)969-1300 to schedule testing. Testing to be completed before a final occupancy inspection.

2. (Informational Purposes)

If no backflow is present between the hydrant and the riser, a check valve at the base of the riser will be required.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.