









12
13



Foundation Notes:

- Drainage shall be maintained around the foundation of all times, both during and after the construction period. Surface water shall flow rapidly away from the foundation. The builder shall obtain the owner's responsibility to maintain drainage and wall materials so that future soil movements are minimized.
- Slab shall be 6" thick U.C.W.
- Perimeter beams shall be 12" x 12" x 12" Rebar beams shall be dropped to extend 12" min. below final grade.
- All drains shall be 1 1/2" x 1 1/2" (See Gen. Notes)
- Concrete contractor shall be provided with a plan showing the location of all drains and the location of the footing engineer's station. The location of drains requiring drilling shall be laid out prior to the concrete placement, and post-tensioning drains shall be drilled when required to avoid the existing footing by at least one foot.
- BS & - indicates beam strand to be dropped down into bottom of beam. See beam strand detail on detail sheet. Beam strand required only if shown on foundation plan.
- See General Notes and Typical Detail Sheet.
- Antenna/Infra drains shall be verified or furnished by the builder. See note #2 under Concrete Construction on General Notes Sheet.
- If uncoordinated fit exists on the site, plans may be required. NOTIFY ENGINEER.

Site Preparation Notes:

- Potential soil movements will increase if building pads are allowed to dry out prior to construction. This office recommends procedures be used to maintain at least a "moist" or "average" soil moisture content.
- Grading plan shall ensure that positive drainage is maintained away from the foundation. This office recommends a 5% slope for the first 10' from the building pad. Failure to maintain drainage may allow water to pond or collect around the foundation, causing potential harm in excess of that predicted in the Geotechnical report.
- After clearing, sloping, and excavating, the exposed sub-grade should be carefully evaluated by good rolling, probing and testing. Any undesirable material should be removed and replaced or stabilized per the geotechnical report. The subgrade should then be evaluated by the Geotechnical Engineer. Construct the building pad by placing and compacting structural fill per the geotechnical report. The top 18" of the building pad shall consist of low volume change (LVC) material, and extend at least 5' beyond the building footprint. A 4 inch granular leveling course and moisture barrier shall be placed below the floor slab. (The leveling course may be considered part of the 18" LVC zone. All fill material shall be approved by the geotechnical engineer prior to placement. All fill grading and soil remediation shall be completed in accordance with the site report and with oversight from the geotechnical engineer.
- The depth to bedrock varied across the site. Each building should be evaluated individually and the bearing material should be determined prior to construction. The footings for each individual building should either bear entirely on native soil and engineered fill or entirely on bedrock. Bearing on multiple material types may result in abrupt differential settlement resulting in cracking and differential movement of buildings.

Example Dimension Notes:
Verify all dimensions with Architectural plans. Contact Architect if there are any discrepancies that cannot be created in the field.

STRAND

10000 Technology Blvd, West Valley, TX 75220
832-424-4224
Registration No. 2006010474

DATE	BY	FOR	REVISION
09/28/2018	MSU	MSU	1
09/28/2018	MSU	MSU	2
09/28/2018	MSU	MSU	3
09/28/2018	MSU	MSU	4
09/28/2018	MSU	MSU	5
09/28/2018	MSU	MSU	6
09/28/2018	MSU	MSU	7
09/28/2018	MSU	MSU	8
09/28/2018	MSU	MSU	9
09/28/2018	MSU	MSU	10

Client:
ACCU-CRETE, INC.
9445 Maplewood Dr
Upper Merion, PA 15104
703-535-7820

Architect:
MSU Architects
3015 W. 75th St., Suite 201
P.O. Box 1416, KS 66206
913-831-1415

Summit Square II Apartments
Lee Summit, MISSOURI
Forming & Reinforcement Plan
Trash Compactor

DATE 09/28/2018
SCALE As Shown
DRN R.D.
CODE 4.12.44.120
FD-8.0
STRAND M18048

Details Trash Compactor
Scale: 3/4" = 1'-0"