

Knapp Engineering, LLC  
89 Beringer CT.  
Saint Charles, MO 63304



FEBRUARY 5, 2020

To:  
AJ Brown Construction

Re:  
Goddard School – Lee’s Summit, MO

To whom it may concern,

Due to some truss and girder alignment and elevation adjustments, the roof truss support girder across the entry were redesigned. The girder trusses are bearing on the stud posts at each end and are held down using a Simpson LGT4-SDS3 at each end. The Simpson connector has an uplift capacity of 4,060# ASD which is far greater than the new uplift will be at each location. The truss construction and connections used are acceptable.

Regards,

A handwritten signature in black ink, appearing to read "Michael D. Knapp".

**Michael D. Knapp, P.E.**



2/5/2020