

### **PLANS REVIEW CONDITIONS**

Permit No: PRCOM20183215	Date: February 12, 2020
Project Title: OAKVIEW STORAGE	Applicant:
Location: 1420 NE DOUGLAS ST, LEES SUMMIT, MO 64086	PALMER ELECTRIC CO 6600 ROYAL ST, BLDG B PLEASANT VALLEY, MO 64068
Type of Work:	
Occupancy Group: S-1	Primary: (816) 479-2587
Description: CLIMATE CONTROLLED STORAGE FACILITY	
Construction Type: Type VB (Unprotected)	
Map Page: 175X	

**Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.**

#### **Alarm Plan Review**

**Reviewed By: Michael Weissenbach**

**Released for Construction**

1. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)

Call (816)969-1300 to schedule alarm testing.

#### **2. (ACTION REQUIRED)**

2018 IFC 907.2

Add one manual pull station by front door.

**The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.**