



RE: 400215
Lot 28 H4

MiTek USA, Inc.

16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2018/TPI2014

Design Program: MiTek 20/20 8.2

Wind Code: N/A

Wind Speed: 115 mph

Roof Load: 45.0 psf

Floor Load: N/A psf


This package includes 44 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I40875214	a1	4/6/2020	27	I40875240	j3	4/6/2020
2	I40875215	a2	4/6/2020	28	I40875241	j4	4/6/2020
3	I40875216	a3	4/6/2020	29	I40875242	j5	4/6/2020
4	I40875217	b1	4/6/2020	30	I40875243	lay1	4/6/2020
5	I40875218	b2	4/6/2020	31	I40875244	r1	4/6/2020
6	I40875219	c1	4/6/2020	32	I40875245	v1	4/6/2020
7	I40875220	c2	4/6/2020	33	I40875246	v2	4/6/2020
8	I40875221	d1	4/6/2020	34	I40875247	v3	4/6/2020
9	I40875222	d2	4/6/2020	35	I40875248	v4	4/6/2020
10	I40875223	e1	4/6/2020	36	I40875249	v5	4/6/2020
11	I40875224	e2	4/6/2020	37	I40875250	v6	4/6/2020
12	I40875225	e3	4/6/2020	38	I40875251	v7	4/6/2020
13	I40875226	g1	4/6/2020	39	I40875252	v8	4/6/2020
14	I40875227	g2	4/6/2020	40	I40875253	v9	4/6/2020
15	I40875228	g3	4/6/2020	41	I40875254	v10	4/6/2020
16	I40875229	h1	4/6/2020	42	I40875255	v11	4/6/2020
17	I40875230	h2	4/6/2020	43	I40875256	v12	4/6/2020
18	I40875231	h3	4/6/2020	44	I40875257	v13	4/6/2020
19	I40875232	h4	4/6/2020				
20	I40875233	h5	4/6/2020				
21	I40875234	h6	4/6/2020				
22	I40875235	h7	4/6/2020				
23	I40875236	h8	4/6/2020				
24	I40875237	h9	4/6/2020				
25	I40875238	j1	4/6/2020				
26	I40875239	j2	4/6/2020				

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
04/20/2020

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision
based on the parameters provided by Wheeler - Waverly.
Truss Design Engineer's Name: Garcia, Juan
My license renewal date for the state of Kansas is April 30, 2022.
Kansas COA: E-943

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.





RE: 400215
Lot 28 H4

MiTek USA, Inc.

16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):

Design Code: IRC2018/TPI2014

Design Program: MiTek 20/20 8.2

Wind Code: N/A

Wind Speed: 115 mph

Roof Load: 45.0 psf


Floor Load: N/A psf

This package includes 44 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I40875214	a1	4/6/2020	27	I40875240	j3	4/6/2020
2	I40875215	a2	4/6/2020	28	I40875241	j4	4/6/2020
3	I40875216	a3	4/6/2020	29	I40875242	j5	4/6/2020
4	I40875217	b1	4/6/2020	30	I40875243	lay1	4/6/2020
5	I40875218	b2	4/6/2020	31	I40875244	r1	4/6/2020
6	I40875219	c1	4/6/2020	32	I40875245	v1	4/6/2020
7	I40875220	c2	4/6/2020	33	I40875246	v2	4/6/2020
8	I40875221	d1	4/6/2020	34	I40875247	v3	4/6/2020
9	I40875222	d2	4/6/2020	35	I40875248	v4	4/6/2020
10	I40875223	e1	4/6/2020	36	I40875249	v5	4/6/2020
11	I40875224	e2	4/6/2020	37	I40875250	v6	4/6/2020
12	I40875225	e3	4/6/2020	38	I40875251	v7	4/6/2020
13	I40875226	g1	4/6/2020	39	I40875252	v8	4/6/2020
14	I40875227	g2	4/6/2020	40	I40875253	v9	4/6/2020
15	I40875228	g3	4/6/2020	41	I40875254	v10	4/6/2020
16	I40875229	h1	4/6/2020	42	I40875255	v11	4/6/2020
17	I40875230	h2	4/6/2020	43	I40875256	v12	4/6/2020
18	I40875231	h3	4/6/2020	44	I40875257	v13	4/6/2020
19	I40875232	h4	4/6/2020				
20	I40875233	h5	4/6/2020				
21	I40875234	h6	4/6/2020				
22	I40875235	h7	4/6/2020				
23	I40875236	h8	4/6/2020				
24	I40875237	h9	4/6/2020				
25	I40875238	j1	4/6/2020				
26	I40875239	j2	4/6/2020				

The truss drawing(s) referenced above have been prepared by
MiTek USA, Inc. under my direct supervision
based on the parameters provided by Wheeler - Waverly.
Truss Design Engineer's Name: Garcia, Juan
My license renewal date for the state of Missouri is December 31, 2020.
Missouri COA: 001193

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



April 06, 2020

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875214
400215	A1	Hip Girder	1	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:14 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-uHLWv1lzhj?z5t218TTfEpOuFdtQBUIMU35tjhzTVkt

Job Reference (optional)

-0-10-8	4-0-0	10-0-0	14-0-0	14-10-8
0-10-8	4-0-0	6-0-0	4-0-0	0-10-8

Scale = 1:26.1




Plate Offsets (X,Y)-- [2:0-4-1,0-0-0], [3:0-3-8,0-2-3], [5:0-4-1,0-0-0], [7:0-3-2,0-6-8], [7:0-3-4,0-1-10], [10:0-3-4,0-1-10], [10:0-1-10,0-3-4]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	-0.13	8-9	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.89	Vert(CT)	-0.27	8-9	>598	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.11	Horz(CT)	0.03	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.11	8-9	>999	240	Weight: 46 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
3-4: 2x4 SPF 2100F 1.8E
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2 *Except*
2-10,5-7: 2x8 SP DSS

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-10-9 oc purlins, except end verticals, and 2-0-0 oc purlins (5-6-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 10=0-3-8, 7=0-3-8
Max Horz 10=-50(LC 6)
Max Uplift 10=-225(LC 8), 7=-225(LC 9)
Max Grav 10=1023(LC 1), 7=1023(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1485/318, 3-4=-1233/302, 4-5=-1487/318, 2-10=-919/222, 5-7=-920/222
BOT CHORD 9-10=-268/1244, 8-9=-270/1231, 7-8=-242/1246
WEBS 3-9=0/338, 4-8=0/338

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=225, 7=225.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 79 lb down and 74 lb up at 4-0-0, 86 lb down and 74 lb up at 6-0-0, and 86 lb down and 74 lb up at 8-0-0, and 79 lb down and 74 lb up at 10-0-0 on top chord, and 220 lb down and 76 lb up at 4-0-0, 31 lb down at 6-0-0, and 31 lb down at 8-0-0, and 220 lb down and 76 lb up at 9-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



April 6, 2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875214
400215	A1	Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:14 2020 Page 2
ID:vBszku21ozNPT?RizYtJMSyXqDi-uHLWv1lzhj?z5t218TTfEpOuFdtQBuiMU35tjhzTVkt

LOAD CASE(S) Standard
Uniform Loads (plf)
Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-5=-70, 5-6=-70, 7-10=-20
Concentrated Loads (lb)
Vert: 3=-46(F) 4=-46(F) 9=-220(F) 8=-220(F) 11=-46(F) 12=-46(F) 13=-25(F) 14=-25(F)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	140875215
400215	A2	Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:16 2020 Page 1

ID: vBsZku21ozNPT?RizYtJMSyXqDi-qgTGKiJDDKfgKBCQGuv7KETL3QikfP_fyMa_nazTVkr



Scale = 1:27.0




Plate Offsets (X,Y)--		[7:0-4-1,0-2-8], [10:0-4-1,0-2-8]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.50	Vert(LL) -0.03 9-10 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.26	Vert(CT) -0.07 9-10 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.06	Horz(CT) 0.01 7 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Wind(LL) 0.01 9-10 >999 240	Weight: 45 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x3 SPF No.2 *Except*
 2-10,5-7: 2x6 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-11-5 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 10=0-3-8, 7=0-3-8
 Max Horz 10=-61(LC 6)
 Max Uplift 10=-94(LC 8), 7=-94(LC 9)
 Max Grav 10=687(LC 1), 7=687(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-803/77, 3-4=-625/115, 4-5=-804/77, 2-10=-624/138, 5-7=-624/138
 BOT CHORD 9-10=-28/627, 8-9=-29/624, 7-8=0/627

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	
400215	A3	Common	4	1		I40875216
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:17 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-Is1fX2Kr_eNxyLncpb0MsS0V5q1BOreoB0KXJ0zTVkq



Scale = 1:27.8



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.54	Vert(LL)	-0.04	MT20	197/144		
TCDL	10.0	Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.09				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.01				
BCDL	10.0	Code IRC2018/TPI2014		Matrix-R		Wind(LL)	0.03	Weight: 40 lb		FT = 10%	

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x6 SPF No.2 *Except*
 3-7: 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-9-9 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 8=0-3-8, 6=0-3-8
 Max Horz 8=-69(LC 6)
 Max Uplift 8=-101(LC 8), 6=-101(LC 9)
 Max Grav 8=687(LC 1), 6=687(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-772/105, 3-4=-772/105, 2-8=-630/150, 4-6=-630/150
 BOT CHORD 7-8=-20/586, 6-7=-20/586
 WEBS 3-7=0/296

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=101, 6=101.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875217
400215	B1	Monopitch	7	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:18 2020 Page 1

ID: vBsZku21ozNPT?RlZyYtJMSyXqDi-n3b1OLTlxVOZVMonJXbPfZinEPf7JLxPg35sTzTVkp



Scale = 1:13.9

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.42	Vert(LL)	-0.03	2-4	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.23	Vert(CT)	-0.06	2-4	>933	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.00	2	****	240		
									Weight: 13 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 2=0-3-8
Max Horz 2=76(LC 5)
Max Uplift 4=-45(LC 8), 2=-58(LC 4)
Max Grav 4=212(LC 1), 2=252(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875218
400215	B2	Monopitch	3	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:18 2020 Page 1

ID:vBsZku21ozNPT?RlZyTjMSyXqDi-n3b1IOLTxVOZVMonJXbPfZdKEMj7JLxPg35sTzTVkp



Scale = 1:18.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.77	Vert(LL)	-0.17	2-4	>553	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.42	Vert(CT)	-0.34	2-4	>276	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.00	2	****	240	Weight: 21 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E

BOT CHORD 2x4 SPF 2100F 1.8E

WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0'-0 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10'-0'-0 oc bracing.

REACTIONS.


(size) 4=Mechanical, 2=0-3-8
Max Horz 2=121(LC 5)
Max Uplift 4=-74(LC 8), 2=-79(LC 4)
Max Grav 4=348(LC 1), 2=386(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-270/121

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6'-0 tall by 2'-0'-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875219
400215	C1	GABLE	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:19 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-FF9PykL5WFdFBex_x03qxt5ybeo7smA5eKpeOvzTVko



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	0.00	1	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	0.00	1	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 35 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


All bearings 10-0-0.
(lb) - Max Horz 2=158(LC 5)
Max Uplift All uplift 100 lb or less at joint(s) 8, 2, 12, 11, 10, 9
Max Grav All reactions 250 lb or less at joint(s) 8, 2, 12, 11, 10, 9

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 2-0-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 2, 12, 11, 10, 9.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875220
400215	C2	Monopitch	10	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:21 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-BeG9NQNM1stzQy5N2R5I1IAFsRPuKZKO5ellTnzTVkm

Job Reference (optional)



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.30	Vert(LL)	-0.02	2-6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.26	Vert(CT)	-0.04	5-6	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.50	Horz(CT)	0.01	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.02	2-6	>999	240	Weight: 33 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 5=Mechanical, 2=0-3-8
Max Horz 2=158(LC 5)
Max Uplift 5=94(LC 8), 2=-115(LC 4)
Max Grav 5=435(LC 1), 2=514(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-782/113
BOT CHORD 2-6=-134/682, 5-6=-134/682
WEBS 3-5=-714/178

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5 except (jt=lb) 2=115.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	140875221
400215	D1	Common Supported Gable	1	1		


Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:22 2020 Page 1

ID: vBsZku21ozNPT?RlZyTjMSyXqDi-fqqYamO_oA?q26gZc8cXZVjTsrpK37oXK11?EzTVkl

0-10-8	11-2-0	22-4-0	23-2-8
0-10-8	11-2-0	11-2-0	0-10-8

Scale = 1:38.6



LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL		1.15		TC	0.09	Vert(LL)	0.00	13		n/r		120		MT20		197/144	
TCDL	10.0	Lumber DOL		1.15		BC	0.06	Vert(CT)	0.00	13		n/r		120					
BCLL	0.0 *	Rep Stress Incr		YES		WB	0.03	Horz(CT)	0.00	12		n/a		n/a					
BCDL	10.0	Code IRC2018/TPI2014				Matrix-S													
																		Weight: 77 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

All bearings 22-4-0.
(lb) - Max Horz 2=-71(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 2, 20, 21, 22, 23, 18, 17, 15, 14, 12
Max Grav All reactions 250 lb or less at joint(s) 2, 19, 20, 21, 22, 18, 17, 15, 12 except 23=275(LC 21),
14=275(LC 22)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 20, 21, 22, 23, 18, 17, 15, 14, 12.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2, 12.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875222
400215	D2	Common	5	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:23 2020 Page 1

ID:vBszku21ozNPT?RlZyYtJMSyXqDi-70Owo6PcZU7hgGEmAs7m6jGYiF?coYhhZynsXgzTVkk

0-10-8	5-3-15	11-2-0	17-0-1	22-4-0	23-2-8
0-10-8	5-3-15	5-10-1	5-10-1	5-3-15	0-10-8

Scale = 1:38.6




Plate Offsets (X,Y)-- [2:0-0-0,0-0-10], [6:0-0-0,0-0-10]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	-0.12 9-10 >999 360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.69	Vert(CT)	-0.25 6-9 >999 240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.19	Horz(CT)	0.07 6 n/a n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.08 9-10 >999 240	Weight: 68 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 2=0-3-8, 6=0-3-8
Max Horz 2=-71(LC 13)
Max Uplift 2=-189(LC 4), 6=-189(LC 5)
Max Grav 2=1063(LC 1), 6=1063(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2232/355, 3-4=-1909/259, 4-5=-1909/260, 5-6=-2232/355
BOT CHORD 2-10=-333/2049, 9-10=-127/1406, 6-9=-280/2049
WEBS 4-9=-59/541, 5-9=-418/221, 4-10=-58/541, 3-10=-418/221

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=189, 6=189.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	
400215	E2	Common	3	1		I40875224

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:25 2020 Page 1

ID:vBsZku21ozNPT?RlZyYtJMSyXqDi-3PWgDnQs55NPvZO8HH9EB8LqH3gDGR6z0GGycZzTVki

0-10-8 5-2-1 10-0-0 14-10-0 20-0-0 20-10-8
0-10-8 5-2-1 4-10-0 4-10-0 5-2-1 0-10-8

4x5 =

Scale = 1:46.3




Plate Offsets (X,Y)--	[2:0-3-5,0-0-0], [6:0-3-5,0-0-0], [8:0-1-14,0-7-1], [8:0-2-5,0-1-8], [10:0-2-5,0-1-8], [10:0-2-11,0-4-0]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.72	Vert(LL)	-0.17	9-10	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.75	Vert(CT)	-0.35	9-10	>662	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.25	Horz(CT)	0.03	8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.05	9	>999	240	Weight: 70 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2 *Except*
2-10,6-8: 2x6 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-3-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 10=0-3-8, 8=0-3-8
Max Horz 10=215(LC 7)
Max Uplift 10=-124(LC 8), 8=-124(LC 9)
Max Grav 10=957(LC 1), 8=957(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1100/163, 3-4=-842/156, 4-5=-842/155, 5-6=-1100/163, 2-10=-855/174, 6-8=-855/174
BOT CHORD 9-10=-147/836, 8-9=-42/803
WEBS 4-9=-48/492, 5-9=-266/215, 3-9=-266/215

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 10=124, 8=124.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875225
400215	E3	Roof Special Girder	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:26 2020 Page 1

ID: vBsZku21ozNPT?RizYtJMSyXqDi-Yb42Q7RusPVGXjzLr_hTkLuxeS58?jT7Fw?W8?zTVkh



8x8 //

Scale = 1:45.5





Plate Offsets (X,Y)--	[5:0-2-14,Edge], [7:Edge,0-2-5], [8:0-4-7,0-7-0], [9:0-6-12,0-1-8], [10:0-4-8,0-4-12], [11:0-7-4,0-6-0], [12:0-6-12,0-1-8], [13:0-3-8,0-3-0]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 1.00	Vert(LL)	-0.17	8-9	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.32	Vert(CT)	-0.30	8-9	>786	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.95	Horz(CT)	0.14	7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.09	8-9	>999	240	Weight: 310 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x10 SP 2400F 2.0E
 WEBS 2x4 SPF No.2 *Except*
 3-12: 2x4 SPF 2100F 1.8E

WEDGE

Left: 2x4 SP No.3, Right: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=0-3-8 (req. 0-5-7), 7=0-3-8 (req. 0-5-7)
 Max Horz 1=-181(LC 25)
 Max Uplift 1=-375(LC 8), 7=-246(LC 9)
 Max Grav 1=6961(LC 1), 7=6942(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-9102/438, 2-3=-14466/672, 3-4=-8589/373, 4-5=-8344/462, 5-6=-9174/480, 6-7=-9499/322
 BOT CHORD 1-13=-412/6986, 12-13=-15/313, 10-11=-585/12345, 8-9=-8/424, 7-8=-201/7551
 WEBS 11-12=-54/1760, 3-11=-286/6184, 9-10=-20/1903, 4-10=-198/301, 2-13=-4060/204, 11-13=-461/7757, 2-11=-169/5323, 3-10=-6056/422, 8-10=-143/5366, 5-10=-385/6632, 5-8=-267/3392, 6-8=-314/536

NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
 Top chords connected as follows: 2x4 - 1 row at 0-3-0 oc.
 Bottom chords connected as follows: 2x10 - 2 rows staggered at 0-6-0 oc.
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- WARNING: Required bearing size at joint(s) 1, 7 greater than input bearing size.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=375, 7=246.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4
400215	E3	Roof Special Girder	1	2	I40875225
					Job Reference (optional)

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:27 2020 Page 2
ID:vBszku21ozNPT?RIzYtJMSyXqDi-0neQeTS7did78tYXPiCiGZQ6OsRNkAkJGual3gRzTVkg

NOTES-

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1338 lb down and 188 lb up at 2-0-0, 1351 lb down and 35 lb up at 4-0-0, 1363 lb down and 44 lb up at 6-0-0, 1363 lb down and 44 lb up at 8-0-0, 1351 lb down and 35 lb up at 10-0-0, 1351 lb down and 35 lb up at 12-0-0, 1338 lb down and 36 lb up at 14-0-0, and 1338 lb down and 36 lb up at 16-0-0, and 1338 lb down and 36 lb up at 18-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
 - Uniform Loads (plf)
 - Vert: 1-5=-70, 5-7=-70, 1-12=-20, 10-11=-20, 7-9=-20
 - Concentrated Loads (lb)
 - Vert: 14=-1338(B) 15=-1351(B) 16=-1363(B) 17=-1363(B) 18=-1351(B) 19=-1351(B) 20=-1338(B) 21=-1338(B) 22=-1338(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	140875226
400215	G1	GABLE	1	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:28 2020 Page 1
ID: vBszku21ozNPT?RizYtJMSyXqDi-U_BprpSIO0mzm17jzPjxpmzLaGkcTpeQiEuDCuzTVkf




Plate Offsets (X,Y)--										[2:0-3,0,0-14], [4:0-3,0,0-9], [6:0-3,0,0-14], [8:0-1,9,0-4,0], [8:0-2,14,0,0-0], [11:0-2,14,0,0-0], [11:0-1,9,0,4-0], [13:0-1,14,0-1,0], [20:0-1,14,0-1,0]									
LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL		1.15		TC	0.72	Vert(LL)	-0.10	9-10	>999		360		MT20		197/144		
TCDL	10.0	Lumber DOL		1.15		BC	0.51	Vert(CT)	-0.24	9-10	>635		240						
BCLL	0.0 *	Rep Stress Incr		YES		WB	0.14	Horz(CT)	0.09	8	n/a		n/a						
BCDL	10.0	Code IRC2018/TPI2014				Matrix-S		Wind(LL)	0.05	9-10	>999		240		Weight: 60 lb		FT = 10%		

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2 *Except*
2-11,6-8: 2x6 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-5-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 11=0-3-8, 8=0-3-8
Max Horz 11=154(LC 7)
Max Uplift 11=-88(LC 8), 8=-88(LC 9)
Max Grav 11=642(LC 1), 8=642(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-966/113, 3-4=-849/230, 4-5=-849/193, 5-6=-966/70, 2-11=-784/128, 6-8=-784/100
BOT CHORD 10-11=-97/776, 9-10=0/453, 8-9=-2/717
WEBS 4-9=-138/417, 4-10=-161/460

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 11, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Wheeler Lumber, Waverly, KS 66871 8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:29 2020 Page 1
ID:vBszku21ozNPT?RlzytJMSyXqDi-yAlB29TN9KuqOBivW6EAL_WWJg4rCGZxuEAIKzTVke
0-10-8 3-3-8 6-6-0 9-8-8 13-0-0 13-10-8
0-10-8 3-3-8 3-2-8 3-2-8 3-3-8 0-10-8
4x5 || Scale = 1:32.9




REACTIONS. (size) 11=0-3-8, 8=0-3-8
 Max Horz 11=154(LC 7)
 Max Uplift 11=-88(LC 8), 8=-88(LC 9)
 Max Grav 11=642(LC 1), 8=642(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-966/113, 3-4=-849/230, 4-5=-849/193, 5-6=-966/70, 2-11=-784/128, 6-8=-784/100
BOT CHORD	10-11=-97/776, 9-10=0/453, 8-9=-2/717
WEBS	4-9=-138/417, 4-10=-161/460

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 5) Bearing at joint(s) 11, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 8.
 - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.




April 6, 2020

Wheeler Lumber, Waverly, KS 66871 8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:30 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-QMJZGVU?wd0h?LH64qIPuB2j44O2xi1jAYzjHmzTVkd

3-3-8 6-6-0 9-8-8 12-10-8
3-3-8 3-2-8 3-2-8 3-2-0

Scale = 1:29.8



LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 5-2-9 oc purlins, except end verticals.
BOT CHORD	2x4 SPF No.2		
WEBS	2x3 SPF No.2 *Except*	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
	1-9,5-6: 2x6 SPF No.2		

REACTIONS. (size) 9=Mechanical, 6=0-2-0
 Max Horz 9=136(LC 5)
 Max Uplift 9=-62(LC 8), 6=-61(LC 9)
 Max Grav 9=559(LC 1), 6=559(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-960/122, 2-3=-865/240, 3-4=-832/206, 4-5=-931/86, 1-9=-681/106, 5-6=-667/81
BOT CHORD	8-9=-119/764, 7-8=-13/441, 6-7=-38/692
WEBS	3-8=-169/475, 3-7=-144/401

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDF=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Bearing at joint(s) 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 6.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9, 6.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875229
400215	H1	Common Supported Gable	2	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:31 2020 Page 1
ID: vBszku21ozNPT?RizYtJMSyXqDi-uZtxTrVdhx8YdUsleXGeQPb?xTubg9gsPCjHpCzTVkc




Plate Offsets (X,Y)--										[18:0-0-10,0-1-4], [19:0-0-0,0-1-4]									
LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL		1.15		TC	0.07	Vert(LL)	-0.00	1	n/r	120		MT20	197/144				
TCDL	10.0	Lumber DOL		1.15		BC	0.05	Vert(CT)	-0.00	1	n/r	120							
BCLL	0.0 *	Rep Stress Incr		YES		WB	0.19	Horz(CT)	0.01	19	n/a	n/a							
BCDL	10.0	Code IRC2018/TPI2014				Matrix-R								Weight: 147 lb	FT = 10%				

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
18-19: 2x3 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.

REACTIONS.

All bearings 31'-0".
(lb) - Max Horz 36=138(LC 12)
Max Uplift All uplift 100 lb or less at joint(s) 36, 29, 30, 31, 32, 33, 34, 26, 25, 24, 23, 22, 21, 20 except 35=-106(LC 8)
Max Grav All reactions 250 lb or less at joint(s) 36, 19, 28, 29, 30, 31, 32, 33, 34, 35, 26, 25, 24, 23, 22, 21, 20

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2'-0" oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 36, 29, 30, 31, 32, 33, 34, 26, 25, 24, 23, 22, 21, 20 except (jt=lb) 35=106.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	140875230
400215	H2	Roof Special	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:33 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-qx?iuWWtCYOGso?hlyJ6Wqg7VHLV8wD9sWCou5zTVka

0-10-8	7-9-10	15-6-0	18-9-0	23-2-7	31-0-0
0-10-8	7-9-10	7-8-6	3-3-0	4-5-7	7-9-9

Scale = 1:55.6




Plate Offsets (X,Y)--		[2:0-5-3,0-0-0], [7:0-5-13,0-4-0], [9:0-2-8,0-2-0], [13:Edge,0-2-8], [14:0-2-8,0-1-8], [15:0-4-2,0-2-1], [15:0-1-13,0-3-8]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.96	Vert(LL) -0.35 11 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.92	Vert(CT) -0.67 13-14 >538 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.76	Horz(CT) 0.24 8 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Wind(LL) 0.20 11 >999 240	Weight: 121 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E *Except*
4-7: 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
4-13,5-10: 2x3 SPF No.2, 8-10: 2x4 SPF 2100F 1.8E
WEBS 2x3 SPF No.2 *Except*
2-15,7-8: 2x10 SP DSS

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
2-2-0 oc bracing: 14-15,8-9.

REACTIONS.


(size) 15=0-3-8, 8=Mechanical
Max Horz 15=137(LC 8)
Max Uplift 15=-198(LC 8), 8=-168(LC 9)
Max Grav 15=1450(LC 1), 8=1358(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2200/268, 3-4=-2418/266, 4-5=-2289/296, 5-6=-3368/300, 6-7=-2137/261,
2-15=-1341/237, 7-8=-1201/209
BOT CHORD 14-15=-274/1833, 4-12=-109/1610, 11-12=-132/2943, 5-11=-99/1179, 8-9=-151/1789
WEBS 3-14=-603/213, 12-14=-299/1946, 3-12=-30/347, 5-12=-1300/199, 9-11=-182/2172,
6-11=-49/1191, 6-9=-1270/194

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 15=198, 8=168.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875231
400215	H3	Roof Special	2	1		

Wheeler Lumber, Waverly, KS 66871


8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 10:26:44 2020 Page 1

ID: vBsZku21ozNPT?RlZyTjMSyXqDi-iObtVmahEQ6ZqH4y6VQ?Bw3gxmLbCNonTJGZ_ozTTD9

-0-10-8	2-3-8	7-9-9	13-6-0	15-6-0	23-2-7	31-0-0
0-10-8	2-3-8	5-6-1	5-8-7	2-0-0	7-8-7	7-9-9

8x8 =

Scale = 1:57.0



2-3-8	7-9-9	13-6-0	23-2-7	31-0-0
2-3-8	5-6-1	5-8-7	9-8-7	7-9-9

Plate Offsets (X,Y)-- [2:0-0-0,0-0-7], [3:0-0-8,0-2-2], [3:0-6-8,0-1-8], [8:0-4-0,0-5-13]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.80	Vert(LL)	-0.32 10-11	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.72	Vert(CT)	-0.72 10-11	>505	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.50	Horz(CT)	0.33 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.15 3-13	>999	240	Weight: 143 lb	FT = 10%

LUMBER-

TOP CHORD 2x6 SP 2400F 2.0E *Except*
6-8: 2x4 SPF 2100F 1.8E
BOT CHORD 2x4 SPF 2100F 1.8E *Except*
2-14: 2x4 SPF No.2, 3-14,5-11: 2x3 SPF No.2
WEBS 2x3 SPF No.2 *Except*
6-10: 2x4 SPF No.2, 8-9: 2x10 SP DSS

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-4-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 2-14.
WEBS 1 Row at midpt 4-12

REACTIONS.


(size) 2=0-3-8, 9=Mechanical
Max Horz 2=106(LC 5)
Max Uplift 2=-21(LC 8), 9=-15(LC 9)
Max Grav 2=1455(LC 1), 9=1371(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-809/45, 3-4=-2973/49, 4-5=-2020/54, 5-6=-1831/102, 6-7=-2171/156, 7-8=-2216/36, 8-9=-1232/55
BOT CHORD 3-13=-51/2719, 12-13=-50/2719, 9-10=0/1862
WEBS 4-13=0/301, 4-12=-1189/108, 10-12=0/1270, 6-12=-51/886, 6-10=-130/698, 7-10=-492/200

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SPF No.2 crushing capacity of 425 psi.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 2 and 15 lb uplift at joint 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875232
400215	H4	Roof Special	2	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 10:26:49 2020 Page 1
ID:vBszku21ozNPT?RlZyTJMSyXqDi-3MOmYUeq2ykrx2zv2?Bu_mWkn2ItYVWdbzKg?zTTD4

0-10-8 2-3-8 7-9-10 15-6-0 23-2-6 24-4-0 31-0-0
0-10-8 2-3-8 5-6-2 7-8-6 7-8-6 1-1-10 6-8-0

Scale = 1:58.8




Plate Offsets (X,Y)-- [2:0-0-0,0-0-7], [3:0-0-8,0-2-2], [3:0-6-8,0-1-8], [8:Edge,0-2-8], [11:0-1-8,0-1-0]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.28	3-13	>999	360	MT20	197/144	
TCDL	10.0	Lumber DOL	1.15	BC	0.81	Vert(CT)	-0.53	3-13	>700	240			
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.36	9	n/a	n/a			
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.16	3-13	>999	240	Weight: 138 lb	FT = 10%	

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
1-5: 2x6 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2 *Except*
3-14: 2x3 SPF No.2, 3-12: 2x4 SPF 2100F 1.8E
WEBS 2x3 SPF No.2 *Except*
7-9,15-17,11-16: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-8.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 2-14.
WEBS 1 Row at midpt 4-11, 6-11, 7-9

REACTIONS.

(size) 9=Mechanical, 2=0-3-8
Max Horz 2=162(LC 5)
Max Uplift 9=24(LC 9), 2=20(LC 8)
Max Grav 9=1383(LC 1), 2=1468(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-817/0, 3-4=-2995/60, 4-5=-1870/50, 5-6=-1861/60, 6-7=-2796/3
BOT CHORD 3-13=-88/2738, 12-13=-87/2738, 11-12=-87/2738, 10-11=-42/2576, 9-10=-39/2684
WEBS 4-13=0/316, 4-11=-1295/148, 5-11=0/1081, 6-11=-1112/93, 6-10=0/466, 7-10=-278/70, 7-9=-2842/30

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- All bearings are assumed to be SPF No.2 crushing capacity of 425 psi.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 24 lb uplift at joint 9 and 20 lb uplift at joint 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 6,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875233
400215	H5	Roof Special	1	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 10:26:58 2020 Page 1
ID:vBszku210zNPT?RlZyIjM5YXQDI-I5RARYITxjtaWR9exRglite3OP41UczrhUfIT_zTTCx

-0-10-8 2-3-8 7-9-10 15-6-0 23-11-0 27-2-6 31-0-0
0-10-8 2-3-8 5-6-2 7-8-6 8-5-0 3-3-6 3-9-10

6x8 =

Scale = 1:57.0




Plate Offsets (X,Y)-- [2:0-0-0,0-0-7], [3:0-0-8,0-2-2], [3:0-6-8,0-1-8], [8:0-2-14,0-1-14], [8:0-2-5,0-4-10], [9:0-0-0,0-4-10], [10:0-2-8,0-1-8], [13:0-1-8,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.80	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.90	Vert(LL) -0.29 3-15 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.84	Vert(CT) -0.56 12-13 >647 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.40 9 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.16 3-15 >999 240	Weight: 140 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x6 SP 2400F 2.0E *Except* 5-8: 2x4 SPF 2100F 1.8E	TOP CHORD Structural wood sheathing directly applied or 3-4-5 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2 *Except* 3-16,6-11: 2x3 SPF No.2, 3-14,9-11: 2x4 SPF 2100F 1.8E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 2-16.
WEBS 2x3 SPF No.2 *Except* 6-13,17-19,13-18: 2x4 SPF No.2, 8-9: 2x10 SP DSS	WEBS 1 Row at midpt 4-13, 6-13

REACTIONS. (size) 2=0-3-8, 9=Mechanical
Max Horz 2=106(LC 5)
Max Uplift 2=-21(LC 8), 9=-15(LC 9)
Max Grav 2=1455(LC 1), 9=1371(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-809/45, 3-4=-2954/56, 4-5=-1848/48, 5-6=-1855/55, 6-7=-3070/48, 7-8=-1992/24, 8-9=-1142/37
BOT CHORD 3-15=-59/2699, 14-15=-58/2699, 13-14=-58/2699, 12-13=0/2819, 6-12=0/473, 9-10=0/1655
WEBS 4-15=0/301, 4-13=-1271/146, 5-13=0/1030, 6-13=-1352/145, 10-12=0/1683, 7-12=0/1178, 7-10=-797/30

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - All bearings are assumed to be SPF No.2 crushing capacity of 425 psi.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 2 and 15 lb uplift at joint 9.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875234
400215	H6	Common	4	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:37 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-jjECkuZOGnuilPJSoN2ggrYujO4okn8Ab1szTVkW

0-10-8 7-9-10 15-6-0 23-2-6 31-0-0
0-10-8 7-9-10 7-8-6 7-8-6 7-9-10

Scale = 1:55.2




Plate Offsets (X,Y)--		[2:0-5-3,0-0-0], [6:0-5-13,0-4-0], [12:0-1-13,0-3-8], [12:0-4-2,0-2-1]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 25.0	2-0-0	TC 0.89	in (loc) l/defl L/d
TCDL 10.0	Plate Grip DOL 1.15	BC 0.92	Vert(LL) -0.27 8-10 >999 360
BCLL 0.0 *	Lumber DOL 1.15	WB 0.47	Vert(CT) -0.51 8-10 >711 240
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.08 7 n/a n/a
	Code IRC2018/TPI2014		Wind(LL) 0.11 8-10 >999 240
			PLATES MT20
			GRIP 197/144
			Weight: 106 lb FT = 10%

LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E
BOT CHORD 2x4 SPF 2100F 1.8E *Except*
9-12: 2x4 SPF No.2
WEBS 2x3 SPF No.2 *Except*
2-12,6-7: 2x10 SP DSS

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2-2-0 oc bracing: 11-12.
1 Row at midpt 5-10, 3-10

REACTIONS.


(size) 12=0-3-8, 7=Mechanical
Max Horz 12=112(LC 5)
Max Uplift 12=-29(LC 8), 7=-16(LC 9)
Max Grav 12=1450(LC 1), 7=1358(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2190/43, 3-4=-1586/73, 4-5=-1589/72, 5-6=-2175/44, 2-12=-1337/73,
6-7=-1211/59
BOT CHORD 11-12=-44/1824, 10-11=-44/1824, 8-10=0/1827, 7-8=0/1827
WEBS 4-10=0/773, 5-10=-651/125, 3-10=-647/124, 3-11=0/274

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 12, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875235
400215	H7	Common	3	1		


Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:38 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-BvobxEa0150ZzZueYVvHDT00Jl3gpF0u0nv8ZlZTVkV

0-10-8 7-9-10 15-6-0 23-2-6 31-0-0 31-10-8
0-10-8 7-9-10 7-8-6 7-8-6 7-9-10 0-10-8

Scale = 1:55.7



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.89	Vert(LL)	-0.22 11-12	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.92	Vert(CT)	-0.44 9-11	>820	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.47	Horz(CT)	0.09 8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.13 11-12	>999	240	Weight: 108 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF 2100F 1.8E	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x3 SPF No.2 *Except*	WEBS 1 Row at midpt 5-11, 3-11
2-13,6-8: 2x10 SP DSS	

REACTIONS.	(size) 13=0-3-8, 8=0-3-8
	Max Horz 13=-126(LC 6)
	Max Uplift 13=-198(LC 8), 8=-198(LC 9)
	Max Grav 13=1449(LC 1), 8=1449(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2187/271, 3-4=-1582/243, 4-5=-1582/243, 5-6=-2187/271, 2-13=-1336/239, 6-8=-1336/239
BOT CHORD	12-13=-265/1821, 11-12=-265/1821, 9-11=-140/1821, 8-9=-140/1821
WEBS	4-11=-48/760, 5-11=-647/250, 5-9=0/274, 3-11=-647/250, 3-12=0/274

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 13=198, 8=198.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875236
400215	H8	Common Girder	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:39 2020 Page 1
ID:vBsZku21ozNPT?RizYtJMSyXqDi-f5Mz9abeoO8QbjTq6DQWl5wB2iS2Ydv1ERfi5zTVkU




LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-0.16	MT20		197/144	
TCDL	10.0	Lumber DOL	1.15	BC	0.65	Vert(CT)	-0.30				
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.81	Horz(CT)	0.07				
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.11				

LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2 *Except* 4-6: 2x4 SPF 2400F 2.0E	TOP CHORD	Structural wood sheathing directly applied.
BOT CHORD	2x6 SP 2400F 2.0E	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SPF No.2	WEBS	1 Row at midpt 5-10
WEDGE			
Right: 2x6 SP No.2			

REACTIONS.	
(size)	6=0-3-8 (req. 0-4-7), 2=0-3-8
Max Horz	2=93(LC 5)
Max Uplift	6=-544(LC 9), 2=-178(LC 8)
Max Grav	6=5627(LC 1), 2=2718(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	2-3=-5014/352, 3-4=-4374/398, 4-5=-4376/397, 5-6=-9433/899
BOT CHORD	2-11=-317/4297, 10-11=-317/4297, 8-10=-779/8913, 7-8=-723/8265, 6-7=-718/8213
WEBS	4-10=-255/3303, 5-10=-5832/721, 5-7=-291/2879, 3-10=-678/221, 3-11=0/305, 5-8=-188/1970

NOTES-	
1)	2-ply truss to be connected together with 10d (0.131"x3") nails as follows: Top chords connected as follows: 2x4 - 1 row at 0-4-0 oc. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-3-0 oc. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
2)	All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3)	Unbalanced roof live loads have been considered for this design.
4)	Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
5)	This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6)	* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
7)	WARNING: Required bearing size at joint(s) 6 greater than input bearing size.
8)	Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=544, 2=178.
9)	This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
10)	Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 3353 lb down and 392 lb up at 21-10-7, 539 lb down and 82 lb up at 23-11-4, 539 lb down and 82 lb up at 25-11-4, and 539 lb down and 82 lb up at 27-11-4, and 540 lb down and 81 lb up at 29-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.



April 6,2020

Continued on page 2	
LOAD CASE(S) Standard	
WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE. Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.	
MiTek 16023 Swingley Ridge Rd Chesterfield, MO 63017	

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875236
400215	H8	Common Girder	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:39 2020 Page 2
ID:vBszku21ozNPT?RizYtJMSyXqDi-f5Mz9abeoO8QbjTq6DQWI5wB2iS2Ydv1ERfi5zTVkU

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-70, 4-6=-70, 2-6=-20
Concentrated Loads (lb)
Vert: 8=-3353(B) 12=-539(B) 13=-539(B) 14=-539(B) 15=-540(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875237
400215	H9	Roof Special	6	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:40 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-7HwLMwcGZiGHct21gwXlITM16qYH8YBT5OFdBzTVkT

0-10-8 7-9-10 15-6-0 22-0-0
0-10-8 7-9-10 7-8-6 6-6-0

4x9 =

Scale = 1:50.9




Plate Offsets (X,Y)-- [2:0-4-1,0-0-0], [6:Edge,0-2-8], [10:0-3-4,0-1-10], [10:0-1-10,0-3-4]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	-0.09	7-9	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.57	Vert(CT)	-0.21	7-9	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.53	Horz(CT)	0.17	12	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.05	7-9	>999	240	Weight: 84 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2 *Except*
2-10: 2x8 SP DSS
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 3-7

REACTIONS.


(size) 10=0-3-8, 12=0-2-8
Max Horz 10=223(LC 5)
Max Uplift 10=-156(LC 8), 12=-122(LC 8)
Max Grav 10=1056(LC 1), 12=943(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1465/195, 3-4=-768/129, 4-5=-705/160, 2-10=-966/201
BOT CHORD 9-10=-269/1196, 7-9=-269/1196
WEBS 3-9=0/302, 3-7=-733/262, 5-7=-93/646, 5-12=-955/124

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 12.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=156, 12=122.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875238
400215	J1	Diagonal Hip Girder	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:41 2020 Page 1

ID:vBsZku21ozNPT?RlZyTjMSyXqDi-bUUjaFdvK007q1dDDeS_qW?eAVFn0j1Kil8pAdzTVkS



Scale = 1:17.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.41	Vert(LL)	-0.03	4-5	>999	360	MT20	197/144
BCLL 10.0	Lumber DOL	1.15	BC 0.25	Vert(CT)	-0.07	4-5	>967	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240		
									Weight: 16 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
3-4: 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-6-6 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 5=0-4-9, 4=Mechanical
Max Horz 5=111(LC 5)
Max Uplift 5=101(LC 4), 4=50(LC 8)
Max Grav 5=346(LC 1), 4=224(LC 1)

FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-306/140

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=101.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 69 lb down and 36 lb up at 2-9-8, and 69 lb down and 36 lb up at 2-9-8 on top chord, and 3 lb down and 1 lb up at 2-9-8, and 3 lb down and 1 lb up at 2-9-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S)

- Standard
- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-70, 2-3=-70, 4-5=-20
Concentrated Loads (lb)
Vert: 7=2(F=1, B=1)



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875239
400215	J2	Jack-Open	4	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:42 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-4g25nbdX5JW_SBBPnLzDNjYs4vdxIAHUwPtMi4zTVkR



Scale = 1:16.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.20	Vert(LL)	-0.01	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	-0.02	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240	Weight: 11 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=0-3-8, 3=Mechanical, 4=Mechanical
Max Horz 5=89(LC 8)
Max Uplift 5=-30(LC 8), 3=-66(LC 8)
Max Grav 5=252(LC 1), 3=116(LC 1), 4=71(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875240
400215	J3	Jack-Open	4	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:42 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-4g25nbdX5JW_SBBPnLzDNjYu9vealAHUwPtMi4zTVkR



Scale = 1:11.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	Weight: 6 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=0-3-8, 3=Mechanical, 4=Mechanical
Max Horz 5=48(LC 8)
Max Uplift 5=-26(LC 8), 3=-30(LC 8)
Max Grav 5=171(LC 1), 3=44(LC 1), 4=31(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875241
400215	J4	Jack-Closed Supported Gable	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:43 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-YsbU_xe9sder3KmcL3USwx54bJ_uUdXd93dvEWzTVkQ



Scale = 1:7.4

Plate Offsets (X,Y)--		[3:0-1-5,0-0-0], [3:0-11-10,0-2-8], [4:0-1-3,0-0-6]							
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	L/defl	L/d
TCLL 25.0		Plate Grip DOL	1.15	TC 0.03		Vert(LL)	-0.00	1	n/r
TCDL 10.0		Lumber DOL	1.15	BC 0.02		Vert(CT)	0.00	1	n/r
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.00		Horz(CT)	-0.00	4	n/a
BCDL 10.0		Code IRC2018/TPI2014		Matrix-P					
						PLATES	GRIP		
						MT20	197/144		
						Weight: 4 lb		FT = 10%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-6-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 4=1-6-0, 2=1-6-0
Max Horz 2=26(LC 5)
Max Uplift 4=13(LC 8), 2=27(LC 4)
Max Grav 4=59(LC 1), 2=93(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875242
400215	J5	Jack-Closed	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:44 2020 Page 1

ID:vBSzku21ozNPT?RlZyTjMSyXqDi-039sCHfndxnihULovm?hS8dFNjK8D4nmOjMTnyzTVkP



Scale = 1:7.4

Plate Offsets (X,Y)--		[3:0-1-5,0-0-0], [3:0-11-10,0-2-8], [4:0-1-3,0-0-6]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 25.0	Plate Grip DOL 1.15	TC 0.02	in (loc) l/defl L/d
TCDL 10.0	Lumber DOL 1.15	BC 0.02	Vert(LL) -0.00 2 >999 360
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Vert(CT) -0.00 2 >999 240
BCDL 10.0	Code IRC2018/TPI2014	Matrix-P	Horz(CT) -0.00 4 n/a n/a
			Wind(LL) 0.00 2 **** 240
			PLATES GRIP
			MT20 197/144
			Weight: 4 lb FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-6-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8
Max Horz 2=26(LC 5)
Max Uplift 4=-13(LC 8), 2=-29(LC 4)
Max Grav 4=57(LC 1), 2=94(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	
400215	LAY1	GABLE	1	1		I40875243
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:45 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-UfjEPdgPOEvZJew_SUWw?MAQ_6fGyXhwdN60JOzTVkO

2-11-0
2-11-0

5-9-15
2-11-0

Scale = 1:22.8




Plate Offsets (X,Y)-- [3:Edge,0-3-0], [4:0-2-1,0-1-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.03	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-P							Weight: 19 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-9-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 5-9-15.
(lb) - Max Horz 1=-78(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) except 7=-103(LC 8), 6=-102(LC 9)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7, 6

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 103 lb uplift at joint 7 and 102 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875244
400215	R1	FLAT GIRDER	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:46 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-yRHcdzg19Y1QwoVB0B29XzjT4WzJhrq3r1rarrzTVkN



Scale = 1:21.9

Plate Offsets (X,Y)--		[4:Edge,0-2-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.46
TCDL 10.0	Lumber DOL	1.15	BC 0.16
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.61
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.06 5 >999 360
			Vert(CT) -0.11 5 >999 240
			Horz(CT) 0.00 4 n/a n/a
			Wind(LL) 0.04 5 >999 240
			PLATES
			MT20
			GRIP
			197/144
			Weight: 150 lb FT = 10%

LUMBER-

TOP CHORD 2x6 SP DSS
BOT CHORD 2x6 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD 2-0-0 oc purlins (6-0-0 max.): 1-3, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 6=Mechanical, 4=0-2-0 (req. 0-2-6)
Max Horz 6=-77(LC 4)
Max Uplift 6=-372(LC 4), 4=-329(LC 5)
Max Grav 6=3373(LC 1), 4=3005(LC 1)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-6=-3245/393, 1-2=-4776/522, 2-3=-4776/522, 3-4=-2876/350
WEBS 1-5=-553/4925, 2-5=-3699/508, 3-5=-555/4937

NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- WARNING: Required bearing size at joint(s) 4 greater than input bearing size.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 372 lb uplift at joint 6 and 329 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 879 lb down and 123 lb up at 1-0-0, 873 lb down and 125 lb up at 3-0-0, 873 lb down and 125 lb up at 5-0-0, 873 lb down and 125 lb up at 7-0-0, and 873 lb down and 125 lb up at 9-0-0, and 873 lb down and 125 lb up at 11-0-0 on top chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard



April 6,2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875244
400215	R1	FLAT GIRDER	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:46 2020 Page 2
ID:vBszku21ozNPT?RizYtJMSyXqDi-yRHcdzg19Y1QwoVB0B29XzjT4WzJhrq3r1rarrzTVkN

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-70, 4-6=-20
Concentrated Loads (lb)
Vert: 7=-879 8=-873 9=-873 10=-873 11=-873 12=-873

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875245
400215	V1	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:46 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-yRHcdzg19Y1QwoVB0B29XzjUOWyBh_H3r1rarrzTVkN



Scale = 1:20.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.44	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.23	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 15 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-4-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=5-3-12, 3=5-3-12
Max Horz 1=126(LC 5)
Max Uplift 1=-18(LC 8), 3=-62(LC 8)
Max Grav 1=214(LC 1), 3=230(LC 15)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 1 and 62 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875246
400215	V2	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:50 2020 Page 1

ID: vBsZku21ozNPT?RlZyYtJMSyXqDi-rDX7TKkYCNXsPPpyF166iPtDD7MAAdnGfmfpn_czTVk



Scale = 1:15.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.19	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 11 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=3-9-12, 3=3-9-12
Max Horz 1=86(LC 7)
Max Uplift 1=-12(LC 8), 3=-42(LC 8)
Max Grav 1=147(LC 1), 3=157(LC 15)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 12 lb uplift at joint 1 and 42 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875247
400215	V3	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:50 2020 Page 1

ID:vBszku21ozNPT?RlzytJM5yXqDi-rDX7TKkYCnXsPPpyF166iPtGS7NMdnGfmfn_czTVk



Scale = 1:10.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 6 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-4-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=2-3-12, 3=2-3-12
Max Horz 1=47(LC 5)
Max Uplift 1=-7(LC 8), 3=-23(LC 8)
Max Grav 1=79(LC 1), 3=85(LC 15)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 1 and 23 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875248
400215	V4	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:51 2020 Page 1
ID:vBszku21ozNPT?RizYtJMSyXqDi-JP4VggkAz4fj1ZN8pkdLEdQN2Xg5MDoo?JZLW2zTVkl



Scale = 1:39.2

Plate Offsets (X,Y)--		[1:0-0-13,0-1-4], [8:0-3-8,Edge], [8:0-0-0,0-1-4]									
LOADING	(psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC 0.32	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB 0.11	Horz(CT)	0.02	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 41 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
2-6: 2x3 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0"-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6'-0"-0 oc bracing.

REACTIONS.


All bearings 13-5-4.
(lb) - Max Horz 8=-171(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 4, 7 except 8=-145(LC 9), 5=-191(LC 9)
Max Grav All reactions 250 lb or less at joint(s) 8, 4, 6 except 7=376(LC 18), 5=616(LC 16)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 2-7=-292/42
WEBS 3-5=-390/243

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6"-0 tall by 2'-0"-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 7 except (jt=lb) 8=145, 5=191.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	
400215	V5	Valley	1	1		I40875249
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:52 2020 Page 1
ID: vBszku21ozNPT?RizYtJMSyXqDi-nbett0lokOnaejyKNS8anqzQx0C5hnyEzlu3UzTVkH



Scale = 1:32.9

Plate Offsets (X,Y)--		[1:0-0-13,0-1-4], [8:0-3-8,Edge], [8:0-0-0,0-1-4]					
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc) l/defl L/d
TCLL 25.0		Plate Grip DOL	1.15	TC 0.21		Vert(LL)	n/a - n/a 999
TCDL 10.0		Lumber DOL	1.15	BC 0.13		Vert(CT)	n/a - n/a 999
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.06		Horz(CT)	0.02 4 n/a n/a
BCDL 10.0		Code IRC2018/TPI2014		Matrix-S			
						PLATES	GRIP
						MT20	197/144
						Weight: 35 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
2-6: 2x3 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


All bearings 11-11-4.
(lb) - Max Horz 8=-131(LC 4)
Max Uplift All uplift 100 lb or less at joint(s) 4, 7 except 8=-106(LC 9), 5=-156(LC 9)
Max Grav All reactions 250 lb or less at joint(s) 8, 4, 6 except 7=313(LC 15), 5=413(LC 16)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 2-7=-262/23
WEBS 3-5=-317/201

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 7 except (jt=lb) 8=106, 5=156.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875250
400215	V6	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:53 2020 Page 1
ID:vBsZku21ozNPT?RizYtJMSyXqDi-FoCG5MmQVivQGtXXw9gpK2VkhLMSp8F5Sd2RbxzTVkG



Scale = 1:27.7

Plate Offsets (X,Y)-- [1:0-0-13,0-1-4], [8:0-3-8,Edge], [8:0-0-0,0-1-4]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.13	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.01	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 30 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
2-6: 2x3 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 10-5-4.
(lb) - Max Horz 8=-108(LC 4)
Max Uplift All uplift 100 lb or less at joint(s) 8, 4 except 5=-136(LC 9)
Max Grav All reactions 250 lb or less at joint(s) 8, 4, 6 except 7=256(LC 1), 5=351(LC 16)


FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 3-5=-277/178

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 4 except (jt=lb) 5=136.
- Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875251
400215	V7	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:54 2020 Page 1
ID: vBszku21ozNPT?RlZyTjMSyXqDi-j_melin2G?1Hu16jUsB2sF2u0li8YaFFhHn?7NzTVkF



Scale = 1:21.8



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.27	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 25 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.


(size) 1=9-9-0, 3=9-9-0, 4=9-9-0
Max Horz 1=-77(LC 4)
Max Uplift 1=-39(LC 8), 3=-48(LC 9), 4=-15(LC 8)
Max Grav 1=205(LC 1), 3=205(LC 1), 4=387(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-4=-252/64

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3, 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875252
400215	V8	Valley	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:55 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-BAK0W2nh1J98VBhv2aiHPTb5a83pH21OwxXYfpzTVkE



Scale = 1:16.4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.15	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 17 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=6-9-0, 3=6-9-0, 4=6-9-0
Max Horz 1=-51(LC 4)
Max Uplift 1=-33(LC 8), 3=-39(LC 9)
Max Grav 1=148(LC 1), 3=148(LC 1), 4=230(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875253
400215	V9	Valley	1	1		

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:56 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-fMuOjOoJodH?7KG6cHDWxg7IDYPw0VIX9bG5CGzTVkD



Scale = 1:9.1

Plate Offsets (X,Y)--		[2:0-2:0,Edge]									
LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.03	Vert(LL)	n/a	in (loc)	l/defl	L/d	MT20
TCDL	10.0	Lumber DOL	1.15	BC	0.08	Vert(CT)	n/a	-	n/a	999	197/144
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a	
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P							Weight: 8 lb
											FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-9-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


REACTIONS.

(size) 1=3-9-0, 3=3-9-0
Max Horz 1=-25(LC 4)
Max Uplift 1=-15(LC 8), 3=-15(LC 9)
Max Grav 1=128(LC 1), 3=128(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875254
400215	V10	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:47 2020 Page 1

ID: vBsZku21ozNPT?RlZyUJMSyXqDi-Qer_qJhfvS9HYy4NauZP4nFj0wKWQRhD4hb7NHZTVkM



Scale = 1:21.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.19	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.05	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 20 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2
OTHERS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=7-2-8, 4=7-2-8, 5=7-2-8
Max Horz 1=136(LC 5)
Max Uplift 4=-26(LC 8), 5=-113(LC 8)
Max Grav 1=82(LC 16), 4=141(LC 1), 5=378(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-5=-294/164

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 4 and 113 lb uplift at joint 5.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875255
400215	V11	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:48 2020 Page 1
ID: vBsZku21ozNPT?RizYtJMSyXqDi-ugPN2filg9H8A6fZ8c4ed_osSKf?9umMJLKgwjzTVkL



Scale = 1:14.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.27	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.15	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 12 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=4-6-8, 3=4-6-8
Max Horz 1=80(LC 5)
Max Uplift 1=-22(LC 8), 3=-42(LC 8)
Max Grav 1=173(LC 1), 3=173(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 1 and 42 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875256
400215	V12	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:48 2020 Page 1

ID:vBszku21ozNPT?RizYtJMSyXqDi-uqPN2filg9H8A6fZ8c4ed_ov1KhP9umMJLKgwjzTVkL



Scale = 1:10.9

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.11	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 8 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-


TOP CHORD Structural wood sheathing directly applied or 3-3-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=3-2-8, 3=3-2-8
Max Horz 1=53(LC 5)
Max Uplift 1=-15(LC 8), 3=-28(LC 8)
Max Grav 1=113(LC 1), 3=113(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 15 lb uplift at joint 1 and 28 lb uplift at joint 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 28 H4	I40875257
400215	V13	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.240 s Mar 9 2020 MiTek Industries, Inc. Mon Apr 6 07:34:49 2020 Page 1

ID:vBsZku21ozNPT?RizYtJMSyXqDi-M0zIF?jwRTP?nGEIhJbt9CLzJkz8uK0VY?4ESAzTVkK



Scale = 1:17.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.52	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.28	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 15 lb	FT = 10%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x3 SPF No.2

BRACING-


TOP CHORD Structural wood sheathing directly applied or 5-11-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 1=5-10-8, 3=5-10-8
Max Horz 1=108(LC 5)
Max Uplift 1=30(LC 8), 3=57(LC 8)
Max Grav 1=233(LC 1), 3=233(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 30 lb uplift at joint 1 and 57 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 6, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{1}{16}$ " from outside edge of truss.

—
—
This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MiTek 2012 software or upon request.**

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



Mitek Engineering Reference Sheet: MII-7473 rev. 10/03/2015



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.