






FRONT EL.
STUCCO & STONE



LEFT EL.
1/8" = 1'-0"




RIGHT EL.
1/8" = 1'-0"



REAR EL.
1/8" = 1'-0"

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/13/2020



JOSEPH A. TOWNS P.E.
MO. LIC E 22017
PROFESSIONAL SEAL
APPLIES TO STRUCTURAL
ELEMENTS ONLY

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.


NICK ZVACEK HOMES
ANDERSON II
LOT 106 MONTECELLO
4712 NE SARATOGA CIRCLE
LEE SUMMIT MO

SCALE
1/4" = 1'-0"

DATE
7-10-20

PLAN NO.
3160

SHEET NO.
1 OF 6




COMBUSTION AIR CALCULATIONS

INPUT CAPACITY
FURNACE = 100,000 BTU/HR
H.W. HEATER = 50,000 BTU/HR
TOTAL = 150,000 BTU/HR

50 CUBIC VOLUME REQ. PER 1,000 BTU/HR
VOLUME IN UNFINISHED
718 X 9 = 6,462 CU. FT.

SINCE UNFINISHED AREA DOES NOT
PROVIDE SUFFICIENT VOLUME FOR NORMAL
INFILTRATION, INSTALL 2 METAL LOUVER
VENTS IN WALL BETWEEN FAMILY ROOM
AND FURNACE ROOM. ONE VENT SHALL BE @
MIN. WITHIN 12" OF THE TOP OF THE WALL,
AND ONE VENT SHALL COMMENCE WITHIN
12" OF THE BOTTOM OF THE WALL. EACH
VENT SHALL PROVIDE A MINIMUM FREE
AREA OR 150 SQUARE INCHES (1" PER 1,000
BTU/HR) SINCE METAL LOUVERS HAVE 75%
FREE AREA, MINIMUM LOUVER SIZE
REQUIRED = 150/75 = 200 SQ. IN.

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/13/2020



JOSEPH A. TOWNS P.E.
MO. LIC E 22017
PROFESSIONAL SEAL
APPLIES TO STRUCTURAL
ELEMENTS ONLY

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.

NICK ZVACEK HOMES
ANDERSON II
LOT 106 MONTECELLO
4712 NE SARATOGA CIRCLE
LEE SUMMIT MO


SCALE
1/4" = 1'-0"

DATE
7-10-20

PLAN NO.
3160

SHEET NO.
2 OF 6

FOUNDATION PLAN
648 SF FINISHED



RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/13/2020

JOSEPH A. TOWNS P.E.
MO. LIC E 22017
PROFESSIONAL SEAL
APPLIES TO STRUCTURAL
ELEMENTS ONLY

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.


NICK ZVACEK HOMES
ANDERSON II
LOT 106 MONTECELLO
4712 NE SARATOGA CIRCLE
LEE SUMMIT MO

SCALE
1/4" = 1'-0"




DATE
7-10-20

PLAN NO.
3160

SHEET NO.
3 OF 6



ROOF PLAN
1/8" = 1-0
ROOF PITCHES 7/12 U.N.O.



RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
08/13/2020

JOSEPH A. TOWNS P.E.
MO. LIC E 22017
PROFESSIONAL SEAL
APPLIES TO STRUCTURAL
ELEMENTS ONLY

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.

NICK ZVACEK HOMES
ANDERSON II
LOT 106 MONTECELLO
4712 NE SARATOGA CIRCLE
LEE SUMMIT MO

SCALE
1/4" = 1-0

DATE
7-10-20

PLAN NO.
3160

SHEET NO.
4 OF 6

DUCTWORK NEEDS TO HAVE AN R-8 VALUE



ALL POINT LOADS SHALL HAVE A MINIMUM OF 2 STUDS UNLESS NOTED OTHERWISE

USE LSTA24 RIDGE STRAPS
ON ALL VAULTS AT RIDGE
OR COLLAR TIES

TYP VAULT WITH STRAPS

The diagram shows a cross-section of a vaulted roof. A vertical ridge strap is positioned at the peak of the vault. Two arrows point from the text 'USE LSTA24 RIDGE STRAPS ON ALL VAULTS AT RIDGE OR COLLAR TIES' to the strap. Below the diagram, the text 'TYP VAULT WITH STRAPS' is written.

5 OF 6

JOSEPH A. TOWNS P.E.
MO. LIC E 22017
PROFESSIONAL SEAL
APPLIES TO STRUCTURAL
ELEMENTS ONLY

TABLE R602.10.3(1) BRACING REQUIREMENTS BASED ON WIND SPEED					
EXPOSURE CATEGORY B 35-FOOT MEAN ROOF HEIGHT 15-FOOT WALL HEIGHT 2 BRACED WALL LINES	Ultimate Design Wind Speed (mph)	Story Location	Braced Wall Line Spacing (feet)	Method LFB*	Method GB
≤ 115	10		10	3.5	3.5
			20	6.5	6.5
			30	9.5	9.5
			40	12.5	12.5
			50	15.0	15.0
			60	18.0	18.0
	20		10	7.0	7.0
			20	12.5	12.5
			30	18.0	18.0
			40	23.5	23.5
			50	29.0	29.0
			60	34.5	34.5
	30		10	NP	10.0
			20	NP	18.5
			30	NP	27.0
			40	NP	35.0
			50	NP	43.0
			60	NP	51.0
	40		10	NP	10.0
			20	NP	18.5
			30	NP	27.0
			40	NP	35.0
			50	NP	43.0
			60	NP	51.0




FIGURE R602.10.6.1
METHOD ABW—ALTERNATE BRACED WALL PANEL










FIGURE R602.10.6.2
METHOD PFH—PORTAL FRAME WITH HOLD-DOWNS

TABLE R602.10.4 BRACING METHODS					
METHODS, MATERIAL	MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA*		
			Fasteners	Spacing	
LFB Let-in bracing	1 x 4 wood or approved metal straps at 45° to 60° angles for maximum 16" stud spacing		Wood: 2-8d common nails or 3-8d (2 1/2" long x 0.113" dia.) nails Metal strap: per manufacturer	Wood: per stud and top and bottom plates Metal: per manufacturer	
DWB Diagonal wood boards	3/4" (1" nominal) for maximum 24" stud spacing		2-8d (2 1/2" long x 0.113" dia.) nails or 2 - 1 1/4" long staples	Per stud	
WSP Wood structural panel (See Section R604)	3/8"		Exterior sheathing per Table R602.3(3) Interior sheathing per Table R602.3(1) or R602.3(2)	6" edges 12" field Varies by fastener	
BY-WSP Wood structural panels with stone or masonry veneer (See Section R602.10.6.5)	3/8"	See Figure R602.10.6.5	8d common (2 1/2" x 0.131) nails	4" at panel edges 12" at intermediate supports 4" at braced wall panel end posts	
SFB Structural fiberboard sheathing	1/2" or 5/8" for maximum 16" stud spacing		1 1/2" long x 0.12" dia. (for 1/2" thick sheathing) 1 1/4" long x 0.12" dia. (for 5/8" thick sheathing) galvanized roofing nails	3" edges 6" field	
GB Gypsum board	1/2"		Nails or screws per Table R602.3(1) for exterior locations Nails or screws per Table R702.3.5 for interior locations	For all braced wall panel locations: 7" edges (including top and bottom plates) 7" field	
PBS Particleboard sheathing (See Section R605)	3/4" or 1/2" for maximum 16" stud spacing		For 3/4", 6d common (2" long x 0.113" dia.) nails For 1/2", 8d common (2 1/2" long x 0.131" dia.) nails	3" edges 6" field	
PCP Portland cement plaster	See Section R703.7 for maximum 16" stud spacing		1 1/2" long, 11 gage, 1/8" dia. head nails or 1" long, 16 gage staples	6" o.c. on all framing members	
HPS Hardboard panel siding	7/8" for maximum 16" stud spacing		0.092" dia., 0.225" dia. head nails with length to accommodate 1 1/2" penetration into studs	4" edges 8" field	
ABW Alternate braced wall	3/8"		See Section R602.10.6.1	See Section R602.10.6.1	

TABLE R602.10.5 MINIMUM LENGTH OF BRACED WALL PANELS					
METHOD (See Table R602.10.4)	MINIMUM LENGTH* (inches)				
	8 feet	10 feet	11 feet	12 feet	CONTRIBUTING LENGTH (inches)
DWB, WSP, SFB, PBS, FCP, HPS, BV-WSP	48	48	48	53	58
GB	48	48	48	53	58
LFB	55	62	69	NP	NP
ABW	SDC A, B and C, ultimate design wind speed < 140 mph	28	32	34	38
	SDC D ₁ , D ₂ and D ₃ , ultimate design wind speed < 140 mph	32	32	34	NP
CS-G	Adjacent clear opening height (inches)	24	27	30	33
CS-WSP, CS-SFB	≤ 64	24	27	30	33
	68	26	27	30	33
	72	27	27	30	33
	76	30	29	30	33
	80	32	30	30	33
	84	35	32	32	33
	88	38	35	33	36
	92	43	37	35	36
	96	48	41	38	36
	100	—	44	40	38
	104	—	49	43	40
	108	—	54	46	43
	112	—	—	50	45
	116	—	—	55	48
	120	—	—	60	52
	124	—	—	—	56
	128	—	—	—	61
	132	—	—	—	66
	136	—	—	—	62
	140	—	—	—	66
	144	—	—	—	72
METHOD (See Table R602.10.4)	Portal header height				
	8 feet	10 feet	11 feet	12 feet	
PFH	Supporting roof only	16	16	16	Note c
	Supporting one story and roof	24	24	24	Note c
PFH	—	24	27	30	Note d
CS-PF	SDC A, B and C	16	18	20	Note e
	SDC D ₁ , D ₂ and D ₃	16	18	20	Note e

For S₁: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s.
NP = Not Permitted.
a. Linear interpolation shall be permitted.
b. Use the actual length when it is greater than or equal to the minimum length.
c. Maximum header height for PFH is 10 feet in accordance with Figure R602.10.6.2, but wall height shall be permitted to be increased to 12 feet with pony wall.
d. Maximum header height for PFH is 10 feet in accordance with Figure R602.10.6.2, but wall height shall be permitted to be increased to 12 feet with pony wall.
e. Maximum header height for CS-PF is 10 feet in accordance with Figure R602.10.6.4, but wall height shall be permitted to be increased to 12 feet with pony wall.

TABLE R602.10.4—continued BRACING METHODS					
METHODS, MATERIAL		MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA*	
				Fasteners	Spacing
Intermittent Bracing Methods	PFH Portal frame with hold-downs	3/4"		See Section R602.10.6.2	See Section R602.10.6.2
	PFH Portal frame at garage	7/16"		See Section R602.10.6.3	See Section R602.10.6.3
Continuous Sheathing Methods	CS-WSP Continuously sheathed wood structural panel	3/4"		Exterior sheathing per Table R602.3(3) Interior sheathing per Table R602.3(1) or R602.3(2)	6" edges 12" field Varies by fastener
	CS-PF ^a Continuously sheathed wood structural panel adjacent to garage openings	7/8"		See Method CS-WSP	See Method CS-WSP
	CS-PF Continuously sheathed portal frame	7/16"		See Section R602.10.6.4	See Section R602.10.6.4
	CS-SFB ^b Continuously sheathed structural fiberboard	1/2" or 5/8" for maximum 16" stud spacing		1 1/2" long x 0.12" dia. (for 1/2" thick sheathing) 1 1/4" long x 0.12" dia. (for 5/8" thick sheathing) galvanized roofing nails	3" edges 6" field

For S₁: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 degree = 0.0175 rad, 1 pound per square foot = 47.88 N/m², 1 mile per hour = 0.447 m/s.
a. Additive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Categories C, D₁, D₂ and D₃.
b. Applies to garage next to garage door opening where supporting gable end wall or roof load only. Shall only be used on one wall of the garage. In Seismic Design Categories D₁, D₂ and D₃, roof covering dead load shall not exceed 3 psf.
c. Garage openings adjacent to a Method CS-G panel shall be provided with a header in accordance with Table R602.7(1). A full-height clear opening shall not be permitted adjacent to a Method CS-G panel.
d. Method CS-SFB does not apply in Seismic Design Categories D₁ and D₂.
e. Method applies to detached one- and two-family dwellings in Seismic Design Categories D₁ through D₃ only.




FIGURE R602.10.6.4
METHOD CS-PF—CONTINUOUSLY SHEATHED PORTAL FRAME PANEL CONSTRUCTION

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

08/13/2020

JOSEPH A. TOWNS P.E.
MO. LIC E 22017
PROFESSIONAL SEAL
APPLIES TO STRUCTURAL
ELEMENTS ONLY

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.

NICK ZVACEK HOMES
ANDERSON II
LOT 106 MONTICELLO
4712 NE SARATOGA CIRCLE
LEE SUMMIT MO

SCALE
1/4" = 1'-0"

DATE
7-10-20

PLAN NO.
3160

SHEET NO.

6 OF 6