

PLANS REVIEW CONDITIONS

Permit No: PRCOM20193321	Date: August 21, 2020
Project Title: ROSS DRESS FOR LESS	Applicant:
Location: 480 NW CHIPMAN RD, LEES SUMMIT, MO 64086	ATRONIC ALARMS INC 8220 MELROSE DR LENEXA, KS 66214
Type of Work:	
Occupancy Group: M	
Description: TENANT FINISH FOR CLOTHING	Primary: (913) 362-0000
SALES ROSS DRESS FOR LESS	
Construction Type: Type IIB (Unprotected)	
Map Page: 195B	

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Alarm Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

2. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)

Call (816)969-1300 to schedule testing.

Alarm Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

1. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)

Call (816)969-1300 to schedule testing.

2. 1. Provide outside horn/strobe to monitor water flow for Ross. Placement to be made on the Northwest corner of Homegoods facing the FDC. Provide signage above the horn/strobe stating 480. Horn/strobe to only activate with water flow.

2. Horn/strobes on the interior to terminate when silenced.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.