



RE: 400565  
Lot 21 HT

MiTek USA, Inc.  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2018/TPI2014

Design Program: MiTek 20/20 8.4

Wind Code: N/A

Wind Speed: 115 mph

Roof Load: 45.0 psf


Floor Load: N/A psf



This package includes 111 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I42655390	A1A	9/1/2020	27	I42655416	H1	9/1/2020
2	I42655391	A2A	9/1/2020	28	I42655417	H2	9/1/2020
3	I42655392	A3	9/1/2020	29	I42655418	H3	9/1/2020
4	I42655393	A4	9/1/2020	30	I42655419	H4	9/1/2020
5	I42655394	A5	9/1/2020	31	I42655420	H6	9/1/2020
6	I42655395	B1	9/1/2020	32	I42655421	H7	9/1/2020
7	I42655396	B2	9/1/2020	33	I42655422	H8	9/1/2020
8	I42655397	B3	9/1/2020	34	I42655423	H9	9/1/2020
9	I42655398	B4	9/1/2020	35	I42655424	J1	9/1/2020
10	I42655399	B5	9/1/2020	36	I42655425	J2	9/1/2020
11	I42655400	B6	9/1/2020	37	I42655426	J3	9/1/2020
12	I42655401	B7	9/1/2020	38	I42655427	J4	9/1/2020
13	I42655402	C1	9/1/2020	39	I42655428	J6	9/1/2020
14	I42655403	C2	9/1/2020	40	I42655429	J7	9/1/2020
15	I42655404	C3	9/1/2020	41	I42655430	J8	9/1/2020
16	I42655405	C4	9/1/2020	42	I42655431	J9	9/1/2020
17	I42655406	C5	9/1/2020	43	I42655432	J10	9/1/2020
18	I42655407	D1	9/1/2020	44	I42655433	J11	9/1/2020
19	I42655408	D2	9/1/2020	45	I42655434	J12	9/1/2020
20	I42655409	D3	9/1/2020	46	I42655435	J13	9/1/2020
21	I42655410	D4	9/1/2020	47	I42655436	J14	9/1/2020
22	I42655411	G1	9/1/2020	48	I42655437	J15	9/1/2020
23	I42655412	G2	9/1/2020	49	I42655438	J16	9/1/2020
24	I42655413	G3	9/1/2020	50	I42655439	J17	9/1/2020
25	I42655414	G4	9/1/2020	51	I42655440	J18	9/1/2020
26	I42655415	G5	9/1/2020	52	I42655441	J19	9/1/2020

The truss drawing(s) referenced above have been prepared by  
MiTek USA, Inc. under my direct supervision  
based on the parameters provided by Wheeler - Waverly.  
Truss Design Engineer's Name: Garcia, Juan  
My license renewal date for the state of Kansas is April 30, 2022.  
Kansas COA: E-943



**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



RE: 400565 - Lot 21 HT

MiTek USA, Inc.

16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**Site Information:**

Project Customer:      Project Name:

Lot/Block:

Subdivision:

Address:

City, County:

State:

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
53	I42655442	J20	9/1/2020	97	I42655486	LAY8	9/1/2020
54	I42655443	J21	9/1/2020	98	I42655487	LAY9	9/1/2020
55	I42655444	J22	9/1/2020	99	I42655488	M1	9/1/2020
56	I42655445	J23	9/1/2020	100	I42655489	M2	9/1/2020
57	I42655446	J24	9/1/2020	101	I42655490	M3	9/1/2020
58	I42655447	J25	9/1/2020	102	I42655491	V1	9/1/2020
59	I42655448	J26	9/1/2020	103	I42655492	V2	9/1/2020
60	I42655449	J27	9/1/2020	104	I42655493	V4	9/1/2020
61	I42655450	J28	9/1/2020	105	I42655494	V5	9/1/2020
62	I42655451	J29	9/1/2020	106	I42655495	V6	9/1/2020
63	I42655452	J30	9/1/2020	107	I42655496	V7	9/1/2020
64	I42655453	J31	9/1/2020	108	I42655497	V8	9/1/2020
65	I42655454	J32	9/1/2020	109	I42655498	V9	9/1/2020
66	I42655455	J33	9/1/2020	110	I42655499	V10	9/1/2020
67	I42655456	J34	9/1/2020	111	I42655500	V11	9/1/2020
68	I42655457	J35	9/1/2020				
69	I42655458	J36	9/1/2020				
70	I42655459	J37	9/1/2020				
71	I42655460	J38	9/1/2020				
72	I42655461	J39	9/1/2020				
73	I42655462	J40	9/1/2020				
74	I42655463	J41	9/1/2020				
75	I42655464	J42	9/1/2020				
76	I42655465	J43	9/1/2020				
77	I42655466	J44	9/1/2020				
78	I42655467	J45	9/1/2020				
79	I42655468	J46	9/1/2020				
80	I42655469	K1	9/1/2020				
81	I42655470	K2	9/1/2020				
82	I42655471	K3	9/1/2020				
83	I42655472	K4	9/1/2020				
84	I42655473	K5	9/1/2020				
85	I42655474	L1	9/1/2020				
86	I42655475	L2	9/1/2020				
87	I42655476	L3	9/1/2020				
88	I42655477	L4	9/1/2020				
89	I42655478	L5	9/1/2020				
90	I42655479	L6	9/1/2020				
91	I42655480	LAY1	9/1/2020				
92	I42655481	LAY2	9/1/2020				
93	I42655482	LAY3	9/1/2020				
94	I42655483	LAY4	9/1/2020				
95	I42655484	LAY5	9/1/2020				
96	I42655485	LAY6	9/1/2020				



RE: 400565  
Lot 21 HT

MiTek USA, Inc.  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2018/TPI2014

Design Program: MiTek 20/20 8.4

Wind Code: N/A

Wind Speed: 115 mph


Roof Load: 45.0 psf

Floor Load: N/A psf

This package includes 111 individual, dated Truss Design Drawings and 0 Additional Drawings.


No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I42655390	A1A	9/1/2020	27	I42655416	H1	9/1/2020
2	I42655391	A2A	9/1/2020	28	I42655417	H2	9/1/2020
3	I42655392	A3	9/1/2020	29	I42655418	H3	9/1/2020
4	I42655393	A4	9/1/2020	30	I42655419	H4	9/1/2020
5	I42655394	A5	9/1/2020	31	I42655420	H6	9/1/2020
6	I42655395	B1	9/1/2020	32	I42655421	H7	9/1/2020
7	I42655396	B2	9/1/2020	33	I42655422	H8	9/1/2020
8	I42655397	B3	9/1/2020	34	I42655423	H9	9/1/2020
9	I42655398	B4	9/1/2020	35	I42655424	J1	9/1/2020
10	I42655399	B5	9/1/2020	36	I42655425	J2	9/1/2020
11	I42655400	B6	9/1/2020	37	I42655426	J3	9/1/2020
12	I42655401	B7	9/1/2020	38	I42655427	J4	9/1/2020
13	I42655402	C1	9/1/2020	39	I42655428	J6	9/1/2020
14	I42655403	C2	9/1/2020	40	I42655429	J7	9/1/2020
15	I42655404	C3	9/1/2020	41	I42655430	J8	9/1/2020
16	I42655405	C4	9/1/2020	42	I42655431	J9	9/1/2020
17	I42655406	C5	9/1/2020	43	I42655432	J10	9/1/2020
18	I42655407	D1	9/1/2020	44	I42655433	J11	9/1/2020
19	I42655408	D2	9/1/2020	45	I42655434	J12	9/1/2020
20	I42655409	D3	9/1/2020	46	I42655435	J13	9/1/2020
21	I42655410	D4	9/1/2020	47	I42655436	J14	9/1/2020
22	I42655411	G1	9/1/2020	48	I42655437	J15	9/1/2020
23	I42655412	G2	9/1/2020	49	I42655438	J16	9/1/2020
24	I42655413	G3	9/1/2020	50	I42655439	J17	9/1/2020
25	I42655414	G4	9/1/2020	51	I42655440	J18	9/1/2020
26	I42655415	G5	9/1/2020	52	I42655441	J19	9/1/2020

The truss drawing(s) referenced above have been prepared by  
MiTek USA, Inc. under my direct supervision  
based on the parameters provided by Wheeler - Waverly.  
Truss Design Engineer's Name: Garcia, Juan  
My license renewal date for the state of Missouri is December 31, 2020.  
Missouri COA: 001193



**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

September 01, 2020



RE: 400565 - Lot 21 HT

MiTek USA, Inc.

16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**Site Information:**

Project Customer:      Project Name:

Lot/Block:

Subdivision:

Address:

City, County:

State:

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
53	I42655442	J20	9/1/2020	97	I42655486	LAY8	9/1/2020
54	I42655443	J21	9/1/2020	98	I42655487	LAY9	9/1/2020
55	I42655444	J22	9/1/2020	99	I42655488	M1	9/1/2020
56	I42655445	J23	9/1/2020	100	I42655489	M2	9/1/2020
57	I42655446	J24	9/1/2020	101	I42655490	M3	9/1/2020
58	I42655447	J25	9/1/2020	102	I42655491	V1	9/1/2020
59	I42655448	J26	9/1/2020	103	I42655492	V2	9/1/2020
60	I42655449	J27	9/1/2020	104	I42655493	V4	9/1/2020
61	I42655450	J28	9/1/2020	105	I42655494	V5	9/1/2020
62	I42655451	J29	9/1/2020	106	I42655495	V6	9/1/2020
63	I42655452	J30	9/1/2020	107	I42655496	V7	9/1/2020
64	I42655453	J31	9/1/2020	108	I42655497	V8	9/1/2020
65	I42655454	J32	9/1/2020	109	I42655498	V9	9/1/2020
66	I42655455	J33	9/1/2020	110	I42655499	V10	9/1/2020
67	I42655456	J34	9/1/2020	111	I42655500	V11	9/1/2020
68	I42655457	J35	9/1/2020				
69	I42655458	J36	9/1/2020				
70	I42655459	J37	9/1/2020				
71	I42655460	J38	9/1/2020				
72	I42655461	J39	9/1/2020				
73	I42655462	J40	9/1/2020				
74	I42655463	J41	9/1/2020				
75	I42655464	J42	9/1/2020				
76	I42655465	J43	9/1/2020				
77	I42655466	J44	9/1/2020				
78	I42655467	J45	9/1/2020				
79	I42655468	J46	9/1/2020				
80	I42655469	K1	9/1/2020				
81	I42655470	K2	9/1/2020				
82	I42655471	K3	9/1/2020				
83	I42655472	K4	9/1/2020				
84	I42655473	K5	9/1/2020				
85	I42655474	L1	9/1/2020				
86	I42655475	L2	9/1/2020				
87	I42655476	L3	9/1/2020				
88	I42655477	L4	9/1/2020				
89	I42655478	L5	9/1/2020				
90	I42655479	L6	9/1/2020				
91	I42655480	LAY1	9/1/2020				
92	I42655481	LAY2	9/1/2020				
93	I42655482	LAY3	9/1/2020				
94	I42655483	LAY4	9/1/2020				
95	I42655484	LAY5	9/1/2020				
96	I42655485	LAY6	9/1/2020				

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655390
400565	A1A	Hip Girder	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:24 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-yRq2q?1fFYVBf2mqu\_X9Fr1?jTu6yLjupUu8uoyi0m9





Plate Offsets (X,Y)--		[2:0-2-0,0-1-8], [3:0-3-8,0-2-3], [5:0-3-8,0-2-3], [6:0-2-0,0-1-8], [8:Edge,0-2-8], [9:0-2-8,0-1-8], [12:0-2-8,0-1-8]	
<b>LOADING</b> (psf)	<b>SPACING-</b>	<b>CSI.</b>	<b>DEFL.</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.53	in (loc) l/defl L/d
TCDL 10.0	Lumber DOL 1.15	BC 0.46	Vert(LL) -0.08 11 >999 360
BCLL 0.0 *	Rep Stress Incr NO	WB 0.43	Vert(CT) -0.14 11-12 >999 240
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Horz(CT) 0.02 8 n/a n/a
			Wind(LL) 0.07 11 >999 240
			<b>PLATES</b> MT20
			<b>GRIP</b> 197/144
			Weight: 59 lb FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-9-8 oc purlins, except end verticals, and 2-0-0 oc purlins (3-6-1 max.): 3-5.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

<b>REACTIONS.</b>	(size) 13=0-3-8, 8=0-3-8
	Max Horz 13=53(LC 7)
	Max Uplift 13=-230(LC 8), 8=-230(LC 9)
	Max Grav 13=1121(LC 1), 8=1121(LC 1)

<b>FORCES.</b>	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-1461/323, 3-4=-2153/510, 4-5=-2153/510, 5-6=-1460/324, 2-13=-1101/235, 6-8=-1100/236
BOT CHORD	11-12=-291/1279, 9-11=-262/1278
WEBS	3-11=-251/981, 4-11=-582/283, 5-11=-251/982, 2-12=-263/1255, 6-9=-264/1254

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 13=230, 8=230.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hangar(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 84 lb down and 72 lb up at 4-2-0, 84 lb down and 72 lb up at 6-2-0, 84 lb down and 72 lb up at 8-2-0, and 84 lb down and 72 lb up at 10-2-0, and 84 lb down and 72 lb up at 12-2-0 on top chord, and 157 lb down and 72 lb up at 3-0-12, 31 lb down at 4-2-0, 31 lb down at 6-2-0, 31 lb down at 8-2-0, 31 lb down at 10-2-0, and 31 lb down at 12-2-0, and 157 lb down and 72 lb up at 13-3-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

<b>LOAD CASE(S)</b> Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



September 1,2020

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655390
400565	A1A	Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber,      Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc.   Tue Sep 1 10:53:24 2020   Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-yRq2q?1fFYVBf2mqu\_X9Fr1?jTu6yLjupUu8uoyi0m9

**LOAD CASE(S)**   Standard

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-5=-70, 5-6=-70, 6-7=-70, 8-13=-20

Concentrated Loads (lb)

Vert: 10=-22(F) 12=-157(F) 11=-22(F) 4=-46(F) 9=-157(F) 14=-46(F) 15=-46(F) 16=-46(F) 17=-46(F) 18=-22(F) 19=-22(F) 20=-22(F)

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655391
400565	A2A	Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:25 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-RdOQ1L2H0sd1HCL1Ri2On2r4\_tBcto228diREyi0m8

Job Reference (optional)

-0-10-8	4-8-12	11-7-4	16-4-0	17-2-8
0-10-8	4-8-12	6-10-8	4-8-12	0-10-8

Scale = 1:29.9




Plate Offsets (X,Y)--		[2:0-1-1,0-2-0], [5:0-1-1,0-2-0], [7:Edge,0-1-8]
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0
TCLL 25.0	Plate Grip DOL	1.15
TCDL 10.0	Lumber DOL	1.15
BCLL 0.0 *	Rep Stress Incr	YES
BCDL 10.0	Code	IRC2018/TPI2014
	<b>CSI.</b>	
	TC	0.94
	BC	0.70
	WB	0.12
	Matrix-S	
	<b>DEFL.</b>	
	in (loc)	l/defl
	Vert(LL)	-0.15 8-10 >999 360
	Vert(CT)	-0.34 8-10 >566 240
	Horz(CT)	0.02 7 n/a n/a
	Wind(LL)	0.10 8-10 >999 240
	<b>PLATES</b>	<b>GRIP</b>
	MT20	197/144
	Weight: 54 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 2-11,5-7: 2x6 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-8 oc purlins, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 11=0-3-8, 7=0-3-8  
 Max Horz 11=66(LC 7)  
 Max Uplift 11=-83(LC 8), 7=-83(LC 9)  
 Max Grav 11=792(LC 1), 7=792(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-975/102, 3-4=-782/114, 4-5=-975/102, 2-11=-694/109, 5-7=-694/109  
 BOT CHORD 10-11=-84/784, 8-10=-86/781, 7-8=-48/784

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	142655392
400565	A3	Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:25 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-RdOQ1L2H0sd1HCL1Ri2On2r6qtCDhtW228diREyi0m8

Job Reference (optional)





Plate Offsets (X,Y)-- [4:0-1-6,0-2-11]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.83	Vert(LL)	-0.12 7-8 >999	360	MT20 197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.60	Vert(CT)	-0.22 7-8 >878	240	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.02 6 n/a	n/a	
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.06 7-8 >999	240	Weight: 53 lb FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 1-9: 2x6 SPF No.2, 4-6: 2x8 SP DSS

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-5-15 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-3.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 9=0-3-8, 6=0-3-8  
 Max Horz 9=-81(LC 4)  
 Max Uplift 9=-74(LC 8), 6=-100(LC 9)  
 Max Grav 9=706(LC 1), 6=795(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-880/82, 2-3=-691/123, 3-4=-897/84, 1-9=-596/116, 4-6=-707/148  
 BOT CHORD 8-9=-32/688, 7-8=-33/687, 6-7=0/693

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9 except (jt=lb) 6=100.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655393
400565	A4	Hip	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871


8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:26 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vpyoFg2vnAluvMwD?PZdKGOEtHa3QKTBGoNFzgyi0m7

3-4-5	8-0-4	8-2-12	12-10-11	16-3-8	17-2-0
3-4-5	4-7-15	0-2-8	4-7-15	3-4-13	0-10-8

4x9 =

Scale = 1:33.9



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCCL	25.0	Plate Grip DOL	1.15	TC	1.00	Vert(LL)	-0.10	MT20		197/144	
TCDL	10.0	Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.17				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.02				
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.07				
								Weight: 61 lb		FT = 10%	

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 1-11: 2x8 SP DSS, 6-8: 2x10 SP DSS

#### BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


(size) 11=0-3-8, 8=0-3-8  
 Max Horz 11=-94(LC 4)  
 Max Uplift 11=-85(LC 8), 8=-114(LC 9)  
 Max Grav 11=699(LC 1), 8=794(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-877/150, 2-3=-725/105, 3-4=-612/114, 4-5=-729/107, 5-6=-862/148,  
 1-11=-599/119, 6-8=-703/149  
 BOT CHORD 10-11=-130/681, 9-10=0/612, 8-9=-79/656

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11 except (jt=lb) 8=114.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. For additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655394
400565	A5	Common	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:27 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-N0WAS03XYTtIWVVPZ74ssTwPuhvv9nSLVS60V6yi0m6

Job Reference (optional)

3-7-8	8-1-8	12-7-8	16-3-8	17-2-0
3-7-8	4-6-0	4-6-0	3-8-0	0-10-8

5x7 =

Scale = 1:32.7




Plate Offsets (X,Y)-- [5:0-1-4,0-2-8], [7:0-3-2,0-1-8]									
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d		<b>PLATES GRIP</b>	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-0.11 9 >999	360	MT20 197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.52	Vert(CT)	-0.19 7-9 >999	240	
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.02 7 n/a	n/a	
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.07 9 >999	240	Weight: 56 lb FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
1-10: 2x6 SPF No.2, 5-7: 2x8 SP DSS

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 10=0-3-8, 7=0-3-8  
Max Horz 10=-94(LC 4)  
Max Uplift 10=-86(LC 8), 7=-113(LC 9)  
Max Grav 10=706(LC 1), 7=795(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-905/153, 2-3=-725/106, 3-4=-727/107, 4-5=-891/150, 1-10=-606/122,  
5-7=-700/150  
BOT CHORD 9-10=-133/709, 7-9=-78/687  
WEBS 3-9=0/309

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10 except (jt=lb) 7=113.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Wheeler Lumber, Waverly, KS 66871 8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:28 2020 Page 1

ID:M6\_qRERJ\_ax8BApGKEbrTSyOHsj-rC4YgM49Jn?c8f3b7qc5PhTkJ5Equ8NUk6sM1Zyi0m5


0-10-8 4-4-9 8-1-1 12-0-0  
0-10-8 4-4-9 3-8-7 3-10-15

Scale = 1:22.5




**REACTIONS.** (size) 9=0-3-8, 6=0-3-8  
 Max Horz 9=90(LC 5)  
 Max Uplift 9=-205(LC 8), 6=-225(LC 5)  
 Max Grav 9=967(LC 1), 6=941(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-9=-1037/300, 2-3=-4369/1066, 3-4=-3110/763, 4-5=-3110/763, 5-6=-688/202  
 BOT CHORD 8-9=-190/372, 7-8=-1011/3967, 6-7=-150/567  
 WEBS 2-8=-883/3688, 3-8=-410/1756, 3-7=-872/302, 4-7=-453/241, 5-7=-636/2587



Continued on page 2



September 1, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** - available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601.



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT
400565	B1	HALF HIP GIRDER	1	2	I42655395
					Job Reference (optional)

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-5=-70, 8-9=-20, 6-8=-20

Concentrated Loads (lb)

Vert: 8=-357(F) 7=-42 4=-100(F) 10=-100(F) 11=-100(F) 12=-42 13=-42

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655396
400565	B2	Half Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:29 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOhsj-JOexti5n457TmpeogY7Kyu?t1Ubvdaodylbva?yi0m4

Job Reference (optional)

-0-10-8	4-3-8	6-0-9	11-8-8
0-10-8	4-3-8	1-9-1	5-7-15




Plate Offsets (X,Y)-- [2:0-2-8,Edge], [9:0-2-0,0-0-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.11	6-7	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.24	6-7	>575	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.57	Horz(CT)	0.09	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.05	7	>999	240	Weight: 42 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-11-12 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 8=0-3-8, 10=Mechanical  
Max Horz 8=90(LC 5)  
Max Uplift 8=-9(LC 8), 10=-26(LC 5)  
Max Grav 8=590(LC 1), 10=487(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-8=-629/73, 2-3=-1835/80, 3-4=-1722/134, 6-9=0/300, 5-9=0/300  
BOT CHORD 6-7=-88/898  
WEBS 2-7=-9/1441, 4-7=-84/922, 4-6=-730/80, 5-10=-578/38

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655397
400565	B3	Monopitch	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:30 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-naCJ425QqOFKNzD\_EFeZU6Y4auxhM27nBPLT6Ryi0m3




Plate Offsets (X,Y)--		[2:0-2-8,Edge]									
<b>LOADING</b> (psf)		<b>SPACING-</b>	2-0-0	<b>CSI.</b>		<b>DEFL.</b>	in (loc)	L/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0		Plate Grip DOL	1.15	TC 0.38		Vert(LL)	-0.12 6-7	>999	360	MT20	197/144
TCDL 10.0		Lumber DOL	1.15	BC 0.45		Vert(CT)	-0.26 6-7	>530	240		
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.50		Horz(CT)	0.09 10	n/a	n/a		
BCDL 10.0		Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.07 7	>999	240	Weight: 44 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 8=0-3-8, 10=Mechanical  
Max Horz 8=108(LC 5)  
Max Uplift 8=-8(LC 8), 10=-25(LC 5)  
Max Grav 8=590(LC 1), 10=487(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-8=-626/84, 2-3=-1846/134, 3-4=-1786/202, 6-9=-7/369, 5-9=-7/369  
BOT CHORD 6-7=-61/534  
WEBS 2-7=-57/1457, 4-7=-159/1300, 4-6=-516/84, 5-10=-502/26

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:30 2020 Page 1

142655398

Job Reference (optional)

ID:M6 gRERi ax8BApGKEbrTSvOHsi-naCJ425QqOFKNzD EFeZU6Y4Aux2MzmnBPLT6Rvi0m3



**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-9=-608/89, 2-3=-1900/201, 3-4=-444/13, 6-10=-44/463, 5-10=-44/463
BOT CHORD	7-8=-251/1566, 6-7=-20/322
WEBS	2-8=-128/1536, 3-8=-44/578, 3-7=-1255/236, 4-7=0/335, 4-6=-530/54, 5-11=-492/38

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-9=608/89, 2-3=1900/201, 3-4=444/13, 6-10=44/463, 5-10=44/463
BOT CHORD	7-8=251/1566, 6-7=20/322
WEBS	2-8=128/1536, 3-8=44/578, 3-7=1255/236, 4-7=0/335, 4-6=530/54, 5-11=492/38

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCFL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9, 11.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655399
400565	B5	Monopitch	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:31 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-FnlhIO62biNB?7oAoy9o1J5BtlFC5RKwQ340euyi0m2



10x12 M18SHS =

Scale = 1:39.9

Plate Offsets (X,Y)-- [2:0-2-8,0-2-8], [4:Edge,0-1-14]									
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d		<b>PLATES</b>	<b>GRIP</b>
TCLL	25.0	Plate Grip DOL	1.15	TC	0.60	Vert(LL)	-0.14 7 >985 360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.29 6-7 >475 240	M18SHS	197/144
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.76	Horz(CT)	0.13 10 n/a n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.10 7 >999 240	Weight: 47 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-11-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
WEBS 1 Row at midpt 3-6

#### REACTIONS.

(size) 8=0-3-8, 10=Mechanical  
Max Horz 8=145(LC 8)  
Max Uplift 10=-65(LC 8)  
Max Grav 8=590(LC 1), 10=487(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-8=-596/83, 2-3=-2027/227, 6-9=-1/288, 5-9=-1/288  
BOT CHORD 6-7=-303/1684  
WEBS 2-7=-164/1697, 3-7=-42/638, 3-6=-1600/303, 5-10=-493/66

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655400
400565	B6	Monopitch	5	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:32 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-jzJ3Vv7gMOW2dHNNMgg1ZXdlBibKqtO4fqZAKyi0m1




Plate Offsets (X,Y)-- [2:0-2-8,0-2-8], [4:0-6-8,Edge]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.63	Vert(LL)	-0.14	6	>972	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.29	5-6	>471	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.77	Horz(CT)	0.13	9	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.10	6	>999	240	Weight: 47 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-7 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
WEBS 1 Row at midpt 3-5

#### REACTIONS.


(size) 7=0-3-8, 9=Mechanical  
Max Horz 7=151(LC 8)  
Max Uplift 9=71(LC 8)  
Max Grav 7=590(LC 1), 9=487(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-7=-595/83, 2-3=-2040/231, 5-8=-2/291, 4-8=-2/291  
BOT CHORD 5-6=-313/1697  
WEBS 2-6=-169/1715, 3-6=-46/642, 3-5=-1623/314, 4-9=-492/72

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655401
400565	B7	Monopitch	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:33 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-C9tRj48l7JevEQyZvNBG6kAWZ6tXZJ?DtNZ7jmyi0m0




Plate Offsets (X,Y)--		[2:0-3-15,Edge], [4:0-6-8,Edge]	
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.59
TCDL 10.0	Lumber DOL	1.15	BC 0.89
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.81
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S
			<b>DEFL.</b>
			in (loc) l/defl L/d
			Vert(LL) -0.16 7 >858 360
			Vert(CT) -0.28 7 >491 240
			Horz(CT) 0.18 10 n/a n/a
			Wind(LL) 0.11 7 >999 240
			<b>PLATES</b> <b>GRIP</b>
			MT20 197/144
			Weight: 46 lb FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2 \*Except\*  
3-7: 2x4 SPF 2100F 1.8E  
WEBS 2x3 SPF No.2 \*Except\*  
2-8: 2x6 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6'-0" oc bracing.

#### REACTIONS.


(size) 8=0-3-8, 10=Mechanical  
Max Horz 8=151(LC 8)  
Max Uplift 10=70(LC 8)  
Max Grav 8=594(LC 1), 10=480(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-590/0, 5-9=-20/338, 4-9=-20/338, 2-8=-552/38  
BOT CHORD 7-8=-84/422, 5-6=-166/1008  
WEBS 3-5=-979/176, 4-10=-484/71

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6" tall by 2'-0" wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655402
400565	C1	Common Supported Gable	1	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:34 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-gMRQwP9wudmmsaXIT5iVfyjpMVQ8lxIM61JgFDyioM?

0-10-8 10-0-0 20-0-0 20-10-8  
0-10-8 10-0-0 10-0-0 0-10-8

Scale = 1:34.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	13	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	-0.00	13	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	0.00	14	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R						Weight: 85 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

All bearings 20-0-0.  
(lb) - Max Horz 24=98(LC 7)  
Max Uplift All uplift 100 lb or less at joint(s) 24, 14, 20, 21, 22, 23, 18, 17, 16, 15  
Max Grav All reactions 250 lb or less at joint(s) 24, 14, 19, 20, 21, 22, 23, 18, 17, 16, 15

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 24, 14, 20, 21, 22, 23, 18, 17, 16, 15.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655403
400565	C2	Common	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:35 2020 Page 1

ID:M6\_qRERj\_ax8BapGKEbrTSyOHsj-8Y?C8I9YfxudUk6y1oEkB9FojvaS1MyWLh2Dnfyi0m\_

Job Reference (optional)

0-10-8 4-7-8 10-0-0 15-4-9 20-0-0 20-10-8  
0-10-8 4-7-8 5-4-9 5-4-9 4-7-8 0-10-8

5x7 =

Scale = 1:39.2




Plate Offsets (X,Y)--	[2:0-1-0,0-2-0], [6:0-1-0,0-2-0]
-----------------------	----------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.86	Vert(LL)	-0.17	9-10	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.73	Vert(CT)	-0.36	9-10	>647	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.21	Horz(CT)	0.03	8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.08	9	>999	240	Weight: 69 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-10,6-8: 2x8 SP DSS

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-1 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


(size) 10=0-3-8, 8=0-3-8  
Max Horz 10=102(LC 7)  
Max Uplift 10=-134(LC 8), 8=-134(LC 9)  
Max Grav 10=955(LC 1), 8=955(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1166/193, 3-4=-929/133, 4-5=-929/133, 5-6=-1166/193, 2-10=-851/182,  
6-8=-851/182  
BOT CHORD 9-10=-172/920, 8-9=-105/920  
WEBS 4-9=0/415

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (it=lb) 10=134, 8=134.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655404
400565	C3	Common	4	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:35 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-8Y?C8l9YfxudUk6y1oEkB9Fo7vzbz1MuWlh2Dnfyi0m\_

Job Reference (optional)

4-4-6	9-8-14	15-1-7	19-8-14	20-7-6
4-4-6	5-4-9	5-4-9	4-7-7	0-10-8

5x7 =

Scale = 1:38.6




Plate Offsets (X,Y)--	[5:0-1-0,0-2-0]
-----------------------	-----------------

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	2-0-0	TC 0.84	Vert(LL)	-0.18	7-8	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.70	Vert(CT)	-0.40	7-8	>572	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.21	Horz(CT)	0.03	7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.11	7-8	>999	240	Weight: 68 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
1-9,5-7: 2x8 SP DSS

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-1 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


(size) 9=Mechanical, 7=0-3-8  
Max Horz 9=-110(LC 4)  
Max Uplift 9=-104(LC 8), 7=-133(LC 9)  
Max Grav 9=859(LC 1), 7=946(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-1108/183, 2-3=-902/131, 3-4=-907/130, 4-5=-1147/192, 1-9=-747/148, 5-7=-838/181  
BOT CHORD 8-9=-160/866, 7-8=-104/905  
WEBS 3-8=0/393

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=104, 7=133.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655405
400565	C4	Monopitch	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:36 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-ckZaL5AAQE0U5uh8bWlzkNo8VJ4fmqLfaLonl5yi0lz



Scale = 1:19.4

Plate Offsets (X,Y)--		[2:0-6-8,Edge]									
<b>LOADING</b> (psf)		<b>SPACING-</b>	2-0-0	<b>CSI.</b>		<b>DEFL.</b>	in (loc)	L/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0		Plate Grip DOL	1.15	TC 0.16		Vert(LL)	-0.01 3-4	>999	360	MT20	197/144
TCDL 10.0		Lumber DOL	1.15	BC 0.09		Vert(CT)	-0.01 3-4	>999	240		
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.13		Horz(CT)	-0.00 6	n/a	n/a		
BCDL 10.0		Code IRC2018/TPI2014		Matrix-R		Wind(LL)	0.00 3-4	>999	240	Weight: 15 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-3-14 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


#### REACTIONS.

(size) 4=Mechanical, 6=Mechanical  
Max Horz 4=81(LC 5)  
Max Uplift 4=-3(LC 8), 6=-61(LC 8)  
Max Grav 4=186(LC 1), 6=158(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 6.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655406
400565	C5	Monopitch	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:37 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-4x7yYRBpBY8Kj2GK8DGCgaLLjRyVJFpo?XKrXyi0ly



Scale = 1:14.4

Plate Offsets (X,Y)--		[2:0-6-8,Edge]							
<b>LOADING</b> (psf)		<b>SPACING-</b>	2-0-0	<b>CSI.</b>		<b>DEFL.</b>	in (loc)	L/defl	L/d
TCLL 25.0		Plate Grip DOL	1.15	TC 0.06		Vert(LL)	-0.00 4	>999	360
TCDL 10.0		Lumber DOL	1.15	BC 0.03		Vert(CT)	-0.00 3	>999	240
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.03		Horz(CT)	-0.00 6	n/a	n/a
BCDL 10.0		Code IRC2018/TPI2014		Matrix-R		Wind(LL)	-0.00 4	>999	240
						<b>PLATES</b>		<b>GRIP</b>	
						MT20		197/144	
						Weight: 9 lb		FT = 10%	

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-7-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 4=0-3-8, 6=Mechanical  
Max Horz 4=56(LC 5)  
Max Uplift 4=-2(LC 8), 6=-33(LC 8)  
Max Grav 4=107(LC 1), 6=81(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655407
400565	D1	Hip Girder	1	2	Job Reference (optional)	

Wheeler Lumber,
Waverly, KS 66871

8.420 s Aug 25 2020
MiTek Industries, Inc.
Tue Sep 1 10:53:41 2020
Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-ziMTOpEJFmemCfZ5N3L8RQVstKbcQ0QOjdVY\_Yji0lu

-0-10-8
3-6-0
5-0-0
9-2-0
13-4-0
18-10-4
26-9-0
34-6-0
39-6-0
40-4-8

0-10-8
3-6-0
1-6-0
4-2-0
4-2-0
5-6-4
7-10-12
7-9-0
5-0-0
0-10-8

Scale = 1:74.0




Plate Offsets (X,Y)-- [7:0-3-8,0-1-8]																	
LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP							
TCLL 25.0		Plate Grip DOL 1.15		TC 0.76		Vert(LL) -0.10 20-21 >999 360		MT20		197/144							
TCDL 10.0		Lumber DOL 1.15		BC 0.88		Vert(CT) -0.17 20-21 >999 240		M18SHS		197/144							
BCLL 0.0 *		Rep Stress Incr NO		WB 0.46		Horz(CT) 0.08 17 n/a n/a											
BCDL 10.0		Code IRC2018/TPI2014		Matrix-S		Wind(LL) 0.09 20-21 >999 240		Weight: 302 lb		FT = 10%							

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-10.
BOT CHORD	2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SPF No.2 *Except* 11-13: 2x6 SPF No.2		

**REACTIONS.** (size) 24=0-3-8, 17=0-3-8, 13=0-3-8  
Max Horz 24=21(LC 7)  
Max Uplift 24=245(LC 4), 17=938(LC 5), 13=241(LC 9)  
Max Grav 24=929(LC 21), 17=3309(LC 1), 13=1061(LC 22)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1169/335, 3-4=-2075/651, 4-5=-1751/616, 5-6=-1749/614, 6-7=-724/2514, 7-9=-1150/265, 9-10=-1153/267, 10-11=-1645/363, 2-24=-858/253, 11-13=-1034/254  
BOT CHORD 23-24=-249/939, 21-22=-484/1851, 20-21=-542/1911, 15-17=-2514/789, 14-15=-298/1457  
WEBS 4-21=-180/518, 5-20=-330/114, 6-20=-588/1867, 6-17=-2734/851, 7-17=-1861/682, 7-15=-1037/3779, 9-15=-819/441, 10-15=-374/112, 10-14=0/321, 11-14=-282/1323

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.  
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 24=245, 17=938, 13=241.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1,2020

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT
400565	D1	Hip Girder	1	2	I42655407
					Job Reference (optional)

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:41 2020 Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-ziMTOpEJFmemCfZ5N3L8RQVstKbcQ0QOjdVY\_Yji0lu

NOTES-

12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 62 lb down and 19 lb up at 5-9-0, 63 lb down and 19 lb up at 7-9-0, 63 lb down and 19 lb up at 9-9-0, 63 lb down and 19 lb up at 11-9-0, 89 lb down and 82 lb up at 13-9-0, 89 lb down and 82 lb up at 15-9-0, 89 lb down and 82 lb up at 17-9-0, 89 lb down and 82 lb up at 19-9-0, 89 lb down and 82 lb up at 21-9-0, 89 lb down and 82 lb up at 23-9-0, 89 lb down and 82 lb up at 25-9-0, 89 lb down and 82 lb up at 27-9-0, 89 lb down and 82 lb up at 29-9-0, and 89 lb down and 82 lb up at 31-9-0, and 87 lb down and 82 lb up at 33-9-0 on top chord, and 222 lb down and 103 lb up at 5-0-0, 80 lb down and 75 lb up at 5-9-0, 80 lb down and 75 lb up at 7-9-0, 80 lb down and 75 lb up at 9-9-0, 80 lb down and 75 lb up at 11-9-0, 34 lb down at 13-5-12, 34 lb down at 15-9-0, 34 lb down at 17-9-0, 34 lb down at 19-9-0, 34 lb down at 21-9-0, 34 lb down at 23-9-0, 34 lb down at 25-9-0, 34 lb down at 27-9-0, 34 lb down at 29-9-0, 34 lb down at 31-9-0, and 34 lb down at 33-9-0, and 222 lb down and 101 lb up at 34-6-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-4=-70, 4-10=-70, 10-11=-70, 11-12=-70, 23-24=-20, 19-22=-20, 13-18=-20

Concentrated Loads (lb)

Vert: 19=-23(F) 6=-51(F) 16=-23(F) 21=-222(F) 14=-222(F) 25=-9(F) 26=-9(F) 27=-9(F) 28=-9(F) 29=-51(F) 30=-51(F) 31=-51(F) 32=-51(F) 33=-51(F) 34=-51(F) 35=-51(F) 36=-51(F) 37=-51(F) 38=-51(F) 39=-80(F) 40=-80(F) 41=-80(F) 42=-80(F) 43=-23(F) 44=-23(F) 45=-23(F) 46=-23(F) 47=-23(F) 48=-23(F) 49=-23(F) 50=-23(F) 51=-23(F)

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655408
400565	D2	Hip	1	1		


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:42 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-Ruwr9F04mdpp8lXmsNze229k0l9NkYyHF5Wly0lt

0-10-8	3-6-0	7-4-13	13-4-0	18-10-4	19-7-1	25-6-6	32-1-3	39-6-0	40-4-8
0-10-8	3-6-0	3-10-13	5-11-3	5-6-4	0-8-13	5-11-5	6-6-14	7-4-13	0-10-8

Scale = 1:74.0



	3-6-0	7-4-13	13-4-0	18-10-4	25-6-6	32-1-3	39-6-0
	3-6-0	3-10-13	5-11-3	5-6-4	6-8-2	6-6-14	7-4-13

Plate Offsets (X,Y)-- [12:Edge,0-7-11], [22:0-3-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.66	Vert(LL)	-0.09 19-20	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.53	Vert(CT)	-0.16 18-19	>999	240	M18SHS	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.84	Horz(CT)	0.07 16	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.06 19-20	>999	240	Weight: 142 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2 \*Except\*  
 3-21: 2x6 SPF No.2, 5-17: 2x3 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 2-22: 2x6 SPF No.2, 10-12: 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-7 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-9.  
 BOT CHORD Rigid ceiling directly applied or 5-2-3 oc bracing.

#### REACTIONS.


(size) 22=0-3-8, 16=0-3-8, 12=0-3-8  
 Max Horz 22=-36(LC 13)  
 Max Uplift 22=-113(LC 8), 16=-350(LC 5), 12=-134(LC 9)  
 Max Grav 22=671(LC 21), 16=2230(LC 1), 12=798(LC 22)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-726/118, 3-4=-900/136, 6-8=-486/155, 8-9=-489/157, 9-10=-1029/149,  
 2-22=-590/127, 10-12=-731/173  
 BOT CHORD 21-22=-102/573, 19-20=-250/1387, 18-19=-44/779, 17-18=-774/154, 5-18=-414/173,  
 16-17=-1196/186, 15-16=-1196/186, 13-15=-72/851, 12-13=-191/526  
 WEBS 3-19=-615/213, 4-19=0/337, 4-18=-772/61, 6-17=-230/1472, 6-16=-2082/426,  
 6-15=-277/1786, 8-15=-507/207, 9-15=-477/20, 9-13=0/269, 10-13=0/365

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 22=113, 16=350, 12=134.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017




Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:43 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-v5UDpUGZnOuURjUVUNcWrbDW8LlurEhBx\_f2BYi0ls

-0-10-8	3-6-0	9-9-10	13-4-0	18-9-7	24-3-9	29-8-6	35-5-6	39-6-0	40-4-8
0-10-8	3-6-0	6-3-10	3-6-6	5-5-7	5-6-1	5-4-13	5-8-15	4-0-10	0-10-8

Scale = 1:71.6



**REACTIONS.** (size) 23=0-3-8, 17=0-3-8 (req. 0-3-9), 13=0-3-8  
 Max Horz 23=52(LC 12)  
 Max Uplift 23=-123(LC 8), 17=-318(LC 5), 13=-155(LC 9)  
 Max Grav 23=664(LC 21), 17=2269(LC 1), 13=803(LC 22)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**TOP CHORD** 2-3=-695/128, 3-4=-576/99, 9-10=-750/153, 10-11=-1027/257, 2-23=-587/134,  
 11-13=-703/205

**BOT CHORD** 22-23=-127/543, 20-21=-368/1537, 19-20=-15/439, 18-19=-794/135, 5-19=-323/132,  
 17-18=-1044/159, 16-17=-1044/159, 14-16=-14/638, 13-14=-180/854

**WEBS** 3-20=-1102/358, 4-20=0/349, 4-19=-664/83, 6-18=-163/1268, 6-17=-2121/388,  
 6-16=-197/1401, 8-16=-399/164, 9-16=-663/28, 9-14=0/360, 10-14=-255/178

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCdL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) WARNING: Required bearing size at joint(s) 17 greater than input bearing size.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 23=123, 17=318, 13=155.
  - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020




Plate Offsets (X,Y)--		[6:0-3-0,0-4-4]									
<b>LOADING</b>	(psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>		<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL	25.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.03 6-7	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.05 6-7	>999	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.33	Horz(CT)	-0.00 9	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.02 6-7	>999	240	Weight: 133 lb	FT = 10%

**LUMBER-**

TOP CHORD	2x4 SPF No.2
BOT CHORD	2x6 SP 2400F 2.0E
WEBS	2x4 SPF No.2
OTHERS	2x4 SPF No.2

<b>BRACING-</b>	
<b>TOP CHORD</b>	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
<b>BOT CHORD</b>	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 7=0-3-8, 9=Mechanical  
Max Horz 7=166(LC 5)  
Max Uplift 7=-295(LC 8), 9=-366(LC 8)  
Max Grav 7=2303(LC 1), 9=2175(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=2265/268, 3-4=270/15, 5-8=307/2101, 4-8=307/2101, 2-7=1671/237  
 BOT CHORD 5-6=346/2027  
 WEBS 3-6=212/1850, 3-5=2334/416, 2-6=157/1905, 4-9=2182/367

**NOTES-**

- 1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCdL=6.0psf; BCdL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=295, 9=366.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 839 lb down and 124 lb up at 1-11-4, 839 lb down and 124 lb up at 3-11-4, 839 lb down and 124 lb up at 5-11-4, and 839 lb down and 124 lb up at 7-11-4, and 175 lb down and 14 lb up at 9-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard



September 1, 2020

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT
400565	D4	Monopitch Girder	1	2	I42655410
					Job Reference (optional)

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:44 2020 Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-NH2b0qGCXh0L37lg3Bur337SHXmYdPKrPbkCbdi0lr

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-4=-70, 5-7=-20

Concentrated Loads (lb)

Vert: 5=-175(F) 10=-839(F) 11=-839(F) 12=-839(F) 13=-839(F)

Wheeler Lumber, Waverly, KS 66871 8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:45 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-rTc\_EAHql?8CgGttcvP4bGgY1x1FMpd\_eFTI74yi0lq  
0-10-8 2-11-6 8-8-0  
0-10-8 2-11-6 5-8-10  
Scale = 1:18.1




Plate Offsets (X,Y)-- [2:0-0-10,0-1-8], [3:0-3-9,Edge]												
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d					<b>PLATES</b>	<b>GRIP</b>
TCLL	25.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.06	5-6	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.64	Vert(CT)	-0.13	5-6	>738	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.51	Horz(CT)	0.01	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.04	5-6	>999	240	Weight: 30 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-7: 2x8 SP DSS

<b>BRACING-</b>	
<b>TOP CHORD</b>	Structural wood sheathing directly applied or 5-1-1 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
<b>BOT CHORD</b>	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=Mechanical, 7=0-3-8  
Max Horz 7=81(LC 7)  
Max Uplift 5=123(LC 5), 7=149(LC 4)  
Max Grav 5=533(LC 1), 7=657(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=-783/156, 4-5=-260/114, 2-7=-537/119
BOT CHORD	6-7=-176/662, 5-6=-180/653
WEBS	3-6=0/281, 3-5=-579/149

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91 mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=123, 7=149.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 77 lb down and 67 lb up at 2-11-6, and 82 lb down and 67 lb up at 5-0-5, and 82 lb down and 67 lb up at 7-0-5 on top chord, and 175 lb down and 64 lb up at 2-11-6, and 32 lb down at 5-0-5, and 32 lb down at 7-0-5 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



September 1, 2020

Continued on page 2



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655411
400565	G1	Half Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:46 2020 Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Jf9MRWIS3JG3IQS3AcwJ8UDjnLNU5Gt8tvDJfWyi0lp

**LOAD CASE(S)** Standard

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-4=-70, 5-7=-20

Concentrated Loads (lb)

Vert: 3=-48(F) 6=-175(F) 8=-48(F) 9=-48(F) 10=-23(F) 11=-23(F)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655412
400565	G2	Half Hip	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871


8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:46 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Jf9MRWIS3JG3IQS3AcwJ8UDmQLT15Le8tvDJfWyi0lp

-0-10-8	4-6-10	8-8-0
0-10-8	4-6-10	4-1-6

5x7 =

Scale = 1:19.5



		4-6-10	8-8-0		
		4-6-10	4-1-6		
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	<b>PLATES</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.51	in (loc) l/defl L/d	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.22	Vert(LL) -0.02 6 >999 360	GRIP 197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.21	Vert(CT) -0.04 5-6 >999 240	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Horz(CT) 0.00 5 n/a n/a	
				Wind(LL) 0.01 6 >999 240	
				Weight: 29 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=Mechanical, 7=0-3-8  
Max Horz 7=109(LC 5)  
Max Uplift 5=69(LC 5), 7=71(LC 8)  
Max Grav 5=377(LC 1), 7=453(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-435/55, 2-7=-390/99  
BOT CHORD 6-7=-81/339, 5-6=-83/337  
WEBS 3-5=-372/70

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655413
400565	G3	Half Hip	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:47 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOhsj-nsjkfsJ4qcOwwa0FkJRYghlx2lp\_qpaH5ZysByyi0lo



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.52	Vert(LL)	-0.03	6-7	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.24	Vert(CT)	-0.07	6-7	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.16	Horz(CT)	0.00	5	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	-0.01	6	>999	240	
								Weight: 29 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=Mechanical, 7=0-3-8  
Max Horz 7=138(LC 7)  
Max Uplift 5=65(LC 5), 7=77(LC 8)  
Max Grav 5=377(LC 1), 7=453(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-365/47, 2-7=-399/119  
BOT CHORD 6-7=-68/260, 5-6=-69/256  
WEBS 3-5=-418/87

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655414
400565	G4	Half Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:48 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-F2H6sCJibwXnXkbRI1znDvl2795AZEbQKDiQkPyi0ln

Job Reference (optional)




Plate Offsets (X,Y)-- [3:0-4-8,0-1-15]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.76	Vert(LL)	-0.08	6-7	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.43	Vert(CT)	-0.18	6-7	>578	240	MT18H	197/144
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.27	Horz(CT)	0.00	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.03	6-7	>999	240	Weight: 31 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-8-3 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=Mechanical, 7=0-3-8  
Max Horz 7=167(LC 5)  
Max Uplift 5=73(LC 8), 7=77(LC 8)  
Max Grav 5=377(LC 1), 7=453(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-285/32, 4-5=-546/61, 2-7=-402/131  
WEBS 3-6=-481/245, 4-6=-189/785

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to bearing plate connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655415
400565	G5	Monopitch	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:48 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-F2H6sCJibwXnXkbRl1znDvl7K95uZFXQKDiQkPyi0In



Scale = 1:28.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.42	Vert(LL)	-0.17	5-6	>603	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.39	Vert(CT)	-0.32	5-6	>313	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.25	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	-0.01	5-6	>999	240		
									Weight: 29 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF 2100F 1.8E  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


(size) 5=Mechanical, 6=0-3-8  
Max Horz 6=188(LC 5)  
Max Uplift 5=91(LC 8), 6=-74(LC 8)  
Max Grav 5=377(LC 1), 6=453(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-436/118, 2-6=-359/123  
BOT CHORD 5-6=-143/351  
WEBS 3-5=-370/189

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 6.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655416
400565	H1	GABLE	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:50 2020 Page 1

ID:M6\_qRERj\_ax8BAPGKEbrTSyOhsj-CRPtHuLy7XnUn2lqPS?FIKNMlymM11pioXBWoHyi0ll




Plate Offsets (X,Y)-- [1:0-0-0,0-1-4], [7:0-3-8,0-5-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.84	Vert(LL) -0.08	7-9	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.45	Vert(CT) -0.15	7-9	>999	240		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.71	Horz(CT) 0.02	6	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Wind(LL) 0.06	7-9	>999	240	Weight: 286 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x8 SP DSS  
WEBS 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-0-15 oc purlins, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 4-5.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
JOINTS 1 Brace at Jt(s): 5, 10, 11

**REACTIONS.** (size) 1=0-5-8, 6=0-3-0  
Max Horz 1=278(LC 28)  
Max Uplift 1=438(LC 8), 6=510(LC 5)  
Max Grav 1=3291(LC 1), 6=3100(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-5190/789, 2-3=-2387/414, 3-4=-1959/279  
BOT CHORD 1-9=-772/4584, 7-9=-772/4584, 6-7=-376/2136  
WEBS 2-9=-167/1916, 2-7=-2606/446, 7-10=-376/2752, 4-10=-376/2755, 4-11=-3030/515, 6-11=-3152/538, 3-10=-431/198, 10-11=-524/204, 11-12=-318/165

#### NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-7-0 oc.  
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-9-0 oc.  
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=438, 6=510.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT
400565	H1	GABLE	1	2	I42655416
					Job Reference (optional)

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:50 2020 Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-CRPtHuLy7XnUn2lqPS?FIKNMlymM11pioXBWoHyi0ll

NOTES-

- 14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 474 lb down and 39 lb up at 0-2-12, 467 lb down and 45 lb up at 2-6-4, 467 lb down and 58 lb up at 4-6-4, 467 lb down and 85 lb up at 6-6-4, 467 lb down and 91 lb up at 8-6-4, 467 lb down and 91 lb up at 10-6-4, 467 lb down and 91 lb up at 12-6-4, 467 lb down and 91 lb up at 14-6-4, and 467 lb down and 91 lb up at 16-6-4, and 461 lb down and 89 lb up at 18-6-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 15) Studding applied to ply: 1(Front)

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)
  - Vert: 1-4=-70, 4-5=-70, 1-6=-20
- Concentrated Loads (lb)
  - Vert: 1=-474(B) 9=-467(B) 7=-467(B) 25=-467(B) 26=-467(B) 27=-467(B) 28=-467(B) 29=-467(B) 30=-467(B) 31=-461(B)



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655417
400565	H2	Roof Special Girder	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871


8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:51 2020 Page 1

ID:M6\_qRERj\_ax8BapGKEbrTSyOhsj-gdzFUEmburVLOBK0z9WUrXwaAM4xmYBt0Bw4Kjyi0lk

6-6-12	13-9-2	17-4-3	19-4-8	22-5-2	25-11-7	28-10-12	29-10-12	32-2-0	33-0-8
6-6-12	7-2-6	3-7-2	2-0-5	3-0-10	3-6-6	2-11-5	1-0-0	2-3-4	0-10-8

8x8 = 6.00 12

Scale = 1:63.2



6-6-12	13-9-2	17-4-3	19-4-8	22-5-2	25-11-7	28-10-12	29-10-12	32-2-0
6-6-12	7-2-6	3-7-2	2-0-5	3-0-10	3-6-6	2-11-5	1-0-0	2-3-4

Plate Offsets (X,Y)-- [8:0-4-7,0-4-0], [13:0-3-8,Edge], [20:0-2-8,0-1-8], [21:Edge,0-5-4]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.64	Vert(LL)	-0.08	18-20	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.62	Vert(CT)	-0.16	18-20	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.45	Horz(CT)	-0.03	16	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.05	18-20	>999	240	
								Weight: 134 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2 \*Except\*  
7-8,8-9: 2x6 SPF No.2  
BOT CHORD 2x4 SPF No.2 \*Except\*  
6-17: 2x3 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
11-13: 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-4-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-7, 9-10.  
BOT CHORD Rigid ceiling directly applied or 9-9-11 oc bracing.  
WEBS 1 Row at midpt 2-18, 5-17

#### REACTIONS.

(size) 16=0-3-8, 13=0-3-8, 21=0-5-8  
Max Horz 21=261(LC 8)  
Max Uplift 16=307(LC 8), 13=131(LC 9), 21=105(LC 29)  
Max Grav 16=1528(LC 2), 13=637(LC 2), 21=883(LC 23)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1441/163, 2-4=-737/79, 4-5=-709/175, 7-8=-695/111, 8-9=-701/107, 9-10=-460/117, 10-11=-613/122, 1-21=-791/138, 11-13=-499/124  
BOT CHORD 20-21=-310/313, 18-20=-358/1273, 16-17=-167/798, 6-16=-303/106, 15-16=-118/681, 14-15=-104/721, 13-14=-70/477  
WEBS 2-18=-734/225, 4-18=-424/216, 5-18=-249/1015, 5-17=-727/197, 7-16=-776/151, 8-15=-11/345, 9-14=-492/65, 10-14=-18/355, 1-20=-48/963

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 16=307, 13=131, 21=105.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 54 lb down and 85 lb up at 29-10-12 on top chord, and 5 lb down and 5 lb up at 29-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

Continued on page 2



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655417
400565	H2	Roof Special Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:51 2020 Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-gdzFUEMburvLOBK0z9WUrXwaAM4xmYBt0Bw4Kjyi0lk

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-5=-70, 5-7=-70, 7-8=-70, 8-9=-70, 9-10=-70, 10-11=-70, 11-12=-70, 17-21=-20, 13-16=-20  
Concentrated Loads (lb)  
Vert: 14=1(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655418
400565	H3	Roof Special	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:53 2020 Page 1

ID:M6\_qRERj\_ax8BapGKEbrTSyOHsj-c05?vvNrQS93eVUP4aYwy?yAAAnMEPG9UUPAPcyi0li

Job Reference (optional)




Plate Offsets (X,Y)--										[8:0-4-6,0-3-15], [13:0-3-8,Edge], [21:0-2-8,0-1-8], [22:Edge,0-5-4]									
LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL		1.15		TC	0.54	Vert(LL)	-0.08	19-21	>999		360		MT20		197/144		
TCDL	10.0	Lumber DOL		1.15		BC	0.56	Vert(CT)	-0.15	19-21	>999		240						
BCLL	0.0 *	Rep Stress Incr		YES		WB	0.60	Horz(CT)	-0.05	17	n/a		n/a						
BCDL	10.0	Code IRC2018/TPI2014				Matrix-S		Wind(LL)	0.04	19-21	>999		240		Weight: 132 lb		FT = 10%		

#### LUMBER-

TOP CHORD 2x4 SPF No.2 \*Except\*  
7-8,8-9: 2x6 SPF No.2  
BOT CHORD 2x4 SPF No.2 \*Except\*  
5-18: 2x3 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
11-13: 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-4-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7, 9-10.  
BOT CHORD Rigid ceiling directly applied or 9-9-13 oc bracing.  
WEBS 1 Row at midpt 4-18, 2-19

#### REACTIONS.

(size) 17=0-3-8, 13=0-3-8, 22=0-5-8  
Max Horz 22=261(LC 8)  
Max Uplift 17=-296(LC 8), 13=-105(LC 9), 22=-105(LC 8)  
Max Grav 17=1522(LC 2), 13=637(LC 2), 22=885(LC 23)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1444/163, 2-4=-742/81, 6-7=-679/109, 7-8=-648/131, 8-9=-607/117,  
9-10=-531/123, 10-11=-681/104, 1-22=-789/138, 11-13=-538/128  
BOT CHORD 21-22=-311/315, 19-21=-357/1275, 18-19=-156/610, 17-18=-152/771, 5-17=-335/125,  
15-16=-42/685, 14-15=-32/604, 13-14=-34/537  
WEBS 6-17=-384/78, 6-16=-42/696, 7-15=-297/59, 8-15=-76/356, 4-18=-926/236,  
2-19=-731/221, 1-21=-45/963, 4-19=-8/580

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 17=296, 13=105, 22=105.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655419
400565	H4	Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:54 2020 Page 1

ID:M6\_qRERj\_ax8BAPGKEbrTSyOHsj-4CeN7FOTBmHwGf3bel3BTAY2iZ5DzrvJi89kx2yi0lh

8-11-7	15-8-0	19-7-12	22-1-13	25-10-12	32-2-0	33-0-8
8-11-7	6-8-9	3-11-12	2-6-1	3-8-15	6-3-4	0-10-8




Plate Offsets (X,Y)--	[7:0-3-10,Edge], [10:Edge,0-7-5], [17:Edge,0-5-11]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	-0.15 16-17	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.58	Vert(CT)	-0.30 16-17	>772	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.70	Horz(CT)	0.02 13	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.04 16	>999	240	Weight: 127 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2 \*Except\*  
 4-15: 2x3 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 1-17: 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and  
 2-0-0 oc purlins (6-0-0 max.): 6-7.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.


(size) 17=0-5-8, 10=0-3-8, 13=0-3-8  
 Max Horz 17=270(LC 8)  
 Max Uplift 17=-61(LC 8), 10=-92(LC 9), 13=-368(LC 8)  
 Max Grav 17=726(LC 2), 10=496(LC 22), 13=1979(LC 2)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-956/34, 2-4=-406/82, 4-5=-345/1369, 5-6=-273/1324, 6-7=-290/105, 7-8=-418/126,  
 1-17=-619/110, 8-10=-440/122  
 BOT CHORD 16-17=-380/543, 4-14=-131/745, 11-13=-508/208, 10-11=-108/263  
 WEBS 2-16=-540/302, 14-16=-302/1080, 2-14=-532/99, 4-13=-1477/430, 5-13=-303/140,  
 6-13=-1345/218, 6-11=-69/743, 7-11=-332/110, 1-16=0/313

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 17, 10 except (jt=lb) 13=368.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655420
400565	H6	Roof Special	2	1		

Wheeler Lumber, Waverly, KS 66871


8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:55 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-YOCmKbP5y4PntpeoC?bQ?N4DRzRSiFNSxouHTVyi0lg

8-11-7	15-8-0	19-7-12	19-11-3	24-2-5	32-2-0	33-0-8
8-11-7	6-8-9	3-11-12	0-3-7	4-3-3	7-11-11	0-10-8

6x6 =

Scale = 1:67.1



8-11-7	15-8-0	19-7-12	24-2-5	32-2-0
8-11-7	6-8-9	3-11-12	4-6-9	7-11-11

Plate Offsets (X,Y)-- [6:0-2-12,Edge], [9:0-4-12,0-2-12], [16:Edge,0-5-11]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	-0.15 15-16	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.58	Vert(CT)	-0.31 15-16	>766	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.88	Horz(CT)	0.03 12	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.04 15	>999	240	Weight: 127 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2 \*Except\*  
 4-14: 2x3 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 1-16: 2x4 SPF No.2, 7-9: 2x6 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 5-0-8 oc bracing.

#### REACTIONS.

(size) 16=0-5-8, 12=0-3-8, 9=0-3-8  
 Max Horz 16=285(LC 8)  
 Max Uplift 16=-56(LC 8), 12=-395(LC 8), 9=-106(LC 9)  
 Max Grav 16=732(LC 2), 12=1962(LC 2), 9=475(LC 22)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-968/23, 2-4=-501/97, 4-5=-333/1344, 5-6=-128/283, 6-7=-267/259, 1-16=-625/105,  
 7-9=-402/152  
 BOT CHORD 15-16=-393/544, 4-13=-136/795, 12-13=-106/307, 10-12=-1193/300, 9-10=-217/528  
 WEBS 2-15=-552/306, 13-15=-308/1096, 2-13=-468/75, 4-12=-1550/419, 5-12=-1420/325,  
 5-10=-179/1309, 6-10=-463/163, 1-15=0/331, 7-10=-580/263

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 16 except (jt=lb) 12=395, 9=106.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655421
400565	H7	Roof Special	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:56 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-0bm8YxQjNxeVzC\_mi6fYbdP1NmPRkRcASer0xyi0lf

0-10-8 8-11-6 15-4-8 18-5-5 24-2-5 32-2-0 33-0-8  
0-10-8 8-11-6 6-5-1 3-0-13 5-9-0 7-11-11 0-10-8

5x7

Scale = 1:67.5




Plate Offsets (X,Y)--	[7:0-4-11,0-2-8], [10:0-4-12,0-2-12], [16:0-3-0,0-2-4]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.83	Vert(LL)	-0.14 11-13	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.67	Vert(CT)	-0.28 15-16	>646	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.76	Horz(CT)	-0.02 10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.03 15-16	>999	240	Weight: 126 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2 \*Except\*  
5-14: 2x3 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-16,8-10: 2x6 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-7 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.  
WEBS 1 Row at midpt 2-15

#### REACTIONS.

(size) 16=0-5-8, 13=0-3-8, 10=0-3-8  
Max Horz 16=299(LC 8)  
Max Uplift 16=-74(LC 8), 13=-302(LC 8), 10=-115(LC 9)  
Max Grav 16=759(LC 2), 13=1506(LC 2), 10=831(LC 2)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-872/20, 6-7=-884/118, 7-8=-950/117, 2-16=-672/125, 8-10=-758/156  
BOT CHORD 15-16=-510/740, 5-13=-286/97, 11-13=-184/822, 10-11=-228/536  
WEBS 3-15=-458/274, 13-15=-282/977, 3-13=-682/105, 6-13=-911/189, 7-11=0/338, 2-15=-59/306, 8-11=-23/379

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 16 except (jt=lb) 13=302, 10=115.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655422
400565	H8	Roof Special	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:57 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-VnKWlHQLUhfV76nAJQdu4oAZUn7PABSIP6NOYNYi0le

Job Reference (optional)



Scale = 1:62.2

Plate Offsets (X,Y)-- [7:0-4-11,0-2-8], [11:Edge,0-2-8], [15:0-3-0,0-2-4]									
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d		<b>PLATES</b>	<b>GRIP</b>
TCLL	25.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.14 14-15 >999 360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.28 14-15 >646 240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.72	Horz(CT)	0.02 9 n/a n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.02 14-15 >999 240	Weight: 116 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2 \*Except\*  
 5-13,6-11: 2x3 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 2-15: 2x6 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-9-6 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.  
 WEBS 1 Row at midpt 2-14

#### REACTIONS.


(size) 15=0-5-8, 12=0-3-8, 9=Mechanical  
 Max Horz 15=245(LC 8)  
 Max Uplift 12=-122(LC 8), 9=-7(LC 8)  
 Max Grav 15=756(LC 2), 12=1284(LC 2), 9=529(LC 2)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-877/0, 5-6=-880/65, 6-7=-851/121, 2-15=-668/22  
 BOT CHORD 14-15=-337/753, 5-12=-682/142, 6-10=-529/165, 9-10=-0/394  
 WEBS 3-14=-442/162, 12-14=-112/963, 3-12=-638/26, 10-12=-62/258, 5-10=-13/439,  
 7-10=-123/808, 2-14=-87/256, 7-9=-498/15

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9 except (jt=lb) 12=122.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655423
400565	H9	GABLE	1	1		


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:58 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-zzuuzdR\_E?nMkGMMt787d0iwSBcTvpQvdm7x4pyi0ld

-0-10-8 0-10-8 8-8-0 8-8-0

Scale = 1:25.7



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.13	Vert(LL)	0.00	2	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	-0.00	1	n/r	120		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R						Weight: 36 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

All bearings 8-8-0.  
(lb) - Max Horz 13=184(LC 5)  
Max Uplift All uplift 100 lb or less at joint(s) 8, 12, 11, 10, 9  
Max Grav All reactions 250 lb or less at joint(s) 13, 8, 12, 11, 10, 9

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 12, 11, 10, 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655425
400565	J2	Jack-Open	5	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:06 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-kWNweMX?MSoDiVzvlpH?yi2FEPKBnRr4T03MMMyi0IV



Scale = 1:15.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.20	Vert(LL)	-0.01	4-5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	-0.02	4-5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240	
								Weight: 11 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=68(LC 8)  
Max Uplift 5=31(LC 8), 3=64(LC 8)  
Max Grav 5=244(LC 1), 3=116(LC 1), 4=71(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655426
400565	J3	Jack-Open	2	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:13 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-1slZ6ldOicgE1a0FFnvekAqUVEj\_wba64cFE6Syi0IO



Scale = 1:13.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	-0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 8 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-7-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=50(LC 5)  
Max Uplift 5=-27(LC 4), 3=-43(LC 8)  
Max Grav 5=193(LC 1), 3=72(LC 1), 4=47(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655427
400565	J4	Jack-Open	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:20 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-JCDDa8in3IZENf2bAIXHWfdgr26A3mJ8hBS6sYyi0IH



Scale = 1:11.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-3-12 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=40(LC 5)  
Max Uplift 5=17(LC 8), 3=23(LC 8), 4=4(LC 5)  
Max Grav 5=150(LC 1), 3=17(LC 1), 4=22(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655428
400565	J6	Diagonal Hip Girder	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:25 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-gA05dsmvulBXUQwZyi7SDiKlp3jek1AtrT9tXlyi0IC



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	-0.11	4-5	>706	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.51	Vert(CT)	-0.22	4-5	>351	240	197/144
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.02	Horz(CT)	-0.00	4	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	-0.01	4-5	>999	240	
								Weight: 24 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 3-4: 2x6 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-11, 4=Mechanical  
 Max Horz 5=97(LC 5)  
 Max Uplift 5=110(LC 4), 4=106(LC 8)  
 Max Grav 5=409(LC 1), 4=383(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-5=-342/176, 3-4=-286/151

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=110, 4=106.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 78 lb down and 48 lb up at 2-11-12, and 76 lb down and 56 lb up at 4-2-6, and 97 lb down and 85 lb up at 6-1-3 on top chord, and 6 lb down at 2-11-12, and 13 lb down at 4-2-6, and 48 lb down at 6-1-3 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70, 2-3=-70, 4-5=-20  
 Concentrated Loads (lb)  
 Vert: 8=-77(F) 9=-1(F) 10=-1(B) 11=-36(F)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655429
400565	J7	Jack-Open	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:26 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-8MaUrBnYebJN5aVIW0ehmwti?T90TUo037vQ4Cyi0IB



Scale = 1:14.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	-0.00	4-5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	-0.00	4-5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	
								Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-7-10 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=58(LC 5)  
Max Uplift 5=-16(LC 8), 3=-50(LC 8)  
Max Grav 5=193(LC 1), 3=72(LC 1), 4=47(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655430
400565	J8	Jack-Open	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:26 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-8MaUrBnYebJN5aVIW0ehmwitLT9ATUo037vQ4Cyi0IB



Scale = 1:12.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	4-5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	-0.00	4-5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	
									Weight: 8 lb FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-5-2 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=50(LC 5)  
Max Uplift 5=-26(LC 4), 3=-41(LC 8)  
Max Grav 5=185(LC 1), 3=65(LC 1), 4=43(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655431
400565	J9	Jack-Open	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:27 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-cY8s2XoAPvREjk4x4j9wl7Pp\_tS?Cx2Alne\_ceyi0IA



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.33	Vert(LL)	-0.02	4-5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.20	Vert(CT)	-0.05	4-5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.03	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.03	4-5	>999	240	
									Weight: 14 lb FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 4-9-15 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=83(LC 8)  
Max Uplift 5=35(LC 8), 3=77(LC 8)  
Max Grav 5=287(LC 1), 3=145(LC 1), 4=87(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655432
400565	J10	Jack-Open	3	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:53:59 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-RASGAzSc?lvDMQxZRrFM9DF??auJeG62sQsVcGyi0lc



Scale = 1:19.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.46	Vert(LL)	-0.04	5-6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.27	Vert(CT)	-0.09	5-6	>702	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.04	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.04	5-6	>999	240	Weight: 15 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-5-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

(size) 6=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 6=94(LC 8)  
Max Uplift 6=37(LC 8), 3=90(LC 8)  
Max Grav 6=313(LC 1), 3=170(LC 1), 4=101(LC 3)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-6=-269/85

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017





Scale = 1:25.2

Plate Offsets (X,Y)-- [2-0-2-0-0-1-4]												
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d				<b>PLATES</b>	<b>GRIP</b>	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.05	4-5	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.10	4-5	>674	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-R		Wind(LL)	0.03	4-5	>999	240	Weight: 19 lb	FT = 10%

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SPF No.2		
WEBS	2x3 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
Max Horz 5=158(LC 5)  
Max Uplift 5=-50(LC 8), 4=-70(LC 8)  
Max Grav 5=335(LC 1), 4=255(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
**TOP CHORD** 2-5=-290/96

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDD=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655434
400565	J12	Jack-Closed	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:00 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vM0fNITEmc14\_aWi?YAbiRoAf\_EENjMB54c29iyi0lb

0-10-8 5-7-0 6-0-0  
0-10-8 5-7-0 0-5-0

Scale = 1:25.9




Plate Offsets (X,Y)-- [2:0-2-0,0-1-4], [3:0-2-0,0-2-8], [4:Edge,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.46	Vert(LL)	-0.05	5-6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.29	Vert(CT)	-0.10	5-6	>684	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	5-6	>999	240	Weight: 19 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 6=0-3-8, 5=Mechanical  
Max Horz 6=152(LC 5)  
Max Uplift 6=-52(LC 8), 5=-62(LC 8)  
Max Grav 6=335(LC 1), 5=255(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-6=-290/98

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 5.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655435
400565	J13	Jack-Closed Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:01 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-NYZ1beTsXw9xbk5xYGhqFeKN7ObK69GLJkLch8yi0la




Plate Offsets (X,Y)-- [2:0-3-0,0-1-4], [3:0-5-0,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.35	Vert(LL)	-0.01	6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	-0.02	6	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.09	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.01	6	>999	240	Weight: 22 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 7=0-3-8, 5=Mechanical  
Max Horz 7=111(LC 24)  
Max Uplift 7=-84(LC 8), 5=-131(LC 5)  
Max Grav 7=382(LC 1), 5=415(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-7=-323/104, 2-3=-294/74  
WEBS 3-5=-292/101

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7 except (jt=lb) 5=131.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 171 lb down and 155 lb up at 3-7-0, and 71 lb down and 71 lb up at 5-10-12 on top chord, and 62 lb down at 3-7-0, and 41 lb down at 5-10-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 3-4=-70, 5-7=-20  
Concentrated Loads (lb)  
Vert: 4=-62(B) 5=-25(B) 6=-42(B) 3=-77(B)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655437
400565	J15	Jack-Open	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:03 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Jxhn0KV63XPer1FKghkIK3Qn7CJAa46en2qim1yi0IY



Scale = 1:11.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-5-15 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=43(LC 5)  
Max Uplift 5=16(LC 8), 3=27(LC 8), 4=2(LC 8)  
Max Grav 5=155(LC 1), 3=27(LC 1), 4=26(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655438
400565	J16	Jack-Open	2	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:03 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Jxhn0KV63XPer1FKghkIK3QmXCipa46en2qim1yi0IY

-0-10-8  
0-10-8  
3-7-0  
3-7-0

Scale = 1:16.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.17	Vert(LL)	-0.01	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	-0.01	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240	Weight: 10 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=76(LC 8)  
Max Uplift 5=20(LC 8), 3=66(LC 8)  
Max Grav 5=232(LC 1), 3=106(LC 1), 4=66(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655439
400565	J17	Jack-Closed	3	1	Job Reference (optional)	


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:04 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-n7F9DgWkqrYVSBqWEOFXsHysYbfkXJLn0iaGItYi0IX

-0-10-8  
0-10-8  
3-0-0  
3-0-0

Scale = 1:15.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	-0.00	4-5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	-0.01	4-5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	
								Weight: 10 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 4=Mechanical  
Max Horz 5=96(LC 5)  
Max Uplift 5=35(LC 8), 4=36(LC 5)  
Max Grav 5=206(LC 1), 4=114(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655440
400565	J18	Jack-Closed	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:04 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-n7F9DgWkqrYVSBqWEOFXsHyv9bdaJXLn0iaGItYi0IX



Scale = 1:17.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.24	Vert(LL)	-0.01	3-4	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	-0.02	3-4	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	3-4	>999	240	
									Weight: 13 lb FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-3-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 4=0-3-8, 3=Mechanical  
Max Horz 4=108(LC 5)  
Max Uplift 4=-29(LC 4), 3=-44(LC 5)  
Max Grav 4=183(LC 1), 3=183(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655441
400565	J19	Jack-Closed	3	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:05 2020 Page 1

ID:M6\_gRERj\_ax8BApGKEbrTSyOHsj-GJpYR0XNb8gM4LPjn5mmPUV?N?xx2\_bxEMJpqqyioIW




Plate Offsets (X,Y)-- [4:Edge,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.53	Vert(LL)	-0.06	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.32	Vert(CT)	-0.12	4-5	>605	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	4-5	>999	240	Weight: 18 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 4=Mechanical  
Max Horz 5=120(LC 5)  
Max Uplift 5=-86(LC 4), 4=-61(LC 8)  
Max Grav 5=350(LC 1), 4=270(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-5=-303/131

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655442
400565	J20	Diagonal Hip Girder	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:06 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-kWNweMX?MSoDiVzVLPH?yi2ABPH9nRr4T03MMMyi0IV



Scale = 1:19.3

Plate Offsets (X,Y)-- [2:0-2-0,0-1-4]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.53	Vert(LL)	-0.05	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.32	Vert(CT)	-0.10	4-5	>686	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	4-5	>999	240	Weight: 18 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-4-9, 4=Mechanical  
Max Horz 5=122(LC 7)  
Max Uplift 5=120(LC 4), 4=70(LC 8)  
Max Grav 5=381(LC 1), 4=254(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-5=-332/155

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=120.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 18 lb up at 1-10-11, and 79 lb down and 48 lb up at 3-0-14, and 79 lb down and 60 lb up at 4-5-15 on top chord, and 6 lb down and 11 lb up at 1-10-11, and 7 lb down at 3-0-14, and 14 lb down at 4-5-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 4-5=-20  
Concentrated Loads (lb)  
Vert: 9=2(B) 10=-1(F) 11=-2(B)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655443
400565	J21	Jack-Open	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:07 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-CixlriYd7mw4JfY5vWoEUvaS8pggWu5Digowv0i0IU



Scale = 1:12.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	-0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 7 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-6-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=49(LC 5)  
Max Uplift 5=-27(LC 4), 3=-41(LC 8)  
Max Grav 5=188(LC 1), 3=67(LC 1), 4=44(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655445
400565	J23	Jack-Open	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:09 2020 Page 1

ID:M6\_qRERj\_ax8BapGKEbrTSyOHsj-8522GNatfNAoZyiU0xriZKfodcMc\_nbW9\_H1zhyi0IS



Scale = 1:10.8

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	0.00	5	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R						Weight: 4 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-1-14 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=38(LC 5)  
Max Uplift 5=17(LC 8), 3=19(LC 8), 4=5(LC 5)  
Max Grav 5=148(LC 1), 3=10(LC 15), 4=19(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655446
400565	J24	Jack-Open	2	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:09 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-8522GNatfNAoZyiU0xriZKfoCcMv\_nbW9\_H1zhyi0IS



Scale = 1:15.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	-0.01	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-9-14 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=61(LC 8)  
Max Uplift 5=-18(LC 8), 3=-53(LC 8)  
Max Grav 5=201(LC 1), 3=79(LC 1), 4=51(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655447
400565	J25	Jack-Open	4	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:10 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-cHcRUjaVQhIfA6HgafMx6YCzj0ghjErgOe1aV7yi0IR



Scale = 1:17.9

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.11	Vert(LL)	-0.01	6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.15	Vert(CT)	-0.01	7-8	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	6	>999	240	Weight: 13 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2 \*Except\*  
3-7: 2x3 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


#### REACTIONS.

(size) 8=0-3-8, 4=Mechanical, 5=Mechanical  
Max Horz 8=85(LC 8)  
Max Uplift 8=22(LC 8), 4=11(LC 8), 5=55(LC 8)  
Max Grav 8=250(LC 1), 4=63(LC 1), 5=100(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 4, 5.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655448
400565	J26	Jack-Open	11	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:11 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-4TAph3b7B\_QWoGss8MtAfl6iQ0CSh4pdlm72Zyi0IQ

-0-10-8 4-0-0  
0-10-8 4-0-0

Scale = 1:17.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.22	Vert(LL)	-0.01	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.14	Vert(CT)	-0.02	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.02	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240	Weight: 11 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=85(LC 8)  
Max Uplift 5=22(LC 8), 3=73(LC 8)  
Max Grav 5=250(LC 1), 3=121(LC 1), 4=74(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655449
400565	J27	Jack-Open	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:11 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-4TAph3b7B\_QWoGss8MtAIII98Q28Sh4pdlm72Zyi0IQ



Scale = 1:9.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.01	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 1-4-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=31(LC 5)  
Max Uplift 5=54(LC 4), 3=17(LC 8)  
Max Grav 5=152(LC 1), 3=21(LC 1), 4=23(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655450
400565	J28	Jack-Open	3	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:12 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-YgkBVpcmxIYNQQR3i3OPBzHHdqMYB8KyryWha0yi0IP



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	-0.01	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	-0.02	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240	Weight: 11 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 3-11-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=60(LC 4)  
Max Uplift 5=61(LC 4), 3=58(LC 8)  
Max Grav 5=247(LC 1), 3=118(LC 1), 4=72(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655451
400565	J29	Jack-Open	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:12 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-YgkBvPcmxIYNQQR3i3OPBzHJtqOMB8KyryWha0yi0IP



Scale = 1:10.1

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.01	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 1-3-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=36(LC 5)  
Max Uplift 5=32(LC 4), 3=18(LC 8), 4=2(LC 5)  
Max Grav 5=150(LC 1), 3=15(LC 1), 4=21(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655452
400565	J30	Diagonal Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:14 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-V2sxJ5e0Tvo4fkbRpUQtGONdWd1Qf2qFJG?oeuyi0IN



Scale = 1:13.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.25	Vert(LL)	-0.02	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	-0.03	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240		
									Weight: 14 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-2 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-4-11, 4=Mechanical  
Max Horz 5=82(LC 22)  
Max Uplift 5=109(LC 4), 4=41(LC 8)  
Max Grav 5=319(LC 1), 4=178(LC 1)

#### FORCES.


(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-282/135

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=109.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 74 lb down and 19 lb up at 1-6-3, and 61 lb down and 18 lb up at 2-1-6 on top chord, and 3 lb down and 2 lb up at 1-6-3, and 4 lb down and 8 lb up at 2-1-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 4-5=-20  
Concentrated Loads (lb)  
Vert: 8=2(F) 9=2(B)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655453
400565	J31	Diagonal Hip Girder	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:14 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-V2sxJ5e0Tvo4fkbRpUQtGONa\_d06f2qFJG?oeuyi0IN



Scale = 1:19.2

Plate Offsets (X,Y)--		[2:0-2-0,0-1-4]							
<b>LOADING</b> (psf)		<b>SPACING-</b>	2-0-0	<b>CSI.</b>		<b>DEFL.</b>	in (loc)	L/defl	L/d
TCLL 25.0		Plate Grip DOL	1.15	TC 0.41		Vert(LL)	-0.03 4-5	>999	360
TCDL 10.0		Lumber DOL	1.15	BC 0.25		Vert(CT)	-0.07 4-5	>962	240
BCLL 0.0 *		Rep Stress Incr	NO	WB 0.00		Horz(CT)	-0.00 4	n/a	n/a
BCDL 10.0		Code IRC2018/TPI2014		Matrix-R		Wind(LL)	0.02 4-5	>999	240
						<b>PLATES</b>		<b>GRIP</b>	
						MT20		197/144	
						Weight: 17 lb		FT = 10%	

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-5-5 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-4-9, 4=Mechanical  
Max Horz 5=122(LC 5)  
Max Uplift 5=106(LC 4), 4=62(LC 8)  
Max Grav 5=341(LC 1), 4=223(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-298/135

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=106.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 71 lb down and 39 lb up at 2-8-7, and 71 lb down and 39 lb up at 2-8-7 on top chord, and 4 lb down and 10 lb up at 2-8-7, and 4 lb down and 10 lb up at 2-8-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 4-5=-20  
Concentrated Loads (lb)  
Vert: 7=1(F=1, B=1)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655454
400565	J32	Jack-Open	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:15 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-zFQKXReeEDwxHt9eNCy6pbvq61PtOV4PXwkLBKy0IM



Scale = 1:12.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 6 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-10-3 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=47(LC 5)  
Max Uplift 5=-17(LC 8), 3=-35(LC 8)  
Max Grav 5=166(LC 1), 3=43(LC 1), 4=33(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655455
400565	J33	Jack-Open	10	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:16 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-RRziknfG?X2ou1kqxvTLMpSzaRjS7yKYmZUujnyi0IL

-0-10-8 0-10-8 3-11-4 3-11-4

Scale = 1:17.8



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	-0.01	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	-0.02	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.02	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	240	Weight: 11 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-11-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=84(LC 8)  
Max Uplift 5=21(LC 8), 3=72(LC 8)  
Max Grav 5=247(LC 1), 3=118(LC 1), 4=72(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655456
400565	J34	Jack-Open	1	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:16 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-RRziknfG?X2ou1kqxvTLMpS?BRkn7yKYmZUujnyi0IL

-0-10-8  
0-10-8  
3-0-6  
3-0-6

Scale = 1:15.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.11	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	-0.01	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-0-6 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=65(LC 8)  
Max Uplift 5=-19(LC 8), 3=-56(LC 8)  
Max Grav 5=209(LC 1), 3=87(LC 1), 4=55(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655457
400565	J35	Jack-Open	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:17 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vdX4y6gumqAfWBj0Ud\_au0?Abr5SsPzi?DDSFdyi0IK



Scale = 1:11.4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-4-6 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=41(LC 5)  
Max Uplift 5=16(LC 8), 3=24(LC 8), 4=3(LC 5)  
Max Grav 5=152(LC 1), 3=20(LC 1), 4=23(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655458
400565	J36	Diagonal Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:17 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-vdX4y6gumqAfWBJ0Ud\_au0?4gr1psPZi?DDSFdyi0IK




Plate Offsets (X,Y)-- [2:0-2-0,0-1-4]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.51	Vert(LL) -0.05	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.31	Vert(CT) -0.10	4-5	>704	240		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT) -0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) 0.02	4-5	>999	240	Weight: 18 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-4-9, 4=Mechanical  
Max Horz 5=120(LC 22)  
Max Uplift 5=118(LC 4), 4=75(LC 8)  
Max Grav 5=378(LC 1), 4=256(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD 2-5=-330/155

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=118.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 25 lb up at 2-2-9, and 78 lb down and 47 lb up at 2-11-11, and 79 lb down and 62 lb up at 4-9-13 on top chord, and 5 lb down and 10 lb up at 2-2-9, and 6 lb down at 2-11-11, and 18 lb down at 4-9-13 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 4-5=-20
- Concentrated Loads (lb)  
Vert: 8=-3(F) 9=1(F) 10=-1(B) 11=-7(F)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655459
400565	J37	Jack-Open	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:18 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Np5S9ShWX8IW8LuC2KVpREXLMFRlbsprEtz?nfyi0IJ



Scale = 1:12.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	-0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 7 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-5-2 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=48(LC 5)  
Max Uplift 5=-27(LC 4), 3=-40(LC 8)  
Max Grav 5=185(LC 1), 3=64(LC 1), 4=43(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655460
400565	J38	Diagonal Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:19 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEBrTSyOHsj-r0fqNoh9ISQNIvTPc202zR4S1ek1KJ3\_SXiZK6yi0ll



Scale = 1:15.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.33	Vert(LL)	-0.02	4-5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.20	Vert(CT)	-0.04	4-5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.02	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	4-5	>999	240	
								Weight: 13 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-10 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-4-9, 3=Mechanical, 4=Mechanical  
Max Horz 5=72(LC 4)  
Max Uplift 5=99(LC 4), 3=68(LC 8)  
Max Grav 5=319(LC 1), 3=136(LC 1), 4=85(LC 3)


**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-280/126

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 73 lb down and 23 lb up at 1-7-5, and 65 lb down and 32 lb up at 2-7-2 on top chord, and 4 lb down and 7 lb up at 1-7-5, and 5 lb down and 10 lb up at 2-7-2 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 4-5=-20  
Concentrated Loads (lb)  
Vert: 8=2(F) 9=1(B)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655461
400565	J39	Jack-Open	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:19 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOhsj-r0fqNoh9ISQNVTPc202zR4W6en\_KJ3\_SXiZK6yi0ll



Scale = 1:10.4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.01	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 1-4-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=37(LC 5)  
Max Uplift 5=31(LC 4), 3=21(LC 8), 4=1(LC 5)  
Max Grav 5=152(LC 1), 3=21(LC 1), 4=23(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655462
400565	J40	Jack-Open	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:21 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-oOnbnUjPq3h5?odnjS2W3s9rbSSL0DZHwrBfo\_yi0IG



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	5	>999	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	-0.00	5	>999	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	5	>999	240	
								Weight: 6 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-7-5 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=44(LC 5)  
Max Uplift 5=16(LC 8), 3=30(LC 8), 4=1(LC 8)  
Max Grav 5=158(LC 1), 3=32(LC 1), 4=28(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655463
400565	J41	Jack-Open	2	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:21 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-oOnbnUjPq3h5?odnjS2W3s9rtSRWoDZHwrBfo\_yi0IG



Scale = 1:15.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.11	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	-0.01	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 3-0-12 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=66(LC 8)  
Max Uplift 5=-19(LC 8), 3=-57(LC 8)  
Max Grav 5=210(LC 1), 3=88(LC 1), 4=56(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655465
400565	J43	Diagonal Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:22 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-GbLz?pk1bNpydyC\_HAalb4i0Nso3XgpR8VxDxQyi0IF



Scale = 1:13.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.13	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	-0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-1-1 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-4-9, 3=Mechanical, 4=Mechanical  
Max Horz 5=68(LC 7)  
Max Uplift 5=89(LC 6), 3=-57(LC 12), 4=-3(LC 19)  
Max Grav 5=104(LC 1), 3=38(LC 1), 4=41(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 23 lb down and 8 lb up at -1-2-14, and 23 lb down and 8 lb up at -1-2-14 on top chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Concentrated Loads (lb)  
Vert: 1=-35(F=-17, B=-17)  
Trapezoidal Loads (plf)  
Vert: 1=0(F=35, B=35)-to-2=-23(F=23, B=23), 2=-2(F=34, B=34)-to-3=-54(F=8, B=8), 5=-0(F=10, B=10)-to-4=-15(F=2, B=2)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655466
400565	J44	Diagonal Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:23 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-knvLCAIfMgxpE6nArt5\_8HFBYG8ZG73aN9gmTtyi0IE



Scale = 1:12.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.10	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	-0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 8 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-7-6 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 5=0-4-9, 3=Mechanical, 4=Mechanical  
Max Horz 5=63(LC 7)  
Max Uplift 5=95(LC 6), 3=-47(LC 12), 4=-2(LC 19)  
Max Grav 5=85(LC 1), 3=28(LC 1), 4=34(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 17 lb down and 6 lb up at -1-2-14, and 17 lb down and 6 lb up at -1-2-14 on top chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Concentrated Loads (lb)  
Vert: 1=-26(F=-13, B=-13)  
Trapezoidal Loads (plf)  
Vert: 1=0(F=35, B=35)-to-6=-18(F=26, B=26), 6=0(F=35, B=35)-to-2=-6(F=32, B=32), 2=-6(F=32, B=32)-to-3=-49(F=10, B=10), 5=-2(F=9, B=9)-to-4=-14(F=3, B=3)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655468
400565	J46	Diagonal Hip Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:24 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-CzSjQWIH7\_3gsGLMPbcDgVnLnUh?alkcpQJ?Jyi0ID



Scale = 1:12.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.13	Vert(LL)	-0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	-0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00	4-5	>999	240	Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-10-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-4-9, 3=Mechanical, 4=Mechanical  
Max Horz 5=61(LC 7)  
Max Uplift 5=95(LC 6), 3=52(LC 12), 4=3(LC 19)  
Max Grav 5=109(LC 1), 3=27(LC 1), 4=37(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 24 lb down and 9 lb up at -1-4-6, and 24 lb down and 9 lb up at -1-4-6 on top chord. The design/selection of such connection device(s) is the responsibility of others.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Concentrated Loads (lb)  
Vert: 1=-36(F=-18, B=-18)  
Trapezoidal Loads (plf)  
Vert: 1=-0(F=35, B=35)-to-2=-26(F=22, B=22), 2=-2(F=34, B=34)-to-3=-50(F=10, B=10), 5=-0(F=10, B=10)-to-4=-14(F=3, B=3)



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655469
400565	K1	Roof Special Structural Gable	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:28 2020 Page 1  
ID:M6\_qRERj\_ax8BapGKEbrTSyOHsj-4liEFtooADZ5Ltf7eRg9rLy0kHjvxKaJXROX84yi0l9

0-10-8 2-3-8 6-5-0 10-6-8 12-10-0 13-8-8  
0-10-8 2-3-8 4-1-8 4-1-8 2-3-8 0-10-8

Scale: 3/8"=1'




Plate Offsets (X,Y)-- [2:0-2-0,0-0-0], [4:0-1-2,0-1-8], [6:0-2-0,0-0-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.20	Vert(LL) -0.16	10-11	>912	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.54	Vert(CT) -0.33	10-11	>436	240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.24	Horz(CT) 0.04	9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Wind(LL) 0.03	10-11	>999	240	Weight: 58 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

(size) 12=0-3-8, 9=0-3-8  
Max Horz 12=97(LC 7)  
Max Uplift 12=-92(LC 8), 9=-92(LC 9)  
Max Grav 12=637(LC 1), 9=637(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-13=-527/84, 2-3=-747/84, 3-4=-780/170, 4-5=-780/157, 5-6=-747/71, 6-8=-527/76  
BOT CHORD 10-11=-10/431  
WEBS 4-10=-74/324, 6-10=-40/693, 4-11=-83/324, 2-11=-52/693

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 12, 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 12, 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655470
400565	K2	Roof Special	2	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871


8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:29 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-ZxGcTDpQxWhy1EKB8CONYUBlg37gmATi574gWyi0i8

-0-10-8	2-3-8	6-5-0	10-6-8	12-10-0	13-8-8
0-10-8	2-3-8	4-1-8	4-1-8	2-3-8	0-10-8

4x5 =

Scale = 1:30.3



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	-0.15 9-10	>979	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.54	Vert(CT)	-0.32 9-10	>472	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.28	Horz(CT)	0.04 8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.02 9-10	>999	240	Weight: 50 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-8-1 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 11=0-3-8, 8=0-3-8  
Max Horz 11=97(LC 7)  
Max Uplift 11=-90(LC 8), 8=-90(LC 9)  
Max Grav 11=637(LC 1), 8=637(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-11=-635/99, 2-3=-942/113, 3-4=-970/198, 4-5=-970/182, 5-6=-942/96, 6-8=-635/90  
BOT CHORD 9-10=-19/505  
WEBS 4-9=-94/442, 6-9=-56/817, 4-10=-105/442, 2-10=-70/817

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 11, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655471
400565	K3	Roof Special	2	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:30 2020 Page 1  
ID:M6\_qRERj\_ax8BapGKEbrTSyOHsj-17q\_gZq2iqppaBpWlrjdwrm1M14PLPKc\_lteDzyi0I7



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.21	Vert(LL)	-0.15	8-9	>979	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.54	Vert(CT)	-0.32	8-9	>472		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.29	Horz(CT)	0.04	7	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Wind(LL)	0.02	8-9	>999		
	Code IRC2018/TPI2014						Weight: 48 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-7-3 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 10=0-3-8, 7=0-3-8  
Max Horz 10=-100(LC 4)  
Max Uplift 10=-68(LC 8), 7=-90(LC 9)  
Max Grav 10=565(LC 1), 7=639(LC 3)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-10=-567/71, 1-2=-961/107, 2-3=-995/195, 3-4=-975/181, 4-5=-947/96, 5-7=-638/90  
BOT CHORD 8-9=-17/510  
WEBS 3-8=-94/441, 5-8=-55/821, 3-9=-102/464, 1-9=-81/832

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 10, 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10, 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655472
400565	K4	Roof Special	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:31 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-VKNNuvrgT8xgCLOiJZEsSzaXqUla8gYIDPcBIPyI0I6



Scale = 1:29.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	-0.15	7-8	>979	360	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.54	Vert(CT)	-0.32	7-8	>471	240	197/144
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.29	Horz(CT)	0.04	6	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.02	7-8	>999	240	
								Weight: 47 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-


TOP CHORD Structural wood sheathing directly applied or 5-7-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 9=0-3-8, 6=0-3-8  
Max Horz 9=-91(LC 4)  
Max Uplift 9=-68(LC 8), 6=-68(LC 9)  
Max Grav 9=568(LC 1), 6=568(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-9=-569/74, 1-2=-966/113, 2-3=-1000/201, 3-4=-1000/192, 4-5=-966/104, 5-6=-569/69  
BOT CHORD 7-8=-28/515  
WEBS 3-7=-101/464, 5-7=-78/836, 3-8=-107/464, 1-8=-86/836

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 9, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9, 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655473
400565	K5	Roof Special Girder	1	2	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:32 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-zWxl5FrJER3XpVztvGI5?B6fWu5kt6ovS3MIHryi0I5



Scale = 1:33.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.40	Vert(LL)	-0.11	4-5	>999	360	MT20	197/144
BCLL 10.0	Lumber DOL	1.15	BC 0.48	Vert(CT)	-0.19	4-5	>776	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.35	Horz(CT)	0.03	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.06	4-5	>999	240		
									Weight: 139 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x6 SP 2400F 2.0E \*Except\*  
2-6: 2x4 SPF No.2  
WEBS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

(size) 4=0-3-8, 7=0-3-8  
Max Horz 7=90(LC 6)  
Max Uplift 4=175(LC 9), 7=229(LC 8)  
Max Grav 4=2661(LC 1), 7=3237(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.



TOP CHORD 1-2=-3494/344, 2-3=-3482/393, 3-4=-2943/294, 1-7=-1816/196  
BOT CHORD 5-6=-27/988, 2-5=-267/152, 4-5=-215/2541  
WEBS 3-5=-304/2710, 1-5=-249/2868

#### NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-9-0 oc.  
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 4=175, 7=229.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 793 lb down and 54 lb up at 0-1-12, 785 lb down and 40 lb up at 2-5-0, 787 lb down and 67 lb up at 4-5-0, 924 lb down and 208 lb up at 6-5-0, 490 lb down and 32 lb up at 8-5-0, and 509 lb down and 27 lb up at 10-5-0, and 516 lb down and 20 lb up at 12-8-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

#### LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



September 1, 2020

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655473
400565	K5	Roof Special Girder	1	2	Job Reference (optional)	

Wheeler Lumber,      Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc.   Tue Sep 1 10:54:32 2020   Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-zWxl5FrJER3XpVzvtGl5?B6fWu5kt6ovS3MIHryi0l5

LOAD CASE(S)   Standard

Uniform Loads (plf)

Vert: 1-3=-70, 3-4=-70, 6-7=-20, 4-5=-20

Concentrated Loads (lb)

Vert: 4=-499(B) 7=-793(B) 8=-785(B) 9=-787(B) 10=-924(B) 11=-490(B) 12=-492(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655474
400565	L1	Hip Girder	1	2	Job Reference (optional)	


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:34 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vu3VWxtZm3JF3o6H\_hnZ4cCwohjXL0bCvNrrMkyi0I3

-0-10-8	4-11-2	11-3-4	17-8-10	24-0-12	28-0-0	28-10-8
0-10-8	4-11-2	6-4-2	6-5-6	6-4-2	3-11-4	0-10-8

Scale = 1:49.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.74	Vert(LL)	-0.18 11-13	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.72	Vert(CT)	-0.34 11-13	>976	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.33	Horz(CT)	0.06 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.17 11-13	>999	240	Weight: 220 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2 \*Except\*  
2-15,7-9: 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-9-4 max.): 3-6.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 15=0-3-8, 9=0-3-8  
Max Horz 15=62(LC 7)  
Max Uplift 15=-453(LC 4), 9=-447(LC 4)  
Max Grav 15=1861(LC 1), 9=1905(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-3240/822, 3-4=-4923/1332, 4-5=-4753/1288, 5-6=-4756/1290, 6-7=-2807/726,  
2-15=-1815/468, 7-9=-1877/455  
BOT CHORD 14-15=-102/257, 13-14=-749/2942, 11-13=-1285/4920, 10-11=-612/2481  
WEBS 3-13=-590/2202, 4-13=-633/339, 5-11=-671/352, 6-11=-674/2488, 2-14=-674/2710,  
7-10=-612/2407

#### NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x3 - 1 row at 0-9-0 oc.  
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 15=453, 9=447.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT
400565	L1	Hip Girder	1	<b>2</b>	I42655474
					Job Reference (optional)

Wheeler Lumber,      Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc.   Tue Sep 1 10:54:34 2020   Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vu3VWxtZm3JF3o6H\_hnZ4cCwohjXL0bCvNrrMkyi0I3

NOTES-

11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 88 lb down and 81 lb up at 6-0-0, 88 lb down and 81 lb up at 8-0-0, 88 lb down and 81 lb up at 10-0-0, 88 lb down and 81 lb up at 12-0-0, 88 lb down and 81 lb up at 14-0-0, 88 lb down and 81 lb up at 16-0-0, 88 lb down and 81 lb up at 18-0-0, 88 lb down and 81 lb up at 20-0-0, and 88 lb down and 81 lb up at 22-0-0, and 80 lb down and 81 lb up at 24-0-12 on top chord, and 224 lb down and 106 lb up at 4-11-2, 32 lb down at 6-0-0, 32 lb down at 8-0-0, 32 lb down at 10-0-0, 32 lb down at 12-0-0, 32 lb down at 14-0-0, 32 lb down at 16-0-0, 32 lb down at 18-0-0, 32 lb down at 20-0-0, and 32 lb down at 22-0-0, and 217 lb down and 88 lb up at 24-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S)   Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
    Vert: 1-2=-70, 2-3=-70, 3-6=-70, 6-7=-70, 7-8=-70, 9-15=-20  
Concentrated Loads (lb)  
    Vert: 6=-48(F) 12=-22(F) 14=-224(F) 5=-48(F) 11=-22(F) 10=-217(F) 16=-48(F) 17=-48(F) 18=-48(F) 19=-48(F) 20=-48(F) 21=-48(F) 22=-48(F) 23=-48(F) 24=-22(F) 25=-22(F) 26=-22(F) 27=-22(F) 28=-22(F) 29=-22(F) 30=-22(F)

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655475
400565	L2	Half Hip	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:35 2020 Page 1  
ID:M6\_qRERj\_ax8BapGKEbrTSyOHsj-N5dtjGuBxMS6gyhUYPJodpk6n56o4T6L81aPuAyi0I2

0-10-8	7-3-14	12-8-14	18-4-6
0-10-8	7-3-14	5-5-0	5-7-8

Scale = 1:32.7




Plate Offsets (X,Y)--		[9:0-2-3,0-5-5]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc)		l/defl L/d		PLATES GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.66	Vert(LL)	-0.09 7-8	>999	360	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.52	Vert(CT)	-0.17 7-8	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.38	Horz(CT)	0.02 6	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.04 7-8	>999	240	Weight: 64 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF 2100F 1.8E \*Except\*  
3-5: 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-9: 2x8 SP DSS

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-10-10 oc purlins, except end verticals, and 2-0-0 oc purlins (5-6-2 max.): 3-5.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 6=Mechanical, 9=0-3-8  
Max Horz 9=123(LC 7)  
Max Uplift 6=41(LC 5), 9=-22(LC 4)  
Max Grav 6=805(LC 1), 9=893(LC 1)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1172/31, 3-4=-950/64, 4-5=-948/62, 5-6=-756/67, 2-9=-801/64  
BOT CHORD 8-9=-72/973, 7-8=-74/970  
WEBS 4-7=-474/103, 5-7=-57/1106

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 9.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655476
400565	L3	Roof Special	1	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:36 2020 Page 1

ID:M6\_qRERj\_ax8BapGKEbrTSyOHSj-rHBGxcvplgazi6Gg66q191HEQVTEptSVNhKyQdyi0l1

0-10-8	3-11-12	8-8-2	14-5-3	15-5-13	18-4-6
0-10-8	3-11-12	4-8-6	5-9-2	1-0-10	2-10-9

Scale = 1:33.4



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655477
400565	L4	Roof Special	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:37 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-KTle8yvR3\_iqwGrsfLGiEqM6vmCYKmebL3Vy3yi0I0

0-10-8	6-3-5	12-0-6	17-10-10	18-4-6
0-10-8	6-3-5	5-9-2	5-10-3	0-5-12

6x8 6.00 12 Scale = 1:39.6




Plate Offsets (X,Y)-- [5:0-2-12,0-2-4], [11:0-2-3,0-5-5]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.99	Vert(LL)	-0.13 9-10	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.65	Vert(CT)	-0.25 9-10	>867	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.56	Horz(CT)	0.02 8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.06 9-10	>999	240	Weight: 76 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2 \*Except\*  
4-5,5-7: 2x6 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-11: 2x8 SP DSS

#### BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-4-14 max.): 3-4, 5-6.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


(size) 8=Mechanical, 11=0-3-8  
Max Horz 11=189(LC 5)  
Max Uplift 8=47(LC 8), 11=41(LC 8)  
Max Grav 8=807(LC 1), 11=893(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1201/56, 3-4=-1118/48, 4-5=-1323/107, 2-11=-787/79  
BOT CHORD 10-11=-56/1010, 9-10=-58/1008  
WEBS 4-9=-919/130, 5-9=-98/1492, 5-8=-755/86

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 11.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1,2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. For additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655478
400565	L5	Roof Special Girder	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:38 2020 Page 2  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-ogJ0MIw3qHqhXQQ2DXsVF5MabJ42HiYnq?p3VVyi0l?

**LOAD CASE(S)** Standard

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-6=-70, 6-7=-70, 10-13=-20, 8-9=-20

Concentrated Loads (lb)

Vert: 3=-26(B) 12=-16(B) 14=-18(B) 15=-18(B) 16=-11(B) 17=-11(B) 18=-284(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:39 2020 Page 1  
ID:M6 qRERi ax8BApGKEbrTSvOHsi-GssQZexiabYX9a?FnENknfvm?iP?0J8x3eYc1xvi0l



- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDF=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 5.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655480
400565	LAY1	GABLE	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:40 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-k2Qmn\_yKLv4OnjaRLyuzKtS6q6xZloA4HIIAYOyi0kz

Job Reference (optional)



Scale = 1:48.6




Plate Offsets (X,Y)--	[4:0-1-10,Edge], [14:0-1-10,Edge]
-----------------------	-----------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.01	17	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 134 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6'-0-0 oc purlins, except 2'-0-0 oc purlins (6'-0-0 max.): 4'-14.  
BOT CHORD Rigid ceiling directly applied or 10'-0-0 oc bracing.

#### REACTIONS.

All bearings 29-3-10.  
(lb) - Max Horz 1=136(LC 4)  
Max Uplift All uplift 100 lb or less at joint(s) 1, 25, 26, 27, 28, 29, 30, 23, 22, 21, 20, 19 except 31=135(LC 8), 18=137(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 1, 17, 25, 26, 27, 28, 29, 30, 31, 23, 22, 21, 20, 19, 18

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-6-0 tall by 2'-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 25, 26, 27, 28, 29, 30, 23, 22, 21, 20, 19 except (it=lb) 31=135, 18=137.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655481
400565	LAY2	GABLE	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:41 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-CF\_9\_Kyy6CCFOt9dufPCs4\_9dWHzUEKEWy1j4qyi0ky



Scale = 1:49.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.57	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.14	Horz(CT)	-0.00	6	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 45 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
WEBS 1 Row at midpt 5-6

#### REACTIONS.

All bearings 7-2-11.  
(lb) - Max Horz 1=349(LC 5)  
Max Uplift All uplift 100 lb or less at joint(s) except 1=-216(LC 6), 6=-155(LC 7), 9=-154(LC 8), 8=-180(LC 8), 7=-160(LC 8)  
Max Grav All reactions 250 lb or less at joint(s) 6, 9, 8, 7 except 1=343(LC 5)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-435/315, 2-3=-353/253, 3-4=-283/194

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) All plates are 2x4 MT20 unless otherwise indicated.
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 216 lb uplift at joint 1, 155 lb uplift at joint 6, 154 lb uplift at joint 9, 180 lb uplift at joint 8 and 160 lb uplift at joint 7.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655482
400565	LAY3	GABLE	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:42 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-gRYXCgzaWK601kqSNxRPIXN4wdBDigNlcGdGyi0kx



Scale = 1:44.8

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.34	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	-0.00	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 32 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-7-10 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


All bearings 5-7-10.  
(lb) - Max Horz 1=271(LC 5)  
Max Uplift All uplift 100 lb or less at joint(s) except 1=-142(LC 6), 5=-122(LC 7), 7=-186(LC 8), 6=-162(LC 8)  
Max Grav All reactions 250 lb or less at joint(s) 5, 7, 6 except 1=256(LC 5)

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-325/241

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 142 lb uplift at joint 1, 122 lb uplift at joint 5, 186 lb uplift at joint 7 and 162 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020


**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Wheeler Lumber, Waverly, KS 66871 8.420 s Aug 25 2020 MITek Industries, Inc. Tue Sep 1 10:54:42 2020 Page 1  
ID:M6\_gRERj\_ax8BApGKEbrTSyOHsj-gRYXCgzatWK601kgSNxRPiXsXwdADiKNlcnGdGyi0kx




<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS	2x4 SPF No.2		

**REACTIONS.** All bearings 7-0-4.  
(lb) - Max Horz =187(LC 5)  
Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8=-117(LC 8), 6=-141(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7, 8, 6

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BC DL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=117, 6=141.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 400565	Truss LAY5	Truss Type GABLE	Qty 1	Ply 1	Lot 21 HT Job Reference (optional)	I42655484
---------------	---------------	---------------------	----------	----------	---------------------------------------	-----------

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:43 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-8d6vP?\_CeqSzeBI004SgyV4ciKz8y9gW\_GWq9ji0kw



Scale = 1:39.8

Plate Offsets (X,Y)--		[3:0-1-10,Edge], [9:0-2-14,Edge]	
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09
TCDL 10.0	Lumber DOL	1.15	BC 0.04
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.09
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S
			<b>DEFL.</b>
			in (loc) l/defl L/d
			Vert(LL) n/a - n/a 999
			Vert(CT) n/a - n/a 999
			Horz(CT) 0.00 12 n/a n/a
			<b>PLATES</b>
			MT20
			<b>GRIP</b>
			197/144
			Weight: 81 lb FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-7.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

All bearings 18-11-3.  
(lb) - Max Horz 1=172(LC 5)  
Max Uplift All uplift 100 lb or less at joint(s) 1, 12, 19, 18, 17, 16 except 20=145(LC 8), 14=144(LC 9), 13=137(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 1, 12, 19, 18, 17, 16, 15, 14, 13 except 20=272(LC 15)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 12, 19, 18, 17, 16 except (jt=lb) 20=145, 14=144, 13=137.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655485
400565	LAY6	GABLE	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:44 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-cqgHcL?qp7aqFLtCaozvUjcosjJPhdkgCwGNh9yi0kv



Scale = 1:29.5

Plate Offsets (X,Y)-- [4:0-1-10,Edge]									
<b>LOADING</b> (psf)		<b>SPACING-</b>	2-0-0	<b>CSI.</b>		<b>DEFL.</b>	in (loc)	L/defl	L/d
TCLL 25.0		Plate Grip DOL	1.15	TC 0.06		Vert(LL)	n/a	-	n/a
TCDL 10.0		Lumber DOL	1.15	BC 0.04		Vert(CT)	n/a	-	n/a
BCLL 0.0 *		Rep Stress Incr	YES	WB 0.03		Horz(CT)	-0.00	7	n/a
BCDL 10.0		Code IRC2018/TPI2014		Matrix-S					
						<b>PLATES</b>	<b>GRIP</b>		
						MT20	197/144		
						Weight: 40 lb	FT = 10%		

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-7.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

All bearings 10-10-2.  
(lb) - Max Horz 1=190(LC 8)  
Max Uplift All uplift 100 lb or less at joint(s) 1, 7, 10, 11, 9, 8 except 12=122(LC 8)  
Max Grav All reactions 250 lb or less at joint(s) 1, 7, 10, 12, 11, 9, 8

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 7, 10, 11, 9, 8 except (jt=lb) 12=122.
- Non Standard bearing condition. Review required.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017




Plate Offsets (X,Y)-- [6:0-2-14,Edge], [7:0-2-4,0-1-8]												
<b>LOADING</b> (psf)		<b>SPACING-</b> 2-0-0		<b>CSI.</b>		<b>DEFL.</b> in (loc) l/defl L/d				<b>PLATES</b> <b>GRIP</b>		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.05	Horz(CT)	-0.00	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 51 lb	FT = 10%

LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD	2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS	2x4 SPF No.2		

**REACTIONS.** All bearings 11-7-10.  
(lb) - Max Horz 1=291(LC 8)  
Max Uplift All uplift 100 lb or less at joint(s) 1, 11, 13 except 7=101(LC 8), 9=108(LC 8), 10=110(LC 8),  
12=108(LC 8)  
Max Grav All reactions 250 lb or less at joint(s) 1, 7, 11, 8, 9, 10, 12, 13

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
**TOP CHORD** 1-2=-333/151. 2-3=-250/123

**NOTES-**

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDF=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 11, 13 except (jt=lb) 7=101, 9=108, 10=110, 12=108.
- 8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 7, 8, 9, 10.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

 **WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 26720 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655487
400565	LAY9	GABLE	1	1	Job Reference (optional)	


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:46 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-ZCn21105xlqYVe1bhC?NZ8i8LX\_19VhzgEIUm1yi0kt



4x5 =

Scale = 1:38.1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.00	7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 45 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
OTHERS 2x4 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

All bearings 10-0-14.  
(lb) - Max Horz 1=173(LC 5)  
Max Uplift All uplift 100 lb or less at joint(s) except 1=124(LC 6), 7=-101(LC 7), 11=-185(LC 8), 12=-141(LC 8), 9=-185(LC 9), 8=-142(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 1, 7, 10, 11, 12, 9, 8

#### FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-271/169, 6-7=-253/141

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 124 lb uplift at joint 1, 101 lb uplift at joint 7, 185 lb uplift at joint 11, 141 lb uplift at joint 12, 185 lb uplift at joint 9 and 142 lb uplift at joint 8.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655488
400565	M1	Hip Girder	1	1		
Job Reference (optional)						

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:48 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-VbvoSj2LTM4GkyBzpd1rfZnLFLXadOTG7YEBqwyi0kr

-0-10-8	2-6-5	9-8-12	11-8-0	12-6-8
0-10-8	2-6-5	7-2-7	1-11-4	0-10-8

Scale = 1:22.2




Plate Offsets (X,Y)--		[3:0-3-8,0-2-5], [4:0-3-8,0-2-3], [7:0-3-8,Edge]							
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.10 8-9 >999	360	MT20 197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.60	Vert(CT)	-0.22 8-9 >610	240	M18SHS 197/144
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.18	Horz(CT)	0.01 7 n/a	n/a	
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S		Wind(LL)	0.08 8-9 >999	240	Weight: 39 lb FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2 \*Except\*  
3-4: 2x4 SPF 2100F 1.8E  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-10: 2x4 SPF 2400F 2.0E, 5-7: 2x4 SPF 2100F 1.8E

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-8-5 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 10=0-3-8, 7=0-3-8  
Max Horz 10=49(LC 7)  
Max Uplift 10=-161(LC 4), 7=-141(LC 9)  
Max Grav 10=581(LC 1), 7=581(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-759/199, 3-4=-551/160, 4-5=-667/158, 2-10=-476/121, 5-7=-467/96  
BOT CHORD 9-10=-186/659, 8-9=-193/658, 7-8=-132/551

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 161 lb uplift at joint 10 and 141 lb uplift at joint 7.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 103 lb down and 132 lb up at 2-6-5, 56 lb down and 37 lb up at 4-7-1, 56 lb down and 37 lb up at 6-5-7, and 56 lb down and 37 lb up at 7-8-0, and 91 lb down and 107 lb up at 9-8-12 on top chord, and 14 lb down and 5 lb up at 2-6-5, 10 lb down and 0 lb up at 4-7-1, 10 lb down and 0 lb up at 6-5-7, and 10 lb down and 0 lb up at 7-8-0, and 14 lb down and 4 lb up at 9-8-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard



September 1, 2020

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT
400565	M1	Hip Girder	1	1	I42655488
Job Reference (optional)					

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-5=-70, 5-6=-70, 7-10=-20

Concentrated Loads (lb)


Vert: 9=2(B) 8=1(B) 14=0(B) 15=0(B) 16=0(B)

Wheeler Lumber, Waverly, KS 66871 8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:48 2020 Page 1

ID:M6\_qRERj\_ax8BAPGKEbrTSyOHsj-VbvoSj2LTM4GkyBzpd1rfZnN9LaldQLG7YEqbwyiOk

0-10-8 4-11-2 11-8-0 12-6-8  
0-10-8 4-11-2 2-9-10 3-11-4 0-10-8


Scale = 1:22.3



**REACTIONS.** (size) 10=0-3-8, 7=0-3-8  
Max Horz 10=63(LC 7)  
Max Uplift 10=-82(LC 8), 7=-71(LC 9)  
Max Grav 10=583(LC 1), 7=583(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-657/74, 3-4=-460/79, 4-5=-602/72, 2-10=-508/114, 5-7=-497/98  
BOT CHORD 9-10=-38/533, 8-9=-40/530, 7-8=-10/463

- 
- A circular professional engineer seal for the State of Missouri. The outer ring contains the text "STATE OF MISSOURI" at the top and "PROFESSIONAL ENGINEER" at the bottom, separated by two stars. In the center, the name "JUAN GARCIA" is displayed above the number "E-2000162101". The seal is blue and white.



September 1, 2020

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655490
400565	M3	Roof Special	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:49 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-znTAg33zEgC7M6mAMLZ4BmKXrkxGMsTPMCz8NMyi0kq

5x7

Scale = 1:21.0




Plate Offsets (X,Y)-- [2:0-4-11,0-2-8], [3:0-3-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.56	Vert(LL)	-0.05	5-6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.38	Vert(CT)	-0.11	5-6	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.01	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.03	5-6	>999	240	Weight: 32 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2 \*Except\*  
2-5: 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.


(size) 6=0-3-8, 4=0-3-8  
Max Horz 6=68(LC 5)  
Max Uplift 6=68(LC 8), 4=58(LC 9)  
Max Grav 6=512(LC 1), 4=512(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-588/77, 2-3=-599/92, 1-6=-429/108, 3-4=-426/88  
BOT CHORD 5-6=-26/458, 4-5=-28/456

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 68 lb uplift at joint 6 and 58 lb uplift at joint 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655491
400565	V1	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:50 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Rz1YtP3b?zK\_GLMw24Jk\_siR8le5KkYbsjvpyi0kp



Scale = 1:16.4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.57	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.31	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 15 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-3-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=6-2-6, 3=6-2-6  
Max Horz 1=99(LC 5)  
Max Uplift 1=35(LC 8), 3=55(LC 8)  
Max Grav 1=243(LC 1), 3=243(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 35 lb uplift at joint 1 and 55 lb uplift at joint 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655492
400565	V2	Valley	1	1	Job Reference (optional)	


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:51 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vAbx4I4DmHTqbQwYUmbYGBPzRYhGqn\_ipWSFRFyi0ko

3-11-2  
3-11-2

Scale = 1:10.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.17	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.09	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-11-2 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=3-10-8, 3=3-10-8  
Max Horz 1=56(LC 5)  
Max Uplift 1=20(LC 8), 3=31(LC 8)  
Max Grav 1=138(LC 1), 3=138(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 20 lb uplift at joint 1 and 31 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655494
400565	V5	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:53 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-sYjhVQ6UHujYrj3xbBd0McUFsMK6lgC?HqxMW7yi0km



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.36	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.08	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 28 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=10-1-0, 4=10-1-0, 5=10-1-0  
Max Horz 1=169(LC 5)  
Max Uplift 1=-2(LC 8), 4=-23(LC 5), 5=-140(LC 8)  
Max Grav 1=195(LC 1), 4=110(LC 1), 5=529(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-5=-400/196

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2 lb uplift at joint 1, 23 lb uplift at joint 4 and 140 lb uplift at joint 5.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655495
400565	V6	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:53 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOhsj-sYjhVQ6UHujYrj3xbBd0McUHPMMXIhd?HqxMW7yi0km

7-8-13  
7-8-13



Scale = 1:20.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.20	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 20 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=7-8-3, 4=7-8-3, 5=7-8-3  
Max Horz 1=126(LC 5)  
Max Uplift 4=-25(LC 8), 5=-104(LC 8)  
Max Grav 1=89(LC 16), 4=140(LC 1), 5=392(LC 1)

#### FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-5=-305/157

#### NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 25 lb uplift at joint 4 and 104 lb uplift at joint 5.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655496
400565	V7	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:54 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-KIG3jm762CrPSte79u8Fuq1UfljV18k8VUhv2ayi0kl



Scale = 1:9.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.10	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 8 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-4-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=3-3-6, 3=3-3-6  
Max Horz 1=46(LC 5)  
Max Uplift 1=-16(LC 8), 3=-25(LC 8)  
Max Grav 1=111(LC 1), 3=111(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 16 lb uplift at joint 1 and 25 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655497
400565	V8	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:54 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-KIG3jm762CrPSte79u8Fuq1Thli\_18k8VUhv2ayi0kl



Scale = 1:12.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.17	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.09	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 9 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-9-8 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=3-9-0, 3=3-9-0  
Max Horz 1=64(LC 5)  
Max Uplift 1=-18(LC 8), 3=-34(LC 8)  
Max Grav 1=138(LC 1), 3=138(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 1 and 34 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655498
400565	V9	Valley	1	1		

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:55 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHSj-oxqRw67kpWzG41DKjbfUR1ZdC92DmbRIk8QSa0yi0kk



Scale = 1:11.8



0-0-8		2-5-8		6-1-14						
0-0-8		2-5-0		3-8-6						
<b>LOADING</b> (psf)		<b>SPACING-</b>	2-0-0	<b>CSI.</b>					<b>PLATES</b>	<b>GRIP</b>
TCLL	25.0	Plate Grip DOL	1.15	TC	0.25				MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.09					
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.04					
BCDL	10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 14 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-1-14 oc purlins, except end verticals, and 2-0-0 oc purlins: 2-3.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

#### REACTIONS.

(size) 1=6-1-6, 4=6-1-6, 5=6-1-6  
Max Horz 1=32(LC 5)  
Max Uplift 1=18(LC 8), 4=34(LC 4), 5=29(LC 5)  
Max Grav 1=55(LC 1), 4=156(LC 1), 5=277(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 1, 34 lb uplift at joint 4 and 29 lb uplift at joint 5.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655499
400565	V10	Valley	1	1	Job Reference (optional)	

Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:50 2020 Page 1  
ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-Rz1YtP3b?zK\_GLMw24Jk\_sqN8M35KOYbsjvpyi0kp



Scale = 1:8.8

LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	MT20		197/144	
BCDL	10.0	Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a				
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00				
BCDL	10.0	Code IRC2018/TPI2014		Matrix-P							
								Weight: 10 lb		FT = 10%	

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-1-14 oc purlins, except end verticals, and 2-0-0 oc purlins: 2-3.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.


#### REACTIONS.

(size) 1=4-1-6, 4=4-1-6, 5=4-1-6  
Max Horz 1=32(LC 5)  
Max Uplift 1=12(LC 8), 4=16(LC 4), 5=19(LC 5)  
Max Grav 1=70(LC 1), 4=68(LC 1), 5=170(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 12 lb uplift at joint 1, 16 lb uplift at joint 4 and 19 lb uplift at joint 5.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 21 HT	I42655500
400565	V11	Valley	1	1		
Job Reference (optional)						


Wheeler Lumber, Waverly, KS 66871

8.420 s Aug 25 2020 MiTek Industries, Inc. Tue Sep 1 10:54:51 2020 Page 1

ID:M6\_qRERj\_ax8BApGKEbrTSyOHsj-vAbx4l4DmHTqbQwYUmbYGBP?YYiPqn\_ipWSFRFyi0ko

2-1-14  
2-1-14

Scale = 1:8.2



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.03	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 5 lb	FT = 10%

#### LUMBER-

TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

#### BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-1-14 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS.

(size) 1=2-1-6, 3=2-1-6  
Max Horz 1=30(LC 5)  
Max Uplift 1=8(LC 8), 3=16(LC 8)  
Max Grav 1=64(LC 1), 3=64(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

#### NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 8 lb uplift at joint 1 and 16 lb uplift at joint 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



September 1, 2020

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017





## General Safety Notes

21. The design does not take into account any dynamic or other loads other than those expressly stated.