




PLANS AND CONSTRUCTION TO BE IN ACCORDANCE WITH 2018 IRC AS ADOPTED BY THE CITY OF LEE'S SUMMIT, MO



MIN. 36" BELOW GRADE

1213 NE Goshen Dr LEE'S SUMMIT, MO

ELEVATIONS



PANAL SIDING FRONT RETURNS SIDES AND BACK, LP PRECISION PANEL SIDING 7/16" MUST BE INSTALLED WITH ITS LONG DIMISION ORIENTED VERTICALLY.

FASTENER SPACING (INCHES O.C.) 6" EDGES AND 12" IN

FASTER PENETRATION INTO STUD MIN, 1-1/2"

FASTENER MUST HAVE A MINIMUM HEAD DIAMETER OF 0.297 INCH, A MINIMUM SHAFT DIAMETER OF 0.113 INCH AND A MINIMUM I FNGTH OF 2-1/2" INCHES

OSB 7/16" UNDER STUCCO AND STONE ON FRONT


FASTENER SPACING ( INCHES O.C. ) 6" EDGES AND 12" IN THE FIELD

FASTER PENETRATION INTO STUD MIN. 1-1/2"


FASTENER MUST HAVE A MINIMUM HEAD DIAMETER OF 0.297 INCH, A MINIMUM SHAFT DIAMETER OF 0.113 INCH AND A MINIMUM LENGTH OF 2-1/2" INCHES



BACK





RIGHT SIDE



LEFT SIDE

1213 NE Goshen Dr LEE'S SUMMIT, MO










PAGE





se plans are drawn to comply with owner's and/ or builder's gen and specifications. The builder is solely responsible and ef or the content and originality of these plans. Any changes the on them after prints are made will be done at the owner's / or builder's expense and responsibility. The contractor Il verify all dimensions and enclosed drawing. The maker of se plans is not an architect or engineer and is not liable for rs and originality once construction has begun. While it has been made in the preparation of this plan to aleas, the maker can not guarantee against hun, aleas and originality or construction and be solely responsite the page.

AND VERIFY ALL DIMENSIONS,
D CONNECTIONS BEFORE
TION BEGINS.
L SYSTEM CODE: SEC.2701
AL SYSTEM CODE: SEC.2801

PAGE 3


PLAN: 11-19-19


SCALE: 1/4" = 1'-0"

BASEMENT

MC-76







Dave Richards Homebuilding, Inc.

ROOF

EXPOSURE CATEGORY B 30 FOOT MEAN ROOF HEIGHT 10 FOOT EAVE-TO-RIDGE HEIGHT 10 FOOT WALL HEIGHT 2 BRACED WALL LINES		MINIMUM TOTAL LENGTH (FEET) OF BRACED WALL PANELS REQUIRED ALONG EACH BRACED WALL LINE®				
Basic Wind Speed (mph)	Story Location	Braced Wall Line Spacing (feet)	Method LIB <sup>b</sup>	Method GB	Methods DWB, WSP, SFB, PBS, PCP, HPS, CS-SFB°	Methods CS-WSP, CS-G CS-PF
		10	3.5	3.5	2.0	2.0
	^	20	7.0	7.0	4.0	3.5
	人 🗎	30	9.5	9.5	5.5	5.0
		40	12.5	12.5	7.5	6.0
	台 日 日	50	15.5	15.5	9.0	7.5
		60	18.5	18.5	10.5	9.0
		10	7.0	7.0	4.0	3.5
		20	13.0	13.0	7.5	6.5
≤ 90		30	18.5	18.5	10.5	9.0
		40	24.0	24.0	14.0	12.0
		50	29.5	29.5	17.0	14.5
		60	35.0	35.0	20.0	17.0
		10	NP	10.5	6.0	5.0
	$\rightarrow$	20	NP	19.0	11.0	9.5
		30	NP	27.5	15.5	13.5
	H	40	NP	35.5	20.5	17.5
	100	50	NP	44.0	25.0	21.5
	1	60	NP	52.0	30.0	25.5

		PANEL LENGTH PER TABLE R602 10.5	
		<del>                                      </del>	
田岡田	MIN. 38" WOOD STRUCTURAL PANEL SHEATHING ON ONE FACE		FOR PANEL SPLICE (IF NEEDED) ADJOINING PANEL EDGES SHALL MEET OVER AND BE FASTENED TO COMMON FRAMING
BRACED WALL PANEL HEIGHT	MIN. 2X4 FRAMING MIN. DOUBLE STUDS REQUIRED.		8D COMMON OR GALV. BOX NAILS @ 6" O.C. AT PANIEL EDGES. FOR SINGLE STORY AND @ 4" O.C. PANIEL EDGES FOR THE FIRST OF 2 STORIES
BRACEL	(2) HOLD-DOWN OR (2) STRAP-TYPE — ANCHORS PER TABLE R602 10.6.1 (ONE) OF EACH SHOWN FOR CLARITY). STRAP-TYPE ANCHORS SHALL BE PERMITTED TO BE ATTACHED OVER		STUDS UNDER HEADER AS REQUIRED
	THE WOOD STRUCTURAL PANEL  PANEL MUST BE ATTACHED TO CONCRETE FOOTING OR		8D COMMON OR GALV. BOX NAILS @ 12" O.C. AT INTERIOR SUPPORTS
	CONCRETE FOUNDATION WALL CONTINUOUS OVER BRACED WALL LINE		MIN. REINFORCING OF FOUNDATION, ONE #4 BAR TOP AND BOTTOM. LAP BARS 15" MINIMUM.
	(2) 1/2" DIAMETER ANCHOR BOLTS LOCATED BETWEEN 6" AND 12" OF EACH END OF THE SEGMENT		MINIMUM FOOTING SIZE UNDER OPENING IS 12" X 12". A TURNED-DOWN SLAB SHALL BE PERMITTED AT DOOR OPENINGS.
For SI: 1 inch = $25.4$ mm.			

FIGURE R602.10.6.1




FIGURE R602.10.6.2 METHOD PFH—PORTAL FRAME WITH HOLD-DOWNS

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

170

TABLE R602.10.4 BRACING METHODS CONNECTION CRITERIA METHODS MATERIAL Spacing Fasteners ood: per stud and Wood: 2-8d common nails  $1 \times 4$  wood or

p and bottom plates approved metal straps t 45° to 60° angles fo maximum 16" 3-8d (21/2" long x 0.113" dia.) nails Metal strap: per manufacturer per manufacturer stud spacing  $2-8d (2^{1}/_{2}" long \times 0.113" dia.)$  nails Per stud maximum 24° 2 - 13/4" long staples stud spacing Exterior sheathing per WSP Wood 6" edges 12" field Table R602.3(3) 3/8" structural panel (See Section R604 Interior sheathing per Table R602.3(1) or R602.3(2) Varies by fastener BV-WSP<sup>e</sup> at panel edges Wood Structura Panels with Stone See Figure R602.10.6.5 8d common  $(2^{1}/_{2}" \times 0.131)$  nails 7/16" supports 4" at braced wall panel end posts r Masonry Vene (See Section R602.10.6.5)  $1^{1}/_{2}$ " long × 0.12" dia. (for  $1^{1}/_{2}$ " thick 1/2" or 25/32" for maximum 16" stud spacing sheathing)  $1^3/4''$  long × 0.12" dia. (for  $2^2/32''$  thick sheathing) Structural 3" edges 6" field Ivanized roofing nails or 8d comm  $(2^1/_2" \log \times 0.131" \text{ dia.})$  nails erboard sheath ils or screws per Table R602.3(1) for For all braced wall panel locations: 7" edges (including top 1/2" Nails or screws per Table R702.3.5 for and bottom plates) 7 Gypsum board For 3/8", 6d common  $\frac{3}{8}$ " or  $\frac{1}{2}$ " for (2" long × 0.113" dia.) nails For 1/2", 8d common (21/2" long × 0.131" dia.) nails 3" edges 6" field sheathing stud spacing

/2" long, 11 gage, 7/16" dia. head nails

092" dia., 0.225" dia. head nails with

7/8" long, 16 gage staples

length to accommodate 11/2"
penetration into studs

See Section R602.10.6.1

6" o.c. on all framing

4" edges 8" field

Section R602.10.6.1

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

TABLE R602.10.4—continued BRACING METHODS CONNECTION CRITERIA MINIMUM THICKNESS METHODS, MATERIAL Spacing **Fasteners** See Section R602.10.6.2 3/8" See Section R602.10.6.2 Portal frame with hold-downs See Section R602.10.6.3 7/16" See Section R602.10.6.3 Portal frame at garage Exterior sheathing per 6" edges 12" field Table R602.3(3) ontinuously sheathed Interior sheathing per Varies by fastener wood structural panel Table R602.3(1) or R602.3(2) CS-Gb, c inuously sheathe See Method CS-WSP See Method CS-WSP wood structural panel adjacent to garage openings CS-PF See Section R602.10.6.4 See Section R602.10.6.4 7/16" tinuously sheathed portal frame  $1^{1}/_{2}$ " long × 0.12" dia. (for  $1/_{2}$ " thick sheathing)  $1^{3}/_{4}$ " long × 0.12" dia. (for  $^{25}/_{32}$ " thick sheathing) CS-SFB<sup>d</sup> 3" edges 6" field Continuously sheathed structural fiberboard stud spacing galvanized roofing nails or 8d common  $(2^{1}/_{2}" \log \times 0.131" \text{ dia.}) \text{ nails}$ 

For SI: 1 inch = 25.4 mm, 1 foot = 305 mm, 1 degree = 0.0175 rad, 1 pound per square foot = 47.8 N/m<sup>2</sup>, 1 mile per hour = 0.447 m/s.

a. Adhesive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Categories C, D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>.

b. Applies to panels next to garage door opening when supporting gable end wall or roof load only. May only be used on one wall of the garage. In Seismic Design Categories D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>, roof covering dead load may not exceed 3 psf.

c. Garage openings adjacent to a Method CS-G panel shall be provided with a header in accordance with Table R502.5(1). A full height clear opening shall not be permitted adjacent to a Method CS-G panel.

d. Method CS-SFB does not apply in Scismic Design Categories D<sub>to</sub>, D<sub>1</sub> and D<sub>2</sub> and in areas where the wind speed exceeds 100 mph.

TABLE R602.10.5
MINIMUM LENGTH OF BRACED WALL PANELS MINIMUM LENGTH CONTRIBUTING LENGTH Wall Height (See Table R602.10.4) 8 feet 9 feet 10 feet 11 feet 12 feet 48 53 58 Actual<sup>b</sup> 48 48 DWB, WSP, SFB, PBS, PCP, HPS, BV-WSP Double sided = Actual 53 58 48 48 GB Single sided =  $0.5 \times Actual$ NP NP Actual<sup>b</sup> 69 LIB 55 62 SDC A, B and C, 42 38 32 34 wind speed < 110 mph ABW SDC Do, D, and D2, NP NP 34 wind speed < 110 mph 48 16 18° 20° Supporting roof only PFH 48 Supporting one story and roof 24 24 24 27° 1.5 x Actual<sup>b</sup> 33<sup>d</sup> 36<sup>d</sup> 27 30 Actual<sup>b</sup> 27 | 30 | 33 | 36 CS-G Actual<sup>b</sup> 18 20 22c 24e CS-PF Adjacent clear opening height (inches) 24 | 27 | 30 | 33 | 36 ≤ 64 30 33 36 27 68 30 33 | 36 72 27 33 36 30 76 30 29 30 30 33 | 36 80 32 84 35 | 32 | 32 | 33 | 33 33 36 88 38 | 35 92 37 | 35 | 35 48 41 38 36 40 38 38 CS-WSP, CS-SFB 44 100 Actual<sup>b</sup> 49 43 40 39 104 54 46 43 41 108 50 45 | 43 112 55 48 45 116 ---60 52 48 120 56 51 124 61 54 128 66 58 132 62 136 66 140 72 144

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s.

NP = Not Permitted.

2012 INTERNATIONAL RESIDENTIAL

PCP

Portland

Hardboard

panel siding

ABW

braced wall

Section R703.6 fo

maximum 16"

stud spacing

" for maximum 16

stud spacing

3/8"

a. Linear interpolation shall be permitted.

b. Use the actual length when it is greater than or equal to the minimum length.

c. Maximum header height for PFH is 10 feet in accordance with Figure R602.10.6.2, but wall height may be increased to 12 feet with pony wall.

d. Maximum opening height for PFG is 10 feet in accordance with Figure R602.10.6.3, but wall height may be increased to 12 feet with pony wall.

—EXTENT OF HEADER WITH DOUBLE PORTAL FRAMES (TWO BRACED WALL PANELS) — EXTENT OF HEADER WITH SINGLE PORTAL FRAME (ONE BRACED WALL PANEL) 2'-18' FINISHED WIDTH OF OPENING FOR SINGLE OR DOUBLE PORTAL TENSION STRAP PER TABLE 602 10.6.4 (ON OPPOSITE SIDE OF SHEATHING) -PONY WALL HEIGHT MIN, 3"X 11-1/4" NET HEADER RRACED WALLLINE CONTINUOUSLY SHEATHED WITH WOOD STRUCTURAL STEEL HEADER PROHIBITED PANELS FASTEN SHEATHING TO HEADER WITH 8D HEADER WITH TWO COMMON OR GALVANIZED BOX NAILS IN 3"GRID ROWS OF 160 SINKER NAILS AT 3" O.C. TYP. IF NEEDED PANEL SPLICE EDGES SHALL PATTERN AS SHOWN HEADER TO JACK-STUD STRAP PER TABLE -OCCUR AND BE ATTACHED TO R602 10.6.4 ON BOTH SIDES OF OPENING OPPOSITE SIDE OF SHEATHING COMMON BLOCKING WITHIN 24" OF WALL MID-HEIGHT, ONE ROW OF 3"O.C. NAILING IS MIN. DOUBLE 2X4 FRAMING COVERED WITH MIN STRUCTURAL PANEL 7/16" THICK WOOD STRUCTURAL PANEL REQUIRED IN EACH SHEATHING SHEATHING WITH 8D COMMON OR GALVANIZED OX NAILS AT 3"O.C. IN ALL FRAMING (STUDS, BLOCKING, AND SILLS) TYP. FRAME CONSTRUCTIO MIN. LENGTH OF PANEL PER TABLE R602.10.5 MIN. (2) 1/2" DIAMETER ANCHOR BOLTS (KING AND JACK STUD). INSTALLED PER R403.1.6 WITH 2'x2'x3/16" PLATE NUMBER OF JACK WASHER STUDS PER TABLES R502.5(1) & (2). 4 . 3 . 3 ANCHOR BOLTS PER OVER CONCRETE OR MASONRY BLOCK FOUNDATION SECTION R403.1.8 (2) FRAMING ANCHORS SHEATHING TO TOP OF BAND OR RIM JOIST TABLE R602.3(1) APPLIED ACROSS SHEATHING JOINT WITH A NAIL SOLE PLATE TO JOIST PER TABLE THE HORIZON TAL AND R602.3(1) VERTICAL DIRECTIONS WOOD STRUCTURAL PANEL SHEATHING OVER APPROVED BAND OR RIM JOIST OR RIMJOIST OVER RAISED WOOD FLOOR - FRAMING ANCHOR OPTION (WHEN PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST) WOOD STRUCTURAL NAIL SOLE NAIL SOLE PLATE ATTACH SHEATHING TO -PANEL SHEATHING PLATE TO JOIST BAND OR RIM JOIST WITH 8D COMMON NAILS AT 3" TO JOIST PER CONTINUOUS OVER BAND PER TABLE TABLE R602.3(1) OR RIMJOIST R602.3(1) O.C. TOP AND BOTTOM 0.04.00.04.2 WOOD STRUCTURAL PANEL SHEATHING OVER APPROVED BAND OR RIM JOIST OR RIMJOIST OVER RAISED WOOD FLOOR - OVERLAP OPTION (WHEN PORTAL SHEATHING LAPS OVER BAND OR RIM BOARD) OF MIS FRONT ELEVATION 900 DEPTH PARE

FIGURE R602.10.6.4

METHOD CS-PF—CONTINUOUSLY SHEATHED PORTAL FRAME

1213 NE Goshen Dr LEE'S SUMMIT, MO

ARIGHOSTIS

9

BRA

S S SCALE: 1/4" TAIL 

Dave Richards Homebuilding,