

**DEVELOPMENT SERVICES**

**PLAN REVIEW CONDITIONS**

August 06, 2020

LYTLE CONSTRUCTION INC  
1100 SE HAMBLER RD  
LEES SUMMIT, MO 64081

Permit No: PRCOM20202038  
Project Title: SAINT LUKES EAST - MRI REPLACEMENT  
Project Address: 80 NE SAINT LUKES BLVD, LEES SUMMIT, MO 64086  
Parcel Number: 52440044000000000  
Location: SAINT LUKES HOSPITAL OF LEES SUMMIT LOTS 1 & 2---LOT 1  
Type of Work: ALTERATION COMMERCIAL  
Occupancy Group: BUSINESS  
Description: MRI REPLACEMENT

***The following is a list of requirements from the City of Lee's Summit that have not been satisfactorily addressed in the plans and specifications. Please contact the appropriate department regarding clarification of comments.***

Development Services Department (816) 969-1200

Fire Department (816) 969-1300

**Fire Plan Review**

**Reviewed By: Michael Weissenbach**

**Approved with Conditions**

1. 2018 IFC 907.1.1- Construction documents. Construction documents for fire alarm systems shall be submitted for review and approval prior to system installation. Construction documents shall include, but not be limited to, all of the following: 1. A floor plan which indicates the use of all rooms. 2. Locations of alarm-initiating and notification appliances. 3. Alarm control and trouble signaling equipment. 4. Annunciation. 5. Power connection. 6. Battery calculations. 7. Conductor type and sizes. 8. Voltage drop calculations. 9. Manufacturers, model numbers and listing information for equipment, devices and materials. 10. Details of ceiling height and construction. 11. The interface of fire safety control functions.

(Informational Purposes)

Any modifications to the fire alarm system, provide PE stamped electronic shop drawings to [mike.weissenbach@cityofls.net](mailto:mike.weissenbach@cityofls.net)

2. 2018 IFC 901.2- Construction documents. The fire code official shall have the authority to require construction documents and calculations for all fire protection systems and to require permits be issued for the installation, rehabilitation or modification of any fire protection system. Construction documents for fire protection systems shall be submitted for review and approval prior to system installation.

(Informational Purposes)

Any modifications to the fire sprinkler system, provide PE stamped electronic shop drawings to [mike.weissenbach@cityofls.net](mailto:mike.weissenbach@cityofls.net)

3. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)

Call (816)969-1300 to schedule testing

4. (Verified At Inspection)

Provide a non-ferrous fire extinguisher in the existing fire extinguisher cabinet.

**Building Plan Review**

**Reviewed By: Joe Frogge**

**Approved**

**Licensed Contractors**

**Reviewed By: Joe Frogge**

**Approved**

\_\_\_\_\_ Approved to issue per the listed conditions.

\_\_\_\_\_ Do not issue per the listed conditions.

\_\_\_\_\_ Approved to construct foundation only per the listed conditions.

\_\_\_\_\_ Requires Final Development Plan approval prior to issuing this building permit.

The applicant agrees to incorporate the aforementioned requirements into the project to conform to applicable City Codes and Ordinances.

\_\_\_\_\_  
Signature of Applicant

\_\_\_\_\_  
Date

\_\_\_\_\_  
Print Applicant Name

\_\_\_\_\_  
CompanyName

***The approval of plans and specifications does not permit the violation of any section of the Building Codes or other City Ordinances or State Law.***

***The review conducted by the City of Lee's Summit Development Services Department shall not be construed as a structural review of the project.***