



LEFT ELEVATION

SCALE: 1/8" = 1'-0"



REAR ELEVATION

SCALE: 1/8" = 1'-0"




RIGHT ELEVATION

SCALE: 1/8" = 1'-0"



FRONT ELEVATION

SCALE: 1/4" = 1'-0"



DISCLAIMER  
ACTUAL PLANS AND ELEVATIONS MAY VARY  
FROM ARCHITECTURAL DRAWINGS.  
DUE TO TERRAIN/BACKFILL PROCESS.  
FRONT ELEVATIONS ARE ARCHITECTURAL  
DRAWINGS AND MAY VARY DUE TO  
MATERIAL AVAILABILITY.

NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010


Residential Builder Resource, LLC  
Custom Home Drafting & Design Service  
Kansas City Metro  
Rural Missouri & Eastern Kansas  
Ph. (816) 472-5072

The Brooklyn  
Lot 3 Whispering Woods  
1920 SW River Run Dr.  
Lee's Summit, MO 64082  
© Copyright 2020

DRAWN BY: RBR


CHECKED BY: CA

DATE: 10-29-20



PROJ. #20-090





LOWER LEVEL PLAN  
SCALE: 1/4" = 1'-0"

SUSPENDED SLAB NOTES:  
- 4000 PSI CONCRETE  
- GRADE 40 REBAR  
- LAP SPLICES MIN 24"  
- NO POINT LOADS ON  
SUSPENDED SLAB

SUSPENDED PORCH STOOP  
SCALE: 1/4" = 1'-0"

BRACED WALL METHODOLOGY  
CONTINUOUS EXTERIOR SHEATHING PER WEF METHOD (BELOW)  
UNLESS OTHERWISE NOTED ON THE PLAN

XXXX EXTERIOR BRACED WALLS:

WEF METHOD: WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN 3/8" WITH MINIMUM SPAN RATINGS OF 24/0 FOR 16" OC STUD SPACING WITH 6d COMMON NAILS AT 6" OC EDGES AND 12" OC FIELD OR SHEATHING THICKNESS NOT LESS THAN 3/8" WITH MINIMUM SPAN RATINGS OF 24/6 FOR 24" OC SPACING WITH 6d COMMON NAILS AT 6" OC EDGES AND 12" OC IN FIELD.  
(NOTE: FRAMING MEMBERS 16" OC MAXIMUM, AND WITH SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS)

//// INTERIOR BRACED WALLS (REF 2-54.0):

GB METHOD: 1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX. FASTENED WITH No 6 - 1/4" TYPE 'W' OR 'S' DRYWALL SCREWS AT 1" OC EDGES AND FIELD (MIN. 4'-0" SECTION FOR BOTH SIDES.)

OR

LIB METHOD: 1x4 WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USF 16 GA. TYPE MB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16" O.C. STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.

STRUCTURAL NOTES:  
- ALL UNMARKED HEADERS MIN (2)#2-2x10  
- ALL HEADERS AND BEAMS MIN #2  
GRADE DFL (OR EQ.)  
- XXXXXXXX = BEARING WALL

COLUMN & PIER PAD SCHEDULE (REF. 5/52.0)				
COLUMN MARK	PAD SIZE	REINFORCEMENT	COLUMN SIZE	COLUMN TYPE
△	30" x 30" x 12"	(4) #4 BAR E.M.	3" NOMINAL, UNO.	SCHEDULE 40 STEEL PIPE (Fg = 36 ksi MIN)
△	36" x 36" x 12"	(4) #4 BAR E.M.	3" NOMINAL, UNO.	
△	42" x 42" x 12"	(5) #4 BAR E.M.	3" NOMINAL, UNO.	
△	48" x 48" x 12"	(6) #4 BAR E.M.	3" NOMINAL, UNO.	
△	54" x 54" x 16"	(8) #4 BAR E.M.	3 1/2" NOMINAL, UNO.	
△	60" x 60" x 16"	(10) #4 BAR E.M.	3 1/2" NOMINAL, UNO.	


- COLUMN & PAD SIZES SHOWN ARE FOR MAXIMUM COLUMN HEIGHT OF 10'-0". REQUIRES SEPARATE ENGR'D DESIGN IF GREATER THAN 10'-0" TALL.
- COLUMN & PIER PAD SIZES SHOWN ARE BASED ON AN ASSUMED MINIMUM ALLOWABLE SOIL BEARING CAPACITY OF 1500 PSF.

COLUMN & PIER SCHEDULE		
MARK	COLUMN SIZE	PIER DIA.
△	6x6	12"
△	6x6	16"
△	6x6	18"
△	6x6	24"
△	6x6	28"

- ALL PIERS TO BEAR ON ORIGINAL UNDISTURBED SOIL OF 1500 PSF BEARING CAPACITY OR FILL COMPACTED AND TESTED TO CONFORM TO THE RECOMMENDATIONS OF A GEOTECHNICAL ENGINEER.
- PIERS SHALL EXTEND BELOW THE FROST LINE: MIN. DEPTH OF 36" BELOW GRADE.
- POST SHALL BE TREATED OR CEDAR WITH SIMPSON ABUS66 POST BASE

DETAIL REFERENCES

- |           |  |           |  |
|-----------|--|-----------|--|
| 1<br>52.0 | TYPICAL FOUNDATION WALL DETAIL                   | 2<br>52.1 | STRUCTURAL GARAGE SLAB<br>PIER PAD DETAIL                    |
| 2<br>52.0 | TYPICAL "UNRESTRAINED"<br>FOUNDATION WALL DETAIL | 3<br>52.1 | STRUCTURAL GARAGE SLAB /<br>WALL SECTION                     |
| 3<br>52.0 | TYPICAL DEAD MAN DETAIL                          | 6<br>52.1 | TYPICAL OVERDIG DETAIL AT<br>BASEMENT SLAB                   |
| 4<br>52.0 | FOUNDATION WALL JUMP DETAIL                      | 1<br>54.0 | ALTERNATE BRACED WALL PANEL<br>DETAIL                        |
| 5<br>52.0 | COLUMN PAD DETAIL                                | 1<br>54.0 | APA NARROW WALL BRACING<br>METHOD WITHOUT HOLD-DOWNS<br>ALT. |
| 1<br>52.1 | TYPICAL STRUCTURAL GARAGE SLAB<br>PLAN           | △         | COLUMN AND PIER PAD SCHEDULE<br>(SHEET 52.0)                 |



APEX ENGINEERS, INC.  
1625 LOCUST ST  
KANSAS CITY, MO 64108  
916.421.3222

STRUCTURAL DESIGN REVIEW

KANSAS ENGINEERING LICENSE: E-292  
MISSOURI ENGINEERING LICENSE: 200304673

NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010

Residential Builder Resource, LLC  
Custom Home Drafting & Design Service  
Kansas City Metro  
Rural Missouri & Eastern Kansas  
Ph. (816) 472-5072


The Brooklyn  
Lot 3 Whispering Woods  
1920 SW River Run Dr.  
Lee's Summit, MO 64082  
© Copyright 2020

DRAWN BY: RBR  
CHECKED BY: CA  
DATE: 10-29-20

A2

PROJ. #20-090





BRACED WALL METHODOLOGY  
CONTINUOUS EXTERIOR SHEATHING PER WSP METHOD (BELOW)  
UNLESS OTHERWISE NOTED ON THE PLAN

XXXX EXTERIOR BRACED WALLS:

WSP METHOD: WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN 5/8" WITH MINIMUM SPAN RATINGS OF 24/0 FOR 16" OC STUD SPACINGS WITH 6d COMMON NAILS AT 6" OC EDGES AND 12" OC FIELD OR SHEATHING THICKNESS NOT LESS THAN 1/2" WITH MINIMUM SPAN RATING OF 24/0 FOR 24" OC SPACING WITH 8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN FIELD.  
(NOTE: FRAMING MEMBERS 16" OC MAX UNLOCKED, AND WITH SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS)

//// INTERIOR BRACED WALLS (REF 2-S4.0):


GB METHOD: 1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX. FASTENED WITH No 6 - 1/2" TYPE 'W' OR 'S' DRYWALL SCREWS AT 1' OC EDGES AND FIELD (MIN. 4'-0" SECTION FOR BOTH SIDES)

OR

LIB METHOD: 1x4 WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA. TYPE WB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16" O.C. STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.

STRUCTURAL NOTES:

- ALL UNMARKED HEADERS MIN (2)#2-2x10
- ALL HEADERS AND BEAMS MIN #2
- GRADE DFL (OR EQ.)
- [XXXXXX] = BEARING WALL



FIRST FLOOR -	1678 SQ. FT.
SECOND FLOOR -	1041 SQ. FT.
LOWER LEVEL -	18 SQ. FT.
TOTAL	2,743 SQ. FT.
GARAGE	671 SQ. FT.
UNFINISHED BASEMENT	1513 SQ. FT.
DECK	143 SQ. FT.

\*ALL WINDOWS TO HAVE U = 0.35 OR LESS.

ALL WINDOWS SIZES ARE EXPRESSED  
IN FEET AND INCHES TO THE UNIT  
SIZE.

NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION

FIRST FLOOR PLAN  
SCALE: 1/4" = 1'-0"

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010


Residential Builder Resource, LLC  
Custom Home Drafting & Design Service  
Kansas City Metro  
Rural Missouri & Eastern Kansas  
Ph. (816) 472-5072

The Brooklyn  
Lot 3 Whispering Woods  
1920 SW River Run Dr.  
Lee's Summit, MO 64082  
© Copyright 2020

DRAWN BY: RBR  
CHECKED BY: CA  
DATE: 10-29-20

PROJ. #20-090





SECOND FLOOR PLAN  
SCALE: 1/4" = 1'-0"

BRACED WALL METHODOLOGY  
CONTINUOUS EXTERIOR SHEATHING PER WSP METHOD (BELOW)  
UNLESS OTHERWISE NOTED ON THE PLAN

XXXX EXTERIOR BRACED WALLS:

WSP METHOD: WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN 5/8" WITH MINIMUM SPAN RATINGS OF 24/0 FOR 16" OC STUD SPACING WITH 6d COMMON NAILS AT 6" OC EDGES AND 12" OC FIELD OR SHEATHING THICKNESS NOT LESS THAN 1/2" WITH MINIMUM SPAN RATING OF 24/0 FOR 24" OC SPACING WITH 8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN FIELD.  
(NOTE: FRAMING MEMBERS 16" OC MAX UNLOCKED, AND WITH SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS)


//// INTERIOR BRACED WALLS (REF 2-S4.0):

GB METHOD: 1/2" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX. FASTENED WITH No 6 - 1 1/4" TYPE 'W' OR 'S' DRYWALL SCREWS AT 1" OC EDGES AND FIELD (MIN. 4'-0" SECTION FOR BOTH SIDES.)

OR

LIB METHOD: 1x4 WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA. TYPE MB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16" O.C. STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.

STRUCTURAL NOTES:  
- ALL UNMARKED HEADERS MIN (2)#2-2x10  
- ALL HEADERS AND BEAMS MIN #2  
GRADE DFL (OR EQ.)  
- [Hatched Box] = BEARING WALL



\*ALL WINDOWS TO HAVE U = 0.35 OR LESS.

ALL WINDOWS SIZES ARE EXPRESSED IN FEET AND INCHES TO THE UNIT SIZE.


NOTE:  
PLANS DESIGNED PER IRC AS ADOPTED BY GOVERNING JURISDICTION

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010


Residential Builder Resource, LLC  
Custom Home Drafting & Design Service  
Kansas City Metro  
Rural Missouri & Eastern Kansas  
Ph. (816) 472-5072

The Brooklyn  
Lot 3 Whispering Woods  
1920 SW River Run Dr.  
Lee's Summit, MO 64082  
© Copyright 2020

DRAWN BY: RBR  
CHECKED BY: CA  
DATE: 10-29-20



PROJ. #20-090



ROOF PLAN

SCALE: 1/4" = 1'-0"

ROOF FRAMING NOTES

ROOF DESIGNED FOR LIGHT ROOF COVERING  
30psf TOTAL LOAD (10psf DL, 20psf LL (SL))

ROOF SYSTEM IS DESIGNED TO MEET REQUIREMENTS OF  
IRC 802

\*RAFTERS (HEM-FIR, DOUG-FIR, OR EQUAL):  
SEE SPAN CHARTS BELOW

CODE MINIMUM

RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	AT 24" OC	11'-7"
#2-2x6	AT 16" OC	14'-2"
#2-2x8	AT 24" OC	14'-8"
#2-2x8	AT 16" OC	17'-11"
#2-2x10	AT 24" OC	17'-10"
#2-2x10	AT 16" OC	21'-11"

NOTE: CODE MINIMUM ALLOWS FOR A RAFTER DEFLECTION OF L/180 TOTAL LOAD

HIGHER PERFORMANCE

RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	AT 24" OC	8'-6"
#2-2x6	AT 16" OC	9'-4"
#2-2x8	AT 24" OC	11'-3"
#2-2x8	AT 16" OC	12'-4"
#2-2x10	AT 24" OC	14'-3"
#2-2x10	AT 16" OC	16'-3"

APEX ENGINEERS, INC. RECOMMENDED DEFLECTION =  
L/360 LIVE LOAD, L/240 TOTAL LOAD

\*RIDGE BOARDS ARE (UNLESS OTHERWISE NOTED)

#2-2x10 UP TO 9:12 PITCH

#2-2x12 OVER 9:12 PITCH

\*ALL HIP AND VALLEYS ARE (UNLESS OTHERWISE NOTED)

#2-2x10 UP TO 9:12 PITCH

#2-2x12 OVER 9:12 PITCH

\*PURLINS ARE 2x6 MIN

- PURLIN STRUTS ARE AT 4'-0" OC

- PURLIN STRUTS SHALL BE INSTALLED AT NOT LESS THAN A  
45 DEGREE ANGLE WITH THE HORIZONTAL

- ALL PURLIN STRUTS SHALL HAVE A MAX UNBRACED  
LENGTH OF 8'-0"

- PURLIN STRUTS SHALL BE CONSTRUCTED IN A "T"  
CONFIGURATION AND PER THE FOLLOWING CHART:

PURLIN STRUT	MAX PURLIN STRUT LENGTH
(2)2x4	8'-0"
(1)2x4 AND (1)2x6	12'-0"
(1)2x6 AND (1)2x8	20'-0"
(2)2x6 AND (1)2x8	30'-0"
CONSULT ARCH ENGR	30'-0"

\*EACH END OF STRUT SHALL BE FASTENED WITH MIN (3)8d OR  
(2)16d NAILS

\*RIDGE BRACERS ARE SAME AS PURLIN BRACES-SPACING,  
SIZE, CONFIGURATION, AND INSTALLATION (SEE PURLIN  
BRACE NOTES ABOVE)

\*HIP AND VALLEY BRACES ARE THE SAME AS PURLIN SIZE,  
CONFIGURATION, AND INSTALLATION (SEE PURLIN BRACE  
NOTES ABOVE)

= ROOF BRACE/STRUT (PER CHART)

-SLASH IS TOP END OF BRACE

-CIRCLE IS BOTTOM END OF BRACE

= PURLIN STRUTS AT 48" OC (PER CHART) U.N.O.

-SLASH IS TOP END OF BRACE

-ARROW IS BEARING LOCATION

----- DENOTES BEARING WALL

----- DENOTES PURLIN

----- DENOTES BEARING STRUCTURE

STRUCTURAL NOTES:


- ALL UNMARKED HEADERS MIN (2)#2-2x10

- ALL HEADERS AND BEAMS MIN #2

GRADE DF/L (OR EQ.)

- [HATCH] = BEARING WALL

1. THIS IS AN ENGINEERED ROOF  
STRUCTURE DESIGNED FOR  
COMPLIANCE WITH IRC 802.3, BUILD  
AS SHOWN WITH NO DEVIATIONS.
2. ALL HIPs ARE DESIGNED TO BE  
CONTROLLED BY BENDING.
3. SHEAR AT BEARING WITH MIN 5 1/2"  
DEPTH DOES NOT CONTROL  
DESIGN. FOR VALLEYS REF 4/S3.2



NOTE:  
PLANS DESIGNED PER IRC AS  
ADOPTED BY GOVERNING JURISDICTION

New Mark Homes  
P.O. Box 12025  
Parkville, Missouri 64152  
Ph. (816) 969-9010

Residential Builder Resource, LLC  
Custom Home Drafting & Design Service  
Kansas City Metro  
Rural Missouri & Eastern Kansas  
Ph. (816) 472-5072

The Brooklyn  
Lot 3 Whispering Woods  
1920 SW River Run Dr.  
Lee's Summit, MO 64082  
© Copyright 2020

DRAWN BY: RBR

CHECKED BY: CA

DATE: 10-29-20

A5

PROJ. #20-090
















**1 TYPICAL STRUCTURAL GARAGE SLAB PLAN**  
S2.1 3/8" = 1'-0"




**2 STRUCTURAL GARAGE SLAB PIER PAD DETAIL**  
S2.1 3/4" = 1'-0"




**3 STRUCTURAL GARAGE SLAB/WALL SECTION**  
S2.1 3/4" = 1'-0"

PIER SCHEDULE		
COLUMN MARK	COL SIZE	PIER DIAMETER
G	PER PLAN	12"
H	PER PLAN	16"
J	PER PLAN	18"
K	PER PLAN	24"
L	PER PLAN	28"




**8 POST BASE DETAIL**  
S2.1 3/4" = 1'-0"




FORMWORK OPTIONS:  
1. PROVIDE VULCRAFT 2VLI (OR EQUAL) CORRUGATED DECKING (SHORE AT MID-SPAN DURING CONSTRUCTION), OR  
2. PLYWOOD FORMS WITH EXPANDABLE BAR JOISTS OR TEMPORARY FRAMED WALLS BY CONTRACTOR.

**7 SUSPENDED PORCH STOOP DETAIL**  
S2.1 3/4" = 1'-0"


EGRESS WINDOW NOTES:  
PER IRC SECTION 310  
1. 5.7 S.F. OPENING MIN.  
2. 24" MIN. CLEAR HEIGHT  
3. 20" MIN. CLEAR WIDTH  
4. 44" MAX HEIGHT A.F.F.




**4 TYPICAL EGRESS WINDOW SECTION DETAIL**  
S2.1 3/4" = 1'-0"




**5 TYPICAL EGRESS WINDOW PLAN**  
S2.1 3/4" = 1'-0"




**6 TYPICAL OVERDIG DETAIL AT BASEMENT SLAB**  
S2.1 3/4" = 1'-0"




**9 POUR STOP DETAIL**  
S2.1 3/4" = 1'-0"




**10 GARAGE SLAB BEARING**  
S2.1 3/4" = 1'-0"




**11 GARAGE SLAB BEAM BEARING**  
S2.1 3/4" = 1'-0"



**12 POUR STOP DETAIL**  
S2.1 3/4" = 1'-0"



**13 GARAGE SLAB BEAM BEARING**  
S2.1 3/4" = 1'-0"




**14 CONCRETE HEADER DETAIL**  
S2.1 3/4" = 1'-0"

STEEL DECKING NOTES:  
• MINIMUM 1-1/2" BEARING  
• FASTEN TO SUPPORT STEEL WITH 5/8" VISIBLE PUDDLE WELDS AT EDGE RIBS AND 12" CENTERS ALONG END BEARING  
• FASTEN SIDE LAPS AND PERIMETER EDGES AT 36" CENTERS WITH #10 TEK SCREWS OR 5/8" PUDDLE WELDS  
• MAX UNSUPPORTED CONSTRUCTION SPAN 6'-0", UNO ON PLANS BY APEX

**TYPICAL SUSPENDED SLAB DETAIL**





12 TYPICAL WALL CROSS-SECTION  
S3.0 1 1/2" = 1'-0"

TABLE R602.3 (5) - SIZE, HEIGHT, AND SPACING OF WOOD STUDS					
STUD SIZE (IN)	LATERALLY UNSUPPORTED STUD HEIGHT*	STRUCTURE SUPPORTED			
		ROOF ONLY	ROOF AND (1) FLOOR	ROOF AND (2) FLOORS	
2x4	10 FEET	24" OC*	16" OC*	N/A	
2x6	10 FEET	24" OC	24" OC	16" OC	


A. LISTED HEIGHTS ARE DISTANCES BETWEEN POINTS OF LATERAL SUPPORT PLACED PERPENDICULAR TO THE PLANE OF THE WALL. BEARING WALLS SHALL BE SHEATHED ON NOT LESS THAN ONE SIDE OR BRIDGING SHALL BE INSTALLED NOT GREATER THAN 4 FEET APART MEASURED VERTICALLY FROM EITHER END OF THE STUD. INCREASES IN UNSUPPORTED HEIGHT ARE PERMITTED WHERE IN THE COMPLIANCE WITH EXCEPTION 2 OF SECTION R602.3.1 OR DESIGNED IN ACCORDANCE WITH ACCEPTED ENGINEERING PRACTICE.

B. A HABITABLE ATTIC ASSEMBLY SUPPORTED BY 2x4 STUDS IS LIMITED TO A ROOF SPAN OF 32 FEET. WHERE THE ROOF SPAN EXCEEDS 32 FEET, THE WALL STUDS SHALL BE INCREASED TO 2x6 OR THE STUDS SHALL BE DESIGNED IN ACCORDANCE WITH ACCEPTED ENGINEERING PRACTICE.


TABLE R602.3 (6) - ALTERNATE WOOD BEARING WALL STUD SIZE, HEIGHT AND SPACING					
ULTIMATE DESIGN WIND SPEED = 115 MPH					
STUD HEIGHT	SUPPORTING	STUD SPACING	MAX ROOF/FLOOR SPAN,		
			12 FEET	24 FEET	24 FEET
11 FEET	ROOF ONLY	12 IN	2x4	2x4	2x4
		16 IN	2x4	2x4	2x4
		24 IN	2x6	2x6	2x6
	ROOF AND ONE FLOOR	12 IN	2x4	2x6	2x6
		16 IN	2x6	2x6	2x6
		24 IN	2x6	2x6	2x6
12 FEET	ROOF ONLY	12 IN	2x4	2x4	2x4
		16 IN	2x4	2x6	2x6
		24 IN	2x6	2x6	2x6
	ROOF AND ONE FLOOR	12 IN	2x4	2x6	2x6
		16 IN	2x6	2x6	2x6
		24 IN	2x6	2x6	2x6

A. WALL STUDS NOT EXCEEDING 16" OC SHALL BE SHEATHED WITH MINIMUM 1/2" GYPSUM BOARD ON THE INTERIOR AND 3/8" WOOD STRUCTURAL PANEL SHEATHING ON THE EXTERIOR. WOOD STRUCTURAL PANEL SHEATHING SHALL BE ATTACHED WITH 8d (2.5" x 0.131") NAILS NOT GREATER THAN 6" OC ALONG PANEL EDGES AND 12" OC AT INTERMEDIATE SUPPORTS, AND ALL PANEL JOINTS SHALL OCCUR OVER STUDS OR BLOCKING.


B. THE MAXIMUM SPAN IS APPLICABLE TO BOTH SINGLE AND MULTIPLE SPAN ROOF AND FLOOR CONDITIONS. THE ROOF ASSEMBLY SHALL NOT CONTAIN A HABITABLE ATTIC.




11 TYPICAL STRINGER DETAIL  
S3.0 3/4" = 1'-0"




10 TYPICAL STAIR/RAIL DETAIL  
S3.0 3/4" = 1'-0"




9 UPSET STEEL BEAM/JOIST CONNECTION  
S3.0 1 1/2" = 1'-0"



8 LEDGER FASTENER PLACEMENT  
S3.0 1 1/2" = 1'-0"




7 TYPICAL CANTILEVER FRAMING WITH DECK ATTACHMENT  
S3.0 3/4" = 1'-0"




DECK LEDGER ATTACHMENT CHART			
DECK JOIST SPAN	1/2" DIA LAG SPACING	EQUIVALENT SPACING FOR 16" OC JOIST BAYS	
UP TO 10'-0"	16" OC	N/A	
10'-1" TO 12'-0"	15" OC	16" OC DBL EVERY OTHER	
12'-1" TO 14'-0"	13" OC	16" OC DBL EVERY OTHER	
14'-1" TO 16'-0"	11" OC	16" OC DBL EVERY JOIST BAY	
16'-1" TO 18'-0"	10" OC	16" OC DBL EVERY JOIST BAY	

NOTE: CHART IS APPLICABLE ONLY WHEN DECK IS SHOWN ON APPROVED PLAN.


6 TYPICAL LEDGER ATTACHMENT  
S3.0 3/4" = 1'-0"




5 TYPICAL LEDGER BOLT SPACING  
S3.0 3/4" = 1'-0"




4 SPliced DECK COLUMN CONNECTION  
S3.0 1 1/2" = 1'-0"



3 SPliced DECK COLUMN CONNECTION  
S3.0 1 1/2" = 1'-0"




2 DECK BEAM/COLUMN CONNECTION  
S3.0 1 1/2" = 1'-0"



1 DECK BEAM/COLUMN CORNER CONDITION  
S3.0 3/4" = 1'-0"





<b>3</b>	<b>BEAM TO GIRDER CONNECTION</b>
<b>S3.1</b>	1 1/2" = 1'-0"

**VIEW B-B**

A TYP. EACH ENDERS ROOF (U.N.O.)

**WOOD BEAM**  
TYP. UPSET  
HEADER

**VIEW A-A**

SIMPSON H2.5A TYP. BOTH FACES OF EACH END OF ALL HEADERS SUPPORTING ROOF (U.N.O.)

**WOOD BEAM**  
TYP. DROPPED  
HEADER

VARIES

The diagram illustrates two alternative framing methods for oblong bored holes in exterior walls and non-bearing partitions. The left side shows details for an exterior or bearing wall, while the right side shows details for a non-bearing partition. Each side includes a cross-section of the wall with a vertical oblong hole. The hole is framed by a double stud, with the top and bottom studs having a width of 5/8" minimum. The hole's diameter is specified as 40% of the stud width, and its depth is 60% of the stud width. A notch is cut into the top and bottom studs, with a depth of 25% of the stud width maximum. The right side shows a similar detail for a non-bearing partition, but the notch depth is specified as 40% of the stud width maximum.

STUD FACE 5/8" MIN

BORED HOLES DIA 40% OF STUD WIDTH, 60% OF STUD WIDTH IF DOUBLE STUD

NOTCH 25% OF STUD WIDTH MAX

EXTERIOR OR BEARING WALL

STUD FACE 5/8" MIN

BORED HOLES DIA 60% OF STUD WIDTH MAX

NOTCH 40% OF STUD WIDTH MAX

NON-BEARING PARTITION

**ALTERNATE FOR OBLONG BORED HOLES**

STUD FACE 5/8" MIN

BORED HOLES DIA 40% OF STUD WIDTH, 60% OF STUD WIDTH IF DOUBLE STUD

NOTCH 25% OF STUD WIDTH MAX

EXTERIOR OR BEARING WALL

STUD FACE 5/8" MIN

BORED HOLES DIA 60% OF STUD WIDTH MAX

NOTCH 40% OF STUD WIDTH MAX

NON-BEARING PARTITION

**HEADERS WITH GREATER THAN 1" GAP BETWEEN VERT MEMBERS**

- 2x PLATE T&B, UNO
- FASTEN PLATE TO EACH VERT MEMBER WITH 10d NAILS AT 16" OC UNO
- HEADER VERT MEMBERS, REF PLAN
- 2x PACKOUT AT EACH END AND 4'-0" OC MAX THROUGHOUT HEADER SPAN
- FASTEN VERT MEMBERS TO PACKOUT WITH (3) 10d NAILS

**HEADERS WITH 1" AND LESS GAP BETWEEN VERT MEMBERS**

- 2x PLATE T&B, UNO
- FASTEN PLATE TO EACH VERT MEMBER WITH 10d NAILS AT 16" OC UNO
- HEADER VERT MEMBERS, REF PLAN
- PLYWOOD PACKOUT BETWEEN VERT MEMBERS
- REF MULTIPLE PLY BEAM NAILING SCHEDULE

PENETRATIONS THRU STUDS					
WALL SIZE	BORED HOLE SIZE			WALL NOTCH	
	STUDS LOAD BEARING		NON LOAD BEARING WALL	LOAD BEARING	NON LOAD
	EXTERIOR WALL			WALL	BEARING WALL
	40%	60%	60%	25%	40%
2x4	1 3/8"	-	2 1/8"	7/8"	1 3/8"
(2) 2x4	-	2 1/8"	2 1/8"	7/8"	1 3/8"
2x6	2 1/4"	-	3 15/16"	1 3/8"	2 1/4"
(2) 2x6	-	3 5/16"	3 15/16"	1 3/8"	2 1/4"
2x8	2 7/8"	-	4 3/8"	1 13/16"	2 7/8"
(2) 2x8	-	4 3/8"	4 3/8"	1 13/16"	2 7/8"


NOTE:  
SEE SECTION R602.6 AND FIGURES R602.6.1  
AND R602.6.2

Diagram illustrating the correct nailing technique for 2x4 and 2x6 lumber. The left side shows a 2x4 with a nail driven at a 1.4° angle from the opposite face. The right side shows a 2x6 with a nail driven at a 1.4° angle from the face shown. Below each lumber section are four diagrams showing the nail patterns for 2-PLY, 4-PLY, 3-PLY, and 5-PLY configurations.

NOTES:


1. EACH 2x PLY SHALL BE FASTENED WITH (1) ROW OF 10d NAILS AT 9" OC, ALTERNATING SIDE TO SIDE
2. 1.4" MIN EDGE DISTANCE, AND STARTING 2 1/2" FROM EACH END.
3. EXTEND FULL AREA OF COLUMN AS SOLID BLOCKING THROUGH JOIST BAYS AND WALLS TO LOAD-BEARING BEAM/WALL BELOW

<b>1</b>	<b>BUILT-UP STUD COLUMN</b>
<b>S3.1</b>	1 1/2" = 1'-0"




10	MULTIPLE PLY BEAM NAILING SCHEDULE
S3.1	NOT TO SCALE






### 8 | OPTIONAL RAFTER BEARING

S3.2 1 1/2" = 1'-0"



### 7 | OPTIONAL RAFTER BEARING


S3.2 1 1/2" = 1'-0"



### 6 | OPTIONAL RAFTER BEARING

S3.2 1 1/2" = 1'-0"

UPLIFT CONNECTION SCHEDULE			
OVERHANG SPAN: 1'-1" TO 1'-9"			
RAFTER SPACING	UPLIFT CONNECTOR	EXPOSURE B	EXPOSURE C
12" OC	SIMPSON H2.5A	(1) AT 24" OC	(1) AT 24" OC
16" OC	SIMPSON H2.5A	(1) AT 32" OC	(1) AT 16" OC
24" OC	SIMPSON H2.5A	(1) AT 24" OC	(1) AT 24" OC
OVERHANG SPAN: 1'-10" TO 2'-6"			
RAFTER SPACING	UPLIFT CONNECTOR	EXPOSURE B	EXPOSURE C
12" OC	SIMPSON H2.5A	(1) AT 12" OC	(1) AT 12" OC
16" OC	SIMPSON H2.5A	(1) AT 16" OC	(2) AT 16" OC
24" OC	SIMPSON H2.5A	(2) AT 24" OC	(2) AT 24" OC
OVERHANG SPAN: 2'-7" TO 3'-9"			
RAFTER SPACING	UPLIFT CONNECTOR	EXPOSURE B	EXPOSURE C
12" OC	SIMPSON H2.5A	(2) AT 12" OC	(2) AT 12" OC
16" OC	SIMPSON H2.5A	(2) AT 16" OC	(2) AT 16" OC
24" OC	SIMPSON H2.5A	(2) AT 24" OC	N/A




### 5 | OUTLOOKER RAFTERS ROOF FRAMING

S3.2 NOT TO SCALE

REQUIRED NUMBER OF SISTER PLIES									
LIGHT ROOF									
2x VALLEY					LVL VALLEY				
# OF SISTER PLIES	RAFTER SIZE				# OF SISTER PLIES	RAFTER SIZE			
0	2x6	2x8	2x10		0	2x6	2x8	2x10	
1	4'-8"	6'-2"	7'-11"		0	8'-8"	11'-5"	14'-7"	
2	9'-5"	*	*		1	*	*	*	
	*	N/A	N/A		2	N/A	N/A	N/A	
HEAVY ROOF									
2x VALLEY					LVL VALLEY				
# OF SISTER PLIES	RAFTER SIZE				# OF SISTER PLIES	RAFTER SIZE			
0	2x6	2x8	2x10		0	6'-6"	8'-7"	10'-11"	
1	3'-6"	4'-7"	5'-11"		1	13'-1"	*	*	
2	7'-1"	9'-3"	*		2	*	N/A	N/A	
	*	*	N/A						

- \*VALLEYS OF A LENGTH GREATER THAN THAT FOUND IN THE CELL ABOVE ARE CONTROLLED BY BENDING. APPLY THE NUMBER OF SISTER PLIES CORRESPONDING TO THIS ROW.
- THIS TABLE IS INTENDED TO BE USED IN CONJUNCTION WITH THE STAMPED, ENGINEERED PLANS AS THEY ARE DRAWN BY APEX. BRACING LOCATIONS SHALL DETERMINE HORIZONTAL UNSUPPORTED SPAN FROM VALLEY BEARING AND BE USED TO DETERMINE THE NUMBER OF SISTERS REQUIRED. BRACING LOCATIONS ARE **NOT** TO BE INFERRED USING THIS TABLE.
  - TABLE VALUES ARE BASED ON A DEPTH OF MEMBER REMAINING, d, EQUAL TO THE DEPTH OF THE RAFTERS. IF d IS OBSERVED TO BE LESS THAN THE DEPTH OF THE RAFTER, THE VALLEY WILL NEED TO BE EITHER REPLACED OR ANALYZED BY APEX.
  - TABLE VALUES ARE VALID FOR TAPERED CUTS ONLY, REF DETAIL 4/S3.2.
  - IF MULTI-PLY VALLEY IS SPECIFIED ON PLAN TREAT EACH ADDITIONAL PLY AS A SISTER PLY WHEN LOOKING UP MAX SPAN.
  - MAX 14'-0" HORIZONTAL RAFTER SPAN IN BOTH DIRECTIONS FROM VALLEY.
  - ALL HIPs ARE DESIGNED TO BE CONTROLLED BY BENDING. SHEAR AT BEARING WITH MIN 5 1/2" DEPTH DOES NOT CONTROL DESIGN.




### 4 | TAPERED VALLEY

S3.2 3/4" = 1'-0"


OVERHANG SPAN	MIN BACKSPAN LENGTH
≤1'-0"	1'-0"
1'-1" to 2'-0"	EQUALS OVERHANG SPAN
≥2'-1"	OVERHANG SPAN x2

NOTES:  
-CHART IS ONLY APPLICABLE IF NO RAFTER BEAM SHOWN ON PLAN.  
-CONTACT EOR IF OVERHANG LENGTH EXCEEDS CHART OPTIONS.




### 3 | RIDGE BEAM DETAIL

S3.2 3/4" = 1'-0"



### 2 | BOLTED RAFTER HIP CONNECTION

S3.2 1 1/2" = 1'-0"









FURR OUT SCHEDULE			
RAFTER SIZE	R-30C INSULATION (X= 9 1/4")	R-38C INSULATION (X=11 1/4")	
2x6	2x6	2x8	
2x8	2x4	2x6	
2x10	NOT REQUIRED	2x4	
2x12	NOT REQUIRED	REQUIRED	
NOTES:			
1. ALL VAULTED RAFTERS SHALL BE #2-2x6 DF-L, MINIMUM, AT 16" OC, PER SPAN CHART, UNLESS NOTED OTHERWISE.			
2. ALL VAULTS SHALL BE FURRED DOWN WITH 2x FRAMING TO THE REQUIRED DEPTH OF INSULATION, PLUS 1" AIR SPACE.			
3. R-30C INSULATION = 8 1/4" THICK			
4. R-38C INSULATION = 10 1/4" THICK			
5. INSULATION REQUIREMENTS MAY BE REDUCED TO R30 IF ROOF/CEILING ASSEMBLY DOES NOT ALLOW SUFFICIENT SPACE BUT IS LIMITED TO VAULTED CEILING AREAS THAT ARE LESS THAN 500 SQUARE FEET OR 20 PERCENT OF THE TOTAL INSULATED CEILING AREA, WHICHEVER IS LESS. (PER N1102.2.2)			

### 1 | VAULTED RAFTER INSULATION FURR OUT

S3.2 3/4" = 1'-0"





**TABLE R602.10.5 (PARTIAL)**

METHOD	MINIMUM LENGTH OF BRACED WALL PANELS					
	MIN LENGTH (INCHES)					
	8 FEET	9 FEET	10 FEET	11 FEET	12 FEET	
1. SUPPORTING ROOF ONLY	16	16	16	16	16	
2. ONE STORY AND ROOF	24	24	24	24	24	
PFG	24	27	30	30	30	

NOTE: MAX HEADER HEIGHT IS 10'-0", BUT WALL HEIGHT SHALL BE PERMITTED TO BE INCREASED TO 12'-0" WITH PONY WALL

**TABLE R602.10.6.4**


MIN WALL STUD FRAMING NOMINAL SIZE AND GRADE	MAX PONY WALL HEIGHT (FEET)	MAX TOTAL WALL HEIGHT (FEET)	MAX OPENING WIDTH (FEET)	TENSION CAPACITY STRAP TABLE	
				TENSION STRAP CAPACITY REQ (LBS)	115 MPH, EXP B
2x4 #2 GRADE	0	10	18	1,000	
				9	1,000
				16	1,025
				18	1,275
				9	1,000
				16	2,175
	2	12	18	2,500	
				9	1,500
				16	3,375
				18	3,975
				9	2,750
				16	3,775
2x6 STUD GRADE	2	12	18	1,000	
				9	2,150
				18	2,550
				9	1,750
				16	2,400
				18	3,800

**BRACED WALL METHODOLOGY**  
CONTINUOUS EXTERIOR SHEATHING (CS-WSP) PER WSP METHOD (BELOW) UNLESS OTHERWISE NOTED ON THE PLAN

**XXXX EXTERIOR BRACED WALLS:**  
WSP METHOD:  
WOOD STRUCTURAL PANEL SHEATHING WITH A THICKNESS NOT LESS THAN 3/8" WITH MINIMUM SPAN RATING OF 24/0 FOR 16" OC STUD SPACING WITH 6d COMMON NAILS AT 6" OC EDGES AND 12" OC FIELD OR SHEATHING THICKNESS NOT LESS THAN 7/16" WITH MINIMUM SPAN RATING OF 24/16 FOR 24" OC SPACING WITH 8d COMMON NAILS AT 6" OC EDGES AND 12" OC IN FIELD.  
(NOTE: FRAMING MEMBERS 16" OC MAX, UNBLOCKED, AND WITH SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS)


**///// INTERIOR BRACED WALLS (REF 2/S4.0):**  
GB METHOD:  
1/2" MIN GYPSUM BOARD OVER STUDS SPACED 24" MAX FASTENED WITH #6 - 1 1/4" TYPE "W" OR "S" DRYWALL SCREWS AT 7" OC EDGES AND FIELD (MIN. 4'-0" SECTION FOR BOTH SIDES.)  
OR  
LIB METHOD:  
1/4" WOOD FASTENED WITH (3) 8d COMMON NAILS OR SIMPSON / USP 16 GA TYPE WB (OR EQUAL) STL. X-BRACE(S) AT 45° TO 60° ANGLES, MAXIMUM 16" OC STUD FASTENED PER MANUFACTURER'S SPECIFICATIONS.





**BRACED WALL PANEL  
CONNECTION WHEN  
PERPENDICULAR TO  
FLOOR/CEILING FRAMING**


**S4.1** 3/4" = 1'-0"



**BRACED WALL PANEL  
CONNECTION WHEN PARALLEL  
TO FLOOR/CEILING FRAMING**


**S4.1** 3/4" = 1'-0"

**CONT. SHEATHED BRACED WALL END CONDITIONS**




**CONTINUOUS SHEATHED BRACED  
WALL END CONDITIONS**

**S4.1** NOT TO SCALE (COMPLIANCE WITH IRC R602.10.7)




**OVER CONCRETE OR MASONRY BLOCK FOUNDATION**



**OVER RAISE WOOD FLOOR - FRAMING ANCHOR OPTION**

(WHEN PORTAL SHEATHING DOES NOT LAP OVER BAND OR RIM JOIST)



**OVER RAISE WOOD FLOOR - OVERLAP OPTION**

(WHEN PORTAL SHEATHING LAPS OVER BAND OR RIMBOARD)

**BRACED WALL PANEL-IRC  
METHOD CS-PF CONTINUOUSLY  
SHEATHED PORTAL FRAME  
PANEL CONSTRUCTION**

**S4.1** 3/4" = 1'-0" (PER IRC R602.10.6.4)