




# LEE'S SUMMIT MISSOURI

## DEMOLITION PERMIT APPLICATION

TYPE	Commercial	<input type="checkbox"/>	Residential	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>
	Commercial Partial	<input type="checkbox"/>	Residential Partial	<input type="checkbox"/>		
DESCRIPTION OF WORK (attach additional pages if necessary)	Demo of House 840 NE Douglas st					
PROJECT INFORMATION	Most recent use of the structure:	Unkown		Plans being submitted:	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
	Square feet of the structure/area being demolished:	1500		Private disposal system being removed:	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
	Number of living units being demolished:	1		Underground fuel storage tanks being removed:	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
	Number of stories:	3		Estimated cost of demolition:	\$21,884.00	
	Will a crane be utilized in the demolition work:	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>				
PROJECT LOCATION AND OWNER	Project Address:	840 NE Douglas St				
	Name:	Philip Tucker		Phone #:	785-885-8075	
	Address:	104 Woodrock Lane AR 72756		Email:	pht04@sbcglobal.net	
APPLICANT (if different)	Business Name:			Phone #:		
	Contact Name:			Email:		
	Address:			State:		
	City:			Zip Code:		
CONTRACTOR (if different)	Business Name:	Temp Stop LLC		Phone #:	816-554-3352	
	Contact Name:	Frank Hale		Email:	frank@tempstop.com	
	Address:	331 NW Capital Dr		State:	Mo	
	City:	Lees Summit		Zip Code:	64086	
UTILITY DISCONNECTS (required for full demolition)	Spire Gas Approval:	Call 1-314-621-6960 for information.		Received by City Staff	<input type="checkbox"/>	
	Every Elec. Approval:	Call 1-888-471-5275 for information.		Received by City Staff	<input type="checkbox"/>	
	Water Approval:	City of Lee's Summit Water Department 816-969-1900		Received by City Staff	<input type="checkbox"/>	
	Sanitary Approval:			Received by City Staff	<input type="checkbox"/>	

<b>PERMIT REQUIREMENTS</b>	<ul style="list-style-type: none"> <li>• The demolition of structures or buildings, partial or complete, shall require a demolition permit. The removal of one-story detached accessory structures used as tool and storage sheds, playhouses, and similar uses, provided the floor area does not exceed one hundred twenty (120) square feet does not require a demolition permit.</li> <li>• When requested by the Building Official, the applicant shall provide; a structural engineers report that describes the methods of demolition including all necessary shoring; plans and information necessary to determine no hazards will be created that endanger the occupants, adjoining properties or general public.</li> <li>• Gas and electric services must be properly abandoned and approved by the appropriate utility company prior to issuance of a permit for complete removal of a structure. Appropriate documentation from the electrical and gas companies documenting proper abandonment.</li> <li>• Water and sanitary services must be abandoned by the Water Utilities Department prior to issuance of a permit for complete removal of a structure. Contact Water Utilites at 816-969-1900 for additional information.</li> <li>• A right-of-way permit and possibly a traffic control permit are required for work located in the row-of-way. Contact the Public Works Department at 816-969-1800 for more information and permit requirements and issuance.</li> <li>• Applicant shall furnish a certificate of liability insurance for personal and property damage in a minimum amount of one hundred thousand dollars (\$100,000) injury each person, three hundred thousand dollars (\$300,000) each occurrence, and fifty thousand dollars (\$50,000) property damage.</li> </ul>
<b>INSPECTIONS</b>	<ul style="list-style-type: none"> <li>• Private disposal systems - The removal of private sanitary waste systems is regulated by the Department of Public Works, Jackson County Planning and Environmental Health. Please contact them at 816-881-4515 for further information.</li> <li>• Contact the City of Lee's Summit Fire Department, 816-969-1300, <b>PRIOR</b> to removal of any underground fuel storage</li> <li>• Demolition waste and the abatement of hazardous materials is regulated by the Missouri Department of Natural Resources. For information regarding demolition waste regulations contact the Hazardous Waste Program at 573-751-3176. For information regarding asbestos contact Air Pollution Control at 573-751-4817. Additional information can also be found at: <a href="http://dnr.mo.gov/env/cdwaste.htm">http://dnr.mo.gov/env/cdwaste.htm</a></li> <li>• Burning of demolition waste of any kind is not allowed in the City of Lee's Summit.</li> <li>• The applicant shall remove all rubbish and materials and fill excavations to existing grade so that the premises are left in a safe and sanitary condition and can be maintained in accordance with the Property Maintenance Code within twenty-eight</li> <li>• A final inspection shall be scheduled after all work required by the demolition permit has been completed</li> <li>• Permits issued for demolition work shall be valid for a maximum duration of sixty (60) days.</li> </ul>
<b>OFFICE USE</b>	   

AFFIDAVIT: I hereby certify that I have the authority to make the foregoing application, and that the application, to the best of my knowledge, is complete, correct, and that the permitted demolition will conform to the regulations in the Codes adopted by the City of Lee's Summit and all applicable ordinances.

  
 \_\_\_\_\_  
 Signature of Owner or Authorized Agent

Frank HAJE  
 \_\_\_\_\_  
 Printed Name of Applicant

11-4-20  
 \_\_\_\_\_  
 Date of Application



Revised November 11, 2019

Jackson County Missouri  
Public Works Department - Development Division  
303 West Walnut Independence, MO 64050 - Phone: 816-881-4530

## BUILDING PERMIT

Permit ID: **BP20200321**

Permission is hereby granted to: **JIM TUCKER**

To: **Raze**

Structure or structures located (general location or street number)

**840 DOUGLAS**

Bldg Types: **Raze**

Zoning:

Fee Total: **\$50.00**

The applicant hereby agrees to abide by the terms of the permit application filed in the office of the Development Division of the Jackson County Public Works Department, and comply with the conditions of building codes, health laws, ordinances and regulations of the State of Missouri and Jackson County, Mo., and furthermore understands that any variance from the provisions of the above mentioned ordinances shall constitute cause for the cancellation of this permit.

This permit shall be null and void if the building or work authorized by this permit is not commenced within 180 days. Before such work can be commenced, the permit holder shall notify the Director of Public Works.

Permit Issued: 10/13/2020



A black ink signature, appearing to be "D. Smith", written over a horizontal line.

Administrator of Planning

A blue ink signature, appearing to be "D. Smith", written over a horizontal line.

Permit Technician



10/15/2020

FRANK@TEMPSTOP.COM

The meter/service has been removed from the following address (es).

<b>Address</b>	<b>Date Removed</b>
840 NE Douglas St 900 NE Douglas St Lee's Summit, MO	All addresses Removed 10/13/2020

If you have any questions, please call 471-KCPL or fax 737-7147.

Thank You,

Jana

*Evergy*



Spire Inc.  
Mailing address  
City, State Zip

October 27, 2020

City of Lee's Summit  
City Hall  
220 SE Green  
Lee's Summit, MO 64063  
816-969-1000


Dear City of Lee's Summit,

This is to notify you that we have abandoned the gas service to the address listed below on October 23, 2020.

840 NE DOUGLAS ST, LEE'S SUMMIT

Sincerely,

Mike Perkins  
Supervisor - Maintenance Department



MISSOURI DEPARTMENT OF NATURAL RESOURCES  
 AIR POLLUTION CONTROL PROGRAM  
**ASBESTOS NESHAP NOTIFICATION OF DEMOLITION  
 AND RENOVATION**

FOR OFFICE USE ONLY	
DATE RECEIVED	POSTMARK
CHECK DATE	CHECK NUMBER
CHECK AMOUNT	NOTIFICATION NUMBER

There is a \$100 review fee for this notification. Processing will be delayed if notification is received without payment.

**1. TYPE OF NOTIFICATION**

O - ORIGINAL    C - CANCELLED    R - REVISION, WRITE REVISION NUMBER \_\_\_\_\_

**2. FACILITY INFORMATION (IDENTIFY OWNER, REMOVAL CONTRACTOR AND OTHER OPERATOR)**

OWNER'S NAME <i>Philip Tucker</i>		ADDRESS <i>104 Woodrock Lane</i>	
CITY <i>Rogers</i>	STATE <i>AR</i>	ZIP CODE <i>72756</i>	EMAIL <i>ph-t04@stcglobal.net</i>
CONTACT <i>OWNER</i>		TELEPHONE NUMBER WITH AREA CODE <i>785-885-8075</i>	
ASBESTOS REMOVAL CONTRACTOR <i>N.A</i>		ADDRESS	
CITY	STATE	ZIP CODE	EMAIL
CONTACT		TELEPHONE NUMBER WITH AREA CODE	
DEMOLITION CONTRACTOR <i>Temp Stop LLC</i>		ADDRESS <i>331 NW Capital Dr</i>	
CITY <i>Lees Summit</i>	STATE <i>MO</i>	ZIP CODE <i>64086</i>	EMAIL <i>Frank@tempstop.com</i>
CONTACT <i>FRANK NAIE</i>		TELEPHONE NUMBER WITH AREA CODE	

**3. TYPE OF OPERATION**

D - DEMO    O - ORDERED DEMO    R - RENOVATION    E - EMERGENCY RENOVATION

**4. IS ASBESTOS PRESENT?**

YES    NO   LIST TYPE(S) OF ASBESTOS MATERIAL TO BE REMOVED  
*2 square feet of sink fan insulation (under coat)*

**5. FACILITY DESCRIPTION**

BUILDING NAME <i>Single Family Home</i>			
ADDRESS <i>840 NE Douglas Street</i>			
CITY <i>Lees Summit</i>	COUNTY <i>JACKSON</i>	STATE <i>MO</i>	ZIP CODE <i>64086</i>
SITE LOCATION			
BUILDING SIZE	NUMBER OF FLOORS <i>2</i>	AGE IN YEARS <i>50</i>	
PRESENT USE <i>Abandon</i>	PRIOR USE <i>Single Family</i>		

**6. PROCEDURE, INCLUDING ANALYTICAL METHOD, IF APPROPRIATE, USED TO DETECT THE PRESENCE OF ASBESTOS MATERIAL. INCLUDE A COPY OF THE ASBESTOS INSPECTION.**

**7. APPROXIMATE AMOUNT OF ASBESTOS, INCLUDING:**

	RACM TO BE REMOVED	NONFRIABLE ASBESTOS MATERIAL TO BE REMOVED		NONFRIABLE ASBESTOS MATERIAL NOT TO BE REMOVED	
		CAT I	CAT II	CAT I	CAT II
PIPS (LINEAR FEET)					
SURFACE AREA (SQUARE FEET)	<i>Sink under coat</i>	<i>2</i>			
VOL. RACM OFF FACILITY COMPONENT (CUBIC FEET)					

<b>8. SCHEDULED DATES DEMO/RENOVATION (MM/DD/YY)</b>			
START: 11-9-20		COMPLETION: 11-30-20	
<b>9. SCHEDULED DATES ASBESTOS REMOVAL (MM/DD/YY)</b>			
START:		WEEKDAY WORK HOURS	WEEKEND WORK HOURS
COMPLETION:			
<b>10. DESCRIPTION OF PLANNED DEMOLITION OR RENOVATION WORK AND METHOD(S) TO BE USED</b>			
Demolition of single family house - 900 N.W. Douglas Street			
<b>11. DESCRIPTION OF WORK PRACTICES AND ENGINEERING CONTROLS TO BE USED TO PREVENT EMISSIONS OF ASBESTOS AT THE DEMOLITION OR RENOVATION SITE.</b>			
House will be wetted during demolition			
<b>12. WASTE TRANSPORTER</b>			
NAME		ADDRESS	
Temp Stop LLC		331 NW Capital Drive	
CITY		STATE	ZIP CODE
Lee's Summit		MO	64086
CONTACT PERSON		TELEPHONE NUMBER WITH AREA CODE	
FRANK NAJE		816 554 3352	
<b>13. WASTE DISPOSAL SITE</b>			
NAME			
Pink Hills Acres			
LOCATION			
3500 NW 7 HWY			
CITY		STATE	ZIP CODE
Blue Springs		MO	64014
TELEPHONE NUMBER WITH AREA CODE			
816-229-6395			
<b>14. IF DEMOLITION ORDERED BY A GOVERNMENT AGENCY, IDENTIFY THE AGENCY BELOW.</b>			
NAME		TITLE	
AGENCY			
DATE OF ORDER (MM/DD/YY) INCLUDE A COPY OF THE ORDER.		DATE ORDERED TO BEGIN (MM/DD/YY)	
<b>15. FOR EMERGENCY RENOVATIONS</b>			
DATE AND HOUR OF EMERGENCY			
DESCRIPTION OF THE SUDDEN, UNEXPECTED EVENT			
EXPLANATION OF HOW THE EVENT CAUSED UNSAFE CONDITIONS OR WOULD CAUSE EQUIPMENT DAMAGE OR AN UNREASONABLE FINANCIAL BURDEN			
<b>16. DESCRIPTION OF PROCEDURES TO BE FOLLOWED IN THE EVENT THAT UNEXPECTED ASBESTOS IS FOUND OR PREVIOUSLY NONFRIABLE ASBESTOS MATERIAL BECOMES CRUMBLER, PULVERIZED OR REDUCED TO POWDER.</b>			
Wetted Down, Bagged, disposed off.			
<b>17. I CERTIFY THAT AN INDIVIDUAL TRAINED IN THE PROVISIONS OF THIS REGULATION (40 CFR PART 61, SUBPART M) WILL BE ON-SITE DURING THE DEMOLITION OR RENOVATION AND EVIDENCE THAT THE REQUIRED TRAINING HAS BEEN ACCOMPLISHED BY THIS PERSON WILL BE AVAILABLE FOR INSPECTION DURING NORMAL BUSINESS HOURS (REQUIRED 1 YEAR AFTER PROMULGATION).</b>			
SIGNATURE OF OWNER/OPERATOR			DATE
Frank Naje			10-27-20
<b>18. I CERTIFY THAT THE ABOVE INFORMATION IS CORRECT.</b>			
SIGNATURE OF OWNER/OPERATOR			DATE
Frank Naje			10-27-20

**TABLE D-1  
ASBESTOS SAMPLE RESULTS**

900 N.E. DOT GLASS STREET					
SAMPLE ID	MATERIAL	COLOR	SAMPLE RESULT	LOCATION	ESTIMATED QUANTITY
TS-1	SIDING	BLUE/GRY	CHRYSOTILE 18%	EXTERIOR	1500SF
TS-2			CHRYSOTILE 18%		
TS-3			CHRYSOTILE 18%		
TP-1	SIDING PAPER	BLACK	ND	EXTERIOR	1500SF
TP-2					
TP-3					
WG-1	WINDOW GLAZE	WHITE	ND	EXTERIOR LIVING ROOM WINDOW	10 TOTAL
WG-2					
WG-3					
AS-1	ASPHALT SHINGLES	WHITE	ND	ROOF	900SF
AS-2					
AS-3					
ASI-1	ASPHALT SHINGLES	GREEN	ND	ROOF	900SF
ASI-2					
ASI-3					
RTP-1	ROOF TAR PAPER	BLACK	ND	ROOF	900SF
RTP-2					
RTP-3					
RF-1	ROOF FLASHING	BLACK	CHRYSOTILE 15%	ROOF	2SF
RF-2			CHRYSOTILE 15%		
RF-3			CHRYSOTILE 15%		
DW-1	DRYWALL	OFF WHITE	ND	THROUGHOUT MAIN FLOOR	1000SF
DW-2					
DW-3					
FV-1	FLOOR VINYL	YELLOW	CHRYSOTILE 65% (BACKING)	ENTRY	12SF
FV-2			CHRYSOTILE 65% (BACKING)		
FV-3			CHRYSOTILE 65% (BACKING)		
FV1-1	FLOOR VINYL	YELLOW	ND	KITCHEN	86SF
FV1-2					
FV1-3					
FL-1	FLOOR LINOLEUM	BLACK	ND	KITCHEN	86SF
FL-2					
FL-3					
FV2-1	FLOOR VINYL	WHITE	ND	BATHROOM	22SF
FV2-2					
FV2-3					
BBM-1	BASEBOARD, MASTIC	BLACK BASEBOARD, YELLOW MASTIC	ND	BATHROOM	131F
BBM-2					
BBM-3					
TT-1			CHRYSOTILE 18%		

**TABLE D-1  
ASBESTOS SAMPLE RESULTS**

SAMPLE ID	MATERIAL	COLOR	SAMPLE RESULT	LOCATION	ESTIMATED QUANTITY
TT-2	LOOSE TILES	GREY	CHRYSOTILE 18%	PILE IN LIVING ROOM	5SF
TT-3			CHRYSOTILE 18%		
SU-1			ND		
SU-2	SINK UNDERCOAT	BLACK	ND	KITCHEN SINK	1 DOUBLE SINK
SU-3					
DC-1					
DC-2	FURNACE DAMPENING CLOTH	TAN	CHRYSOTILE 90%	BASEMENT HVAC	1
DC-3			CHRYSOTILE 90%		
WW-1			CHRYSOTILE 90%		
WW-2	WIRE WRAP	BLACK	ND	ALL ELECTRICAL WIRE- LIVING ROOM	UNKNOWN
WW-3					

Notes

ID Identification  
 NA Not applicable  
 ND None detected

October 19, 2020

Frank Hale, President  
Temp-Stop, LLC  
Frank@tempstop.com

Re: 840 NE Douglas St. Asbestos Testing  
Lee's Summit, MO 64086  
KCTE Project Number E20-20-093

Mr. Hale,

Kansas City Testing and Engineering, LLC (KCTE) completed sampling of suspected asbestos-containing materials at the referenced location on October 9, 2020. The sampling was performed in general accordance with our proposal #EP20-20-242 by Lauren Robertson, a State of Missouri licensed asbestos inspector. Three samples were taken for each homogenous building material that considered to be a suspect asbestos-containing material (ACM). Analysis of the collected samples by polarized light microscopy (PLM) in compliance with the EPA Interim Method for the Determination of Asbestos in Bulk Insulation Samples (as found in 40 CFR, Part 763, Subpart E, Appendix E) was performed by ACT, an accredited laboratory located in Lenexa, KS.

Samples taken of suspect ACM included: rubberized stair treads, sink undercoating, drywall, vinyl floor tile, sheet vinyl flooring, vinyl cove base, ceiling texture, asphalt roof shingles, window glazing, tar paper, rubberized roof membrane, flashing/caulking, acoustic ceiling tiles, and linoleum flooring. Asbestos was detected in the **sink undercoating**. Please see attached sampling log and PLM analysis results for further details including material type, location, asbestos content, and estimated quantity. A figure is also attached that lays out the floor plan of the structure and where the identified ACM is located.

In addition to asbestos sampling, an inventory was taken of the household hazardous waste (HHW) within the structure. The following HHW was identified:

- 1 Freezer
- 1 Dehumidifier
- 1 qt. Pine Sol
- 32 oz. Wax remover
- 2 qt. Drain cleaner
- 22 oz. Murphy oil soap
- 1 qt. Mop detergent
- 20 oz. Motor oil
- 24 oz. Round-Up Herbicide
- 24 oz. Insecticide
- 2 Fluorescent tube lights
- 2 Fluorescent light ballasts
- 17 oz. Lysol tub cleaner
- 17 oz. Scrubbing Bubbles
- 24 oz. Lysol bowl cleaner
- 16 oz. Mildew stain remover
- 11 oz. Deet bug spray
- 8 oz. Windshield washer fluid
- 40 oz. Mildew stain remover

If you have any questions concerning the work performed, please do not hesitate to contact us at (785) 979-8039 or [spencer.setka@kctestng.com](mailto:spencer.setka@kctestng.com).

Respectfully submitted,



Spencer Setka, GIT  
Project Manager




Ron Wood, RG  
Environmental Services Manager

Attachments: Sampling Log, ACT Sample Analysis Results, Chain of Custody, ACM Location Figure

Asbestos Containing Material ●

SAMPLE ID	MATERIAL	COLOR	SAMPLE RESULT	LOCATION	ESTIMATED QUANTITY
SU-1	SINK UNDERCOAT	BLACK	CHRYSOITILE 3%	KITCHEN DOUBLE SINK	1 SINK
SU-2			CHRYSOITILE 3%		
SU-3			CHRYSOITILE 3%		



**Figure 1**  
 Asbestos Location Map  
 840 N.E. Douglas Street  
 Lee's Summit, MO  
 Project No. E20-20-122



TABLE D-1  
ASBESTOS SAMPLE RESULTS

840 N.E. DOUGLAS STREET

SAMPLE ID	MATERIAL	COLOR	SAMPLE RESULT	LOCATION	ESTIMATED QUANTITY
ST-1	STAIR TREAD	BROWN	ND	STAIRS TO BASEMENT	30SF
ST-2					
ST-3					
SU-1	SINK UNDERCOAT	BLACK	CHRYSOITILE 3%	KITCHEN DOUBLE SINK	1 SINK
SU-2					
SU-3					
DW-1	DRYWALL	WHITE	ND	THROUGHOUT	1200SF
DW-2					
DW-3					
VFT-1	9x9 VINYL FLOOR TILE	RED TILE, YELLOW MASTIC	ND	ENTRY	12SF
VFT-2					
VFT-3					
BVF-1	VINYL FLOOR	GREEN MULTI	ND	1ST FLOOR BATH	36SF
BVF-2					
BVF-3					
BBM-1	BASEBOARD, MASTIC	BROWN BASEBOARD, TAN MASTIC	ND	1ST FLOOR BATH	30LF
BBM-2					
BBM-3					
BVFI-1	VINYL FLOOR	CREAM	ND	2ND FLOOR BATH	22SF
BVFI-2					
BVFI-3					
BBM1-1	BASEBOARD, MASTIC	DARK BROWN BASEBOARD, BROWN MASTIC	ND	2ND FLOOR BATH	8LF
BBM1-2					
BBM1-3					
CTI-1	CEILING TEXTURE	WHITE	ND	2ND FLOOR THROUGHOUT	295SF
CTI-2					
CTI-3					
RS2-1	ROOF SHINGLE	BLACK/GREY	ND	GARAGE ROOF	525SF
RS2-2					
RS2-3					
WG-1	WINDOW GLAZE	WHITE	ND	EXTERIOR HOUSE WINDOWS, EXTERIOR GARAGE WINDOWS	16 TOTAL
WG-2					
WG-3					
TP-1	TAR PAPER	BLACK	ND	EXTERIOR UNDER SIDING	1800SF
TP-2					
TP-3					
RS-1	ROOF SHINGLE	GREY	ND	ROOF	1120SF
RS-2					
RS-3					
RSI-1					

TABLE D-1  
ASBESTOS SAMPLE RESULTS

RSI-2	ROOF SHINGLE	TAN	ND	ROOF	1120SF
RSI-3					
TPI-1	TAR PAPER	BLACK	ND	ROOF TAR PAPER UNDER SHINGLES	1120SF
TPI-2					
TPI-3					
CC-1	CHIMNEY CAULK	BLACK	ND	CHIMNEY VENT (EXTERIOR)	8SF
CC-2					
CC-3					
RM-1	ROOF MATERIAL (RUBBER)	BLACK	ND	W. SIDE OF 2ND FLOOR ROOF	510SF
RM-2					
RM-3					
RP-1	ROOF PAPER	BLACK	ND	W. SIDE OF 2ND FLOOR ROOF	510SF
RP-2					
RP-3					
CT-1	CEILING TILE	WHITE	ND	BASEMENT	300SF
CT-2					
CT-3					
SL-1	STAIR LINOLEUM	RED/BROWN	ND	BASEMENT STAIRS, KITCHEN, FRONT ENTRY	150SF
SL-2					
SL-3					

Notes

- ID Identification
- NA Not applicable
- ND None detected

# ACT

14953 W. 101st Terrace  
Lenexa, Kansas 66215  
913-492-1337

October 14, 2020

KC Testing & Engineering  
1308 Adams  
Kansas City, KS 66103

PROJECT: 840 NE Douglas St.  
REPORT NO. B-74330

Enclosed please find results for bulk samples submitted to our laboratory for asbestos analysis from the above referenced project.

The asbestos analysis was performed using Polarized Light Microscopy (PLM) with dispersion staining in accordance with the required EPA Interim Method for the Determination of Asbestos in Bulk Insulation Samples, as found in 40 CFR, Part 763, Subpart E, Appendix E.

The asbestos fiber type and percentage are reported. The method of measurement is based on calibrated visual estimation. The data provided herein is related only to those samples submitted for analysis. Samples comprised of **greater than one percent (1%) asbestos** are to be considered an asbestos containing material.

Verification by PLM point counting is available upon request. Due to limitations of the PLM microscope and the matrix of floor tile, any floor tile sample found to contain NO asbestos may be verified by TEM analysis upon the client's request. An additional fee will apply.

If samples submitted are not homogeneous, sub-samples of the components are analyzed separately as layers. A composite result may be requested.

This report may not be used by the client to claim product endorsement by NIST, NVLAP or any agency of the U.S. Government. This report shall not be reproduced, except in full, without the written approval of ACT.

If you have any questions, please contact me at 913-492-1337.

Respectfully submitted,



Tami L. Van  
Laboratory Director



NVLAP Lab Code: 101649-0

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>1 / B74330-1</u>		Location of Material: <u>Stair tread</u>	
Layer No.: _____		Description of Material: <u>Brown flat smooth brittle rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>2 / B74330-2</u>		Location of Material: <u>Stair tread</u>	
Layer No.: _____		Description of Material: <u>Brown flat smooth brittle rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>3 / B74330-3</u>		Location of Material: <u>Stair tread</u>	
Layer No.: _____		Description of Material: <u>Brown flat smooth brittle rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>4 / B74330-4</u>		Location of Material: <u>Sink undercoat</u>	
Layer No.: _____		Description of Material: <u>Black tar</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>CHRYBOTILE</b>	<b>3</b>		
			Non-Fibrous Percentage
			Bulk/Binder 97

Sample No./Lab ID: <u>5 / B74330-5</u>		Location of Material: <u>Sink undercoat</u>	
Layer No.: _____		Description of Material: <u>Black tar</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>CHRYBOTILE</b>	<b>3</b>		
			Non-Fibrous Percentage
			Bulk/Binder 97

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson  
 ANALYST: Tami Van

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020  
 Analysis date: 10/14/2020

Sample No./Lab ID: 6 / B74330-6  
 Layer No.: \_\_\_\_\_

Location of Material: Sink undercoat  
 Description of Material: Black tar

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
CHRYSTILE	3			Bulk/Binder 97

Sample No./Lab ID: 7 / B74330-7  
 Layer No.: \_\_\_\_\_

Location of Material: Drywall  
 Description of Material: White chalky/brown fibrous/paint

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
NONE DETECTED		Cellulose	12	Bulk/Binder 88

Sample No./Lab ID: 8 / B74330-8  
 Layer No.: \_\_\_\_\_

Location of Material: Drywall  
 Description of Material: White chalky/brown fibrous/paint

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
NONE DETECTED		Cellulose	12	Bulk/Binder 88

Sample No./Lab ID: 9 / B74330-9  
 Layer No.: \_\_\_\_\_

Location of Material: Drywall  
 Description of Material: White chalky/brown fibrous/paint

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
NONE DETECTED		Cellulose	12	Bulk/Binder 88

Sample No./Lab ID: 10 / B74330-10  
 Layer No.: 1

Location of Material: Vinyl floor tile (9x9)  
 Description of Material: Reddish-brown/gray smooth rubbery

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
NONE DETECTED		Cellulose	3	Bulk/Binder 97

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>10 / B74330-10</u>		Location of Material: <u>Flooring</u>	
Layer No.: <u>2</u>		Description of Material: <u>White chalky</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>10 / B74330-10</u>		Location of Material: <u>Adhesive</u>	
Layer No.: <u>3</u>		Description of Material: <u>Gold brittle</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>10 / B74330-10</u>		Location of Material: <u>Flooring</u>	
Layer No.: <u>4</u>		Description of Material: <u>Red rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>		Cellulose	5
			Non-Fibrous Percentage
			Bulk/Binder 95

Sample No./Lab ID: <u>11 / B74330-11</u>		Location of Material: <u>Vinyl floor tile (9x9)</u>	
Layer No.: <u>1</u>		Description of Material: <u>Reddish-brown/gray smooth rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>		Cellulose	3
			Non-Fibrous Percentage
			Bulk/Binder 97

Sample No./Lab ID: <u>11 / B74330-11</u>		Location of Material: <u>Flooring</u>	
Layer No.: <u>2</u>		Description of Material: <u>White chalky</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>11 / B74330-11</u>		Location of Material: <u>Adhesive</u>	
Layer No.: <u>3</u>		Description of Material: <u>Gold brittle</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>11 / B74330-11</u>		Location of Material: <u>Flooring</u>	
Layer No.: <u>4</u>		Description of Material: <u>Red rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>		Cellulose	5
			Non-Fibrous Percentage
			Bulk/Binder 95

Sample No./Lab ID: <u>12 / B74330-12</u>		Location of Material: <u>Vinyl floor tile (9x9)</u>	
Layer No.: <u>1</u>		Description of Material: <u>Reddish-brown/gray smooth rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>		Cellulose	3
			Non-Fibrous Percentage
			Bulk/Binder 97

Sample No./Lab ID: <u>12 / B74330-12</u>		Location of Material: <u>Adhesive</u>	
Layer No.: <u>2</u>		Description of Material: <u>Gold brittle</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

Sample No./Lab ID: <u>13 / B74330-13</u>		Location of Material: <u>Baseboard</u>	
Layer No.: <u>1</u>		Description of Material: <u>Black smooth rubbery</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Non-Fibrous Percentage
			Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson  
 ANALYST: Tami Van

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020  
 Analysis date: 10/14/2020

Sample No./Lab ID: 13 / B74330-13  
 Layer No.: 2

Location of Material: Adhesive  
 Description of Material: Dk brown brittle

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 14 / B74330-14  
 Layer No.: 1

Location of Material: Baseboard  
 Description of Material: Black smooth rubbery

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 14 / B74330-14  
 Layer No.: 2

Location of Material: Adhesive  
 Description of Material: Dk brown brittle

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 15 / B74330-15  
 Layer No.: 1

Location of Material: Baseboard  
 Description of Material: Black smooth rubbery

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 15 / B74330-15  
 Layer No.: 2

Location of Material: Adhesive  
 Description of Material: Dk brown brittle

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>16 / B74330-16</u>		Location of Material: <u>Vinyl floor</u>	
Layer No.: <u>1</u>		Description of Material: <u>Cream flat smooth pliable</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Bulk/Binder 100

Sample No./Lab ID: <u>16 / B74330-16</u>		Location of Material: <u>Backing</u>	
Layer No.: <u>2</u>		Description of Material: <u>Gray compact fibrous</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>		Cellulose	75
		Fibrous glass	10
			Bulk/Binder 15

Sample No./Lab ID: <u>17 / B74330-17</u>		Location of Material: <u>Vinyl floor</u>	
Layer No.: <u>1</u>		Description of Material: <u>Cream flat smooth pliable</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Bulk/Binder 100

Sample No./Lab ID: <u>17 / B74330-17</u>		Location of Material: <u>Backing</u>	
Layer No.: <u>2</u>		Description of Material: <u>Gray compact fibrous</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>		Cellulose	75
		Fibrous glass	10
			Bulk/Binder 15

Sample No./Lab ID: <u>18 / B74330-18</u>		Location of Material: <u>Vinyl floor</u>	
Layer No.: <u>1</u>		Description of Material: <u>Cream flat smooth pliable</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage
<b>NONE DETECTED</b>			
			Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: 18 / B74330-18  
 Layer No.: 2

Location of Material: Backing  
 Description of Material: Gray compact fibrous

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose	75	Bulk/Binder 15
		Fibrous glass	10	

Sample No./Lab ID: 19 / B74330-19  
 Layer No.: 1

Location of Material: Baseboard  
 Description of Material: Brown smooth rubbery

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 19 / B74330-19  
 Layer No.: 2

Location of Material: Adhesive  
 Description of Material: Dk brown brittle

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 20 / B74330-20  
 Layer No.: 1

Location of Material: Baseboard  
 Description of Material: Brown smooth rubbery

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 20 / B74330-20  
 Layer No.: 2

Location of Material: Adhesive  
 Description of Material: Dk brown brittle

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>21 / B74330-21</u>	Location of Material: <u>Baseboard</u>
Layer No.: <u>1</u>	Description of Material: <u>Brown smooth rubbery</u>

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>		<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>					Bulk/Binder 100

Sample No./Lab ID: <u>21 / B74330-21</u>	Location of Material: <u>Adhesive</u>
Layer No.: <u>2</u>	Description of Material: <u>Dk brown brittle</u>

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>		<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>					Bulk/Binder 100

Sample No./Lab ID: <u>22 / B74330-22</u>	Location of Material: <u>Ceiling texture</u>
Layer No.: _____	Description of Material: <u>White shiny chalky</u>

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>		<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>					Bulk/Binder 100

Sample No./Lab ID: <u>23 / B74330-23</u>	Location of Material: <u>Ceiling texture</u>
Layer No.: _____	Description of Material: <u>White shiny chalky</u>

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>		<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>					Bulk/Binder 100

Sample No./Lab ID: <u>24 / B74330-24</u>	Location of Material: <u>Ceiling texture</u>
Layer No.: _____	Description of Material: <u>White shiny chalky</u>

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>		<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>					Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>25 / B74330-25</u>		Location of Material: <u>Roof shingle</u>		
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>		
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	55	Bulk/Binder 35
		Hair	10	

Sample No./Lab ID: <u>26 / B74330-26</u>		Location of Material: <u>Roof shingle</u>		
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>		
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	55	Bulk/Binder 35
		Hair	10	

Sample No./Lab ID: <u>27 / B74330-27</u>		Location of Material: <u>Roof shingle</u>		
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>		
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	55	Bulk/Binder 35
		Hair	10	

Sample No./Lab ID: <u>28 / B74330-28</u>		Location of Material: <u>Window glaze</u>		
Layer No.: _____		Description of Material: <u>Tan brittle chalky</u>		
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: <u>29 / B74330-29</u>		Location of Material: <u>Window glaze</u>		
Layer No.: _____		Description of Material: <u>Tan brittle chalky</u>		
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>				Bulk/Binder 100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson  
 ANALYST: Tami Van

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020  
 Analysis date: 10/14/2020

Sample No./Lab ID: 30 / B74330-30  
 Layer No.: \_\_\_\_\_

Location of Material: Window glaze  
 Description of Material: Tan brittle chalky

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 31 / B74330-31  
 Layer No.: \_\_\_\_\_

Location of Material: Tar paper  
 Description of Material: Black tarry fibrous

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose	80	Bulk/Binder 10
		Hair	10	

Sample No./Lab ID: 32 / B74330-32  
 Layer No.: \_\_\_\_\_

Location of Material: Tar paper  
 Description of Material: Black tarry fibrous

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose	80	Bulk/Binder 10
		Hair	10	

Sample No./Lab ID: 33 / B74330-33  
 Layer No.: \_\_\_\_\_

Location of Material: Tar paper  
 Description of Material: Black tarry fibrous

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose	80	Bulk/Binder 10
		Hair	10	

Sample No./Lab ID: 34 / B74330-34  
 Layer No.: \_\_\_\_\_

Location of Material: Roof shingle  
 Description of Material: Black fibrous tar / rocks

Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Percentage	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose	55	Bulk/Binder 35
		Hair	10	

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson  
 ANALYST: Tami Van

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020  
 Analysis date: 10/14/2020

Sample No./Lab ID: <u>35 / B74330-35</u>		Location of Material: <u>Roof shingle</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose Hair	Bulk/Binder 35
		55 10	

Sample No./Lab ID: <u>36 / B74330-36</u>		Location of Material: <u>Roof shingle</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose Hair	Bulk/Binder 35
		55 10	

Sample No./Lab ID: <u>37 / B74330-37</u>		Location of Material: <u>Roof shingle</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose Hair	Bulk/Binder 35
		55 10	

Sample No./Lab ID: <u>38 / B74330-38</u>		Location of Material: <u>Roof shingle</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose Hair	Bulk/Binder 35
		55 10	

Sample No./Lab ID: <u>39 / B74330-39</u>		Location of Material: <u>Roof shingle</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar / rocks</u>	
Asbestos Fiber Type	Percentage	Non-Asbestos Fiber Type	Non-Fibrous Percentage
<b>NONE DETECTED</b>		Cellulose Hair	Bulk/Binder 35
		55 10	

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>40 / B74330-40</u>		Location of Material: <u>Tar paper</u>	
Layer No.: _____		Description of Material: <u>Black tarry fibrous</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	Bulk/Binder
		Hair	10
			80
			10

Sample No./Lab ID: <u>41 / B74330-41</u>		Location of Material: <u>Tar paper</u>	
Layer No.: _____		Description of Material: <u>Black tarry fibrous</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	Bulk/Binder
		Hair	10
			80
			10

Sample No./Lab ID: <u>42 / B74330-42</u>		Location of Material: <u>Tar paper</u>	
Layer No.: _____		Description of Material: <u>Black tarry fibrous</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	Bulk/Binder
		Hair	10
			80
			10

Sample No./Lab ID: <u>43 / B74330-43</u>		Location of Material: <u>Chimney caulk</u>	
Layer No.: _____		Description of Material: <u>Gray/brown/black putty</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>			Bulk/Binder
			100

Sample No./Lab ID: <u>44 / B74330-44</u>		Location of Material: <u>Chimney caulk</u>	
Layer No.: _____		Description of Material: <u>Gray/brown/black putty</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>			Bulk/Binder
			100

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson  
 ANALYST: Tami Van

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020  
 Analysis date: 10/14/2020

Sample No./Lab ID: 45 / B74330-45  
 Layer No.: \_\_\_\_\_

Location of Material: Chimney caulk  
 Description of Material: Gray/brown/black putty

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>				Bulk/Binder 100

Sample No./Lab ID: 46 / B74330-46  
 Layer No.: \_\_\_\_\_

Location of Material: Roof material  
 Description of Material: Black fibrous tar

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Synthetic	12	Bulk/Binder 88

Sample No./Lab ID: 47 / B74330-47  
 Layer No.: \_\_\_\_\_

Location of Material: Roof material  
 Description of Material: Black fibrous tar

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Synthetic	12	Bulk/Binder 88

Sample No./Lab ID: 48 / B74330-48  
 Layer No.: \_\_\_\_\_

Location of Material: Roof material  
 Description of Material: Black fibrous tar

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Synthetic	12	Bulk/Binder 88

Sample No./Lab ID: 49 / B74330-49  
 Layer No.: \_\_\_\_\_

Location of Material: Roof paper  
 Description of Material: Black fibrous tar

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Fibrous glass	30	Bulk/Binder 70

## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: <u>50 / B74330-50</u>		Location of Material: <u>Roof paper</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Fibrous glass	Bulk/Binder 70

Sample No./Lab ID: <u>51 / B74330-51</u>		Location of Material: <u>Roof paper</u>	
Layer No.: _____		Description of Material: <u>Black fibrous tar</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Fibrous glass	Bulk/Binder 70

Sample No./Lab ID: <u>52 / B74330-52</u>		Location of Material: <u>Ceiling texture (appears to be tile - TV)</u>	
Layer No.: _____		Description of Material: <u>Brown thick fibrous / paint</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	Bulk/Binder 2

Sample No./Lab ID: <u>53 / B74330-53</u>		Location of Material: <u>Ceiling texture (appears to be tile - TV)</u>	
Layer No.: _____		Description of Material: <u>Brown thick fibrous / paint</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	Bulk/Binder 2

Sample No./Lab ID: <u>54 / B74330-54</u>		Location of Material: <u>Ceiling texture (appears to be tile - TV)</u>	
Layer No.: _____		Description of Material: <u>Brown thick fibrous / paint</u>	
<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	Bulk/Binder 2



## Asbestos Bulk Analysis Laboratory Report

Client Name: KC Testing & Engineering  
 Project Name: 840 NE Douglas St.

REPORT NO.: B-74330  
 RUSH TAT \_\_\_\_\_

Date collected: 10/9/2020  
 Collected by: L. Robertson

Submitted by: L. Robertson  
 Date sample submitted: 10/12/2020

ANALYST: Tami Van

Analysis date: 10/14/2020

Sample No./Lab ID: 57 / B74330-57  
 Layer No.: 2

Location of Material: Backing  
 Description of Material: Gray/black compact fibrous

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
<b>NONE DETECTED</b>		Cellulose	75	Bulk/Binder
		Hair	10	15

Sample No./Lab ID: \_\_\_\_\_  
 Layer No.: \_\_\_\_\_

Location of Material: \_\_\_\_\_  
 Description of Material: \_\_\_\_\_

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
				Bulk/Binder

Sample No./Lab ID: \_\_\_\_\_  
 Layer No.: \_\_\_\_\_

Location of Material: \_\_\_\_\_  
 Description of Material: \_\_\_\_\_

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
				Bulk/Binder

Sample No./Lab ID: \_\_\_\_\_  
 Layer No.: \_\_\_\_\_

Location of Material: \_\_\_\_\_  
 Description of Material: \_\_\_\_\_

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
				Bulk/Binder

Sample No./Lab ID: \_\_\_\_\_  
 Layer No.: \_\_\_\_\_

Location of Material: \_\_\_\_\_  
 Description of Material: \_\_\_\_\_

<u>Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Asbestos Fiber Type</u>	<u>Percentage</u>	<u>Non-Fibrous Percentage</u>
				Bulk/Binder

# ACT

## Environmental

14963 W. 101st Terrace, Lenexa, KS 66215  
(913) 492-1337

### Asbestos Chain of Custody / Analysis Request

1 of 3

Lab Report No.:
B 74330

Customer:	KOTE	Contact:	Lauren Robertson
Address:		Phone:	417-483-7621
City/State/Zip:	Kansas City, KS		
Email:	lauren.robertson@koteching.com		

PLM
<input checked="" type="checkbox"/> Bulk
<input type="checkbox"/> Wipe

PCIM
NIOSH Method 7400

Project: 840 NE Douglas St.  
 900 NE Douglas St.  
 Project No.: E20-20-122 PO No.:

Turnaround Time
Rush/Same Day*
24 Hour

\*Call for availability

Collected by: Lauren Robertson  
 Date: 10-09-2020  
 Report results via:  Phone  Email  
 Date Required: \_\_\_\_\_

\*\*Composite result if Sheetrock/Joint compound sample is positive \_\_\_\_\_

Sample No.	Material Type	ACT Lab ID
ST-1	Stair tread	B74330-1
ST-2	↓	-2
ST-3	↓	-3
SU-1	Sink undercoat	-4
SU-2	↓	-5
SU-3	↓	-6
DW-1	Drywall	-7
DW-2	↓	-8
DW-3	↓	-9
VFT-1	Vinyl floor tile (x9)	-10
VFT-2	↓	-11
VFT-3	↓	-12

Sample No.	Material Type	ACT Lab ID
BBM-1	Baseboard + Mastic	B74330-13
BBM-2	↓	14
BBM-3	↓	15
BVF-1	Vinyl floor	16
BVF-2	↓	17
BVF-3	↓	18
BBM-1	Baseboard + Mastic	-19
BBM-2	↓	20
BBM-3	↓	-21
CTI-1	Ceiling Texture	-22
CTI-2	↓	23
CTI-3	↓	-24

Relinquished by	Date/Time	Received by	Date/Time	Sample Condition: Acceptable <input type="checkbox"/> Other <input type="checkbox"/>
Lauren C. Robertson	10/12/20 12:30	Lauren C. Robertson	10/12/20	840 NE Douglas (labeled bag)
Comments/Instructions				

# ACT

## Environmental

14953 W. 101st Terrace, Lenexa, KS 66215  
(913) 492-1337

### Asbestos Chain of Custody / Analysis Request

2 of 3

Lab Report No.:
B 74330

Customer:	KCTE	Contact:	Lauren Robertson
Address:		Phone:	417-483-7621
City/State/Zip:	Kansas City, KS		
Email:	lauren.robertson@kctesting.com		

PLIM
<input checked="" type="checkbox"/> Bulk
<input type="checkbox"/> Wipe

PCIM
NIOSH Method 7400

Turnaround Time
Rush/Same Day *
24 Hour

\*Call for availability

Collected by: L. Robertson  
Date: 10-9-2020

Project: 840 NE Douglas St.  
900 NE Douglas St  
Project No.: EZO-20-122 PO No.:

Report results via:
Phone _____ Email <input checked="" type="checkbox"/>

Date Required: \_\_\_\_\_

\*\*Composite result if Sheetrock/Joint compound sample is positive \_\_\_\_\_

Sample No.	Material Type	ACT Lab ID
RS2-1	Roof Shingle	B74330-25
RS2-2	↓	-26
RS2-3	↓	-27
WG-1	Window Glaze	-28
WG-2	↓	-29
WG-3	↓	-30
TP-1	Tar Paper	-31
TP-2	↓	-32
TP-3	↓	-33
RS-1	Roof Shingle	-34
RS-2	↓	-35
RS-3	↓	-36

Sample No.	Material Type	ACT Lab ID
RS1-1	Roof Shingle	B74330-37
RS1-2	↓	-38
RS1-3	↓	-39
TPI-1	Tar paper	-40
TPI-2	↓	-41
TPI-3	↓	-42
CC-1	Chimney Caulk	-43
CC-2	↓	-44
CC-3	↓	-45
RM-1	Roof material	-46
RM-2	↓	-47
RM-3	↓	-48

Relinquished by \_\_\_\_\_ Date/Time \_\_\_\_\_ Received by \_\_\_\_\_ Date/Time \_\_\_\_\_ Sample Condition: Acceptable \_\_\_\_\_ Other \_\_\_\_\_

_____	_____
_____	_____

840 NE Douglas  
(labeled bag)  
Comments/Instructions

