

BIM 360://13-20102-00 Lees Summit Middle School 4/13-20102-00_Lee's Summit Middle School 4_ST_2020.rvt

SPECIAL STRUCTURAL INSPECTIONS:

1. IN ACCORDANCE WITH IBC SECTION 1704. AS NOTED BELOW, TESTING AND INSPECTION SHALL BE BY AN INDEPENDENT TESTING/INSPECTION FIRM UNDER THE SUPERVISION OF A LICENSED ENGINEER EMPLOYED BY THAT FIRM. THIS ENGINEER SHALL BE DEEMED THE DESIGNATED ENGINEER OF RECORD FOR SPECIAL INSPECTIONS PERFORMED BY HIS FIRM OR HIS CONSULTANTS. INSPECTORS SHALL BE ICBO CERTIFIED AND APPROVED BY THE BUILDING OFFICIAL.

2. THE DESIGNATED ENGINEER OF RECORD FOR SPECIAL INSPECTIONS SHALL BE RESPONSIBLE FOR DEFINING THE ACTIVITIES OF THE INSPECTORS, FOR CERTIFYING THE QUALIFICATIONS OF THE INSPECTORS WITH THE BUILDING OFFICIAL, AND TO ATTEND THE PRECONSTRUCTION MEETING TO DEFINE THEIR SCOPE OF SERVICES AND THE TESTING OR TEST PROCEDURES THAT ARE REQUIRED AS OUTLINED IN THE INTERNATIONAL BUILDING CODE.

3. SPECIAL INSPECTION IS TO BE PROVIDED IN ADDITION TO THE INSPECTIONS CONDUCTED BY THE LOCAL DEPARTMENT OF BUILDING SAFETY AND SHALL NOT BE CONSIDERED TO RELIEVE THE OWNER OR HIS AUTHORIZED AGENT FROM REQUESTING THE PERIODIC AND CALLED INSPECTIONS REQUIRED BY SECTION 110 OF THE INTERNATIONAL BUILDING CODE.

4. CONCRETE: PER SECTION 1705.3 WITH EXCEPTIONS, THE FOLLOWING ITEMS REQUIRE SPECIAL INSPECTION. ALL CONCRETE EXCEPT SLAB-ON-GRADE, SIDEWALKS, AND DRIVEWAYS. ALL SLABS REQUIRE TESTING FOR FLOOR FLATNESS AND LEVELNESS PER PROJECT SPECIFICATIONS.

8. STEEL CONSTRUCTION: SPECIAL INSPECTIONS SHALL BE IN ACCORDANCE WITH THE QUALITY ASSURANCE INSPECTION REQUIREMENTS OF AISC 360. SPECIAL INSPECTION FOR SEISMIC RESISTANCE SHALL BE IN ACCORDANCE WITH AISC 341 AND SHALL COMPLY WITH IBC SECTION 1705.12. PROVIDE INSPECTION PER IBC SECTION 1704.2.5 FOR STRUCTURAL LOAD-BEARING MEMBERS AND ASSEMBLIES FABRICATED ON THE PREMISES OF A FABRICATOR'S SHOP. THESE INSPECTORS SHALL BE AT THE CONTRACTOR'S EXPENSE IF THE FABRICATOR IS NOT AN APPROVED FABRICATOR PER IBC SECTION 1704.2.5.1.

7. WELDING: WELDING INSPECTION SHALL BE IN COMPLIANCE WITH AWS D1.1, THE BASIS FOR WELDING INSPECTOR QUALIFICATIONS SHALL BE AWS D1.1. PROVIDE SPECIAL INSPECTION IN ACCORDANCE WITH AISC TABLE N5.4-1 THROUGH TABLE N5.4-3.

8. HIGH STRENGTH BOLTING: INSTALLATION OF HIGH STRENGTH BOLTS SHALL BE PERIODICALLY INSPECTED IN ACCORDANCE WITH AISC SPECIFICATIONS. PROVIDE SPECIAL INSPECTION IN ACCORDANCE WITH AISC TABLE N5.6-1 THROUGH TABLE N5.6-3.

9. INSPECTION OF STEEL ELEMENTS OF COMPOSITE CONSTRUCTION PRIOR TO CONCRETE PLACEMENT SHALL BE PER AISC TABLE N6-1.

10. STEEL CONSTRUCTION OTHER THAN STRUCTURAL STEEL SHALL BE PER IBC SECTION 1705.2.2 AND REQUIREMENTS OF SDI QA/QC, AND 1705.2.3 FOR OPEN-WEB STEEL JOISTS AND JOIST GIRDERS.

11. STRUCTURAL MASONRY: MASONRY CONSTRUCTION SHALL BE INSPECTED AND VERIFIED IN ACCORDANCE WITH TMS 402/AO 530/ASCE 5 AND TMS 602/AO 530/ASCE 6 AS FOLLOWS:

a. ENGINEERED MASONRY IN RISK CATEGORY I, II, OR III STRUCTURES: THE MINIMUM SPECIAL INSPECTION PROGRAM FOR MASONRY SHALL COMPLY WITH LEVEL II QUALITY ASSURANCE, TABLE 4.

b. ENGINEERED MASONRY IN RISK CATEGORY IV STRUCTURES: THE MINIMUM SPECIAL INSPECTION PROGRAM FOR MASONRY SHALL COMPLY WITH LEVEL III QUALITY ASSURANCE, TABLE 5.

12. GRADING, EXCAVATION AND FILLING: PER SECTION 1705.6. SEE CIVIL DRAWINGS AND SPECIFICATION DIVISION 2.

13. SPRAY-APPLIED FIREPROOFING: PER SECTION 1705.14. SEE ARCHITECTURAL DRAWINGS FOR ALL FIREPROOFING METHODS AND REQUIREMENTS.

14. FIRE RESISTANT PENETRATIONS AND JOINTS: PER SECTION 1705.17

15. NONBEARING EXTERIOR STUD WALLS AND EXTERIOR VENEER: PER SECTION 1705.12.5 WITH EXCEPTIONS.

16. EXPANSION BOLT, SCREW ANCHOR AND ADHESIVE ANCHOR INSTALLATION TO VERIFY INSTALLATION IN ACCORDANCE WITH ICBO REPORTS NOTED PREVIOUSLY OR APPROVED EQUAL.

17. HEADED CONCRETE SHEAR CONNECTORS: INSPECTED AND TESTED PER AMERICAN WELDING SOCIETY CODE AWS D1.1.

18. CONTINUOUS SPECIAL INSPECTION IS REQUIRED FOR THE INSTALLATION OF ALL STORM SHELTER DOOR, WINDOW AND PROTECTIVE OPENING DEVICES, INCLUDING THE ANCHORAGE TO WALL/ROOF.

19. THE INSPECTOR SHALL OBSERVE THE WORK ASSIGNED TO BE CERTAIN IT CONFORMS TO THE APPROVED DESIGN DRAWINGS AND SPECIFICATIONS.

20. THE INSPECTOR SHALL FURNISH DAILY INSPECTION REPORTS ON THE WORK TO THE BUILDING OFFICIAL AND TO THE ENGINEER. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, AND, IF UNCORRECTED, TO THE ENGINEER AND THE BUILDING OFFICIAL.

21. THE TESTING/INSPECTION FIRMS ENGINEER SHALL COMPLETE, SIGN AND SEAL A FINAL REPORT CERTIFYING THAT TO THE BEST OF HIS KNOWLEDGE, THE WORK IS IN CONFORMANCE WITH THE CONTRACT DOCUMENTS.

22. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE CONSTRUCTION SCHEDULE WITH THE OWNER'S SPECIAL INSPECTION REPRESENTATIVE IN A TIMELY MANNER AND SHALL NOT PROCEED WITH CONSTRUCTION OF COMPONENTS THAT MAY INTERFERE WITH THE INSPECTORS' ABILITY TO PERFORM CODE REQUIRED INSPECTIONS. ANY COST INCURRED ASSOCIATED WITH REMOVAL OF WORK TO PERFORM INSPECTIONS WILL BE BORNE BY THE CONTRACTOR.

23. STEEL DETAILING: THE SPECIAL INSPECTOR SHALL PERFORM AN INSPECTION OF THE STEEL FRAME TO VERIFY COMPLIANCE WITH THE DETAILS SHOWN ON THE APPROVED CONSTRUCTION DOCUMENTS, SUCH AS BRACING, STIFFENING, MEMBER LOCATIONS AND PROPER APPLICATION OF JOINT DETAILS AT EACH CONNECTION.

TABLE 1705.3 REQUIRED VERIFICATION AND INSPECTION OF CONCRETE CONSTRUCTION					IBC REFERENCE
VERIFICATION AND INSPECTION	CONTINUOUS	PERIODIC	REFERENCED STANDARD		
1. Inspect reinforcement, including prestressing tendons, and verify placement	-	X	ACI 318 Ch. 20, 25.2, 26.3, 26.6, 1-26.6.3		1908.4
2. Reinforcing bar welding: a. Verify weldability of reinforcing bars other than ASTM A706 b. Inspect single-pass fillet welds, maximum 5/16", and c. Inspect all other welds	-	X	AWS D1.4 ACI 318, 26.6.4		-
3. Inspection of anchors cast in concrete	-	X	ACI 318, 17.8.2		-
4. Inspection of anchors post-installed in hardened concrete members: a. Adhesive anchors installed in horizontally or upward inclined orientations to resist sustained tension loads b. Mechanical anchors and adhesive anchors not defined in 4-a	X	-	ACI 318, 17.8.2.4		-
5. Verify use of required design mix	-	X	ACI 318 Ch. 19, 26.4.3, 26.4.4		1904.1, 1904.2, 1908.2, 1908.3
6. Prior to concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete	X	-	ASTM C 172 ASTM C 31 ACI 318, 26.5, 26.12		1908.10
7. Inspection of concrete and stone placement for proper application techniques	X	-	ACI 318, 26.5		1908.6, 1908.7, 1908.8
8. Verify maintenance of specified curing temperature and techniques	-	X	ACI 318, 26.5.3, 26.5.5		1908.9
9. Inspect precast concrete for: a. Application of prestressing forces; and b. Grouting of bonded prestressing tendons in the seismic force-resisting system	X	-	ACI 318, 26.10		-
10. Inspect erection of precast concrete members	-	X	ACI 318, 26.9		-
11. Verification of in-situ concrete strength, prior to stressing of tendons in post-tensioned concrete and prior to removal of shores and forms from beams and structural slabs	-	X	ACI 318, 26.11.2		-
12. Inspect formwork for shape, location, and dimensions of the concrete member being formed	-	X	ACI 318, 26.11.1, 21(b)		-

For Sec. 1: 1 inch = 25.4 mm
a. Where applicable, see also Section 1705.12, Special Inspections for seismic resistance.
b. Specific requirements for special inspection shall be included in the research report for the anchor issued by an approved source in accordance with 17.8.2 in ACI 318 or other qualification procedures. Where specific requirements are not provided, special inspection requirements shall be specified by the registered design professional and shall be approved by the building official prior to the commencement of the work.

TABLE 1705.6 REQUIRED VERIFICATION AND INSPECTION OF SOILS			
VERIFICATION AND INSPECTION TASK	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	
1. Verify materials below shallow foundations are adequate to achieve the design bearing capacity	-		X
2. Verify excavations are extended to proper depth and have reached proper material	-		X
3. Perform classification and testing of compacted fill materials	-		X
4. Verify use of proper materials, densities and lift thicknesses during placement and compaction of compacted fill materials	X		-
5. Prior to placement of compacted fill, observe subsgrade and verify that site has been prepared properly	-		X

MASONRY: TMS 402/802-16; Table 3 - Level 2 Quality Assurance				
MINIMUM TESTS				
Prior to construction, verification of compliance of submittals	Art 1.5			
Prior to construction, verification of f'm and f'ACC, except where specifically exempted by the Code	Art 1.4 B			
During construction, verification of Slump flow and Visual Stability Index (VSI) when self-consolidating grout is delivered to the project.	Art 1.5 & 1.6.3			
MINIMUM INSPECTION				
Inspection Task	Frequency (a)	Periodic	Reference for Criteria	
	Continuous	Periodic	TMS 402	TMS 602
1. As masonry construction begins, verify that the following are in compliance: a. Proportions of site-prepared mortar		X	Art. 2.1, 2.6 A & 2.6 C	
b. Grade and size of prestressing tendons and anchorages		X	Art. 2.4 B, 2.4 H	
c. Grade, type and size of reinforcement, connectors, anchor bolts, and prestressing tendons and anchorages		X	Art. 3.4 & 3.6 A	
d. Prestressing technique		X	Art. 3.6 B	
e. Properties of thin-bed mortar for AAC masonry	X(b)	X(c)	Art. 2.1 C.1	
f. Sample panel construction		X	Art. 1.6 D	
2. Prior to grouting, verify that the following are in compliance: a. Grout Splice		X	Art. 3.2 D & 3.2 F	
b. Placement of prestressing tendons and anchorages		X	Sec. 10.8 & 10.9	Art. 2.4 & 3.6
c. Placement of reinforcement, connectors, and anchor bolts		X	Sec. 6.1, 6.3.1	Art. 3.2 E, 3.4 & 3.6 & 6.3.7
d. Proportions of site-prepared grout and prestressing grout for bonded tendons		X	Art. 2.6 B, & 2.4 G.1.b	
3. Verify compliance of the following during construction: a. Materials and procedures with the approved submittals b. Placement of masonry units and mortar joint construction c. Size and location of structural elements d. Type, size, and location of anchors, including other details of anchorage of masonry to structural members, frames, or other construction		X	Art. 1.5	
e. Welding of reinforcement	X		Sec. 6.1 E.1.2	
f. Preparation, construction, and protection of masonry during cold weather (temperature below 40°F (4°C)) or hot weather (temperature above 50°F (32.2°C))	X		Art. 1.8 C, & 1.6 D	
g. Application and measurement of prestressing force		X	Art. 3.6 B	
h. Placement of grout and prestressing grout for bonded tendons is in compliance	X		Art. 3.5 & 3.6 C	
i. Placement of AAC masonry units and construction of thin-bed mortar joints	X(b)	X(c)	Art. 3.3 B & 3.3 F.1.b	
4. Observe preparation of grout specimens, mortar specimens, and/or prisms		X	Art. 1.4 B.2.a.3, 1.4 B.2.b.3, 1.4 B.2.c.3, 1.4 B.3 & 1.4 B.4	

(a) Frequency refers to the frequency of inspection, which may be continuous during the task listed or periodically during the listed task, as defined in the table.
(b) Required for the first 5000 square feet (465 square meters) of AAC masonry.
(c) Required after the first 5000 square feet (465 square meters) of AAC masonry.

AISC 360 TABLE N5.4-1 Inspection Tasks Prior to Welding			
Inspection Tasks Prior to Welding	QC	QA	
Welder qualification records and current records	P	O	
Welding procedure specifications (WPS) available	P	P	
Manufacturer certifications for welding consumables available	P	P	
Material identification (type/grade)	O	O	
Welder identification system 1	O	O	
Fit-up of groove welds (including joint geometry) · Joint preparation · Dimensions (alignment, root opening, root face, bevel) · Cleanliness (condition of steel surfaces) · Testing (lack weld quality and location) · Backing type and fit (if applicable)		O	O
Configuration and finish of access holes		O	O
Fit-up of fillet welds · Dimensions (alignment, gaps at root) · Cleanliness (condition of steel surfaces) · Testing (lack weld quality and location)		O	O
Check welding equipment		O	-
1. The fabricator or erector, as applicable, shall maintain a system by which a welder who has welded a joint or member can be identified. Stamps, if used, shall be the low-stress type. O- Observe these items on a random basis. Operations need not be delayed pending these inspections. P- Perform these tasks for each welded joint or member.			

AISC 360 TABLE N5.4-2 Inspection Tasks During Welding			
Inspection Tasks During Welding	QC	QA	
Control and handling of welding consumables · Packaging · Exposure control		O	O
No welding over cracked tack welds		O	O
Environmental conditions · Wind speed within limits · Precipitation and temperature		O	O
WPS followed Settings on welding equipment · Travel speed · Selected welding materials · Shielding gas type/flow rate · Preheat applied Interpass temperature maintained (min./max.) · Proper position (F, V, H, OH)		O	O
Welding techniques Interpass and final cleaning Each pass within profile limitations Each pass meets quality requirements		O	O
Placement and installation of steel headed stud anchors	P	P	
O- Observe these items on a random basis. Operations need not be delayed pending these inspections. P- Perform these tasks for each welded joint or member.			

AISC 360 TABLE N5.4-3 Inspection Tasks After Welding			
Inspection Tasks After Welding	QC	QA	
Welds cleaned	O	O	
Size, length and location of welds		P	P
Welds meet visual acceptance criteria Crack protection Weldbase-metal fusion Center cross section Weld profiles Weld size Undercut Porosity		P	P
Arc strikes	P	P	
k-area [a]		P	P
Weld access holes in rolled heavy shapes and built-up heavy shapes [b]		P	P
Backing removed and weld tabs removed (if required)		P	P
Repair activities		P	P
Document acceptance or rejection of welded joint or member		P	P
No prohibited welds have been added without the approval of the EOR	O	O	O

[a] When welding of doubler plates, continuity plates or stiffeners has been performed in the k-area, visually inspect the web k-area for cracks within 3 in. (75 mm) of the weld.
[b] After rolled heavy shapes (see Section A3.1c) and built-up heavy shapes (see Section A3.1d) are welded, visually inspect the weld access hole for cracks.

O- Observe these items on a random basis. Operations need not be delayed pending these inspections.
P- Perform these tasks for each welded joint or member.

AISC 360 TABLE N5.6-1 Inspection Tasks Prior to Bolting			
Inspection Tasks Prior to Bolting	QC	QA	
Manufacturer's certifications available for fastener materials	O	P	
Fasteners marked in accordance with ASTM requirements	O	O	
Correct fasteners selected for the joint detail (grade, type, bolt length if threads are to be excluded from shear plane)	O	O	
Correct bolting procedure selected for joint detail	O	O	
Connecting elements, including the appropriate laying surface condition and hole preparation, if specified, meet applicable requirements	O	O	
Pre-installation verification testing by installation personnel observed and documented for fastener assemblies and methods used	P	O	
Proper storage provided for bolts, nuts, washers and other fastener components	O	O	
O- Observe these items on a random basis. Operations need not be delayed pending these inspections. P- Perform these tasks for each welded joint or member.			

AISC 360 TABLE N5.6-2 Inspection Tasks During Bolting			
Inspection Tasks During Bolting	QC	QA	
Fastener assemblies placed in all holes and washers and nuts are positioned as required	O	O	
Joint brought to the snug-tight condition prior to the pretensioning operation	O	O	
Fastener component not turned by the wrench prevented from rotating	O	O	
Fasteners are pretensioned in accordance with the RCSC Specification, progressing systematically from the most rigid joint toward the free edges	O	O	
O- Observe these items on a random basis. Operations need not be delayed pending these inspections. P- Perform these tasks for each welded joint or member.			

AISC 360 TABLE N5.6-3 Inspection Tasks After Bolting			
Inspection Tasks After Bolting	QC	QA	
Document acceptance or rejection of bolted connections	P	P	
O- Observe these items on a random basis. Operations need not be delayed pending these inspections. P- Perform these tasks for each welded joint or member.			

TABLE 1705.2.3 REQUIRED SPECIAL INSPECTIONS OF OPEN-WEB STEEL JOISTS AND JOIST GIRDERS			
TYPE	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	
1. Installation of open-web steel joists and joist girders: a. End Connections - welding or bolting b. Bridging - Horizontal or diagonal	-		X
1. Standard bridging 2. Bridging that differs from the SJI specifications listed in Section 2207.1	-		X

ABBREVIATIONS:
ABBREVIATIONS ARE AS SHOWN IN THE CONTRACT DOCUMENTS WITH THE FOLLOWING EXCEPTIONS:

@ AT
& AND
ANCHOR ROD
ADON ADDITION OR ADDITIONAL
AHU AIR HANDLING UNIT
ADON ADDITIONAL
ANCH ANCHOR
APPROX APPROXIMATE
ARCH ARCHITECTURAL
BLDG BUILDING
BM (S) BEAM (S)
BOT BOTTOM
BRDG BRIDGING
BRG BEARING
BTWN BETWEEN
CANL CHANNEL
CANL CANISTER
CIP CAST-IN-PLACE CONCRETE
CJ CONSTRUCTION/CONTROL JOINT
CJP COMPLETE JOINT PENETRATION
CNTRLINE CENTERLINE
CMU CONCRETE MASONRY UNIT
COL COLUMN
CONC CONCRETE
CONN(S) CONNECTION (S)
CONST CONSTRUCTION
CP CAST
db BAR DIAMETER
DIA DEFORMED BAR ANCHOR
DET DETAIL
DIA DIAMETER
DOW DEFORMED WIRE ANCHOR
DWG (S) DRAWING (S)
EA EACH
EXT EXTENDED END
EJ EXPANSION JOINT
EL ELEVATION
ELEV ELEVATION
EMBED EMBEDMENT
ENGR ENGINEER
EQ EQUIP
EQUIV EQUIVALENT
EQV EQUIVALENT
EW EACH WAY
EXIST EXISTING
EXP EXPANSION
EXT EXTERIOR
FAC FACE
FAB FABRICATE
FC 28 DAY CONCRETE STRENGTH
FD FOUNDATION
FIN FINISH (ED)
FS FLOOR
FTG FOOTING
FTG FOOTING
FV FIELD VERIFY
FY YIELD STRENGTH
GALV GALVANIZED
GEN GENERAL
HGR HANGER
HORIZ HORIZONTAL
HSA HEADED STUD ANCHOR
HSS HOLLOW STRUCTURAL SHAPE
INT INTERIOR
JOINT JOINT
KIPS KIPS
KSF KIPS PER SQUARE FOOT
ZL DOUBLE ANGLE
L ANGLE
LLBB LONG LEG BACK TO BACK
PD (S) POUND (S)
Ld DEVELOPMENT LENGTH
LLH LONG LEG HORIZONTAL
LVV LONG LEG VERTICAL
LWC LIGHT WEIGHT CONCRETE
MAS MASONRY
MAX MAXIMUM
MC MOMENT CONNECTION
MECH MECHANICAL
MEZZ MEZZANINE
MFR MANUFACTURE (R)
MIN MINIMUM
MISC MISCELLANEOUS
NIC NOT IN CONTRACT
NS NEAR SIDE
NTS NOT TO SCALE
NWC NORMAL WEIGHT CONCRETE
OC ON CENTER
OPENING (S) OPENING (S)
OPP OPPOSITE
OPPOSITE HAND
PC PRECAST CONCRETE
PCF POUNDS PER CUBIC FOOT
PL PLATE
PLF POUNDS PER LINEAR FOOT
PRELIM PRELIMINARY
PSF POUNDS PER SQUARE FOOT
PSI POUNDS PER SQUARE INCH
PT POST-TENSION (ED)ING
QTY QUANTITY
RAD / R RADIUS
RE / REF REFERENCE
REINF REINFORCEMENT
REQD REQUIRED
REV REVISION
RTU ROOF TOP UNIT
SC SHEAR CONNECTOR (S)
SCHED SCHEDULE
SECT SECTION
SHT SHEET
SIM SIMILAR
SLBB SHORT LEG BACK TO BACK
SPA SPACE (ING)
SPEC SPECIFICATION (S)
SQ SQUARE
STD STANDARD
STL STEEL
STR STRIP
STRUCT STRUCTURE
SYM SYMMETRICAL
T THRO
T&B TOP AND BOTTOM
TOP OF
TOC TOP OF CONCRETE
TOM TOP OF MASONRY
TOP OF STEEL
TYP TYPICAL
UNO UNLESS NOTED OTHERWISE
VERT VERTICAL
W WIDE FLANGE
WGT WEIGHT
WP WORK POINT
WT STEEL TEE SECTION
WWR WELDED WIRE REINFORCEMENT
X-STR EXTRA STRONG
XX-STR DOUBLE EXTRA STRONG

SYMBOLS AND NOTATIONS


MOMENT CONNECTION	
BEAM SPLICE	
COLLECTOR BEAM AXIAL CONNECTION (TENSION OR COMPRESSION, 15k MIN WHERE AXIAL LOAD NOT INDICATED PER PLAN)	
COLUMN CENTER LINE	
CMU	
COMPOSITE BEAM	
CONCRETE	
EARTH (UNDISTURBED)	
FLOOR OR ROOF SLOPE	
FLOOR STEP IN ELEVATION	
GRAVEL	
STRUCTURED SLAB OR METAL DECK SPAN DIRECTION	
PRECAST CONCRETE	
GROUT	
ROCK	
TOP OF STEEL ELEVATION FROM NOTED TOS	
WELDED WIRE REINFORCEMENT	
KEYNOTE MARK	
COLUMN MARK	
FOOTING MARK	
CONCRETE COLUMN MARK	
STEEL BRACED FRAME BAY	
MATCHLINE	
REVISION MARK	
CROSS REFERENCE	
DETAIL REFERENCE	
DETAIL OR WALL SECTION	
FRAME OR SHEAR WALL ELEVATION	
ELEVATION DATUM MARK	
FLOOR OPENING	
ARCHITECTURAL EXTERIOR/CLADDING LINE	

BN 360/1/13-20102-20 Lee's Summit Middle School 4/13/20102-20 Lee's Summit Middle School 4_ST_2020.rvt
11/4/2020 3:50:40 PM



SHELTER ROOF PLAN (MWFRS)

SCALE: 1/8" = 1'-0"



SHELTER SLAB ON GRADE PLAN (MWFRS)

SCALE: 1/8" = 1'-0"



STRUCTURAL NOTES

GENERAL STORM SHELTER NOTES:

- THE PORTION OF STRUCTURE SHOWN ON THIS SHEET IS BASED ON STRUCTURAL RECOMMENDATIONS LISTED IN ICC 500-2014/CONSAS STANDARD FOR THE DESIGN AND CONSTRUCTION OF STORM SHELTERS. SHELTER HAS NOT BEEN CONSTRUCTED WITHIN AN AREA SUSCEPTIBLE TO FLOODING.
- ALL COMPONENTS THAT MAKE UP THE STORM SHELTER AREA, INCLUDING DEFERRED SUBMITTALS, SHALL BE DESIGNED IN STRICT ACCORDANCE WITH ICC 500 STANDARDS. CALCULATIONS SHALL BE PROVIDED AT EACH CONNECTION FOR VERIFICATION OF LOAD PATH.
- STORM SHELTER WALL AND SLAB ASSEMBLIES HAVE BEEN SELECTED BASED ON ICC 500 AND FEMA 361 RECOMMENDATIONS. NO ADDITIONAL TESTING OR ANALYSIS HAS BEEN PERFORMED TO ESTIMATE THE DYNAMIC IMPACT OF OBJECTS FOUND IN THE ACTUAL ENVIRONMENT AGAINST THE STRUCTURE.
- REFER TO ARCHITECTURAL, CIVIL, MEP DRAWINGS FOR STORM SHUTTERS, DOORS, WINDOWS AND ATTACHMENT OF THESE COMPONENTS TO THE BUILDING STRUCTURE.
- DIAPHRAGM SHEARS HAVE BEEN DISTRIBUTED BASED ON A RIGID DIAPHRAGM ASSUMPTION AND ARE SHOWN AS STRENGTH (ULTIMATE) LEVEL WIND FORCES.
- LOWER LEVEL SLAB-ON-GRADE IS USED AS A STRUCTURAL DIAPHRAGM DISTRIBUTING FORCES TO THE FOUNDATIONS. CONTRACTOR SHALL SUBMIT A POUR PLAN FOR REVIEW SHOWING PLANNED LOCATIONS FOR CONSTRUCTION JOINTS.

SHELTER TYPE:
COMMUNITY TORNADO

WIND LOADS:
IN ACCORDANCE WITH ASCE 7-10, CHAPTER 26 AND 27 DIRECTIONAL PROCEDURE
BASIC WIND SPEED V = 250 MPH
Iw=1.0
PARTIALLY ENCLOSED, EXPOSURE CATEGORY = "C"
Kzt=1.0
Kd=1.0
GCF=+0.55

LIVE LOAD:
ROOF: 100 PSF

LOAD COMBINATIONS:

- ALL WIND LOADS SHOWN ON THIS SHEET ARE STRENGTH (ULTIMATE) LEVEL LOADS AND SHALL BE APPLIED WITH THE FOLLOWING LOAD COMBINATIONS IN ADDITION TO THE STANDARD LOAD COMBINATIONS OF ASCE 7-10 CHAPTER 2. COMBINATIONS INDICATED AS NA ARE SEISMIC LOAD CONDITIONS THAT WILL NOT GOVERN IN THE DESIGN.

LEED	ASD
1) 1.4D	1) D
2) 1.2D + 1.6L + 0.5(Lr or S)	2) D + L
3) 1.2D + 1.6(Lr or S) + 0.5(Wx)	3) D + (Lr or S)
4) 1.2D + 1.0Wx + 1.0(Lr or S)	4) D + 0.75L + 0.75(Lr or S)
5) NA	5) D + 0.6Wx
6) 0.9D + 1.0Wx	6) D + 0.75L + 0.75(0.6Wx) + 0.75(Lr or S)
7) NA	7) 0.6D + 0.6Wx
	8) N/A

ALL LOAD CONDITION DESIGNATIONS ARE PER ASCE 7-10 EXCEPT THE FOLLOWING:
Wx = EXTREME WIND EVENT WIND LOAD

TORNADO MISSILE IMPACT CRITERIA:

- MANUFACTURERS SHALL PROVIDE DATA INDICATING THAT ALL STRUCTURAL PRODUCTS MEET THE IMPACT CRITERIA TEST REQUIRED BY ICC-500 INCLUDING THE IMPACT FROM THE END OF A 15-LB 2x4 AT THE FOLLOWING VELOCITY.

- VERTICAL SURFACES = 100 MPH
- HORIZONTAL SURFACES = 67 MPH

- ALL COMPONENTS OF THE STORM SHELTER ENVELOPE SHALL BE TESTED IN ACCORDANCE WITH ICC-500, SECTION 304 (PRESSURE) AND SECTION 305 (IMPACT).

QUALITY ASSURANCE, SPECIAL INSPECTIONS AND STRUCTURAL OBSERVATIONS

FOR STORM SHELTER (ICC 500-2014):

THE FOLLOWING SPECIAL INSPECTION REQUIREMENTS SHALL BE PERFORMED ON ALL STORM SHELTER COMPONENTS IN ADDITION TO SPECIAL INSPECTION REQUIREMENTS AS STATED IN 2015 IBC ON SHEET S0.2.

- QUALITY ASSURANCE FOR WIND REQUIREMENTS PLAN SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 1705. ALL COMPONENTS MAKING UP THE STRUCTURAL SYSTEM OF THE STORM SHELTER AS FOLLOWS:

- THE MAIN WIND-FORCE-RESISTING SYSTEM THAT IS SUBJECT TO QUALITY ASSURANCE ARE THE:
 - PRECAST CONCRETE ROOF STRUCTURE, INCLUDING ROOF DIAPHRAGM CONNECTIONS, REINFORCEMENT, CHORDS, COLLECTORS, AND CONNECTIONS TO SHEAR WALLS
 - PRECAST CONCRETE SHEAR WALLS INCLUDING CONNECTION TO DIAPHRAGMS, WALL PANEL TO PANEL CONNECTIONS AND PANEL TO FOOTING CONNECTIONS.
 - CONCRETE FOUNDATIONS
 - FABRICATION AND INSTALLATION OF COMPONENTS AND ASSEMBLIES AT SHELTER ENVELOPE REQUIRED TO MEET MISSILE IMPACT TESTING OF ICC 500 INCLUDING DOORS, WINDOWS, AND OPENING PROTECTION DEVICES.

2. SPECIAL INSPECTIONS REQUIRED ARE INDICATED UNDER SPECIAL INSPECTION ON SHEET S0.2 AND THE ADDITIONAL REQUIREMENTS OF SECTION 1706 OF THE IBC. MATERIALS TESTING REQUIRED IS INDICATED UNDER THE SPECIFICATION FOR EACH MATERIAL.

- STRUCTURAL OBSERVATIONS SHALL BE PERFORMED BY A REGISTERED DESIGN PROFESSIONAL EMPLOYED BY THE OWNER TO CONDUCT VISUAL OBSERVATIONS OF THE CONSTRUCTION OF THE STRUCTURAL SYSTEM FOR GENERAL CONFORMANCE TO THE APPROVED CONSTRUCTION DOCUMENTS AT SIGNIFICANT CONSTRUCTION STAGES AND AT COMPLETION OF THE CONSTRUCTION OF THE STRUCTURAL SYSTEM.

- DISTRIBUTION OF OBSERVATION, TESTING AND SPECIAL INSPECTION REPORTS SHALL BE WITHIN TWENTY-FOUR (24) HOURS AFTER EACH SPECIAL INSPECTION, SUBMIT TWO (2) COPIES OF INSPECTION REPORTS TO THE CONTRACTOR, ARCHITECT AND BUILDING OFFICIAL.

- CONTRACTOR RESPONSIBILITY: EACH CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF A MAIN-FORCE RESISTING SYSTEM, OR A WIND-RESISTING COMPONENT LISTED IN THE QUALITY ASSURANCE PLAN, SHALL SUBMIT A WRITTEN CONTRACTOR'S STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND TO THE OWNER PRIOR TO THE COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENTS. THE CONTRACTOR'S STATEMENT OF RESPONSIBILITY SHALL INCLUDE THE FOLLOWING:

- ACKNOWLEDGEMENT OF AWARENESS OF THE SPECIAL REQUIREMENTS CONTAINED IN THE QUALITY ASSURANCE PLAN.
- ACKNOWLEDGE THAT CONTROL WILL BE EXERCISED TO OBTAIN CONFORMANCE WITHIN THE CONSTRUCTION DOCUMENTS APPROVED BY THE BUILDING OFFICIAL.
- PROCEDURES FOR EXERCISING CONTROL WITHIN THE CONTRACTOR'S ORGANIZATION THE METHOD AND FREQUENCY OF REPORTING, AND DISTRIBUTION OF THE REPORTS.
- IDENTIFICATION AND QUALIFICATIONS OF THE PERSON(S) EXERCISING SUCH CONTROL AND THEIR POSITION IN THE ORGANIZATION.

COMPONENT AND CLADDING WIND LOADS:

ALL LOADS SHALL BE CONSIDERED AS POSITIVE OR NEGATIVE.

- WALLS: Wx = 250 PSF (ZONE 4, TYP)
Wx = 300 PSF (ZONE 5, WITHIN 8'-0" OF CORNERS)
- PARAPETS: Wx = 520 PSF (CASE A ZONE 2)
Wx = 520 PSF (CASE A ZONE 3)
Wx = 310 PSF (CASE B INTERIOR)
Wx = 360 PSF (CASE B CORNER)
- ROOFS: Wx = 360 PSF (UPLIFT ZONE 1)
Wx = 240 PSF (UPLIFT ZONE 1)
Wx = 460 PSF (UPLIFT ZONE 2)
Wx = 460 PSF (UPLIFT ZONE 3)
Wx = 140 PSF (POSITIVE ZONE 1 & 1)
Wx = 240 PSF (POSITIVE ZONE 2 & 3)

MAIN WIND FORCE RESISTING SYSTEM LOADS (MWFRS):

Wx = 200 PSF (WINDWARD)
Wx = 160 PSF (LEEWARD)
Wx = 185 PSF (SIDE WALL)
USE 200 PSF AGAINST WALL IN EACH ORTHOGONAL DIRECTION

Wx = 210 PSF (ROOF UPLIFT PRESSURE)
Wx = 250 PSF (WINDWARD NET PARAPET PRESSURE)
Wx = 170 PSF (LEEWARD NET PARAPET PRESSURE)

NOTATIONS:

V = TOTAL DIAPHRAGM SHEAR DUE TO EXTREME WIND EVENT IN DIRECTION INDICATED.
Wd = UNIFORMLY DISTRIBUTED LOAD APPLIED TO ROOF DIAPHRAGM (PERPENDICULAR TO WALL)
Ww = TOTAL SHEAR LOAD RESISTED BY THE ENTIRE LENGTH OF SHEAR WALL FROM DIAPHRAGM FORCE DISTRIBUTION
Wv = DIAPHRAGM SHEAR WALL FORCE OVER THE LENGTH OF THE WALL (PARALLEL TO WALL)

- TO PARAPET PER PLAN
- TO ROOF PER PLAN

Wd= 3,800 PLF

- TO SLAB 100'-0"
- TO FOOTING VARIES

Wd= 3,000 PLF



1
S0.4

SHELTER WINDWARD WALL SECTION (MWFRS)

SCALE: 1/4" = 1'-0"



BM 352/1/13-20102-01 Lee's Summit Middle School 4/13-20102-01_Lee's Summit Middle School_4_ST_2020.rvt
10/19/2020 11:10:54 AM



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64681

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
1 ADDENDUM 002 10/19/20

13-20102-00


GRID GEOMETRY
PLAN

S0.5




DLR Group
© DLR Group
1001 SE Bailey Road
Lee's Summit, MO 64681
Missouri State Certificate of Authority #00939

RELEASE FOR
CONSTRUCTION
AS NOTED ON P.LANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
12/09/2020



 **FOUNDATION PLAN - AREA D**
SCALE: 1/8" = 1'-0"



- 1 8" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES
2 12" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES
3 8" CMU LOAD-BEARING WALL, REINFORCE WITH (1) #5 VERTICAL
@ 16" OC.
4 8" CMU LOAD-BEARING WALL, REINFORCE WITH (2) #5 VERTICAL
@ 8" OC.

LEE'S SUMMIT MI
LEE'S SUMMIT R-7 SCHOOL DISTRICT

13-20102-00

S1.1E



KEY PLAN

A
B
C
D
E
F
G

KEY PLAN

A

□

1

2

,

1

7

7


BIM 360://13-20102-00 Lees Summit Middle School 4/13-20102-00_Lee's Summit Middle School 4_ST_2020.rvt

BM 362/13-20102-00 Lee's Summit Middle School 4/13/20102-00 Lee's Summit Middle School 4_ST_2020.rvt
11/4/2020 3:52:24 PM




FOUNDATION PLAN - AREA F


SCALE: 1/8" = 1'-0"



1. 6" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES.
2. 12" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES.
3. 6" CMU LOAD-BEARING WALL, REINFORCE WITH (1) #5 VERTICAL @ 16" OC.
4. 6" CMU LOAD-BEARING WALL, REINFORCE WITH (2) #5 VERTICAL @ 8" OC.



KEY PLAN



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT


1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64661

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
1 ACCESSION 002 10/19/20
2 PR001 11/11/20

13-20102-00

FOUNDATION
PLAN - AREA F

S1.1F





BM 352/13-20102-01 Lee's Summit Middle School 4/13/20102-01 Lee's Summit Middle School 4 ST_2020.dwt
10/19/2020 11:11:59 AM




FOUNDATION PLAN - AREA G

SCALE: 1/8" = 1'-0"



KEY PLAN



- 1 8" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES.
- 2 12" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES.
- 3 8" CMU LOAD-BEARING WALL, REINFORCE WITH (1) #5 VERTICAL @ 16" OC.
- 4 8" CMU LOAD-BEARING WALL, REINFORCE WITH (2) #5 VERTICAL @ 8" OC.

LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
1 ADDENDUM 002 10/19/20

13-20102-00

FOUNDATION
PLAN - AREA G


S1.1G




DLR Group
© DLR Group
1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081
Missouri State Certificate of Authority #000939

RELEASE FOR
CONSTRUCTION
AS NOTED ON P.LANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
12/09/2020

BM 360/1/19-20102-00 Lee's Summit Middle School 4/19/20102-00_Lee's Summit Middle School_4_ST_2020.dwg
10/7/2020 4:33:22 PM



 **FOUNDATION PLAN - AREA T**
SCALE: 1/8" = 1'-0"



- 1 8" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES.
- 2 12" CMU LOAD-BEARING WALL, REINFORCE PER GENERAL NOTES.
- 3 8" CMU LOAD-BEARING WALL, REINFORCE WITH (1) #5 VERTICAL @ 10' OC
- 4 8" CMU LOAD-BEARING WALL, REINFORCE WITH (2) #5 VERTICAL @ 8' OC.

LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64681

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS

13-20102-00

FOUNDATION
PLAN AREAS S &
T

S1.1S



DLR Group
© DLR Group
1001 SE Bailey Road
Lee's Summit, MO 64681
Missouri State Certificate of Authority #00939

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
12/09/2020



SCALE: 1/8" = 1'-0"


- 
- NORTH

- 




FLOOR FRAMING PLAN - AREA E


BM 350/13-20102-00 Lee's Summit Middle School 4/13/20102-00 Lee's Summit Middle School 4_ST_2020.rvt
11/4/2020 3:55:00 PM



- 1 BOTTOM FLANGE BRACE PER TYPICAL DETAIL, PER 56/54.2 AND 51/55.1
- 2 ROOF HATCH PER ARCHITECTURAL DRAWINGS. PROVIDE 22SS.1
- 3 MECHANICAL UNIT OF MAXIMUM WEIGHT INDICATED, CONFIRM WITH MECHANICAL SUPPLIER.
- 4 GYM EQUIPMENT ALLOWANCE OF WEIGHT INDICATED, CONFIRM WEIGHT AND DETAILS WITH ACTUAL EQUIPMENT SELECTED. CONNECTIONS TO ROOF STRUCTURE IS BY THE GYM EQUIPMENT SUPPLIER.



KEY PLAN



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
1 ADDENDUM 002 10/19/20
2 PR001 11/11/20

13-20102-00

FLOOR AND LOW
ROOF FRAMING
PLAN - AREA F


S2.1F

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
LEE'S SUMMIT, MISSOURI


12/09/2020


DLR Group
© DLR Group
1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081
Missouri State Certificate of Authority #00039





- 1 BOTTOM FLANGE BRACE PER TYPICAL DETAIL PER 56/S4.2 AND S1/S5.1
- 2 ROOF HATCH PER ARCHITECTURAL DRAWINGS. PROVIDE 22/S5.1.
- 3 MECHANICAL UNIT OF MAXIMUM WEIGHT INDICATED, CONFIRM WITH MECHANICAL SUPPLIER.
- 4 GYM EQUIPMENT ALLOWANCE OF WEIGHT INDICATED, CONFIRM WEIGHT AND DETAILS WITH ACTUAL EQUIPMENT SELECTED. CONNECTIONS TO ROOF STRUCTURE IS BY THE GYM EQUIPMENT SUPPLIER.






LEE'S SUMMIT MIDDLE SCHOOL #4
LEE'S SUMMIT R-7 SCHOOL DISTRICT
1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
1 ACADDENUM 002 10/19/20

13-20102-00
ROOF FRAMING
PLAN - AREA D



S2.2D



ROOF FRAMING PLAN - AREA D
SCALE: 1/8" = 1'-0"

- 1 BOTTOM FLANGE BRACE PER TYPICAL DETAIL PER SPS4.2 AND S155.1
- 2 ROOF HATCH PER ARCHITECTURAL DRAWINGS. PROVIDE 22S5.1.
- 3 MECHANICAL UNIT OF MAXIMUM WEIGHT INDICATED. CONFIRM WITH MECHANICAL SUPPLIER
- 4 GYM EQUIPMENT ALLOWANCE OF WEIGHT INDICATED. CONFIRM WEIGHT AND DETAILS WITH ACTUAL EQUIPMENT SELECTED. CONNECTIONS TO ROOF STRUCTURE IS BY THE GYM EQUIPMENT SUPPLIER.

KEY PLAN



- 







-

BM 360/1/13-20102-00 Lee's Summit Middle School 4/13/20102-00_Lee's Summit Middle School_4_ST_2020.rvt
10/7/2020 4:38:15 PM

 **ROOF FRAMING PLAN - AREA S**
SCALE: 1/8" = 1'-0"



 **ROOF FRAMING PLAN - AREA T**
SCALE: 1/8" = 1'-0"



- 1 BOTTOM FLANGE BRACE PER TYPICAL DETAIL PER 56/84.2 AND 51/55.1
- 2 ROOF HATCH PER ARCHITECTURAL DRAWINGS. PROVIDE 22/55.1.
- 3 MECHANICAL UNIT OF MAXIMUM WEIGHT INDICATED, CONFIRM WITH MECHANICAL SUPPLIER.
- 4 GYM EQUIPMENT ALLOWANCE OF WEIGHT INDICATED, CONFIRM WEIGHT AND DETAILS WITH ACTUAL EQUIPMENT SELECTED. CONNECTIONS TO ROOF STRUCTURE IS BY THE GYM EQUIPMENT SUPPLIER.

LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64681

















PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
















13-20102-00

ROOF FRAMING
PLAN - AREAS S &
T





S2.2S







CONC COLUMN SCHEDULE				
MARK	SIZE	VERTICAL REINFORCEMENT	TIES	TYPE
CC1	24 x 24	(6) #5 VERT	#4 TIES @ 3R@12	TYPE 1
CC2	24 x 24	(10) #5 VERT	#4 TIES @ 3R@12	TYPE 2
CC3	36 x 36	(12) #6 VERT	#4 TIES @ 3R@12	TYPE 3
CC4	20 x 20	(6) #6 VERT	#4 TIES @ 3R@12	TYPE 1






A. BEAMS:

1. THE NUMBER SHOWN THIS (NO) FOLLOWING THE BEAM SIZE INDICATES THE NUMBER OF 3/4" HEADED STUDS TO BE PLACED ON THE BEAM. ALL BEAMS (AND GIRDERS) SHALL HAVE HEADED STUDS ATTACHED TO THE TOP FLANGE. IF NO SPECIFIC STUD QUANTITY IS NOTED ON PLANS, THE MAXIMUM STUD SPACING SHALL BE 2'-0". DECK VALLEYS WITHOUT STUDS SHALL BE WELDED.

2. STUD PLACEMENT SHALL BE AS FOLLOWS:

- NUMBER OF STUDS IS LESS THAN THE NUMBER OF DECK VALLEYS. UNIFORMLY SPACE STUDS SYMMETRICALLY WITH THE BEAM CENTERLINE.
- NUMBER OF STUDS IS GREATER THAN THE NUMBER OF DECK VALLEYS. PLACE ONE STUD IN EACH VALLEY STARTING AT THE ENDS OF THE BEAM. WHEN TWO STUDS ARE REQUIRED, PLACE STUDS 1 1/2' EACH SIDE OF THE BEAM WEB.

NOTE: SPACE 'A' TO COORDINATE WITH DECK LAYOUT.



EXAMPLE LAYOUT


11 TYP STUD PLACEMENT DETAIL

S4.2 SCALE: 1/2" = 1'-0"

B. GIRDERS:


1. THE SERIES OF NUMBERS SHOWN THIS (NO, NO, NO) FOLLOWING THE GIRDER SIZE WHEN ADDED TOGETHER, REPRESENT THE TOTAL NUMBER OF STUDS TO BE PLACED ON THE GIRDER. FOR EXAMPLE, (10-3-10) REPRESENTS THE TOTAL OF 23 STUDS TO BE PLACED ON THE GIRDER. THE FIRST AND LAST NUMBERS REPRESENTS THE NUMBER OF STUDS TO BE PLACED BETWEEN THE END OF THE GIRDER AND THE FIRST (OR LAST) INTERSECTING BEAM. THE MIDDLE NUMBER REPRESENTS THE NUMBER OF STUDS TO BE LOCATED BETWEEN THE TWO INTERSECTING BEAMS.

2. PLACE STUDS UNIFORMLY ALONG THE BEAMS OR PORTION OF BEAM INDICATED. CENTER THE STUDS OVER THE WEB AND PROVIDE A MAXIMUM SPACING OF 2'-0" AND A MINIMUM SPACING OF 4'-12". IF THE REQUIRED NUMBER OF STUDS EXCEEDS WHAT CAN BE PLACED AT 4'-12", PLACE A SECOND ROW OF STUDS SPACED AT 4'-12" CENTERS STARTING AT THE END OF THE BEAM UNTIL THE REQUIRED NUMBER OF STUDS IS REACHED. WHEN TWO ROWS OF STUDS ARE REQUIRED, PLACE STUDS 1 1/2' EACH SIDE OF THE BEAM CENTER LINE.



EXAMPLE LAYOUT

EXAMPLE: (10-3-10)




A AT COMP BEAM

B AT COMP GIRDER

13 TYP COMPOSITE BM & GIRDER DETAIL

S4.2 SCALE: 1" = 1'-0"




A EOS <1'-6"


B EOS >1'-6"

14 TYP SLAB EDGE DETAIL

S4.2 SCALE: 3/4" = 1'-0"




NOTE: VERIFY SIZE AND LOCATION WITH MECHANICAL OR ELECTRICAL CONTRACTOR




26 TYP SLAB REENTRANT CORNER DETAIL

S4.2 SCALE: 3/4" = 1'-0"




31 TYP REINFORCING AT FLOOR PENETRATIONS

S4.2 SCALE: 3/4" = 1'-0"




33 TYP WINDOW AT FLOOR SLAB DETAIL

S4.2 SCALE: 3/4" = 1'-0"




34 TYP RAILING DETAIL

S4.2 SCALE: 3/4" = 1'-0"




35 TYP CONSTRUCTION JOINT IN COMPOSITE SLAB

S4.2 SCALE: 3/4" = 1'-0"



36 TYP CONSTRUCTION JOINT IN COMPOSITE SLAB

S4.2 SCALE: 3/4" = 1'-0"




41 BAR TO PLATE WELD SCHEDULE

S4.2 SCALE: 3" = 1'-0"

				SPUCE			
ELECTRODE	PL THICKNESS (IN)	MINIMUM LENGTH OF WELD (IN)				MIN SPLICE LENGTH (IN)	
	BAR SIZE	1/4	5/16	3/8	7/16	1/2	MIN SPLICE LENGTH (IN)
E70	3	1 1/2	1 1/2	1 1/2	1 1/2	1 1/2	3
	4	2	2	2	2	2	4 1/2
	5	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	5 1/4
	6	3	3	3	3	3	6
	7	3 3/4	3 1/4	3 1/4	3 1/4	3 1/4	6 3/4
	8	5	4	3 3/4	3 3/4	3 3/4	7 1/2
	9	6 1/4	5	4 1/4	4 1/4	4 1/4	9
	10	8	6 1/4	5 1/4	4 3/4	4 3/4	9 3/4
11	9 3/4	7 3/4	6 1/2	5 1/2	5 3/4	10 1/2	


42 WELD PARALLEL TO BAR SCHED

S4.2 SCALE: 3" = 1'-0"




43 TYP WF BASE CLOSURE PLATE DETAIL

S4.2 SCALE: 1" = 1'-0"




44 TYP STAIR CONN TO FLOOR SLAB DETAIL

S4.2 SCALE: 3/4" = 1'-0"




45 TYP OPERABLE PARTITION SUPPORT DETAIL

S4.2 SCALE: 3/4" = 1'-0"




A BEAM PARALLEL TO DECK SPAN




51 TYP ELEVATOR SHAFT DETAIL

S4.2 SCALE: 3/4" = 1'-0"




52 TYP SWING SUPPORT DETAIL

S4.2 SCALE: 3/4" = 1'-0"




53 TYP OVERHEAD DOOR SUPPORT DETAIL

S4.2 SCALE: 3/4" = 1'-0"



54 COMPOSITE FLOOR SLAB SCHEDULE


S4.2 SCALE: 3/4" = 1'-0"



B BEAM PERPENDICULAR TO DECK SPAN

56 TYP BOTTOM FLANGE BRACE DETAIL

S4.2 SCALE: 3/4" = 1'-0"



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT


1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS


13-20102-00

FLOOR FRAMING
SECTIONS


S4.5




11 SECTION
S4.7 SCALE: 3/4" = 1'-0"




12 SECTION
S4.7 SCALE: 3/4" = 1'-0"




13 SECTION
S4.7 SCALE: 3/4" = 1'-0"




14 SECTION
S4.7 SCALE: 3/4" = 1'-0"




15 SECTION
S4.7 SCALE: 3/4" = 1'-0"




31 SECTION
S4.7 SCALE: 3/4" = 1'-0"




32 SECTION
S4.7 SCALE: 3/4" = 1'-0"




33 SECTION
S4.7 SCALE: 3/4" = 1'-0"




34 SECTION
S4.7 SCALE: 3/4" = 1'-0"




35 SECTION
S4.7 SCALE: 3/4" = 1'-0"








41 SECTION
S4.7 SCALE: 3/4" = 1'-0"



























42 SECTION
S4.7 SCALE: 1 1/2" = 1'-0"



43 SECTION
S4.7 SCALE: 3/4" = 1'-0"



10/19/2020 11:15:03 AM
B:\320\13-20102-20\Lee's Summit Middle School 4\13-20102-20_Lee's Summit Middle School_4_S1_2020.rvt



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT


1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64081

PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS
1 ACADDOWN 002 10/19/20

13-20102-00
ROOF FRAMING SECTIONS

S5.5






NOTE:
DESIGN JOISTS TO HAVE A MINIMUM
FUNDAMENTAL NATURAL FREQUENCY
GREATER THAN 4 HZ USING MASS
FROM TRUSS SELF WEIGHT PLUS 5 PSF
DEAD LOAD. MAXIMUM TOTAL
DEFLECTION SHALL NOT EXCEED 1/4"
AT HANGER LOCATION UNDER FULL
DESIGN LOADS


BM 320/1/13-20102-00 Lee's Summit Middle School 4/13/2010 2:00 PM Lee's Summit Middle School 4_ST_2020.dwt
10/7/2020 4:39:51 PM

- BRACING CONNECTION NOTES
1. ALL CONNECTIONS SHOWN ARE SCHEMATIC ONLY. FINAL CONNECTION DESIGN CALCULATIONS AND DETAILING SHALL BE PROVIDED BY THE STEEL FABRICATOR'S ENGINEER.
 2. REFER TO PLANS FOR ADDITIONAL SHEAR AND AXIAL REACTIONS NOT SHOWN.
 3. ALL CONNECTIONS SHALL BE DESIGNED IN ACCORDANCE WITH AISC LOAD AND RESISTANCE FACTOR DESIGN (LRFD) TO RESIST FACTORED REACTIONS PROVIDED FOR AN R = 3 SYSTEM.
 4. THE WORKPOINT SHALL BE DEFINED AS THE INTERSECTION OF ALL MEMBER CENTROIDS FRAMING INTO THE JOINT. STEEL SUPPLIER SHALL DESIGN THE CONNECTIONS TO TRANSFER ALL FORCES TO THE WORKPOINT.




12 TYP HSS BRACE CONNECTION DETAIL

S6.1 SCALE: 3/4" = 1'-0"



13 TYP HSS BRACE CONNECTION DETAIL

S6.1 SCALE: 1" = 1'-0"



14 BRACE CONNECTION DETAIL

S6.1 SCALE: 1" = 1'-0"



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD
LEE'S SUMMIT, MO 64681


PACKAGE 3 - BUILDING & SITE
- ISSUE FOR PERMIT
10/08/20
REVISIONS

13-20102-00


BRACED FRAME
TYPICAL DETAILS

S6.1


BM 352/1/15-20102-00 Lee's Summit Middle School 4/15/20102-00 Lee's Summit Middle School 4_ST_2020.rvt
10/7/2020 4:40:02 PM




11
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"




13
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"




14
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"




15
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"




41
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"



42
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"



43
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"



44
S6.3 ELEVATION
SCALE: 1/8" = 1'-0"