



RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

12/14/2020

MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

Re: 2542170
Summit/9 Woodside

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource (Valley Center).

Pages or sheets covered by this seal: I43813071 thru I43813133

My license renewal date for the state of Missouri is December 31, 2021.

Missouri COA: Engineering 001193



December 2, 2020

Sevier, Scott ,Engineer

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813071
2542170	A1	Roof Special	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:19 2020 Page 1

ID:clow4Ylgl7ioX0?ly?5BCcz33zm-nOHGOj7WWhrNpZjXkN44HDKcP3VucBzwOEoDwryDLcl

0-10-8 3-3-8 6-7-8 9-0-3 13-8-0 14-6-1 20-0-0 26-7-14 33-3-13 40-0-0 40-10-8
0-10-8 3-3-8 3-4-0 2-4-11 4-7-13 0-10-1 5-5-15 6-7-14 6-7-14 6-8-3 0-10-8

10x10 =

Scale = 1:89.5



3-3-8 6-7-8 9-0-3 10-1-12 13-8-0 14-6-1 20-1-10 30-0-10 40-0-0
3-3-8 3-4-0 2-4-11 1-1-9 3-6-4 0-10-1 5-7-9 9-11-0 9-11-6

Plate Offsets (X,Y)-- [2:0-3-15,0-2-1], [12:Edge,0-2-4], [15:0-5-7,0-1-8], [18:0-2-4,0-5-4], [25:0-3-8,0-2-0], [28:0-8-0,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.91	Vert(LL)	-0.30 18-19	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.83	Vert(CT)	-0.75 15-17	>636	180	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.93	Horz(CT)	0.33 12	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 213 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
9-13: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2 *Except*
2-28: 2x8 SP 2400F 2.0E, 21-28: 2x6 SPF 2100F 1.8E
18-21: 2x6 SPF No.2, 12-16: 2x4 SPF 1650F 1.5E
WEBS 2x4 SPF No.2 *Except*
3-28: 2x6 SPF No.2
SLIDER Right 2x4 SPF No.2 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-18, 6-18, 3-25
JOINTS 1 Brace at Jt(s): 24

REACTIONS.

(size) 2=0-3-8, 12=(0-3-8 + bearing block) (req. 0-3-9)
Max Horz 2=167(LC 12)
Max Uplift 2=-171(LC 12), 12=-170(LC 13)
Max Grav 2=2270(LC 1), 12=2284(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-7535/636, 3-5=-4738/356, 5-6=-3644/278, 6-7=-2728/280, 7-8=-2816/280,
8-10=-3519/271, 10-12=-3826/287
BOT CHORD 2-28=-696/6843, 27-28=-663/6365, 25-27=-659/6253, 24-25=-342/4068, 20-24=-342/4068,
19-20=-346/4180, 18-19=-173/3154, 7-18=-116/1880, 15-17=0/325, 12-15=-162/3308
WEBS 3-28=-80/1428, 15-18=-119/2659, 8-18=-861/244, 8-15=-12/338, 10-15=-421/192,
6-18=-1214/217, 6-19=-40/842, 5-19=-1239/209, 5-25=-10/644, 3-25=-2220/321

NOTES-

- 2x4 SPF 1650F 1.5E bearing block 12" long at jt. 12 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF 1650F 1.5E.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 20-1-9, Exterior(2R) 20-1-9 to 23-1-9, Interior(1) 23-1-9 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=171, 12=170.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	A2	Roof Special	3	1	I43813072

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:24 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-fAXnE4A1ZvLpIB0lzD80R3VlagtaY_AWJrmQ3byDLcH

0-10-8 3-3-8 6-7-8 8-11-8 13-8-0 14-5-12 20-0-0 25-5-15 25-6-13 30-11-14 31-1-11 36-8-8 40-0-0 40-10-8
0-10-8 3-3-8 3-4-0 2-4-0 4-8-8 0-9-12 5-6-4 5-5-15 0-0-14 5-5-1 0-1-13 5-6-13 3-3-8 0-10-8

6x6 =

Scale = 1:90.5



3-3-8 6-7-8 8-11-8 10-1-12 13-8-0 14-5-12 20-0-0 25-5-15 29-0-5 30-11-14 36-8-8 40-0-0
3-3-8 3-4-0 2-4-0 1-2-4 3-6-4 0-9-12 5-6-4 5-5-15 3-6-6 1-11-9 5-8-10 3-3-8

Plate Offsets (X,Y)-- [2:0-3-15,0-2-1], [12:0-3-15,0-2-1], [14:0-8-0,Edge], [15:0-3-8,0-2-0], [25:0-3-8,0-2-0], [28:0-8-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.90	Vert(LL)	-0.33	18-20	>999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.82	Vert(CT)	-0.73	18-20	>656	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.98	Horz(CT)	0.40	12	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 224 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SPF No.2 *Except*	BOT CHORD Rigid ceiling directly applied.
2-28,12-14: 2x8 SP 2400F 2.0E, 19-28,14-17: 2x6 SPF 2100F 1.8E	WEBS 1 Row at midpt 6-18, 3-25, 8-18, 11-15
17-19: 2x6 SPF No.2	JOINTS 1 Brace at Jt(s): 25
WEBS 2x4 SPF No.2	

REACTIONS. (size) 2=0-3-8, 12=0-3-8
Max Horz 2=165(LC 12)
Max Uplift 2=-170(LC 12), 12=-170(LC 13)
Max Grav 2=2279(LC 1), 12=2279(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-7518/631, 3-5=-4790/356, 5-6=-3654/278, 6-7=-2813/282, 7-8=-2813/281,
8-9=-3654/274, 9-11=-4811/302, 11-12=-7574/471
BOT CHORD 2-28=-691/6824, 27-28=-666/6464, 25-27=-664/6356, 24-25=-345/4118, 21-24=-345/4118,
20-21=-347/4227, 18-20=-172/3165, 16-18=-45/3164, 15-16=-132/4245,
14-15=-370/6512, 12-14=-375/6879
WEBS 3-28=-75/1375, 7-18=-118/1929, 11-14=-6/1391, 6-18=-1154/221, 6-20=-44/760,
5-20=-1277/210, 5-25=-9/679, 3-25=-2269/324, 8-16=-33/769, 8-18=-1157/210,
9-15=0/707, 9-16=-1305/183, 11-15=-2298/241

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 20-0-0, Exterior(2R) 20-0-0 to 23-0-0, Interior(1) 23-0-0 to 40-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Bearing at joint(s) 2, 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=170, 12=170.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813073
2542170	A3	Hip	1	1		


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:29 2020 Page 1

ID:clow4Ylgr7iox0?ly?5BCcz33zm-07KgHnE9ORz5OyvGlmk86CCFhbjDJFT7TBloyDLcC

-0-10-8 3-3-8 6-7-8 10-8-4 13-8-0 14-3-4 18-0-0 22-0-0 29-4-4 36-8-8 40-0-0 40-10-8
0-10-8 3-3-8 3-4-0 4-0-12 2-11-12 0-7-4 3-8-12 4-0-0 7-4-4 7-4-4 3-3-8 0-10-8

Scale = 1:83.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.71	Vert(LL)	-0.32	17	>999	240	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.82	Vert(CT)	-0.71	23-25	>678	180	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.67	Horz(CT)	0.43	11	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 220 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF 1650F 1.5E *Except* 6-7: 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied, except 2-0-0 oc purlins (3-3-2 max.): 6-7.
BOT CHORD 2x4 SPF No.2 *Except* 2-26,11-13: 2x8 SP 2400F 2.0E, 19-26,13-16: 2x6 SPF 2100F 1.8E 16-19: 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SPF No.2 *Except* 3-26,10-13: 2x6 SPF No.2	WEBS 1 Row at midpt 3-22, 6-15, 8-15, 10-14, 5-17 JOINTS 1 Brace at Jt(s): 22

REACTIONS.	(size) 2=0-3-8, 11=0-3-8 Max Horz 2=148(LC 12) Max Uplift 2=174(LC 12), 11=174(LC 13) Max Grav 2=2279(LC 1), 11=2279(LC 1)
-------------------	---

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-7643/632, 3-5=-4451/326, 5-6=-3183/282, 6-7=-2694/290, 7-8=-3184/280, 8-10=-4496/293, 10-11=-7731/488
BOT CHORD	2-26=-678/6956, 25-26=-657/6474, 23-25=-639/6324, 22-23=-639/6324, 18-22=-266/3754, 17-18=-284/3903, 15-17=-71/2694, 14-15=-135/3945, 13-14=-396/6540, 11-13=-395/7041
WEBS	3-26=-53/1471, 3-22=-2594/376, 6-17=-69/868, 7-15=-46/861, 8-15=-1460/239, 8-14=0/678, 10-14=-2619/291, 10-13=0/1507, 5-17=-1414/251, 5-22=0/656

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 18-0-0, Exterior(2E) 18-0-0 to 22-0-0, Exterior(2R) 22-0-0 to 26-2-15, Interior(1) 26-2-15 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Bearing at joint(s) 2, 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=174, 11=174.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813074
2542170	A4	Hip	1	1		


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:34 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-M57ZKVIID_cOVjnDYJKNrAv?hil?ud1_cPByQ0yDLC7

-0-10-8 3-3-8 6-7-8 9-8-12 13-8-0 16-0-0 20-0-0 24-0-0 30-4-4 36-8-8 40-0-0 40-10-8
0-10-8 3-3-8 3-4-0 3-1-4 3-11-4 2-4-0 4-0-0 4-0-0 6-4-4 6-4-4 3-3-8 0-10-8

Scale = 1:80.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.92	Vert(LL)	-0.33	16-18	>999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.82	Vert(CT)	-0.75	16-18	>637	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.50	Horz(CT)	0.42	12	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 219 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied, except
BOT CHORD 2x4 SPF No.2 *Except*	2-0-0 oc purlins (3-1-15 max.): 6-8.
2-27,12-14: 2x8 SP 2400F 2.0E, 20-27,14-17: 2x6 SPF 2100F 1.8E	BOT CHORD Rigid ceiling directly applied.
17-20: 2x6 SPF No.2	WEBS 1 Row at midpt 9-16, 11-15, 5-18, 3-24
WEBS 2x4 SPF No.2 *Except*	JOINTS 1 Brace at Jt(s): 24
3-27,11-14: 2x6 SPF No.2	

REACTIONS.	(size) 2=0-3-8, 12=0-3-8
	Max Horz 2=-132(LC 17)
	Max Uplift 2=-178(LC 12), 12=-178(LC 13)
	Max Grav 2=2279(LC 1), 12=2279(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-7599/623, 3-5=-4615/353, 5-6=-3476/279, 6-7=-2979/282, 7-8=-2980/282, 8-9=-3479/277, 9-11=-4674/318, 11-12=-7654/495
BOT CHORD	2-27=-649/6907, 26-27=-625/6424, 24-26=-620/6291, 23-24=-297/3928, 19-23=-297/3928, 18-19=-302/4062, 16-18=-78/3094, 15-16=-152/4117, 14-15=-391/6466, 12-14=-396/6959
WEBS	3-27=-58/1457, 6-18=-27/1060, 8-16=-35/1055, 9-16=-1334/220, 9-15=0/661, 11-15=-2378/254, 11-14=-5/1472, 5-18=-1278/235, 5-24=0/618, 3-24=-2392/326, 7-18=-432/126, 7-16=-431/127

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 16-0-0, Exterior(2R) 16-0-0 to 20-0-0, Interior(1) 20-0-0 to 24-0-0, Exterior(2R) 24-0-0 to 28-2-15, Interior(1) 28-2-15 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Bearing at joint(s) 2, 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=178, 12=178.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813075
2542170	A5	Hip	1	1		

Builders FirstSource (Valley Center),
Valley Center, KS - 67147,
8.240 s Mar 9 2020 MiTek Industries, Inc.
Tue Dec 1 11:31:37 2020
Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-ngphyXKBVv_zMBWoDRt4ToXXwIE5uaQJNPc1LyDLc4

0-10-8 6-10-3 12-8-0 14-0-0 20-0-0 26-0-0 31-4-4 36-8-8 40-0-0 40-10-8
0-10-8 6-10-3 5-9-13 1-4-0 6-0-0 6-0-0 5-4-4 5-4-4 3-3-8 0-10-8




Plate Offsets (X,Y)--	[2:0-1-3,0-2-10], [2:0-4-9,0-2-1], [2:0-0-3,0-0-0], [6:0-6-0,0-0-15], [8:0-6-0,0-0-15], [12:0-3-15,0-2-1], [14:0-8-0,Edge], [15:0-3-8,0-2-0], [19:0-4-0,0-3-0], [22:0-3-8,0-3-0]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.86	Vert(LL)	-0.30	18	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.85	Vert(CT)	-0.67	18-19	>720	180	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.84	Horz(CT)	0.30	12	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 205 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied, except
BOT CHORD 2x4 SPF 1650F 1.5E *Except*	2-0-0 oc purlins (2-2-0 max.); 6-8.
5-21: 2x4 SPF No.2, 17-19: 2x6 SPF No.2, 12-14: 2x8 SP 2400F 2.0E	BOT CHORD Rigid ceiling directly applied. Except:
14-17: 2x6 SPF 2100F 1.8E	10-0-0 oc bracing: 19-21
WEBS 2x4 SPF No.2	WEBS 1 Row at midpt 11-15
WEDGE	
Left: 2x6 SPF No.2	

REACTIONS. (size) 2=(0-3-8 + bearing block) (req. 0-3-10), 12=0-3-8
Max Horz 2=116(LC 12)
Max Uplift 2=-171(LC 12), 12=-176(LC 13)
Max Grav 2=2294(LC 1), 12=2286(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3957/277, 3-5=-4021/289, 5-6=-3855/328, 6-7=-3701/288, 7-8=-3701/288, 8-9=-3798/276, 9-11=-4912/326, 11-12=-7576/490
BOT CHORD 2-22=-269/3408, 21-22=-18/271, 18-19=-137/3286, 16-18=-56/3295, 15-16=-158/4342, 14-15=-382/6506, 12-14=-391/6875
WEBS 3-22=-572/117, 19-22=-255/3194, 3-19=-42/281, 6-19=-94/884, 6-18=-113/748, 7-18=-656/170, 8-18=-110/749, 8-16=-38/762, 9-16=-1244/183, 9-15=0/705, 11-15=-2198/227, 11-14=-18/1387

- NOTES-**
- 2x4 SPF 1650F 1.5E bearing block 12" long at jt. 2 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF 1650F 1.5E.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCdL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 14-0-0, Exterior(2R) 14-0-0 to 18-2-15, Interior(1) 18-2-15 to 26-0-0, Exterior(2R) 26-0-0 to 30-2-15, Interior(1) 30-2-15 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=171, 12=176.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and conforms to standard ANSI/TPI 1.



December 2,2020

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813075
2542170	A5	Hip	1	1	Job Reference (optional)	

- NOTES-**
- 10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813076
2542170	A6	Hip	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:44 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-40kLQwQas2sziFY88PVjFHKImkiUE6wSwzcUIRyDLbz

Job Reference (optional)

0-10-8 1-7-8 2-3-8 7-1-12 12-0-0 20-0-0 28-0-0 32-4-4 36-8-8 40-0-0 40-10-8
0-10-8 1-7-8 0-8-0 4-10-4 4-10-4 8-0-0 8-0-0 4-4-4 4-4-4 3-3-8 0-10-8

Scale = 1:73.7



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.82	Vert(LL)	-0.31 15 >999	MT20	197/144		
TCDL	20.0	Lumber DOL	1.15	BC	0.81	Vert(CT)	-0.70 13-15 >683	MT20HS	148/108		
BCLL	0.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.35 9 n/a n/a	MT18HS	197/144		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS				Weight: 240 lb	FT = 20%		

LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2 *Except* 4-6: 2x6 SPF No.2, 1-3: 2x8 SP 2400F 2.0E	TOP CHORD	Structural wood sheathing directly applied, except 2-0-0 oc purlins (2-10-0 max.): 4-6.
BOT CHORD	2x4 SPF No.2 *Except* 2-16,11-14: 2x6 SPF 2100F 1.8E, 9-11: 2x8 SP 2400F 2.0E 14-16: 2x6 SPF No.2	BOT CHORD	Rigid ceiling directly applied.
WEBS	2x4 SPF No.2		
OTHERS	2x8 SP 2400F 2.0E		
LBR SCAB	1-3 2x8 SP 2400F 2.0E one side		

REACTIONS.	
(size)	1=0-3-8, 9=0-3-8
Max Horz	1=-104(LC 17)
Max Uplift	1=-151(LC 12), 9=-183(LC 13)
Max Grav	1=2215(LC 1), 9=2273(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD	1-2=-981/119, 2-3=-5118/388, 3-4=-4132/314, 4-5=-4494/329, 5-6=-4494/329, 6-7=-4125/304, 7-8=-5114/364, 8-9=-7456/510
BOT CHORD	2-18=-360/4736, 17-18=-358/4750, 15-17=-183/3604, 13-15=-91/3616, 12-13=-203/4536, 11-12=-393/6399, 9-11=-407/6757
WEBS	4-17=-8725, 4-15=-175/1214, 5-15=-963/240, 6-15=-172/1197, 6-13=-14/764, 8-11=-30/1324, 3-18=0/287, 3-17=-1274/198, 8-12=-1908/194, 7-12=-16/718, 7-13=-1108/162

- NOTES-**
- Attached 7-11-3 scab 1 to 3, front face(s) 2x8 SP 2400F 2.0E with 2 row(s) of 10d (0.131"x3") nails spaced 9" o.c. except : starting at 3-2-15 from end at joint 3, nail 2 row(s) at 2" o.c. for 3-0-5; starting at 0-0-15 from end at joint 3, nail 2 row(s) at 7" o.c. for 2-0-0.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-0-11, Interior(1) 3-0-11 to 12-0-0, Exterior(2R) 12-0-0 to 16-2-15, Interior(1) 16-2-15 to 28-0-0, Exterior(2R) 28-0-0 to 32-4-4, Interior(1) 32-4-4 to 40-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Bearing at joint(s) 1, 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=151, 9=183.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and Conference signed ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813076
2542170	A6	Hip	1	1	Job Reference (optional)	

- NOTES-**
- 10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813077
2542170	A7	Hip	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:47 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-UbQT3xSS9zFYZJHjpY3QtvYGOynkRQ9vcwq8MmyDLbw

-0-10-8	2-3-8	5-10-5	10-0-0	16-3-1	22-4-7	28-4-0	30-0-0	34-11-13	40-0-0	40-10-8
0-10-8	2-3-8	3-6-13	4-1-11	6-3-1	6-1-5	5-11-9	1-8-0	4-11-13	5-0-3	0-10-8

Scale = 1:72.3




Plate Offsets (X, Y)-- [4:0-4-12,0-3-0], [11:0-0-1,0-0-3], [11:0-0-3,0-5-0], [11:0-3-8,Edge], [15:0-2-12,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.82	Vert(LL)	-0.25	3-19	>668	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.58	Vert(CT)	-0.60	3-19	>282	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.89	Horz(CT)	0.22	17	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 162 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
1-4: 2x6 SPF No.2, 4-7: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (6-0-0 max.): 4-9.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. All bearings 0-3-8 except (jt=length) 16=14-3-8, 15=14-3-8, 15=14-3-8.
(lb) - Max Horz 2=88(LC 12)
Max Uplift All uplift 100 lb or less at joint(s) 2, 11 except 16=223(LC 9),
15=179(LC 8)
Max Grav All reactions 250 lb or less at joint(s) 17 except 2=586(LC 25),
11=590(LC 26), 16=3008(LC 25), 15=674(LC 26), 15=375(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-22=-269/98, 3-4=-159/283, 5-6=-276/2500, 6-8=-46/381, 8-9=-43/400,
10-11=-569/129
BOT CHORD 17-19=-1413/275, 16-17=-1413/275, 15-16=-1515/279, 8-15=-407/120, 13-14=-258/0,
11-13=-40/476
WEBS 4-19=-772/173, 5-19=-185/1669, 5-16=-1839/229, 6-16=-1706/178, 6-15=-151/1429,
13-15=-10/345, 9-15=-830/141, 9-13=-61/499, 10-13=-578/170

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-12, Interior(1) 2-1-12 to 10-0-0, Exterior(2R) 10-0-0 to 14-2-15, Interior(1) 14-2-15 to 30-0-0, Exterior(2R) 30-0-0 to 34-2-15, Interior(1) 34-2-15 to 40-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 11 except (jt=lb) 16=223, 15=179.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813078
2542170	A8	Hip	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:52 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-rYDM6fWbzWtrfU9hc5fbazf5szSx6ezelCYv2zyDLbr

-0-10-8 2-3-8 8-0-0 11-8-8 13-10-4 21-0-0 28-1-12 30-3-8 32-0-0 37-8-8 40-0-0 40-10-8
0-10-8 2-3-8 5-8-8 3-8-8 2-1-12 7-1-12 7-1-12 2-1-12 1-8-8 5-8-8 2-3-8 0-10-8

Scale = 1:72.3




Plate Offsets (X,Y)--		[2:0-2-6,0-1-3], [2:0-9-7,0-2-6], [3:0-4-8,Edge], [10:0-4-0,Edge], [11:0-1-2,0-2-3], [11:0-0-6,0-7-7]
LOADING (psf)	SPACING-	2-0-0
TCLL 25.0	Plate Grip DOL	1.15
TCDL 20.0	Lumber DOL	1.15
BCLL 0.0	Rep Stress Incr	YES
BCDL 10.0	Code IRC2018/TPI2014	
CSI.	DEFL.	in (loc) l/defl L/d
TC 0.88	Vert(LL) -0.18 3-23	>918 240
BC 0.71	Vert(CT) -0.41 3-23	>406 180
WB 0.98	Horz(CT) 0.16 11	n/a n/a
Matrix-AS		
PLATES	GRIP	
MT20	197/144	
Weight: 169 lb		FT = 20%

LUMBER-

TOP CHORD 2x6 SPF No.2 *Except*
4-7,7-9: 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2, Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (6-0-0 max.): 4-9.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-20

REACTIONS.

All bearings 0-3-8.
(lb) - Max Horz 2=-70(LC 17)
Max Uplift All uplift 100 lb or less at joint(s) 2, 11 except 20=-155(LC 12),
17=-134(LC 13)
Max Grav All reactions 250 lb or less at joint(s) except 2=720(LC 25), 11=598(LC
26), 20=1754(LC 25), 17=1641(LC 26)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-28=-415/79, 3-4=-692/97, 4-5=-591/120, 5-6=-444/180, 6-8=-444/180, 9-10=-334/95,
10-11=-319/85
BOT CHORD 3-24=-39/292, 3-23=-38/609, 22-23=-426/68, 18-20=-324/52, 17-18=-311/48,
14-15=-409/63, 10-14=0/268
WEBS 4-23=-387/124, 5-23=-114/1161, 20-22=-1646/218, 5-22=-1614/247, 5-18=-109/886,
6-18=-659/183, 8-18=-106/869, 15-17=-1533/197, 8-15=-1529/215, 8-14=-37/864,
9-14=-390/75

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed;
MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-12, Interior(1) 2-1-12 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15,
Interior(1) 12-2-15 to 32-0-0, Exterior(2R) 32-0-0 to 36-2-15, Interior(1) 36-2-15 to 40-10-8 zone; cantilever left and right exposed ;
end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip
DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 11 except
(jt=lb) 20=155, 17=134.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and
referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum
sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:31:56 2020 Page 1
 ID:clow4Ylg7iox0?ly?5BCcz33zm-jkSty0Z51kNG85TSrxjXkpqmmalO2UvDgqW7BkyDLbn
 0-10-8 2-3-8 | 6-0-0 | 11-8-8 | 13-10-4 | 21-0-0 | 28-1-12 | 30-3-8 | 34-0-0 | 37-8-8 | 40-0-0 40-10-8
 0-10-8 2-3-8 | 3-8-8 | 5-8-8 | 2-1-12 | 7-1-12 | 7-1-12 | 2-1-12 | 3-8-8 | 3-8-8 | 2-3-8 0-10-8
 Scale = 1:72.6



REACTIONS. All bearings 0-3-8 except (jt=length) 22=0-6-2 (input: 0-3-8), 19=0-5-12 (input: 0-3-8).
 (lb) - Max Horz 2=-53(LC 13)
 Max Uplift All uplift 100 lb or less at joint(s) except 2=-181(LC 8), 13=-141(LC 9), 22=-649(LC 8), 19=-597(LC 9)
 Max Grav All reactions 250 lb or less at joint(s) except 2=982(LC 21), 13=689(LC 22), 22=3898(LC 21), 19=3668(LC 22)

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) **WARNING:** Required bearing size at joint(s) 22, 19 greater than input bearing size.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 181 lb uplift at joint 2, 141 lb uplift at joint 13, 649 lb uplift at joint 22 and 597 lb uplift at joint 19.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 9) "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.



December 2, 2020

Continued on page 2



 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813079
2542170	A9	Hip Girder	1	1	Job Reference (optional)	

- NOTES-**
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 143 lb down and 107 lb up at 12-0-12, 143 lb down and 107 lb up at 14-0-12, 143 lb down and 107 lb up at 16-0-12, 143 lb down and 107 lb up at 18-0-12, 143 lb down and 99 lb up at 20-0-0, 143 lb down and 107 lb up at 21-11-4, 143 lb down and 107 lb up at 23-11-4, 143 lb down and 107 lb up at 25-11-4, and 143 lb down and 107 lb up at 27-11-4, and 143 lb down and 107 lb up at 29-11-4 on top chord, and 796 lb down and 223 lb up at 6-0-0, and 796 lb down and 223 lb up at 33-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

- LOAD CASE(S)** Standard
- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)
- Vert: 1-3=-90, 3-4=-90, 4-11=-90, 11-12=-90, 12-14=-90, 26-27=-20, 3-24=-20, 18-23=-20, 12-17=-20, 15-30=-20
- Concentrated Loads (lb)
- Vert: 4=-123(B) 7=-143(B) 5=-143(B) 21=-67(B) 18=-67(B) 10=-143(B) 25=-796(B) 22=-67(B) 24=-67(B) 6=-143(B) 9=-143(B) 19=-67(B) 16=-796(B) 11=-123(B) 33=-123(B) 34=-123(B) 35=-143(B) 36=-143(B) 37=-143(B) 38=-143(B) 39=-143(B) 40=-123(B) 41=-89(B) 42=-89(B) 43=-67(B) 44=-67(B) 45=-67(B) 46=-67(B) 47=-67(B) 48=-89(B)

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813080
2542170	B1	Roof Special	3	1		


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:00 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-c5iOnOcc5zticjmD4moTvF_SKB8M_J2pbSUKKVyDLbj

-0-10-8	6-10-3	13-8-0	20-0-0	26-7-14	33-3-13	40-0-0	40-10-8
0-10-8	6-10-3	6-9-13	6-4-0	6-7-14	6-7-14	6-8-3	0-10-8

Scale = 1:76.6



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.91	Vert(LL)	-0.27 17-18	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.93	Vert(CT)	-0.70 14-16	>680	180	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.79	Horz(CT)	0.24 11	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 189 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 1-4,8-12: 2x4 SPF 1650F 1.5E	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SPF No.2 *Except* 2-19,11-15: 2x4 SPF 1650F 1.5E	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SPF No.2	WEBS 1 Row at midpt 5-17, 7-17
WEDGE Left: 2x6 SPF No.2	
SLIDER Right 2x4 SPF No.2 2-0-0	

REACTIONS.	(size) 2=(0-3-8 + bearing block) (req. 0-3-9), 11=(0-3-8 + bearing block) (req. 0-3-9)
	Max Horz 2=-167(LC 17)
	Max Uplift 2=-170(LC 12), 11=-170(LC 13)
	Max Grav 2=2270(LC 1), 11=2284(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-3923/274, 3-5=-3791/286, 5-6=-2759/277, 6-7=-2810/279, 7-9=-3519/270, 9-11=-3825/286
BOT CHORD	2-20=-318/3380, 5-18=-13/692, 17-18=-207/3294, 6-17=-102/1855, 11-14=-161/3308
WEBS	3-20=-428/124, 18-20=-302/3206, 5-17=-1270/240, 14-17=-107/2771, 7-17=-865/245, 7-14=-14/341, 9-14=-421/192

- NOTES-**
- 2x4 SPF 1650F 1.5E bearing block 12" long at jt. 2 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF 1650F 1.5E.
 - 2x4 SPF 1650F 1.5E bearing block 12" long at jt. 11 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF 1650F 1.5E.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 20-1-9, Exterior(2R) 20-1-9 to 23-1-9, Interior(1) 23-1-9 to 40-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 170 lb uplift at joint 2 and 170 lb uplift at joint 11.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813081
2542170	B2	Roof Special	1	1		


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:04 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-Usxudlf79CO85K4_JcsP3V9CeoYjw9pPW4SYTHyDLbf

0-10-8	6-10-3	13-8-0	20-0-0	20-4-0	26-8-5	33-0-11	39-8-8
0-10-8	6-10-3	6-9-13	6-4-0	0-4-0	6-4-5	6-4-5	6-7-13

Scale = 1:73.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.63	Vert(LL)	-0.14	13-15	>999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.71	Vert(CT)	-0.29	13-15	>800		
BCLL 0.0	Rep Stress Incr	YES	WB 0.67	Horz(CT)	0.03	16	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 193 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied. Except:
WEBS 2x4 SPF No.2	1 Row at midpt 7-16
WEDGE	1 Row at midpt 5-16, 6-16, 13-16, 8-16
Left: 2x4 SPF No.2	
SLIDER Right 2x4 SPF No.2 2-0-0	

REACTIONS.	(size) 2=0-3-8, 16=(0-3-8 + bearing block) (req. 0-4-6), 12=Mechanical
	Max Horz 2=175(LC 12)
	Max Uplift 2=96(LC 12), 16=153(LC 12), 12=102(LC 13)
	Max Grav 2=986(LC 25), 16=2777(LC 1), 12=826(LC 26)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-1321/122, 3-5=-599/101, 5-6=0/763, 6-7=0/623, 7-8=0/806, 8-10=-731/176, 10-12=-1006/188
BOT CHORD	2-20=-192/1079, 5-18=-4/571, 16-18=-49/428, 7-16=-534/135, 12-13=-90/892
WEBS	18-20=-184/1031, 3-18=-746/155, 5-16=-1145/229, 6-16=-721/79, 8-16=-994/235, 8-13=-36/694, 10-13=-557/196

- NOTES-**
- 2x4 SPF No.2 bearing block 12" long at jt. 16 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 20-0-0, Exterior(2R) 20-0-0 to 23-0-0, Interior(1) 23-0-0 to 39-8-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 96 lb uplift at joint 2, 153 lb uplift at joint 16 and 102 lb uplift at joint 12.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813082
2542170	B3	Hip	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:07 2020 Page 1

ID:clow4Ylgt7iox0?ly?5BCcz33zm-vRd1Fnh?R7miyopZ_kQ6h7njY0an7SVrC2gC3byDLbc

0-10-8	4-8-15	9-5-8	13-8-12	18-0-0	20-4-0	22-0-0	27-9-11	33-7-5	39-8-8
0-10-8	4-8-15	4-8-9	4-3-4	4-3-4	2-4-0	1-8-0	5-9-11	5-9-11	6-1-3

Scale = 1:76.6




Plate Offsets (X,Y)-- [2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge], [14:0-5-1,Edge], [18:0-3-4,0-3-4]

LOADING (psf)	SPACING-	2:0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.59	Vert(LL)	-0.18 15-17	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.75	Vert(CT)	-0.37 15-17	>625	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.87	Horz(CT)	0.03 18	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 191 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied, except
BOT CHORD 2x4 SPF No.2	2-0-0 oc purlins (10-0-0 max.): 7-9.
WEBS 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied.
WEDGE	WEBS 1 Row at midpt 7-18, 10-17
Left: 2x4 SPF No.2	JOINTS 1 Brace at Jt(s): 24
SLIDER Right 2x4 SPF No.2 2-0-0	

REACTIONS. (size) 2=0-3-8, 18=(0-3-8 + bearing block) (req. 0-3-13), 14=Mechanical
Max Horz 2=157(LC 12)
Max Uplift 2=-104(LC 12), 18=-144(LC 12), 14=-136(LC 13)
Max Grav 2=1099(LC 25), 18=2446(LC 1), 14=974(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1627/145, 3-5=-1466/161, 5-6=-1473/244, 7-8=-16/324, 8-9=0/466, 9-10=-36/344,
10-12=-1033/230, 12-14=-1318/259
BOT CHORD 2-23=-218/1375, 5-21=-408/146, 20-21=-44/597, 17-18=-81/745, 18-24=-658/75,
8-24=-339/52, 15-17=-31/645, 14-15=-157/1168
WEBS 21-23=-185/1372, 6-21=-168/1103, 6-20=-904/221, 7-20=-75/868, 7-18=-1083/126,
10-17=-1008/205, 10-15=0/604, 12-15=-473/173, 9-24=-407/49

NOTES-

- 2x4 SPF No.2 bearing block 12" long at jt. 18 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 18-0-0, Exterior(2E) 18-0-0 to 22-0-0, Exterior(2R) 22-0-0 to 26-2-15, Interior(1) 26-2-15 to 39-8-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 104 lb uplift at joint 2, 144 lb uplift at joint 18 and 136 lb uplift at joint 14.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813083
2542170	B4	Hip	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:10 2020 Page 1

ID:clow4Ylgr7ioX0?ly?5BCcz33zm-J0JAupktk28HpFX8ftzpJmPCIdfEKwWHu?vsgwyDLbZ

0-10-8	4-8-15	9-5-8	16-0-0	20-4-0	24-0-0	31-8-8	39-8-8
0-10-8	4-8-15	4-8-9	6-6-8	4-4-0	3-8-0	7-8-8	8-0-0

Scale = 1:74.4




Plate Offsets (X,Y)-- [2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge], [12:0-5-1,Edge], [17:0-3-4,Edge], [20:0-6-0,0-2-12]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d			PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.06	13-28	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.51	Vert(CT)	-0.16	13-28	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.40	Horz(CT)	0.04	17	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 186 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x4 SPF No.2
 SLIDER Right 2x4 SPF No.2 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
 2-0-0 oc purlins (6-0-0 max.): 6-8.
 BOT CHORD Rigid ceiling directly applied. Except:
 1 Row at midpt 7-17
 WEBS 1 Row at midpt 5-19, 6-17, 8-15, 10-15

REACTIONS.

(size) 2=0-3-8, 17=(0-3-8 + bearing block) (req. 0-3-12), 12=Mechanical
 Max Horz 2=142(LC 12)
 Max Uplift 2=136(LC 12), 17=82(LC 12), 12=165(LC 13)
 Max Grav 2=1103(LC 25), 17=2409(LC 1), 12=979(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1627/205, 3-5=-1480/248, 5-6=-543/193, 6-7=0/359, 7-8=-271/281, 8-10=-466/263,
 10-12=-1284/295
 BOT CHORD 2-22=-253/1372, 5-20=-2/474, 19-20=-224/1299, 17-19=-28/347, 7-17=-1358/119,
 15-16=-271/40, 13-15=-172/1115, 12-13=-172/1115
 WEBS 20-22=-224/1305, 5-19=-1096/228, 6-19=-37/664, 6-17=-1172/130, 8-15=-392/41,
 10-15=-995/204, 10-13=0/328, 7-15=-69/1143

NOTES-

- 2x4 SPF No.2 bearing block 12" long at jt. 17 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 16-0-0, Exterior(2R) 16-0-0 to 20-5-12, Interior(1) 20-5-12 to 24-0-0, Exterior(2R) 24-0-0 to 28-2-15, Interior(1) 28-2-15 to 39-8-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 136 lb uplift at joint 2, 82 lb uplift at joint 17 and 165 lb uplift at joint 12.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2,2020


WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:11 2020 Page 1
 ID:clow4Ylgf7iox0?ly?5BCcz33zm-nCsY59IWVLG8RP6KDaU2rxOcd?B3HCR7fePDNyDLbY
 -0-10-8 4-5-12 8-11-2 14-0-0 20-4-0 26-0-0 32-8-8 39-8-8
 0-10-8 4-5-12 4-5-7 5-0-14 6-4-0 5-8-0 6-8-8 7-0-0
 Scale = 1:74.6



LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x4 SPF No.2
 SLIDER Right 2x4 SPF No.2 2-0-0

BRACING-	
TOP CHORD	Structural wood sheathing directly applied, except: 2-0-0 oc purlins (6-0-0 max.): 6-8.
BOT CHORD	Rigid ceiling directly applied. Except: 1 Row at midpt 7-16

REACTIONS. (size) 11=Mechanical, 2=0-3-8, 16=(0-3-8 + bearing block) (req. 0-3-11)
 Max Horz 2=126(LC 12)
 Max Uplift 11=154(LC 13), 2=-142(LC 12), 16=-79(LC 12)
 Max Grav 11=987(LC 26), 2=1126(LC 25), 16=2364(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD
2-3=-1680/218, 3-5=-1614/270, 5-6=-849/203, 6-7=-678/217, 7-8=-495/265,
8-9=-686/250, 9-11=-1343/275

BOT CHORD
2-21=-252/1423, 5-19=-22/437, 18-19=-227/1394, 7-16=-2248/150, 12-13=-164/1178,
11-12=-164/1178

WEBS
3-21=-280/111, 19-21=-244/1351, 5-18=-894/189, 7-18=-127/1196, 7-13=-66/1062,
8-12=-276/48, 9-13=-811/173, 9-12=0/268

NOTES-

- 1) 2x4 SPF No.2 bearing block 12" long at jt. 16 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
- 2) Unbalanced roof live loads have been considered for this design.
- 3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDF=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 14-0-0, Exterior(2R) 14-0-0 to 18-2-15, Interior(1) 18-2-15 to 26-0-0, Exterior(2R) 26-0-0 to 30-2-15, Interior(1) 30-2-15 to 39-8-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 4) Provide adequate drainage to prevent water ponding.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 154 lb uplift at joint 11, 142 lb uplift at joint 2 and 79 lb uplift at joint 16.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2, 2020



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813085
2542170	B6	Hip	1	1		


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:14 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-CnYgjAnOoGejlrvuj2ITcZsFqyZGcKtpdt3phyDLbV

0-10-8	3-11-6	6-11-6	12-0-0	16-2-0	20-4-0	28-0-0	33-8-8	39-8-8
0-10-8	3-11-6	3-0-0	5-0-10	4-2-0	4-2-0	7-8-0	5-8-8	6-0-0

Scale = 1:73.2



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	-0.12 16-18	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.74	Vert(CT)	-0.23 16-18	>999	180	MT18HS	197/144
BCLL 0.0	Rep Stress Incr	YES	WB 0.93	Horz(CT)	0.05 16	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 173 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied, except
BOT CHORD 2x4 SPF No.2	2-0-0 oc purlins (5-3-13 max.): 5-8.
WEBS 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied.
WEDGE	
Left: 2x4 SPF No.2	
SLIDER Right 2x4 SPF No.2 2-0-0	

REACTIONS.	(size) 11=Mechanical, 2=0-3-8, 16=(0-3-8 + bearing block) (req. 0-3-12)
	Max Horz 2=110(LC 12)
	Max Uplift 11=-140(LC 13), 2=-138(LC 12), 16=-118(LC 9)
	Max Grav 11=964(LC 26), 2=1108(LC 25), 16=2400(LC 1)

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-1634/209, 3-4=-1910/300, 4-5=-1107/201, 5-6=-901/212, 6-7=0/350, 7-8=-691/246, 8-9=-862/230, 9-11=-1326/249
BOT CHORD	2-21=-232/1383, 4-19=-37/436, 18-19=-278/1731, 16-18=-68/434, 7-16=-1348/190, 13-15=-274/38, 12-13=-151/1171, 11-12=-151/1171
WEBS	4-18=-942/211, 6-18=-37/731, 6-16=-1164/171, 7-13=-80/1184, 8-13=-259/93, 9-13=-590/141, 3-21=-471/120, 19-21=-224/1338, 3-19=-34/326

- NOTES-**
- 2x4 SPF No.2 bearing block 12" long at jt. 16 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
 - Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 12-0-0, Exterior(2R) 12-0-0 to 16-2-0, Interior(1) 16-2-0 to 28-0-0, Exterior(2R) 28-0-0 to 32-2-15, Interior(1) 32-2-15 to 39-8-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 11, 138 lb uplift at joint 2 and 118 lb uplift at joint 16.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:19 2020 Page 1

ID:clow4Ylqf7jox0?lv?5BCcz33zm-YILZnurXcpH?OeithGewAfHIOrevx_lczvagVvyDLbO



FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD
2-3=-3263/446, 3-4=-1428/197, 4-5=-677/158, 5-6=0/526, 6-8=-485/218, 8-9=-831/224,
9-10=-1017/214, 10-12=-1318/264

BOT CHORD
2-22=-458/2942, 21-22=-443/2768, 19-21=-120/1158, 17-19=-58/674, 6-17=-1417/174,
15-16=-465/71, 13-15=-45/485, 12-13=-170/1179

WEBS
3-22=-287/12, 3-21=-1616/328, 4-21=0/464, 4-19=-637/79, 5-19=0/463, 5-17=-1493/173,
6-15=-112/1277, 8-15=-81/125, 8-13=-14/542, 10-13=-418/141

- 1) 2x4 SPF No.2 bearing block 12' long at jt. 17 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
- 2) Unbalanced roof live loads have been considered for this design.
- 3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 10-0-0, Exterior(2R) 10-0-0 to 14-2-15, Interior(1) 14-2-15 to 30-0-0, Exterior(2R) 30-0-0 to 34-2-15, Interior(1) 34-2-15 to 39-8-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 4) Provide adequate drainage to prevent water ponding.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 133 lb uplift at joint 12, 129 lb uplift at joint 2 and 169 lb uplift at joint 17.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 12) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2, 2020



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813087
2542170	B8	Roof Special	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:22 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-zK1iPvtPvkfaF5SSMOBdolvJB3md8FV2ftpV5EyDLbN

Job Reference (optional)

0-10-8	3-3-8	8-0-0	13-4-12	16-6-0	20-0-0
0-10-8	3-3-8	4-8-8	5-4-12	3-1-4	3-6-0

Scale = 1:38.8



LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.50	Vert(LL)	-0.05 11-12 >999 240	MT20		197/144	
TCDL	20.0	Lumber DOL	1.15	BC	0.41	Vert(CT)	-0.11 11-12 >999 180				
BCLL	0.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.04 9 n/a n/a				
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							
								Weight: 87 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 2-12: 2x6 SPF No.2
 WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and
 2-0-0 oc purlins (10-0-0 max.): 4-5.
 BOT CHORD Rigid ceiling directly applied.

REACTIONS.

All bearings 6-11-14 except (jt=length) 2=0-3-8.
 (lb) - Max Horz 2=161(LC 9)
 Max Uplift All uplift 100 lb or less at joint(s) 7, 2 except 9=203(LC 12), 8=199(LC 25)
 Max Grav All reactions 250 lb or less at joint(s) 7, 8 except 2=664(LC 1), 9=1598(LC 1), 9=1598(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1583/233, 3-4=-557/84, 4-5=-154/601, 5-6=-145/728
 BOT CHORD 2-12=-397/1407, 11-12=-372/1307, 9-11=-124/416
 WEBS 3-12=-54/383, 3-11=-899/255, 4-11=-0/360, 4-9=-1171/250, 6-9=-909/206, 6-8=-67/308

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-0-0, Exterior(2R) 8-0-0 to 11-0-0, Interior(1) 11-0-0 to 16-6-0, Exterior(2R) 16-6-0 to 19-6-0, Interior(1) 19-6-0 to 19-10-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 7, 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 2 except (jt=lb) 9=203, 8=199.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813088
2542170	B9	Half Hip Girder	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:32 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-gFeUVK?hYov9SeDNyVMzCPJ?s54Jur2WyRE0SfyDLbD

Job Reference (optional)

-0-10-8	3-3-8	6-0-0	9-8-8	13-0-0
0-10-8	3-3-8	2-8-8	3-8-8	3-3-8

Scale = 1:25.2




Plate Offsets (X,Y)-- [2-0-3-3,0-2-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	-0.08	9-10	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.19	9-10	>817	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.53	Horz(CT)	0.12	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 54 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 2-10: 2x6 SPF 2100F 1.8E, 8-10: 2x4 SPF 1650F 1.5E
 WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-7-2 oc purlins, except end verticals, and 2-0-0 oc purlins (3-10-5 max.): 4-6.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 7=0-3-8
 Max Horz 2=123(LC 7)
 Max Uplift 2=-200(LC 8), 7=-284(LC 5)
 Max Grav 2=1326(LC 1), 7=1539(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3900/637, 3-4=-2809/479, 4-5=-1845/335, 5-6=-1789/318, 6-7=-1484/320
 BOT CHORD 2-10=-624/3485, 9-10=-588/3287, 8-9=-473/2466
 WEBS 3-10=-109/762, 3-9=-819/174, 4-9=-131/1001, 4-8=-729/134, 5-8=-767/229, 6-8=-410/2143

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Bearing at joint(s) 2, 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=200, 7=284.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 228 lb down and 115 lb up at 6-0-0, 204 lb down and 115 lb up at 8-0-0, and 202 lb down and 116 lb up at 10-0-0, and 189 lb down and 126 lb up at 12-0-0 on top chord, and 527 lb down and 113 lb up at 6-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard



December 2, 2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	B9	Half Hip Girder	1	1	I43813088
Job Reference (optional)					

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-4=-90, 4-6=-90, 10-11=-20, 8-10=-20, 7-8=-20

Concentrated Loads (lb)

Vert: 4=-204(F) 8=-9 9=-527(F) 14=-204(F) 15=-202(F) 16=-189(F) 17=-6(F) 18=-30

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	C1	Roof Special Girder	1	2	I43813089

Builders FirstSource (Valley Center),
Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc.
Tue Dec 1 11:32:37 2020
Page 1


ID:clow4Ylgf7iox0?ly?5BCcz33zm-0CRNY23pNLYSZP5Kk2y8vS0mt6m394FG6ixn7syDLb8

2-0-4
3-3-8
6-7-14
10-0-4
10-9-4
14-1-10
17-6-0
18-9-4
20-9-8

2-0-4
1-3-4
3-4-6
3-4-6
0-9-0
3-4-6
3-4-6
1-3-4
2-0-4

5x5 =
6x6 =

Scale = 1:44.7



Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	C1	Roof Special Girder	1	2	I43813089
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:37 2020 Page 2
ID:c1ow4Yl9f7iox0?ly?5BCcz33zm-0CRNY23pNLYSZP5Kk2y8vS0mt6m394FG6ixn7syDLb8

NOTES-

- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 25=736, 9=803.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 12) Use Simpson Strong-Tie HUS26 (14-16d Girder, 6-16d Truss) or equivalent at 4-0-12 from the left end to connect truss(es) to back face of bottom chord.
- 13) Use Simpson Strong-Tie LUS26 (4-SD9112 Girder, 4-SD9212 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 6-0-12 from the left end to 8-0-12 to connect truss(es) to back face of bottom chord.
- 14) Use Simpson Strong-Tie LUS26 (4-10d Girder, 4-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 10-0-12 from the left end to 18-0-12 to connect truss(es) to back face of bottom chord.
- 15) Fill all nail holes where hanger is in contact with lumber.
- 16) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 79 lb down and 2 lb up at 0-0-12, and 825 lb down and 103 lb up at 20-0-12 on top chord, and 128 lb down and 52 lb up at 2-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)
 - Vert: 3-24=-90, 3-4=-90, 4-8=-90, 24-26=-160, 7-8=-160, 25-33=-160, 22-33=-110, 10-22=-20, 10-40=-110, 9-40=-160
- Concentrated Loads (lb)
 - Vert: 16=-892(B) 13=-927(B) 8=-825(B) 24=-133(B) 27=-2253(B) 28=-1024(B) 29=-1024(B) 30=-904(B) 31=-919(B) 32=-864(B)


 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:42 2020 Page 1
 ID:clow4Ylgf7iox0?ly?5BCcz33zm-NAEGclYcTAlfA_ixbYJcWkmz7YaqSh?F_yFp4yDLb3
 0-10-8 4-2-9 8-4-12 12-4-12 16-6-15 20-9-8 21-8-0
 0-10-8 4-2-9 4-2-3 4-0-0 4-2-3 4-2-9 0-10-8
 Scale = 1:37.3



BRACING-	
TOP CHORD	Structural wood sheathing directly applied, except 2-0-0 oc purlins (4-11-8 max.): 4-5.
BOT CHORD	Rigid ceiling directly applied.

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-1874/217, 3-4=-1556/181, 4-5=-1319/195, 5-6=-1555/181, 6-7=-1874/217
BOT CHORD	2-11=-155/1602, 9-11=-47/1319, 7-9=-136/1602
WEBS	3-11=-328/130, 4-11=0/310, 5-9=0/310, 6-9=-328/130

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-4-12, Exterior(2E) 8-4-12 to 12-4-12, Exterior(2R) 12-4-12 to 16-8-14, Interior(1) 16-8-14 to 21-8-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=100, 7=100.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2.2020



Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601.



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	143813091
2542170	C3	Hip Girder	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:46 2020 Page 1

ID:clow4YlGf7iox07ly?5BCcz33zm-GxUnR7ATF6gA8nH3mRdFmMuNlkWmEdaAcDmyryDLb?

0-10-8	3-2-9	6-4-12	10-4-12	14-4-12	17-6-15	20-9-8	21-8-0
0-10-8	3-2-9	3-2-3	4-0-0	4-0-0	3-2-3	3-2-9	0-10-8

Scale = 1:37.3




Plate Offsets (X,Y)-- [2:0-0-0,0-2-1], [4:0-6-12,0-1-4], [6:0-6-12,0-1-4], [8:0-0-0,0-2-1], [11:0-3-8,0-4-12], [13:0-3-8,0-4-12]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL 1.15		TC	0.68	Vert(LL)	-0.13	12	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL 1.15		BC	0.53	Vert(CT)	-0.27	12	>909	180	MT20HS	148/108
BCLL	0.0	Rep Stress Incr NO		WB	0.26	Horz(CT)	0.06	8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 99 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
4-6: 2x4 SPF 1650F 1.5E
BOT CHORD 2x6 SPF 2100F 1.8E
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SP No.3, Right: 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-3-1 oc purlins, except
2-0-0 oc purlins (2-9-4 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 8=0-3-8
Max Horz 2=-56(LC 34)
Max Uplift 2=-456(LC 8), 8=-456(LC 9)
Max Grav 2=2614(LC 1), 8=2614(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-4462/799, 3-4=-4709/891, 4-5=-4795/893, 5-6=-4795/893, 6-7=-4709/892,
7-8=-4462/800
BOT CHORD 2-15=-714/3917, 13-15=-714/3917, 12-13=-745/4168, 11-12=-690/4168, 10-11=-659/3917,
8-10=-659/3917
WEBS 3-15=-420/116, 3-13=-243/487, 4-13=-199/1067, 4-12=-172/881, 5-12=-770/201,
6-12=-172/881, 6-11=-199/1067, 7-11=-244/487, 7-10=-420/115

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=456, 8=456.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 929 lb down and 243 lb up at 6-4-12, and 929 lb down and 243 lb up at 14-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

Continued on page 2



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	C3	Hip Girder	1	1	I43813091
Job Reference (optional)					

LOAD CASE(S)
Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)

Vert: 1-4=-90, 4-6=-90, 6-9=-90, 16-19=-20
- Concentrated Loads (lb)

Vert: 4=-114(F) 6=-114(F) 13=-929(F) 12=-119(F) 5=-114(F) 11=-929(F) 22=-114(F) 23=-114(F) 24=-119(F) 25=-119(F)




Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813092
2542170	CJ1	Diagonal Hip Girder	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:49 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-gW9v48CLY13l?F0eRZAyO_W_Fx?kzb61sarQXAYDLay



Scale = 1:22.1

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.32	Vert(LL)	-0.03	8	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.36	Vert(CT)	-0.06	8	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.28	Horz(CT)	0.03	7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP						Weight: 31 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 2-8: 2x6 SPF No.2
 WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-11-3 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-4-3, 7=Mechanical
 Max Horz 2=116(LC 5)
 Max Uplift 2=-96(LC 4), 7=-85(LC 8)
 Max Grav 2=606(LC 1), 7=549(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1349/187
 BOT CHORD 2-8=-213/1245, 7-8=-202/1168
 WEBS 3-8=-4/335, 3-7=-1217/231

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 7.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) "NAILED" indicates 3-10d (0.148"x3") or 2-12d (0.148"x3.25") toe-nails per NDS guidelines.
- 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 110 lb down and 83 lb up at 5-7-7, and 110 lb down and 83 lb up at 5-7-7 on top chord. The design/selection of such connection device(s) is the responsibility of others.
- 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
 Uniform Loads (plf)
 Vert: 1-4=-90, 4-5=-40, 8-9=-20, 6-8=-20
 Concentrated Loads (lb)
 Vert: 13=-140(F=-70, B=-70) 14=2(F=1, B=1)



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813093
2542170	CJ2	Diagonal Hip Girder	2	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:52 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-45r2iAEDryRKsilD7hjf0d8NM9?SAy9TTY448VyDLav




Plate Offsets (X,Y)--	[2:0-0-3,0-0-15], [3:0-3-0,0-3-4], [8:0-3-8,0-1-8]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.71	Vert(LL)	-0.12	10	>845	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.42	Vert(CT)	-0.25	10	>397	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.26	Horz(CT)	0.13	8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP						Weight: 35 lb	FT = 20%

LUMBER-

TOP CHORD 2x6 SPF 2100F 1.8E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-10-4 oc bracing.

REACTIONS.

(size) 2=0-4-9, 8=Mechanical
Max Horz 2=129(LC 4)
Max Uplift 2=154(LC 4), 8=174(LC 8)
Max Grav 2=740(LC 1), 8=735(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-1303/270
BOT CHORD 3-9=-359/1391, 8-9=-354/1378
WEBS 4-8=-1521/391

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=154, 8=174.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Use Simpson Strong-Tie TJC37 (4 nail, 30-90) or equivalent at 5-7-7 from the left end to connect truss(es) to front face of bottom chord, skewed 45.0 deg. to the left, sloping 0.0 deg. down.
- Use Simpson Strong-Tie TJC37 (4 nail 90-150) or equivalent at 5-7-7 from the left end to connect truss(es) to back face of bottom chord, skewed 45.0 deg. to the right, sloping 0.0 deg. down.
- Fill all nail holes where hanger is in contact with lumber.
- "NAILED" indicates 3-10d (0.148"x3") or 2-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-90, 3-5=-90, 5-6=-40, 10-11=-20, 3-7=-20
Concentrated Loads (lb)
Vert: 10=-93(F=-46, B=-46) 9=-361(F=-181, B=-181)



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813094
2542170	CJ3	Diagonal Hip Girder	2	1	Job Reference (optional)	

LOAD CASE(S)
Standard
Concentrated Loads (lb)
Vert: 12=-168(F=-84, B=-84) 13=-404(F=-202, B=-202)

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813095
2542170	CJ4	Diagonal Hip Girder	2	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:32:59 2020 Page 1
ID:clow4Ylqf7iox0?ly?5BCcz33zm-NRmhAZKcC5JKCnnZ1fLlo5xhuzHdJ6jV97GyubyDLao




Plate Offsets (X,Y)-- [2:0-3-14,0-5-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	-0.04	7-8	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.83	Vert(CT)	-0.09	7-8	>999	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.33	Horz(CT)	0.01	7	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 32 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-7-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 7=Mechanical, 2=0-4-9
Max Horz 2=134(LC 7)
Max Uplift 7=-161(LC 8), 2=-163(LC 4)
Max Grav 7=722(LC 1), 2=727(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1046/219
BOT CHORD 2-8=-220/937, 7-8=-220/937
WEBS 3-8=-82/412, 3-7=-1030/273

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=161, 2=163.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Use Simpson Strong-Tie TJC37 (4 nail, 30-90) or equivalent at 5-7-7 from the left end to connect truss(es) to front face of bottom chord, skewed 45.0 deg.to the left, sloping 0.0 deg. down.
- Use Simpson Strong-Tie TJC37 (4 nail 90-150) or equivalent at 5-7-7 from the left end to connect truss(es) to back face of bottom chord, skewed 45.0 deg.to the right, sloping 0.0 deg. down.
- Fill all nail holes where hanger is in contact with lumber.
- "NAILED" indicates 3-10d (0.148"x3") or 2-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-90, 4-5=-40, 6-9=-20



December 2,2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813095
2542170	CJ4	Diagonal Hip Girder	2	1	Job Reference (optional)	


LOAD CASE(S) Standard
 Concentrated Loads (lb)
 Vert: 12=-87(F=-41, B=-46) 13=-344(F=-165, B=-179)

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813096
2542170	CJ5	Diagonal Hip Girder	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:02 2020 Page 1

ID:clow4Ylgt7iox0?ly?5BCcz33zm-o0SqobMVU0hv3FW8ioy?QkZ9UBQuWXgr5VcVvyDLal



Scale: 3/4"=1'

Plate Offsets (X,Y)-- [2:0-3-14,0-5-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	0.05	6-9	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.41	Vert(CT)	-0.09	6-9	>642	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	0.02	2	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 17 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-1-13 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 6=Mechanical, 2=0-3-8
Max Horz 6=88(LC 7)
Max Uplift 6=68(LC 8), 2=-103(LC 4)
Max Grav 6=299(LC 1), 2=422(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6 except (jt=lb) 2=103.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- "NAILED" indicates 3-10d (0.148"x3") or 2-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-90, 3-4=-40, 5-7=-20
Concentrated Loads (lb)
Vert: 10=-57(F=-29, B=-29)



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813097
2542170	D1	Common	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:03 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-GD0C0xN7FKpmgO5KGVQEyx5Noah8FwI54IE91MyDLak

5-0-3	10-0-0	14-8-8	19-8-8
5-0-3	4-11-13	4-8-8	5-0-0

Scale = 1:36.5




Plate Offsets (X,Y)--		[1:0-0-3,0-5-0], [1:0-0-1,0-0-3], [6:0-3-8,Edge], [7:0-4-0,0-3-4]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 25.0	Plate Grip DOL 1.15	TC 0.31	in (loc) l/defl L/d
TCDL 20.0	Lumber DOL 1.15	BC 0.73	Vert(LL) -0.13 7-14 >999 240
BCLL 0.0	Rep Stress Incr YES	WB 0.30	Vert(CT) -0.29 7-14 >829 180
BCDL 10.0	Code IRC2018/TPI2014	Matrix-AS	Horz(CT) 0.04 6 n/a n/a
		PLATES MT20	
		GRIP 197/144	
		Weight: 69 lb FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x4 SPF No.2
 SLIDER Right 2x4 SPF No.2 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied.
 BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 6=Mechanical, 1=0-3-8
 Max Horz 1=82(LC 12)
 Max Uplift 6=-73(LC 13), 1=-75(LC 12)
 Max Grav 6=1084(LC 1), 1=1084(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1742/260, 2-3=-1293/198, 3-4=-1280/200, 4-6=-1625/249
 BOT CHORD 1-7=-177/1486, 6-7=-156/1396
 WEBS 2-7=-509/174, 3-7=-26/614, 4-7=-428/163

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 10-0-0, Exterior(2R) 10-0-0 to 13-0-0, Interior(1) 13-0-0 to 19-8-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 1.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813098
2542170	D2	Hip	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:06 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-gohLeyP0YFCLXspvxe_xaZjl1okQSJUXmjTqehyDLah

Job Reference (optional)



Scale = 1:35.8




Plate Offsets (X,Y)--		[1:0-3-8,Edge], [1:0-0-3,0-5-0], [1:0-0-1,0-0-3], [2:1-6-4,0-2-0], [3:0-4-0,0-1-15], [5:0-5-1,Edge]										
LOADING (psf)		SPACING-2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-0.09	8-15	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.22	8-15	>999	180	MT18HS	197/144
BCLL	0.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.03	1	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 66 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied, except
BOT CHORD	2x4 SPF No.2		2-0-0 oc purlins (4-8-4 max.): 2-3.
WEBS	2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied.
WEDGE			
Left: 2x4 SPF No.2			
SLIDER	Right 2x4 SPF No.2 2-0-0		

REACTIONS. (size) 5=Mechanical, 1=0-3-8
Max Horz 1=65(LC 12)
Max Uplift 5=-77(LC 13), 1=-80(LC 12)
Max Grav 5=1084(LC 1), 1=1084(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1605/186, 2-3=-1265/214, 3-5=-1471/184
BOT CHORD 1-8=-92/1308, 6-8=-94/1303, 5-6=-82/1271
WEBS 2-8=0/254, 3-6=0/250

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 8-0-0, Exterior(2E) 8-0-0 to 12-0-0, Exterior(2R) 12-0-0 to 16-2-15, Interior(1) 16-2-15 to 19-8-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 1.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813099
2542170	D3	Hip Girder	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:16 2020 Page 1
ID:clow4Ylg77iox0?ly?5BCcz33zm-Njl7kNXHBKSwkOaqXk9H_g8VMqBkoqh?4HuL?6yDLax



Scale = 1:33.5



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.64	Vert(LL)	-0.11	10	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.51	Vert(CT)	-0.23	10	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.22	Horz(CT)	0.05	7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MS						Weight: 90 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except*	TOP CHORD Structural wood sheathing directly applied or 2-6-10 oc purlins, except
3-5: 2x4 SPF 1650F 1.5E	2-0-0 oc purlins (2-11-4 max.): 3-5.
BOT CHORD 2x6 SPF 2100F 1.8E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	
WEDGE	
Right: 2x4 SPF No.2	

REACTIONS.	(size) 1=0-3-8, 7=Mechanical
Max Horz 1=49(LC 8)	
Max Uplift 1=-357(LC 8), 7=-363(LC 9)	
Max Grav 1=2287(LC 1), 7=2323(LC 1)	

FORCES.	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	1-2=-3987/646, 2-3=-4218/716, 3-4=-4323/706, 4-5=-4323/706, 5-6=-4105/698, 6-7=-3707/607
BOT CHORD	1-13=-586/3496, 12-13=-586/3496, 10-12=-603/3738, 9-10=-545/3654, 8-9=-499/3238, 7-8=-499/3238
WEBS	2-13=-390/93, 2-12=-209/464, 3-12=-114/877, 3-10=-128/805, 4-10=-829/260, 5-10=-140/904, 5-9=-97/760, 6-9=-196/667, 6-8=-551/110

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=357, 7=363.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 167 lb down and 107 lb up at 6-0-0, 143 lb down and 107 lb up at 8-0-12, 143 lb down and 99 lb up at 10-0-0, and 143 lb down and 107 lb up at 11-11-4, and 167 lb down and 107 lb up at 14-0-0 on top chord, and 761 lb down and 174 lb up at 6-0-0, and 761 lb down and 174 lb up at 13-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).



December 2,2020

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813099
2542170	D3	Hip Girder	1	1	Job Reference (optional)	

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-90, 3-5=-90, 5-7=-90, 14-17=-20

Concentrated Loads (lb)


Vert: 3=-143(F) 5=-143(F) 12=-761(F) 4=-143(F) 10=-67(F) 9=-761(F) 20=-143(F) 21=-143(F) 22=-67(F) 23=-67(F)

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813100
2542170	E1	Hip Girder	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:17 2020 Page 1

ID:clow4Ylgl7ioX0?ly?5BCcz33zm-rvsVjYvydanMY904RgWXugnFEbKXI48lxdvXYyDLaW



Scale = 1:19.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.25	Vert(LL)	-0.01 6	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.23	Vert(CT)	-0.02 6	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.15	Horz(CT)	0.01 4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP					Weight: 28 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x6 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-5-4 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 4=0-3-8
Max Horz 2=-37(LC 13)
Max Uplift 2=-142(LC 8), 4=-142(LC 9)
Max Grav 2=808(LC 1), 4=808(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1089/219, 3-4=-1089/218
BOT CHORD 2-6=-158/901, 4-6=-158/901
WEBS 3-6=-108/606

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=142, 4=142.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 579 lb down and 191 lb up at 3-8-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-90, 3-5=-90, 7-10=-20
Concentrated Loads (lb)
Vert: 3=-45(F) 6=-579(F)



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813101
2542170	E2	Common	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:19 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-olzFNPZ9UFqVbsJPCsi_cJm8u1HI?DIRmF60bQyDLaU



Scale = 1:17.7




Plate Offsets (X,Y)--										[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge], [4:0-0-1,0-0-3], [4:0-0-3,0-5-0], [4:0-3-8,Edge]											
LOADING (psf)		SPACING-		2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP			
TCLL	25.0	Plate Grip DOL		1.15		TC 0.18		Vert(LL)		-0.01		6-9		>999		240		MT20		197/144	
TCDL	20.0	Lumber DOL		1.15		BC 0.17		Vert(CT)		-0.01		6-9		>999		180					
BCLL	0.0	Rep Stress Incr		YES		WB 0.04		Horz(CT)		0.00		2		n/a		n/a					
BCDL	10.0	Code IRC2018/TPI2014				Matrix-AS												Weight: 24 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE

Left: 2x4 SPF No.2, Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 2=0-3-8, 4=0-3-8
Max Horz 2=37(LC 12)
Max Uplift 2=-46(LC 12), 4=-46(LC 13)
Max Grav 2=496(LC 1), 4=496(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-484/176, 3-4=-484/176
BOT CHORD 2-6=-54/368, 4-6=-54/368

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-9-8, Exterior(2R) 3-9-8 to 6-11-11, Interior(1) 6-11-11 to 8-5-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J1	Truss Type Jack-Open	Qty 15	Ply 1	Summit/9 Woodside I43813102
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:22 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-CtfO?Qc2nAD3SJ2_t?GhExOYiFFCCadtSCLgClyDLaR



Scale = 1:20.7

Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 25.0	Plate Grip DOL 1.15	TC 0.59	in (loc) l/defl L/d
TCDL 20.0	Lumber DOL 1.15	BC 0.44	Vert(LL) 0.07 4-7 >956 240
BCLL 0.0	Rep Stress Incr YES	WB 0.00	Vert(CT) -0.16 4-7 >454 180
BCDL 10.0	Code IRC2018/TPI2014	Matrix-AS	Horz(CT) 0.03 2 n/a n/a
			PLATES MT20
			GRIP 197/144
			Weight: 16 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=123(LC 12)
Max Uplift 3=82(LC 12), 2=-23(LC 12)
Max Grav 3=233(LC 1), 2=411(LC 1), 4=116(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-11-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J2	Truss Type Jack-Open	Qty 5	Ply 1	Summit/9 Woodside Job Reference (optional)	I43813103
----------------	-------------	-------------------------	----------	----------	---	-----------

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:34:18 2020 Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-Ze2ZlaHAbNG7AwKI9IGqVli4lpJrKvU7KwvdAWyDLZZ



Scale = 1:20.7

Plate Offsets (X,Y)--										[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge], [3:0-4-4,Edge]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL.		in (loc)		l/defl		L/d		PLATES		GRIP			
TCLL	25.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	0.11	3-5	>645	240	MT20		197/144						
TCDL	20.0	Lumber DOL	1.15	BC	0.60	Vert(CT)	-0.21	3-5	>333	180									
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.15	5	n/a	n/a									
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 18 lb		FT = 20%						

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=123(LC 12)
Max Uplift 4=-68(LC 12), 2=-22(LC 12), 5=-1(LC 12)
Max Grav 4=213(LC 1), 2=413(LC 1), 5=118(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-0-5, Interior(1) 2-0-5 to 5-11-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2, 5.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J3	Truss Type Jack-Closed	Qty 4	Ply 1	Summit/9 Woodside I43813104
----------------	-------------	---------------------------	----------	----------	--------------------------------

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:35:10 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-2eBDgMvnLLpPwlkCgC0cjs4_n9DVQMnH0VO_VyDLYI



Scale = 1:15.7

Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge], [3:0-3-0,0-2-7]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.30
TCDL 20.0	Lumber DOL	1.15	BC 0.20
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MR
DEFL.	in (loc)	l/defl	L/d
Vert(LL)	-0.02	8	>999
Vert(CT)	-0.03	8	>999
Horz(CT)	0.03	7	n/a
PLATES	GRIP		
MT20	197/144		
Weight: 14 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 7=Mechanical, 2=0-3-8
Max Horz 2=67(LC 9)
Max Uplift 7=39(LC 12), 2=25(LC 12)
Max Grav 7=209(LC 1), 2=289(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-0-5, Interior(1) 2-0-5 to 3-10-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J4	Truss Type Jack-Closed	Qty 6	Ply 1	Summit/9 Woodside I43813105
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:35:54 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-l6rrvPRO_sMVhgfBnw_LO?heTWD1pKFFPs9jYxyDLY3

-0-10-8
0-10-8
1-10-15
1-10-15

Scale = 1:10.7




Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	-0.00	9	>999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	-0.00	9	>999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	2	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP					Weight: 8 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 5=Mechanical
Max Horz 2=48(LC 11)
Max Uplift 2=-24(LC 12), 5=-16(LC 12)
Max Grav 2=200(LC 1), 5=75(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J5	Truss Type Jack-Closed	Qty 4	Ply 1	Summit/9 Woodside Job Reference (optional)
----------------	-------------	---------------------------	----------	----------	---

I43813106

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:36:25 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-L4DZP?pqhOG6vRX95w2c8XTxe0oGaLwpXBAs7eyDLXa

-0-10-8
0-10-8

2-3-11
2-3-11

Scale = 1:11.7




Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07
TCDL 20.0	Lumber DOL	1.15	BC 0.04
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-MP
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.00 9 >999 240
			Vert(CT) -0.00 9 >999 180
			Horz(CT) 0.00 2 n/a n/a
			PLATES
			MT20
			GRIP
			197/144
			Weight: 9 lb
			FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-3-11 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 6=Mechanical, 2=0-3-8
 Max Horz 2=55(LC 11)
 Max Uplift 6=22(LC 12), 2=23(LC 12)
 Max Grav 6=112(LC 1), 2=207(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job 2542170	Truss J6	Truss Type Jack-Closed	Qty 4	Ply 1	Summit/9 Woodside Job Reference (optional)
----------------	-------------	---------------------------	----------	----------	---

I43813107

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:37:12 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-T6YKG4OJcqBR2fdBLIOdYVsvxzoI5cZkL?3rGQyDLWr

0-10-8 4-3-11
0-10-8 4-3-11

Scale = 1:16.7




Plate Offsets (X,Y)-- [2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.25	Vert(LL)	0.02	6-9	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.20	Vert(CT)	-0.03	6-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.01	2	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 15 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 6=Mechanical, 2=0-3-8
Max Horz 2=93(LC 11)
Max Uplift 6=-41(LC 12), 2=-29(LC 12)
Max Grav 6=230(LC 1), 2=309(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 4-3-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	J7	Jack-Open	5	1	I43813108
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:39:50 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-rW63R5IQPN50?xiYcUDhymSt?fdy63L?gaKcQgYDLUN



Scale = 1:21.7




Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL 1.15	TC 0.51	DEFL. in (loc) l/defl L/d
TCDL 20.0	Lumber DOL 1.15	BC 0.63	Vert(LL) 0.13 6-9 >592 240
BCLL 0.0	Rep Stress Incr YES	WB 0.02	Vert(CT) -0.26 6-9 >294 180
BCDL 10.0	Code IRC2018/TPI2014	Matrix-AS	Horz(CT) 0.04 2 n/a n/a
			PLATES MT20
			GRIP 197/144
			Weight: 20 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
 BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
 Max Horz 2=128(LC 12)
 Max Uplift 4=-54(LC 12), 2=-24(LC 12), 5=-15(LC 12)
 Max Grav 4=204(LC 1), 2=433(LC 1), 5=139(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 6-4-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2, 5.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	J8	Jack-Closed	2	1	I43813109
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:41:03 2020 Page 1

ID:clow4Ylgr7iox0?ly?5BCcz33zm-CZ0f3BDDplfG9naNJ1oP9_QN4eJj4lkSRWYuXyDLTE

-0-10-8
0-10-8
3-10-15
3-10-15

Scale = 1:15.7




Plate Offsets (X,Y)--	[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.20	Vert(LL)	-0.01	6-9	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	-0.02	6-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.01	2	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP						Weight: 14 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 6=Mechanical, 2=0-3-8
Max Horz 2=85(LC 11)
Max Uplift 6=-37(LC 12), 2=-28(LC 12)
Max Grav 6=208(LC 1), 2=288(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-10-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J9	Truss Type Jack-Closed	Qty 1	Ply 1	Summit/9 Woodside I43813110
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:41:46 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-Sq6wnmiB50jZwmZrPrJufEGp8PMSHXO3LdRKuYyDLSZ



Scale = 1:10.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.03	Vert(LL)	-0.00 6	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	-0.00 6	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00 4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MR						
								Weight: 5 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-7-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 4=Mechanical, 6=Mechanical
Max Horz 6=42(LC 9)
Max Uplift 4=-15(LC 12), 6=-2(LC 12)
Max Grav 4=69(LC 1), 6=79(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 6.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	J10	Jack-Closed	1	1	I43813111
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:23 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-g3DmCmcgYTLw4TcARinwm9wpHeg3x1t1hs4DkCyDLaQ



Scale = 1:15.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.15	Vert(LL)	-0.00	5-6	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	-0.01	5-6	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MR							
										Weight: 11 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=Mechanical, 6=Mechanical
Max Horz 6=80(LC 9)
Max Uplift 5=-36(LC 12), 6=-6(LC 12)
Max Grav 5=193(LC 1), 6=175(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 6.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813112
2542170	J11	Jack-Open	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:36 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-oZVgxDMqUTz48T6gixW_ouz3lu7qUw5xgOkPixyDLaD

-0-10-8
0-10-8
1-10-15
1-10-15

Scale = 1:10.7




Plate Offsets (X,Y)-- [2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d			PLATES	GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	-0.00	7	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	-0.00	7	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 7 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=49(LC 12)
Max Uplift 3=23(LC 12), 2=-18(LC 12)
Max Grav 3=60(LC 1), 2=201(LC 1), 4=35(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J12	Truss Type Jack-Closed	Qty 1	Ply 1	Summit/9 Woodside Job Reference (optional) I43813113
----------------	--------------	---------------------------	----------	----------	--

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:42 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-djsyBGrb3JkEsOZq2BdO19D2SJ7fudaq2KBkvbyDLa7



Scale = 1:15.7

Plate Offsets (X,Y)-- [1:0-0-1,0-0-3], [1:0-0-3,0-5-0], [1:0-3-8,Edge]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	0.02	5-8	>999	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.20	Vert(CT)	-0.03	5-8	>999	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01	1	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP							Weight: 12 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 5=Mechanical, 1=0-3-8
Max Horz 1=78(LC 11)
Max Uplift 5=39(LC 12), 1=9(LC 12)
Max Grav 5=217(LC 1), 1=200(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 3-10-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 1.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J13	Truss Type Jack-Open	Qty 1	Ply 1	Summit/9 Woodside Job Reference (optional)	I43813114
----------------	--------------	-------------------------	----------	----------	---	-----------

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:49 2020 Page 1

ID:clow4Ylgf7iox0?ly75BCcz33zm-w3nbffw_QScEBTcAy9F1qe?Fq7Xj1oJsfvObfhyDLA0



Scale = 1:15.2




Plate Offsets (X,Y)-- [2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	-0.01 4-7 >999 240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	-0.02 4-7 >999 180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.01 2 n/a n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MP				Weight: 11 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-8-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=81(LC 12)
Max Uplift 3=-48(LC 12), 2=-20(LC 12)
Max Grav 3=135(LC 1), 2=290(LC 1), 4=73(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-8-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J14	Truss Type Jack-Closed	Qty 2	Ply 1	Summit/9 Woodside I43813115
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:51 2020 Page 1
ID:clow4Ylgt7iox0?ly?5BCcz33zm-sSvL4LyEy4syRnly4aHVv35dVxEQVio97DtikayDLA_



Scale = 1:10.0

Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07
TCDL 20.0	Lumber DOL	1.15	BC 0.03
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-MP
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.00 9 >999 240
			Vert(CT) -0.00 9 >999 180
			Horz(CT) 0.00 2 n/a n/a
			PLATES GRIP
			MT20 197/144
			Weight: 7 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-7-11 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 5=Mechanical
Max Horz 2=43(LC 11)
Max Uplift 2=-24(LC 12), 5=-13(LC 12)
Max Grav 2=188(LC 1), 5=57(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J15	Truss Type Jack-Closed	Qty 2	Ply 1	Summit/9 Woodside I43813116
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:53 2020 Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-oq16V1_UUh7gg4vxB?Jz_UAz?kwizclSaXmpnSyDLZy



Scale = 1:10.0

Plate Offsets (X,Y)--		[2:0-0-1,0-0-3], [2:0-0-3,0-5-0], [2:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07
TCDL 20.0	Lumber DOL	1.15	BC 0.03
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-MP
DEFL.	in (loc)	L/defl	L/d
Vert(LL)	-0.00	9	>999
Vert(CT)	-0.00	9	>999
Horz(CT)	-0.00	2	n/a
PLATES	GRIP		
MT20	197/144		
Weight: 7 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-7-11 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 5=Mechanical
Max Horz 5=43(LC 11)
Max Uplift 2=-24(LC 12), 5=-13(LC 12)
Max Grav 2=188(LC 1), 5=57(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 5.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2542170	Truss J16	Truss Type Jack-Open	Qty 1	Ply 1	Summit/9 Woodside Job Reference (optional)	I43813117
----------------	--------------	-------------------------	----------	----------	---	-----------

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:33:55 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-kD9swj?l0INovO3KJQMR3vF73YZuRU7k1rrwsLyDLZw



Scale = 1:21.4

Plate Offsets (X,Y)-- [2:0-3-13,0-1-5], [3:0-1-12,0-0-14], [6:0-3-0,0-2-4]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	0.10	6	>725	240	MT20	197/144	
TCDL	20.0	Lumber DOL	1.15	BC	0.25	Vert(CT)	-0.17	6	>422	180			
BCLL	0.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.05	2	n/a	n/a			
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 17 lb	FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
2-6: 2x6 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS. (size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=123(LC 12)
Max Uplift 4=98(LC 12), 2=-23(LC 12)
Max Grav 4=272(LC 1), 2=411(LC 1), 5=98(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-370/44
WEBS 3-6=-243/449

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-11-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss J17	Truss Type Jack-Open	Qty 1	Ply 1	Summit/9 Woodside I43813118
----------------	--------------	-------------------------	----------	----------	--------------------------------

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:34:00 2020 Page 1

ID:clow4YlGf7iox0?ly?5BCcz33zm-5AylzQ3tqr?g09xH6zycmyyZVZFB6mGTB7YgXYyDLZr



Scale = 1:20.9




Plate Offsets (X,Y)-- [2:0-2-13,0-1-8]							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	L/defl	L/d
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	0.16	6	>444
TCDL 20.0	Lumber DOL	1.15	BC 0.30	Vert(CT)	-0.30	6	>235
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.09	5	n/a
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS				
				PLATES	GRIP		
				MT20	197/144		
				Weight: 19 lb	FT = 20%		

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
2-6: 2x6 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=123(LC 12)
Max Uplift 4=-86(LC 12), 2=-23(LC 12)
Max Grav 4=292(LC 1), 2=411(LC 1), 5=58(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-11-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	J18	Jack-Open	2	1	I43813119

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:34:05 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-S8le077ofNdz6wqFuXXnT0gqUayBn1XDLPGRcmYDLZm



Scale = 1:21.2

Plate Offsets (X,Y)-- [2:0-2-9,0-1-8]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.87	Vert(LL)	0.15	6	>464	240	MT20	197/144
TCDL	20.0	Lumber DOL	1.15	BC	0.31	Vert(CT)	-0.29	6	>245	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.09	5	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 19 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 2-6: 2x6 SPF No.2
 WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
 BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
 Max Horz 2=123(LC 12)
 Max Uplift 4=-85(LC 12), 2=-23(LC 12)
 Max Grav 4=294(LC 1), 2=411(LC 1), 5=53(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-11-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	J19	Jack-Open	2	1	I43813120
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:34:11 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-GI7vHBCnEDO6qrHOFneBjHw?H?1JBIO5jKjmQPpyDLZg



Scale = 1:15.7

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	-0.01	6	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.14	Vert(CT)	-0.01	6-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.02	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP						Weight: 14 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2 *Except*
2-6: 2x6 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8, 5=Mechanical
Max Horz 2=84(LC 12)
Max Uplift 4=49(LC 12), 2=20(LC 12)
Max Grav 4=197(LC 1), 2=299(LC 1), 5=11(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-10-3 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Bearing at joint(s) 2 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	J20	Jack-Open	2	1	I43813121
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:34:39 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-ShpV9IXLeqv8B9Qnug8lrB4q1HdekPhD9hVFPoyDLZE



Scale = 1:10.7

Plate Offsets (X,Y)-- [2:0-1-15,0-0-0], [2:0-2-7,0-3-0], [5:0-0-13,0-1-10]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	-0.00	5	>999	240	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	-0.00	5	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MR						Weight: 6 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 4=Mechanical, 5=0-3-8
Max Horz 5=43(LC 12)
Max Uplift 3=-26(LC 12), 5=-20(LC 12)
Max Grav 3=57(LC 1), 4=31(LC 3), 5=215(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 5 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 5.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813122
2542170	LG1	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:10 2020 Page 1

ID:clow4YlGf7ioX0?ly?5BCcz33zm-ISZ_pz?EROk9oSPSpukWdHFuc4Y9vLDbsMFbk9yDLsB

5-11-4	21-10-10	27-9-14
5-11-4	15-11-6	5-11-4

Scale = 1:46.7




Plate Offsets (X,Y)--	[4:0-2-10,Edge], [12:0-2-10,Edge], [22:0-2-8,0-3-0]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.14	Horz(CT)	0.01	15	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 144 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-12.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 27-9-14.
(lb) - Max Horz 1=-153(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 15, 22, 23, 24, 25, 26, 21, 20, 19 except 27=-128(LC 12), 28=-115(LC 12), 17=-127(LC 13), 16=-115(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 15, 22, 23, 24, 25, 26, 28, 21, 20, 19, 18, 16 except 27=259(LC 19), 17=258(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-15 to 3-3-15, Interior(1) 3-3-15 to 5-11-4, Exterior(2R) 5-11-4 to 9-10-15, Interior(1) 9-10-15 to 21-10-10, Exterior(2R) 21-10-10 to 25-10-15, Interior(1) 25-10-15 to 27-5-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 15, 22, 23, 24, 25, 26, 21, 20, 19 except (jt=lb) 27=128, 28=115, 17=127, 16=115.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	LG2	GABLE	1	1	I43813123
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:18 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-W_20Ui5GYrl0mh0?HZtOyzaGXJHrnz4nibB00hyDLS3



4x4 =

Scale = 1:53.3



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.04	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.14	Horz(CT)	0.00	9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 80 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 5-13

REACTIONS.

All bearings 15-9-14.
(lb) - Max Horz 1=205(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 1, 9 except 14=-119(LC 12), 15=-119(LC 12), 16=-116(LC 12), 12=-117(LC 13), 11=-120(LC 13), 10=-116(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 9, 13, 15, 16, 11, 10 except 14=255(LC 19), 12=253(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-281/183, 8-9=-252/178

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-15 to 3-3-15, Interior(1) 3-3-15 to 7-10-15, Exterior(2R) 7-10-15 to 10-10-15, Interior(1) 10-10-15 to 15-5-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 9 except (jt=lb) 14=119, 15=119, 16=116, 12=117, 11=120, 10=116.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss LG3	Truss Type GABLE	Qty 1	Ply 1	Summit/9 Woodside 143813124
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:25 2020 Page 1
ID:clow4Ylgr7iox0?ly?5BCcz33zm-pKzfz5Afv?d05m2LBXV1kSNSd7gKw8rpJBNUlNyDLRy



Scale = 1:67.2

Plate Offsets (X,Y)--		[19:0-2-8,0-3-0]			
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.08	Vert(LL) n/a - n/a 999	MT20	197/144
TCDL 20.0	Lumber DOL 1.15	BC 0.05	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.14	Horz(CT) 0.01 11 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S		Weight: 112 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 6-16, 5-17, 7-15

REACTIONS.

All bearings 19-9-14.
(lb) - Max Horz 1=-260(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 11 except 1=-113(LC 10), 17=-115(LC 12), 18=-120(LC 12),
19=-119(LC 12), 20=-118(LC 12), 15=-112(LC 13), 14=-121(LC 13), 13=-116(LC 13), 12=-116(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 11, 16, 18, 19, 20, 14, 13, 12 except 1=270(LC 12), 17=254(LC 19), 15=251(LC 20)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-374/238, 2-3=-259/194, 10-11=-333/231

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-15 to 3-3-15, Interior(1) 3-3-15 to 9-10-15, Exterior(2R) 9-10-15 to 12-10-15, Interior(1) 12-10-15 to 19-5-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11 except (jt=lb) 1=113, 17=115, 18=120, 19=119, 20=118, 15=112, 14=121, 13=116, 12=116.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside
2542170	LG4	GABLE	1	1	I43813125
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:33 2020 Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-atSheqGg0Sdu3?ffDfv38ipfMOYon3_9RJ1JyDLRq



Scale = 1:26.9

Plate Offsets (X,Y)--		[3:0-2-8,0-1-12]							
LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in (loc)	L/defl	L/d
TCLL 25.0		Plate Grip DOL	1.15	TC 0.14		Vert(LL)	n/a	n/a	999
TCDL 20.0		Lumber DOL	1.15	BC 0.03		Vert(CT)	n/a	n/a	999
BCLL 0.0		Rep Stress Incr	YES	WB 0.06		Horz(CT)	0.00	5	n/a
BCDL 10.0		Code IRC2018/TPI2014		Matrix-P					
						PLATES		GRIP	
						MT20		197/144	
						Weight: 26 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-11-11 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 5-11-11.
(lb) - Max Horz 1=147(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 6 except 7=135(LC 12)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 6 except 7=269(LC 19)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-268/289
WEBS 2-7=-265/162

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-15 to 3-3-15, Interior(1) 3-3-15 to 3-11-4, Exterior(2E) 3-11-4 to 5-9-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 6 except (jt=lb) 7=135.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813126
2542170	LG5	GABLE	1	1	Job Reference (optional)	


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:39 2020 Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-O1pyvuLRclO1nw71?TlJIPysEnRzCV5tXNmdFzyDLRk

3-10-15 3-10-15 7-9-14 3-10-15

4x4 =

Scale = 1:29.9



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 29 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 7-9-14.
(lb) - Max Horz 1=97(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8=-133(LC 12), 6=-133(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=267(LC 19), 6=267(LC 20)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-256/157, 4-6=-256/157

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-15 to 3-3-15, Interior(1) 3-3-15 to 3-10-15, Exterior(2R) 3-10-15 to 6-10-15, Interior(1) 6-10-15 to 7-5-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=133, 6=133.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813127
2542170	LG6	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:42 2020 Page 1

ID:clow4YlGf7iox0?ly?5BCcz33zm-pcV5XvNjvDmceNrhcJ0w1aMU_TgPsqJDK?HslyDLRh

3-10-15 3-10-15 7-9-14 3-10-15

Scale = 1:29.9

4x4 =



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.02	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 29 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 7-9-14.
(lb) - Max Horz 1=97(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 8=-133(LC 12), 6=-133(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=267(LC 19), 6=267(LC 20)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-256/157, 4-6=-256/157

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-3-15 to 3-3-15, Interior(1) 3-3-15 to 3-10-15, Exterior(2R) 3-10-15 to 6-10-15, Interior(1) 6-10-15 to 7-5-15 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 8=133, 6=133.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss V1	Truss Type GABLE	Qty 1	Ply 1	Summit/9 Woodside Job Reference (optional)	I43813128
----------------	-------------	---------------------	----------	----------	---	-----------

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:44 2020 Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-l_crybPZQr0Kth?_o1LU?Sfhqo9ctmAcHeUOWAyDLRf



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.14	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 33 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 12-0-9.
(lb) - Max Horz 1=-43(LC 17)
Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 8, 6
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7 except 8=361(LC 25), 6=361(LC 26)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-8=-288/162, 4-6=-288/162

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-7-9 to 3-6-4, Interior(1) 3-6-4 to 6-0-4, Exterior(2R) 6-0-4 to 9-0-4, Interior(1) 9-0-4 to 11-5-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 8, 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813129
2542170	V2	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:46 2020 Page 1
ID:clow4Ylgf7iox0?ly?5BCcz33zm-hNkbNHQqySG27_9NwRNY5tl?LbpSLfgv8yzV?3yDLRd



Scale = 1:15.2

LOADING (psf)		SPACING-		CSI.		DEFL.		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	n/a	MT20		197/144	
TCDL	20.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	n/a				
BCLL	0.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	0.00				
BCDL	10.0	Code IRC2018/TPI2014		Matrix-P							
								Weight: 19 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=7-11-9, 3=7-11-9, 4=7-11-9
Max Horz 1=-27(LC 17)
Max Uplift 1=-28(LC 12), 3=-33(LC 13)
Max Grav 1=193(LC 1), 3=193(LC 1), 4=361(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-276/135

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-7-9 to 3-7-9, Interior(1) 3-7-9 to 4-0-4, Exterior(2R) 4-0-4 to 7-0-4, Interior(1) 7-0-4 to 7-5-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss V3	Truss Type Valley	Qty 1	Ply 1	Summit/9 Woodside I43813130
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:48 2020 Page 1
ID:clow4Ylgf7iox0?iy?5BCcz33zm-dlsMnzS4U3WmMIJm1sQQAlqLrPVnpZvBcGSc3yyDLRb



Scale = 1:22.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.27	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 23 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=7-9-12, 4=7-9-12, 5=7-9-12
Max Horz 1=133(LC 9)
Max Uplift 4=-19(LC 9), 5=-89(LC 12)
Max Grav 1=129(LC 20), 4=166(LC 1), 5=489(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-5=-400/232

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-7-9 to 3-10-4, Interior(1) 3-10-4 to 7-8-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 5.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2542170	Truss V5	Truss Type Valley	Qty 1	Ply 1	Summit/9 Woodside Job Reference (optional)	I43813132
----------------	-------------	----------------------	----------	----------	---	-----------

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:52 2020 Page 1

ID:clow4Ylgf7iox0?ly?5BCcz33zm-WX5tdKVaY11BrwcXGiUMK8?2d0szlNknWuQpCjyDLRX



Scale = 1:12.4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.22	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 20.0	Lumber DOL	1.15	BC 0.09	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 10 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-4 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=3-9-12, 3=3-9-12
Max Horz 1=58(LC 9)
Max Uplift 1=-12(LC 12), 3=-27(LC 12)
Max Grav 1=169(LC 1), 3=169(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2, 2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/9 Woodside	I43813133
2542170	V6	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.240 s Mar 9 2020 MiTek Industries, Inc. Tue Dec 1 11:42:56 2020 Page 1
ID:c1ow4Ylgf7iox0?ly?5BCcz33zm-OILNTiY5cXXdJXwIVYZIU_9mFdEjhBjNRWO1LUyDLRT



Scale = 1:8.1



0-0-8				4-4-1							
0-0-8				4-3-9							
Plate Offsets (X,Y)-- [2:0-3-0,Edge]											
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL 1.15		TC	0.05	Vert(LL)	n/a - n/a	999	MT20	197/144	
TCDL	20.0	Lumber DOL 1.15		BC	0.10	Vert(CT)	n/a - n/a	999			
BCLL	0.0	Rep Stress Incr YES		WB	0.00	Horz(CT)	0.00 3 n/a	n/a			
BCDL	10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 9 lb	FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-4-1 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=4-3-1, 3=4-3-1
Max Horz 1=-12(LC 13)
Max Uplift 1=-12(LC 12), 3=-12(LC 13)
Max Grav 1=169(LC 1), 3=169(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



December 2,2020

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless X, Y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- $\frac{3}{16}$ " from outside edge of truss.

—
—
This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MITek 20120 software or upon request.**

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1.1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.