

PLANS REVIEW CONDITIONS

Permit No:	PRCOM20191955	Date:	December 23, 2020
Project Title:	ATTIC STORAGE OF LEES SUMMIT	Applicant:	
Location:	920 NE DEERBROOK ST, LEES SUMMIT, MO 64086		
Type of Work:			AEGIS FIRE PROTECTION LLC
Occupancy Group:	S-1		11936 W 119TH ST #262
Description:	NEW ENCLOSED CONDITIONED		OVERLAND PARK, KS 66213
	SELF STORAGE BUILDING	Primary:	(913) 825-0343
Construction Type:	Type IIB (Unprotected)		
Map Page:	175Z		

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

1. 2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)

Call (816)969-1300 to schedule a hydrostatic and a water flow test.

2. (Informational Purposes)

Provide 4 inch Storz connection with a 30 degree elbow for the FDC connection.

Sprinkler Plan Review

Reviewed By: Michael Weissenbach

Released for Construction

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.