



January 7, 2021

Washam Homes

Re: 1801 SW River Run Dr  
Lot 21, Whispering Woods  
Lee's Summit, MO

Apex Engineers Inc. observed the house under construction at the above referenced address. Our firm has been retained to address comments from the city rough-in inspection. For the purposes of this report the house will be referred to as facing east.

1. *Load bearing 2x4 wall between stairs to basement and foundation wall is supporting two floors plus roof/ceiling assembly. Provide engineered solution for repair or comply with table R602.3(5).*
  - After computations, our firm recommends the following:
    - Double each 2x4 stud in the wall of concern, so that there is (2)-2x4 studs at 16" OC.
    - The built-up wood column (stud pack) supporting the LVL spanning over the garage shall consist of a minimum of (4)-2x4 studs. The studs shall align above and below the wall plate line.

**\*\*Built-up wood column - Each 2x4 ply shall be fastened with 1 row of 10d nails at 9" on center alternating side to side, 1.4" min edge distance, and starting 2.5" from each end.**

Contingent upon the repairs outline above, our firm recommends approval of these items.


Please call if our firm can of further assistance.

#### **LIMITATIONS**

The scope of our services includes only those items specifically addressed herein. All other items are outside the scope of this inspection; including any environmental assessment (such as, but not limited to mold, mildew, or presence of any other toxic substance or environmental risks).

In addition, the scope our services does not include any evaluation of the building or site for job-site safety and/or hazardous conditions. All construction shall be performed in compliance with IRC and OSHA standards at all times. Our firm has not been retained to examine the site or building for any of these conditions. In addition, the contractor shall retain sole responsibility for the quality of work, for adhering to plans, specifications, appropriate codes, and, for repairing defects, deficiencies or omission, regardless of when they are found. By the use of this report it is understood the above conditions are agreed to.

Best Regards,  
Apex Engineers, Inc.

  
Joshua M. Jensen, P.E.  
Project Engineer

Clayton J. Hess  
Principal





## Wood Column

Lic. #: KW-06005244

DESCRIPTION: Walls Studs in Basement

### Code References

Calculations per NDS 2018, IBC 2018, CBC 2019, ASCE 7-16

Load Combinations Used : ASCE 7-16

### General Information

Analysis Method : Allowable Stress Design				Wood Section Name 2-2x4	
End Fixities Top & Bottom Pinned				Wood Grading/Manuf. Graded Lumber	
Overall Column Height		9.0 ft		Wood Member Type Sawn	
( Used for non-slender calculations )					
Wood Species Douglas Fir - Larch		Exact Width 3.0 in Allow Stress Modification Factors			
Wood Grade Stud		Exact Depth 3.50 in Cf or Cv for Bending 1.10			
Fb +	700.0 psi	Fv	180.0 psi	Area	10.50 in^2 Cf or Cv for Compression 1.050
Fb -	700.0 psi	Ft	450.0 psi	Ix	10.719 in^4 Cf or Cv for Tension 1.10
Fc - Prll	850.0 psi	Density	31.210 pcf	Iy	7.875 in^4 Cm : Wet Use Factor 1.0
Fc - Perp	625.0 psi				Ct : Temperature Factor 1.0
E : Modulus of Elasticity . . .		x-x Bending	y-y Bending	Axial	Cfu : Flat Use Factor 1.0
	Basic	1,400.0	1,400.0	1,400.0 ksi	Kf : Built-up columns 1.0 NDS 15.3.2
	Minimum	510.0	510.0		Use Cr : Repetitive ? No
Brace condition for deflection (buckling) along columns :					
				X-X (width) axis :	Fully braced against buckling ABOUT Y-Y Axis
				Y-Y (depth) axis :	Unbraced Length for buckling ABOUT X-X Axis = 9.0 ft, K = 1.0

### Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Column self weight included : 20.482 lbs \* Dead Load Factor

AXIAL LOADS . . .

Axial Load at 9.0 ft, D = 1.681 k

### DESIGN SUMMARY

#### Bending & Shear Check Results

PASS	Max. Axial+Bending Stress Ratio =	0.4324 : 1	Maximum SERVICE Lateral Load Reactions . .	
	Load Combination	+D+H	Top along Y-Y	0.0 k
	Governing NDS Formula	Comp Only, $f_c/F_c'$	Bottom along Y-Y	0.0 k
	Location of max.above base	0.0 ft	Top along X-X	0.0 k
	At maximum location values are . . .		Bottom along X-X	0.0 k
	Applied Axial	1.701 k	Maximum SERVICE Load Lateral Deflections . .	
	Applied Mx	0.0 k-ft	Along Y-Y	0.0 in at 0.0 ft above base
	Applied My	0.0 k-ft	for load combination : n/a	
	Fc : Allowable	374.739 psi	Along X-X	0.0 in at 0.0 ft above base
			for load combination : n/a	
PASS	Maximum Shear Stress Ratio =	0.0 : 1	Other Factors used to calculate allowable stresses . .	
	Load Combination	+0.60D+0.70E+H	Bending	Compression
	Location of max.above base	9.0 ft		Tension
	Applied Design Shear	0.0 psi		
	Allowable Shear	288.0 psi		

### Load Combination Results

Load Combination	C <sub>D</sub>	C <sub>P</sub>	Maximum Axial + Bending Stress Ratios			Maximum Shear Ratios		
			Stress Ratio	Status	Location	Stress Ratio	Status	Location
+D+H	0.900	0.467	0.4324	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+L+H	1.000	0.429	0.4233	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+Lr+H	1.250	0.355	0.4086	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+S+H	1.150	0.382	0.4135	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.750Lr+0.750L+H	1.250	0.355	0.4086	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.750L+0.750S+H	1.150	0.382	0.4135	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.60W+H	1.600	0.286	0.3975	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.750Lr+0.750L+0.450W+H	1.600	0.286	0.3975	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.750L+0.750S+0.450W+H	1.600	0.286	0.3975	PASS	0.0 ft	0.0	PASS	9.0 ft
+0.60D+0.60W+0.60H	1.600	0.286	0.2385	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.70E+0.60H	1.600	0.286	0.3975	PASS	0.0 ft	0.0	PASS	9.0 ft
+D+0.750L+0.750S+0.5250E+H	1.600	0.286	0.3975	PASS	0.0 ft	0.0	PASS	9.0 ft



Apex Engineers, Inc  
1625 Locust  
Kansas City, MO 64108  
www.apex-engineers.com



Project Title:  
Engineer:  
Project ID:  
Project Descr:

Printed: 8 JAN 2021, 10:36AM

File: 1801 SW River Run Dr Calcs.ec6

Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.17

APEX ENGINEERS INC

## Wood Column

Lic. #: KW-06005244

DESCRIPTION: Walls Studs in Basement

### Load Combination Results

Load Combination	C <sub>D</sub>	C <sub>P</sub>	Maximum Axial + Bending Stress Ratios			Maximum Shear Ratios		
			Stress Ratio	Status	Location	Stress Ratio	Status	Location
+0.60D+0.70E+H	1.600	0.286	0.2385	PASS	0.0 ft	0.0	PASS	9.0 ft

### Maximum Reactions

Note: Only non-zero reactions are listed.

Load Combination	X-X Axis Reaction		k	Y-Y Axis Reaction		Axial Reaction	My - End Moments		k-ft	Mx - End Moments	
	@ Base	@ Top		@ Base	@ Top	@ Base	@ Base	@ Top		@ Base	@ Top
+D+H						1.701					
+D+L+H						1.701					
+D+Lr+H						1.701					
+D+S+H						1.701					
+D+0.750Lr+0.750L+H						1.701					
+D+0.750L+0.750S+H						1.701					
+D+0.60W+H						1.701					
+D+0.750Lr+0.750L+0.450W+H						1.701					
+D+0.750L+0.750S+0.450W+H						1.701					
+0.60D+0.60W+0.60H						1.021					
+D+0.70E+0.60H						1.701					
+D+0.750L+0.750S+0.5250E+H						1.701					
+0.60D+0.70E+H						1.021					
D Only						1.701					
Lr Only											
L Only											
S Only											
W Only											
E Only											
H Only											

### Maximum Deflections for Load Combinations

Load Combination	Max. X-X Deflection		Distance	Max. Y-Y Deflection		Distance
+D+H	0.0000	in	0.000	0.0000	in	0.000
+D+L+H	0.0000	in	0.000	0.0000	in	0.000
+D+Lr+H	0.0000	in	0.000	0.0000	in	0.000
+D+S+H	0.0000	in	0.000	0.0000	in	0.000
+D+0.750Lr+0.750L+H	0.0000	in	0.000	0.0000	in	0.000
+D+0.750L+0.750S+H	0.0000	in	0.000	0.0000	in	0.000
+D+0.60W+H	0.0000	in	0.000	0.0000	in	0.000
+D+0.750Lr+0.750L+0.450W+H	0.0000	in	0.000	0.0000	in	0.000
+D+0.750L+0.750S+0.450W+H	0.0000	in	0.000	0.0000	in	0.000
+0.60D+0.60W+0.60H	0.0000	in	0.000	0.0000	in	0.000
+D+0.70E+0.60H	0.0000	in	0.000	0.0000	in	0.000
+D+0.750L+0.750S+0.5250E+H	0.0000	in	0.000	0.0000	in	0.000
+0.60D+0.70E+H	0.0000	in	0.000	0.0000	in	0.000
D Only	0.0000	in	0.000	0.0000	in	0.000
Lr Only	0.0000	in	0.000	0.0000	in	0.000
L Only	0.0000	in	0.000	0.0000	in	0.000
S Only	0.0000	in	0.000	0.0000	in	0.000
W Only	0.0000	in	0.000	0.0000	in	0.000
E Only	0.0000	in	0.000	0.0000	in	0.000
H Only	0.0000	in	0.000	0.0000	in	0.000



Apex Engineers, Inc  
1625 Locust  
Kansas City, MO 64108  
www.apex-engineers.com



Project Title:  
Engineer:  
Project ID:  
Project Descr:

Printed: 8 JAN 2021, 10:36AM

File: 1801 SW River Run Dr Calcs.ec6

Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.17


APEX ENGINEERS INC

## Wood Column

Lic. # : KW-06005244

DESCRIPTION: Walls Studs in Basement

### Sketches





Apex Engineers, Inc.  
1625 Locust St.  
Kansas City, Missouri 64108  
www.apex-engineers.com

Job Address: 1801 SW River Run Dr  
Lee's Summit, MO

Sheet # \_\_\_\_\_ of \_\_\_\_\_

Engineer: JMJ

Date: 1/8/2021

### Wall Uniform Loads

- Dead load of wall = 92 lbs/ft
- Second Floor Over Garage = 240 lbs/ft
- 1<sup>st</sup> to Lower Stair Landing = 225 lbs/ft

### Wall Point Loads

- Ceiling Beam over Entry = 540 lbs
- LVL Ridge = 1839 lbs
- Ceiling Beam over hallway = 600 lbs
- Second floor (4) 1 3/4" x 9 1/4" Beam = 1877 lbs
- 1<sup>st</sup> Floor

### Total load Per Stud

$$(16/12) (92 + 240 + 225) + (1877 \text{ lbs} / 2) = 1681 \text{ lbs/stud}$$

See enercalc file for stud Capacity Calculations

