


C:\Backup\Revit\WB-Lees Summit\MO_Y18_MECH_200921_dum.rvt 12/7/2021 3:55:56 PM

MECHANICAL SYMBOLS ABBREVIATIONS


(SOME SYMBOLS MAY NOT BE USED ON THE DRAWINGS)

SHEET SYMBOLS

DUCTWORK



PIPING SYMBOLS



HVAC DESIGN CRITERIA

ASHRAE FUNDAMENTALS 2009:	SUMMER COOLING DESIGN (1.0%):
KANSAS CITY WSO AP	93.0°F DRY BULB
ELEVATION: 973' LATITUDE: 39.32°N, 94.72°W	75°F MEAN COINCIDENT WET BULB
WINTER HEATING DESIGN (99.6%):	
-1°F DRY BULB	
SUMMER DEHUMIDIFICATION DESIGN (0.4%):	
86.7°F DRY BULB	
76.5°F DEWPOINT	

GENERAL NOTES


- REFER TO SPECIFICATIONS FOR MATERIALS AND METHODS FOR CONSTRUCTION.
- DUCTWORK SIZES SHOWN ARE FREE AIR STREAM DIMENSIONS.
- INSTALL DUCTWORK AND PIPING TO PROVIDE THE MAXIMUM POSSIBLE CLEAR HEIGHT UNDERNEATH. (BETWEEN STRUCTURE OR CEILING AND TOP OF DUCT).
- WHERE APPROVAL CODES HAVE BEEN ESTABLISHED BY OSHA, UNDERWRITER'S LABORATORY, AMERICAN CODES, ANSI, ASME, ASA, ASHRAE, ASTM, ARI, NEL, NFPA, SMACNA, OR THE STATE FIRE INSURANCE REGULATORY BODY, FOLLOW THESE STANDARDS WHETHER OR NOT INDICATED ON THE DRAWINGS AND SPECIFICATIONS.
- PROVIDE THE ENTIRE SYSTEM AND ITS COMPONENT ITEMS OF EQUIPMENT IN OPERATING CONDITION FREE OF OBJECTIONABLE VIBRATION OR NOISE.
- PERFORM WORK IN ACCORDANCE WITH THE LATEST EDITIONS, REVISIONS, AMENDMENTS OR SUPPLEMENTS OF APPLICABLE STATUTES, ORDINANCES, CODES OR REGULATIONS OF FEDERAL, STATE AND LOCAL AUTHORITIES HAVING JURISDICTION IN EFFECT ON THE DATE BIDS ARE RECEIVED.
- COORDINATE WORK SO THAT INTERFERENCES BETWEEN PIPING, DUCTWORK, EQUIPMENT, PLUMBING WORK, ELECTRICAL WORK, AND BUILDING STRUCTURE WILL BE AVOIDED.
- FURNISH ACCESS DOORS FOR INSTALLATION IN WALLS AND CEILINGS WHERE ACCESS IS REQUIRED TO CONCEALED MECHANICAL EQUIPMENT, VALVES, CONTROLS AND OTHER DEVICES.
- COORDINATE THE EXACT LOCATION OF DRAIN AND MECHANICAL EQUIPMENT LOCATIONS WITH MECHANICAL, ARCHITECTURAL, AND STRUCTURAL DRAWINGS PRIOR TO INSTALLATION.
- RECTANGULAR ELBOWS SHALL BE LONG-RADIUS ELBOWS UNLESS OTHERWISE SHOWN OR NOTED. SUPPLY AIR STANDARD NON-RADIUS 90° ELBOWS SHALL HAVE TURNING VANES.
- AIR CONDITIONING LOAD CALCULATIONS BASED ON KANSAS CITY, MISSOURI CLIMATE DATA. ADJUST UNIT SIZES, AIRFLOW, DUCT SIZES AND AIR DEVICES TO HVAC LOAD CALCULATIONS BASED ON STORE LOCATION. COORDINATE RTU LOCATIONS, DIMENSIONS, AND WEIGHTS WITH STRUCTURAL ENGINEER AND ARCHITECT.

LAT	LEAVING AIR TEMPERATURE
LBS	POUNDS
LF	LINEAR FEET
LG	LENGTH
LPS	LOW PRESSURE STEAM
LTHW	LOW TEMPERATURE HOT WATER
LWT	LEAVING WATER TEMPERATURE
MAT	MIXED AIR TEMPERATURE
MCA	MINIMUM CIRCUIT AMPACITY
MOCp	MAXIMUM OVERCURRENT PROTECTION
MAX	MAXIMUM
MBH	BTU PER HOUR (THOUSAND)
MIN	MINIMUM
N.C.	NORMALLY CLOSED
N.O.	NORMALLY OPEN
N/A	NOT APPLICABLE
NC	NOISE CRITERIA
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OBD	OPOSED BLADE DAMPER
OD	OUTSIDE DIAMETER
PD	PUMPED DISCHARGE
PBD	PARALLEL BLADE DAMPER
PH	PHASE (ELECTRICAL)
PPM	PARTS PER MILLION
PRESS	PRESSURE
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PSIA	PSI ABSOLUTE
PSIG	PSI GAGE
R	RANKINE
R-22	REFRIGERANT (NUMBER INDICATES TYPE)
RA	RETURN AIR
RAF	RELIEF AIR FAN
RECIRC	RECIRCULATE
RH	RELATIVE HUMIDITY
RHC	REHEAT COIL
RPM	REVOLUTIONS PER MINUTE
SA	SUPPLY AIR
SC	SHADING COEFFICIENT
SCFM	CUBIC FEET PER MINUTE-STANDARD CONDITIONS
SD	SMOKE DAMPER
SEC	SECOND
SF	SQUARE FEET
SG	SPECIFIC GRAVITY
SHG	SENSIBLE HEAT GAIN
SHR	SENSIBLE HEAT RATIO
SP	STATIC PRESSURE
SPEC	SPECIFICATION
SQ	SQUARE
SSD	SUB-SOIL DRAINAGE
STD	STANDARD
SUCT	SUCTION
t	TIME
T	TEMPERATURE
TD	TEMPERATURE DIFFERENCE
TEMP	TEMPERATURE
TOC	TOP OF CONCRETE
TOD	TOP OF DUCT
TONS	TONS OF REFRIGERATION
TOP	TOP OF PIPE
TOS	TOP OF STEEL
TSP	TOTAL STATIC PRESSURE
T-STAT	THERMOSTAT
TU	TERMINAL UNIT
TYP	TYPICAL
U	HEAT TRANSFER COEFFICIENT
UH	UNIT HEATER
UF	UNDER FLOOR
V	VOLT
VA	VOLT AMPERE
VAC	VACUUM
VAV	VARIABLE AIR VOLUME
VD	VOLUME DAMPER
VENT	VENTILATION
VERT	VERTICAL
VFD	VARIABLE FREQUENCY DRIVE
VOL	VOLUME
VP	VELOCITY PRESSURE
W	HUMIDITY RATIO OR WATT
W.C.	WATER COLUMN
W.G.	WATER GAUGE
WB	WET BULB
WT	WEIGHT
YR	YEAR

DETAIL TITLE
SCALE: 1/2" = 1'-0"



NORTH ARROW



NECK/CFM BUBBLE

AHU-1 OR RTU-XXX

EQUIPMENT TAG



AIR FLOW INDICATOR



NOTE BY SYMBOL (KEYNOTE)



REVISION



POINT OF CONNECTION (NEW TO EXISTING)



POINT OF DISCONNECTION


MECHANICAL EQUIPMENT




COMBINATION FIRE/SMOKE DAMPER



FIRE DAMPER




SMOKE DAMPER



COMBINATION FIRE/SMOKE DAMPER IN VERTICAL SA DUCT




COMBINATION FIRE/SMOKE DAMPER IN VERTICAL RA DUCT



NEW EQUIPMENT (SIZE, SHAPE WILL VARY)



FUTURE KITCHEN / VENTILATION EQUIPMENT (SIZE, SHAPE WILL VARY)



EQUIPMENT TO REMAIN (SIZE, SHAPE WILL VARY)



DUCT STATIC PRESSURE SENSOR



DIFFERENTIAL PRESSURE SENSOR



WALL MOUNTED THERMOSTAT



WALL MOUNTED TEMPERATURE SENSOR



CARBON DIOXIDE SENSOR



OCCUPANCY SENSOR



ms consultants, inc.
engineers, architects, planners
2221 Schrock Road
Columbus, Ohio 43229
p 614.898.7100
f 614.898.7570
www.msconsultants.com

**WHATABURGER 20-M
LEE'S SUMMIT**

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO



NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.



12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No. 20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01

Client Project No.:

Drawing Title:

**GENERAL NOTES, SYMBOLS
AND ABBREVIATIONS**

Date: 12/22/2020 Phase: BID SET


Designed: DCU

Drawing No.:

Drawn: DCU

Checked: KFF

M0.1



A. REFER TO M0.1 FOR GENERAL NOTES, SYMBOLS AND ABBREVIATIONS.

B. SMOKE DETECTORS SHALL BE PROVIDED BY THE FIRE ALARM CONTRACTOR AND INSTALLED IN THE SUPPLY AND RETURN SIDES OF RTU. COORDINATE WIRING FOR SHUTDOWN WITH ELECTRICAL SCOPE. MOUNT SMOKE DETECTORS AT ACCESSIBLE LOCATIONS. REFERENCE M6.1E FOR RTU SCHEDULE. ACTIVATION OF SMOKE DETECTORS SHALL SHUT DOWN RTU AND ACTIVATE THE AUDIBLE AND VISUAL SIGNAL PROVIDED.

C. THE EMERSON SITE SUPERVISOR DISPLAY AND CONTROLLER PANEL SHALL BE MOUNTED AND INSTALLED FLUSH IN THE MANAGER'S OFFICE AT 5' AFF TO CENTER.

D. PER IECC 2018, PARAGRAPH C408.2.1, A THIRD PARTY SHALL BE HIRED BY THE OWNER AS PART OF THIS PROJECT TO PROVIDE/PERFORM THE FOLLOWING ITEMS:

- A NARRATIVE DESCRIPTION OF THE ACTIVITIES THAT WILL BE ACCOMPLISHED DURING EACH PHASE OF COMMISSIONING, INCLUDING THE PERSONNEL INTENDED TO ACCOMPLISH EACH OF THE ACTIVITIES.
- A LISTING OF THE SPECIFIC EQUIPMENT, APPLIANCES OR SYSTEMS TO BE TESTED AND A DESCRIPTION OF THE TESTS TO BE PERFORMED.
- FUNCTIONS TO BE TESTED INCLUDING, BUT NOT LIMITED TO, CALIBRATIONS AND ECONOMIZER CONTROLS.
- CONDITIONS UNDER WHICH THE TEST WILL BE PERFORMED. TESTING SHALL AFFIRM WINTER AND SUMMER DESIGN CONDITIONS AND FULL OUTSIDE AIR CONDITIONS.
- MEASURABLE CRITERIA FOR PERFORMANCE.

E. KITCHEN HOODS, ANSUL FIRE SUPPRESSION SYSTEM AND HOOD CONTROLS SHALL BE OWNER-FURNISHED AND CONTRACTOR-INSTALLED.

1 ELECTRIC UNIT HEATER. REFER TO VIEW B2 ON SHEET M5.2.

2 SUPPLY AIR DIFFUSER (TYP.), REFER TO VIEW B2 ON SHEET M5.1.

3 SUPPLY AIR SLOT DIFFUSER, REFER TO VIEW A3 ON SHEET M5.1.

4 2X2 LOCKABLE ACCESS DOOR IN HARD CEILING FOR ACCESS TO BATHROOM EXHAUST DAMPERS
RE: ARCHITECTURE.

5 28X20 SUPPLY DUCT UP TO RTU-1.

6 28X20 SUPPLY DUCT UP TO RTU-2.

7 CONNECT KITCHEN EXHAUST HOOD ABOVE FRYER UP TO KEF-2 WITH 12" DIA. PRE-FABRICATED U
710 LISTED AND LABELED GREASE DUCT. PROVIDE TRANSITIONS AS REQUIRED.

8 CONNECT KITCHEN EXHAUST HOOD ABOVE GRILLS UP TO KEF-4 WITH 18" DIA. PRE-FABRICATED U
710 LISTED AND LABELED GREASE DUCT. PROVIDE TRANSITIONS AS REQUIRED.

9 RTU-4 DDC CONTROLLER PANEL RECESSED MOUNTED IN WALL.

10 RTU-2 DDC CONTROLLER PANEL RECESSED MOUNTED IN WALL.

11 EMERSON SITE SUPERVISOR DISPLAY AND CONTROLLER PANEL RECESSED MOUNTED IN WALL.

12 RTU-3 DDC CONTROLLER PANEL RECESSED MOUNTED IN WALL.


13 61/5 RETURN AIR DUCT UP TO RTU-1 ON ROOF. REFER TO VIEW A1 ON SHEET M2.1, AND VIEW C4
ON SHEET M2.1.



REV	DESCRIPTION	DATE
1	REV-1 Plan Revision	01/27/21

M.I.I.

M1.1



A1 MECHANICAL ROOF PLAN
1/8" = 1'-0"

GENERAL NOTES

- A. REFER TO M0.1 FOR GENERAL NOTES, SYMBOLS AND ABBREVIATIONS.
- B. SMOKE DETECTORS SHALL BE PROVIDED BY THE FIRE ALARM CONTRACTOR AND INSTALLED IN THE SUPPLY AND RETURN SIDES OF ROOFTOP UNIT. COORDINATE WIRING FOR SHUTDOWN WITH ELECTRICAL SCOPE. MOUNT SMOKE DETECTORS IN ACCESSIBLE LOCATIONS. REFERENCE M0.1 FOR RTU SCHEDULE. ACTIVATION OF SMOKE DETECTORS SHALL SHUT DOWN RTU AND ACTIVATE THE AUDIBLE AND VISUAL SIGNAL PROVIDED.
- C. THE EMERSON SITE SUPERVISOR DISPLAY AND CONTROLLER PANEL SHALL BE MOUNTED AND INSTALLED FLUSH IN THE MANAGER'S OFFICE AT 5' AFF TO CENTER.
- D. PER IECC 2018, PARAGRAPH C408.2.1 A THIRD PARTY SHALL BE HIRED BY THE OWNER AS PART OF THIS PROJECT TO PROVIDE/PERFORM THE FOLLOWING ITEMS:
- A NARRATIVE DESCRIPTION OF THE ACTIVITIES THAT WILL BE ACCOMPLISHED DURING EACH PHASE OF COMMISSIONING, INCLUDING THE PERSONNEL INTENDED TO ACCOMPLISH EACH OF THE ACTIVITIES.
 - A LISTING OF THE SPECIFIC EQUIPMENT, APPLIANCES OR SYSTEMS TO BE TESTED AND A DESCRIPTION OF THE TESTS TO BE PERFORMED.
 - FUNCTIONS TO BE TESTED INCLUDING, BUT NOT LIMITED TO, CALIBRATIONS AND ECONOMIZER CONTROLS.
 - CONDITIONS UNDER WHICH THE TEST WILL BE PERFORMED. TESTING SHALL AFFIRM WINTER AND SUMMER DESIGN CONDITIONS AND FULL OUTSIDE AIR CONDITIONS.
 - MEASURABLE CRITERIA FOR PERFORMANCE.
- E. KITCHEN HOODS, ANSUL FIRE SUPPRESSION SYSTEM AND HOOD CONTROLS SHALL BE OWNER-FURNISHED AND CONTRACTOR-INSTALLED.
- F. MAINTAIN A MINIMUM CLEARANCE OF 10 FEET BETWEEN OUTSIDE AIR INTAKES AND ANY EXHAUST, FLUES, OR VENTS THROUGH ROOF.

KEYNOTES

- 1 CENTRIFUGAL UPBLAST GREASE HOOD EXHAUST FAN MOUNTED ON MANUFACTURER PROVIDED ROOF CURB. REFER TO VIEW A2 ON SHEET M0.1.
- 2 CENTRIFUGAL DOWNBLAST EXHAUST FAN MOUNTED ON MANUFACTURER PROVIDED ROOF CURB, REFER TO VIEW A1 ON SHEET M0.1.
- 3 ROOF ACCESS HATCH REFER TO ARCHITECTURAL SHEETS.
- 4 KITCHEN FREEZER CONDENSING UNIT MOUNTED ON ROOFTOP. PROVIDED BY OWNER. COORDINATE EXACT LOCATION ON SITE AND ROUTE REFRIGERATION PIPING THROUGH ROOF PENETRATION (BY OTHERS).
- 5 KITCHEN REFRIGERATOR CONDENSING UNIT MOUNTED ON ROOFTOP. PROVIDED BY OWNER. COORDINATE EXACT LOCATION ON SITE AND ROUTE REFRIGERATION PIPING THROUGH ROOF PENETRATION (BY OTHERS).
- 6 REFRIGERATION PIPING ROOF PENETRATION (BY OTHERS).
- 7 KITCHEN ICEMAKER CONDENSING UNIT MOUNTED ON ROOFTOP. PROVIDED BY OWNER. COORDINATE EXACT LOCATION ON SITE AND ROUTE REFRIGERANT PIPING THROUGH ROOF PENETRATION (BY OTHERS).
- 8 KITCHEN MULTIPLEX CONDENSING UNIT MOUNTED ON ROOFTOP. PROVIDED BY OWNER. COORDINATE EXACT LOCATION ON SITE AND ROUTE REFRIGERANT PIPING THROUGH ROOF PENETRATION (BY OTHERS).
- 9 ROUTE CONDENSATE LINE DOWN THROUGH ROOF. REFER TO SHEET M1.1 FOR CONTINUATION.



ms consultants, inc.
engineers, architects, planners
2221 Schrock Road
Columbus, Ohio 43229
p 614.898.7100
f 614.898.7570
www.msconsultants.com

**WHATABURGER 20-M
LEE'S SUMMIT**

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO



NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.



12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No.20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01

Client Project No.:

Drawing Title:

MECHANICAL ROOF PLAN

Date: 12/22/2020 Phase: BID SET

Designed: DCU

Drawn: DCU


Checked: KFF

Drawing No.:

M2.1


C:\Backup\Revit\WB-Lees Summit-MO_Y18_MECH_200921_dum.rvt

12/7/2021 3:56:10 PM




NOTE: COORDINATE FINAL DIMENSIONS WITH ROOF INSTALLER.


A1 ROOF MOUNTED EXHAUST FAN AND CURB DETAIL
N.T.S.



A2 ROOFTOP GREASE EXHAUST FAN DETAIL
N.T.S.




C3 LOW PROFILE HOOD DETAIL
N.T.S.




NOTE: INSTALL FLEXIBLE DUCTWORK SUPPORTS AT ALL ROUND NECK OUTLETS/INLETS UNLESS OTHERWISE NOTED ON DRAWINGS.


B2 DIFFUSER CONNECTION DETAIL
N.T.S.



C4 ROOFTOP HVAC UNIT DETAIL
N.T.S.



B4 HOOD EXHAUST DUCT DETAIL
N.T.S.



A3 PLENUM SLOT DIFFUSER DETAIL
N.T.S.



ms consultants, inc.
engineers, architects, planners
2221 Schrock Road
Columbus, Ohio 43229
p 614.898.7100
f 614.898.7570
www.msconsultants.com

WHATABURGER 20-M
LEE'S SUMMIT

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO



NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.



12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No.20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01

Client Project No.:

Drawing Title:

MECHANICAL DETAILS

Date: 12/22/2020 Phase: BID SET

Designed: DCU


Drawn: DCU

Checked: KFF

Drawing No.:

M5.1

C:\Backup\Revit\WB-Lees Summit\MO_Y18_MECH_200921_dum.rvt 12/7/2021 3:56:11 PM





ms consultants, inc.
engineers, architects, planners
2221 Schrock Road
Columbus, Ohio 43229
p 614.898.7100
f 614.898.7570
www.msconsultants.com


WHATABURGER 20-M
LEE'S SUMMIT

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO



WHATABURGER

NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.



12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No.20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01
Client Project No.:
Drawing Title:
MECHANICAL DETAILS

Date: 12/22/2020 Phase: BID SET
Designed: DCU
Drawn: DCU
Checked: KFF

Drawing No.:
M5.2

C:\Backup\Revit\WB-Lees Summit-MO_Y18_MECH_200921_dum.rvt 12/7/2021 3:56:12 PM

ROOFTOP UNIT SCHEDULE																											
TAG	SERVES	MANUFACTURER	MODEL	REFRIGERANT	AIR FLOW	AIR FLOW VENTILATION	FAN							COOLING						HEATING			VOLTAGE	PHASE	MCA	WEIGHT (LB)	NOTES
							FAN TYPE	MOTOR HP	QUANTITY FANS	DRIVE TYPE	RPM	ESP (IN W.C.)	TSP (IN W.C.)	TOTAL CAPACITY (MBH)	CAPACITY SENSIBLE (MBH)	EAT DB	EAT WB	LAT DB	LAT WB	TOTAL CAPACITY (KW)	EAT (°F)	MAX LAT (°F)					
RTU-1	DINING PERIMETER	LENNOX	LCH156H4M	R-410A	4000 CFM	1300 CFM	BELT	3	1	BELT	998	1.00	1.51	154	150	81.6	76.7	56.9	56.3	60	-1	95	208 V	3	139	2056	1,2,3,4,5,6,7,8,9
RTU-2	DINING INTERIOR	LENNOX	LCH156H4M	R-410A	4000 CFM	1300 CFM	BELT	3	1	BELT	998	1.00	1.51	154	150	81.6	76.7	56.9	56.3	60	-1	95	208 V	3	139	2056	1,2,3,4,5,6,7,8,9
RTU-3	KITCHEN	LENNOX	LCH240H4M	R-410A	6000 CFM	1500 CFM	BELT	5	1	BELT	895	1.00	1.15	235	146	81.6	76.7	53.4	54.1	90	-1	95	208 V	3	209	2446	1,2,3,4,5,6,7,8,9

NOTES:
1. PROVIDE WITH PREMIUM EFFICIENCY MOTORS IN ACCORDANCE WITH NEMA MG-1.
2. PROVIDE WITH SUPPLY AND RETURN SMOKE DETECTORS TO SHUT DOWN UNIT UPON SMOKE DETECTION.
3. PROVIDE WITH NETWORK CARD FOR INTERFACE WITH BUILDING MANAGEMENT SYSTEM.
4. SIZE AND SELECT ROOFTOP UNITS BASED ON 0.4% DEHUMIDIFICATION DESIGN DAY CONDITIONS OF 86.7°F DB, 76.5°F DEWPOINT.
5. PROVIDE HOT GAS REHEAT.
6. PROVIDE VARIABLE SPEED MOTOR.
7. PROVIDE MODULATING OUTSIDE AIR DAMPER.
8. PROVIDE ULTRA LOW LEAKAGE ECONOMIZER WITH BAROMETRIC RELIEF DAMPER, AND FAULT DETECTION AND DIAGNOSTIC.
9. PROVIDE FACTORY MOUNTED AND WIRED CONDENSATE OVERFLOW SWITCH.

EXHAUST FAN SCHEDULE													
TAG	TYPE	MANUFACTURER	MODEL	AIR FLOW	TSP (IN W.C.)	RPM	BHP	HP	DRIVE TYPE	VOLTAGE	PHASE	WEIGHT (LBS.)	NOTES
EF-1	ROOF-MOUNTED CENTRIFUGAL DOWNBLAST	GREENHECK	G-088-VG	300 CFM	0.60	1257	0.07	0.07	DIRECT	120	1	38	1,2
KEF-1	ROOF-MOUNTED CENTRIFUGAL UPBLAST	GREENHECK	CUBE-161HP-10	1913 CFM	0.75	1366	0.57	0.75	BELT	208	1	81	2,3,4
KEF-2	ROOF-MOUNTED CENTRIFUGAL UPBLAST	GREENHECK	CUBE-121	1216 CFM	0.75	1418	0.30	0.33	BELT	208	1	64	2,3,4

NOTES:
1. PROVIDE INSULATED 12" ROOF CURB.
2. PROVIDE WITH INTEGRAL DISCONNECT SWITCH.
3. PROVIDE GREASE BOX.
4. PROVIDE INSULATED AND VENTED 18" ROOF CURB.

AIR DEVICE SCHEDULE													
TAG	MANUFACTURER	MODEL	FACE SIZE	NECK SIZE (IN.)	MAX NC	PATTERN	MOUNTING	SLOT LENGTH	SLOT WIDTH	SLOT QTY	SYSTEM CLASSIFICATION	COMMENTS	
A3	TITUS	TMS	24 X 24	6	30	4-WAY	LAY-IN	-	-	-	SUPPLY AIR	1	
A4	TITUS	TMS	24 X 24	8	30	4-WAY	LAY-IN	-	-	-	SUPPLY AIR	1	
A5	TITUS	TMS	24 X 24	10	30	4-WAY	LAY-IN	-	-	-	SUPPLY AIR	1	
A6	TITUS	TMS	24 X 24	12	30	4-WAY	LAY-IN	-	-	-	SUPPLY AIR	1	
B3	TITUS	TMS	24 X 24	6	30	4-WAY	FLANGE	-	-	-	SUPPLY AIR	1,2	
C8	TITUS	50F	24 X 24	18 X 18	30	4-WAY	LAY-IN	-	-	-	RETURN AIR		
F1	TITUS	50F	12 X 12	6 X 6	30	4-WAY	FLANGE	-	-	-	EXHAUST AIR	2	
H1	TITUS	TBDI-30	24 X 3-1/2	12	30	2-WAY	FLANGE	48	3/4	2	SUPPLY AIR	3	
H9	TITUS	TBDI-30	60 X 3-1/2	8	30	2-WAY	FLANGE	60	3/4	2	SUPPLY AIR	3	
H10	TITUS	TBDI-80	60 X 7-1/2	12	30	2-WAY	FLANGE	60	1-1/2	3	SUPPLY AIR	3	
L1	TITUS	FL-1S-JT	SEE PLANS		30	1-WAY	FLANGE	CONTINUOUS	1-1/2	1		4	
P1	TITUS	FBPI	48 X 3-1/2	8	30	-	FLANGE	60	-	-	SUPPLY AIR	3	
P3	TITUS	FBPI	60 X 3-1/2	8	30	-	FLANGE	60	-	-	SUPPLY AIR	3	

NOTES:
1. PROVIDE BACKPAN INSULATION.
2. PROVIDE PLASTER FRAME FOR MOUNTING IN GYP. CEILING.
3. PROVIDE INSULATED PLENUM.
4. CONTINUOUS LINEAR SLOT DIFFUSER TO BE INSTALLED IN GYP. CEILING. PROVIDE INSULATED SUPPLY AIR PLENUMS AS SCHEDULED FOR A COMPLETE SYSTEM.

ELECTRIC UNIT HEATER SCHEDULE						
TAG	MANUFACTURER	MODEL	HEATING TOTAL CAPACITY (BTU/HR.)	VOLTAGE	PHASE	WEIGHT (LB.)
UH-1	REZNOR	EGW	5118	208 V	1	20

AIR BALANCE AND VENTILATION CALCULATION:

TOTAL OUTSIDE AIR INTAKE = 4100 CFM

TOTAL GREASE HOOD EXHAUST = 3129 CFM
TOTAL RESTROOM EXHAUST = 300 CFM

OUTSIDE AIRFLOW - (GREASE HOOD EXHAUST AIRFLOW + RESTROOM EXHAUST AIRFLOW) = NET POSITIVE AIRFLOW

4100 CFM - (3129 + 300) = 671 CFM

ASHRAE 62.1 VENTILATION AIRFLOW REQUIRED = 1457 CFM
IMC 2018 VENTILATION AIRFLOW REQUIRED = 1457 CFM



ms consultants, inc.
engineers, architects, planners
2221 Schrock Road
Columbus, Ohio 43229
p 614.898.7100
f 614.898.7570
www.msconsultants.com

WHATABURGER 20-M
LEE'S SUMMIT

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO



NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.



12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No.20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01

Client Project No.:

Drawing Title:



MECHANICAL SCHEDULES

Date: 12/22/2020 Phase: BID SET


Designed: DCU Drawing No.:
Drawn: DCU
Checked: KFF

M6.1

AE	ANALYZER ELEMENT
DDC	DIRECT DIGITAL CONTROL
BMS	BUILDING MANAGEMENT SYSTEM
RDC	ROOFTOP UNIT DDC CONTROLLER
FACP	FIRE ALARM CONTROL PANEL




FIRE/SMOKE CONTROL:
UPON SENSING A BUILDING FIRE ALARM, THE KITCHEN EXHAUST FAN SHALL BE CYCLED OFF THRU THE FIRE ALARM PANEL. FAN STATUS SHALL BE REPORTED TO THE BAS.



VARIABLE SPEED OPERATION
BASED ON THE RTU INTERNAL CONTROLS, THE RDC SHALL VARY THE FAN SPEED AND OUTSIDE AIR DAMPER POSITION, BASED ON CALL FOR COOLING IN THE SPACE. THERE SHALL BE A MINIMUM OF TWO FAN SPEEDS AND TWO DAMPER POSITIONS TO MAINTAIN CONSTANT OUTSIDE AIRFLOW FOR EACH FAN SPEED SETTINGS. THE RDC SHALL LOAD AND UNLOAD COMPRESSORS BASED ON THE UNIT INTERNAL CONTROLS TO CONDITION OR DEHUMIDIFY THE SPACE AS NEEDED.

C. GENERAL ALARM
ANY TROUBLE ALARM OR FAULT WITHIN THE UNIT ONBOARD CONTROLS WILL GENERATE A GENERAL ALARM TO THE BMS.



ALARMS:
ALARMS SHALL BE PROVIDED AS FOLLOWS:

1. FAN FAILURE: FAN COMMANDED ON BUT STATUS IS OFF.
2. FAN IN HAND: FAN COMMANDED OFF BUT STATUS IS ON.
3. FAN BELT FAILURE: MOTOR AMPERAGE READS ZERO AS MEASURED BY CURRENT TRANSDUCER

C3 GENERAL EXHAUST FAN CONTROL DIAGRAM
N.T.S.

A1) PACKAGED ROOFTOP UNIT CONTROLS DIAGRAM
N.T.S.



WHATABURGER 20-M LEE'S SUMMIT

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO



NOTICE: THIS ARCHITECTURAL AND ENGINEERING
DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED
ONLY PURSUANT TO THE AGREEMENT WITH THE
ARCHITECT. NO OTHER USE, DISSEMINATION, OR
DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN
CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS
OF COPYRIGHT AND OTHERWISE ARE HEREBY
SPECIFICALLY RESERVED.



12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No.20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01

Client Project No.

Drawing Title:

MECHANICAL CONTROLS

Date: 12/22/2020

Phase: BID SET

Designed: DCU

Drawing No.:

Drawn : DCU


A43-1

M7.1

CONTROLS I/O LIST									
Device No.	Service	I/O Board Point	Terminals	Description	AI	AO	DI	DO	Remarks
RTU-1	Kitchen	Input 1	TB1-1/2	Space Temperature	1				
RTU-1	Kitchen	Input 2	TB1-3/4	Supply Temperature	1				
RTU-1	Kitchen	Input 3	TB1-5/6	Return Humidity	1				
RTU-1	Kitchen	Input 4	TB1-7/8	Outside Air Damper Actuator Position	1				
RTU-1	Kitchen	Input 1	TB2-1/2	Return Air Damper Position	1				
RTU-1	Kitchen	Input 2	TB2-3/4	SPARE					
RTU-1	Kitchen	Input 3	TB2-5/6	SPARE					
RTU-1	Kitchen	Input 4	TB2-7/8	SPARE					
RTU-1	Kitchen	Input 1	TB3-1/2	Return Air Smoke Detector			1		Dry Contact
RTU-1	Kitchen	Input 2	TB3-3/4	Supply Air Smoke Detector			1		Dry Contact
RTU-1	Kitchen	Input 3	TB3-5/6	Supply Fan Run Status			1		Dry Contact
RTU-1	Kitchen	Input 4	TB3-7/8	Electric Heating Coil Status			1		Dry Contact
RTU-1	Kitchen	Input 1	TB4-1/2	Compressor Status			1		Dry Contact
RTU-1	Kitchen	Input 2	TB4-3/4	Kitchen Exhaust Fan 1 Run Status			1		Dry Contact
RTU-1	Kitchen	Input 3	TB4-5/6	Kitchen Exhaust Fan 2 Run Status			1		Dry Contact
RTU-1	Kitchen	Input 4	TB4-7/8	Kitchen Exhaust Fan 3 Run Status			1		Dry Contact
RTU-1	Kitchen	Output 1	+/-	Outside Air Damper Actuator Position Cmd			1		Modulating Damper
RTU-1	Kitchen	Output 2	+/-	Return Air Damper Position Cmd			1		Modulating Damper
RTU-1	Kitchen	Output 3	+/-	SPARE					
RTU-1	Kitchen	Output 4	+/-	SPARE					
RTU-1	Kitchen	Relay Out 1	NO/C	Supply Fan Start/Stop Cmd				1	Relay is Form C (NO/C/NC) and can be set in field
RTU-1	Kitchen	Relay Out 2	NO/C/NC	SPARE					
RTU-1	Kitchen	Relay Out 3	NO/C/NC	SPARE					
RTU-1	Kitchen	Relay Out 4	NO/C/NC	SPARE					
RTU-1	Kitchen	Relay Out 5	NO/C/NC	SPARE					
RTU-1	Kitchen	Relay Out 6	NO/C/NC	SPARE					
RTU-1	Kitchen	Relay Out 7	NO/C/NC	SPARE					
RTU-1	Kitchen	Relay Out 8	NO/C/NC	SPARE					
Sub-total Points Connected					5	2	9	0	Multiflex RCB Controller has 16 Inputs (AI or DI), 8 Relay Outputs, 4 Analog Outputs (AO)
RTU-2	Dining Room	Input 1	TB1-1/2	Space Temperature	1				
RTU-2	Dining Room	Input 2	TB1-3/4	Supply Temperature	1				
RTU-2	Dining Room	Input 3	TB1-5/6	Return Humidity	1				
RTU-2	Dining Room	Input 4	TB1-7/8	Outside Air Damper Actuator Position	1				
RTU-2	Dining Room	Input 1	TB2-1/2	Return Air Damper Position	1				
RTU-2	Dining Room	Input 2	TB2-3/4	SPARE					
RTU-2	Dining Room	Input 3	TB2-5/6	SPARE					
RTU-2	Dining Room	Input 4	TB2-7/8	SPARE					
RTU-2	Dining Room	Input 1	TB3-1/2	SPARE					
RTU-2	Dining Room	Input 2	TB3-3/4	SPARE					
RTU-2	Dining Room	Input 3	TB3-5/6	Return Air Smoke Detector			1		Dry Contact
RTU-2	Dining Room	Input 4	TB3-7/8	Supply Air Smoke Detector			1		Dry Contact
RTU-2	Dining Room	Input 1	TB4-1/2	Supply Fan Run Status			1		Dry Contact
RTU-2	Dining Room	Input 2	TB4-3/4	Electric Heating Coil Status			1		Dry Contact
RTU-2	Dining Room	Input 3	TB4-5/6	Air Cooled Condenser Status			1		Dry Contact
RTU-2	Dining Room	Input 4	TB4-7/8	Clogged Filter			1		Dry Contact
RTU-2	Dining Room	Output 1	+/-	Outside Air Damper Actuator Position Cmd			1		Modulating Damper
RTU-2	Dining Room	Output 2	+/-	Return Air Damper Position Cmd			1		Modulating Damper
RTU-2	Dining Room	Output 3	+/-	SPARE					
RTU-2	Dining Room	Output 4	+/-	SPARE					
RTU-2	Dining Room	Relay Out 1	NO/C	Supply Fan Start/Stop Cmd				1	Relay is Form C (NO/C/NC) and can be set in field
RTU-2	Dining Room	Relay Out 2	NO/C/NC	SPARE					
RTU-2	Dining Room	Relay Out 3	NO/C/NC	SPARE					
RTU-2	Dining Room	Relay Out 4	NO/C/NC	SPARE					
RTU-2	Dining Room	Relay Out 5	NO/C/NC	SPARE					
RTU-2	Dining Room	Relay Out 6	NO/C/NC	SPARE					
RTU-2	Dining Room	Relay Out 7	NO/C/NC	SPARE					
RTU-2	Dining Room	Relay Out 8	NO/C/NC	SPARE					
Sub-total Points Connected					5	2	6	1	Multiflex RCB Controller has 16 Inputs (AI or DI), 8 Relay Outputs, 4 Analog Outputs (AO)
RTU-3	Dining Room	Input 1	TB1-1/2	Space Temperature	1				
RTU-3	Dining Room	Input 2	TB1-3/4	Supply Temperature	1				
RTU-3	Dining Room	Input 3	TB1-5/6	Return Humidity	1				
RTU-3	Dining Room	Input 4	TB1-7/8	Outside Air Damper Actuator Position	1				
RTU-3	Dining Room	Input 1	TB2-1/2	Return Air Damper Position	1				
RTU-3	Dining Room	Input 2	TB2-3/4	SPARE					
RTU-3	Dining Room	Input 3	TB2-5/6	SPARE					
RTU-3	Dining Room	Input 4	TB2-7/8	SPARE					
RTU-3	Dining Room	Input 1	TB3-1/2	SPARE					
RTU-3	Dining Room	Input 2	TB3-3/4	SPARE					
RTU-3	Dining Room	Input 3	TB3-5/6	Return Air Smoke Detector			1		Dry Contact
RTU-3	Dining Room	Input 4	TB3-7/8	Supply Air Smoke Detector			1		Dry Contact
RTU-3	Dining Room	Input 1	TB4-1/2	Supply Fan Run Status			1		Dry Contact
RTU-3	Dining Room	Input 2	TB4-3/4	Electric Heating Coil Status			1		Dry Contact
RTU-3	Dining Room	Input 3	TB4-5/6	Air Cooled Condenser Status			1		Dry Contact
RTU-3	Dining Room	Input 4	TB4-7/8	Clogged Filter			1		Dry Contact
RTU-3	Dining Room	Output 1	+/-	Outside Air Damper Actuator Position Cmd			1		Modulating Damper
RTU-3	Dining Room	Output 2	+/-	Return Air Damper Position Cmd			1		Modulating Damper
RTU-3	Dining Room	Output 3	+/-	SPARE					
RTU-3	Dining Room	Output 4	+/-	SPARE					
RTU-3	Dining Room	Relay Out 1	NO/C	Supply Fan Start/Stop Cmd				1	Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 2	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 3	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 4	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 5	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 6	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 7	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
RTU-3	Dining Room	Relay Out 8	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
Sub-total Points Connected					5	3	4	1	Multiflex RCB Controller has 16 Inputs (AI or DI), 8 Relay Outputs, 4 Analog Outputs (AO)
SSC	Supervisor Controller	RL1	NO/C (16/17)	Relay Output #1 to Lighting Panel				1	Relay is Form C (NO/C/NC) and can be set in field
SSC	Supervisor Controller	RL2	NO/C (19/17)	Relay Output #2 to Lighting Panel				1	Relay is Form C (NO/C/NC) and can be set in field
SSC	Supervisor Controller	RL3	NO/C (21/24)	Alarm (Combo Audible/Visual Unit)					Relay is Form C (NO/C/NC) and can be set in field
SSC	Supervisor Controller	RL4	NO/C/NC	SPARE					Relay is Form C (NO/C/NC) and can be set in field
SSC	Supervisor Controller	PB1	+/-	Outside Air Temperature	1				From Outdoor Weather Station (Emerson 809-7001)
SSC	Supervisor Controller	PB2	+/-	Outdoor Humidity	1				From Outdoor Weather Station (Emerson 809-7001)
SSC	Supervisor Controller	PB3	+/-	Light Level Sensor	1				From Outdoor Weather Station (Emerson 809-7001)
SSC	Supervisor Controller	PB4	+/-	Walk-in Freezer Temperature	1				
SSC	Supervisor Controller	PB5	+/-	Walk-in Cooler Temperature	1				
SSC	Supervisor Controller	PB6	+/-	Reach In Meat Box Temperature	1				
SSC	Supervisor Controller	PB7	+/-	SPARE					
SSC	Supervisor Controller	PB8	+/-	SPARE					
SSC	Supervisor Controller	DI1	10/9	Emergency Shutdown Pushbutton #1				1	Dry Inputs
SSC	Supervisor Controller	DI2	11/9	Emergency Shutdown Pushbutton #2				1	Dry Inputs
SSC	Supervisor Controller	DI3	12/9 or 14	SPARE					Dry Contact
SSC	Supervisor Controller	DI4	13/9 or 14	SPARE					Dry Contact
Sub-total Points Connected					6	0	2	2	Multiflex RCB Controller has 16 Inputs (AI or DI), 8 Relay Outputs, 4 Analog Outputs (AO)
Total Points Connected					21	7	21	4	

A1 CONTROLS I/O List

B2 CONTROL SYSTEM DIAGRAM



GENERAL NOTES

- A. DIAGRAM IS FUNCTIONAL REPRESENTATION OF SYSTEM ARCHITECTURE. FINAL CONFIGURATION DEPENDENT UPON ACTUAL EQUIPMENT SELECTED.
- B. SENSORS SHALL BE PROVIDED AND USED AS SHARED INFORMATION POINTS IN THE DDC SYSTEM CONTROL PROGRAMS.
- C. PANELS SHALL BE FABRICATED, PRE-WIRED AND TESTED AT THE VENDOR FACILITY TO PROVIDE A COMPLETE INSTALLATION.
- D. PROVIDE PROGRAMMING OF THE DDC SYSTEM AND COMMISSIONING REPORT THAT INCLUDES SIGN-OFF BY RESTAURANT MANAGER AND CORPORATE HEADQUARTERS OF THE INSTALLATION.
- E. PROVIDE REQUIRED WIRING AND ASSOCIATED ACCESSORIES TO INTERCONNECT THE KITCHEN HOOD ANSUL SYSTEMS WITH THE KITCHEN UNIT RTU TO SHUT DOWN UNIT IF ANSUL SYSTEM IS ACTIVATED.
- F. REFER TO DWG M1.1 FOR DDC CONTROL PANEL LOCATIONS.

KEYNOTES

- 1 ETHERNET SWITCH (BY CORPORATE HEADQUARTERS).
- 2 TRANSFORMER 120VAC TO 24VAC (75VA).
- 3 EMERSON MULTIFLEX RCB CONTROLLER (810-3062).
- 4 EMERSON SITE SUPERVISOR CONTROLLER.
- 5 EMERSON SITE SUPERVISOR DISPLAY 10.1 IN W/AC ADAPTER (818-7240).
- 6 FUSED TERMINAL BLOCK.

ms consultants, inc.
engineers, architects, planners
2221 Schrock Road
Columbus, Ohio 43229
p 614.898.7100
f 614.898.7570
www.msconsultants.com

WHATABURGER 20-M LEE'S SUMMIT

1460 NE DOUGLAS ST
LEE'S SUMMIT, MO

NOTICE: THIS ARCHITECTURAL AND ENGINEERING DRAWING IS GIVEN IN CONFIDENCE AND SHALL BE USED ONLY PURSUANT TO THE AGREEMENT WITH THE ARCHITECT. NO OTHER USE, DISSEMINATION, OR DUPLICATION MAY BE MADE WITHOUT PRIOR WRITTEN CONSENT OF THE ARCHITECT. ALL COMMON LAW RIGHTS OF COPYRIGHT AND OTHERWISE ARE HEREBY SPECIFICALLY RESERVED.

12/22/20
PROFESSIONAL OF RECORD:
JASON E. CHRISTOFF No.20012002143
EXP DATE: 12/31/20

REV	DESCRIPTION	DATE

Project No.: 62-40497-01
Client Project No.:
Drawing Title:
CONTROL SYSTEM DIAGRAM

Date: 12/22/2020 Phase: BID SET
Designed: DCU Drawing No.:
Drawn: DCU
Checked: KFF

M8.1