
RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI 03/05/2021



NOTE:

ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.

ELEVATIONS:

GARAGE DOORS SHALL MEET DASMA FOR ULTIMATE DESIGN WIND SPEED OF 115 MPH REQUIREMENTS. WALL FRAMING SHALL BE DOUGLAS FIR LARCH #2 UNLESS OTHERWISE NOTED.

IN BEARING WALLS, STUDS WHICH ARE NOT MORE THAN TEN FEET IN LENGTH SHALL BE SPACED NOT MORE THAN IS SPECIFIED BY IRC TABLE R602.3(5) FOR CORRESPONDING STUD SIZE. WATER-RESISTIVE EXTERIOR WALL BARRIER IN WALL SECTION SHALL COMPLY

WITH IRC R703.2. WHEN APPLICABLE, CONTINUOUS STUDS BETWEEN FLOOR AND ROOF/CEILING DIAPHRAGM SHALL COMPLY WITH IRC R602.3.


ALL UNMARKED HEADERS SHALL BE A MINIMUM #2 DOUGLAS FIR LARCH (2) 2 X 10 ON LOAD BEARING WALLS.


SHIPLAP SIDING MUST BE FASTENED AT BOTH UNDERLAP AND OVERLAP.



FR[

 FRONT & REAR ELEVATION NOTES 1.12 TOP OF FOOTING DEPTH DETERMINED PER SITE. 1.41 6X6 CEDAR POST 2.62 DOUBLED 1X8" LP SMART TRIM. 1 1/2" ARCH ON GARAGE DOOR TRIM UNLESS NOTED OTHERWISE OF ELEVATION. 3.11 LP SMART PANEL LAP SIDING WITH 5/4X6 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.14 CEDAR SHAKE SHINGLE SIDING. 3.17 MANUFACTURED STONE VENEER. 	CPG DBA
 1.41 6X6 CEDAR POST 2.62 DOUBLED 1X8" LP SMART TRIM. 1 1/2" ARCH ON GARAGE DOOR TRIM UNLESS NOTED OTHERWISE O ELEVATION. 3.11 LP SMART PANEL LAP SIDING WITH 5/4X6 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE. 3.14 CEDAR SHAKE SHINGLE SIDING. 	
 2.62 DOUBLED 1X8" LP SMART TRIM. 1 1/2" ARCH ON GARAGE DOOR TRIM UNLESS NOTED OTHERWISE OF ELEVATION. 3.11 LP SMART PANEL LAP SIDING WITH 5/4X6 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE. 3.14 CEDAR SHAKE SHINGLE SIDING. 	
ELEVATION. 3.11 LP SMART PANEL LAP SIDING WITH 5/4X6 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE. 3.14 CEDAR SHAKE SHINGLE SIDING.	
 SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE. 3.14 CEDAR SHAKE SHINGLE SIDING. 	
 3.13 LP SMART PANEL SIDING WITH 3/4X4 LP SMART TRIM AROUND DOORS, WINDOWS, AND CORNERS UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE. 3.14 CEDAR SHAKE SHINGLE SIDING. 	SUMMIT
UNLESS NOTED OTHERWISE. BOTTOM OF SIDING SHALL BE A MINIMUM OF 6" ABOVE GRADE. 3.14 CEDAR SHAKE SHINGLE SIDING.	HOMES
3.14 CEDAR SHAKE SHINGLE SIDING.	120 SE 30TH ST. LEE'S SUMMIT, MO 64082
3.17 MANUFACTURED STONE VENEER	816-246-6700
3.18 CAST STONE CAP	COPYRIGHT 2017
3.44 BOX BASE WITH STONE VENEER TO 36" AND 8X8	THIS DRAWING HAS BEEN PREPARED BY SUMMIT HOMES, OR UNDER THEIR DIRECT SUPERVISION AS AN INSTRUMENT OF SERVICE AND IS INTENDED FOR USE
CEDAR POST. SEE PLAN FOR FINISHED SIZE. 3.55 6"X8"X11" CEDAR CORBEL WITH CHAMFERED EDGE	SPECIFICATIONS, AND DESIGNS, INCLUDING THE OVERALL LAYOUT, FORM, AND COMPOSITION OF SPACES ARE PROTECTED BY COPYRIGHT REGISTERED
LATE 3.58 2X CEDAR TRIM – SEE ELEVATIONS FOR SIZE. 3.62 CEDAR SHUTTERS. ALL SHUTTERS TO BE 18" WID	TO CPG, INC. ANY REPRODUCTION, USE, OR DISCLOSURE OF THE INFORMATION CONTAINED HEREIN WITHOUT THE WRITTEN CONSENT FROM CPG, INC.
USING (3) 2X6 BOARDS. LP SMART TRIM TO BE INSTALLED AROUND WINDOW PRIOR TO SHUTTER	BIDDING AND CONSTRUCTION OF THIS PROJECT IS STRICTLY PROHIBITED.
INSTALLED AROUND WINDOW PRIOR TO SHOTTER INSTALLATION. 4.00 COVERING WILL HAVE 1 ROOF VENT AND 4 SOFFI	т
VENTS	ADDRESS:
4.11 MINIMUM ROOFING COMPOSITION- 30 YR COMPOS SHINGLES ON 15# FELT ON 1/2" OSB SHEATHING AS REQUIRED BY CODE.	
AS REQUIRED BY CODE. 4.31 BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR POSITIVE DRAINAGE.	N P
7.25 TOP OF FIREPLACE VENT TO BE 3'-8" ABOVE FIF	RST
FLOOR DECK.	
	FOR SMAN IDE #5
RONT ELEVATION (S) BRACKET DETAIL (S)	
$\frac{\text{KLINI} \text{ELEVATION}}{\text{SCALE:} 1/4' = 1'-0'} \begin{pmatrix} 2 \\ 2 \end{pmatrix} \qquad \frac{\text{BRACKET DETAIL}}{\text{SCALE:} 1' = 1'-0'} \begin{pmatrix} 3 \\ 3 \end{pmatrix}$	
GENERAL NOTES	
DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDAR	RD
TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VA	
WINDOW SIZES ARE WRITTEN IN FEET AND INCHES PER	
INDUSTRY STANDARDS. EX: 3050 SH = 3'-0" X 5'-0" SINGLE HUNG, 3066 FIX = 3'-0" X 6'-6" FIXED.	
	PROFESSIONAL SEAL:
SHEET INDEX	SPECIF MISCON
A1. FRONT AND REAR ELEVATION	BRADLEY
A2. LEFT AND RIGHT ELEVATION A3. FOUNDATION FLOOR PLAN	+ Huxqk □ □ HUXQk + HUXQk+ HUX
A3. FOUNDATION FLOOR PLAN	
A5. ROOF PLAN	
	RESIDENTIAL ENGINEERING SERVICES,LLC IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS
	ONLY. ARCHITECTURAL PLANS WERE PRODUCED BY OTHERS.
FINISHED	RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300
DECK MAIN FLOOR 1703	LEE'S SUMMIT, MO 64063 816-399-4901
ARIES	
ARIES TOTAL 2828 UNFINISHED 395	DRAWN BY:
ARIES TOTAL 2828	J. ROSENBLUM
ARIES TOTAL 2828 UNFINISHED 2828 LOWER LEVEL - UNFINISHED 395 COVERED DECK 140	J. ROSENBLUM
ARIES ARIES TOTAL 2828 TOTAL 2828 UNFINISHED 395 COVERED DECK 140 PATIO 190 GARAGE 663	
ARIES Image: Constraint of the second se	J. ROSENBLUM
ARIES ARIES TOTAL 2828 TOTAL 2828 UNFINISHED 395 COVERED DECK 140 PATIO 190 GARAGE 663	ISSUE DATE:
ARIES Image: Constraint of the second se	ISSUE DATE:
ARIES TOTAL 2828 UNFINISHED LOWER LEVEL - UNFINISHED 395 COVERED DECK 140 PATIO GARAGE ENGINEER TRUSS I-JOIST RES MID-AMERICA	ISSUE DATE: 02.09.21
ARIES ARIES TOTAL 2828 UNFINISHED LOWER LEVEL - UNFINISHED 395 COVERED DECK 140 PATIO 190 GARAGE ENGINEER TRUSS I-JOIST RES MID-AMERICA	ISSUE DATE: 02.09.21 SHEET NUMBER:
ARIES ARIES TOTAL 2828 TOTAL 2828 UNFINISHED 395 COVERED DECK 140 PATIO 190 GARAGE 663 ENGINEER TRUSS I-JOIST RES MID-AMERICA REVISIONS NO. DATE DESCRIPTION	ISSUE DATE: 02.09.21





SUMMERER SOUPLOT PLAN FOR FOUNDATION ELEVATION HEIGHTS **

NOTE:

ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.

FOUNDATION NOTES:

ALL FOOTINGS MEET OR EXCEED MINIMUM FROST DEPTH OF 36".

SOIL BEARING CAPACITY SHALL BE 2000 PSF. COMPRESSIVE STRENGTH OF CONCRETE F'C COMPRESSIVE STRENGTH SHALL BE AS SPECIFIED IN IRC TABLE R402.2. REQUIRED AIR ENTRAINMENT SHALL BE 5-7%. ALL FOUNDATION WALLS ENCLOSING BELOW GRADE SPACE SHALL BE DAMPPROOFED. DAMPPRROFING SHALL EXTEND FROM THE EDGE OF THE FOOTING TO THE FINISHED GRADE (R-406.1). METHOD OF DAMPPROOFING OR WATERPROOFING SHALL BE A MINIMUM 6-MIL THICK MOISTURE BARRIER OVER

POROUS GRAVEL BASE UNDER BASEMENT FLOOR SLAB PER R405.2.2. LAP JOINTS SHALL BE A MINIMUM 6". FOUNDATION WALLS SHALL BE DAMPPROOFED PER IRC SECTION R406. FOUNDATION DRAINAGE WILL BE IN ACCORDANCE WITH WITH IRC SECTION R405. BASEMENT EGRESS OPENINGS SHALL BE IN ACCORDANCE WITH IRC SECTION R310.1

ALL INTERIOR FOOTINGS OF LOAD BEARING WALLS AND COLUMNS SHALL BE ISOLATED FROM THE BASEMENT FLOOR SLAB. ALL ANCHOR BOLTS SHALL NOT BE SPACED MORE THAN 6' O.C. AND BE EMBEDDED INTO THE CONCRETE A MINIMUM OF 7" .

ALL UNMARKED HEADERS SHALL BE A MINIMUM #2 DOUGLAS FIR LARCH (2) 2 X 10 ON LOAD BEARING WALLS.


BACKFILL SHALL NOT BE PLACED AGAINST THE WALL UNTIL THE WALL HAS SUFFICIENT STRENGTH OR HAS BEEN SUFFICIENTLY BRACED TO PREVENT DAMAGE BY BACKFILL.


IF BASEMENT SLAB ELEVATION IS ABOVE GRADE CONSULT ENGINEER.

STEEL BEAM FLANGE WIDTH: W8X10 - 3.94" W8x13- 4"


IS	OLATE	D	FDI	JT	ING	S	AND	COLU	MN PADS
SYM	PIER PAD SIZE	DE	PTH	RE		RCE	NIMUM MENT I STE	GRADE	SCHEDULE 40 STEEL COLUMN, MIN FY = 35 KSI
	30″×30″	1'	-0″		(5)	#4	BAR	E.W.	3″ DIAMETER
B	36″×36″	1'	-0″		(6)	#4	BAR	E.W.	3″ DIAMETER
<u>c</u>	42″×42″	1'	-2″		(7)	#4	BAR	E.W.	3″ DIAMETER
	48″×48″	1'	-4″		(8)	#4	BAR	E.W.	3″ DIAMETER
	48″×48″	1'	-4″		(8)	#4	BAR	E.W.	NZA
Æ	54″×54″	1'	-4″		(9)	#4	BAR	E.W.	3.5″ DIAMETER
F	60″×60″	1'	-6″		(10)	#4	BAR	E.W.	3.5″ DIAMETER
IS	GLATE	D	F۵	DT	ING	S	AND	COLL	IMN PADS
SYM	PIER DIAMETI	ER	DEP	ТН	MINI	MUM		NFORCEN <si ste<="" td=""><td>1ENT GRADE 40 EL</td></si>	1ENT GRADE 40 EL
G	12″		3'-() <i>"</i>			(4)	VERTIC	AL #4
Â	16″		3'-() <i>"</i>			(4)	VERTIC	AL #4
\bigtriangleup	18″	8″ 3′-() <i>"</i>	(4) VERTICAL #4				
Ŕ	24″		3'-(J <i>"</i>			(4)	VERTIC	AL #4
\triangle	28″		3'-(J <i>″</i>			(4)	VERTIC	AL #4

COLUMN AND PAD SIZES ARE FOR A MAXIMUM COLUMN HEIGHT OF 10'. COLUMNS GREATER THAN 10' REQUIRE A SEPARATE ENGINEERED DESIGN. FOOTINGS A-F SPACING OF 6" O.C. WITH 3" CLEAR COVER.





SCALE: 1/4" = 1'-0"



	NOTE:		
<text><text><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item><list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></list-item></text></text>	ALL CONSTRUCTION SHALL CONFORM TO	MAIN FLOOR PLAN NOTES 1.22 EXPOSED TOP OF FOUNDATION WALL.	CPG DBA
 Marchaeler Marken (Marken) Marken (Marken)	OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.	2.12 2X6 STUD WALL2.31 SIX SIDED TUB ASSEMBLY INCLUDING THERMOPLY ON	
 2) J. 31 WIS BRAIN UND PROVINTING PROVINTI	MINIMUM #2 DOUGLAS FIR LARCH (2) 2 X	TUB/SHOWER UNIT	SUMMIT
 Michael Petricition Michael Petricition<	BASEMENT EGRESS WINDOWS ARE TO		
 All PLANE DECK YOURS ON INTERE RATE MICHAEL SCHWART AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF THE RATE OF INTERE RATE MICHAEL AND THE REPORT OF THE REPORT OF INTERE RATE MICHAEL AND THE REPORT OF THE RATE OF INTERE RATE OF INTERE RATE MICHAEL AND THE REPORT OF THE RATE OF INTERE RATE OF INTERE RATE MICHAEL AND THE REPORT OF THE RATE OF INTERE RATE OF INTEREST INTERE RATE OF I	WINDOW FALL PROTECTION REQUIREMENTS TO COMPLY WITH	CEDAR POST. SEE PLAN FOR FINISHED SIZE.	120 SE 30TH ST.
 American Schull, Marchael Mark, Marchael Mark, Markel Mark, Markel Mark, Markel Mark, Markel Mark, Markel Ma	STAIRS SHALL COMPLY WITH IRC R311.7. THE MAXIMUM RISER HEIGHT OF	5.01 PLUMBING FOR WASHER ON INTERIOR WALL.	
 MCREW AND CONCERNENT REQUIRED. MCREW AND CONCERNENT REQUIRED. MCREW AND CONCERNENT REPORT RECENT REPORT REPORT	AND THE TREADS SHALL PROVIDE A	5.21 FIBERGLASS BASE WITH TILE WALLS: SEE DETAIL.	
 BOCKE BERKEN, DURAL STATUS OF A STATUS OF	SELF CLOSING DEVICES ARE REQUIRED	ACCESS.	THIS DRAWING HAS BEEN PREPARED BY SUMMIT HOMES, OR UNDER THEIR DIRECT SUPERVISION AS AN INSTRUMENT OF SERVICE AND IS INTENDED FOR USE
 AN ACCESSION DE CONCENTRATIONE AND ACCESSION DE CO	STEEL COLUMNS WILL BE A MINIMUM OF	BACKER BOARD AND 2 LATCHES. BUMP TRUSSES	SPECIFICATIONS, AND DESIGNS, INCLUDING THE OVERALL LAYOUT, FORM, AND COMPOSITION OF SPACES ARE PROTECTED BY COPYRIGHT REGISTERED
The provide to a variable to a variable to experiment of the provide the provide to a variable to experiment of the provide to the provide to a variable to experiment of the provide to the prov		MANUFACTURER'S RECOMMENDATIONS. FIREPLACE	DISCLOSURE OF THE INFORMATION CONTAINED HEREIN WITHOUT THE WRITTEN CONSENT FROM CPG, INC. D/B/A SUMMIT HOMES EXCEPT AS REQUIRED FOR
 ADDRESS: ADDRESS:<	R326/KCBRC.	DEEP. INSTALL INSULATION AND AIR BARRIER BEHIND	STRICTLY PROHIBITED.
2021 MINING ALL CONTRUCTS 217 11 MINITE DE ENTRUS MULTING 218 11 ANUTE DE ENTRUS MULTING 219 11 ANUTE DE ENTRUS MULTING 210 11 ANUTE DE ENTRUS MULTING 211 11 ANUTE DE ENTRUS MULTING 212 211 ANUTE DE ENTRUS MULTING 212 211 ANUTE DE ENTRUS MULTING 213 11 ANUTE DE ENTRUS MULTING 214 214 ANUTE DE ENTRUS MULTING 214 214 ANUTE DE ENTRUS MULTING 214 214 ANUTE DE ENTRUS MULTING 214 215 FULCIONE MULTING 214 215 FULCIONE MULTING 214 215 FULCIONE MULTING 214 215 FULCIONE MULTING 215 FULCIONE MULTING 214 ANUTE DE ANUTE DE ENTRUS 216 ANUTE DE ANUTE D	ENCASED ELECTRODE (FOOTING REBAR)	7.41 OPEN HANDRAILS	
PHONE IN A COUNTRY MARK PREVENCE TO INFORMATE AND A COUNTRY TANDARD AND A COUNTRY A	(UFER GROUND).	7.71 20 MINUTE FIRE RATED SOLID CORE WITH	202 NW JOSHUA DR
CENTRAL MOTES LICCALOR AND PARE ILLER AND PARE ILLER AND PARE LICCALOR AND PARE ILLER LICCALOR AND PARE ILLER AND PARE AND PARE ILLER LICCALOR AND PARE ILLER AND PARE ILLER AND PARE ILLER AND PARE AND PARE AND PARE ILLER AND PARE AND PARE ILLER AND PARE ILLER AND PARE AND PARE AND PARE AND	SECTION R315.	7.88 CHANGE IN FLOORING MATERIAL	
ALL WALES AND LINKS IN THE BOOKS AND BUILTON AND COMPTENDED RESOLUTION IN 103 29, IL CODETING AND COLUNIONS INTO BE SERVICE ALL CONTINUES AND AND TEAM TEAM ALL CONTINUES AND AND TEAM ALL WALES AND COLUMN SERVICE ALL WAL	SECTION N1102.4.1 AND TABLE	LOCATION WITH PERSONAL BUILDER.	
HIGHER HARS LOORERSPECTOR AND CELING; BHALL BE MACORDACE WITH RC 2014 DISCIDENT 23 HALL PROVINCE AN INMUNE TO DOUBL DOST UNDER LATE VALS & TAND OVER BHALL BE DOUBLAS FRI LARCH # 2XX STUDG AT 10 OCF HILL HARD TO MONITOR DOWNERS DIFERENCE AND EXCENTIONED AN INMUNE TO MAIL TO MONITOR ALL VALS & TAND OVER BHALL BE DOUBLAS FRI LARCH # 2XX STUDG AT 10 CONTINUODED INLESS OTHERWISE DIFERENCE AND EXCENTIONED DIFERENCE AND EXCENTIONED DIFERENCE DIFERENCE AND EXCENTIONED DIFERENCE AND EXCENTIONED DIFERENCE DIFERENCE AND EXCENTIONED DIFERENCE D	DUCTS, AIR HANDLERS, FILTER BOXES AND BUILDING CAVITIES USED AS DUCTS	8.44 BENCH WITH COAT HOOKS	
LEDEBRIFLOOR AND CELING SHALL BE IN ACCORDANCE WITH RC 502 A CANNER WALL HAVE AT LEAST A CANNER WALL BARE AT LEAST COLCAS FILL ARCH 22XI STUDS AT 10 COLCAS FILL ARCH 22X	N1103.2.2)		
A STARKS PRAM A MINIMUM POUDLE JOIST UNDER POUDLE JOIST UNDER P	LEDGERS(FLOOR AND CEILING) SHALL BE IN ACCORDANCE WITH IRC 507.		
ALL WALE UNDER 12 SHALL BE DOCADES FIL LARCINE DAT INFO OTHERWISE NOTION ALL WALES TO AND OVER SHALL BE DOCADES FIL AND	A 3:1 BACK SPAN. A MINIMUM OF DOUBLE JOIST UNDER		
DI-HINNER NOTED ALL WALESS OTHERWORE STUDS AT 00 CFR 14 LEGATI CONTRUCUS (INLESS OTHERWORE NOTED) GENERAL NOTES WINDOWS TO COMPLY WITH IR CR312.2 FOR FALL PROJECTIVAL SPRING PROJECTIVAL UNDER STORE RATION DETERMINE NOTED: MUNDOWS TO COMPLY WITH IR CR312.2 FOR FALL PROJECTIVAL SPRING PROJECTIVAL SPRING INTERIOR BRACED VALLS ARE AT 16" O.C. UNLESS NOTED INTERIOR BRACED VALLS ARE ALLOWED AT 24" 0.C. ROOF AND CELING FRAMING ARE REFERINGINGERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER SIZING IS EXPECTED TO VARY FR VENDOR.	ALL WALLS UNDER 12' SHALL BE DOUGLAS FIR LARCH #2 2X4 STUDS AT 16"		MAN E #5
NOTED. SERVERAL NOTES SERVERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, ANTERIOR BEARING WALLS, AND INTERIOR RARCED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCED AVIALS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCED AVIALS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RARCE ART AGE PRE-ENSINGERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBERT SIZING IS EXPECTED TO VARY PER VENDOR. DIMENSIONAL CUTUL LUMBER SIZING IS EXPECTED TO VARY	ALL WALLS 12' AND OVER SHALL BE		
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS, ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RALLS, ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RALLS, ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RALLS, ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR RALLS, ARE AT 16" O.C. UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD PER VENDOR.	STUDS AT 16" O.C. FULL HEIGHT		SRAI 000
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.	<u>NOTED).</u>		E G ≥
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY			PROFESSIONAL SEAL:
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY			BRADUEY ST
GENERAL NOTES WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION. ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			Auxor *
GENERAL NOTESSERVICES, LLC IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITEPLANS WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300 LEE'S SUMIT, MO 64063 816-399-4901ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE.RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300 LEE'S SUMIT, MO 64063 816-399-4901ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C.DRAWN BY: J. ROSENBLUMDIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.DRAWN BY: J. ROSENBLUM			
GENERAL NOTESFOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300 LEE'S SUMMIT, MO 64063 816-399-4901ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE.FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE.DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.DRAWN BY: J. ROSENBLUM			
GENERAL NOTESWINDOWS TO COMPLY WITH IRC R312.2 FOR FALL PROTECTION.WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300 LEE'S SUMMIT, MO 64063 816-399-4901ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE.WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300 LEE'S SUMMIT, MO 64063 816-399-4901ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C.DRAWN BY: J. ROSENBLUMDIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.DRAWN BY: J. ROSENBLUM		GENERAL NOTES	FOR STRUCTURAL SPECIFICATIONS
ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND INTERIOR BRACED WALLS ARE AT 16" O.C. UNLESS NOTED OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.		WINDOWS TO COMPLY WITH IRC R312.2 FOR FALL	WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERING
OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED, NON-CABINET WALLS ARE ALLOWED AT 24" O.C. ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR. DTHERWISE.		ALL EXTERIOR WALLS, INTERIOR BEARING WALLS, AND	600 SW JEFFERSON SUITE 300 LEE'S SUMMIT, MO 64063
ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD TRUSSES UNLESS NOTED OTHERWISE. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.		OTHERWISE. ALL INTERIOR NON-LOAD BEARING, NON-BRACED,	
DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.		ROOF AND CEILING FRAMING ARE PRE-ENGINEERED WOOD	
TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY PER VENDOR.			
		TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY	
HVAC DUCTWORK RUNNING THROUGH THE ATTIC SPACEISSUE DATE:SHALL BE HUNG FROM ABOVE TO ALLOW COMPLETEISSUE DATE:INSULATION SURROUND.02.09.21			_
PROVIDE BLOCKING AT ALL CEILING JUMPS FOR INSULATION.			
2X6 EXTERIOR WALL OVER 12' SHALL BE DOUGLAS FIR #2. SHEET NUMBER: SMOKE AND CARBON MONOXIDE DETECTORS SHOW ON PLANS			SHEET NUMBER:
ARE TO BE CONSIDERED RECOMMENDATIONS ONLY. FINAL		ARE TO BE CONSIDERED RECOMMENDATIONS ONLY. FINAL PLACEMENT IS TO BE DETERMINED BY MUNICIPAL	
N FLOR PLAN 1 SCALE: 1/4" = 1'-0"	$\frac{N FLOOR PLAN}{SCALE: 1/4' = 1'-0'} (1)$	INDUSTRY STANDARDS. EX: 3050 SH = 3'-0" X 5'-0" SINGLE	A4. U

- SUMMIT, MISSOURI
- 03/05/2021
 - TRUSS ROOF NOTES: (BY OTHERS) 1) DESIGNED FOR LIGHT ROOF COVERING
 - TOP CHORD: LIVE LOAD/SNOW LOAD (PSF): 25
 - DEAD LOAD (PSF): BOTTOM CHORD:
 - DEAD LOAD(PSF): 10 2) ALL EXTERIOR AND/OR LOAD BEARING WALL HEADERS
 - SHALL BE MIN. (2) #2 2 x 10 UNLESS OTHERWISE NOTED.

10

- 3) CONSULT ENGINEER IF TRUSSES BEAR ON INTERIOR WALLS SHOWN AS NON-LOAD BEARING ON APPROVED PRINTS.
- 4) MIN. STUD PACK OF (4) 2 x 4 OR (4) 2 x 6 DOUGLAS FIR
- LARCH #2 (DEPENDING ON WALL THICKNESS) BELOW EACH
 BEARING POINT OF EACH GIRDER TRUSS, UNLESS
 OTHERWISE NOTED. STUD PACKS SHALL BE CARRIED DOWN
 TO FOUNDATION OR LOAD SUPPORTING MEMBER.
 5) PROVIDE 2x SOLID BLOCKING SUPPORT BELOW ALL POINT
- LOADS CONTINUOUS TO BEARING STRUCTURE AND/OR FOUNDATION BELOW.
 6) ROOF IS ENGINEERED TO COMPLY WITH IRC 802
- ------ = ROOF TRUSS FRAMING DIRECTION
- "G.T." = GIRDER TRUSS LOCATION= INTERIOR LOAD BEARING WALL


NOTE:

ALL CONSTRUCTION SHALL CONFORM TO 2018 INTERNATIONAL RESIDENTIAL CODE OR ATTACHED ENGINEER SPECIFICATIONS WHERE APPLICABLE.

ROOF:

ROOF IS DESIGNED FOR 20 PSF SNOW LOAD.

WOOD TRUSSES SHALL BE IN ACCORDANCE WITH IRC SECTION R802.10. CEILING JOIST OR RAFTER TIE CONNECTIONS BETWEEN RAFTERS, RIDGE BEAM, REQUIRED COLLAR TIES OR RIDGE STRAPS SHALL COMPLY WITH DETAILS AND IRC SECTION R802, R802.3, R802.3.1, R802.11.



ROOF PLAN NOTES CPG DBA 4.00 COVERING WILL HAVE 1 ROOF VENT AND 4 SOFFIT VENTS 4.11 MINIMUM ROOFING COMPOSITION- 30 YR COMPOSITE SHINGLES ON 15# FELT ON 1/2" OSB SHEATHING OR AS REQUIRED BY CODE. **SUMMIT** 4.31 BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR POSITIVE DRAINAGE. HOMES 120 SE 30TH ST. LEE'S SUMMIT, MO 64082 816-246-6700 COPYRIGHT 2017 THIS DRAWING HAS BEEN PREPARED BY SUMMIT HOMES, OR UNDER THEIR DIRECT SUPERVISION AS AN INSTRUMENT OF SERVICE AND IS INTENDED FOR USE ONLY ON THIS PROJECT. ALL DRAWINGS, SPECIFICATIONS, AND DESIGNS, INCLUDING THE OVERALL LAYOUT, FORM, AND COMPOSITION OF SPACES ARE PROTECTED BY COPYRIGHT REGISTERED TO CPG, INC. ANY REPRODUCTION, USE, OR DISCLOSURE OF THE INFORMATION CONTAINED HEREIN WITHOUT THE WRITTEN CONSENT FROM CPG. INC D/B/A SUMMIT HOMES EXCEPT AS REQUIRED FOR BIDDING AND CONSTRUCTION OF THIS PROJECT IS STRICTLY PROHIBITED. ADDRESS: 202 NW JOSHUA DR LEE'S SUMMIT, MO BRADFORD CRAFTSMAN WOODSIDE #52 PROFESSIONAL SEAL: RESIDENTIAL ENGINEERING SERVICES,LLC IS RESPONSIBLE FOR STRUCTURAL SPECIFICATIONS ONLY. ARCHITECTURAL PLANS WERE PRODUCED BY OTHERS. RESIDENTIAL ENGINEERING SERVICES, LLC 600 SW JEFFERSON SUITE 300 LEE'S SUMMIT, MO 64063 816-399-4901 GENERAL NOTES ROOF AND CEILING FRAMING ARE PRE-ENGINEERED ROOF TRUSSES. ASPHALT SHINGLES MIN 2/12. FLASH ALL PENETRATIONS AND DRAWN BY: INTERSECTIONS. J. ROSENBLUM VENT EACH ENCLOSED ATTIC SPACE. NET AREA OPENING = 1/50TH OF VENTED AREA OR 1/300TH IF 580% OF VENTING NEAR TOP. ISSUE DATE: BUILD CRICKET VALLEY AWAY FROM INTERSECTION FOR 02.09.21 POSITIVE DRAINAGE. SEE FRAMING SPECIFICATIONS FOR DETAILS. DIMENSIONAL LUMBER IS LABELED PER INDUSTRY STANDARD TERMINOLOGY. ACTUAL LUMBER SIZING IS EXPECTED TO VARY SHEET NUMBER: PER VENDOR. HVAC DUCTWORK RUNNING THROUGH ATTIC SHALL BE HUNG FROM ABOVE TO ALLOW COMPLETE INSULATION SURROUND. PROVIDE BLOCKING AT ALL CEILING JUMPS FOR INSULATION. <u>ROOF PLAN</u> PROVIDE FOAM INSULATION AT EXTERIOR WHERE MAIN LEVEL ROOF LINE MEETS UPPER LEVEL WALLS. SCALE: 1/4" = 1'-0"

GENERAL NOTES

RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEV

> PLANS SHALL COMPLY WITH THE 2018 INTERNATIONAL RESIDENTIAL CODE (IRC) WITH AMENDMENTS AS ADOPTED BY THE APPROPRIATE GOVERNING JURISDICTION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IF ANY CHANGES OR DEVIATIONS FROM THE PLAN ARE MADE DURING CONSTRUCTION. THE ENGINEER OF RECORD MAY REQUIRE REVISED DRAWING OR CALCULATIONS AT ITS DISCRETION.

IF DISCREPANCIES ARE IDENTIFIED THE MOST CONSERVATIVE SPECIFICATION SHALL APPLY.

LOADING

DEAD		
LIGHT ROOF	10 PSF	
HEAVY ROOF	+10 PSF	(CONCRETE, SLATE, TILE)
ROOF + CEILING (NO STORAGE)	15 PSF	
ROOF + CEILING (STORAGE)	20 PSF	
CEILING JOISTS (STORAGE)	10 PSF	
EXTERIOR BACONIES / DECK	10 PSF	
INTERIOR FLOOR (MAIN FLOOR)	15 PSF	
INTERIOR FLOOR (UPPER FLOORS)	10 PSF	
8" THICK MASONRY WALL	80 PSF	
6" THICK MASONRY WALL	85 PSF	
EXTERIOR LIGHT FRAMED WOOD WALLS	15 PSF	
INTERIOR LIGHT FRAMED WOOD WALLS	10 PSF*	
*(INTERIOR WALLS IN	ICLUDED IN	15 PSF DEAD LOAD)
LIVE		

ROOF LIVE LOAD	15 PSF	
FLOOR LIVE LOAD	40 PSF	(HABITABLE)
GARAGE	50 PSF	
STORAGE	20 PSF	(UN-INHABITABLE)
GUARDRAIL		
CONTINUOUS LINEAR	50 PLD	
MAXIMUM POINTLOAD	200 LBS	
SNOW		
GROUND SNOW LOAD	20 PSF	
MIND		
WIND		

ULTIMATE DESIGN WIND SPEED VELOCITY 115 MPH EXPOSURE CATEGORY

SOIL AND SITE ASSUMPTIONS:

- FOUNDATION DESIGN ASSUME A MINIMUM SOIL BEARING PRESSURE FOR THE SITE OF 2,000 PSF CONTRACTOR TO VISUALLY INSPECT SITE OR PROVIDE GEOTECHNICAL INVESTIGATION TO VERIFY MINIMUM ACCEPTABLE SOIL CONDITIONS SW, SP, SM, SC, GM, AND GX AS DEFINED PER IRC TABLE R301.5. THE CONTRACTOR IS RESPONSIBLE FOR ANY SOIL CONDITION THAT DOES NOT MEET THE MINIMUM REQUIREMENTS AND CONTACTING THE ENGINEER OF RECORD.
- PROVIDE A MINIMUM SOIL COVER OF <u>36 INCHES MEASURED FROM THE BOTTOM OF CONCRETE ON</u> ALL FOUNDATIONS.
- ACCESSORY STRUCTURES WITH AN EAVE HEIGHT LESS THAN 10'-0" AND AN AREA LESS THAN 600 FT² MAT PROVIDE A MINIMUM SOIL COVER OF 12 INCHES MEASURED FROM THE BOTTOM OF CONCRETE.
- 4. SITE GRADING SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM THE STRUCTURE AT A MINIMUM OF 0.5%.
- 5. LATERAL SOIL PRESSURES
- ACTIVE 30 PSF AT-REST 60 PSF

PASSIVE 150 PSF

FOUNDATION NOTES:

FOUNDATION ANCHORAGE (IRC 403.1.6)

SILL PLATES SHALL BE BOLTED TO THE FOUNDATION WALL WITH A MINIMUM 1/2" DIAMETER ANCHOR BOLTS EMBEDDER AT LEAST 7" INTO THE CONCRETE. BOLTS SHALL BE SPACED NO GREATER THAN 6' 0.C. THERE SHALL BE A MINIMUM OF TWO BOLTS PER PLATE SECTION, WITH A BOLT PLACED WITHIN 12" AND NOT CLOSER THAN 7 BOLT DIAMETERS, OF THE END OF EACH PLATE SECTION. A PROPERLY SIZED NUT AND WASHER SHALL BE TIGHTENED ON EACH BOLT TO THE PLATE, (NOTE: 7" EMBEDMENT + 1-1/2" SILL PLATE + 3/4" FOR NUT AND WASHER EXCEEDS A 9" LONG BOLT.)

WALL BRACING METHODS PER IRC R602 MAY REQUIRE ADDITIONAL ANCHORAGE.

CONCRETE SLABS PLACED ON FILL MATERIAL WHICH EXCEEDS 24" OF COMPACTED GRANULATED MATERIAL (SAND OR GRAVEL) OR 8" OF EARTH: THIS MAY OCCUR AT GARAGE FLOOR FILLS, OR OVER EXCAVATED AREAS UNDER FLOOR SLABS. THE DESIGN AND INSTALLATION DETAILS IN THIS DOCUMENT (WHERE APPLICABLE BASED ON SIZE AND SPACING LIMITATIONS) MAY BE USED IN LIEU OF PROVIDING A SEPARATE DESIGN. STRUCTURAL SLABS EXCEEDING THE SPANS AND CONDITIONS OF THE APPROVED DETAILS SHALL BE DESIGNED BY A

SLABS AT MAX 4' OVER-DIG ADJACENT TO FOUNDATION WALL: WHERE SOIL IS EXCAVATED FOR A MAXIMUM DIMENSION OF 4' HORIZONTALLY ADJACENT TO A FOUNDATION WALL, THE STANDARD OVER-DIG DETAIL MAY BE USED IN LIEU OF A COMPLETE STRUCTURAL SLAB. SEE "TYPICAL FOOTING/FOUNDATION WALL/STANDARD SLAB AT MAX 4' OVER-DIG DIAGRAM FOR DETAILS.

VAPOR RETARDER / BARRIER (IRC R506.2.3)

PROFESSIONAL ENGINEER.

A 6 MIL POLYETHYLENE OR APPROVED VAPOR RETARDER WITH JOINTS LAPPED A MINIMUM OF 6" IS REQUIRED BETWEEN THE CONCRETE FLOOR SLAB AND THE BASE COURSE OR PREPARED SUBGRADE, (NOT REQUIRED FOR GARAGE SLABS OR DETACHED ACCESSORY BUILDINGS)

FOUNDATION AND LOT GRADING (IRC R401.3)

GRADES SHALL BE SLOPED AWAY FROM THE FOUNDATION A MINIMUM OF 6" IN THE FIRST 10'. ALTERNATE APPROACHES MAY BE APPROVED IF THE ALTERNATE DESIGN IS EQUIVALENT IN EFFECTIVENESS AND PERFORMANCE, AND PROVIDES FOR POSITIVE SITE DRAINAGE.

IRC R403.1.4

- THE BOTTOM OF ALL FOOTINGS SHALL EXTEND NOT LESS THAN 36" BELOW GRADE FOR FROST
- PROTECTION. FOOTINGS FOR FREESTANDING ACCESSORY STRUCTURES WITH AN AREA OF 600 SF OR LESS AND AN EAVE HEIGHT OF 10' OR LESS SHALL EXTEND BELOW GRADE A MINIMUM OF 12".

FOOTINGS:

MASONRY OR CONCRETE FOOTINGS, OR APPROVED STRUCTURAL SYSTEM TO SAFELY SUPPORT THE IMPOSED LOADS AND SHALL BE SIZED AND REINFORCED IN ACCORDANCE WITH THIS STANDARD OR THE STRUCTURE AND FROM ONE LEVEL TO THE NEXT. THE CONTINUOUS TRANSITIONS BETWEEN FOOTINGS AT DIFFERENT LEVELS ENCLOSING USABLE SPACE SHALL BE MADE BY APPROVED SOLID JUMPS OR SUPPORT SYSTEMS TO PROVIDE SAFE SUPPORT OF THE STRUCTURE. SEE "TYPICAL FOOTING/FOUNDATION WALLS/STANDARD SLAB AT MAXIMUM 4" OVER-DIG AND "FOOTING JUMP" DIAGRAMS FOR MORE DETAIL (PER KC, MO STANDARDS)

<u>CONCRETE</u>

- 1. ALL CONCRETE CONSTRUCTION SHOULD CONFORM TO ACI 318-11 AND THE 2018 INTERNATIONAL RESIDENTIAL CODE.
- 2. THE MINIMUM CONCRETE 28 DAY COMPRESSIVE STRENGTH SHALL BE AS SPECIFIED IN IRC TABLE R402.2.
- 3. CONCRETE MIX TO UTILIZE A MAXIMUM WATER-CEMENT MATERIALS RATIO OF 0.45 FOR ALL APPLICATIONS. ALL CONCRETE TO HAVE MAXIMUM 0.10 PERCENT WATER SOLUBLE CHLORIDE CONTENT BY WEIGHT OF CEMENT. ADMIXTURES SHALL NOT CONTAIN ANY CHLORIDES.
- 4. CONCRETE POURED AGAINST AN EXISTING SURGACE SHOULD BE ROUGHENED TO A MINIMUM 1/4 INCH AMPLITUDE.
- 5. REBAR CLEAR DISTANCE SHALL BE AS FOLLOWS: -CAST AGAINST AND PERMANENT CONTACT WITH GROUND3 IN -EXPOSED TO WEATHER OR IN CONTACT WITH GROUND - NOT EXPOSED TO WEATHER OR GROUND
- 6. CONCRETE MIX DESIGN SHALL BE 6% (±1%) AIR-ENTRAINED FOR GARAGE SLABS, FOOTINGS, WALLS, OR FLATWORK EXPOSED TO WEATHER.
- 7. SHORING AND RESHORING: BEFORE CONCRETE STRENGTH REACHES 70% OF STRENGTH DETERMINED BY CYLINDERS OR 28

DAYS -SHORING MAY NOT BE REMOVED SOONER THAN RECOMMENDED BY ASTM 374-04 SECTION 3.7.2.3.

MINIMUM STANDARDS:

OTHERWISE. REINFORCING BAR SHALL BE GRADE 60 MINIMUM.

CONCRETE REINFORCEMENT STEEL

- 1. REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60.
- 2. SMOOTH BARS OR WELDED WIRE FABRIC SHALL CONFORM TO ASTM 185.
- 3. ALL REBAR LAP SPLICES SHALL BE CLASS B LAP SPLICES AS SHOWN ON THE LAP SPLICE SCHEDULE.
- 4. DEVELOPMENT LENGTH NOTED IS EQUAL TO 80% OF THE LENGTH NOTED IN THE LAP SPLICE SCHEDULE.
- 5. 90% HOOK SHOWN IN DRAWINGS SHALL BE STANDARD PER ACI 318-14 -STRAIGHT EXTENSION LENGTH = $12xØ_{BAR}$ -BEND DIAMETER = $12XØ_{BAR}$
- 6. LAP SPLICE SCHEDULE (SEE TABLE 1.1)
- 7. HOOKED DOWELS:
- REINFORCING AND EXTENDED TO 3" CLEAR FROM BOTTOM OF FOUNDATION
- 8. PROVIDE 2 #5 BARS AROUND PERIMETER OF ALL SUSPENDED SLABS
- 9. HORIZONTAL WALL REINFORCING SHALL TERMINATE AT THE END OF THE WALL WITH A STANDARD HOOK
- 10. TOP AND BOTTOM HORIZONTAL REINFORCING SHALL BE PLACED 1-1/2" TO 2" FROM THE TOP AND BOTTOM OF THE WALL

FOOTNOTES:

- 1. WALL HEIGHT IS MEASURED FROM THE TOP OF THE WALL TO THE TOP OF THE FLOOR SLAB.
- 2. VERTICAL REINFORCEMENT FOR CONCRETE WALLS THAT ARE NOT FULL HEIGHT AND FOR SHALL HAVE VERTICAL REINFORCEMENT PLACE AS FOLLOWS:
- A. 8" WALL MINIMUM 5" FROM THE OUTSIDE FACE. B. 10" WALL - MINIMUM 6-3/4" FROM THE OUTSIDE FACE. C. EXTEND BARS TO WITHIN 8" OF THE TOP OF THE WALL.
- 3. HORIZONTAL REINFORCEMENT:
- A. ONE BAR SHALL BE PLACED WITHIN 12" OF THE TOP OF THE WALL.
- BEHIND THE VERTICAL REINFORCEMENT (I.E. 2" TOWARD THE INSIDE). D. SUPPLEMENTAL REINFORCEMENT AT CORNERS - PLACE 1 #4 REBAR 48" LONG AT 45 DEGREE
- CORNERS
- 5. AT MASONRY LEDGES THE MINIMUM WALL THICKNESS SHALL BE 3-1/2". LEDGES SHALL NOT EXCEED
- 6. STRAIGHT WALLS MORE THAN 5' TALL AND MORE THAN 16' LONG SHALL BE PROVIDED WITH EXTERIOR BRACED RETURN WALLS. WALL LENGTH SHALL BE MEASURED USING INSIDE THE SHORTEST DIMENSION BETWEEN INTERSECTING WALLS (SEE TYPICAL DEAD MAN SECTION).

NORMAL WEIGHT CONCRETE LAP SPLICE SCHEDULE, IN							
TOP I	BARS	OTHEF	RBARS				
CASE 1	CASE 2	CASE 1	CASE 2				
28	42	22	32				
37	56	29	43				
47	70	36	54				
56	84	43	64				
	LAP TOP I CASE 1 28 37 47	LAP SPLICE SCI TOP BARS CASE 1 CASE 2 28 42 37 56 47 70	LAP SPLICE SCHEDULE, INTOP BARSOTHERCASE 1CASE 2CASE 1284222375629477036				

TABLE 1.1

EXTERIOR WALLS, BEARING WALLS, COLUMN AND PIERS SHALL BE SUPPORTED ON CONTINUOUS SOLID SHALL BE ENGINEERED DESIGN. FOOTINGS UNDER FOUNDATION WALLS SHALL BE CONTINUOUS AROUND

2 IN 1.5 IN

-SHORING AND SUPPORTING FORMWORK SHALL NOT BE REMOVED FROM HORIZONTAL MEMBERS

CONCRETE SHALL BE 6% (± 1%) AIR-ENTRAINED FOR GARAGE SLABS AND FOR ALL LOCATION'S FOOTINGS, WALLS OR FLATWORK WHERE EXPOSED TO WEATHER. REBAR SHALL BE MINIMUM 60 KSI UNLESS NOTED

7.1. HOOKED DOWELS FROM FOUNDATIONS TO WALL SHALL BE PROVIDED TO MATCH VERTICAL WALL 7.2. HOOKED DOWELS MATCH SLAB REINFORCING FROM SLAB TO WALLS OR SLAB TO FOUNDATION

REINFORCEMENT SPACED 24" O.C. MAY BE PLACED IN THE MIDDLE OF THE WALL. OTHER WALLS

B. OTHER BARS SHALL BE EQUALLY SPACED WITH SPACING NOT TO EXCEED 24" O.C. C. HORIZONTAL BARS SHOULD BE AS CLOSE TO THE TENSION FACE AS POSSIBLE (INTERIOR); AND

ANGLE AT CORNERS OF OPENINGS. PLACE REINFORCEMENT WITHIN 6" OF THE EDGE OF INSIDE

4. REINFORCEMENT SHALL BE LAPPED A MINIMUM 24" AT ENDS, SPLICES, AND AROUND CORNERS.

A DEPTH OF MORE THAN 24" BELOW THE TOP OF THE WALL FOR WALL THICKNESS LESS THAN 4" PROVIDE #4 BARS AT MAXIMUM 24" O.C. TO WITHIN 8" OF THE TOP OF THE WALL.

STEEL DECK - SUSPENDED SLABS

1. STEEL DECK QUALITY, FABRICATION, DELIVERY, INSTALLATION AND ATTACHMENT SHALL COMPLY WITH THE PROVISIONS OF THE STEEL DECK INSTITUTE, SDI.

STEEL ROOF DECK SHALL BE AS FOLLOWS UNLESS NOTED OTHERWISE ON CONSTRUCTION DRAWINGS:

- WIDE RIB CONFIGURATION
- 1.5" DEPTH 24GA DESIGN THICKNESS
- MAXIMUM SINGLE SPAN OF 4'-8" OR CONTINUOUS SPAN OF 5'-10"
- GALVANIZE PER ASTM A653 OR SHOP PRIME PER ASTM A1008
- ATTACH STEEL ROOF DECK TO SUPPORTS WITH #12 TEK AT 18" O.C. ATTACH STEEL ROOF DECK SIDELAPS WITH #10 TEK OR CRIMP/BUTTON PUNCH AT 36" O.C. OR MID-SPAN, WHICHEVER IS SMALLER
- 3. CONTRACTOR AND/OR DECK MANUFACTURER SHALL FURNISH ALL NECESSARY DECK CLOSURE ACCESSORIES TO PROVIDE A FINISHED SURFACE FOR THE APPLICATION OF ROOF INSULATION AND ROOF COVERING.
- 4. STEEL FLOOR DECK SHALL BE AS FOLLOWS UNLESS NOTED OTHERWISE ON CONSTRUCTION DRAWINGS:

STEEL DECK - SUSPENDED SLABS STEEL DECK QUALITY, FABRICATION, DELIVERY, INSTALLATION AND ATTACHMENT SHALL COMPLY WITH THE PROVISIONS OF THE STEEL DECK INSTITUTE, SDI.

CONTRACTOR AND/OR DECK MANUFACTURER SHALL FURNISH ALL NECESSARY DECK CLOSURE ACCESSORIES TO PROVIDE A FINISHED SURFACE FOR THE APPLICATION OF ROOF INSULATION AND ROOF COVERING

- STEEL FLOOR DECK SHALL BE AS FOLLOWS UNLESS NOTED OTHERWISE ON CONSTRUCTION DRAWINGS: 2" COMPOSITE DECK WITH 6" TOTAL SLAB THICKNESS 19GA DESIGN THICKNESS
 - MAXIMUM SINGLE SPAN DURING CONSTRUCTION OF 8', 2 SPAN OF 10'-1", OR 3 SPAN OF 10'-5".
 - MAXIMUM SPAN SHALL NOT EXCEED 12.5'. PROVIDE W2.1xW2.1 WELDED WIRE MESH OR #4 @ 12" O.C. EACH WAY. PROVIDE 2" REBAR
 - COVER MEASURED FROM TOP OF THE SLAB GALVANIZE PER ASTM A653
 - MINIMUM BEARING LENGTH AT EDGE SUPPORTS IS 2"
 - MINIMUM BEARING LENGTH AT INTERIOR SUPPORTS IS 4" ATTACH STEEL COMPOSITE FLOOR DECK TO SUPPORTS WITH 5/8" ARC PUDDLE WELDS AT 12" O.C. MECHANICAL FASTENERS EITHER POWDER ACTUATED, PNEUMATICALLY DRIVEN, OR SCREWS MAY BE USED IN LIEU OF WELDING PROVIDED THEY ARE APPROVED.
 - ATTACH STEEL ROOF DECK SIDELAPS WITH #10 TEK OR CRIMP/BUTTON PUNCH AT 36" O.C. OR MID-SPAN, WHICHEVER IS SMALLER.
- CONTRACTOR AND/OR DECK MANUFACTURER SHALL FURNISH ALL NECESSARY POUR STOPS, COLUMN CLOSURES, END PLATES, AND COVER PLATES AS NEEDED.

STRUCTURAL STEEL

1. STEEL DESIGN, FABRICATION, AND ERECTION SHALL CONFORM WITH AMERICAN INSTITUTE OF STEEL CONSTRUCTION.

STEEL GRADE AND SPECIFICATION SHALL BE AS FOLLOWS:	
HOLLOW STRUCTURAL SECTIONS:	ASTM A500 (Fy = 46 KS
CHANNELS, PLATES AND ANGLES:	ASTM A36 (Fy = 36 KS
WIDE FLANGES:	ASTM A992 (Fy = 50 K
COLUMNS:	ASTM A53 GR. B (Fy= 3
ANCHOR RODS:	ASTM F1554 (Fy = 36 KS

- 3. BOLTS SHALL CONFORM TO ASTM A307
- WELDING SHALL CONFORM TO THE AWS CODES FOR BUILDING CONSTRUCTION. WELDING SHALL BE PERFORMED IN ACCORDANCE TO WELDING PROCEDURE SPECIFICATION (WPS) AS REQUIRED IN AWS D1.1 THE WPS VARIABLES SHALL BE WITHIN THE PARAMETERS ESTABLISHED BY THE FILLER-METAL MANUFACTURER.
- WELDS SHALL USE E70XX ELECTRODES AND A MINIMUM OR 3/16" SIZE UNLESS NOTED OTHERWISE.
- 6. ALL WELDS SPECIFIED AS FIELD WELDS MAY BE SHOP WELDED AT THE CONTRACTOR'S OPTION IF ERECTION CAN STILL BE EXECUTED.

ENERGY REQUIREMENTS:

- AS REQUIRED PER M1503.6.

GARAGES:

- ABOVE.

- PER R302.5.1.

STAIRWAYS:

GLAZING

FRAMING NOTES:

- WALLS.

KSI) KSI) 35 KSI) KSI)

1. LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE SHALL BE IC-RATED, LEAKAGE RATED, AND SEALED TO THE GYPSUM WALLBOARD AS REQUIRED PER IRC N1102.4.4.

2. PROGRAMMABLE THERMOSTATS SHALL BE INSTALLED AS REQUIRED PER N1103.1.1.

3. AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2% AIR LEAKAGE RATE PER N1103.3.2.1.

4. BUILDING FRAMING CAVITIES SHALL NOT BE USED AS DUCTS OR PLENUMS.

5. HOT WATER PIPES SHALL BE INSULATED AS REQUIRED PER N1103.4.

6. ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR AS REQUIRED PER IRC M1504.3. 7. MAKEUP AIR SYSTEMS SHALL BE INSTALLED FOR KITCHEN EXHAUST HOODS THAT EXCEED 400 CFM

8. AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING SPACE AND THE GARAGE PER M1601.6 ENERGY CONSERVATION.

1. THE GARAGE FLOOR SHALL SLOPE TOWARDS THE GARAGE DOORWAYS.

2. DOORS BETWEEN THE GARAGE AND THE DWELLING - MINIMUM 1-3/8" SOLID CORE OR HONEY COMBED STEEL DOOR OR 20 MINUTE FIRE RATED.

3. THE GARAGE SHALL BE SEPARATED FROM THE DWELLING AND IT'S ATTIC AREAS BY A MINIMUM 5/8" GYPSUM BOARD APPLIED TO THE GARAGE SIDE WHERE A FLOOR/CEILING SPACE IS PROVIDED

4. THE GARAGE COLUMNS AND BEAMS SUPPORTING THE SEPARATION SHALL ALSO BE PROTECTED WITH 5/8" GYPSUM BOARD OR EQUIVALENT. WHERE HABITABLE SPACE OCCURS ABOVE THE GARAGE THE FLOOR CEILING ASSEMBLY SHALL BE PROTECTED WITH A MINIMUM PS TYPE "X" GYPSUM BOARD ON THE GARAGE CEILING.

5. GARAGE DOOR AND FRAME - THE "H" FRAME FOR THE ATTACHMENT OF THE TRACK AND COUNTER BALANCE SHALL CONSIST OF THE FOLLOWING 2x6 VERTICAL JAMBS RUNNING FROM THE FLOOR TO CEILING, ATTACHED WITH 1-3/4"x0.120" NAILS AT 7" O.C. STAGGERED WITH (7) 3-1/4"x0.120" NAILS THROUGH THE JAMB INTO THE HEADER. A MINIMUM OF 2x8 HEADER FOR ATTACHMENT OF COUNTER BALANCE SYSTEM.

6. SELF CLOSING DEVICES SHALL BE INSTALLED FOR GARAGE AND/OR DWELLING SEPARATION DOORS

7. GARAGE VEHICLE DOORS AND FRAMES SHALL BE DESIGNED AND INSTALLED TO MEET THE 90 MPH WIND LOAD REQUIREMENTS OF DASMA 108 AND ASTM E330-96 (IRC 301.2.1).

1. STAIRWAYS SHALL PROVIDE A MAXIMUM 7-3/4" RISE AND A MINIMUM 10" RUN.

2. PROVIDE GUARD RAILS BETWEEN 36" GUARD RAILS ON THE OPEN SIDES OF RAISED FLOORS, PORCHES AND BALCONIES; MINIMUM 34" GUARD RAILS ON THE OPEN SIDES OF STAIRWAYS LOCATED MORE THAN 30" ABOVE THE FLOOR OR GRADE BELOW.

3. GUARD RAIL ENCLOSURES SHALL HAVE INTERMEDIATE RAILS OF ORNAMENTAL PATTERNS THAT DO NOT ALLOW PASSAGE OF A SPHERE 4" IN DIAMETER.

4. EACH STAIRWAY OF THREE OR MORE RISERS SHALL PROVIDE A CONTINUOUS HANDRAIL ON AT LEAST ONE SIDE BETWEEN 34" AND 38" ABOVE THE NOSING OF THE TREADS.

5. HANDRAILS SHALL HAVE A CIRCULAR CROSS SECTION OF 1-1/4" TO 2-5/8" OR OTHER APPROVED GRASPABLE SHAPE PER IRC R311.5.6.

6. MINIMUM 6'-8" OF HEADROOM CLEARANCE IS REQUIRED IN STAIRWAYS.

7. ENCLOSED ACCESSIBLE SPACE UNDER STAIRWAYS SHALL HAVE WALLS AND THE UNDERSIDE OF THE STAIR AND LANDING PROTECTED WITH 1/2" GYPSUM BOARD ON ENCLOSURE SIDE PER IRC R311.2.2.

1. GLAZING IN HAZARDOUS LOCATIONS AS IDENTIFIED IN IRC R308.4 SHALL BE OF APPROVED SAFETY GLAZING MATERIALS; GLASS IN STORM DOORS; INDIVIDUAL FIXED OR OPENABLE PANELS ADJACENT TO A DOOR WHERE THE NEAREST VERTICAL EDGE IS WITHIN A 24" ARCH OF THE DOOR IN A CLOSED POSITION AND WHOSE BOTTOM EDGE IS WITHIN 60" OF THE FLOOR: WALLS ENCLOSING STAIRWAYS AND LANDINGS WHERE THE GLAZING IS WITHIN 60" OF THE TOP OR BOTTOM OF THE STAIR; ENCLOSURES FOR SPAS, TUBS, SHOWERS, AND WHIRLPOOLS; GLAZING IN FIXED OR OPENABLE PANELS EXCEEDING 8 SF AND WHOSE BOTTOM EDGE IS LESS THAN 18" ABOVE THE FLOOR OR WALKING SURFACE WITHIN 36".

2. WINDOW FALL PROTECTION SHALL BE PROVIDED IN ACCORDANCE WITH R312.2.

EMERGENCY EGRESS AND RESCUE

1. PROVIDE ONE WINDOW FROM EACH BEDROOM THAT HAS A MINIMUM OPENABLE AREA OF 5.7 SF WITH A MINIMUM OPENABLE HEIGHT OF 24" AND WIDTH OF 21"

2. BASEMENT EGRESS TO MEET THE REQUIREMENTS OF IRC R310.

3. PROVIDE SMOKE ALARMS IN EACH SLEEPING ROOM, OUTSIDE OF EACH SLEEPING AREA AND ON EACH FLOOR INCLUDING BASEMENTS. ALARMS SHALL BE INTERCONNECTED IN SUCH A MANNER THAT THE ACTUATION OF ONE ALARM WILL ACTIVATE ALL OF THE ALARMS IN THE DWELLING.

4. CARBON MONOXIDE DETECTORS SHALL BE INSTALLED AS REQUIRED PER R315.

1. ALL LUMBER SIZES ARE DOUGLAS FIR-LARCH #2 UNLESS OTHERWISE NOTED.

2. ALL UNMARKED HEADERS SHALL BE A MINIMUM #2 DOUGLAS FIR LARCH (2) 2x10 ON LOAD BEARING

3. ALL HEADER/BEAMS TO BEAR ON A MINIMUM OF (2) 2x4 POSTS UNLESS NOTED OTHERWISE.

4. DOUBLE JOIST UNDER INTERIOR NON-LOAD BEARING WALLS.

5. CANTILEVERS, OVER BEAMS, AND DOOR JAMBS SHALL BE BLOCKED

6. ANY WOOD MEMBERS IN CONTACT WITH CONCRETE OR MASONRY (OR THE FURRING THEY ARE ATTACHED TO) SHALL BE OF DECAY RESISTANT MATERIAL.

7. INTERIOR NON LOAD BEARING WALLS SHALL BE ISOLATED FROM THE FLOOR FRAMING ABOVE UNLESS THE INTERIOR NON LOAD BEARING WALL RESTS DIRECTLY ON A FOOTING.

8. LVL STRENGTH SHALL BE VERSA-LAM 3100 Fb UNLESS NOTED OTHERWISE.



7 \frown

7

SHEET #

GN1.0

MT, MISSOURI 5/2021			
	2018 IR	C TABLE R602.3(1) (SEE IRC FOR FOOT	NOTES)
ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION
		ROOF	1
1	BLOCKING BETWEEN CEILING JOISTS OR RAFTERS TO TOP PLATE	4-8D BOX (2-1/2"x0.113") OR 3-8D COMMON (2-1/2" x 0.131"); OR 3-10D BOX (3" x 0.128"); OR 3-3" x 0.131" NAILS	TOE NAIL
2	CEILING JOSTS TO TOP PLATE	4-8D BOX (2-1/2"x0.113") OR 3-8D COMMON (2-1/2" x 0.131"); OR 3-10D BOX (3" x 0.128"); OR 3-3" x 0.131" NAILS	PER JOIST, TOE NAIL
3	CEILING JOISTS NOT ATTACHED TO PARALLEL RAFTER LAPS OVER PARTITIONS	4-10D BOX (3" X 0.128"); OR 3-16D COMMON (3-1/2" X 0.162"); OR 4-3" X 0.131" NAILS	FACE NAIL
4	CEILING JOIST ATTACHED TO PARALLEL RAFTER (HEEL JOINT)	TABLE R802.5.2	FACE NAIL
5	COLLAR TIE TO RAFTER, FACE NAIL OR 1-1/4"x20 GAGE RIDGE STRAP TO RAFTER	4-10D BOX (3" X 0.128"); OR 3-10D COMMON (3" X 0.148"); OR 4-3" X 0.131" NAILS	FACE NAIL EACH RAFTER
6	RAFTER OR ROOF TRUSS TO PLATE	3-16d BOX NAILS (3-1/2"x0.135") OR 3-10d COMMON NAILS (3"x0.148"); OR 4-10D BOX (3" X .128"); OR 4-3" X 0.131" NAILS	2 TOE NAILS ON ONE SIDE AND 1 TOE NAI ON OPPOSITE SIDE OF EACH RAFTER OR TRUSS
7	ROOF RAFTERS TO RIDGE, VALLEY OR HIP RAFTERS OR ROOF RAFTER	4-16D (3-1/2"x0.135") ; OR 3-10D COMMON (3" X 0.148"); OR 4-10D BOX (3" X 0.128"); OR 4-3" X0.131" NAILS	TOE NAIL
	TO MINIMUM 2" RIDGE BEAM	3-16d BOX NAILS (3-1/2"x0.135") OR 2-16D COMMON NAILS (3-1/2"x0.162"); OR 3-10D BOX (3" X .128"); OR 3-3" X 0.131" NAILS	END NAIL
		WALL	
	STUD TO STUD (NOT AT BRACED	16D COMMON (3-1/2" X 0.162")	24" O.C. FACE NAIL
8	WALL PANELS)	10d BOX (3"x0.128"); OR 3" X 0.131" NAILS	16" O.C. FACE NAIL
9	STUD TO STUD AND ABUTTING STUDS AT INTERSECTING WALL CORNERS (AT BRACED WALL	16D BOX (3-1/2"x0.135"); OR 3" X 0.131" NAILS	12" O.C. FACE NAIL
	PANELS)	16D COMMON (3-1/2" X 0.162")	16" O.C. FACE NAIL
10	BUILT-UP HEADER (2" TO 2"	16D COMMON (3-1/2"x0.162")	16" O.C. ALONG EACH EDGE FACE NAIL
10	HEADER WITH $\frac{1}{2}$ " SPACER)	16D BOX (3-1/2" X 0.135)	12" ALONG EACH EDGE EACE NAIL

RELEASE FOR

	2018 IR	C TABLE R602.3(1) (SEE IRC FOR FOOTN	IOTES)	2018 IRC TABLE R602.3(1) (SEE IRC FOR FOOTNOTES)				
ITEM	DESCRIPTION OF BUILDING	NUMBER AND TYPE OF FASTENER	SPACING AND LOCATION			FLOOR		
	ELEMENTS BLOCKING BETWEEN CEILING	ROOF 4-8D BOX (2-1/2"x0.113") OR 3-8D COMMON (2-1/2" x 0.131"); OR		21	JOST TO SILL, TOP PLATE OR GIRDER	4-8D BOX (2-1/2" X 0.113"); OR 3-8D COMMON (2-1/2" X 0.131"); OR 3-10D BOX (3" X 0.128"); OR 3-3" X 0.131" NAILS	TOE	NAIL
1	JOISTS OR RAFTERS TO TOP PLATE	3-10D BOX (3" x 0.128"); OR	TOE NAIL		RIM JOIST, BAND JOIST OR	8d BOX (2-1/2"x0.113")	4" O.C.	TOE NAIL
2	CEILING JOSTS TO TOP PLATE	3-3" x 0.131" NAILS 4-8D BOX (2-1/2"x0.113") OR 3-8D COMMON (2-1/2" x 0.131"); OR 3-10D BOX (3" x 0.128"); OR	PER JOIST, TOE NAIL	22	BLOCKING TO SILL OR TOP PLATE (ROOF APPLICATIONS ALSO)	8D COMMON (2-1/2" X 0.131"); OR 10D BOX (3" X 0.128"); OR 3" X 0.131" NAILS	6" O.C.	TOE NAIL
3	CEILING JOISTS NOT ATTACHED TO PARALLEL RAFTER LAPS OVER PARTITIONS	3-3" x 0.131" NAILS	FACE NAIL	23	1"x6" SUBFLOOR OR LESS TO EACH JOIST	3-8D BOX (2-1/2" X 0.113"); OR 2-8D COMMON (2-1/2" X 0.131"); OR 3-10D BOX (3" X 0.128"); OR 2 STAPLES, 1" CROWN, 16 GA, 1-3/4" LONG		E NAIL
4	CEILING JOIST ATTACHED TO PARALLEL RAFTER (HEEL JOINT)	TABLE R802.5.2	FACE NAIL			FLOOR		
5	COLLAR TIE TO RAFTER, FACE NAIL OR 1-1/4"x20 GAGE RIDGE STRAP	4-10D BOX (3" X 0.128"); OR 3-10D COMMON (3" X 0.148"); OR	FACE NAIL EACH RAFTER	24	2" SUBFLOOR TO JOIST OR GIRDER	3-16D BOX (3-1/2" X 0.135"); OR 2-16D COMMON (3-1/2"x0.162")	BLIND ANI	FACE NAIL
	TO RAFTER	4-3" X 0.131" NAILS 3-16d BOX NAILS (3-1/2"x0.135") OR		25	2" PLANKS (PLANK & BEAM - FLOOR & ROOF)	3-16D BOX (3-1/2" X 0.135"); OR 2-16D COMMON (3-1/2"x0.162")	AT EACH BEAF	RING, FACE NAIL
6	RAFTER OR ROOF TRUSS TO PLATE	3-16d BOX NAILS (3-1/2 x0.135) OR 3-10d COMMON NAILS (3"x0.148"); OR 4-10D BOX (3" X .128"); OR 4-3" X 0.131" NAILS 4-16D (3-1/2"x0.135") ; OR	2 TOE NAILS ON ONE SIDE AND 1 TOE NAIL ON OPPOSITE SIDE OF EACH RAFTER OR TRUSS	26	BAND OR RIM JOIST TO JOIST	3-16D COMMON (3-1/2" X 0.162"); OR 4-10 BOX (3" X 0.128"); OR 4-3" X 0.131" NAILS ; OR 4-3" X 14 GA. STAPLES, <u>7</u> 6" CROWN	END	NAIL
7	ROOF RAFTERS TO RIDGE, VALLEY OR HIP RAFTERS OR ROOF RAFTER	4-10D (3-1/2 X0.133), OK 3-10D COMMON (3" X 0.148"); OR 4-10D BOX (3" X 0.128"); OR 4-3" X0.131" NAILS	TOE NAIL			20D COMMON (4" X 0.192"); OR	NAIL EACH LAYER AS TOP END AND BOTTO	
	TO MINIMUM 2" RIDGE BEAM	3-16d BOX NAILS (3-1/2"x0.135") OR 2-16D COMMON NAILS (3-1/2"x0.162"); OR 3-10D BOX (3" X .128"); OR 3-3" X 0.131" NAILS	END NAIL	27	BUILT-UP GIRDERS AND BEAMS, 2" LUMBER LAYERS	10D BOX (3" X 0.128"); OR 3" X 0.131" NAILS AND: 2-20D COMMON (4" X 0.192"); OR 3-10D BOX (3" X 0.128"); OR 3-3" X 0.131" NAILS	24" O.C. FACE NAIL AT STAGGERED ON OPPO FACE NAIL AT ENDS A	OSITE SIDES
		WALL 16D COMMON (3-1/2" X 0.162")	24" O.C. FACE NAIL			4-16D BOX (3-1/2" X 0.135"); OR		
8	STUD TO STUD (NOT AT BRACED WALL PANELS)	10d BOX (3"x0.128"); OR 3" X 0.131" NAILS	16" O.C. FACE NAIL	28	LEDGER STRIP SUPPORTING JOISTS OR RAFTERS	3-16D COMMON (3-1/2" X 0.162"); OR 4-10D BOX (3" X 0.128"); OR 4-3" X 0.131" NAILS	AT EACH JOIST OR	RAFTER, FACE NAIL
9	STUD TO STUD AND ABUTTING STUDS AT INTERSECTING WALL CORNERS (AT BRACED WALL	16D BOX (3-1/2"x0.135"); OR 3" X 0.131" NAILS	12" O.C. FACE NAIL	29	BRIDGING OR BLOCKING TO	2-10D BOX (3" X 0.128"); OR 2-8D COMMON (2-1/2" X 0.131"; OR 2-3" X	EACH ENI	D, TOE NAIL
	PANELS)	16D COMMON (3-1/2" X 0.162")	16" O.C. FACE NAIL		JOIST	0.131") NAILS		
10	BUILT-UP HEADER (2" TO 2" HEADER WITH ¹ / ₂ " SPACER)	16D COMMON (3-1/2"x0.162") 16D BOX (3-1/2" X 0.135)	16" O.C. ALONG EACH EDGE FACE NAIL 12" ALONG EACH EDGE FACE NAIL		M DESCRIPTION OF BUILDING NUMBER AND TYPE OF FASTENER		SPACING OF	FASTENERS
11	CONTINUOUS HEADER TO STUD	5-8D BOX (2-1/2" X 0.113"); OR 4-8D COMMON (2-1/2" X 0.131"); OR 4-10D BOX (3" X 0.128")	TOENAIL	ITEM		NUMBER AND TYPE OF FASTENER	EDGES (IN)	INTERMEDIATE SUPPORTS (IN)
		16D COMMON (3-1/2" X 0.162")	16" O.C. FACE NAIL			6d COMMON (2"x0.113") NAILS (SUBFLOOR,		
12	TOP PLATE TO TOP PLATE	10d BOX (3"x0.128"); OR 3" X 0.131" NAILS	12" O.C. FACE NAIL	30	3/8" - 1/2"	WALL) 8d COMMON (2-1/2"x0.131") NAIL (ROOF); OR RSRS-01 (2-38" X 0.113") NAIL (ROOF)	6	12
13	DOUBLE TOP PLATE SPLICE	8-16D COMMON(3-1/2" X 0.162"); OR 12-16D BOX (3-1/2" X 0.135"); OR 12-10D BOX (3" X 0.128"); OR	FACE NAIL ON EACH SIDE OF END JOINT (MINIMUM 24" LAP SPLICE LENGTH EACH SIDE OF END JOINT)	31	19/32"-1"	8d COMMON NAIL (2-1/2"x0.131"); OR RSRS-01 (2-3/8" X 0.113") NAIL (ROOF)	6	12
	BOTTOM PLATE TO JOIST, RIM	12-3" X 0.131" NAILS 16D COMMON (3-1/2" X 0.162")	16" O.C. FACE NAIL	32	1-1/8" - 1-1.4"	10d COMMON (3"x0.148") NAIL OR 8D (2-1/2"x0.131") DEFORMED NAIL	6	12
14	JOIST, BAND JOIST OR BLOCKING	16D BOX (3-1/2"x0.135"); OR	12" O.C. FACE NAIL			OTHER WALL SHEATHING		
15	(NOT AT BRACED WALL PANELS) BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST BLOCKING (AT	3" X 0.131" NAILS 3-16d BOX NAILS (3-1/2"x0.135") OR 2-16D COMMON (3-1/2"x0.162"); OR	3 EACH 16" O.C. FACE NAIL 2 EACH 16" O.C. FACE NAIL	33	1/2" STRUCTURAL CELLULOSIC FIBERBOARD SHEATHING	1-1/2" GALVANIZED ROOFING NAIL, 7/16" HEAD DIAMETER, OR 1-1/4" LONG 16 GA. STAPLE WITH 76" OR 1" CROWN	3	6
	BRACED WALL PANELS)	4-3" X 0.131" NAILS 4-8D BOX (2-1/2"x0.113") OR 3-16D BOX (3-1/2" x 0.135"); OR	4 EACH 16" O.C. FACE NAIL	34	25/32" STRUCTURAL CELLULOSTIC FIBERBOARD SHEATHING	1-3/4" GALVANIZED ROOFING NAIL, 7/16" HEAD DIAMETER, OR 1-1/2" LONG 16 GA STAPLE WITH <u>7</u> 6" OR 1" CROWN	3	6
16	TOP OR BOTTOM PLATE TO STUD	4-8D COMMON (2-1/2" X 0.131"); OR 4-10D BOX (3" x 0.128"); OR 4-3" x 0.131" NAILS	TOE NAIL	35	1/2" GYPSUM SHEATHING	1-1/2" GALVANIZED ROOFING NAIL; STAPLE GALVANIZED, 1-1/2" LONG; 1-1/4" SCREWS, TYPE "W" OR "S"	7	7
		3-16D BOX (3-1/2" x 0.135"); OR 2-16D COMMON (3-1/2" X 0.162"); OR 3-10D BOX (3" x 0.128"); OR 3-3" x 0.131" NAILS	END NAIL	36	5/8" GYPSUM SHEATHING	1-3/4" GALVANIZED ROOFING NAIL; STAPLE GALVANIZED, 1-5/8" LONG; 1-5/8" SCREWS, TYPE "W" OR "S"	7	7
		3-10D BOX (3" X 0.128"); OR			WOOD STRUCTUR	AL PANELS, COMBINATION SUBFLOOR U	NDERLAYMENT TO F	RAMING
17	TOP PLATES, LAPS AT CORNERS AND INTERSECTIONS	2-16D COMMON (3-1/2" X 0.162"); OR 3-3" X 0.131" NAILS	FACE NAIL	37	3/4" AND LESS	6D DEFORMED (2"x0.120") NAIL OR 8D COMMON (2-1/2"x0.131") NAIL	6	12
18	1" BRACE TO EACH STUD AND PLATE	3-8D BOX (2-1/2" X 0.113"); OR 2-8D COMMON (2-1/2" X 0.131"); OR 2-10D BOX (3" X 0.128"); OR	FACE NAIL	38	7/8" - 1"	8D COMMON (2-1/2"x0.131") NAIL OR 8D DEFORMED (2-1/2"x0.120") NAIL 10D COMMON (3"x0.148") NAIL OR	6	12
19	1"x6" SHEATHING TO EACH BEARING	2 STAPLES 1-3/4" 3-8D BOX (2-1/2" X 0.113"); OR 2-8D COMMON (2-1/2" X 0.131"); OR 2-10D BOX (3" X 0.128"); OR 2 STAPLES, 1" CROWN, 16 GA, 1-3/4" LONG	FACE NAIL	39	1-1/8" - 1-1/4"	8D DEFORMED (2-1/2"x0.120") NAIL	6	12
	1"x8" AND WIDER SHEATHING TO	3-8D BOX (2-1/2" X 0.113"); OR 3-8D COMMON (2-1/2" X 0.131"); OR 3-10D BOX (3" X 0.128"); OR 3 STAPLES, 1" CROWN, 16 GA, 1-3/4" LONG			-			
20	EACH BEARING	WIDER THAN 1" X 8" 4-8D BOX (2-1/2" X 0.113"); OR 3-8D COMMON (2-1/2" X 0.131"); OR 3-10D BOX (3" X 0.128"); OR 4 STAPLES, 1" CROWN, 16 GA, 1-3/4" LONG	FACE NAIL			TABLE R507.2.1 PLACEMENT OF LAG SCF LEDGERS AND BAND MINIMUM END AND EDGE DISTANCES AND (INCHES)	JOISTS	

TABLE R507/2 FASTENER SPACING FOR A SOUTHERN PINE OR HEM-FIR DECK LEDGER 2" NOMINAL SOLID SAWN SPRUCE-PINE-FIR BAND JOIST (DECK LIVE LOAD = 40PSF, DECK DEAD LOAD = 10 PSF)								
JOIST SPAN	6' AND LESS	6'1 TO 8'	8'1 TO 10'	10'1 TO 12'	12'1 TO 14'	14'1 TO 16'	16'1 TO 18'	
CONNECTION DETAILS		ON CENTER SPACING OF FASTENERS						
1/2" DIAMETER LAG SCREW WITH 15/32" MAX SHEATHING	30	23	18	15	13	11	10	
1/2" DIAMETER BOLT WITH 15/32" MAX SHEATHING	36	36	34	29	24	21	19	
1/2" DIAMETER BOLT WITH 15/32" MAX SHEATHING AND 1/2" STACKED WASHERS	36	36	29	24	21	18	16	


MINIMUM WALL STUD FRAMING NOMINAL SIZE AND GRADE	MAXIMUM PONY WALL HEIGHT (FEET)	MAXIMUM TOTAL WALL HEIGHT (FEET)	MAXIMUM OPENING WIDTH (FEET)	(F (E
	0	10	18	
			9	
	1	10	16	
			18	
			9	
	2	10	16	
2x4 NO 2 GRADE			18	
<u> </u>		12	9	
	2		16	
			18	
			9	
	4	12	16	
			18	
			9	
	2	12	16	
2x6 STUD			18	
GRADE			9	
	4	12	16	
			18	
	1			L


MINIMUM LENGTH OF BRACED WALL PANELS TABLE RE (PARTIAL)							
		MINIMUM LENGTH (IN					
M	ETHOD		WALL HEIGHT				
		8 FEET	9 FEET				
	SUPPORTING ROOF ONLY	16	16				
PFH	PFH SUPPORTING ONE STORY AND ROOF		24				
	PFG	24	27				
0	CS-PF	16	18				
CS-WSP	ADJACENT CLEAR OPENING CS-WSP HEIGHT (INCHES)						
	LESS THAN OR EQUAL TO 64	24	27				
	BRACING METHODS TABLE R602 10.4 (PARTIAL)						


BRACING METHODS TABLE R602.10.4 (PARTIAL)					
METHODS,	MINIMUM	CONNECTION CR			
MATERIAL	THICKNESS	FASTENERS			
WSP - WOOD		EXTERIOR SHEATHING PER TABLE R602.3(3)	6"		
STRUCTURAL PANEL	3/8	INTERIOR SHEATHING PER TABLE R602.3(1) OR R602.3(2)	V F		
CS-WSP CONTINUOUSLY		EXERIOR SHEATHING PER TABLE R602.3(3)	6"		
SHEATHED WOOD STRUCTURAL PANEL	3/8	INTERIOR SHEATHING PER TABLE R602.3(1) OR R602.3(2)	V F.		
PFH - PORTAL FRAME WITH HOLD DOWNS	3/8	SEE IRC SECTION R602.10.6.2	SEE R		
PFG - PORTAL FRAME AT GARAGE	3/8	SEE IRC SECTION R602.10.6.3	SEE R		
LIB	1x4 WOOD OR APPROVED METAL STRAPS AT 45 TO 60	WOOD: 2-8d COMMON NAILS OR 3-8d NAILS	WOO AN BOT		
LET-IN-BRACING	DEGREE ANGLES FOR MAX 16" STUD SPACING	METAL STRAP: PER MANUFACTURER	M MAN		
GB-GYPSUM	1/2	NAILS OR SCREWS PER TABLE R602.3(1) FOR EXTERIOR LOCATIONS	FOR W		
BOARD	172	NAILS OR SCREWS PER TABLE R702.3.5 FOR INTERIOR LOCATIONS	EDGE TOP / PLAT		


TABLE R507.2.1 PLACEMENT OF LAG SCREWS AND BOLTS IN DECK LEDGERS AND BAND JOISTS					
MINIMUM END AND EDGE DISTANCES AND SPACING BETWEEN ROWS (INCHES)					
TOP EDGE		BOTTOM EDGE	ENDS	ROW SPACING	
LEDGER	2	1/4	2	1-5/8	
BAND JOIST	3/4	2	2	1-5/8	


	REQUIREMENTS FOR WOOD STRUCTURAL PANEL WALL SHEATHING USED TO RESIST WIND PRESSURES IRC TABLE 602.3(3) (PARTIAL)							
MINIMUM NAIL		MINIMUM WOOD STRUCTURAL	MINIMUM NOMINAL PANEL	MAX WALL STUD	PANEL NAIL SPACING		ULTIMATE DESIGN V V ULT (MP	
	SIZE	PENETRATION (IN)	PANEL SPAN RATING	THICKNESS (IN)	SPACING	EDGES (IN O.C.)	FIELD (IN O.C.)	В
	6d COMMON	1.5	24/0	3/8	16	6	12	140
	8d COMMON	1.75	24/16	7/16	16	6	12	170
		1.75	24/10	//10	24	6	12	140












RELEASE FOR


2x TREATED SILL PLATE W/ 1/2" DIAMETER ANCHOR BOLTS PER IRC SILL GASKET BASI BASEMENT SLAB (PER PLAN) POR BARRIER ON TOP OF RIGID INSULATION, BELOW - INTERIOR DRAIN TI

∕− (8) #4 6'-8" @ 8" O.C. EW


- BOTTOM STEEL CAST WITH SLAB - #3 TIES @ 12" O.C.


MIN 3 $\underbrace{\begin{pmatrix} 6 \\ S3.0 \end{pmatrix}}_{\underline{N.T.S.}} \underline{FOOTING DETAIL}$





 \bigotimes 24" LAP MINIMUM DOWELS DOWELS ∽ FII I – BOTTOM STEEL #4'S @ 12" OC CORNER STEEL - DOUBLE #4 5' LONG EW @ MID-DEPTH OF SLAB 24" LAP MINIMUM DOWELS RECESS _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ SPLIT SLAB OVER WALL AT RECESS 12' MAX 24' MAX GARAGE SLAB ON FILL 1 <u>N.T.S.</u> S3.0





HELIX REQUIREMENTS:

RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW

- FOUNDATION WALL SHALL NOT EXCEED 9' HEIGHT.
- DEAD MAN SHALL BE A MAXIMUM 3'8" FROM TOP OF FOUNDATION WALL ELSE HELIX NOT PERMITTED.
- ALL CONCRETE SHALL BE REINFORCED WITH HELIX MICRO REBAR ALONG WITH ANY ADDITIONAL REBAR AS NOTED:
- 9.0 LB/CUBIC YARD DOSAGE OF HELIX 5-25.
- VERIFY DOSAGE AT FORM INSPECTION.
- SEE MIXING REQUIREMENTS ON THIS PAGE. MINIMUM 3000 PSI FOOTING COMPRESSIVE STRENGTH
- MINIMUM 3000 PSI WALL COMPRESSIVE CONCRETE STRENGTH.
- AIR ENTRAINED BETWEEN 5-7% OF CONCRETE VOLUME.
- GRADE 60 REINFORCING STEEL UNLESS OTHERWISE NOTED. LAP SPLICES 24" MINIMUM.
- ASSUMED 2000 PSF BEARING (TO BE VERIFIED BY GEOTECHNICAL ENGINEER). • WALL SHALL BE BACK-FILLED WITH CLEAN, LEAN CLAY, OR BETTER, LOW VOLUME CHANGE MATERIAL. ON-SITE MATERIAL MAY BE USED IF DEEMED ACCEPTABLE BY THE GEOTECHNICAL ENGINEER.


HELIX ALTERNATE DESIGN NOT VALID IF ANY ONE OF THE FOLLOWING CONDITIONS ARE MET:

• NON-UNIFORM FOOTING SUPPORT (IE. CAST IN PLACE PIERS, PUSH PILES). DAYLIGHT WALLS EXCEEDING 6' TALL FOR A LENGTH GREATER THAN 6'.

HELIX DOSING INSTRUCTIONS:


MIXING SHOULD BE DONE ACCORDANCE WITH ASTM C94 AND THE MIXING INSTRUCTIONS BELOW. THE DOSAGES OF HELIX ADDED TO THE MIX SHOULD BE NOTED ON THE BATCH DOCUMENTATION IN ACCORDANCE WITH UNIFORM EVALUATION SERVICE ER 279 SECTION 5.15. VERIFIED USING PROCEDURE IN ER 279 APPENDIX A.

A SLUMP OF 125 MM OR 5" OR HIGHER WILL FACILITATE STRIKE OFF. A SLUMP OF LESS THAN 4" IS NOT RECOMMENDED AS THIS WILL PREVENT SURFACE SEGREGATION OF THE CEMENT AND FINES FROM THE AGGREGATE AND HELIX. SLUMP SHOULD BE MEASURED ON THE INITIAL LOAD AND ADJUSTMENTS MADE WITH A WATER REDUCER OR PLASTICIZER (NOT WATER).









		HELIX DOSAGE							
4	ALL STRIP FOOTINGS AND GRADE BEAMS 9 LB/CU FT								
	ISOLATED FOOTINGS AND COLUMN PADS								
1	PIER PAD SIZE	DE	EPTH		NIMUM REINFORCEMENT GRADE 60 KSI STEEL	SCHEDULE 40 STEEL COLUMN, MIN FY = 35 KSI	HELIX DOSAGE		
7	30"x30"	1	'-0"		(5) #4 BAR E.W.	3" DIAMETER	12.5 LB/CU FT		
7	36"x36"	1	'-0"		(6) #4 BAR E.W.	3" DIAMETER	12.5 LB/CU FT		
7	42"x42"	1	'-2"		(7) #4 BAR E.W.	3" DIAMETER	12.5 LB/CU FT		
7	48"x48"	1	1'-4"		(8) #4 BAR E.W.	3" DIAMETER	12.5 LB/CU FT		
7	48"x48"	48"x48" 1'-4"			(8) #4 BAR E.W.	N/A	12.5 LB/CU FT		
7	54"x54"	1	'-4"		(9) #4 BAR E.W.	3.5" DIAMETER	12.5 LB/CU FT		
7	60"x60"	1	'-6"		(10) #4 BAR E.W.	3.5" DIAMETER	12.5 LB/CU FT		
Λ	I PIER DIAMETER DE		DEP.	тн	MINIMUM REINFORCE GRADE 60 KSI STE	HELIX DOSAGE			
12" 3'-0")"	(4) VERTICA	12.5 LB/CU FT					
7	16" 3'-0)"	(4) VERTICA	12.5 LB/CU FT				
18"		3'-0)"	(4) VERTICAL #4		12.5 LB/CU FT			
24" 3'-0)"	(4) VERTICA	12.5 LB/CU FT					
7	28" 3'-0")"	(4) VERTICA	12.5 LB/CU FT				

NSIONS		HEIGHT ABOVE REINFORCINGBARS FOOTING (GRADE 60)		HELIX DOSAGE.	
"F"	"G"	"Y"	"Z"	HEEK BOOKOE.	
8"	3'-4"	2'-6"	4 BARS AT 24" O.C.	9.0 LB/CUBIC YARD	
8"	4'-4"	2'-6"	4 BARS AT 24" O.C.	9.0 LB/CUBIC YARD	

WALL DETAIL N.T.S

