EAST BRIDGE PLANS
FOR
PARAGON STAR DEVELOPMENT – LEE'S SUMMIT, MO

View High Dr, View High Pkwy, River Rd
Sections 33 & 34–Township 48–Range 32
City of Lee's Summit
Jackson County, Missouri

Design Speed = 40 mph

Summary of Quantities

Item No.	Description	Unit	Unit Quantity
1	East Bridge	L.S.	1



Scale: 1"=1000'

INDEX OF SHEETS

PROJECT BENCHMARK

BM #11 – Chiseled "L" on top Northeast corner of concrete guardrail at the Northeast corner of I470 bridge spanning View High Drive.
EL=833.80

UTILITY CONTACTS

Sanitary Sewers
Mr. Jeff Thorn, PE
City of Lee's Summit Water Utilities
1200 SE Hamblen Road
Lee's Summit, MO 64063
(816) 969–1922
email: jeff.thorn@cityofLS.net

Mr. Jeff Shook
Little Blue Valley Sewer District
21101 East 78 Highway
Independence, MO 64057
(816) 285–1522
email: jshook@lbvsd.net

Water
Mr. Jeff Thorn, PE
City of Lee's Summit Water Utilities
1200 SE Hamblen Road
Lee's Summit, MO 64063
(816) 969–1922
email: jeff.thorn@cityofLS.net

Electric Service
Mr. Nathan Michael
Evergy
P.O. Box 418679
Kansas City, MO 64141
(816) 220–5210
Fax (816) 245–3623
email: Nathan.Michael@kcpl.com

Gas
Mr. Donnie Richards
Missouri Gas Energy
7500 E 35th Terrace
Kansas City, MO 64129
(816) 472–9464
Fax (816) 472–3488
email: donnie.richards@sug.com

Cable Television
Mr. Greg Thomas
Time Warner Cable
8221 W. 119th Street
Overland Park, KS 66213
(913) 643–1950
email: greg.thomas@twcable.com

Telephone
Ms. Glenda Charles
AT&T
1425 Oak Street
Kansas City, MO 64106
(816) 365–1669
Fax (816) 275–1109
email: gc6954@att.com

Missouri One Call System 1–800–344–7483 (DIG–RITE)

VICINITY MAP

Section 33 & 34-T48N-R32W

DEVELOPED AND OWNED BY:
PARAGON STAR LLC
801 NORTHWEST COMMERCE CENTER
LEE'S SUMMIT, MISSOURI 64086
PHONE: (816) 802–6801
CONTACT: Mr. Flip Short
EMAIL: fshort@legacytouch.com

PREPARED & SUBMITTED BY:
GEORGE BUTLER ASSOCIATES, INC.
9801 RENNER BOULEVARD
LENEXA, KANSAS 66219
PHONE: 913–492–0400
FAX: 913–577–8312
CONTACT: BRAD BURTON P.E.
EMAIL: BBURTON@GBATEAM.COM

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER

PROJECT ENGINEER:

10/13/20
DATE:

Kent Monter
Digitally signed by Kent Monter
Reason: I am approving this document
Date: 2021.03.05 14:33:45-06'00'

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

10/13/20 – PLANS FOR CONSTRUCTION

EAST BRIDGE
(50'-105'-50') PRESTRESSED CONCRETE NU-GIRDER SPANS

SEC/SUR 34 TWP 48N RGE 32W



✳ 2:1 (H:V) Slope (Normal) 2'-0" Thick Type 2 Rock Blanket with Permanent Erosion Control Geotextile

ELEVATION
(Looking North)
(Aesthetics not shown for clarity)



PLAN

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	1
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

BM #11 Chiseled "L" on top Northeast corner of concrete guardrail at Northeast corner of I-470 Bridge spanning View High Drive.
Elev. = 833.80

Notice and Disclaimer Regarding Boring Log Data

"⊕" Indicates location of borings.

The locations of all subsurface borings for this structure are shown on the plan sheet(s) for this structure. The boring data for all locations indicated, as well as any other boring logs or other factual records of subsurface data and investigations performed by the Geotechnical Engineer for the design of the bridge, are shown on Sheet No. 30. No greater significance or weight should be given to the boring data depicted on the plan sheets than is given to the subsurface data available from the Engineer or elsewhere.

The Engineer does not represent or warrant that any such boring data accurately depicts the conditions to be encountered in constructing this bridge. A contractor assumes all risks it may encounter in basing its bid prices, time or schedule of performance on the boring data depicted here, or on any other documentation not expressly warranted, which the contractor may obtain from the Engineer.

Hydrologic Data
Drainage Area = 56.8 (sq. mi.) Design Flood Frequency = 50 years Design Flood Discharge = 4,794 cfs Design Flood (D.F.) Elevation = 809.4
Base Flood (100-year)
Base Flood Elevation = 810.9 Base Flood Discharge = 5,636 cfs Estimated Backwater = 0.1 ft Average Velocity thru Opening = 2.4 ft/s
Freeboard (50-year)
Design High Water = 809.4
Freeboard = 2.6 ft
Roadway Overtopping
Overtopping Flood Frequency >500 years

N

Notes:

Roadway fill shall be completed to the final roadway section and up to the elevation of the bottom of the concrete beam within the limits of the structure and for not less than 25 feet in back of the fill face of the end bents before any piles are driven for any bents falling within the embankment section.

All bents are parallel.

All longitudinal dimensions shown are horizontal.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

BRIDGE: EAST PARAGON PARKWAY OVER LITTLE BLUE RIVER

General Notes:

Design Specifications:
2012 AASHTO LRFD Bridge Design Specifications (6th Ed.) and 2013 Interim Revisions.
Seismic Design Category = A
All referenced specifications shall refer to Missouri Standard Specifications for Highway Construction unless otherwise noted. Construction of the bridge shall conform to the MoDOT standard specificiation. Payment for construction of the bridge shall be completely covered by the lump sum.

Design Loading:
Vehicular = HL-93
Future Wearing Surface = 35 lb/sf
Earth = 120 lb/cf
Equivalent Fluid Pressure = 70 lb/cf

Design Unit Stresses:

Class B Concrete (Substructure)	f'c = 4,000 psi
Class B-1 Concrete (Barrier Curb)	f'c = 4,000 psi
Class B-2 Concrete (Superstructure except Barrier Curb	f'c = 4,000 psi
Reinforcing Steel (Grade 60)	fy = 60,000 psi
Structural Steel HP Pile (ASTM A709 Grade 50S)	fy = 50,000 psi

For Precast Prestressed Panel Stresses, see Sheet No. 17.
For Prestressed Girder Stresses, See Sheets No. 14 & 15.

Neoprene Pads:
Plain and Laminated Neoprene Bearing Pads shall be 60 durometer and shall be in accordance with Sec 716.

Joint Filler:
All joint filler shall be in accordance with Section 1057 for preformed sponge rubber expansion and partition joint filler, except as noted.

Reinforcing Steel:
Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.
All reinforcement shall be epoxy coated.

Minimum clearance between galvanized piles and uncoated (plain) bar supports shall be 1 1/2". Nylon, PVC, or other polyethylene spacers shall be used to maintain clearance. Nylon cable ties shall be used to bind the spacers to the reinforcement.

Miscellaneous:
City Construction personnel will indicate the type of joint filler option used under the precast panels for this structure:

☐ Constant Joint Filler

☐ Variable Joint Filler

FOUNDATION DATA

TYPE	DESIGN DATA		BENT NUMBER 1	2	3	4
Load Bearing Pile	Pile Type and Size		HP12x53	HP12x53	HP12x53	HP12x53
	Number	ea	7	15	12	7
	Approximate Length per Each	ft	55	38	10	45
	Pile Point Reinforcement	ea	7	15	12	7
	Min. Galvanized Penetration (Elev.)	ft	full depth	full depth	full depth	full depth
	Est. Max. Scour Depth 500 (Elev.)	ft	794	790	792	786
	Pile Driving Verification Method		WEAP	DT	DT	WEAP
	Resistance Factor		0.5	0.65	0.65	0.5
	Minimum Nominal Axial Compressive Resistance	kip	428	512	540	434

WEAP = Wave Equation Analysis of Piles

Minimum Nominal Axial Compressive Resistance = Maximum Factored Loads/Resistance Factor

Prebore for piles at Bent No. 3 to elevation 769.0.

HP piles are anticipated to be driven to refusal on rock. Review all borings for depth of rock and restrict driving as appropriate to comply with hard rock driving criteria in accordance with Sec 702.

All piles shall be galvanized to the full length of pile.

Pile point reinforcement need not be galvanized. Shop drawings will not be required for pile point reinforcement.

The contractor shall make every effort to achieve the minimum galvanized penetration (elevation) shown on the plans for all piles. Deviations in penetration less than 5 feet of the minimum will be considered acceptable provided the contractor makes the necessary corrections to ensure the minimum penetration is achieved on subsequent piles.

Method of forming the slab shall be as shown on the plans and in accordance with Sec 703. All hardware for forming the slab to be left in place as a permanent part of the structure shall be coated in accordance with ASTM A123 or ASTM B633 with a thickness class SC 4 and a finish type I, II, or III.

Contractor to provide shoring plan for piers signed and sealed by a professional engineer licensed in the State of Missouri.

For all drill and grout applications the contractor shall use one of the qualified resin anchor systems in accordance with Sec. 1039

Contractor shall provide rebar shop drawings for review prior to ordering reinforcement.





STIRRUP HOOK DIMENSIONS GRADES 40 - 50 - 60 KSI					
BAR SIZE	D (IN.)	90° HOOK		135° HOOK	
		HOOK A OR G		HOOK A OR G	APPROX. H
#4	2"	4 1/2"		4 1/2"	3"
#5	2 1/2"	6"		5 1/2"	3 3/4"
#6	4 1/2"	12"		8"	4 1/2"

NOTE: UNLESS OTHERWISE NOTED, DIAMETER "D" IS THE SAME FOR ALL BENDS AND HOOKS ON A BAR.

END HOOK DIMENSIONS				
BAR SIZE	D (IN.)	ALL GRADES		
		180° HOOKS		90° HOOKS
		A OR G	J	A OR G
#3	2 1/4"	5"	3"	6"
#4	3"	6"	4"	8"
#5	3 3/4"	7"	5"	10"
#6	4 1/2"	8"	6"	12"
#7	5 1/4"	10"	7"	14"
#8	6"	11"	8"	16"
#9	9 1/2"	15"	11 3/4"	19"
#10	10 3/4"	17"	13 1/4"	22"
#11	12"	19"	14 3/4"	2'-0"
#14	18 1/4"	2'-3"	21 3/4"	2'-7"

NOTE:

ALL STANDARD HOOKS AND BENDS OTHER THAN 180 DEGREE ARE TO BE BENT WITH SAME PROCEDURE AS FOR 90 DEGREE STANDARD HOOKS.
HOOKS AND BENDS SHALL BE IN ACCORDANCE WITH THE PROCEDURES AS SHOWN ON THIS SHEET.
E = EPOXY COATED REINFORCEMENT.
S = STIRRUP.
X = BAR IS INCLUDED IN SUBSTRUCTURE QUANTITIES.
V = BAR DIMENSIONS VARY IN EQUAL INCREMENTS BETWEEN DIMENSIONS SHOWN ON THIS LINE AND THE FOLLOWING LINE.
NO. EA. = NUMBER OF BARS OF EACH LENGTH.
NOMINAL LENGTHS ARE BASED ON OUT TO OUT DIMENSIONS SHOWN IN BENDING DIAGRAMS AND ARE LISTED FOR FABRICATORS USE. (NEAREST INCH)
ACTUAL LENGTHS ARE MEASURED ALONG CENTERLINE BAR TO THE NEAREST INCH.
PAYWEIGHTS ARE BASED ON ACTUAL LENGTHS.
FOUR ANGLE OR CHANNEL SPACERS ARE REQUIRED FOR EACH COLUMN SPIRAL. SPACERS ARE TO BE PLACED ON INSIDE OF SPIRALS. LENGTH AND WEIGHT OF COLUMN SPIRALS DO NOT INCLUDE SPLICES OR SPACERS.
REINFORCING STEEL (GRADE 60) FY = 60,000 PSI.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE: 09-17-20
DESIGN BY: JJM
DRAWN BY: DWM
PROJECT NO.: 12720
SHEET NO.: 2
TOTAL SHEETS: 30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GENERAL NOTES

Note: This drawing is not to scale. Follow dimensions.



PLAN OF BEAM



PLAN OF BEAM SHOWING REINFORCEMENT
(Note: Steps and keys not shown for clarity)



SECTION THRU KEY



BEARING PAD DETAIL



✳ Galvanizing material shall be omitted or removed 1 inch clear of weld locations. See special provisions.

STEEL PILE SPLICE
(if required)

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

Notes:

For details of End Bent No. 1 not shown, see Sheets No. 4 & 5.

For details of Vertical Drain at End Bents, see Sheet No. 6.

Reinforcing steel shall be shifted to clear piles. U-bars shall clear piles by at least 1½″.

All concrete in the end bent above top of beam and below top of slab shall be Class B-2.

For reinforcement of Barrier Curb, see Sheets No. 21-23 and 26.

DETAILS OF END BENT NO. 1

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	3
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



SECTION NEAR END BENT
(Stirrup reinforcement and keys not shown for clarity)



PART PLAN
(Note: Steps and keys not shown for clarity)

DETAILS OF END BENT NO. 1

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	4
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



DETAIL A



BAR BENDING DIAGRAMS

Notes:

For details of End Bent No. 1 not shown, see Sheets No. 3 & 5.

For details of Vertical Drain at End Bents, see Sheet No. 6.

Reinforcing steel shall be shifted to clear piles. U-bars shall clear piles by at least 1½".

All concrete in the end bent above top of beam and below top of slab shall be Class B-2.

For reinforcement of Barrier Curb, see Sheets No. 21-23 and 26.

Reinforcing steel shall be shifted as necessary to miss conduit system.

For Conduit Details, see Sheet No. 26 and 27.

For Elevations A-A & B-B, See Sheet No. 5.

For Sections C-C, D-D, E-E & F-F See Sheet No. 5.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	5
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



ELEVATION A-A



TYPICAL SECTION THRU ELEVATION A-A

Looking down station
(* Varies)



ELEVATION B-B



SECTION C-C



SECTION D-D



SECTION E-E



SECTION F-F



DETAIL G



BAR BENDING DIAGRAMS

DETAILS OF END BENT NO. 1

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

Notes:

For details of End Bent No. 1 not shown, See Sheets No. 3 & 4.

For location of Elevations A-A & B-B, See Sheet No. 4.

For location of Sections C-C, D-D, E-E & F-F See Sheet No. 4.

Reinforcing steel shall be shifted to clear piles. U bars shall clear piles by at least 1 1/2 inch.

For reinforcement of Barrier Curb, See Sheets No. 21-23 and 26.

HP pile shall be galvanized to the minimum galvanized penetration (elevation) (See Foundation Data).

Note: This drawing is not to scale. Follow dimensions.



ELEVATION OF SOUTH WING



ELEVATION OF END BENT



PLAN OF END BENT



PART SECTION A-A
(Section thru wing similar)



DETAIL A



ELEVATION OF SOUTH WING



PART PLAN

OPTIONAL TURNED DRAIN
(Only if rock is encountered outside of wing)

General Notes:

All drain pipe shall be sloped 1 to 2 percent.

Drain pipe may be either 6-inch diameter corrugated metallic-coated steel pipe underdrain, 4-inch diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4-inch diameter corrugated polyethylene (PE) drain pipe.

Drain pipe shall be placed at fill face of end bent and inside face of wings. The pipe shall slope to lowest grade of ground line, also missing the lower beam of end bent by a minimum of 1 1/2 inches.

Perforated pipe shall be placed at fill face side and inside face of wings at the bottom of end bent and plain pipe shall be used where the vertical drain ends to the exit at ground line.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

VERTICAL DRAIN AT END BENTS
(Squared end bent shown, skewed end bent similar)

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	6
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



STEEL PILE SPLICE
(if required)



SECTION A-A



SECTION B-B



SECTION C-C

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	7
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



ELEVATION
Note: Dowels & Keys on beam not shown for clarity.



PLAN OF FOOTING



SECTION D-D

Notes:

Hooks shown shall be standard 180 degree hooks.

For details of Int. Bent No. 2 not shown, see Sheet No. 8.

Reinforcing steel shall be shifted to clear piles by 1½".

For steps 2" or more, use 2¼"x½" joint filler up vertical face.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

DETAILS OF INTERMEDIATE BENT NO. 2

Note: This drawing is not to scale. Follow dimensions.



PLAN OF BEAM SHOWING REINFORCEMENT



DETAIL OF KEY



PLAN OF BEAM



BEARING PAD DETAIL

DETAILS OF INTERMEDIATE BENT NO. 2

Note: This drawing is not to scale. Follow dimensions.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

Notes:

For details of Int. Bent No. 2 not shown, see Sheet No. 7.

For steps 2″ or more, use 2¼″x½″ joint filler up vertical face.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	8
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



STEEL PILE SPLICE
(if required)



SECTION A-A



SECTION B-B



SECTION C-C



ELEVATION

Note: Dowels & Keys on beam not shown for clarity.



PLAN OF FOOTING



SECTION D-D

Notes:

Hooks shown shall be standard 180 degree hooks.

For details of Int. Bent No. 3 not shown, see Sheet No. 10.

Reinforcing steel shall be shifted to clear piles by 1½".

For steps 2" or more, use 2¼"x½" joint filler up vertical face.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

DETAILS OF INTERMEDIATE BENT NO. 3

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

NO.	DATE	REVISIONS	BY	APPROVED

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	9
TOTAL SHEETS	30

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri



PLAN OF BEAM SHOWING REINFORCEMENT



DETAIL OF KEY



PLAN OF BEAM



BEARING PAD DETAIL

DETAILS OF INTERMEDIATE BENT NO. 3

Note: This drawing is not to scale. Follow dimensions.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

Notes:

For details of Int. Bent No. 3 not shown, see Sheet No. 9.

For steps 2″ or more, use 2¼″x½″ joint filler up vertical face.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	10
TOTAL SHEETS	30

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



PLAN OF BEAM



PLAN OF BEAM SHOWING REINFORCEMENT
(Note: Steps and keys not shown for clarity)



SECTION THRU KEY



BEARING PAD DETAIL

Notes:

For details of End Bent No. 4 not shown, see Sheets No. 12 and 13.

For details of Vertical Drain at End Bents, see Sheet No. 6.

Reinforcing steel shall be shifted to clear piles. U-bars shall clear piles by at least 1½″.

All concrete in the end bent above top of beam and below top of slab shall be Class B-2.

For reinforcement of Barrier Curb, see Sheets No. 21-23 and 26.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

DETAILS OF END BENT NO. 4

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	11
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



SECTION NEAR END BENT
(Stirrup reinforcement not shown for clarity)



DETAIL A



PART PLAN
(Note: Steps not shown for clarity)



BAR BENDING DIAGRAMS

Notes:

For details of End Bent No. 4 not shown, see Sheets No. 11 and 13.

For details of Vertical Drain at End Bents, see Sheet No. 6.

Reinforcing steel shall be shifted to clear piles. U-bars shall clear piles by at least 1½".

All concrete in the end bent above top of beam and below top of slab shall be Class B-2.

For reinforcement of Barrier Curb, see Sheets No. 21-23 and 26.

Reinforcing steel shall be shifted as necessary to miss conduit system.

For Conduit Details, see Sheet No. 26 and 27.

For Elevations A-A & B-B, See Sheet No. 13.

For Sections C-C, D-D, E-E & F-F See Sheet No. 13.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

DETAILS OF END BENT NO. 4

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	12
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



ELEVATION A-A



TYPICAL SECTION THRU ELEVATION B-B

Looking up station
(✳ Varies)



ELEVATION B-B



SECTION C-C



SECTION D-D



SECTION E-E



SECTION F-F



DETAIL G



BAR BENDING DIAGRAMS

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021

Notes:

For details of End Bent No. 4 not shown, See Sheets No. 11 and 12.

For location of Elevations A-A & B-B, See Sheet No. 12.

For location of Sections C-C, D-D, E-E & F-F See Sheet No. 12.

Reinforcing steel shall be shifted to clear piles. U bars shall clear piles by at least 1 1/2 inch.

For reinforcement of Barrier Curb, See Sheets No. 21-23 and 26.

HP pile shall be galvanized to the minimum galvanized penetration (elevation) (See Foundation Data).

DETAILS OF END BENT NO. 4

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	13
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

Concrete for prestressed girders shall be Class A-1 with f'c = 8500 psi and f'ci = 7000 psi.

(+) indicates prestressing strand.

Use 14 strands with an initial prestress force of 615.2 kips.

Prestressing tendons shall be uncoated, seven-wire, low-relaxation strands, 0.6 inch diameter in accordance with AASHTO M 203, Grade 270. Pretensioned members shall be in accordance with Sec 1029.
Fabricator shall be responsible for location and design of lifting devices.

✳ Girder top flange shall be steel troweled to a smooth finish for 8" at the edges, as shown. Apply two layers of 30-lb roofing felt as a bond breaker to this region only excluding where joint filler is applied. The center portion shall be rough finished by scarifying the surface transversely with a wire brush, and no laitance shall remain on the surface.

✳✳ At the contractor's option the location for bent-up strands may be varied from that shown for fully bonded strands only. The total number of bent-up strands shall not be changed. One strand tie bar is required for each layer of bent-up strands except at end bents which require one bar on the bottom layer of strands only. No additional payment will be made if additional strand tie bars are required.

Fabricator shall be responsible for location and design of lifting devices.



INTERIOR GIRDER AT ALL BENTS & EXTERIOR GIRDER AT END BENT FOR SPANS 1 & 3 GIRDERS



LEFT EXTERIOR GIRDER AT INTERMEDIATE BENT FOR SPANS 1 & 3 GIRDERS (ROTATE 180° FOR RIGHT EXTERIOR)



DIMENSIONS



STRAND ARRANGEMENTS

TOP FLANGE BLOCKOUT



STRAND DETAILS AT GIRDER ENDS

BILL OF REINFORCING STEEL - EACH GIRDER

NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE
72	3 G1	2'-10"	8
2	4 G3	3'-10 1/4"	20
2	4 G4	2'-1"	20
2	4 G5	2'-8 1/8"	20

BENDING DIAGRAMS



G4 and G5 not required for interior girders.

WELDED WIRE REINFORCEMENT - EACH GIRDER

MARK	WIRE SIZE	S	L	J
WWR1	D31	6"	4'-6"	6"
WWR2	D31	12"	9'-0"	10 1/4"
WWR3	D31	12"	20'-0"	

BENDING DIAGRAMS





S = Vertical wire spacing

L = Length of WWR mats

J = Distance between WWR mats

WELDED WIRE PLACEMENT



SECTION A-A

Strands not shown for clarity.



HALF ELEVATION OF GIRDER SPAN (1-2) & (3-4)

Exterior and interior girders are the same, except for coil ties and top flange blockout. Reinforcement support strands not shown for clarity.



SECTION B-B

Strands not shown for clarity.

General Notes:

Reinforcing Steel:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual bar lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All bar reinforcement shall be Grade 60.

Welded Wire Reinforcement (WWR) shall be in accordance with AASHTO M 221. WWR shall not be epoxy coated.

Miscellaneous:

Coil ties shall be held in place in the forms by slotted wire-setting-studs projecting thru forms. Studs are to be left in place or replaced with temporary plugs until girders are erected, then replaced by coil tie rods.

The contractor shall provide bracing necessary for lateral and torsional stability of the girders during construction of the concrete slab and remove the bracing after the slab has attained 75% design strength. Contractor shall not drill holes in the girders.

For location of coil ties and #6 bars at concrete bent diaphragms, see Sheets No. 4, 5, 12, 13 and 16.

For Girder Camber Diagram, see Sheet No. 18.

Precaster shall make necessary adjustment in length of girder to account for slope of road and camber of girder. Adjust beam length and top flange blockout dimensions as necessary.



BEARING PLATE DETAILS

Galvanize the 1/2" bearing plate (ASTM A709 Grade 36) in accordance with ASTM A123.



DETAILS OF VENT HOLE

Place vent holes at or near upgrade 1/3 point of girders and clear reinforcing steel or strands by 1 1/2" minimum.



DETAILS OF COIL TIES

Cast 1"Ø hole horizontally in girder for #6 bar 5'-6" long and clear reinforcing steel or strands by 1 1/2" minimum.

✳✳✳ Length of coil tie rods at exterior face of exterior girders at end bents = 2'-4".

✳✳✳ Length of coil tie rods at faces adjacent to conduit blockout of Girders No. 1 & 2 at intermediate bents = 17".

Note: This drawing is not to scale. Follow dimensions.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

GBA architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	14
TOTAL SHEETS	30

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

Concrete for prestressed girders shall be Class A-1 with f'c = 8500 psi and f'ci = 7000 psi.

(+) indicates prestressing strand.

Use 38 strands with an initial prestress force of 1669.8 kips.

Prestressing tendons shall be uncoated, seven-wire, low-relaxation strands, 0.6 inch diameter in accordance with AASHTO M 203, Grade 270. Pretensioned members shall be in accordance with Sec 1029.
Fabricator shall be responsible for location and design of lifting devices.

✳ Girder top flange shall be steel troweled to a smooth finish for 8" at the edges, as shown. Apply two layers of 30-lb roofing felt as a bond breaker to this region only excluding where joint filler is applied. The center portion shall be rough finished by scarifying the surface transversely with a wire brush, and no laitance shall remain on the surface.

✳✳ At the contractor's option the location for bent-up strands may be varied from that shown for fully bonded strands only. The total number of bent-up strands shall not be changed. One strand tie bar is required for each layer of bent-up strands except at end bents which require one bar on the bottom layer of strands only. No additional payment will be made if additional strand tie bars are required.

Fabricator shall be responsible for location and design of lifting devices.



INTERIOR GIRDER AT INTERMEDIATE BENT FOR SPAN 2 GIRDERS



LEFT EXTERIOR GIRDER AT INTERMEDIATE BENT FOR SPAN 2 GIRDERS (ROTATE 180° FOR RIGHT EXTERIOR)

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	15
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

TOP FLANGE BLOCKOUT



DIMENSIONS

℄ GIRDER

END OF GIRDER

END BENT

INTERMEDIATE BENT

STRAND ARRANGEMENTS

STRAND DETAILS AT GIRDER ENDS

BILL OF REINFORCING STEEL - EACH GIRDER

NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE
125	3 G1	2'-10"	8
2	4 G3	3'-10¼"	20
2	4 G4	2'-1"	20
2	4 G5	2'-8⅛"	20

BENDING DIAGRAMS



G4 and G5 not required for interior girders.

WELDED WIRE REINFORCEMENT - EACH GIRDER

MARK	WIRE SIZE	S	L	J
WWR1	D31	6"	6'-6"	6"
WWR2	D31	6"	8'-6"	6"
WWR3	D31	12"	13'-0"	12"
WWR6	D31	12"	5'-0"	12¾"
WWR7	D31	18"	32'-0"	

BENDING DIAGRAMS



WELDED WIRE PLACEMENT



SECTION A-A

Strands not shown for clarity.



HALF ELEVATION OF GIRDER SPAN (2-3)

Exterior and interior girders are the same, except for coil ties, and top flange blockout. Reinforcement support strands not shown for clarity.

SECTION B-B

Strands not shown for clarity.



S = Vertical wire spacing

L = Length of WWR mats

J = Distance between WWR mats



BEARING PLATE DETAILS

Galvanize the 1/2" bearing plate (ASTM A709 Grade 36) in accordance with ASTM A123.



DETAILS OF VENT HOLE

Place vent holes at or near upgrade 1/3 point of girders and clear reinforcing steel or strands by 1 1/2" minimum.



DETAILS OF COIL TIES

Cast 1"Ø hole horizontally in girder for #6 bar 5'-6" long and clear reinforcing steel or strands by 1 1/2" minimum.

✳✳✳ Length of coil tie rods at exterior face of exterior girders at end bents = 2'-4".

✳✳✳ Length of coil tie rods at faces adjacent to conduit blockout of Girders No. 1 & 2 at intermediate bents = 17".

General Notes:

Reinforcing Steel:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual bar lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All bar reinforcement shall be Grade 60.

Welded Wire Reinforcement (WWR) shall be in accordance with AASHTO M 221. WWR shall not be epoxy coated.

Miscellaneous:

Coil ties shall be held in place in the forms by slotted wire-setting-studs projecting thru forms. Studs are to be left in place or replaced with temporary plugs until girders are erected, then replaced by coil tie rods.

The contractor shall provide bracing necessary for lateral and torsional stability of the girders during construction of the concrete slab and remove the bracing after the slab has attained 75% design strength. Contractor shall not drill holes in the girders.

For location of coil ties and #6 bars at concrete bent diaphragms, see Sheets No. 4, 5, 12, 13 and 16.

For Girder Camber Diagram, see Sheet No. 18.

Precaster shall make necessary adjustment in length of girder to account for slope of road and camber of girder. Adjust beam length and top flange blockout dimensions as necessary.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	16
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



SECTION NEAR INTERMEDIATE BENT

(Conduits and conduit hanger not shown for clarity.)



SECTION B-B



SECTION A-A

#5-U100

#5-U105

#6-H103

#5-H105

#5-H104



DETAIL C

Notes:

Diaphragms at Intermediate Bents shall be built vertically.

For locations of Strand Tie Bars, see Sheets No. 14 and 15.

For locations and details of Coil Tie Rods, see Sheets No. 14 and 15.

For Pedestrian Fence and Pedestrian Rail details, see Architectural Sheets.

For conduit details, see Sheets No. 26 and 27.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

DETAILS OF CONCRETE DIAPHRAGMS AT INTERMEDIATE BENTS NO. 2 & 3

Note: This drawing is not to scale. Follow dimensions.



SQUARED END PANELS OR TRUNCATED END PANELS

PLAN SHOWING PANELS PLACEMENT

* #5-S Bars at abt. 9" cts. (1)
** #3-P1 at 12" cts. (End panels only)



BENDING DIAGRAM FOR U1 BAR

U1 Bars may be oriented at right angles to location and spacing shown. U1 Bars shall be placed between P1 bars.



SECTION B-B



PLAN OF OPTIONAL SKEWED END PANEL



PLAN OF OPTIONAL TRUNCATED END PANEL

*** 3" (Min.), 6" (Max.)



PLAN OF SQUARED PANEL

SKEWED END PANELS



SECTION A-A

Joint Filler Dimensions		
Width	Height	
	Min.	Max.
3"	1"	4"

Reference Notes:

Plan of Panels Placement:

(1) S-bars shown are bottom steel in slab between panels and used with squared and truncated end panels only.

(2) Extend S-bars 18 inches beyond the front face of end bents and int. bents for squared and truncated end panels only.

(3) Extend S-bars 9 inches beyond edge of girder (Typ.).

(4) End panels shall be dimensioned 1/2" min. to 1 1/2" max. from the inside face of diaphragm.

(5) For truncated end panels, use a min. of #5-S bars at 6" crossings in openings, or min. 4x4-W7xW7.

Plans of Panels:

(6) For end panels only, P1 bars shall be 2'-0" in length and embedded 12". P1 bars will not be required for panels at squared integral end bents.

(7) #3-P2 bars near edge of panel at bottom (under strands).

(8) Use #3-P3 bars if panel is skewed 45° or greater.

(9) Any strand 2'-0" or shorter shall have a #4 reinforcing bar on each side of it, centered between strands. Strands 2'-0" or shorter may then be debonded at the fabricator's option.

(10) Optional 1/2" x 45° Chamfer one or both sides at bottom.

Section A-A:

(11) Slab thickness over prestressed panels varies due to girder camber. In order to maintain minimum slab thickness, it may be necessary to raise the grade uniformly throughout the structure. No payment will be made for additional labor or materials required for necessary grade adjustment.

(12) Contractor shall ensure proper consolidation under and between panels.

(13) At the contractor's option, the variation in slab thickness over prestressed panels may be eliminated or reduced by increasing and varying the girder top flange thickness. Dimensions shall be shown on the shop drawings.

General Notes:

Prestressed Panels:

Concrete for prestressed panels shall be Class A-1 with f'c = 6,000 psi, f'ci = 4,000 psi.

The top surface of all panels shall receive a scored finish with a depth of scoring of 1/8" perpendicular to the prestressing strands in the panels.

Prestressing tendons shall be high-tensile strength, uncoated, seven-wire, low-relaxation strands for prestressed concrete in accordance with AASHTO M 203 Grade 270, with nominal diameter of strand = 3/8" and nominal area = 0.085 sq.in. and minimum ultimate strength = 22.95 kips (270 ksi). Larger strands may be used with the same spacing and initial tension.

Initial prestressing force = 17.2 kips/strand.

The method and sequence of releasing the strands shall be shown on the shop drawings.

Suitable anchorage devices for lifting panels may be cast in panels, provided the devices are shown on the shop drawings and approved by the engineer. Panel lengths shall be determined by the contractor and shown on the shop drawings.

When squared end panels are used at skewed bents, the skewed portion shall be cast full depth. No separate payment will be made for additional concrete and reinforcing required.

Support from diaphragm forms is required under the optional skewed end until cast-in-place concrete has reached 3,000 psi compressive strength.

Prestressed panels shall be brought to saturated surface-dry (SSD) condition just prior to the deck pour. There shall be no free standing water on the panels or in the area to be cast.

The prestressed panel quantities are not included in the table of estimated quantities for the slab.

Reinforcing Steel:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

If U1 bars interfere with placement of slab steel, U1 loops may be bent over, as necessary, to clear slab steel.

Deformed welded wire reinforcement (WWR) providing a minimum area of reinforcing perpendicular to strands of 0.22 sq in./ft, with spacing parallel to strands sufficient to ensure proper handling, may be used in lieu of the #3-P2 bars shown. Wire diameter shall not be larger than 0.375 inch. The above alternative reinforcement criteria may be used in lieu of the #3-P3 bars, when required, and placed over a width not less than 2 feet.

The following reinforcing steel shall be tied securely to the strands with the following maximum spacing in each direction:
- #3-P2 bars at 16 inches.
- WWR at 24 inches.

The #3-U1 bars shall be tied securely to #3-P2 bars, to WWR or to strands (when placed between P1 bars) at about 3-foot centers.

Minimum reinforcement steel length shall be 2'-0".

All reinforcement other than prestressing strands shall be epoxy coated.

Precast panels may be in contact with stirrup reinforcing in diaphragms.

S-bars are not listed in the bill of reinforcing.

Cost of S-bars will be considered completely covered by the contract unit price for the slab.

Joint Filler:

Joint filler shall be preformed fiber expansion joint material in accordance with Sec 1057 or expanded or extruded polystyrene bedding material in accordance with Sec 1073.

Use Slab Haunching Diagram on Sheet No. 18 for determining thickness of joint filler within the limits noted in the table of Joint Filler Dimensions.

Thicker material may be used on one or both sides of the girder to reduce cast-in-place concrete thickness to within tolerances.

The same thickness of preformed fiber expansion joint material shall be used under any one edge of any panel except at locations where top flange thickness may be stepped. The maximum change in thickness between adjacent panels shall be 1/4 inch. The polystyrene bedding material may be cut with a transition to match haunch height above top of flange.

Joint filler shall be glued to the girder. When thickness exceeds 1 1/2 inches, the joint filler shall be glued top and bottom. The glue used shall be the type recommended by the joint filler manufacturer.

Edges of panels shall be uniformly seated on the joint filler before slab reinforcement is placed.

DETAILS OF PRESTRESSED PANELS

Note: This drawing is not to scale. Follow dimensions.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	TOTAL SHEETS
17	30

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



THEORETICAL SLAB HAUNCH WITHOUT PRECAST PANELS



THEORETICAL SLAB HAUNCH WITH PRECAST PANELS



TYPICAL SLAB ELEVATIONS DIAGRAM



	Span (1-2)			Span (2-3)			Span (3-4)		
	"A"	"B"	"C"	"A"	"B"	"C"	"A"	"B"	"C"
Ext. Girder	0"	1/8"	1/8"	1 7/8"	5"	2 3/4"	0"	1/8"	1/8"
Int. Girder	0"			1 3/4"			0"		

GIRDER CAMBER DIAGRAM

Conversion factors for girder camber.
0.1 pt. = 0.314 x 0.5 pt.
0.2 pt. = 0.593 x 0.5 pt.
0.25 pt. = 0.7125 x 0.5 pt.
0.3 pt. = 0.813 x 0.5 pt.
0.4 pt. = 0.952 x 0.5 pt.



THEORETICAL SLAB HAUNCHING DIAGRAM

If girder camber is different from that shown in the camber diagram, in order to maintain minimum slab thickness, an adjustment of the slab haunches, an increase in slab thickness or a raise in grade uniformly throughout the structure shall be necessary. No payment will be made for additional labor or materials required for variation in haunching, slab thickness or grade adjustment.

Theoretical Bottom of Slab Elevations at Centerline of Girder
(Prior to forming for slab)

	Span (1-2) (49'-5" ℄ brg - ℄ brg.)					Span (2-3) (103'-10" ℄ brg - ℄ brg.)											Span (3-4) (49'-5" ℄ brg - ℄ brg.)				
	℄ brg.	.25	.50	.75	℄ brg.	℄ brg.	0.10	0.20	0.30	0.40	0.50	0.60	0.70	0.80	0.90	℄ brg.	℄ brg.	.25	.50	.75	℄ brg.
Girder No. 1	819.02	819.41	819.75	820.03	820.26	820.28	820.51	820.71	820.85	820.94	820.96	820.93	820.85	820.70	820.51	820.27	820.25	820.02	819.74	819.40	819.01
Girder No. 2	819.21	819.60	819.94	820.22	820.45	820.47	820.71	820.90	821.05	821.14	821.17	821.14	821.05	820.90	820.70	820.46	820.44	820.21	819.93	819.59	819.20
Girder No. 3	819.39	819.79	820.13	820.41	820.63	820.65	820.89	821.09	821.24	821.32	821.35	821.32	821.23	821.09	820.89	820.65	820.63	820.40	820.12	819.78	819.38
Girder No. 4	819.58	819.97	820.31	820.59	820.82	820.84	821.08	821.28	821.42	821.51	821.54	821.51	821.42	821.27	821.07	820.83	820.81	820.59	820.30	819.96	819.57
Girder No. 5	819.47	819.86	820.20	820.48	820.70	820.72	820.97	821.16	821.31	821.40	821.43	821.40	821.30	821.16	820.96	820.72	820.70	820.47	820.19	819.85	819.46
Girder No. 6	819.28	819.67	820.01	820.29	820.52	820.54	820.77	820.97	821.11	821.19	821.22	821.19	821.10	820.96	820.77	820.53	820.51	820.28	820.00	819.66	819.27

Elevations are based on a constant slab thickness of 8 1/2" and include allowance for theoretical dead load deflections due to weight of slab including precast panel.

SLAB DETAILS

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	18
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021



Note: This drawing is not to scale. Follow dimensions.

Note:
Barrier and curb reinforcement not shown for clarity.

PLAN OF SLAB SHOWING REINFORCING

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	19
TOTAL SHEETS	30

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	TOTAL SHEETS
20	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



HALF SECTION NEAR MIDSPAN

SECTION THRU SLAB
(Median not shown for clarity.)

HALF SECTION NEAR INTERMEDIATE BENT



OPTIONAL SHIFTING
TOP BARS AT BARRIER





SIDEWALK CURB AND PEDESTRIAN
FENCE ATTACHMENT DETAIL

For Curb
details, see
Sheet No. 25



DETAIL B



DETAIL A

	Sequence of Pours					Min. rate of pour cu. yds./hr.
	Direction					With retarder
Basic sequence	1	2	3	4	5	25
	Either direction					
Alternate pours to the basic skip sequence are subject to the approval of the engineer in accordance with Sec 703.						
Alternate "A" pours	1	5 + 2		4 + 3		38
	End to 5	1 to 4		2 to end		
Alternate "B" pours	1 + 5 + 2		4 + 3			38
	End to 4		2 to end			
Alternate "C" pours	1 + 5 + 2 + 4 + 3					38
	End to end					

Note: The contractor shall pour and satisfactorily finish the slab pours at the rate given.

SLAB POURING SEQUENCE



FULL DEPTH SLAB



** Adjust the construction joint to a clearance of 6 inches minimum from the panel joint.

SLAB ON PANELS

SLAB CONSTRUCTION JOINT

Notes:

For details of precast prestressed panels, see Sheet No. 17.

For reinforcement of Barrier Curb not shown, see Sheets No. 21-23 and 26.

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. 18.

For Plan of Slab Showing Reinforcement, see Sheet No. 19.

For Conduit details, see Sheets No 26 and 27.

For Pedestrian Fence and Pedestrian Rail details, see Architectural Sheets.

For median details, see Street Plans.

The sidewalk segment of the bridge shall have a minimum cross-slope of 1.5%. Cross-slopes steeper than 2% are not compliant with ADA and must be made compliant by whatever means necessary, including removal and replacement.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

SLAB DETAILS

Note: This drawing is not to scale. Follow dimensions.



ELEVATION OF LEFT BARRIER CURB

Longitudinal dimensions are horizontal.



ELEVATION OF RIGHT BARRIER CURB

Longitudinal dimensions are horizontal.

PART ELEVATION AT FORMED JOINT



SECTION THRU SAW CUT JOINT

(Use when conduit is required)
(Place conduit in center of concrete section of barrier)



SECTION B-B



PART ELEVATION OF BARRIER CURB



SECTION A-A

The cross-sectional area above the slab = 3.56 sq. ft.



BAR BENDING DIAGRAM



R-BAR PERMISSIBLE ALTERNATE SHAPE

** The R3 bar and #5 bottom transverse slab bar in cantilever (P/S panels only) combination may be furnished as one bar as shown, at the contractor's option.

General Notes

Top of barrier curb shall be built parallel to grade with barrier curb joints (except at end bents) normal to grade.

All exposed edges of barrier curb shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.

Concrete in the barrier curb shall be Class B-1.

Concrete traffic barrier delineators shall be placed on top of the barrier curb as shown on Missouri Standard Plans 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides.

Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.

For Conduit Details, see Sheets No. 26 and 27.

CONVENTIONAL-FORMED BARRIER CURB

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	21
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021



SECTION A-A



SECTION B-B



SECTION C-C



K10

✱✱ Varies 8" to 2'-10"



ELEVATION
END BENT NO. 1

ELEVATION
END BENT NO. 4



PLAN
END BENT NO. 1

PLAN
END BENT NO. 4

General Notes

Concrete traffic barrier delineators shall be placed on top of the barrier curb as shown on Missouri Standard Plans 617.10 and in accordance with Sec 617 of the Missouri Standard Specifications for Highway Construction. Delineators on bridges with two-lane, two way traffic shall have retroreflective sheeting on both sides.

Reinforcing Steel:
Minimum clearance to reinforcing steel shall be $1\frac{1}{2}$".

CONVENTIONAL-FORMED LEFT BARRIER CURB AT END BENTS ON CONCRETE APPROACH SLAB

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	22
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021



SECTION A-A



SECTION B-B



SECTION C-C



ELEVATION
END BENT NO. 1

ELEVATION
END BENT NO. 4



PLAN
END BENT NO. 1

PLAN
END BENT NO. 4



K1
** Varies 1'-10" to 4'-0"

General Notes

Concrete traffic barrier delineators shall be placed on top of the barrier curb as shown on Missouri Standard Plans 617.10 and in accordance with Sec 617 of the Missouri Standard Specifications for Highway Construction. Delineators on bridges with two-lane, two way traffic shall have retroreflective sheeting on both sides.

Reinforcing Steel:
Minimum clearance to reinforcing steel shall be 1½".

CONVENTIONAL-FORMED RIGHT BARRIER CURB AT END BENTS ON WING

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	23
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021



ELEVATION

(Looking North)

(Pedestrian Fence not shown for clarity. See Architectural Sheets.)

Notes:

For details of Light Support and Barrier reinforcement, see Sheet No. 26.

For conduit details, see Sheets No. 26 and 27.

For light standards, light baseplate, and wiring, see "Public Street, Storm Sewer and Street Lighting Plans for Paragon Star Development Paragon Parkway" plans set.

For curb and raised median details, see Sheet No. 25.

For aesthetic details and connections, see Architectural Sheets.



DETAIL A



DETAIL B



PLAN

(Conduit System with hanger not shown for clarity)

GENERAL PLAN AND ELEVATION OF AESTHETIC DETAILS, LIGHTING, AND CONDUIT

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	24
TOTAL SHEETS	30

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021



TYPICAL SECTION

PART ELEVATION
AT FORMED JOINT



For curb extents see Sheet No. 24. Curb joints are similar to barrier curb joints.

SIDEWALK CURB DETAIL ON CONCRETE APPROACH SLAB



For curb extents see Sheet No. 24. Curb joints are similar to barrier curb joints.

SIDEWALK CURB DETAIL ON WING



PLAN OF MEDIAN ON BRIDGE & APPROACH SLAB

Note:

See Street Plans for median details and extents.

MEDIAN AND CURB DETAILS

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	25
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

Notes:

Cost of furnishing and placing anchor bolts for light standard will be considered completely covered by the contract lump sum price for the bridge.

All conduits shall be rigid nonmetallic schedule 40 heavy wall polyvinyl chloride (PVC) with 3" minimum cover in concrete. Each section of conduit shall bear the Underwriters Laboratories (UL) label.

All conduit clamps for conduits not encased in concrete shall be commercially-available, nonmetallic conduit clamps and approved by the engineer.

Anchor bolts and nuts shall be ASTM F1554 Grade 55. Anchor bolts, nuts and washers shall be fully galvanized.

Shift reinforcing steel in field where necessary to clear conduit and junction boxes.

Light standards, wiring and fixtures shall be furnished and installed by others.

For details of light standards, light baseplate, and wiring, see Lighting Plans sheet.

Contractor shall verify the bolt size and pattern in accordance with the light pole manufacturer's specifications prior to placing the anchor bolts.

Expansion fittings shall be placed as shown and set in accordance with the manufacturer's requirements and based on the air temperature at the time of setting given an estimated total expansion movement of 1 inch using a maximum temperature range of 120°F and a maximum temperature of 110°F. Additional expansion fittings beyond what is specified on the bridge plans shall be provided and placed in accordance with the conduit manufacturer's recommendations.

Use "surface" mounting, except adjacent to sidewalks.

All end bent, intermediate bent, and barrier junction boxes shall be PVC molded in accordance with Sec 1062. The conduit terminations shall be permanentor separable. The terminations and covers shall be of watertight construction and shall meet requirements for NEMA 4 enclosure.

Placement of junction boxes and covers, complete in place, shall be flush with the pedestrian face of barrier. Junction boxes and covers may be recessed up to $\frac{1}{4}$".

Weep holes shall be provided at low points or other critical locations to drain any moisture in the conduit system. Conduit shall be sloped to drain.

Drainage shall be provided at low points or other critical locations of all conduits and all junction boxes in accordance with Sec 707. All conduits shall be sloped to drain where possible.

All 1" and 2" diameter conduits shall be secured to concrete with nonmetallic clamps at about 5'-0" cts. Concrete anchors for clamps shall be in accordance with Federal Specification FF-S-325, Group II, Type 4, Class I and shall be galvanized in accordance with ASTM A153, B695-91 Class 50 or stainless steel. Minimum embedment in concrete shall be 1 3/4". The supplier shall furnish a manufacturer's certification that the concrete anchors meet the required material and galvanizing specifications.

Junction box size shown on plan may require special order. No other size may be substituted.

City Construction Personnel: Indicate in field and on bridge plans for future work the exact location of buried conduit at ends of bridge that are capped and not immediately used.

Payment for furnishing and installing light supports, concrete and reinforcing steel, and Conduit System, complete in place, will be considered completely covered by the contract lump sum price for the bridge.

Cast-in-place anchors for the 12-duct conduit system shall be designed per the conduit hanger's engineer and the design shall be signed and sealed by a registerd Professional Engineer in the State of Missouri. The design and details shall be submitted to the owner for review a minimum for four weeks prior to the start of fabrication.



TYPICAL SECTION AT END BENT
SHOWING CONDUIT SYSTEM



EXPANSION FITTING DETAIL



PART PLAN



PART PLAN



SECTION C-C SECTION D-D

(Conduit not shown for clarity)

LIGHT SUPPORTS ON LEFT BARRIER



BENDING DIAGRAMS



CONDUIT SYSTEM HANGER DETAIL

CONDUIT DETAILS

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	26
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans
Paragon Star Development
Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021



TYPICAL END BENT ELEVATION SHOWING
LIGHTING AND CONDUIT

(End Bent No. 4 shown, End Bent No. 1 similar)



TYPICAL INT. BENT ELEVATION SHOWING
LIGHTING AND CONDUIT

(Right fascia shown, left fascia similar)



PLAN AT LEFT BARRIER CURB

(Left barrier at End Bent No. 1 shown,
left barrier at End Bent No. 4 similar)



ELEVATION SHOWING CONDUITS
NEAR END BENTS AT LEFT
BARRIER CURB

(Left barrier at End Bent No. 1 shown,
Left barrier at End Bent No. 4 similar)



TYPICAL SECTION
OF LEFT
BARRIER CURB

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021

CONDUIT DETAILS

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	27
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED



PART PLAN SHOWING REINFORCEMENT



UNDERSEAL ACCESS HOLE DETAIL

(If required)



CONST. JOINT DETAIL



SECTION E-E

(Between curbs)

(See Street plans for concrete curb on Approach Slab to roadway curb details)

General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 (f'c = 4,000 psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with fy = 60,000 psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by lap splicing the #5 bars 29".

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge before pouring the bridge approach slab.

For Concrete Approach Pavement details, see Street plans.

See Street Plans for details of Curb on Approach Slab.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract lump sum price for the bridge.

✳ Seal joint between vertical face of approach slab and wing with "Silicone Joint Sealant for Saw Cut and Formed Joints" in accordance with Sec 717.



SECTION A-A



SECTION B-B



SECTION C-C



SECTION D-D PART ELEVATION

DETAILS OF TIMBER HEADER

Remove timber header when concrete pavement is placed.

DETAILS OF BRIDGE APPROACH SLAB (MAJOR ROAD)

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	28
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.:	29
TOTAL SHEETS	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

As-Built Pile Data

Pile No.	Length in Place (ft)	PDA Nom. Axial Compressive Resistance (kips)	PDA End of Drive Blow Count (blows/in.)	Actual End of Drive Blow Count (blows/in.)	Remarks
					END BENT NO. 1
1					
2					
3					
4					
5					
6					
7					
					INT. BENT NO. 2
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					

As-Built Pile Data

Pile No.	Length in Place (ft)	PDA Nom. Axial Compressive Resistance (kips)	PDA End of Drive Blow Count (blows/in.)	Actual End of Drive Blow Count (blows/in.)	Remarks
					INT. BENT NO. 3
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
					END BENT NO. 4
35					
36					
37					
38					
39					
40					
41					

Note:
Indicate in remarks column:
A. Pile type and grade
B. Batter
C. Driven to practical refusal
D. PDA test pile
E. Minimum tip elevation controlled
(Use when actual blow count is less than PDA blow count due to minimum tip elevation requirement. A plus sign (+) shall be placed after the PDA nominal axial compressive resistance value indicating actual value is higher than PDA value.)

This sheet to be completed by City construction personnel.

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

AS-BUILT PILE DATA

Note: This drawing is not to scale. Follow dimensions.

STATE OF MISSOURI
JOSHUA J. MILLER
NUMBER PE-2009010386
REGISTERED PROFESSIONAL ENGINEER
10/13/20

GBA
architects
engineers
9801 Renner Boulevard
Lenexa, Kansas 66219
913.492.0400
www.gbateam.com

DATE:	09-17-20
DESIGN BY:	JJM
DRAWN BY:	DWM
PROJECT NO.:	12720
SHEET NO.	TOTAL SHEETS
30	30

JOSHUA J. MILLER
PROFESSIONAL ENGINEER
PE-2009010386

East Bridge Plans

Paragon Star Development

Lee's Summit, Missouri

NO.	DATE	REVISIONS	BY	APPROVED

BORING LOG NO. B-5

Page 1 of 1

PROJECT: Paragon Star Bridges

CLIENT: GBA, Lenexa, KS

SITE: I-470 and View High Drive, Lee's Summit, MO

LOCATION See Exploration Plan

Latitude: 38.9389° Longitude: -94.4442°

Approximate Surface Elev.: 802 (Ft.) +/-

MODEL LAYER	GRAPHIC LOG	DEPTH	ELEVATION (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (In.)	FIELD TEST RESULTS	UNCONFINED COMPRESSIVE STRENGTH (tsf)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	ATTERBERG LIMITS LL-PL-PI	PERCENT FINES
2		0.5	801.5+/-										
			6" ROOT ZONE										
			LEAN CLAY (CL), brown to gray, medium stiff - with organics to 1.5 feet				10	2-3-3 N=6		25		41-21-20	
				5			13		1.73	17	109		
							12	2-2-2 N=4		32			
			- very soft to soft, with fine sand below 8 feet	10			20		0.29	30	97	42-21-21	
							12	0-0-0 N=0		35			94
				15									
							12	0-0-0 N=0		32			
				20									
							12	0-1-1 N=2		33			
				25									
							12	0-1-1 N=2		37			
				30									
							12	0-1-1 N=2		32			95
				35									
			- stiff with gravel below 38.5 feet				6	5-7-7 N=14		19			
		41.0	761+/-	40									
3			**SHALE**, with limestone lenses, gray, highly to moderately weathered				3	50/5"		16			
		48.7	753.5+/-	45									
			Boring Terminated at 48.7 Feet				2	50/2"		24			

Stratification lines are approximate. In-situ, the transition may be gradual.
Classification estimated from disturbed samples. Core samples and petrographic analysis may reveal other rock types.

Hammer Type: Automatic

Advancement Method:
0 to 10 ft: Continuous Flight Augers
10 to 48.7 ft.: Wash Bore

Abandonment Method:
Boring backfilled with Auger Cuttings

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Elevations were interpolated from a topographic site plan

Notes:

WATER LEVEL OBSERVATIONS

▽ *8 ft. while drilling*
▽ *7 ft. at completion*

Terracon
15620 W 113th St
Lenexa, KS

Boring Started: 07-01-2019 | Boring Completed: 07-01-2019
Drill Rig: 884 | Driller: DB
Project No.: 02195051

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT: GEO SMART LOG-NO WELL 02195051 PARAGON STAR BRID.GPJ TERRACON_DATATEMPLATE.GDT 7/16/19

BORING LOG NO. B-7

Page 1 of 1

PROJECT: Paragon Star Bridges

CLIENT: GBA, Lenexa, KS

SITE: I-470 and View High Drive, Lee's Summit, MO

LOCATION See Exploration Plan

Latitude: 38.9389° Longitude: -94.4435°

Approximate Surface Elev.: 816 (Ft.) +/-

MODEL LAYER	GRAPHIC LOG	DEPTH	ELEVATION (Ft.)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (In.)	FIELD TEST RESULTS	UNCONFINED COMPRESSIVE STRENGTH (tsf)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	ATTERBERG LIMITS LL-PL-PI	PERCENT FINES
2		0.5	815.5+/-										
			6" ROOT ZONE										
			LEAN CLAY (CL), with fine sand, brown to gray, medium stiff				10	2-3-3 N=6		21			
				5									
					▽								
			- very soft to soft below 8.5 feet				12	0-2-1 N=3		29			
				10									
							12	0-0-0 N=0		33			
				15									
							3	0-0-1 N=1		32			99
				20									
							6	0-0-0 N=0		35			
				25									
							12	0-0-0 N=0		38			
				30									
							12	0-0-0 N=0		33			98
				35									
							12	1-1-1 N=2		33			
				40									
		43.5	772.5+/-										
3			**SHALE**, gray, highly to moderately weathered				3	50/3"		15			
		48.7	767.5+/-	45									
			Boring Terminated at 48.7 Feet				2	50/2"		21			

Stratification lines are approximate. In-situ, the transition may be gradual.
Classification estimated from disturbed samples. Core samples and petrographic analysis may reveal other rock types.

Hammer Type: Automatic

Advancement Method:
0 to 10 ft: Continuous Flight Augers
10 to 48.7 ft.: Wash Bore

Abandonment Method:
Boring backfilled with Auger Cuttings

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Elevations were interpolated from a topographic site plan

Notes:

WATER LEVEL OBSERVATIONS

▽ *8.5 ft. at completion*

Terracon
15620 W 113th St
Lenexa, KS

Boring Started: 07-02-2019 | Boring Completed: 07-02-2019
Drill Rig: 884 | Driller: DB
Project No.: 02195051

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT: GEO SMART LOG-NO WELL 02195051 PARAGON STAR BRID.GPJ TERRACON_DATATEMPLATE.GDT 7/16/19

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021

BORING DATA

Note: For locations of borings, see Sheet No. 1.

Note: This drawing is not to scale. Follow dimensions.

GENERAL NOTES

1. "A" SERIES DRAWINGS PERTAIN TO, BUT ARE NOT LIMITED TO: BRIDGE RAILS, RAIL STRUCTURE, RAIL FINISHES, AND BRIDGE LIGHTING.

2. ALL SPOT ELEVATIONS ARE TO STATE BASE PLANE COORDINATES USED BY THE BRIDGE AND CIVIL SCOPES.

3. ALL SPOT ELEVATIONS ARE FOR GENERAL COORDINATION PURPOSES ONLY. REFERENCE CIVIL AND BRIDGE SCOPES FOR OFFICIAL ELEVATIONS.

4. ALL WELDS ARE TO BE CONTINUOUS AND WATER TIGHT U.N.O.

5. ALL STEEL IS TO BE FULLY GALVANIZED. ANY GALVANIZING REMOVED DURING THE CONSTRUCTION OR INSTALLATION PROCESS SHALL BE REPAIRED WITH A ZINC-RICH PRIMER. BECAUSE ZINC-RICH PRIMER IS UNDERSTOOD TO BE A SHORTER LIVED FINISH AS WELL AS HAVING A DIFFERENT APPEARCE THAN ACTUAL GALVANIZING, EVERY EFFORT SHALL BE MADE TO MINIMIZE RELIANCE UPON ZINC-RICH PRIMER.

6. ANY DIMENSIONS BETWEEN PRIMARY STRUCTURAL ELEMENTS (SUCH AS GRIDS) ARE FOR REFERENCE ONLY. REFERENCE BRIDGE STUCTURE DRAWINGS FOR OFFICIAL DIMENSIONS OF BRIDGE STRUCTURE.

7. ALSO FOR REFERENCE ONLY ARE PORTRAYAL OF BRIDGE COMPONENTS, INCLUDING BUT NOT LIMITED TO: *BRIDGE DECK*, *CURB TRANSITION BARRIERS*, *ROADWAY BARRIERS*, *GIRDERS*, *PIER BEAMS*, PIERS, *ABUTMENTS*, *ABUTMENT WING WALLS*, AND *APPROACH SLABS*. REFERENCE BRIDGE STUCTURE DRAWINGS FOR OFFICIAL DOCUMENTATION OF BRIDGE COMPONENTS.

8. REFERENCE CIVIL DRAWINGS FOR ADJACENCT CIVIL SCOPE, INCLUDING BUT NOT LIMITED TO: ADJACENT *DRIVE* PAVING, *CURBS*, MEDIANS, AND STREET SIGNAGE.

9. REFERENCE BRIDGE ELECTRICAL/LIGHTING PACKAGE FOR ADDITIONAL LIGHTING INFORMATION AT BRIDGE DECK LIGHTING AND AT BRIDGE SIDE LIGHTING.

10. FOR INFORMATION ON CONDUIT ROUTING, REFERENCE ALL OF THE FOLLOWING: BRIDGE RAIL DRAWINGS, BRIDGE DRAWINGS, ELECTRICAL/LIGHTING DRAWINGS.

11. ALL ELECTRICAL CONDUIT SHALL BE WRAPPED TIGHT TO AND ALIGNED WITH ADJACENT SURFACES. RADIUSED CORNERS ARE TO BE KEPT TO BUILDABLE MINIMUM, AND CHANGES IN DIRECTION SHALL BE 90 DEGREES WHERE POSSIBLE.

CODE INFORMATION

IBC 2018
- GUARD RAIL
  - HEIGHT: 42" MINIMUM
  - WHERE REQUIRED: AT LOCATIONS OF ELEVATION CHANGE > 30".
  - STRUCTURAL RESISTANCE FOR HORIZONTAL FORCES
    - POINT LOAD: 200 LB
    - DESTRIBUTED LOAD: 50 LB / LF
  - MAXIMUM OPENING WIDTH: 4"

PROJECT-SPECIFIC TERMINOLOGY

OFFICIAL TERMS USED THROUGHOUT RAIL SCOPE ARE DENOTED BY *ITALICS*.

BRIDGE AND CIVIL - (FOR REFERENCE ONLY, SEE BRIDGE AND CIVIL DWGS FOR OFFICIAL TERMINOLOGY PERTAINING TO RESPECTIVE SCOPES)

DRIVE - PAVED PATH INTENDED FOR VEHICULAR TRAVEL. ALSO CALLED A ROAD.

APPROACH SLAB - ROADWAY SURFACE TRANSITION SITUATED BETWEEN THE *BRIDGE DECK* AND *DRIVE*.

BRIDGE - A STRUCTURE SPANNING A LAND AREA OF RELATIVELY LOWER GRADE ELEVATIONS, TYPICALLY CONNECTING *DRIVES* AND/OR *PEDESTRIAN PATHWAYS* ON EITHER SIDE.

ROADWAY - AT A PAVED *DRIVE* OR *BRIDGE*, THE PORTION OF CONSTRUCTION INTENDED FOR VEHICULAR TRAVEL.

SIDEWALK - TYPICALLY RUNNING PARALLEL WITH AND IN VICINITY TO A *DRIVE*, A PAVED GROUND CONSTRUCTION INTENDED FOR TRAVEL BY INHABITANTS ON FOOT (PEDESTRIANS).

PEDESTRIAN PATHWAY - ON A *BRIDGE*, THE PORTION OF THE *BRIDGE DECK* INTENTED FOR INHABITANTS ON FOOT (PEDISTRIANS).

BRIDGE DECK - THE CONTINOUS HORIZONTAL CONCRETE SLAB WORKING IN CONCERT WITH THE REST OF THE BRIDGE STRUCTURE. THE DECK'S PRIMARY FUNCTIONS ARE: 1. PROVIDE A FINISH SURFACE FOR VEHICLES AND PEDESTRIANS ON THE *BRIDGE*. 2. (IN SOME CASES) ACT AS A DIAPHRAGM, PROVIDING STABILITY TO OVERALL STRUCTURAL SYSTEM OF THE BRIDGE (RE: BRIDGE DWGS). 3. THE *BRIDGE DECK* AND *BRIDGE DECK EDGE ANGLE* TRANSFER LOADS FROM THE *RAIL ASSEMBLIES* AND *ROADWAY BARRIERS* BACK TO THE *BRIDGE GIRDERS*, *PIER BEAMS* AND *BRIDGE PIERS*.

BRIDGE DECK EDGE ANGLE - THE EMBEDDED STEEL SHAPE AT THE *BRIDGE DECK* EDGE PROVIDING FOR THE *RAIL ASSEMBLIES* IN-FIELD ATTACHMENT TO THE *BRIDGE DECK*.

ABUTMENT - AN ASSEMBLY OF VERTICAL CONCRETE WALLS LOCATED AT THE ENDS OF EACH *BRIDGE* CLEAR SPAN. INCLUDES THE *MAIN ABUTMENT* AND *ABUTMENT WING WALLS*.

ABUTMENT (MAIN) - THE PORTION OF THE *ABUTMENT* RUNNING PERPENDICULAR TO THE DIRECTION OF BRIDGE TRAVEL. MAIN ABUTMENT'S PRIMARY FUNCTIONS ARE TO: 1. SUPPORT THE END RUNS OF BRIDGE GIRDERS AND 2. RETAIN SOIL UNDER THE APPROACH SLAB.

ABUTMENT (WING WALLS) - THE RETURN LEGS OF THE *ABUTMENT* RUNNING PARALLEL WITH THE DIRECTION OF BRIDGE TRAVEL. THE WING WALLS PRIMARY FUNCTIONS ARE: 1. TO RETAIN SOIL UNDER THE APPROACH SLABS.

ROADWAY BARRIER - A CONCRETE WALL ON TOP OF THE *BRIDGE DECK* WHOSE PRIMARY FUNCTIONS INCLUDE: KEEPING VEHICLES ON THE *ROADWAY* 2. KEEPING PEDESTRIANS OFF THE *ROADWAY* (***PEDESTRIAN/ROADWAY BARRIER*** WHEN DOING BOTH).

CURB - CONCRETE PROFILE ALONG THE *ROADWAY* EDGE WHOSE PRIMARY FUNCTIONS INCLUDE: 1. CHANNELING WATER DRAINAGE ALONG DESIGNED PATHWAYS 2. KEEPING STRAY VEHICLES ON THE *ROADWAY* BY ACTING AS A MINOR PHYSICAL BARRIER AND AS A NOTIFICATION.

CURB TRANSITION BARRIER - CONCRETE WALL WITH A SLOPING TOP SURFACE, ACTING AS A GRADUAL CHANGE IN HEIGHT FROM A *ROADWAY CURB* TO A *BRIDGE ROADWAY BARRIER*. PRIMARY FUNCTIONS: 1. ELIMINATE A BLUNT FORCE IMPACT OF STRAY VEHICALS UPON CROSSING A BRIDGE

BRIDGE LONG SPAN GIRDERS - STRUCTURAL MEMBERS THAT SPAN THE OPENING BENEATH THE BRIDGE, SITUATED UNDER THE *BRIDGE DECK* AND OVER THE *BRIDGE PIER BEAMS / BENTS*.

BRIDGE PIER BEAMS OR BENTS - CONCRETE GIRDER DIRECTLY ATOP *BRIDGE PIERS*, THESE MEMBERS COLLECT ALL THE FORCES OF THE *LONG SPAN BRIDGE GIRDERS* AND "BENDS" (*BENT*) THE FORCES TO THE PIERS.

BRIDGE PIERS - SITUATED AT INTERMEDIATE *BRIDGE BENTS*, *PIERS* ARE VERTICAL CONCRETE COLUMNS WHOSE PRIMARY FUNCTIONS ARE TO: 1. TRANSFER VERTICAL LOADS FROM *BRIDGE PIER BEAMS* TO PIER FOUNDATION SYSTEMS IN THE GROUND. 2. CREATE A CLEARING UNDER A BRIDGE FOR OTHER ENTITIES (SUCH AS WATER) TO PASS. 3. MAINTAIN A PLAN PROFILE THAT REDUCES FRICTION BETWEEN MOVING WATER PASSING UNDER THE BRIDGE.

1 A01.00 **SITE PLAN - ARCHITECTURAL**

SCALE : 1" = 100'-0"

RAILS

RAIL VERT - A SINGLE VERTICAL STEEL MEMBER OR "PICKET" IN THE *RAIL ASSEMBLY*. *RAIL VERTS* MAKE UP THE BULK OF THE MEMBERS IN THE *RAIL ASSEMBLIES*.

RAIL HORIZONTAL - A CONTINUOUS STEEL MEMBER, MORE OR LESS HORIZONTAL, THAT CONNECTS MULTIPLE *RAIL VERTS* TO MAKE A RIGID *RAIL GUARD*.

RAIL GUARD - THE RIGID COLLECTION OF *RAIL VERTS* AND *RAIL HORIZONTALS*.

WING WALL FACE PLATE - AT BRIDGE *ABUTMENT WING WALLS*, A SURFACE APPLIED PLATE PROVIDING FOR THE *RAIL ASSEMBLIES'* ATTACHMENT TO THE *ABUTMENT WING WALL*.

RAIL ANCHORAGE - ANY CONNECTIVE STEEL INTERMEDIATE TO THE *RAIL GUARD* AND EITHER THE *BRIDGE DECK EDGE ANGLE (NORTH AND SOUTH RAIL RUNS AT BRIDGE DECK)*, *WING WALL FACE PLATE* (NORTH AND SOUTH RAIL RUNS AT WING WALLS), OR *ROADWAY/PEDESTRIAN BARRIER* (MIDDLE RAIL RUNS).

RAIL ASSEMBLY - A COLLECTION OF *RAIL VERTS*, *RAIL HORIZONTALS*, AND *RAIL ANCHORAGE* TO BE SHOP FABRICATED INTO A SINGLE, RIGID CONSTRUCTION FOR HOT-DIP GALVANIZING AND SHIPPING TO THE SITE. *RAIL ASSEMBLY* LENGTH SHALL BE DICTATED BY SIZE OF GALVANIZING TANK AVAILABLE TO CONTRACTOR.

RAIL RUN - REFERS TO A CONTINUOS COLLECTION OF SEQUENTIAL *RAIL ASSEMBLIES* ALONG A SINGLE PATH. BOTH THE WEST AND EAST BRIDGES EACH HAVE A *SOUTH*, *NORTH*, AND *MIDDLE RAIL RUN*.

BASELINE ELEVATION - A THEORETICAL ELEVATION ESTABLISHED FOR EACH *RAIL RUN* TO: 1. ALLOW COMMUNICATION OF VERTICAL DIMENSIONS USING SMALLER VALUES 2. ASSIST THE METAL FABRICATOR IN ALIGNING RAIL COMPONENTS DURING SHOP ASSEMBLY AND FIELD INSTALLATION. THE BASELINE ELEVATION IS SET AT 1'-0" BELOW THE LOWEST POINT OF THE ENTIRE RAIL RUN.

RAIL BREAK - MITERED JOINT IN *RAIL VERT*.

WEST BRIDGE - RAIL SHEET LIST

REV #	SHEET #	DESCRIPTION
	A01.00	GENERAL - SITE PLAN
	A01.10	PLANS
	A03.10	WEST BRIDGE - NORTH RAIL RUN
	A03.11	WEST BRIDGE - SOUTH RAIL RUN
	A03.12	WEST BRIDGE - MIDDLE RAIL RUN
	A05.20	RAIL DETAILS
	A05.21	RAIL DETAILS
	A05.30	LIGHT MOUNT DETAILS
	A06.10	RAIL VERT TYPES
	A06.11	SCHEDULE - WEST BRIDGE RAIL VERTS - NORTH RAIL RUN
	A06.12	SCHEDULE - WEST BRIDGE RAIL VERTS - SOUTH RAIL RUN
	A06.13	SCHEDULE - WEST BRIDGE RAIL VERTS - MIDDLE RAIL RUN

EAST BRIDGE - RAIL SHEET LIST

REV #	SHEET #	DESCRIPTION
	A01.00	GENERAL - SITE PLAN
	A01.10	PLANS
	A03.20	EAST BRIDGE - NORTH RAIL RUN
	A03.21	EAST BRIDGE - SOUTH RAIL RUN
	A03.22	EAST BRIDGE - MIDDLE RAIL RUN
	A05.20	RAIL DETAILS
	A05.21	RAIL DETAILS
	A05.30	LIGHT MOUNT DETAILS
	A06.10	RAIL VERT TYPES
	A06.14	SCHEDULE - EAST BRIDGE RAIL VERTS - NORTH RAIL RUN
	A06.15	SCHEDULE - EAST BRIDGE RAIL VERTS - SOUTH RAIL RUN
	A06.16	SCHEDULE - EAST BRIDGE RAIL VERTS - MIDDLE RAIL RUN

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI

03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGOS
NUMBER A-005244
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED: NJC
DRAWN: NJC
REVIEWED: CLR

SHEET TITLE
GENERAL - SITE PLAN

SHEET NUMBER
A01.00

Plotted: 10/13/2020 10:33:48 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



1 A01.00 | A01.10 SCALE : 3/32" = 1'-0"

PLAN-BRIDGE_E



2 A01.00 | A01.10 SCALE : 3/32" = 1'-0"

PLAN-BRIDGE_W

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

STATE OF MISSOURI
CRAIG DERCY ROGGE
NUMBER A-005244
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
PLANS

SHEET NUMBER
A01.10

Plotted 10/13/2020 10:34:07 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



1 / A01.10 | A03.20

LAYOUT ELEVATION

SCALE : 3/32" = 1'-0"

RAIL VERTS: EN1 thru EN577
577 VERTS @ 5" O.C.
SPACING BEGINS @ LEFT.



2 / A01.10 | A03.20

ELEVATION

SCALE : 3/32" = 1'-0"

RAIL LAYOUT LINE NOTES

1. LAYOUT LINES PORTRAY BASIC LOCATIONS OF *RAIL VERT* TOP, BOTTOM & *BREAKS*, AND *RAIL HORIZONTALS*.
RE: 01/A06.10 *RAIL VERT* TYPES AND RAIL SCHEDULES FOR EXACT LOCATIONS AT EACH *RAIL VERT*.

LAYOUT LINE LEGEND

RAIL VERT TOP / BOTTOM LINE

RAIL VERT BREAK LINE

RAIL HORIZONTAL LINE

RAIL REFERENCE

1. RE: A01.00 FOR PROJECT TERMINOLOGY.

2. RE: RAIL ELEVATIONS FOR:
   a. *RAIL VERT LAYOUT*
   b. *RAIL HORIZONTAL* LAYOUT
   c. *RAIL VERT BREAK* LAYOUT.

3. RE: 1 / A06.10 FOR:
   a. *RAIL VERT* CONFIGURATION TYPES.

4. RE: RAIL SCHEDULES FOR:
   a. *RAIL VERT* VERTICAL LOCATION RELATIVE TO EACH RAIL RUN BASELINE ELEVATION
   b. *RAIL VERT* LEG LENGTHS
   c. *RAIL VERT BREAK* ANGLES
   d. *ANCHORAGE* LOCATIONS
   e. *RAIL HORIZONTAL* LOCATIONS

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGGE
NUMBER A-0028246
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
EAST BRIDGE - NORTH RAIL RUN

SHEET NUMBER
A03.20

Plotted 10/13/2020 10:34:10 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



LAYOUT ELEVATION

2 | A01.10 | A03.21 SCALE : 3/32" = 1'-0"

RAIL LAYOUT LINE NOTES

1. LAYOUT LINES PORTRAY BASIC LOCATIONS OF *RAIL VERT* TOP, BOTTOM & *BREAKS*, AND *RAIL HORIZONTALS*. RE: 01/A06.10 *RAIL VERT* TYPES AND RAIL SCHEDULES FOR EXACT LOCATIONS AT EACH *RAIL VERT*.

LAYOUT LINE LEGEND

RAIL VERT TOP / BOTTOM LINE

RAIL VERT BREAK LINE

RAIL HORIZONTAL LINE



ELEVATION

1 | A01.10 | A03.21 SCALE : 3/32" = 1'-0"

RAIL REFERENCE

1. RE: A01.00 FOR PROJECT TERMINOLOGY.
2. RE: RAIL ELEVATIONS FOR:
   a. *RAIL VERT LAYOUT*.
   b. *RAIL HORIZONTAL* LAYOUT
   c. *RAIL VERT BREAK* LAYOUT.
3. RE: 1 / A06.10 FOR:
   a. *RAIL VERT* CONFIGURATION TYPES.
4. RE: RAIL SCHEDULES FOR:
   a. *RAIL VERT* VERTICAL LOCATION RELATIVE TO EACH RAIL RUN BASELINE ELEVATION
   b. *RAIL VERT* LEG LENGTHS
   c. *RAIL VERT BREAK* ANGLES
   d. *ANCHORAGE* LOCATIONS
   e. *RAIL HORIZONTAL* LOCATIONS

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI · CRAIG DEROY ROGOE · NUMBER A-005244 · REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
EAST BRIDGE - SOUTH RAIL RUN

SHEET NUMBER
A03.21

Plotted 10/13/2020 10:34:15 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



LAYOUT ELEVATION

1 / A01.10 | A03.22 SCALE : 3/32" = 1'-0"

RAIL LAYOUT LINE NOTES

1. LAYOUT LINES PORTRAY BASIC LOCATIONS OF *RAIL VERT* TOP, BOTTOM & *BREAKS*, AND *RAIL HORIZONTALS*.
RE: 01/A06.10 *RAIL VERT* TYPES AND RAIL SCHEDULES FOR EXACT LOCATIONS AT EACH *RAIL VERT*.

LAYOUT LINE LEGEND

RAIL VERT TOP / BOTTOM LINE

RAIL VERT BREAK LINE

RAIL HORIZONTAL LINE



ELEVATION

2 / A01.10 | A03.22 SCALE : 3/32" = 1'-0"

RAIL REFERENCE

1. RE: A01.00 FOR PROJECT TERMINOLOGY.

2. RE: RAIL ELEVATIONS FOR:
   a. *RAIL VERT LAYOUT*.
   b. *RAIL HORIZONTAL* LAYOUT
   c. *RAIL VERT BREAK* LAYOUT.

3. RE: 1 / A06.10 FOR:
   a. *RAIL VERT* CONFIGURATION TYPES.

4. RE: RAIL SCHEDULES FOR:
   a. *RAIL VERT* VERTICAL LOCATION RELATIVE TO EACH RAIL RUN BASELINE ELEVATION
   b. *RAIL VERT* LEG LENGTHS
   c. *RAIL VERT BREAK* ANGLES
   d. *ANCHORAGE* LOCATIONS
   e. *RAIL HORIZONTAL* LOCATIONS

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGOE
NUMBER A-005244
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
EAST BRIDGE - MIDDLE RAIL RUN

SHEET NUMBER
A03.22

Plotted 10/13/2020 10:34:19 AM – BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



PLAN DETAIL @ TYP. ANCHORAGE

1 A05.20 | A05.20 SCALE : 1 1/2" = 1'-0"



DETAIL - RAIL @ DECK EDGE - TYP

3 A05.20 | A05.20 SCALE : 1 1/2" = 1'-0"

RAIL REFERENCE

1. RE: A01.00 FOR PROJECT TERMINOLOGY.
2. RE: RAIL ELEVATIONS FOR:
   a. *RAIL VERT LAYOUT*
   b. *RAIL HORIZONTAL* LAYOUT
   c. *RAIL VERT BREAK* LAYOUT.
3. RE: 1 / A06.10 FOR:
   a. *RAIL VERT* CONFIGURATION TYPES.
4. RE: RAIL SCHEDULES FOR:
   a. *RAIL VERT* VERTICAL LOCATION RELATIVE TO EACH RAIL RUN BASELINE ELEVATION
   b. *RAIL VERT* LEG LENGTHS
   c. *RAIL VERT BREAK* ANGLES
   d. *ANCHORAGE* LOCATIONS
   e. *RAIL HORIZONTAL* LOCATIONS



TYP RAIL SECTION @ MID RAIL

5 A01.10 | A05.20 SCALE : 3/4" = 1'-0"



SECTION - TYP RAIL @ N & S ENDS

4 A01.10 | A05.20 SCALE : 3/4" = 1'-0"



SECTION - TYP RAIL @ N & S DECK

2 A01.10 | A05.20 SCALE : 3/4" = 1'-0"

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGIE
NUMBER A-9052#4
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
RAIL DETAILS

SHEET NUMBER
A05.20

Plotted: 10/13/2020 10:34:59 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



RAIL ELEVATION - N&S RAIL RUNS

2 A01.10 | A05.21 SCALE : 3/4" = 1'-0"



RAIL ELEVATION @ MID RAIL RUN END W/ LAMP

4 A01.10 | A05.21 SCALE : 3/4" = 1'-0"

LAYOUT LINE LEGEND

- RAIL VERT TOP / BOTTOM LINE
- RAIL VERT BREAK LINE
- RAIL HORIZONTAL LINE

RAIL LAYOUT LINE NOTES

1. LAYOUT LINES PORTRAY BASIC LOCATIONS OF RAIL VERT TOP, BOTTOM & BREAKS, AND RAIL HORIZONTALS. RE: 01/A06.10 RAIL VERT TYPES AND RAIL SCHEDULES FOR EXACT LOCATIONS AT EACH RAIL VERT.



RAIL ELEVATION - TYP - @ MID RAIL RUN END

3 A01.10 | A05.21 SCALE : 3/4" = 1'-0"



RAIL ELEVATION - AT LAMP

1 A01.10 | A05.21 SCALE : 3/4" = 1'-0"

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGERS
NUMBER A-805244
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
RAIL DETAILS

SHEET NUMBER
A05.21

Plotted 10/13/2020 10:35:07 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt



6 PLAN DETAIL - LIGHT MOUNT

SCALE : 3" = 1'-0"



3 SECTION @ SIDE LIGHT SUPPORT

SCALE : 3" = 1'-0"



2 ELEVATION - DIRECT LIGHT MOUNT

SCALE : 3/4" = 1'-0"

5 LIGHT MOUNT PLATE

SCALE : 3" = 1'-0"



4 LIGHT MOUNT BASE PLATE

SCALE : 3" = 1'-0"

1 LIGHT MOUNT ELEVATION - W BRIDGE - PIER BEAMS

A03.10 | A05.30 SCALE : 1 1/2" = 1'-0"

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGGE
NUMBER A-9052244
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
LIGHT MOUNT DETAILS

SHEET NUMBER
A05.30

Plotted 10/13/2020 10:35:17 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt

RAIL VERT TYPE NOTES

1. RAIL "P01V" ELEVATIONS SHALL BE USED FOR VERTICAL ALIGNMENT OF MEMBERS DURING SHOP ASSEMBLY.

2. VERTICAL DIMENSIONS OR ELEVATIONS STATED IN *RAIL VERT* SCHEDULES ARE TO *BASELINE ELEVATION* FOR EACH *RAIL RUN*. *THE BASELINE ELEVATION* IS ARBITRARILY SET TO 1'-0" BELOW THE LOWEST POINT OF EACH *RAIL RUN* AND IS UNIQUE TO EACH *RAIL RUN*.

3. *ANCHORAGE* SPACING LOGIC IS SPECIFIED IN DOCUMENTS, BUT *ANCHORAGE* IS NOT PRESENT AT EVERY *RAIL VERT*. BECAUSE SPECIFIC *ANCHORAGE* PLAN LOCATIONS ARE LAID OUT BY FABRICATOR, "ANV" ELEVATION HAS BEEN PROVIDED FOR ALL *RAIL VERTS*.

RAIL VERT TYPE LEGEND

"#" SYMBOL REPRESENTS A NUMBER

P0# - POINT AT CENTERPOINT OF *RAIL VERT* SEGMENT, LOCATED AT EITHER: *RAIL VERT ENDS* (TOP/BOTTOM) OR *RAIL VERT BREAKS*.

P0#V - POINT VERTICAL DISTANCE TO *BASELINE ELEVATION*

L0# - *RAIL VERT* SEGEMENT (LEG) OR LENGTH OF SEGMENT (LEG)

H0# - *RAIL HORIZONTAL*

H0#V - *RAIL HORIZONTAL* VERTICAL DISTANCE TO *BASELINE ELEVATION*

A0# - ANGLE BETWEEN ADJACENT *RAIL VERT* SEGMENTS

AN01 - CENTERLINE OF *ANCHORAGE*

ANV - *ANCHORAGE* VERTICAL DISTANCE TO *BASELINE ELEVATION*

RAIL VERT ID LOGIC

WN134B

- *BRIDGE* CODE: W = WEST, E = EAST
- *RAIL RUN* CODE: N = NORTH, S = SOUTH, M = MIDDLE
- NUMBER IN SEQUENCE (LEFT TO RIGHT)
- *RAIL VERT* TYPE RE: 1 / A06.10



RAIL VERT - TYPE "A" (MIDDLE RAILS)

RAIL VERT - TYPE "B" (SIDE RAILS)

RAIL VERT - TYPE "C" (SIDE RAILS)

1 A06.10 RAIL VERT TYPES

SCALE : 1 1/2" = 1'-0"



3 A05.21 A06.10 DETAIL ELEVATION - ANCHORAGE AT MID RAIL RUN

SCALE : 3" = 1'-0"



2 A05.21 A06.10 DETAIL ELEVATION - PLATE ANCHORS

SCALE : 3" = 1'-0"

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGGE
NUMBER A-2005244
REGISTERED ARCHITECT
10-13-2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED:	NJC
DRAWN:	NJC
REVIEWED:	CLR

SHEET TITLE
RAIL VERT TYPES

SHEET NUMBER
A06.10

Plotted: 10/13/2020 10:35:24 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt

EAST BRIDGE - NORTH RUN

ID	P01V	L01	A01	L02	A02	L03	LTOT	ANV	H03V	H04V
EN1B	4'-0 7/8"	1'-2 1/4"	162.021°	3'-2 7/8"			4'-5 1/8"	4'-4 1/8"	5'-1 5/8"	7'-1 1/8"
EN2B	4'-0 7/8"	1'-3"	161.971°	3'-2 1/2"			4'-5 1/2"	4'-4 1/4"	5'-2 1/8"	7'-1 5/8"
EN3B	4'-0 7/8"	1'-3 7/8"	161.919°	3'-2 1/8"			4'-6"	4'-4 3/8"	5'-2 5/8"	7'-2 1/8"
EN4B	4'-0 3/4"	1'-4 5/8"	161.866°	3'-1 7/8"			4'-6 1/2"	4'-4 1/2"	5'-3 1/8"	7'-2 5/8"
EN5B	4'-0 5/8"	1'-5 3/8"	161.812°	3'-1 1/2"			4'-7"	4'-4 3/4"	5'-3 5/8"	7'-3 1/8"
EN6B	4'-0 1/2"	1'-6 3/8"	161.752°	3'-1 1/8"			4'-7 1/2"	4'-4 7/8"	5'-4"	7'-3 1/2"
EN7B	4'-0 3/8"	1'-7 1/4"	161.692°	3'-0 7/8"			4'-8 1/8"	4'-5"	5'-4 1/2"	7'-4"
EN8B	4'-0 1/8"	1'-8 1/8"	161.631°	3'-0 1/2"			4'-8 5/8"	4'-5 1/8"	5'-5"	7'-4 1/2"
EN9B	4'-0"	1'-9"	161.567°	3'-0 1/8"			4'-9 1/4"	4'-5 3/8"	5'-5 1/2"	7'-5"
EN10B	3'-11 3/4"	1'-9 7/8"	161.502°	2'-11 5/8"			4'-9 7/8"	4'-5 1/2"	5'-6"	7'-5 3/8"
EN11B	3'-11 1/2"	1'-11"	161.431°	2'-11 1/2"			4'-10 1/2"	4'-5 5/8"	5'-6 3/8"	7'-5 7/8"
EN12B	3'-11 1/4"	2'-0"	161.360°	2'-11 1/8"			4'-11 1/8"	4'-5 7/8"	5'-6 7/8"	7'-6 3/8"
EN13B	3'-11"	2'-1"	161.288°	2'-10 7/8"			4'-11 3/4"	4'-6"	5'-7 3/8"	7'-6 7/8"
EN14B	3'-10 5/8"	2'-2"	161.209°	2'-10 1/2"			5'-0 1/2"	4'-6 1/8"	5'-7 7/8"	7'-7 1/4"
EN15B	3'-10 1/4"	2'-3 1/8"	161.130°	2'-10 1/8"			5'-1 1/4"	4'-6 1/4"	5'-8 1/4"	7'-7 3/4"
EN16B	3'-10"	2'-4 1/8"	161.049°	2'-9 3/4"			5'-2"	4'-6 1/2"	5'-8 3/4"	7'-8 1/4"
EN17B	3'-9 5/8"	2'-5 1/4"	160.964°	2'-9 1/2"			5'-2 3/4"	4'-6 5/8"	5'-9 1/4"	7'-8 5/8"
EN18B	3'-9 1/8"	2'-6 3/8"	160.876°	2'-9 1/8"			5'-3 1/2"	4'-6 3/4"	5'-9 5/8"	7'-9 1/8"
EN19B	3'-8 3/4"	2'-7 1/2"	160.786°	2'-8 3/4"			5'-4 1/4"	4'-6 7/8"	5'-10 1/8"	7'-9 5/8"
EN20B	3'-8 1/4"	2'-8 3/4"	160.692°	2'-8 3/8"			5'-5 1/8"	4'-7 1/8"	5'-10 5/8"	7'-10"
EN21B	3'-7 7/8"	2'-9 7/8"	160.594°	2'-8"			5'-6"	4'-7 1/4"	5'-11"	7'-10 1/2"
EN22B	3'-7 3/8"	2'-11 1/8"	160.494°	2'-7 3/4"			5'-6 7/8"	4'-7 3/8"	5'-11 1/2"	7'-11"
EN23B	3'-6 7/8"	3'-0 3/8"	160.390°	2'-7 3/8"			5'-7 3/4"	4'-7 1/2"	6'-0"	7'-11 3/8"
EN24B	3'-6 1/4"	3'-1 5/8"	160.282°	2'-7"			5'-8 5/8"	4'-7 3/4"	6'-0 5/8"	7'-11 7/8"
EN25B	3'-5 3/4"	3'-3"	160.170°	2'-6 5/8"			5'-9 5/8"	4'-7 7/8"	6'-0 7/8"	8'-0 1/4"
EN26B	3'-5 1/8"	3'-4 1/4"	160.054°	2'-6 1/4"			5'-10 1/2"	4'-8"	6'-1 1/4"	8'-0 3/4"
EN27B	3'-4 5/8"	3'-5 3/8"	159.934°	2'-5 7/8"			5'-11 1/2"	4'-8 1/8"	6'-1 3/4"	8'-1 1/8"
EN28B	3'-3 7/8"	3'-7"	159.811°	2'-5 1/2"			6'-0 1/2"	4'-8 3/8"	6'-2 1/8"	8'-1 5/8"
EN29B	3'-3 1/4"	3'-8 3/8"	159.682°	2'-5 1/4"			6'-1 1/2"	4'-8 1/2"	6'-2 5/8"	8'-2 1/8"
EN30B	3'-2 3/4"	3'-9 3/4"	159.548°	2'-4 7/8"			6'-2 5/8"	4'-8 5/8"	6'-3 1/8"	8'-2 1/2"
EN31B	3'-1 7/8"	3'-11 1/8"	159.412°	2'-4 1/2"			6'-3 5/8"	4'-8 7/8"	6'-3 7/8"	8'-3"
EN32B	3'-1 3/8"	4'-0 5/8"	159.273°	2'-4 1/8"			6'-4 3/4"	4'-9"	6'-4 3/8"	8'-3 5/8"
EN33B	3'-0 7/8"	4'-2 1/4"	159.131°	2'-3 7/8"			6'-5 7/8"	4'-9 1/8"	6'-4 7/8"	8'-4 1/8"
EN34B	3'-0 3/8"	4'-3 7/8"	158.987°	2'-3 1/2"			6'-7"	4'-9 3/8"	6'-5 3/8"	8'-4 5/8"
EN35B	2'-10 3/4"	4'-5 1/8"	158.807°	2'-3"			6'-8 1/8"	4'-9 1/2"	6'-5 1/4"	8'-4 5/8"
EN36B	2'-10"	4'-6 3/8"	158.624°	2'-2 5/8"			6'-9 3/8"	4'-9 5/8"	6'-6 1/8"	8'-5 1/8"
EN37B	2'-9 1/8"	4'-8 1/4"	158.471°	2'-2 1/4"			6'-10 1/2"	4'-9 3/4"	6'-6 7/8"	8'-5 1/8"
EN38B	2'-8 1/4"	4'-9 7/8"	158.292°	2'-1 7/8"			6'-11 3/4"	4'-9 7/8"	6'-6 1/2"	8'-5"
EN39B	2'-7 3/8"	4'-11 1/2"	158.112°	2'-1 1/2"			7'-1"	4'-10 1/8"	6'-7"	8'-6 3/8"
EN40B	2'-6 1/2"	5'-1 1/8"	157.914°	2'-1 1/8"			7'-2 1/4"	4'-10 1/4"	6'-7 3/8"	8'-6 3/4"
EN41B	2'-5 1/2"	5'-2 3/4"	157.715°	2'-0 3/4"			7'-3 5/8"	4'-10 3/8"	6'-7 3/4"	8'-7 1/4"
EN42B	2'-4 5/8"	5'-4 3/8"	157.514°	2'-0 3/8"			7'-4 7/8"	4'-10 1/2"	6'-8 1/4"	8'-7 5/8"
EN43B	2'-3 5/8"	5'-6 1/8"	157.291°	2'-0"			7'-6 1/4"	4'-10 3/4"	6'-8 5/8"	8'-8"
EN44B	2'-2 5/8"	5'-7 7/8"	157.066°	1'-11 5/8"			7'-7 5/8"	4'-10 7/8"	6'-9"	8'-8 3/8"
EN45B	2'-1 1/2"	5'-9 5/8"	156.834°	1'-11 1/4"			7'-9"	4'-11"	6'-9 1/2"	8'-8 7/8"
EN46B	2'-0 1/2"	5'-11 1/2"	156.590°	1'-10 7/8"			7'-10 3/8"	4'-11 1/8"	6'-9 7/8"	8'-9 1/4"
EN47C	1'-10 1/8"	6'-1 3/8"	156.326°	1'-10 1/2"	156.481°	1'-10 5/8"	8'-0 1/4"	4'-11 3/8"	6'-10 1/4"	8'-9 3/4"
EN48C	1'-10 1/8"	1'-9 1/2"	127.730°	5'-11 3/4"	156.463°	1'-10 1/2"	9'-7 3/4"	4'-11 1/2"	6'-10 5/8"	8'-10 1/8"
EN49C	1'-10 1/4"	1'-9 7/8"	129.054°	5'-11 1/2"	156.447°	1'-10 3/8"	9'-7 3/4"	4'-11 5/8"	6'-11 1/8"	8'-10 1/2"
EN50C	1'-10 3/8"	1'-10 1/4"	130.503°	5'-11 1/2"	156.429°	1'-10 1/4"	9'-7 3/4"	4'-11 3/4"	6'-11 1/2"	8'-10 7/8"
EN51C	1'-10 1/2"	1'-10 3/4"	131.483°	5'-11"	156.411°	1'-10"	9'-7 5/8"	4'-11 7/8"	6'-11 7/8"	8'-11 3/8"
EN52C	1'-10 5/8"	1'-11 1/8"	132.600°	5'-10 3/4"	156.393°	1'-9 7/8"	9'-7 5/8"	5'-0 1/8"	7'-0 1/4"	8'-11 3/4"
EN53C	1'-10 7/8"	1'-11 5/8"	133.875°	5'-10 3/4"	156.375°	1'-9 3/4"	9'-7 3/4"	5'-0 1/4"	7'-0 3/4"	8'-12 1/8"
EN54C	1'-10 7/8"	1'-11 7/8"	134.667°	5'-10 1/4"	156.357°	1'-9 5/8"	9'-7 3/4"	5'-0 3/8"	7'-1 1/8"	9'-0 1/2"
EN55C	1'-11"	2'-0 1/4"	135.621°	5'-10"	156.338°	1'-9 3/8"	9'-7 3/4"	5'-0 1/2"	7'-1 1/2"	9'-0 7/8"
EN56C	1'-11 1/4"	2'-0 5/8"	136.738°	5'-9 7/8"	156.319°	1'-9 1/4"	9'-7 3/4"	5'-0 5/8"	7'-1 7/8"	9'-1 3/8"
EN57C	1'-11 1/4"	2'-1 1/8"	137.381°	5'-9 5/8"	156.301°	1'-9 1/8"	9'-7 7/8"	5'-0 3/4"	7'-2 1/4"	9'-1 3/4"
EN58C	1'-11 3/8"	2'-1 1/2"	138.195°	5'-9 1/2"	156.282°	1'-9"	9'-7 7/8"	5'-1"	7'-2 5/8"	9'-2 1/8"
EN59C	1'-11 3/8"	2'-1 7/8"	138.960°	5'-9 1/4"	156.263°	1'-8 3/4"	9'-8"	5'-1 1/8"	7'-3"	9'-2 5/8"
EN60C	1'-11 5/8"	2'-2 1/4"	139.700°	5'-9 1/8"	156.244°	1'-8 5/8"	9'-8"	5'-1 1/4"	7'-3 1/2"	9'-2 7/8"
EN61C	1'-11 3/4"	2'-2 3/4"	140.421°	5'-9"	156.223°	1'-8 1/2"	9'-8 1/8"	5'-1 3/8"	7'-3 7/8"	9'-3 1/4"
EN62C	1'-11 7/8"	2'-3"	141.060°	5'-8 3/4"	156.203°	1'-8 3/8"	9'-8 1/8"	5'-1 1/2"	7'-4 1/4"	9'-3 5/8"
EN63C	1'-12"	2'-3 3/8"	141.691°	5'-8 5/8"	156.182°	1'-8 1/8"	9'-8 1/4"	5'-1 5/8"	7'-4 5/8"	9'-4"
EN64C	1'-12 1/8"	2'-3 3/4"	142.299°	5'-8 1/2"	156.164°	1'-8"	9'-8 1/8"	5'-1 7/8"	7'-5"	9'-4 1/2"
EN65C	1'-12 1/4"	2'-4 1/8"	142.856°	5'-8 3/8"	156.143°	1'-7 7/8"	9'-8 1/2"	5'-2"	7'-5 3/8"	9'-4 7/8"
EN66C	1'-12 3/8"	2'-4 1/2"	143.397°	5'-8 1/4"	156.122°	1'-7 3/4"	9'-8 1/2"	5'-2 1/8"	7'-5 3/4"	9'-5 1/4"
EN67C	1'-12 7/8"	2'-4 7/8"	143.911°	5'-8 1/8"	156.102°	1'-7 5/8"	9'-8 5/8"	5'-2 1/4"	7'-6 1/8"	9'-5 5/8"
EN68C	1'-12 7/8"	2'-5 1/4"	144.399°	5'-8 1/8"	156.079°	1'-7 3/8"	9'-8 3/4"	5'-2 3/8"	7'-6 1/2"	9'-6"
EN69C	1'-12 3/4"	2'-5 1/2"	144.864°	5'-8"	156.058°	1'-7 1/4"	9'-8 7/8"	5'-2 1/2"	7'-6 7/8"	9'-6 3/8"
EN70C	1'-12 7/8"	2'-5 7/8"	145.309°	5'-7 7/8"	156.037°	1'-7 1/8"	9'-9"	5'-2 3/4"	7'-7 1/4"	9'-6 3/4"
EN71C	1'-13"	2'-6 1/4"	145.729°	5'-7 7/8"	156.014°	1'-7"	9'-9"	5'-2 7/8"	7'-7 5/8"	9'-7 1/8"
EN72C	1'-13 1/8"	2'-6 1/2"	146.127°	5'-7 3/4"	155.993°	1'-6 7/8"	9'-9 1/8"	5'-3"	7'-8"	9'-7 1/2"
EN73C	1'-13 1/4"	2'-6 7/8"	146.508°	5'-7 3/4"	155.970°	1'-6 3/4"	9'-9 1/4"	5'-3 1/8"	7'-8 3/8"	9'-7 7/8"
EN74C	1'-13 3/8"	2'-7 1/8"	146.870°	5'-7 3/4"	155.947°	1'-6 5/8"	9'-9 3/8"	5'-3 1/4"	7'-8 3/4"	9'-8 1/4"
EN75C	1'-13 1/2"	2'-7 3/8"	147.215°	5'-7 5/8"	155.925°	1'-6 3/8"	9'-9 1/2"	5'-3 3/8"	7'-9 1/8"	9'-8 1/2"
EN76C	1'-13 5/8"	2'-7 5/8"	147.541°	5'-7 5/8"	155.902°	1'-6 1/4"	9'-9 5/8"	5'-3 1/2"	7'-9 5/8"	9'-8 7/8"
EN77C	1'-13 3/4"	2'-8"	147.851°	5'-7 5/8"	155.879°	1'-6 1/8"	9'-9 3/4"	5'-3 3/4"	7'-9 3/4"	9'-9 1/4"
EN78C	1'-13 7/8"	2'-8 1/4"	148.147°	5'-7 5/8"	155.855°	1'-6"	9'-9 7/8"	5'-3 7/8"	7'-10 1/8"	9'-9 5/8"
EN79C	1'-14"	2'-8 1/2"	148.427°	5'-7 5/8"	155.830°	1'-5 7/8"	9'-10"	5'-4"	7'-10 1/2"	9'-9 7/8"
EN80C	1'-14 1/8"	2'-8 3/4"	148.692°	5'-7 5/8"	155.807°	1'-5 3/4"	9'-10 1/8"	5'-4 1/8"	7'-10 7/8"	9'-10 3/8"
EN81C	1'-14 1/4"	2'-9"	148.943°	5'-7 5/8"	155.782°	1'-5 5/8"	9'-10 1/4"	5'-4 1/4"	7'-11 1/4"	9'-10 1/4"
EN82C	1'-14 3/8"	2'-9 1/8"	149.180°	5'-7 3/4"	155.757°	1'-5 1/2"	9'-10 3/8"	5'-4 3/8"	7'-11 1/2"	9'-11 1/8"
EN83C	1'-14 1/2"	2'-9 3/8"	149.406°	5'-7 3/4"	155.732°	1'-5 1/4"	9'-10 1/2"	5'-4 5/8"	7'-11 7/8"	9'-11 3/8"
EN84C	1'-14 5/8"	2'-9 5/8"	149.618°	5'-7 3/4"	155.706°	1'-5 1/8"	9'-10 5/8"	5'-4 3/4"	8'-0 1/4"	9'-11 3/4"
EN85C	1'-14 7/8"	2'-9 7/8"	149.817°	5'-7 7/8"	155.683°	1'-5"	9'-10 3/4"	5'-4 7/8"	8'-0 5/8"	10'-0 1/8"
EN86C	1'-14 7/8"	2'-10"	150.006°	5'-8"	155.657°	1'-4 7/8"	9'-10 7/8"	5'-5"	8'-1"	10'-0 1/2"
EN87C	1'-14 7/8"	2'-10 1/4"	150.183°	5'-8"	155.629°	1'-4 3/4"	9'-11"	5'-5 1/8"	8'-1 1/4"	10'-0 7/8"
EN88C	1'-15"	2'-10 3/8"	150.349°	5'-8 1/8"	155.604°	1'-4 5/8"	9'-11 1/8"	5'-5 1/4"	8'-1 5/8"	10'-1 1/8"
EN89C	1'-15 1/8"	2'-10 1/2"	150.503°	5'-8 1/4"	155.577°	1'-4 1/2"	9'-11 1/4"	5'-5 3/8"	8'-2"	10'-1 1/2"
EN90C	1'-15 1/4"	2'-10 5/8"	150.648°	5'-8 1/4"	155.550°	1'-4 3/8"	9'-11 3/8"	5'-5 5/8"	8'-2 1/4"	10'-1 7/8"
EN91C	1'-15 3/8"	2'-10 7/8"	150.782°	5'-8 3/8"	155.523°	1'-4 1/4"	9'-11 1/2"	5'-5 3/4"	8'-2 5/8"	10'-2 1/4"
EN92C	1'-15 1/2"	2'-11"	150.907°	5'-8 1/2"	155.494°	1'-4 1/8"	9'-11 5/8"	5'-5 7/8"	8'-2 7/8"	10'-2 1/2"
EN93C	1'-15 5/8"	2'-11 1/8"	151.021°	5'-8 5/8"	155.468°	1'-4"	9'-11 3/4"	5'-6"	8'-3 1/4"	10'-2 7/8"
EN94C	1'-15 3/4"	2'-11 3/8"	151.126°	5'-8 7/8"	155.439°	1'-3 7/8"	9'-11 7/8"	5'-6 1/8"	8'-3 5/8"	10'-3 1/4"
EN95C	1'-15 7/8"	2'-11 1/4"	151.222°	5'-9"	155.409°	1'-3 3/4"	10'-0"	5'-6 3/8"	8'-4"	10'-3 3/4"
EN96C	1'-16"	2'-11 3/8"	151.308°	5'-9 1/8"	155.381°	1'-3 5/8"	10'-0 1/8"	5'-6 1/2"	8'-4 1/4"	10'-3 7/8"
EN97C	1'-16 1/8"	2'-11 1/2"	151.385°	5'-9 1/4"	155.353°	1'-3 1/2"	10'-0 1/4"	5'-6 5/8"	8'-4 5/8"	10'-4 1/4"
EN98C	1'-16 1/4"	2'-11 5/8"	151.454°	5'-9 1/2"	155.323°	1'-3 3/8"	10'-0 3/8"	5'-6 3/4"	8'-5"	10'-4 1/2"
EN99C	1'-16 3/8"	2'-11 5/8"	151.513°	5'-9 5/8"	155.293°	1'-3 1/4"	10'-0 1/2"	5'-6 7/8"	8'-5 1/4"	10'-4 7/8"
EN100C	1'-16 1/2"	2'-11 3/4"	151.565°	5'-9 7/8"	155.261°	1'-3"	10'-0 5/8"	5'-7"	8'-5 5/8"	10'-5 1/8"
EN101C	1'-16 5/8"	2'-11 3/4"	151.606°	5'-10 1/8"	155.233°	1'-2 7/8"	10'-0 3/4"	5'-7 1/4"	8'-5 7/8"	10'-5 1/2"
EN102C	1'-16 3/4"	2'-11 3/4"	151.640°	5'-10 1/4"	155.202°	1'-2 3/4"	10'-0 7/8"	5'-7 3/8"	8'-6 1/4"	10'-5 7/8"
EN103C	1'-16 7/8"	2'-11 7/8"	151.690°	5'-10 1/2"	155.169°	1'-2 5/8"	10'-1"	5'-7 3/4"	8'-6 5/8"	10'-6 1/4"
EN104C	1'-17"	2'-11 7/8"	151.682°	5'-10 3/4"	155.140°	1'-2 5/8"	10'-1 1/8"	5'-7 7/8"	8'-6 7/8"	10'-6 1/2"
EN105C	1'-17 1/8"	2'-11 7/8"	151.690°	5'-11"	155.107°	1'-2 1/2"	10'-1 1/4"	5'-7 5/8"	8'-7 1/8"	
EN106C	1'-17 1/4"	2'-11 7/8"	151.690°	5'-11 1/4"	155.074°	1'-2 3/8"	10'-1 3/8"	5'-7 3/4"	8'-7 1/2"	
EN107C	1'-17 3/8"	2'-11 7/8"	151.681°	5'-11 1/2"	155.042°	1'-2 1/4"	10'-1 1/2"	5'-7 7/8"	8'-7 3/4"	
EN108C	1'-17 1/2"	2'-11 7/8"	151.665°	5'-11 3/4"	155.008°	1'-2 1/8"	10'-1 5/8"	5'-8"	8'-8 1/8"	
EN109C	1'-17 5/8"	2'-11 3/4"	151.639°	6'-0"	154.975°	1'-2"	10'-1 3/4"	5'-8 1/8"	8'-8 3/8"	
EN110C	1'-17 3/4"	2'-11 3/4"	151.605°	6'-0 3/8"	154.940°	1'-1 7/8"	10'-1 7/8"	5'-8 1/8"	8'-8 3/4"	
EN111C	1'-17 7/8"	2'-11 3/4"	151.563°	6'-0 5/8"	154.905°	1'-1 3/4"	10'-2"	5'-8 1/4"	8'-9"	
EN112C	1'-18"	2'-11 5/8"	151.512°	6'-0 7/8"	154.871°	1'-1 5/8"	10'-2 1/8"	5'-8 3/8"	8'-9 1/4"	
EN113C	1'-18 1/8"	2'-11 5/8"	151.451°	6'-1 1/4"	154.837°	1'-1 1/2"	10'-2 1/4"	5'-8 1/2"	8'-9 5/8"	
EN114C	1'-18 1/4"	2'-11 5/8"	151.383°	6'-1 5/8"	154.802°	1'-1 3/8"	10'-2 3/8"	5'-8 5/8"	8'-9 7/8"	
EN115C	1'-18 3/8"	2'-11 3/8"	151.306°	6'-1 7/8"	154.765°	1'-1 1/4"	10'-2 1/2"	5'-8 3/4"	8'-10 1/4"	
EN116C	1'-18 1/2"	2'-11 1/4"	151.220°	6'-2 1/4"	154.729°	1'-1 1/8"	10'-2 5/8"	5'-8 3/4"	8'-10 1/2"	
EN117C	1'-18 5/8"	2'-11 1/4"	151.123°	6'-2 5/8"	154.691°	1'-1"	10'-2 7/8"	5'-8 7/8"	8'-10 7/8"	
EN118C	1'-18 3/4"	2'-11 1/8"	151.018°	6'-3"	154.654°	1'-0 7/8"	10'-3"	5'-9"	8'-11 1/8"	
EN119C	1'-18 7/8"	2'-11"	150.903°	6'-3 3/8"	154.618°	1'-0 3/4"	10'-3 1/8"	5'-9 1/8"	8'-11 3/8"	
EN120C	1'-19"	2'-10 7/8"	150.780°	6'-3 3/4"	154.580°	1'-0 5/8"	10'-3 1/4"	5'-9 1/4"	8'-11 3/4"	
EN121C	1'-19 1/8"	2'-10 5/8"	150.644°	6'-4 1/8"	154.542°	1'-0 5/8"	10'-3 3/8"	5'-9 3/8"	8'-11 7/8"	
EN122C	1'-19 1/4"	2'-10 1/2"	150.500°	6'-4 1/2"	154.501°	1'-0 1/2"	10'-3 1/2"	5'-9 1/2"	9'-0 1/4"	
EN123C	1'-19 3/8"	2'-10 3/8"	150.346°	6'-4 7/8"	154.462°	1'-0 3/8"	10'-3 5/8"	5'-9 1/2"	9'-0 1/2"	
EN124C	1'-19 1/2"	2'-10 1/8"	150.181°	6'-5 1/4"	154.422°	1'-0 1/4"	10'-3 3/4"	5'-9 5/8"	9'-0 3/4"	
EN125C	1'-19 5/8"	2'-10"	150.004°	6'-5 3/4"	154.383°	1'-0 1/8"	10'-3 7/8"	5'-9 3/4"	9'-1"	
EN126C	1'-19 3/4"	2'-9 3/4"	149.815°	6'-6 1/8"	154.342°	1'-0"	10'-4"	5'-9 7/8"	9'-1 3/8"	
EN127C	1'-19 7/8"	2'-9 5/8"	149.616°	6'-6 5/8"	154.301°	0'-11 7/8"	10'-4 1/8"	5'-10"	9'-1 5/8"	
EN128C	1'-20"	2'-9 3/8"	149.405°	6'-7"	154.259°	0'-11 3/4"	10'-4 1/4"	5'-10 1/8"	9'-1 7/8"	
EN129C	1'-10 1/8"	2'-9 1/8"	149.180°	6'-7 1/2"	154.217°	0'-11 3/4"	9'-7 3/4"	4'-11 3/8"	6'-10 1/8"	9'-2 1/8"
EN130C	1'-10 1/4"	2'-9"	148.943°	6'-8"	154.174°	0'-11 5/8"	9'-7 3/4"	4'-11 1/2"	6'-10 1/4"	9'-2 3/8"
EN131C	1'-10 3/8"	2'-8 3/4"	148.692°	6'-8 1/2"	154.129°	0'-11 1/2"	9'-7 3/4"	4'-11 5/8"	6'-10 3/8"	9'-2 5/8"
EN132C	1'-10 1/2"	2'-8 1/2"	148.428°	6'-9"	154.087°	0'-11 3/8"	9'-7 3/4"	4'-11 3/4"	6'-10 1/2"	9'-3"
EN133C	1'-10 5/8"	2'-8 1/4"	148.150°	6'-9 3/8"	154.040°	0'-11 1/4"	9'-7 7/8"	4'-11 7/8"	6'-10 5/8"	9'-3 1/4"
EN134C	1'-10 3/4"	2'-8"	147.856°	6'-10"	153.995°	0'-11 1/8"	9'-7 7/8"	5'-0"	6'-10 3/4"	9'-3 1/2"
EN135C	1'-10 7/8"	2'-7 5/8"	147.546°	6'-10 1/2"	153.950°	0'-11 1/8"	9'-7 5/8"	5'-0 1/8"	6'-10 7/8"	9'-3 3/4"
EN136C	1'-11"	2'-7 3/8"	147.221°	6'-11"	153.905°	0'-11"	9'-7 5/8"	5'-0 1/8"	6'-11"	9'-4"
EN137C	1'-11 1/8"	2'-7 1/8"	146.879°	6'-11 1/2"	153.859°	0'-10 7/8"	9'-7 5/8"	5'-0 1/4"	6'-11 1/8"	9'-4 1/4"
EN138C	1'-11 1/4"	2'-6 7/8"	146.518°	7'-0"	153.811°	0'-10 3/4"	9'-7 5/8"	5'-0 1/4"	6'-11 1/4"	9'-4 1/2"
EN139C	1'-11 1/4"	2'-6 1/2"	146.140°	7'-0 5/8"	153.767°	0'-10 5/8"	9'-7 5/8"	5'-0 3/4"	6'-11 1/4"	9'-4 3/4"
EN140C	1'-11 3/8"	2'-6 1/4"	145.742°	7'-1 1/8"	153.717°	0'-10 1/2"	9'-7 5/8"	5'-0 3/4"	6'-11 3/8"	9'-5"
EN141C	1'-11 1/2"	2'-5 7/8"	145.323°	7'-1 3/4"	153.668°	0'-10 1/2"	9'-7 5/8"	5'-0 7/8"	6'-11 1/2"	9'-5 1/4"
EN142C	1'-11 5/8"	2'-5 1/2"	144.882°	7'-2 1/4"	153.621°	0'-10 3/8"	9'-7 5/8"	5'-0 7/8"	6'-11 5/8"	9'-5 1/2"
EN143C	1'-11 3/4"	2'-5 1/4"	144.421°	7'-2 7/8"	153.568°	0'-10 1/4"	9'-7 5/8"	5'-1"	6'-11 3/4"	9'-5 3/4"
EN144C	1'-11 7/8"	2'-4 7/8"	143.936°	7'-3 1/2"	153.519°	0'-10 1/8"	9'-7 5/8"	5'-1 1/8"	6'-11 7/8"	9'-6"
EN145C	2'-0"	2'-4 1/2"	143.425°	7'-4 1/2"	153.467°	0'-10 1/8"	9'-7 5/8"	5'-1 1/4"	7'-0"	9'-6 1/4"
EN146C	2'-0 1/8"	2'-4 1/8"	142.889°	7'-4 3/4"	153.414°	0'-10"	9'-7 7/8"	5'-1 3/8"	7'-0"	9'-6 1/2"
EN147C	2'-0 1/4"	2'-3 7/8"	142.325°	7'-5 3/8"	153.361°	0'-9 7/8"	10'-7"	5'-1 1/2"	7'-0 1/8"	9'-6 3/4"
EN148C	2'-0 3/8"	2'-3 1/2"	141.732°	7'-6"	153.309°	0'-9 3/4"	10'-7 1/8"	5'-1 5/8"	7'-0 1/4"	9'-7"
EN149C	2'-0 1/2"	2'-3 1/8"	141.108°	7'-6 5/8"	153.255°	0'-9 3/4"	10'-7 3/8"	5'-1 3/4"	7'-0 3/4"	9'-7 1/4"
EN150C	2'-0 5/8"	2'-2 3/4"	140.452°	7'-7 1/4"	153.202°	0'-9 5/8"	10'-7 1/2"	5'-1 7/8"	7'-0 3/4"	9'-7 1/2"
EN151C	2'-0 3/4"	2'-2 3/8"	139.761°	7'-7 7/8"	153.147°	0'-9 1/2"	10'-7 3/4"	5'-2"	7'-0 7/8"	9'-7 3/4"
EN152C	2'-0 7/8"	2'-1 7/8"	139.035°	7'-8 1/2"	153.092°	0'-9 3/8"	10'-7 7/8"	5'-2 1/8"	7'-1 3/8"	9'-8"
EN153C	2'-1"	2'-1 1/2"	138.271°	7'-9 1/4"	153.035°	0'-9 3/8"	10'-8 1/8"	5'-2 3/8"	7'-1 3/8"	9'-8 1/4"
EN154C	2'-1 1/8"	2'-1 1/8"	137.466°	7'-9 7/8"	152.979°	0'-9 1/4"	10'-8 1/4"	5'-2 1/2"	7'-1 3/4"	9'-8 1/2"
EN155C	2'-1 1/4"	2'-0 3/4"	136.618°	7'-10 5/8"	152.921°	0'-9 1/8"	10'-8 1/2"	5'-2 5/8"	6'-1"	9'-8 5/8"
EN156C	2'-1 3/8"	2'-0 3/8"	135.723°	7'-11 1/4"	152.863°	0'-9 1/8"	10'-8 3/4"	5'-2 7/8"	6'-1"	9'-8 7/8"
EN157C	2'-1 1/2"	2'-0"	134.783°	8'-0"	152.803°	0'-9"	10'-9"	5'-3"	6'-1 1/8"	9'-9 1/8"
EN158C	2'-1 5/8"	1'-11 1/2"	133.789°	8'-0 3/4"	152.744°	0'-8 7/8"	10'-9 1/8"	5'-3 1/8"	6'-1 1/4"	9'-9 1/4"
EN159C	2'-1 3/4"	1'-11 1/8"	132.742°	8'-1 1/2"	152.686°	0'-8 3/4"	10'-9 3/8"	5'-3 3/8"	6'-1 3/8"	9'-9 1/2"
EN160C	2'-1 7/8"	1'-10 3/4"	131.639°	8'-2 1/4"	152.626°	0'-8 3/4"	10'-9 5/8"	5'-3 1/2"	6'-1 1/2"	9'-9 3/4"
EN161C	2'-2"	1'-10 3/8"	130.473°	8'-3"	152.563°	0'-8 5/8"	10'-9 7/8"	5'-3 5/8"	6'-1 5/8"	9'-10"
EN162C	2'-2 1/8"	1'-10"	129.244°	8'-3 3/4"	152.501°	0'-8 1/2"	10'-10 1/4"	5'-3 7/8"	6'-1 5/8"	9'-10 1/8"
EN163C	2'-2 1/4"	1'-9 1/2"	127.947°	8'-4 1/2"	152.436°	0'-8 1/2"	10'-10 1/2"	5'-4"	6'-1 3/4"	9'-10 3/4"
EN164

EAST BRIDGE - SOUTH RUN

ID	P01V	L01	A01	L02	A02	L03	LTOT	ANV	H03V	H04V
ES1B	4'-1 1/4"	1'-2 5/8"	161.960°	3'-2 3/4"			4'-5 3/8"	4'-4 3/4"	5'-2 3/8"	7'-0 3/4"
ES2B	4'-1 1/8"	1'-3 3/8"	161.918°	3'-2 3/8"			4'-5 3/4"	4'-4 7/8"	5'-2 3/4"	7'-1 1/4"
ES3B	4'-1 1/8"	1'-4 1/8"	161.875°	3'-2 1/8"			4'-6 1/4"	4'-5"	5'-3 1/4"	7'-1 3/4"
ES4B	4'-1"	1'-5"	161.830°	3'-1 3/4"			4'-6 3/4"	4'-5 1/8"	5'-3 3/4"	7'-2 1/4"
ES5B	4'-0 7/8"	1'-5 3/4"	161.784°	3'-1 1/2"			4'-7 1/4"	4'-5 1/4"	5'-4 1/4"	7'-2 3/4"
ES6B	4'-0 3/4"	1'-6 5/8"	161.735°	3'-1 1/8"			4'-7 3/4"	4'-5 3/8"	5'-4 3/4"	7'-3 1/4"
ES7B	4'-0 5/8"	1'-7 3/8"	161.685°	3'-0 3/4"			4'-8 1/4"	4'-5 1/2"	5'-5 1/4"	7'-3 5/8"
ES8B	4'-0 1/2"	1'-8 3/8"	161.632°	3'-0 1/2"			4'-8 7/8"	4'-5 3/4"	5'-5 5/8"	7'-4 1/8"
ES9B	4'-0 1/4"	1'-9 1/4"	161.577°	3'-0 1/4"			4'-9 1/2"	4'-5 7/8"	5'-6 1/8"	7'-4 5/8"
ES10B	4'-0"	1'-10 1/8"	161.521°	2'-11 7/8"			4'-10"	4'-6"	5'-6 5/8"	7'-5 1/8"
ES11B	3'-11 7/8"	1'-11 1/8"	161.462°	2'-11 1/2"			4'-10 5/8"	4'-6 1/8"	5'-7 1/8"	7'-5 1/2"
ES12B	3'-11 1/2"	2'-0 1/8"	161.401°	2'-11 1/4"			4'-11 3/8"	4'-6 1/4"	5'-7 1/2"	7'-6"
ES13B	3'-11 1/4"	2'-1 1/8"	161.339°	2'-10 7/8"			5'-0"	4'-6 3/8"	5'-8"	7'-6 1/2"
ES14B	3'-11"	2'-2 1/8"	161.273°	2'-10 5/8"			5'-0 3/4"	4'-6 1/2"	5'-8 1/2"	7'-7"
ES15B	3'-10 5/8"	2'-3 1/8"	161.205°	2'-10 1/4"			5'-1 3/8"	4'-6 5/8"	5'-9"	7'-7 3/8"
ES16B	3'-10 1/4"	2'-4 1/8"	161.135°	2'-9 7/8"			5'-2 1/8"	4'-6 3/4"	5'-9 3/8"	7'-7 7/8"
ES17B	3'-9 7/8"	2'-5 1/4"	161.062°	2'-9 5/8"			5'-2 7/8"	4'-7"	5'-9 7/8"	7'-8 3/8"
ES18B	3'-9 1/2"	2'-6 3/8"	160.987°	2'-9 1/4"			5'-3 5/8"	4'-7 1/8"	5'-10 3/8"	7'-8 3/4"
ES19B	3'-9 1/8"	2'-7 1/2"	160.909°	2'-9"			5'-4 1/2"	4'-7 1/4"	5'-10 3/4"	7'-9 1/4"
ES20B	3'-8 5/8"	2'-8 5/8"	160.828°	2'-8 5/8"			5'-5 1/4"	4'-7 3/8"	5'-11 1/4"	7'-9 3/4"
ES21B	3'-8 1/8"	2'-9 7/8"	160.744°	2'-8 1/4"			5'-6 1/8"	4'-7 1/2"	5'-11 5/8"	7'-10 1/8"
ES22B	3'-7 1/2"	2'-11 1/8"	160.657°	2'-8"			5'-7"	4'-7 5/8"	6'-0 1/8"	7'-10 5/8"
ES23B	3'-7 1/8"	3'-0 1/4"	160.568°	2'-7 5/8"			5'-7 7/8"	4'-7 3/4"	6'-0 5/8"	7'-11"
ES24B	3'-6 5/8"	3'-1 1/2"	160.475°	2'-7 1/4"			5'-8 3/4"	4'-8 1/8"	6'-1"	7'-11 1/2"
ES25B	3'-6"	3'-2 3/4"	160.379°	2'-7"			5'-9 3/4"	4'-8"	6'-1 1/2"	8'-0"
ES26B	3'-5 1/2"	3'-4 1/8"	160.278°	2'-6 5/8"			5'-10 3/4"	4'-8 1/8"	6'-1 7/8"	8'-0 3/8"
ES27B	3'-4 7/8"	3'-5 3/8"	160.173°	2'-6 1/4"			5'-11 5/8"	4'-8 3/8"	6'-2 3/8"	8'-0 7/8"
ES28B	3'-4 1/4"	3'-6 3/4"	160.068°	2'-5 7/8"			6'-0 5/8"	4'-8 1/2"	6'-2 3/4"	8'-1 1/4"
ES29B	3'-3 5/8"	3'-8 1/8"	159.957°	2'-5 5/8"			6'-1 5/8"	4'-8 5/8"	6'-3 1/4"	8'-1 3/4"
ES30B	3'-3 1/8"	3'-9 3/8"	159.842°	2'-5 3/4"			6'-2 3/4"	4'-8 3/4"	6'-3 5/8"	8'-2 1/8"
ES31B	3'-2 1/4"	3'-10 7/8"	159.723°	2'-4 7/8"			6'-3 3/4"	4'-8 7/8"	6'-4 1/8"	8'-2 5/8"
ES32B	3'-1 1/2"	4'-0 3/8"	159.599°	2'-4 1/2"			6'-4 7/8"	4'-9"	6'-4 1/2"	8'-3"
ES33B	3'-0 3/4"	4'-1 3/4"	159.471°	2'-4 1/4"			6'-6"	4'-9 1/8"	6'-5"	8'-3 1/2"
ES34B	3'-0"	4'-3 1/4"	159.339°	2'-3 7/8"			6'-7 1/8"	4'-9 1/4"	6'-5 3/8"	8'-3 7/8"
ES35B	2'-11 1/8"	4'-4 3/4"	159.201°	2'-3 1/2"			6'-8 1/4"	4'-9 3/8"	6'-5 7/8"	8'-4 3/8"
ES36B	2'-10 3/8"	4'-6 1/2"	159.059°	2'-3 1/8"			6'-9 1/2"	4'-9 1/2"	6'-6 1/4"	8'-4 3/4"
ES37B	2'-9 1/2"	4'-7 7/8"	158.911°	2'-2 3/4"			6'-10 5/8"	4'-9 3/4"	6'-6 3/4"	8'-5 1/8"
ES38B	2'-8 5/8"	4'-9 3/8"	158.757°	2'-2 1/2"			6'-11 7/8"	4'-9 7/8"	6'-7 1/8"	8'-5 5/8"
ES39B	2'-7 3/4"	4'-11"	158.598°	2'-2 1/8"			7'-1 1/8"	4'-10"	6'-7 1/2"	8'-6"
ES40B	2'-6 7/8"	5'-0 5/8"	158.433°	2'-1 3/4"			7'-2 3/8"	4'-10 1/8"	6'-8"	8'-6 1/2"
ES41B	2'-5 7/8"	5'-2 1/4"	158.261°	2'-1 3/8"			7'-3 5/8"	4'-10 1/4"	6'-8 3/8"	8'-6 7/8"
ES42B	2'-5"	5'-3 7/8"	158.084°	2'-1"			7'-5"	4'-10 3/8"	6'-8 3/4"	8'-7 3/8"
ES43B	2'-4"	5'-5 5/8"	157.899°	2'-0 5/8"			7'-6 1/4"	4'-10 1/2"	6'-9 1/4"	8'-7 3/4"
ES44B	2'-3"	5'-7 3/8"	157.708°	2'-0 3/8"			7'-7 5/8"	4'-10 5/8"	6'-9 5/8"	8'-8 1/8"
ES45B	2'-1 7/8"	5'-9 1/8"	157.507°	2'-0"			7'-9"	4'-10 3/4"	6'-10"	8'-8 1/2"
ES46B	2'-0 7/8"	5'-10 7/8"	157.299°	1'-11 5/8"			7'-10 1/2"	4'-10 7/8"	6'-10 3/8"	8'-9"
ES47C	1'-10 3/8"	1'-9 1/8"	157.084°	1'-11 1/4"	157.223°	1'-11 3/8"	4'-7 7/8"	4'-11 1/8"	6'-10 7/8"	8'-9 3/8"
ES48C	1'-10 1/2"	1'-9 1/2"	127.836°	5'-11 1/8"	157.208°	1'-11 1/4"	9'-7 7/8"	4'-11 1/4"	6'-11 1/4"	8'-9 3/4"
ES49C	1'-10 5/8"	1'-9 7/8"	129.144°	5'-10 7/8"	157.194°	1'-11"	9'-7 3/4"	4'-11 3/8"	6'-11 5/8"	8'-10 1/8"
ES50C	1'-10 3/4"	1'-10 5/8"	130.452°	5'-10 5/8"	157.180°	1'-10 7/8"	9'-7 3/4"	4'-11 5/8"	7'-0"	8'-10 5/8"
ES51C	1'-10 7/8"	1'-10 3/4"	131.560°	5'-10 3/8"	157.166°	1'-10 3/4"	9'-7 3/4"	4'-11 3/4"	7'-0 1/2"	8'-11"
ES52C	1'-11"	1'-11 1/8"	132.675°	5'-10 1/8"	157.151°	1'-10 5/8"	9'-7 3/4"	4'-11 7/8"	7'-0 7/8"	8'-11 3/8"
ES53C	1'-11 1/8"	1'-11 3/8"	133.730°	5'-9 7/8"	157.136°	1'-10 3/8"	9'-7 3/4"	5'-0"	7'-1 1/4"	8'-11 3/4"
ES54C	1'-11 1/4"	1'-11 7/8"	134.730°	5'-9 5/8"	157.121°	1'-10 1/4"	9'-7 7/8"	5'-0 1/4"	7'-1 5/8"	9'-0 1/8"
ES55C	1'-11 1/4"	2'-0 3/8"	135.678°	5'-9 1/2"	157.106°	1'-10 1/8"	9'-7 7/8"	5'-0 3/8"	7'-2"	9'-0 5/8"
ES56C	1'-11 3/8"	2'-0 7/8"	136.562°	5'-9 1/4"	157.090°	1'-9 7/8"	9'-7 7/8"	5'-0 1/2"	7'-2 1/2"	9'-1"
ES57C	1'-11 1/2"	2'-1 1/8"	137.433°	5'-9"	157.076°	1'-9 3/4"	9'-8"	5'-0 3/4"	7'-2 7/8"	9'-1 3/8"
ES58C	1'-11 5/8"	2'-1 1/2"	138.242°	5'-8 7/8"	157.060°	1'-9 5/8"	9'-8"	5'-0 7/8"	7'-3 1/4"	9'-1 3/4"
ES59C	1'-11 3/4"	2'-1 7/8"	139.041°	5'-8 5/8"	157.045°	1'-9 1/2"	9'-8 1/8"	5'-1"	7'-3 5/8"	9'-2 1/8"
ES60C	1'-11 7/8"	2'-2 1/4"	139.741°	5'-8 1/2"	157.027°	1'-9 1/4"	9'-8 1/8"	5'-1 1/8"	7'-4"	9'-2 1/2"
ES64C	1'-12 3/8"	2'-2 3/4"	140.316°	5'-8"	156.963°	1'-8 3/4"	9'-8 1/4"	5'-1 5/8"	7'-4 3/8"	9'-2 7/8"
ES65C	1'-12 1/2"	2'-3 1/8"	142.881°	5'-7 7/8"	156.945°	1'-8 1/2"	9'-8 5/8"	5'-1 3/4"	7'-4 7/8"	9'-3 1/2"
ES66C	1'-12 5/8"	2'-4 1/2"	143.419°	5'-7 3/4"	156.927°	1'-8 3/8"	9'-8 5/8"	5'-1 7/8"	7'-5"	9'-4 7/8"
ES67C	1'-12 3/4"	2'-5 3/8"	143.930°	5'-7 5/8"	156.911°	1'-8 1/4"	9'-8 3/4"	5'-2 1/8"	7'-5 3/8"	9'-5 1/4"
ES68C	1'-12 7/8"	2'-5 1/4"	144.417°	5'-7 5/8"	156.894°	1'-8 1/8"	9'-8 7/8"	5'-2 1/4"	7'-7"	9'-5 5/8"
ES69C	1'-13"	2'-5 1/2"	144.880°	5'-7 1/2"	156.876°	1'-7 7/8"	9'-9"	5'-2 3/8"	7'-7 3/8"	9'-6"
ES70C	1'-13 1/8"	2'-5 7/8"	145.321°	5'-7 1/2"	156.858°	1'-7 3/4"	9'-9 1/8"	5'-2 1/2"	7'-7 3/4"	9'-6 3/8"
ES71C	1'-13 1/4"	2'-6 1/4"	145.740°	5'-7 3/8"	156.841°	1'-7 5/8"	9'-9 1/4"	5'-2 5/8"	7'-8 1/8"	9'-6 3/4"
ES72C	1'-13 3/8"	2'-6 1/2"	146.139°	5'-7 3/8"	156.823°	1'-7 1/2"	9'-9 3/8"	5'-2 3/4"	7'-8 1/2"	9'-7 1/8"
ES73C	1'-13 1/2"	2'-6 7/8"	146.519°	5'-7 1/4"	156.802°	1'-7 3/8"	9'-9 1/2"	5'-2 7/8"	7'-8 7/8"	9'-7 1/2"
ES74C	1'-13 5/8"	2'-7 1/8"	146.878°	5'-7 1/4"	156.785°	1'-7 1/4"	9'-9 1/2"	5'-3"	7'-9 1/4"	9'-7 7/8"
ES75C	1'-13 3/4"	2'-7 3/8"	147.221°	5'-7 1/4"	156.766°	1'-7"	9'-9 5/8"	5'-3 1/8"	7'-9 5/8"	9'-8 1/4"
ES76C	1'-13 3/4"	2'-7 5/8"	147.540°	5'-7 1/4"	156.747°	1'-6 7/8"	9'-9 3/4"	5'-3 1/4"	7'-9 7/8"	9'-8 5/8"
ES77C	1'-13 7/8"	2'-8"	147.855°	5'-7 1/4"	156.728°	1'-6 3/4"	9'-9 7/8"	5'-3 3/8"	7'-10 1/4"	9'-8 7/8"
ES78C	1'-14"	2'-8 1/4"	148.149°	5'-7 1/4"	156.707°	1'-6 5/8"	9'-10"	5'-3 5/8"	7'-10 5/8"	9'-9 1/4"
ES79C	1'-14 1/8"	2'-8 1/2"	148.427°	5'-7 1/4"	156.688°	1'-6 1/2"	9'-10 1/8"	5'-3 3/4"	7'-11"	9'-9 5/8"
ES80C	1'-14 1/4"	2'-8 3/4"	148.690°	5'-7 1/4"	156.668°	1'-6 3/8"	9'-10 1/4"	5'-3 7/8"	7'-11 3/8"	9'-10"
ES81C	1'-14 3/8"	2'-9"	148.941°	5'-7 1/4"	156.648°	1'-6 1/4"	9'-10 3/8"	5'-4"	7'-11 3/4"	9'-10 3/8"
ES82C	1'-14 1/2"	2'-9 1/8"	149.177°	5'-7 1/4"	156.628°	1'-6"	9'-10 1/2"	5'-4 1/8"	8'-0"	9'-10 3/4"
ES83C	1'-14 5/8"	2'-9 3/8"	149.400°	5'-7 3/8"	156.606°	1'-5 7/8"	9'-10 5/8"	5'-4 1/4"	8'-0 3/8"	9'-11 1/8"
ES84C	1'-14 3/4"	2'-9 5/8"	149.612°	5'-7 3/8"	156.586°	1'-5 3/4"	9'-10 3/4"	5'-4 3/8"	8'-0 3/4"	9'-11 1/2"
ES85C	1'-14 7/8"	2'-9 3/4"	149.810°	5'-7 1/2"	156.564°	1'-5 5/8"	9'-10 7/8"	5'-4 1/2"	8'-1 1/8"	9'-11 3/4"
ES86C	1'-15"	2'-10"	149.998°	5'-7 1/2"	156.544°	1'-5 1/2"	9'-11"	5'-4 5/8"	8'-1 5/8"	10'-0 1/8"
ES87C	1'-15 1/8"	2'-10 1/8"	150.174°	5'-7 5/8"	156.521°	1'-5 3/8"	9'-11 1/8"	5'-4 3/4"	8'-1 3/4"	10'-0 1/2"
ES88C	1'-15 1/4"	2'-10 3/8"	150.338°	5'-7 3/4"	156.499°	1'-5 1/4"	9'-11 1/4"	5'-4 7/8"	8'-2 1/8"	10'-0 7/8"
ES89C	1'-15 3/8"	2'-10 5/8"	150.492°	5'-7 7/8"	156.477°	1'-5 1/8"	9'-11 1/2"	5'-5"	8'-2 1/2"	10'-1 3/8"
ES90C	1'-15 1/2"	2'-10 5/8"	150.634°	5'-8"	156.454°	1'-5"	9'-11 5/8"	5'-5 1/4"	8'-2 3/4"	10'-1 1/2"
ES91C	1'-15 5/8"	2'-10 3/4"	150.768°	5'-8 1/8"	156.432°	1'-4 3/4"	9'-11 3/4"	5'-5 3/8"	8'-3 1/8"	10'-1 7/8"
ES92C	1'-15 3/4"	2'-11"	150.891°	5'-8 1/4"	156.409°	1'-4 5/8"	9'-11 7/8"	5'-5 1/2"	8'-3 1/2"	10'-2 1/8"
ES93C	1'-15 7/8"	2'-11 1/8"	151.005°	5'-8 3/8"	156.384°	1'-4 1/2"	10'-0"	5'-5 5/8"	8'-3 3/4"	10'-2 1/2"
ES94C	1'-16"	2'-11 1/4"	151.109°	5'-8 1/2"	156.362°	1'-4 3/8"	10'-0 1/8"	5'-5 3/4"	8'-4 1/8"	10'-2 7/8"
ES95C	1'-16 1/8"	2'-11 1/4"	151.204°	5'-8 5/8"	156.338°	1'-4 1/4"	10'-0 1/4"	5'-5 7/8"	8'-4 3/8"	10'-3 1/8"
ES96C	1'-16 1/8"	2'-11 3/8"	151.289°	5'-8 7/8"	156.315°	1'-4 1/8"	10'-0 3/8"	5'-6"	8'-4 3/4"	10'-3 1/2"
ES97C	1'-16 1/4"	2'-11 3/8"	151.365°	5'-9"	156.289°	1'-4"	10'-0 1/2"	5'-6 1/8"	8'-5 1/8"	10'-3 7/8"
ES98C	1'-16 3/8"	2'-11 1/2"	151.433°	5'-9 1/8"	156.264°	1'-3 7/8"	10'-0 5/8"	5'-6 1/4"	8'-5 1/2"	10'-4 1/8"
ES99C	1'-16 1/2"	2'-11 5/8"	151.492°	5'-9 3/8"	156.239°	1'-3 3/4"	10'-0 3/4"	5'-6 3/8"	8'-5 3/4"	10'-4 1/2"
ES100C	1'-16 5/8"	2'-11 5/8"	151.542°	5'-9 5/8"	156.215°	1'-3 5/8"	10'-0 7/8"	5'-6 1/2"	8'-6"	10'-4 7/8"
ES101C	1'-16 3/4"	2'-11 3/4"	151.583°	5'-9 3/4"	156.189°	1'-3 1/2"	10'-1"	5'-6 5/8"	8'-6 3/8"	10'-5 1/8"
ES102C	1'-16 7/8"	2'-11 3/4"	151.616°	5'-10"	156.162°	1'-3 3/8"	10'-1 1/8"	5'-6 7/8"	8'-6 5/8"	10'-5 1/2"
ES103C	1'-17"	2'-11 7/8"	151.640°	5'-10 1/4"	156.136°	1'-3 1/4"	10'-1 1/4"	5'-7"	8'-7"	10'-5 3/4"
ES104C	1'-17 1/8"	2'-11 3/4"	151.655°	5'-10 1/2"	156.111°	1'-3 1/8"	10'-1 3/8"	5'-7 1/8"	8'-7 1/4"	10'-6 1/8"
ES105C	1'-17 1/4"	2'-11 7/8"	151.662°	5'-10 3/4"	156.084°	1'-3"	10'-1 1/2"	5'-7 1/4"	8'-7 5/8"	
ES106C	1'-17 3/8"	2'-11 7/8"	151.661°	5'-11"	156.057°	1'-2 7/8"	10'-1 5/8"	5'-7 3/8"	8'-7 7/8"	
ES107C	1'-17 5/8"	2'-11 3/4"	151.651°	5'-11 1/4"	156.028°	1'-2 3/4"	10'-1 3/4"	5'-7 1/2"	8'-8 1/4"	
ES108C	1'-17 5/8"	2'-11 3/4"	151.634°	5'-11 1/2"	156.001°	1'-2 5/8"	10'-1 7/8"	5'-7 5/8"	8'-8 1/2"	
ES109C	1'-17 3/4"	2'-11 3/4"	151.608°	5'-11 3/4"	155.972°	1'-2 1/2"	10'-2"	5'-7 3/4"	8'-8 7/8"	
ES110C	1'-17 7/8"	2'-11 3/4"	151.572°	6'-0 1/8"	155.945°	1'-2 3/8"	10'-2 1/4"	5'-7 7/8"	8'-9 1/8"	
ES111C	1'-18"	2'-11 3/4"	151.529°	6'-0 3/8"	155.916°	1'-2 1/4"	10'-2 3/8"	5'-8"	8'-9 3/8"	
ES112C	1'-18 1/8"	2'-11 5/8"	151.475°	6'-0 3/4"	155.887°	1'-2 1/8"	10'-2 1/2"	5'-8 1/8"	8'-9 3/4"	
ES113C	1'-18 1/4"	2'-11 1/2"	151.414°	6'-1"	155.857°	1'-2"	10'-2 5/8"	5'-8 3/8"	8'-10"	
ES114C	1'-18 3/8"	2'-11 1/2"	151.345°	6'-1 3/8"	155.825°	1'-1 7/8"	10'-2 3/4"	5'-8 1/2"	8'-10 3/8"	
ES115C	1'-18 1/2"	2'-11 3/8"	151.266°	6'-1 3/4"	155.797°	1'-1 3/4"	10'-2 7/8"	5'-8 5/8"	8'-10 5/8"	
ES116C	1'-18 1/2"	2'-11 1/4"	151.177°	6'-2"	155.767°	1'-1 5/8"	10'-3"	5'-8 3/4"	8'-10 7/8"	
ES117C	1'-18 5/8"	2'-11 1/8"	151.080°	6'-2 3/8"	155.733°	1'-1 1/2"	10'-3 1/8"	5'-8 7/8"	8'-11 1/8"	
ES118C	1'-18 3/4"	2'-11"	150.974°	6'-2 3/4"	155.702°	1'-1 3/8"	10'-3 1/4"	5'-9"	8'-11 1/2"	
ES119C	1'-18 7/8"	2'-10 7/8"	150.858°	6'-3 1/8"	155.671°	1'-1 1/4"	10'-3 3/8"	5'-9"	8'-11 3/4"	
ES120C	1'-19"	2'-10 3/4"	150.732°	6'-3 1/2"	155.640°	1'-1 1/4"	10'-3 1/2"	5'-9 1/8"	9'-0"	
ES121C	1'-19 1/8"	2'-10 5/8"	150.596°	6'-3 7/8"	155.606°	1'-1 1/8"	10'-3 5/8"	5'-9 1/4"	9'-0 3/8"	
ES122C	1'-19 1/4"	2'-10 1/2"	150.450°	6'-4 3/8"	155.573"	1'-1"	10'-3 3/4"	5'-9 3/8"	9'-0 5/8"	
ES123C	1'-19 3/8"	2'-10 1/4"	150.294°	6'-4 3/4"	155.541"	1'-0 7/8"	10'-3 7/8"	5'-9 1/2"	9'-0 7/8"	
ES124C	1'-19 1/2"	2'-10 1/8"	150.127°	6'-5 1/8"	155.505"	1'-0 3/4"	10'-4"	5'-9 5/8"	9'-1 1/8"	
ES125C	1'-19 5/8"	2'-10"	149.948°	6'-5 5/8"	155.472"	1'-0 5/8"	10'-4 1/8"	5'-9 5/8"	9'-1 1/2"	
ES126C	1'-19 3/4"	2'-9 3/4"	149.758°	6'-6"	155.438"	1'-0 1/2"	10'-4 1/4"	5'-9 3/4"	9'-1 3/4"	
ES127C	1'-19 7/8"	2'-9 1/2"	149.557°	6'-6 1/2"	155.402"	1'-0 3/8"	10'-4 3/8"	5'-9 7/8"	9'-2"	
ES128C	1'-20"	2'-9 3/8"	149.344°	6'-7"	155.365"	1'-0 1/4"	10'-4 1/2"	5'-10"	9'-2 1/4"	
ES129C	1'-10 1/8"	2'-9 1/8"	149.117°	6'-7 3/8"	155.329"	1'-0 1/8"	10'-4 3/4"	5'-10 1/8"	9'-2 1/2"	
ES130C	1'-10 1/4"	2'-8 7/8"	148.878°	6'-7 7/8"	155.295°	1'-0"	10'-4 7/8"	5'-10 1/8"	9'-2 3/4"	
ES131C	1'-10"	2'-8 5/8"	148.626°	6'-8 3/8"	155.260°	1'-0"	10'-5"	5'-10 1/4"	9'-3"	
ES132C	1'-10 1/2"	2'-8 3/8"	148.359°	6'-8 7/8"	155.219°	0'-11 7/8"	10'-5 1/8"	5'-10 3/8"	9'-3 3/8"	
ES133C	1'-10 5/8"	2'-8 1/8"	148.078°	6'-9 3/8"	155.182°	0'-11 3/4"	10'-5 1/4"	5'-10 1/2"	9'-3 5/8"	
ES134C	1'-10 3/4"	2'-7 7/8"	147.780°	6'-9 7/8"	155.143°	0'-11 5/8"	10'-5 3/8"	5'-10 5/8"	9'-3 7/8"	
ES135C	1'-10 7/8"	2'-7 5/8"	147.468°	6'-10 3/8"	155.105°	0'-11 1/2"	10'-5 1/2"	5'-10 5/8"	9'-4 1/8"	
ES136C	1'-11"	2'-7 3/8"	147.140°	6'-10 7/8"	155.066°	0'-11 1/2"	10'-5 5/8"	5'-10 3/4"	9'-4 3/8"	
ES137C	1'-11"	2'-7"	146.795°	6'-11 1/2"	155.024°	0'-11 3/8"	10'-5 7/8"	5'-10 7/8"	9'-4 5/8"	
ES138C	1'-11 1/8"	2'-6 3/4"	146.431°	7'-0"	154.986°	0'-11 1/4"	10'-6"	5'-11"	9'-4 7/8"	
ES139C	1'-11 1/4"	2'-6 1/2"	146.049°	7'-0 1/2"	154.943°	0'-11 1/8"	10'-6 1/8"	5'-11 1/8"	9'-5 1/8"	
ES140C	1'-11 3/8"	2'-6 1/4"	145.648°	7'-1 1/8"	154.904°	0'-11"	10'-6 1/4"	5'-11 1/4"	9'-5 3/8"	
ES141C	1'-11 1/2"	2'-5 3/4"	145.226°	7'-1 3/4"	154.863°	0'-10 7/8"	10'-6 3/8"	5'-11 1/4"	9'-5 5/8"	
ES142C	1'-11 5/8"	2'-5 1/2"	144.783°	7'-2 1/4"	154.819°	0'-10 7/8"	10'-6 5/8"	5'-11 3/8"	9'-5 7/8"	
ES143C	1'-11 3/4"	2'-5 1/8"	144.317°	7'-2 7/8"	154.777°	0'-10 3/4"	10'-6 3/4"	5'-11 1/2"	9'-6 1/8"	
ES144C	1'-11 7/8"	2'-4 3/4"	143.826°	7'-3 1/2"	154.733°	0'-10 5/8"	10'-6 7/8"	5'-11 5/8"	9'-6 3/8"	
ES145C	2'-0"	2'-4 1/2"	143.311°	7'-4 1/2"	154.689°	0'-10 5/8"	10'-7"	5'-11 5/8"	9'-6 5/8"	
ES146C	2'-0 1/8"	2'-4 1/8"	142.771°	7'-4 3/4"	154.647°	0'-10 3/8"	10'-7 1/4"	5'-11 3/4"	9'-6 7/8"	
ES147C	2'-0 1/4"	2'-3 3/4"	142.202°	7'-5 3/8"	154.602°	0'-10 3/8"	10'-7 1/8"	5'-11 7/8"	9'-7 1/8"	
ES148C	2'-0 3/8"	2'-3 3/8"	141.603°	7'-6"	154.555°	0'-10 1/4"	10'-7 5/8"	6'-0"	9'-7 3/8"	
ES149C	2'-0 1/2"	2'-3"	140.975°	7'-6 5/8"	154.509°	0'-10 1/8"	10'-7 3/4"	6'-0 1/8"	9'-7 1/2"	
ES150C	2'-0 5/8"	2'-2 5/8"	140.313°	7'-7 1/4"	154.461°	0'-10"	10'-7 7/8"	6'-0 1/8"	9'-7 3/4"	
ES151C	2'-0 3/4"	2'-2 1/4"	139.617°	7'-7 7/8"	154.413°	0'-10"	10'-8 1/8"	6'-0 1/4"	9'-8"	
ES152C	2'-0 7/8"	2'-1 7/8"	138.883°	7'-8 5/8"	154.367°	0'-9 7/8"	10'-8 1/4"	6'-0 3/8"	9'-8 1/4"	
ES153C	2'-1"	2'-1 1/2"	138.113°	7'-9 1/4"	154.318°	0'-9 3/4"	10'-8 1/2"	6'-0 1/2"	9'-8 1/2"	
ES154C	2'-1 1/8"	2'-1 1/8"	137.299°	7'-10"	154.268°	0'-9 5/8"	10'-8 3/4"	6'-0 5/8"	9'-8 3/4"	
ES155C	2'-1 1/4"	2'-0 5/8"	136.445°	7'-10 5/8"	154.218°	0'-9 5/8"	10'-8 7/8"	6'-0 5/8"	9'-8 7/8"	
ES156C	2'-1 3/8"	2'-0 1/4"	135.541°	7'-11 3/8"	154.168°	0'-9 1/2"	10'-9 1/8"	6'-0 3/4"	9'-9 1/8"	
ES157C	2'-1 1/2"	1'-11 7/8"	134.589°	8'-0 1/8"	154.120°	0'-9 3/8"	10'-9 1/4"	6'-0 7/8"	9'-9 3/8"	
ES158C	2'-1 1/2"	1'-11 1/2"	133.588°	8'-0 7/8"	154.070°	0'-9 1/4"	10'-9 5/8"	6'-1"	9'-9 5/8"	
ES159C	2'-1 5/8"	1'-11 1/8"	132.530°	8'-1 1/2"	154.017°	0'-9 1/4"	10'-9 7/8"	6'-1 1/8"	9'-9 7/8"	
ES160C	2'-1 3/4"	1'-10 5/8"	131.417°	8'-2 1/4"	153.962°	0'-9 1/8"	10'-10 1/8"	6'-1 1/8"	9'-10"	
ES161C	2'-1 7/8"	1'-10 1/4"	130.241°	8'-3"	153.911°	0'-9"	10'-10 3/8"	6'-1 1/4"	9'-10 1/4"	
ES162C	2'-2"	1'-9 7/8"	129.000°	8'-3 3/4"	153.858°	0'-9"	10'-10 5/8"	6'-1 3/8"	9'-10 1/2"	
ES163C	2'-2 1/8"	1'-9 1/2"	127.692°	8'-4 5/8"	153.798°	0'-8 7/8"	10'-10 7/8"	6'-1 1/2"	9'-10 5/8"	
ES164C	2'-2 1/4"	1'-9 1/2"	127.755°	8'-4 3/4"	153.747°	0'-8 3/4"	10'-11"	6'-1 5/8"	9'-10 7/8"	
ES165C	2'-2 1/4"	1'-9 1/4"	128.740°	8'-4 3/8"	153.690°	0'-8 3/4"	10'-11"	6'-1 5/8"	9'-11 1/8"	
ES166C	2'-2 1/4"	1'-10 1/8"	129.692°	8'-4 3/8"	153.630°	0'-8 5/8"	10'-11"	6'-1 3/4"	9'-11 1/4"	
ES167C	2'-2 1/4"	1'-10 3/8"	130.606°	8'-4 1/8"	153.575°	0'-8 1/2"	10'-11"	6'-1 7/8"	9'-11 1/2"	
ES168C	2'-2 1/4"	1'-10 3/4"	131.482°	8'-3 7/8"	153.517°	0'-8 1/2"	10'-11"	6'-1 7/8"	9'-11 3/4"	
ES169C	2'-2 1/4"	1'-11"	132.349°	8'-3 5/8"	153.460°	0'-8 3/8"	10'-11"	6'-2"	9'-11 7/8"	

EAST BRIDGE - SOUTH RUN

| ID | P01V | L01 | A01 | L02 | A02 | L03 | LTOT | ANV | H03V | H04V |
|---|---|---

EAST BRIDGE - MIDDLE RUN

ID	P01V	L01	A01	L02	A02	L03	LTOT	ANV	H03V	H04V
EM1A	1'-0"	0'-4 1/8"					0'-4 1/8"	1'-5"	1'-2 5/8"	
EM2A	1'-0 1/4"	0'-4 5/8"					0'-4 5/8"	1'-5 1/4"	1'-3 1/8"	
EM3A	1'-0 3/8"	0'-5 1/4"					0'-5 1/4"	1'-5 3/8"	1'-3 5/8"	
EM4A	1'-0 1/2"	0'-5 7/8"					0'-5 7/8"	1'-5 1/2"	1'-4 1/8"	
EM5A	1'-0 5/8"	0'-6 3/8"					0'-6 3/8"	1'-5 5/8"	1'-4 1/2"	
EM6A	1'-0 7/8"	0'-7"					0'-7"	1'-5 7/8"	1'-5"	
EM7A	1'-1"	0'-7 1/2"					0'-7 1/2"	1'-6"	1'-5 1/2"	
EM8A	1'-1 1/8"	0'-8 1/8"					0'-8 1/8"	1'-6 1/8"	1'-6"	
EM9A	1'-1 3/8"	0'-8 5/8"					0'-8 5/8"	1'-6 3/8"	1'-6 1/2"	
EM10A	1'-1 1/2"	0'-9 1/4"					0'-9 1/4"	1'-6 1/2"	1'-7"	
EM11A	1'-1 5/8"	0'-9 7/8"					0'-9 7/8"	1'-6 5/8"	1'-7 3/8"	
EM12A	1'-1 3/4"	0'-10 3/8"					0'-10 3/8"	1'-6 3/4"	1'-7 7/8"	
EM13A	1'-2"	0'-11"					0'-11"	1'-7"	1'-8 3/8"	
EM14A	1'-2 1/8"	0'-11 1/2"					0'-11 1/2"	1'-7 1/8"	1'-8 7/8"	
EM15A	1'-2 1/4"	1'-0 1/8"					1'-0 1/8"	1'-7 1/4"	1'-9 1/4"	
EM16A	1'-2 1/2"	1'-0 5/8"					1'-0 5/8"	1'-7 1/2"	1'-9 3/4"	
EM17A	1'-2 5/8"	1'-1 1/4"					1'-1 1/4"	1'-7 5/8"	1'-10 1/4"	
EM18A	1'-2 3/4"	1'-1 3/4"					1'-1 3/4"	1'-7 3/4"	1'-10 5/8"	
EM19A	1'-2 7/8"	1'-2 3/8"					1'-2 3/8"	1'-7 7/8"	1'-11 1/8"	
EM20A	1'-3 1/8"	1'-3"					1'-3"	1'-8 1/8"	1'-11 5/8"	
EM21A	1'-3 1/4"	1'-3 1/2"					1'-3 1/2"	1'-8 1/4"	2'-0"	
EM22A	1'-3 3/8"	1'-4 1/8"					1'-4 1/8"	1'-8 3/8"	2'-0 1/2"	
EM23A	1'-3 5/8"	1'-4 5/8"					1'-4 5/8"	1'-8 5/8"	2'-1"	
EM24A	1'-3 3/4"	1'-5 1/4"					1'-5 1/4"	1'-8 3/4"	2'-1 3/8"	
EM25A	1'-3 7/8"	1'-5 3/4"					1'-5 3/4"	1'-8 7/8"	2'-1 7/8"	
EM26A	1'-4"	1'-6 3/8"					1'-6 3/8"	1'-9"	2'-2 1/4"	
EM27A	1'-4 1/4"	1'-7"					1'-7"	1'-9 1/4"	2'-2 3/4"	
EM28A	1'-4 3/8"	1'-7 1/2"					1'-7 1/2"	1'-9 3/8"	2'-3 1/4"	
EM29A	1'-4 1/2"	1'-8 1/8"					1'-8 1/8"	1'-9 1/2"	2'-3 5/8"	
EM30A	1'-4 3/4"	1'-8 5/8"					1'-8 5/8"	1'-9 3/4"	2'-4 1/8"	
EM31A	1'-4 7/8"	1'-9 1/4"					1'-9 1/4"	1'-9 7/8"	2'-4 1/2"	
EM32A	1'-5"	1'-9 3/4"					1'-9 3/4"	1'-10"	2'-5"	
EM33A	1'-5 1/8"	1'-10 3/8"					1'-10 3/8"	1'-10 1/8"	2'-5 3/8"	
EM34A	1'-5 3/8"	1'-10 7/8"					1'-10 7/8"	1'-10 3/8"	2'-5 7/8"	
EM35A	1'-5 1/2"	1'-11 1/2"					1'-11 1/2"	1'-10 1/2"	2'-6 1/4"	
EM36A	1'-5 5/8"	2'-0 1/8"					2'-0 1/8"	1'-10 5/8"	2'-6 3/4"	
EM37A	1'-5 7/8"	2'-0 5/8"					2'-0 5/8"	1'-10 7/8"	2'-7 1/8"	
EM38A	1'-6"	2'-1 1/4"					2'-1 1/4"	1'-11"	2'-7 1/2"	
EM39A	1'-6 1/8"	2'-1 3/4"					2'-1 3/4"	1'-11 1/8"	2'-8"	
EM40A	1'-6 1/4"	2'-2 3/8"					2'-2 3/8"	1'-11 1/4"	2'-8 3/8"	
EM41A	1'-6 1/2"	2'-2 7/8"					2'-2 7/8"	1'-11 1/2"	2'-8 7/8"	
EM42A	1'-6 5/8"	2'-3 1/2"					2'-3 1/2"	1'-11 5/8"	2'-9 1/4"	
EM43A	1'-6 3/4"	2'-4"					2'-4"	1'-11 3/4"	2'-9 5/8"	
EM44A	1'-7"	2'-4 5/8"					2'-4 5/8"	2'-0"	2'-10 1/8"	
EM45A	1'-7 1/8"	2'-5 1/4"					2'-5 1/4"	2'-0 1/8"	2'-10 1/2"	
EM46A	1'-7 1/4"	2'-5 3/4"					2'-5 3/4"	2'-0 1/4"	2'-10 7/8"	
EM47A	1'-7 3/8"	2'-6 1/4"					2'-6 1/4"	2'-0 3/8"	2'-11 1/4"	
EM48A	1'-7 5/8"	2'-6 1/2"					2'-6 1/2"	2'-0 5/8"	2'-11 3/4"	
EM49A	1'-7 3/4"	2'-6 7/8"					2'-6 7/8"	2'-0 3/4"	3'-0 1/8"	
EM50A	1'-7 7/8"	2'-7 1/4"					2'-7 1/4"	2'-0 7/8"	3'-0 1/2"	
EM51A	1'-8"	2'-7 5/8"					2'-7 5/8"	2'-1"	3'-1"	
EM52A	1'-8 1/8"	2'-7 7/8"					2'-7 7/8"	2'-1 1/8"	3'-1 3/8"	
EM53A	1'-8 1/4"	2'-8 1/4"					2'-8 1/4"	2'-1 1/4"	3'-1 3/4"	
EM54A	1'-8 1/2"	2'-8 5/8"					2'-8 5/8"	2'-1 1/2"	3'-2 1/8"	
EM55A	1'-8 5/8"	2'-8 7/8"					2'-8 7/8"	2'-1 5/8"	3'-2 1/2"	
EM56A	1'-8 3/4"	2'-9 1/4"					2'-9 1/4"	2'-1 3/4"	3'-3"	
EM57A	1'-8 7/8"	2'-9 5/8"					2'-9 5/8"	2'-1 7/8"	3'-3 3/8"	
EM58A	1'-9"	2'-9 7/8"					2'-9 7/8"	2'-2"	3'-3 3/4"	
EM59A	1'-9 1/8"	2'-10 1/4"					2'-10 1/4"	2'-2 1/8"	3'-4 1/8"	
EM60A	1'-9 1/4"	2'-10 5/8"					2'-10 5/8"	2'-2 1/4"	3'-4 1/2"	
EM61A	1'-9 1/2"	2'-10 7/8"					2'-10 7/8"	2'-2 1/2"	3'-4 7/8"	
EM62A	1'-9 5/8"	2'-11 1/4"					2'-11 1/4"	2'-2 5/8"	3'-5 1/4"	
EM63A	1'-9 3/4"	2'-11 1/2"					2'-11 1/2"	2'-2 3/4"	3'-5 5/8"	
EM64A	1'-9 7/8"	2'-11 7/8"					2'-11 7/8"	2'-2 7/8"	3'-6"	
EM65A	1'-10"	3'-0 1/8"					3'-0 1/8"	2'-3"	3'-6 3/8"	
EM66A	1'-10 1/8"	3'-0 1/2"					3'-0 1/2"	2'-3 1/8"	3'-6 7/8"	
EM67A	1'-10 1/4"	3'-0 3/4"					3'-0 3/4"	2'-3 1/4"	3'-7 1/4"	
EM68A	1'-10 1/2"	3'-1 1/8"					3'-1 1/8"	2'-3 1/2"	3'-7 5/8"	
EM69A	1'-10 5/8"	3'-1 3/8"					3'-1 3/8"	2'-3 5/8"	3'-8"	
EM70A	1'-10 3/4"	3'-1 3/4"					3'-1 3/4"	2'-3 3/4"	3'-8 3/8"	
EM71A	1'-10 7/8"	3'-2"					3'-2"	2'-3 7/8"	3'-8 3/4"	
EM72A	1'-11"	3'-2 1/4"					3'-2 1/4"	2'-4"	3'-9"	
EM73A	1'-11 1/8"	3'-2 5/8"					3'-2 5/8"	2'-4 1/8"	3'-9 3/8"	
EM74A	1'-11 3/8"	3'-2 7/8"					3'-2 7/8"	2'-4 3/8"	3'-9 3/4"	
EM75A	1'-11 1/2"	3'-3 1/8"					3'-3 1/8"	2'-4 1/2"	3'-10 1/8"	
EM76A	1'-11 5/8"	3'-3 1/2"					3'-3 1/2"	2'-4 5/8"	3'-10 1/2"	
EM77A	1'-11 3/4"	3'-3 3/4"					3'-3 3/4"	2'-4 3/4"	3'-10 7/8"	
EM78A	1'-11 7/8"	3'-4"					3'-4"	2'-4 7/8"	3'-11 1/4"	
EM79A	2'-0"	3'-4 3/8"					3'-4 3/8"	2'-5"	3'-11 5/8"	
EM80A	2'-0 1/8"	3'-4 5/8"					3'-4 5/8"	2'-5 1/8"	4'-0"	
EM81A	2'-0 3/8"	3'-4 7/8"					3'-4 7/8"	2'-5 3/8"	4'-0 1/4"	
EM82A	2'-0 1/2"	3'-5 1/8"					3'-5 1/8"	2'-5 1/2"	4'-0 5/8"	
EM83A	2'-0 5/8"	3'-5 1/2"					3'-5 1/2"	2'-5 5/8"	4'-1"	
EM84A	2'-0 3/4"	3'-5 3/4"					3'-5 3/4"	2'-5 3/4"	4'-1 3/8"	
EM85A	2'-0 7/8"	3'-6"					3'-6"	2'-5 7/8"	4'-1 3/4"	
EM86A	2'-1"	3'-6 1/4"					3'-6 1/4"	2'-6"	4'-2"	
EM87A	2'-1 1/8"	3'-6 1/2"					3'-6 1/2"	2'-6 1/8"	4'-2 3/8"	
EM88A	2'-1 3/8"	3'-6 3/4"					3'-6 3/4"	2'-6 3/8"	4'-2 3/4"	
EM89A	2'-1 1/2"	3'-7 1/8"					3'-7 1/8"	2'-6 1/2"	4'-3 1/8"	
EM90A	2'-1 5/8"	3'-7 3/8"					3'-7 3/8"	2'-6 5/8"	4'-3 3/8"	
EM91A	2'-1 3/4"	3'-7 5/8"					3'-7 5/8"	2'-6 3/4"	4'-3 3/4"	
EM92A	2'-1 7/8"	3'-7 7/8"					3'-7 7/8"	2'-6 7/8"	4'-4 1/8"	
EM93A	2'-2"	3'-8 1/8"					3'-8 1/8"	2'-7"	4'-4 3/8"	
EM94A	2'-2 1/8"	3'-8 3/8"					3'-8 3/8"	2'-7 1/8"	4'-4 3/4"	
EM95A	2'-2 3/8"	3'-8 5/8"					3'-8 5/8"	2'-7 3/8"	4'-5 1/8"	
EM96A	2'-2 1/2"	3'-8 7/8"					3'-8 7/8"	2'-7 1/2"	4'-5 3/8"	
EM97A	2'-2 5/8"	3'-9 1/8"					3'-9 1/8"	2'-7 5/8"	4'-5 3/4"	
EM98A	2'-2 3/4"	3'-9 3/8"					3'-9 3/8"	2'-7 3/4"	4'-6 1/8"	
EM99A	2'-2 7/8"	3'-9 5/8"					3'-9 5/8"	2'-7 7/8"	4'-6 3/8"	
EM100A	2'-3"	3'-9 7/8"					3'-9 7/8"	2'-8"	4'-6 3/4"	
EM101A	2'-3 1/4"	3'-10 1/8"					3'-10 1/8"	2'-8 1/4"	4'-7"	
EM102A	2'-3 3/8"	3'-10 3/8"					3'-10 3/8"	2'-8 3/8"	4'-7 3/8"	
EM103A	2'-3 3/8"	3'-10 5/8"					3'-10 5/8"	2'-8 3/8"	4'-7 5/8"	
EM104A	2'-3 1/2"	3'-10 7/8"					3'-10 7/8"	2'-8 1/2"	4'-8"	
EM105A	2'-3 5/8"	3'-11 1/8"					3'-11 1/8"	2'-8 5/8"	4'-8 1/4"	
EM106A	2'-3 3/4"	3'-11 3/8"					3'-11 3/8"	2'-8 3/4"	4'-8 5/8"	
EM107A	2'-3 7/8"	3'-11 3/4"					3'-11 3/4"	2'-8 7/8"	4'-8 7/8"	
EM108A	2'-4"	4'-0"					4'-0"	2'-9"	4'-9 1/4"	
EM109A	2'-4"	4'-0 1/4"					4'-0 1/4"	2'-9"	4'-9 1/2"	
EM110A	2'-4 1/8"	4'-0 1/2"					4'-0 1/2"	2'-9 1/8"	4'-9 7/8"	
EM111A	2'-4 1/4"	4'-0 3/4"					4'-0 3/4"	2'-9 1/4"	4'-10 1/8"	
EM112A	2'-4 3/8"	4'-1"					4'-1"	2'-9 3/8"	4'-10 1/2"	
EM113A	2'-4 1/2"	4'-1 1/4"					4'-1 1/4"	2'-9 1/2"	4'-10 3/4"	
EM114A	2'-4 5/8"	4'-1 1/2"					4'-1 1/2"	2'-9 5/8"	4'-11"	
EM115A	2'-4 3/4"	4'-1 3/4"					4'-1 3/4"	2'-9 3/4"	4'-11 3/8"	
EM116A	2'-4 3/4"	4'-2"					4'-2"	2'-9 3/4"	4'-11 5/8"	
EM117A	2'-4 7/8"	4'-2 1/4"					4'-2 1/4"	2'-9 7/8"	4'-11 7/8"	
EM118A	2'-5"	4'-2 1/2"					4'-2 1/2"	2'-10"	5'-0 1/4"	
EM119A	2'-5 1/8"	4'-2 3/4"					4'-2 3/4"	2'-10 1/8"	5'-0 1/2"	
EM120A	2'-5 1/4"	4'-3"					4'-3"	2'-10 1/4"	5'-0 3/4"	
EM121A	2'-5 3/8"	4'-3 1/4"					4'-3 1/4"	2'-10 3/8"	5'-1 1/8"	
EM122A	2'-5 1/2"	4'-3 3/8"					4'-3 3/8"	2'-10 1/2"	5'-1 3/8"	
EM123A	2'-5 1/2"	4'-3 5/8"					4'-3 5/8"	2'-10 1/2"	5'-1 5/8"	
EM124A	2'-5 5/8"	4'-3 7/8"					4'-3 7/8"	2'-10 5/8"	5'-2"	
EM125A	2'-5 3/4"	4'-4 1/8"					4'-4 1/8"	2'-10 3/4"	5'-2 1/4"	
EM126A	2'-5 7/8"	4'-4 3/8"					4'-4 3/8"	2'-10 7/8"	5'-2 1/2"	
EM127A	2'-6"	4'-4 5/8"					4'-4 5/8"	2'-11"	5'-2 3/4"	
EM128A	2'-6 1/8"	4'-4 3/4"					4'-4 3/4"	2'-11 1/8"	5'-3"	
EM129A	2'-6 1/8"	4'-5"					4'-5"	2'-11 1/8"	5'-3 3/8"	
EM130A	2'-6 1/4"	4'-5 1/4"					4'-5 1/4"	2'-11 1/4"	5'-3 5/8"	
EM131A	2'-6 3/8"	4'-5 1/2"					4'-5 1/2"	2'-11 3/8"	5'-3 7/8"	
EM132A	2'-6 1/2"	4'-5 5/8"					4'-5 5/8"	2'-11 1/2"	5'-4 1/8"	
EM133A	2'-6 5/8"	4'-5 7/8"					4'-5 7/8"	2'-11 5/8"	5'-4 3/8"	
EM134A	2'-6 3/4"	4'-6 1/8"					4'-6 1/8"	2'-11 3/4"	5'-4 5/8"	
EM135A	2'-6 7/8"	4'-6 1/4"					4'-6 1/4"	2'-11 7/8"	5'-4 7/8"	
EM136A	2'-6 7/8"	4'-6 1/2"					4'-6 1/2"	2'-11 7/8"	5'-5 1/4"	
EM137A	2'-7"	4'-6 3/4"					4'-6 3/4"	3'-0"	5'-5 1/2"	
EM138A	2'-7 1/8"	4'-6 7/8"					4'-6 7/8"	3'-0 1/8"	5'-5 3/4"	
EM139A	2'-7 1/4"	4'-7 1/8"					4'-7 1/8"	3'-0 1/4"	5'-6"	
EM140A	2'-7 3/8"	4'-7 3/8"					4'-7 3/8"	3'-0 3/8"	5'-6 1/4"	
EM141A	2'-7 1/2"	4'-7 1/2"					4'-7 1/2"	3'-0 1/2"	5'-6 1/2"	
EM142A	2'-7 1/2"	4'-7 3/4"					4'-7 3/4"	3'-0 1/2"	5'-6 3/4"	
EM143A	2'-7 5/8"	4'-7 7/8"					4'-7 7/8"	3'-0 5/8"	5'-7"	
EM144A	2'-7 3/4"	4'-8 1/8"					4'-8 1/8"	3'-0 3/4"	5'-7 1/4"	6'-7 3/8"
EM145A	2'-7 7/8"	4'-8 1/4"					4'-8 1/4"	3'-0 7/8"	5'-7 1/2"	6'-7 5/8"
EM146A	2'-8"	4'-8 1/2"					4'-8 1/2"	3'-1"	5'-7 3/4"	6'-8"
EM147A	2'-8 1/8"	4'-8 5/8"					4'-8 5/8"	3'-1 1/8"	5'-8"	6'-8 1/4"
EM148A	2'-8 1/4"	4'-8 7/8"					4'-8 7/8"	3'-1 1/4"	5'-8 1/4"	6'-8 1/2"
EM149A	2'-8 1/4"	4'-9"					4'-9"	3'-1 1/4"	5'-8 3/8"	6'-8 7/8"
EM150A	2'-8 3/8"	4'-9 1/4"					4'-9 1/4"	3'-1 3/8"	5'-8 5/8"	6'-9 1/8"
EM151A	2'-8 1/2"	4'-9 3/8"					4'-9 3/8"	3'-1 1/2"	5'-8 7/8"	6'-9 3/8"
EM152A	2'-8 5/8"	4'-9 1/2"					4'-9 1/2"	3'-1 5/8"	5'-9 1/8"	6'-9 3/4"
EM153A	5'-5 5/8"	2'-0 3/4"					2'-0 3/4"	3'-1 3/4"	5'-9 3/8"	6'-10"
EM154A	5'-5 5/8"	2'-1"					2'-1"	3'-1 7/8"	5'-9 5/8"	6'-10 1/4"
EM155A	5'-5 5/8"	2'-1 3/8"					2'-1 3/8"	3'-1 7/8"	5'-9 7/8"	6'-10 1/2"
EM160A	5'-5 5/8"	2'-2 5/8"					2'-2 5/8"	3'-2 1/2"	5'-11"	6'-11 7/8"
EM161A	5'-5 5/8"	2'-2 7/8"					2'-2 7/8"	3'-2 5/8"	5'-11 1/8"	7'-0 1/8"
EM162A	5'-5 5/8"	2'-3 1/8"					2'-3 1/8"	3'-2 5/8"	5'-11 3/8"	7'-0 3/8"
EM163A	2'-9 3/4"	4'-11 3/8"					4'-11 3/8"	3'-2 3/4"	5'-11 5/8"	7'-0 3/4"
EM164A	2'-9 3/4"	4'-11 1/2"					4'-11 1/2"	3'-2 3/4"	5'-11 7/8"	7'-1"
EM165A	2'-9 7/8"	4'-11 3/4"					4'-11 3/4"	3'-2 7/8"	6'-0"	7'-1 1/4"
EM166A	2'-10"	4'-11 7/8"					4'-11 7/8"	3'-3"	6'-0 1/4"	7'-1 1/2"
EM167A	2'-10"	5'-0 1/8"					5'-0 1/8"	3'-3"	6'-0 1/2"	7'-1 7/8"
EM168A	2'-10 1/8"	5'-0 1/4"					5'-0 1/4"	3'-3 1/8"	6'-0 5/8"	7'-2"
EM169A	2'-10 1/8"	5'-0 1/2"					5'-0 1/2"	3'-3 1/8"	6'-0 7/8"	7'-2 3/8"
EM170A	2'-10 1/4"	5'-0 5/8"					5'-0 5/8"	3'-3 1/4"	6'-1 1/8"	7'-2 1/2"
EM171A	2'-10 1/4"	5'-0 3/4"					5'-0 3/4"	3'-3 1/4"	6'-1 1/4"	7'-2 3/4"

EAST BRIDGE - MIDDLE RUN

ID	P01V	L01	A01	L02	A02	L03	LTOT	ANV	H03V	H04V
EM172A	2'-10 3/8"	5'-1"					5'-1"	3'-3 3/8"	6'-1 1/2"	
EM173A	2'-10 3/8"	5'-1 1/8"					5'-1 1/8"	3'-3 3/8"	6'-1 5/8"	
EM174A	2'-10 1/2"	5'-1 3/8"					5'-1 3/8"	3'-3 1/2"	6'-1 7/8"	
EM175A	2'-10 1/2"	5'-1 1/2"					5'-1 1/2"	3'-3 1/2"	6'-2 1/8"	
EM176A	2'-10 5/8"	5'-1 5/8"					5'-1 5/8"	3'-3 5/8"	6'-2 1/4"	
EM177A	2'-10 3/4"	5'-1 3/4"					5'-1 3/4"	3'-3 3/4"	6'-2 1/2"	
EM178A	2'-10 3/4"	5'-2"					5'-2"	3'-3 3/4"	6'-2 5/8"	
EM179A	2'-10 7/8"	5'-2 1/8"					5'-2 1/8"	3'-3 7/8"	6'-2 7/8"	
EM180A	2'-10 7/8"	5'-2 1/4"					5'-2 1/4"	3'-3 7/8"	6'-3"	
EM181A	2'-11"	5'-2 3/8"					5'-2 3/8"	3'-4"	6'-3 1/4"	
EM182A	2'-11"	5'-2 5/8"					5'-2 5/8"	3'-4"	6'-3 3/8"	
EM183A	2'-11 1/8"	5'-2 3/4"					5'-2 3/4"	3'-4 1/8"	6'-3 5/8"	
EM184A	2'-11 1/8"	5'-2 7/8"					5'-2 7/8"	3'-4 1/8"	6'-3 3/4"	
EM185A	2'-11 1/4"	5'-3"					5'-3"	3'-4 1/4"	6'-3 7/8"	
EM186A	2'-11 1/4"	5'-3 1/8"					5'-3 1/8"	3'-4 1/4"	6'-4 1/8"	
EM187A	2'-11 3/8"	5'-3 1/4"					5'-3 1/4"	3'-4 3/8"	6'-4 1/4"	
EM188A	2'-11 1/2"	5'-3 1/2"					5'-3 1/2"	3'-4 1/2"	6'-4 1/2"	
EM189A	2'-11 1/2"	5'-3 5/8"					5'-3 5/8"	3'-4 1/2"	6'-4 5/8"	
EM190A	2'-11 5/8"	5'-3 3/4"					5'-3 3/4"	3'-4 5/8"	6'-4 3/4"	
EM191A	2'-11 5/8"	5'-3 7/8"					5'-3 7/8"	3'-4 5/8"	6'-5"	
EM192A	2'-11 3/4"	5'-4"					5'-4"	3'-4 3/4"	6'-5 1/8"	
EM193A	2'-11 3/4"	5'-4 1/8"					5'-4 1/8"	3'-4 3/4"	6'-5 1/4"	
EM194A	2'-11 7/8"	5'-4 1/4"					5'-4 1/4"	3'-4 7/8"	6'-5 1/2"	
EM195A	2'-11 7/8"	5'-4 3/8"					5'-4 3/8"	3'-4 7/8"	6'-5 5/8"	
EM196A	3'-0"	5'-4 1/2"					5'-4 1/2"	3'-5"	6'-5 3/4"	
EM197A	3'-0"	5'-4 5/8"					5'-4 5/8"	3'-5"	6'-6"	
EM198A	3'-0 1/8"	5'-4 3/4"					5'-4 3/4"	3'-5 1/8"	6'-6 1/8"	
EM199A	3'-0 1/4"	5'-4 7/8"					5'-4 7/8"	3'-5 1/4"	6'-6 1/4"	
EM200A	3'-0 1/4"	5'-5"					5'-5"	3'-5 1/4"	6'-6 3/8"	
EM201A	3'-0 3/8"	5'-5"					5'-5"	3'-5 3/8"	6'-6 5/8"	
EM202A	3'-0 3/8"	5'-5 1/8"					5'-5 1/8"	3'-5 3/8"	6'-6 3/4"	
EM203A	3'-0 1/2"	5'-5 1/4"					5'-5 1/4"	3'-5 1/2"	6'-6 7/8"	
EM204A	3'-0 1/2"	5'-5 3/8"					5'-5 3/8"	3'-5 1/2"	6'-7"	
EM205A	3'-0 5/8"	5'-5 1/2"					5'-5 1/2"	3'-5 5/8"	6'-7 1/8"	
EM206A	3'-0 5/8"	5'-5 5/8"					5'-5 5/8"	3'-5 5/8"	6'-7 1/4"	
EM207A	3'-0 3/4"	5'-5 5/8"					5'-5 5/8"	3'-5 3/4"	6'-7 1/2"	
EM208A	3'-0 7/8"	5'-5 3/4"					5'-5 3/4"	3'-5 7/8"	6'-7 5/8"	
EM209A	3'-0 7/8"	5'-5 7/8"					5'-5 7/8"	3'-5 7/8"	6'-7 3/4"	
EM210A	3'-1"	5'-6"					5'-6"	3'-6"	6'-7 7/8"	
EM211A	3'-1"	5'-6 1/8"					5'-6 1/8"	3'-6"	6'-8"	
EM212A	3'-1 1/8"	5'-6 1/8"					5'-6 1/8"	3'-6 1/8"	6'-8 1/8"	
EM213A	3'-1 1/8"	5'-6 1/4"					5'-6 1/4"	3'-6 1/8"	6'-8 1/4"	
EM214A	3'-1 1/4"	5'-6 3/8"					5'-6 3/8"	3'-6 1/4"	6'-8 3/8"	
EM215A	3'-1 1/4"	5'-6 3/8"					5'-6 3/8"	3'-6 1/4"	6'-8 1/2"	
EM216A	3'-1 3/8"	5'-6 1/2"					5'-6 1/2"	3'-6 3/8"	6'-8 5/8"	
EM217A	3'-1 3/8"	5'-6 5/8"					5'-6 5/8"	3'-6 3/8"	6'-8 3/4"	
EM218A	3'-1 1/2"	5'-6 5/8"					5'-6 5/8"	3'-6 1/2"	6'-8 7/8"	
EM219A	3'-1 5/8"	5'-6 3/4"					5'-6 3/4"	3'-6 5/8"	6'-9"	
EM220A	3'-1 5/8"	5'-6 3/4"					5'-6 3/4"	3'-6 5/8"	6'-9 1/8"	
EM221A	3'-1 3/4"	5'-6 7/8"					5'-6 7/8"	3'-6 3/4"	6'-9 1/4"	
EM222A	3'-1 3/4"	5'-7"					5'-7"	3'-6 3/4"	6'-9 3/8"	
EM223A	3'-1 3/4"	5'-7 1/8"					5'-7 1/8"	3'-6 3/4"	6'-9 1/2"	
EM224A	3'-1 3/4"	5'-7 1/8"					5'-7 1/8"	3'-6 3/4"	6'-9 5/8"	
EM225A	3'-1 7/8"	5'-7 1/4"					5'-7 1/4"	3'-6 7/8"	6'-9 3/4"	
EM226A	3'-1 7/8"	5'-7 3/8"					5'-7 3/8"	3'-6 7/8"	6'-9 3/4"	
EM227A	3'-1 7/8"	5'-7 1/2"					5'-7 1/2"	3'-6 7/8"	6'-9 7/8"	
EM228A	3'-1 7/8"	5'-7 5/8"					5'-7 5/8"	3'-6 7/8"	6'-10"	
EM229A	3'-1 7/8"	5'-7 3/4"					5'-7 3/4"	3'-6 7/8"	6'-10 1/8"	
EM230A	3'-2"	5'-7 3/4"					5'-7 3/4"	3'-7"	6'-10 1/4"	
EM231A	3'-2"	5'-7 7/8"					5'-7 7/8"	3'-7"	6'-10 3/8"	
EM232A	3'-2"	5'-8"					5'-8"	3'-7"	6'-10 3/8"	
EM233A	3'-2"	5'-8 1/8"					5'-8 1/8"	3'-7"	6'-10 1/2"	
EM234A	3'-2"	5'-8 1/8"					5'-8 1/8"	3'-7"	6'-10 5/8"	
EM235A	3'-2"	5'-8 1/4"					5'-8 1/4"	3'-7"	6'-10 3/4"	
EM236A	3'-2 1/8"	5'-8 3/8"					5'-8 3/8"	3'-7 1/8"	6'-10 7/8"	
EM237A	3'-2 1/8"	5'-8 1/2"					5'-8 1/2"	3'-7 1/8"	6'-10 7/8"	
EM238A	3'-2 1/8"	5'-8 1/2"					5'-8 1/2"	3'-7 1/8"	6'-11"	
EM239A	3'-2 1/8"	5'-8 5/8"					5'-8 5/8"	3'-7 1/8"	6'-11 1/8"	
EM240A	3'-2 1/8"	5'-8 5/8"					5'-8 5/8"	3'-7 1/8"	6'-11 1/8"	
EM241A	3'-2 1/8"	5'-8 3/4"					5'-8 3/4"	3'-7 1/8"	6'-11 1/4"	
EM242A	3'-2 1/4"	5'-8 7/8"					5'-8 7/8"	3'-7 1/4"	6'-11 3/8"	
EM243A	3'-2 1/4"	5'-8 7/8"					5'-8 7/8"	3'-7 1/4"	6'-11 3/8"	
EM244A	3'-2 1/4"	5'-9"					5'-9"	3'-7 1/4"	6'-11 1/2"	
EM245A	3'-2 1/4"	5'-9"					5'-9"	3'-7 1/4"	6'-11 5/8"	
EM246A	3'-2 1/4"	5'-9 1/8"					5'-9 1/8"	3'-7 1/4"	6'-11 5/8"	
EM247A	3'-2 3/8"	5'-9 1/8"					5'-9 1/8"	3'-7 3/8"	6'-11 3/4"	
EM248A	3'-2 3/8"	5'-9 1/4"					5'-9 1/4"	3'-7 3/8"	6'-11 3/4"	
EM249A	3'-2 3/8"	5'-9 1/4"					5'-9 1/4"	3'-7 3/8"	6'-11 7/8"	
EM250A	3'-2 3/8"	5'-9 3/8"					5'-9 3/8"	3'-7 3/8"	7'-0"	
EM251A	3'-2 3/8"	5'-9 3/8"					5'-9 3/8"	3'-7 3/8"	7'-0"	
EM252A	3'-2 3/8"	5'-9 1/2"					5'-9 1/2"	3'-7 3/8"	7'-0 1/8"	
EM253A	3'-2 1/2"	5'-9 1/2"					5'-9 1/2"	3'-7 1/2"	7'-0 1/8"	
EM254A	3'-2 1/2"	5'-9 5/8"					5'-9 5/8"	3'-7 1/2"	7'-0 1/4"	
EM255A	3'-2 1/2"	5'-9 5/8"					5'-9 5/8"	3'-7 1/2"	7'-0 1/4"	
EM256A	3'-2 1/2"	5'-9 5/8"					5'-9 5/8"	3'-7 1/2"	7'-0 3/8"	
EM257A	3'-2 1/2"	5'-9 3/4"					5'-9 3/4"	3'-7 1/2"	7'-0 3/8"	
EM258A	3'-2 5/8"	5'-9 3/4"					5'-9 3/4"	3'-7 5/8"	7'-0 3/8"	
EM259A	3'-2 5/8"	5'-9 3/4"					5'-9 3/4"	3'-7 5/8"	7'-0 1/2"	
EM260A	3'-2 5/8"	5'-9 7/8"					5'-9 7/8"	3'-7 5/8"	7'-0 1/2"	
EM261A	3'-2 5/8"	5'-9 7/8"					5'-9 7/8"	3'-7 5/8"	7'-0 5/8"	
EM262A	3'-2 5/8"	5'-9 7/8"					5'-9 7/8"	3'-7 5/8"	7'-0 5/8"	
EM263A	3'-2 5/8"	5'-9 7/8"					5'-9 7/8"	3'-7 5/8"	7'-0 3/4"	
EM264A	3'-2 3/4"	5'-10"					5'-10"	3'-7 3/4"	7'-0 3/4"	
EM265A	3'-2 3/4"	5'-10"					5'-10"	3'-7 3/4"	7'-0 3/4"	
EM266A	3'-2 3/4"	5'-10"					5'-10"	3'-7 3/4"	7'-0 7/8"	
EM267A	3'-2 3/4"	5'-10"					5'-10"	3'-7 3/4"	7'-0 7/8"	
EM268A	3'-2 3/4"	5'-10 1/8"					5'-10 1/8"	3'-7 3/4"	7'-0 7/8"	
EM269A	3'-2 7/8"	5'-10 1/8"					5'-10 1/8"	3'-7 7/8"	7'-1"	
EM270A	3'-2 7/8"	5'-10 1/8"					5'-10 1/8"	3'-7 7/8"	7'-1"	
EM271A	3'-2 7/8"	5'-10 1/8"					5'-10 1/8"	3'-7 7/8"	7'-1"	
EM272A	3'-2 7/8"	5'-10 1/8"					5'-10 1/8"	3'-7 7/8"	7'-1"	
EM273A	3'-2 7/8"	5'-10 1/8"					5'-10 1/8"	3'-7 7/8"	7'-1 1/8"	
EM274A	3'-2 7/8"	5'-10 1/8"					5'-10 1/8"	3'-7 7/8"	7'-1 1/8"	
EM275A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/8"	
EM276A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/8"	
EM277A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/8"	
EM278A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/4"	
EM279A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/4"	
EM280A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM281A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM282A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM283A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM284A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM285A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 1/4"	
EM286A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 3/8"	
EM287A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 3/8"	
EM288A	3'-3 1/4"	5'-10"					5'-10"	3'-8 1/4"	7'-1 3/8"	
EM289A	3'-3 3/8"	5'-10"					5'-10"	3'-8 3/8"	7'-1 3/8"	
EM290A	3'-3 3/8"	5'-10"					5'-10"	3'-8 3/8"	7'-1 3/8"	
EM291A	3'-3 1/4"	5'-10"					5'-10"	3'-8 1/4"	7'-1 3/8"	
EM292A	3'-3 1/4"	5'-10"					5'-10"	3'-8 1/4"	7'-1 3/8"	
EM293A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 3/8"	
EM294A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 3/8"	
EM295A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 3/8"	
EM296A	3'-3 1/4"	5'-10 1/8"					5'-10 1/8"	3'-8 1/4"	7'-1 3/8"	
EM297A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM298A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM299A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM300A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM301A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM302A	3'-3 1/8"	5'-10 1/8"					5'-10 1/8"	3'-8 1/8"	7'-1 1/4"	
EM303A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/4"	
EM304A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/4"	
EM305A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/8"	
EM306A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/8"	
EM307A	3'-3"	5'-10 1/8"					5'-10 1/8"	3'-8"	7'-1 1/8"	
EM308A	3'-3"	5'-10"					5'-10"	3'-8"	7'-1 1/8"	
EM309A	3'-2 7/8"	5'-10"					5'-10"	3'-7 7/8"	7'-1"	
EM310A	3'-2 7/8"	5'-10"					5'-10"	3'-7 7/8"	7'-1"	
EM311A	3'-2 7/8"	5'-10"					5'-10"	3'-7 7/8"	7'-1"	
EM312A	3'-2 7/8"	5'-10"					5'-10"	3'-7 7/8"	7'-1"	
EM313A	3'-2 7/8"	5'-10"					5'-10"	3'-7 7/8"	7'-0 7/8"	
EM314A	3'-2 3/4"	5'-9 7/8"					5'-9 7/8"	3'-7 3/4"	7'-0 7/8"	
EM315A	3'-2 3/4"	5'-9 7/8"					5'-9 7/8"	3'-7 3/4"	7'-0 7/8"	
EM316A	3'-2 3/4"	5'-9 7/8"					5'-9 7/8"	3'-7 3/4"	7'-0 3/4"	
EM317A	3'-2 3/4"	5'-9 7/8"					5'-9 7/8"	3'-7 3/4"	7'-0 3/4"	
EM318A	3'-2 3/4"	5'-9 3/4"					5'-9 3/4"	3'-7 3/4"	7'-0 3/4"	
EM319A	3'-2 3/4"	5'-9 3/4"					5'-9 3/4"	3'-7 3/4"	7'-0 5/8"	
EM320A	3'-2 5/8"	5'-9 3/4"					5'-9 3/4"	3'-7 5/8"	7'-0 5/8"	
EM321A	3'-2 5/8"	5'-9 5/8"					5'-9 5/8"	3'-7 5/8"	7'-0 5/8"	
EM322A	3'-2 5/8"	5'-9 5/8"					5'-9 5/8"	3'-7 5/8"	7'-0 1/2"	
EM323A	3'-2 5/8"	5'-9 5/8"					5'-9 5/8"	3'-7 5/8"	7'-0 1/2"	
EM324A	3'-2 5/8"	5'-9 1/2"					5'-9 1/2"	3'-7 5/8"	7'-0 3/8"	
EM325A	3'-2 5/8"	5'-9 1/2"					5'-9 1/2"	3'-7 5/8"	7'-0 3/8"	
EM326A	3'-2 1/2"	5'-9 1/2"					5'-9 1/2"	3'-7 1/2"	7'-0 1/4"	
EM327A	3'-2 1/2"	5'-9 3/8"					5'-9 3/8"	3'-7 1/2"	7'-0 1/4"	
EM328A	3'-2 1/2"	5'-9 3/8"					5'-9 3/8"	3'-7 1/2"	7'-0 1/8"	
EM329A	3'-2 1/2"	5'-9 1/4"					5'-9 1/4"	3'-7 1/2"	7'-0 1/8"	
EM330A	3'-2 1/2"	5'-9 1/4"					5'-9 1/4"	3'-7 1/2"	7'-0"	
EM331A	3'-2 1/2"	5'-9 1/8"					5'-9 1/8"	3'-7 1/2"	7'-0"	
EM332A	3'-2 3/8"	5'-9 1/8"					5'-9 1/8"	3'-7 3/8"	6'-11 7/8"	
EM333A	3'-2 3/8"	5'-9"					5'-9"	3'-7 3/8"	6'-11 7/8"	
EM334A	3'-2 3/8"	5'-9"					5'-9"	3'-7 3/8"	6'-11 3/4"	
EM335A	3'-2 3/8"	5'-8 7/8"					5'-8 7/8"	3'-7 3/8"	6'-11 3/4"	
EM336A	3'-2 3/8"	5'-8 7/8"					5'-8 7/8"	3'-7 3/8"	6'-11 5/8"	
EM337A	3'-2 3/8"	5'-8 3/4"					5'-8 3/4"	3'-7 3/8"	6'-11 1/2"	
EM338A	3'-2 1/4"	5'-8 5/8"					5'-8 5/8"	3'-7 1/4"	6'-11 1/2"	
EM339A	3'-2 1/4"	5'-8 5/8"					5'-8 5/8"	3'-7 1/4"	6'-11 3/8"	

EAST BRIDGE - MIDDLE RUN

ID	P01V	L01	A01	L02	A02	L03	LTOT	ANV	H03V	H04V
EM340A	3'-2 1/4"	5'-8 1/2"					5'-8 1/2"	3'-7 1/4"	6'-11 1/4"	
EM341A	3'-2 1/4"	5'-8 1/2"					5'-8 1/2"	3'-7 1/4"	6'-11 1/4"	
EM342A	3'-2 1/4"	5'-8 3/8"					5'-8 3/8"	3'-7 1/4"	6'-11 1/8"	
EM343A	3'-2 1/8"	5'-8 1/4"					5'-8 1/4"	3'-7 1/8"	6'-11"	
EM344A	3'-2 1/8"	5'-8 1/4"					5'-8 1/4"	3'-7 1/8"	6'-11"	
EM345A	3'-2"	5'-8 1/4"					5'-8 1/4"	3'-7"	6'-10 7/8"	
EM346A	3'-2"	5'-8 1/8"					5'-8 1/8"	3'-7"	6'-10 3/4"	
EM347A	3'-1 7/8"	5'-8 1/8"					5'-8 1/8"	3'-6 7/8"	6'-10 5/8"	
EM348A	3'-1 7/8"	5'-8"					5'-8"	3'-6 7/8"	6'-10 5/8"	
EM349A	3'-1 7/8"	5'-8"					5'-8"	3'-6 7/8"	6'-10 1/2"	
EM350A	3'-1 3/4"	5'-7 7/8"					5'-7 7/8"	3'-6 3/4"	6'-10 3/8"	
EM351A	3'-1 3/4"	5'-7 3/4"					5'-7 3/4"	3'-6 3/4"	6'-10 1/4"	
EM352A	3'-1 5/8"	5'-7 3/4"					5'-7 3/4"	3'-6 5/8"	6'-10 1/4"	
EM353A	3'-1 5/8"	5'-7 5/8"					5'-7 5/8"	3'-6 5/8"	6'-10 1/8"	
EM354A	3'-1 5/8"	5'-7 5/8"					5'-7 5/8"	3'-6 5/8"	6'-10"	
EM355A	3'-1 1/2"	5'-7 1/2"					5'-7 1/2"	3'-6 1/2"	6'-9 7/8"	
EM356A	3'-1 1/2"	5'-7 3/8"					5'-7 3/8"	3'-6 1/2"	6'-9 3/4"	
EM357A	3'-1 3/8"	5'-7 3/8"					5'-7 3/8"	3'-6 3/8"	6'-9 5/8"	
EM358A	3'-1 3/8"	5'-7 1/4"					5'-7 1/4"	3'-6 3/8"	6'-9 1/2"	
EM359A	3'-1 1/4"	5'-7 1/8"					5'-7 1/8"	3'-6 1/4"	6'-9 3/8"	
EM360A	3'-1 1/4"	5'-7 1/8"					5'-7 1/8"	3'-6 1/4"	6'-9 3/8"	
EM361A	3'-1 1/4"	5'-7"					5'-7"	3'-6 1/4"	6'-9 1/4"	
EM362A	3'-1 1/8"	5'-6 7/8"					5'-6 7/8"	3'-6 1/8"	6'-9 1/8"	
EM363A	3'-1 1/8"	5'-6 3/4"					5'-6 3/4"	3'-6 1/8"	6'-9"	
EM364A	3'-1"	5'-6 3/4"					5'-6 3/4"	3'-6"	6'-8 7/8"	
EM365A	3'-1"	5'-6 5/8"					5'-6 5/8"	3'-6"	6'-8 3/4"	
EM366A	3'-1"	5'-6 1/2"					5'-6 1/2"	3'-6"	6'-8 5/8"	
EM367A	3'-0 7/8"	5'-6 3/8"					5'-6 3/8"	3'-5 7/8"	6'-8 1/2"	
EM368A	3'-0 7/8"	5'-6 1/4"					5'-6 1/4"	3'-5 7/8"	6'-8 3/8"	
EM369A	3'-0 3/4"	5'-6 1/8"					5'-6 1/8"	3'-5 3/4"	6'-8 1/4"	
EM370A	3'-0 3/4"	5'-6 1/8"					5'-6 1/8"	3'-5 3/4"	6'-8 1/8"	
EM371A	3'-0 5/8"	5'-6"					5'-6"	3'-5 5/8"	6'-7 7/8"	
EM372A	3'-0 5/8"	5'-5 7/8"					5'-5 7/8"	3'-5 5/8"	6'-7 3/4"	
EM373A	3'-0 5/8"	5'-5 3/4"					5'-5 3/4"	3'-5 5/8"	6'-7 5/8"	
EM374A	3'-0 1/2"	5'-5 5/8"					5'-5 5/8"	3'-5 1/2"	6'-7 1/2"	
EM375A	3'-0 1/2"	5'-5 1/2"					5'-5 1/2"	3'-5 1/2"	6'-7 3/8"	
EM376A	3'-0 3/8"	5'-5 3/8"					5'-5 3/8"	3'-5 3/8"	6'-7 1/4"	
EM377A	3'-0 3/8"	5'-5 1/4"					5'-5 1/4"	3'-5 3/8"	6'-7 1/8"	
EM378A	3'-0 1/4"	5'-5 1/8"					5'-5 1/8"	3'-5 1/4"	6'-7"	
EM379A	3'-0 1/4"	5'-5"					5'-5"	3'-5 1/4"	6'-6 3/4"	
EM380A	3'-0 1/4"	5'-4 7/8"					5'-4 7/8"	3'-5 1/4"	6'-6 5/8"	
EM381A	3'-0 1/8"	5'-4 3/4"					5'-4 3/4"	3'-5 1/8"	6'-6 1/2"	
EM382A	3'-0 1/8"	5'-4 5/8"					5'-4 5/8"	3'-5 1/8"	6'-6 3/8"	
EM383A	3'-0"	5'-4 1/2"					5'-4 1/2"	3'-5"	6'-6 1/4"	
EM384A	3'-0"	5'-4 3/8"					5'-4 3/8"	3'-5"	6'-6"	
EM385A	3'-0"	5'-4 1/4"					5'-4 1/4"	3'-5"	6'-5 7/8"	
EM386A	2'-11 7/8"	5'-4"					5'-4"	3'-4 7/8"	6'-5 3/4"	
EM387A	2'-11 7/8"	5'-3 7/8"					5'-3 7/8"	3'-4 7/8"	6'-5 1/2"	
EM388A	2'-11 3/4"	5'-3 3/4"					5'-3 3/4"	3'-4 3/4"	6'-5 3/8"	
EM389A	2'-11 3/4"	5'-3 5/8"					5'-3 5/8"	3'-4 3/4"	6'-5 1/4"	
EM390A	2'-11 5/8"	5'-3 1/2"					5'-3 1/2"	3'-4 5/8"	6'-5 1/8"	
EM391A	2'-11 5/8"	5'-3 1/4"					5'-3 1/4"	3'-4 5/8"	6'-4 7/8"	
EM392A	2'-11 5/8"	5'-3 1/8"					5'-3 1/8"	3'-4 5/8"	6'-4 3/4"	
EM393A	2'-11 1/2"	5'-3"					5'-3"	3'-4 1/2"	6'-4 1/2"	
EM394A	2'-11 1/2"	5'-2 7/8"					5'-2 7/8"	3'-4 1/2"	6'-4 3/8"	
EM395A	2'-11 3/8"	5'-2 5/8"					5'-2 5/8"	3'-4 3/8"	6'-4 1/4"	
EM396A	2'-11 3/8"	5'-2 1/2"					5'-2 1/2"	3'-4 3/8"	6'-4"	
EM397A	2'-11 3/8"	5'-2 3/8"					5'-2 3/8"	3'-4 3/8"	6'-3 7/8"	
EM398A	2'-11 1/4"	5'-2 1/8"					5'-2 1/8"	3'-4 1/4"	6'-3 5/8"	
EM399A	2'-11 1/4"	5'-2"					5'-2"	3'-4 1/4"	6'-3 1/2"	
EM400A	2'-11 1/8"	5'-1 7/8"					5'-1 7/8"	3'-4 1/8"	6'-3 3/8"	
EM401A	2'-11 1/8"	5'-1 5/8"					5'-1 5/8"	3'-4 1/8"	6'-3 1/8"	
EM402A	2'-11"	5'-1 1/2"					5'-1 1/2"	3'-4"	6'-3"	
EM403A	2'-11"	5'-1 3/8"					5'-1 3/8"	3'-4"	6'-2 3/4"	
EM404A	2'-10 7/8"	5'-1 1/4"					5'-1 1/4"	3'-3 7/8"	6'-2 5/8"	
EM405A	2'-10 3/4"	5'-1 1/8"					5'-1 1/8"	3'-3 3/4"	6'-2 3/8"	
EM406A	2'-10 5/8"	5'-1"					5'-1"	3'-3 5/8"	6'-2 1/8"	
EM407A	2'-10 1/2"	5'-0 7/8"					5'-0 7/8"	3'-3 1/2"	6'-2"	
EM408A	2'-10 1/2"	5'-0 3/4"					5'-0 3/4"	3'-3 1/2"	6'-1 3/4"	7'-3 1/4"
EM409A	2'-10 3/8"	5'-0 1/2"					5'-0 1/2"	3'-3 3/8"	6'-1 5/8"	7'-3"
EM410A	2'-10 1/4"	5'-0 3/8"					5'-0 3/8"	3'-3 1/4"	6'-1 3/8"	7'-2 3/4"
EM411A	2'-10 1/8"	5'-0 1/4"					5'-0 1/4"	3'-3 1/8"	6'-1 1/4"	7'-2 1/2"
EM412A	2'-10"	5'-0 1/8"					5'-0 1/8"	3'-3"	6'-1"	7'-2 1/4"
EM413A	2'-10"	5'-0"					5'-0"	3'-3"	6'-0 3/4"	7'-2"
EM414A	2'-9 7/8"	4'-11 7/8"					4'-11 7/8"	3'-2 7/8"	6'-0 5/8"	7'-1 3/4"
EM415A	2'-9 3/4"	4'-11 5/8"					4'-11 5/8"	3'-2 3/4"	6'-0 3/8"	7'-1 1/2"
EM416A	2'-9 5/8"	4'-11 1/2"					4'-11 1/2"	3'-2 5/8"	6'-0 1/8"	7'-1 1/4"
EM417A	5'-5 5/8"	2'-3 1/4"					2'-3 1/4"	3'-2 5/8"	6'-0"	7'-1"
EM418A	5'-5 5/8"	2'-3"					2'-3"	3'-2 1/2"	5'-11 3/4"	7'-0 3/4"
EM419A	5'-5 5/8"	2'-2 3/4"					2'-2 3/4"	3'-2 3/8"	5'-11 1/2"	7'-0 1/2"
EM424A	5'-5 5/8"	2'-1 3/8"					2'-1 3/8"	3'-1 7/8"	5'-10 3/8"	6'-11 1/8"
EM425A	5'-5 5/8"	2'-1 1/8"					2'-1 1/8"	3'-1 3/4"	5'-10 1/4"	6'-10 7/8"
EM426A	5'-5 5/8"	2'-0 7/8"					2'-0 7/8"	3'-1 5/8"	5'-10"	6'-10 5/8"
EM427A	2'-8 5/8"	4'-9 5/8"					4'-9 5/8"	3'-1 5/8"	5'-9 3/4"	6'-10 3/8"
EM428A	2'-8 1/2"	4'-9 1/2"					4'-9 1/2"	3'-1 1/2"	5'-9 1/2"	6'-10"
EM429A	2'-8 3/8"	4'-9 1/4"					4'-9 1/4"	3'-1 3/8"	5'-9 1/4"	6'-9 3/4"
EM430A	2'-8 1/4"	4'-9 1/8"					4'-9 1/8"	3'-1 1/4"	5'-9"	6'-9 1/2"
EM431A	2'-8 1/4"	4'-8 7/8"					4'-8 7/8"	3'-1 1/4"	5'-8 7/8"	6'-9 1/8"
EM432A	2'-8 1/8"	4'-8 3/4"					4'-8 3/4"	3'-1 1/8"	5'-8 5/8"	6'-8 7/8"
EM433A	2'-8"	4'-8 1/2"					4'-8 1/2"	3'-1"	5'-8 3/8"	6'-8 5/8"
EM434A	2'-7 7/8"	4'-8 3/8"					4'-8 3/8"	3'-0 7/8"	5'-8 1/8"	6'-8 1/4"
EM435A	2'-7 3/4"	4'-8 1/8"					4'-8 1/8"	3'-0 3/4"	5'-7 7/8"	6'-8"
EM436A	2'-7 3/4"	4'-8"					4'-8"	3'-0 3/4"	5'-7 5/8"	
EM437A	2'-7 5/8"	4'-7 3/4"					4'-7 3/4"	3'-0 5/8"	5'-7 3/8"	
EM438A	2'-7 1/2"	4'-7 1/2"					4'-7 1/2"	3'-0 1/2"	5'-7 1/8"	
EM439A	2'-7 3/8"	4'-7 3/8"					4'-7 3/8"	3'-0 3/8"	5'-6 7/8"	
EM440A	2'-7 1/4"	4'-7 1/8"					4'-7 1/8"	3'-0 1/4"	5'-6 5/8"	
EM441A	2'-7 1/4"	4'-6 7/8"					4'-6 7/8"	3'-0 1/4"	5'-6 3/8"	
EM442A	2'-7 1/8"	4'-6 3/4"					4'-6 3/4"	3'-0 1/8"	5'-6 1/8"	
EM443A	2'-7"	4'-6 1/2"					4'-6 1/2"	3'-0"	5'-5 7/8"	
EM444A	2'-6 7/8"	4'-6 1/4"					4'-6 1/4"	2'-11 7/8"	5'-5 5/8"	
EM445A	2'-6 7/8"	4'-6 1/8"					4'-6 1/8"	2'-11 7/8"	5'-5 3/8"	
EM446A	2'-6 3/4"	4'-5 7/8"					4'-5 7/8"	2'-11 3/4"	5'-5 1/8"	
EM447A	2'-6 5/8"	4'-5 5/8"					4'-5 5/8"	2'-11 5/8"	5'-4 7/8"	
EM448A	2'-6 1/2"	4'-5 3/8"					4'-5 3/8"	2'-11 1/2"	5'-4 1/2"	
EM449A	2'-6 3/8"	4'-5 1/4"					4'-5 1/4"	2'-11 3/8"	5'-4 1/4"	
EM450A	2'-6 3/8"	4'-5"					4'-5"	2'-11 3/8"	5'-4"	
EM451A	2'-6 1/4"	4'-4 3/4"					4'-4 3/4"	2'-11 1/4"	5'-3 3/4"	
EM452A	2'-6 1/8"	4'-4 1/2"					4'-4 1/2"	2'-11 1/8"	5'-3 1/2"	
EM453A	2'-6"	4'-4 1/4"					4'-4 1/4"	2'-11"	5'-3 1/4"	
EM454A	2'-5 7/8"	4'-4"					4'-4"	2'-10 7/8"	5'-3"	
EM455A	2'-5 7/8"	4'-3 3/4"					4'-3 3/4"	2'-10 7/8"	5'-2 5/8"	
EM456A	2'-5 3/4"	4'-3 5/8"					4'-3 5/8"	2'-10 3/4"	5'-2 3/8"	
EM457A	2'-5 5/8"	4'-3 3/8"					4'-3 3/8"	2'-10 5/8"	5'-2 1/8"	
EM458A	2'-5 1/2"	4'-3 1/8"					4'-3 1/8"	2'-10 1/2"	5'-1 7/8"	
EM459A	2'-5 1/2"	4'-2 7/8"					4'-2 7/8"	2'-10 1/2"	5'-1 1/2"	
EM460A	2'-5 3/8"	4'-2 5/8"					4'-2 5/8"	2'-10 3/8"	5'-1 1/4"	
EM461A	2'-5 1/4"	4'-2 3/8"					4'-2 3/8"	2'-10 1/4"	5'-1"	
EM462A	2'-5 1/8"	4'-2 1/8"					4'-2 1/8"	2'-10 1/8"	5'-0 3/4"	
EM463A	2'-5"	4'-1 7/8"					4'-1 7/8"	2'-10"	5'-0 3/8"	
EM464A	2'-4 7/8"	4'-1 5/8"					4'-1 5/8"	2'-9 7/8"	5'-0 1/8"	
EM465A	2'-4 3/4"	4'-1 1/2"					4'-1 1/2"	2'-9 3/4"	4'-11 7/8"	
EM466A	2'-4 5/8"	4'-1 1/4"					4'-1 1/4"	2'-9 5/8"	4'-11 1/2"	
EM467A	2'-4 1/2"	4'-1"					4'-1"	2'-9 1/2"	4'-11 1/4"	
EM468A	2'-4 3/8"	4'-0 3/4"					4'-0 3/4"	2'-9 3/8"	4'-10 7/8"	
EM469A	2'-4 1/8"	4'-0 1/2"					4'-0 1/2"	2'-9 1/8"	4'-10 5/8"	
EM470A	2'-4"	4'-0 3/8"					4'-0 3/8"	2'-9"	4'-10 3/8"	
EM471A	2'-3 7/8"	4'-0 1/8"					4'-0 1/8"	2'-8 7/8"	4'-10"	
EM472A	2'-3 3/4"	3'-11 7/8"					3'-11 7/8"	2'-8 3/4"	4'-9 3/4"	
EM473A	2'-3 5/8"	3'-11 5/8"					3'-11 5/8"	2'-8 5/8"	4'-9 3/8"	
EM474A	2'-3 1/2"	3'-11 3/8"					3'-11 3/8"	2'-8 1/2"	4'-9 1/8"	
EM475A	2'-3 3/8"	3'-11 1/8"					3'-11 1/8"	2'-8 3/8"	4'-8 3/4"	
EM476A	2'-3 1/4"	3'-10 7/8"					3'-10 7/8"	2'-8 1/4"	4'-8 1/2"	
EM477A	2'-3 1/8"	3'-10 5/8"					3'-10 5/8"	2'-8 1/8"	4'-8 1/8"	
EM478A	2'-3"	3'-10 3/8"					3'-10 3/8"	2'-8"	4'-7 7/8"	
EM479A	2'-2 7/8"	3'-10 1/8"					3'-10 1/8"	2'-7 7/8"	4'-7 1/2"	
EM480A	2'-2 3/4"	3'-9 7/8"					3'-9 7/8"	2'-7 3/4"	4'-7 1/4"	
EM481A	2'-2 1/2"	3'-9 5/8"					3'-9 5/8"	2'-7 1/2"	4'-6 7/8"	
EM482A	2'-2 3/8"	3'-9 3/8"					3'-9 3/8"	2'-7 3/8"	4'-6 5/8"	
EM483A	2'-2 1/4"	3'-9 1/8"					3'-9 1/8"	2'-7 1/4"	4'-6 1/4"	
EM484A	2'-2 1/8"	3'-8 7/8"					3'-8 7/8"	2'-7 1/8"	4'-6"	
EM485A	2'-2"	3'-8 5/8"					3'-8 5/8"	2'-7"	4'-5 5/8"	
EM486A	2'-1 7/8"	3'-8 3/8"					3'-8 3/8"	2'-6 7/8"	4'-5 1/4"	
EM487A	2'-1 3/4"	3'-8 1/8"					3'-8 1/8"	2'-6 3/4"	4'-5"	
EM488A	2'-1 5/8"	3'-7 7/8"					3'-7 7/8"	2'-6 5/8"	4'-4 5/8"	
EM489A	2'-1 1/2"	3'-7 5/8"					3'-7 5/8"	2'-6 1/2"	4'-4 1/4"	
EM490A	2'-1 3/8"	3'-7 3/8"					3'-7 3/8"	2'-6 3/8"	4'-4"	
EM491A	2'-1 1/4"	3'-7"					3'-7"	2'-6 1/4"	4'-3 5/8"	
EM492A	2'-1"	3'-6 3/4"					3'-6 3/4"	2'-6"	4'-3 1/4"	
EM493A	2'-0 7/8"	3'-6 1/2"					3'-6 1/2"	2'-5 7/8"	4'-3"	
EM494A	2'-0 3/4"	3'-6 1/4"					3'-6 1/4"	2'-5 3/4"	4'-2 5/8"	
EM495A	2'-0 5/8"	3'-5 7/8"					3'-5 7/8"	2'-5 5/8"	4'-2 1/4"	
EM496A	2'-0 1/2"	3'-5 5/8"					3'-5 5/8"	2'-5 1/2"	4'-1 7/8"	
EM497A	2'-0 3/8"	3'-5 3/8"					3'-5 3/8"	2'-5 3/8"	4'-1 5/8"	
EM498A	2'-0 1/4"	3'-5 1/8"					3'-5 1/8"	2'-5 1/4"	4'-1 1/4"	
EM499A	2'-0 1/8"	3'-4 3/4"					3'-4 3/4"	2'-5 1/8"	4'-0 7/8"	
EM500A	2'-0"	3'-4 1/2"					3'-4 1/2"	2'-5"	4'-0 1/2"	
EM501A	1'-11 7/8"	3'-4 1/4"					3'-4 1/4"	2'-4 7/8"	4'-0 1/8"	
EM502A	1'-11 3/4"	3'-3 7/8"					3'-3 7/8"	2'-4 3/4"	3'-11 3/4"	
EM503A	1'-11 5/8"	3'-3 5/8"					3'-3 5/8"	2'-4 5/8"	3'-11 1/2"	
EM504A	1'-11 3/8"	3'-3 3/8"					3'-3 3/8"	2'-4 3/8"	3'-11 1/8"	
EM505A	1'-11 1/4"	3'-3"					3'-3"	2'-4 1/4"	3'-10 3/4"	
EM506A	1'-11 1/8"	3'-2 3/4"					3'-2 3/4"	2'-4 1/8"	3'-10 3/8"	
EM507A	1'-11"	3'-2 3/8"					3'-2 3/8"	2'-4"	3'-10"	
EM508A	1'-10 7/8"	3'-2 1/8"					3'-2 1/8"	2'-3 7/8"	3'-9 5/8"	
EM509A	1'-10 3/4"	3'-1 3/4"					3'-1 3/4"	2'-3 3/4"	3'-9 1/4"	
EM510A	1'-10 5/8"	3'-1 1/2"					3'-1 1/2"	2'-3 5/8"	3'-8 7/8"	
EM511A	1'-10 1/2"	3'-1 1/8"					3'-1 1/8"	2'-3 1/2"	3'-8 1/2"	

EAST BRIDGE - MIDDLE RUN

ID	P01V	L01	A01	L02	A02	L03	LTOT	ANV	H03V	H04V
EM512A	1'-10 3/8"	3'-0 7/8"					3'-0 7/8"	2'-3 3/8"	3'-8 1/8"	
EM513A	1'-10 1/4"	3'-0 1/2"					3'-0 1/2"	2'-3 1/4"	3'-7 3/4"	
EM514A	1'-10 1/8"	3'-0 1/4"					3'-0 1/4"	2'-3 1/8"	3'-7 3/8"	
EM515A	1'-10"	2'-11 7/8"					2'-11 7/8"	2'-3"	3'-7"	
EM516A	1'-9 3/4"	2'-11 5/8"					2'-11 5/8"	2'-2 3/4"	3'-6 5/8"	
EM517A	1'-9 5/8"	2'-11 1/4"					2'-11 1/4"	2'-2 5/8"	3'-6 1/4"	
EM518A	1'-9 1/2"	2'-10 7/8"					2'-10 7/8"	2'-2 1/2"	3'-5 7/8"	
EM519A	1'-9 3/8"	2'-10 5/8"					2'-10 5/8"	2'-2 3/8"	3'-5 1/2"	
EM520A	1'-9 1/4"	2'-10 1/4"					2'-10 1/4"	2'-2 1/4"	3'-5 1/8"	
EM521A	1'-9 1/8"	2'-9 7/8"					2'-9 7/8"	2'-2 1/8"	3'-4 3/4"	
EM522A	1'-9"	2'-9 5/8"					2'-9 5/8"	2'-2"	3'-4 3/8"	
EM523A	1'-8 7/8"	2'-9 1/4"					2'-9 1/4"	2'-1 7/8"	3'-4"	
EM524A	1'-8 3/4"	2'-8 7/8"					2'-8 7/8"	2'-1 3/4"	3'-3 5/8"	
EM525A	1'-8 5/8"	2'-8 5/8"					2'-8 5/8"	2'-1 5/8"	3'-3 1/8"	
EM526A	1'-8 1/2"	2'-8 1/4"					2'-8 1/4"	2'-1 1/2"	3'-2 3/4"	
EM527A	1'-8 1/4"	2'-7 7/8"					2'-7 7/8"	2'-1 1/4"	3'-2 3/8"	
EM528A	1'-8 1/8"	2'-7 1/2"					2'-7 1/2"	2'-1 1/8"	3'-2"	
EM529A	1'-8"	2'-7 1/4"					2'-7 1/4"	2'-1"	3'-1 5/8"	
EM530A	1'-7 7/8"	2'-6 7/8"					2'-6 7/8"	2'-0 7/8"	3'-1 1/8"	
EM531A	1'-7 3/4"	2'-6 1/2"					2'-6 1/2"	2'-0 3/4"	3'-0 3/4"	
EM532A	1'-7 5/8"	2'-6 1/8"					2'-6 1/8"	2'-0 5/8"	3'-0 3/8"	
EM533A	1'-7 1/2"	2'-5 5/8"					2'-5 5/8"	2'-0 1/2"	3'-0"	
EM534A	1'-7 3/8"	2'-5 1/8"					2'-5 1/8"	2'-0 3/8"	2'-11 1/2"	
EM535A	1'-7 1/4"	2'-4 1/2"					2'-4 1/2"	2'-0 1/4"	2'-11 1/8"	
EM536A	1'-7 1/8"	2'-4"					2'-4"	2'-0 1/8"	2'-10 3/4"	
EM537A	1'-6 7/8"	2'-3 3/8"					2'-3 3/8"	1'-11 7/8"	2'-10 3/8"	
EM538A	1'-6 3/4"	2'-2 3/4"					2'-2 3/4"	1'-11 3/4"	2'-9 7/8"	
EM539A	1'-6 5/8"	2'-2 1/4"					2'-2 1/4"	1'-11 5/8"	2'-9 1/2"	
EM540A	1'-6 1/2"	2'-1 5/8"					2'-1 5/8"	1'-11 1/2"	2'-9 1/8"	
EM541A	1'-6 3/8"	2'-1 1/8"					2'-1 1/8"	1'-11 3/8"	2'-8 5/8"	
EM542A	1'-6 1/4"	2'-0 1/2"					2'-0 1/2"	1'-11 1/4"	2'-8 1/4"	
EM543A	1'-6 1/8"	2'-0"					2'-0"	1'-11 1/8"	2'-7 3/4"	
EM544A	1'-6"	1'-11 3/8"					1'-11 3/8"	1'-11"	2'-7 3/8"	
EM545A	1'-5 7/8"	1'-10 7/8"					1'-10 7/8"	1'-10 7/8"	2'-7"	
EM546A	1'-5 3/4"	1'-10 1/4"					1'-10 1/4"	1'-10 3/4"	2'-6 1/2"	
EM547A	1'-5 5/8"	1'-9 5/8"					1'-9 5/8"	1'-10 5/8"	2'-6 1/8"	
EM548A	1'-5 1/2"	1'-9 1/8"					1'-9 1/8"	1'-10 1/2"	2'-5 5/8"	
EM549A	1'-5 1/4"	1'-8 1/2"					1'-8 1/2"	1'-10 1/4"	2'-5 1/4"	
EM550A	1'-5 1/8"	1'-8"					1'-8"	1'-10 1/8"	2'-4 3/4"	
EM551A	1'-5"	1'-7 3/8"					1'-7 3/8"	1'-10"	2'-4 3/8"	
EM552A	1'-4 7/8"	1'-6 7/8"					1'-6 7/8"	1'-9 7/8"	2'-3 7/8"	
EM553A	1'-4 3/4"	1'-6 1/4"					1'-6 1/4"	1'-9 3/4"	2'-3 1/2"	
EM554A	1'-4 5/8"	1'-5 5/8"					1'-5 5/8"	1'-9 5/8"	2'-3"	
EM555A	1'-4 1/2"	1'-5 1/8"					1'-5 1/8"	1'-9 1/2"	2'-2 5/8"	
EM556A	1'-4 3/8"	1'-4 1/2"					1'-4 1/2"	1'-9 3/8"	2'-2 1/8"	
EM557A	1'-4 1/4"	1'-4"					1'-4"	1'-9 1/4"	2'-1 5/8"	
EM558A	1'-4 1/8"	1'-3 3/8"					1'-3 3/8"	1'-9 1/8"	2'-1 1/4"	
EM559A	1'-4"	1'-2 7/8"					1'-2 7/8"	1'-9"	2'-0 3/4"	
EM560A	1'-3 3/4"	1'-2 1/4"					1'-2 1/4"	1'-8 3/4"	2'-0 3/8"	
EM561A	1'-3 5/8"	1'-1 3/4"					1'-1 3/4"	1'-8 5/8"	1'-11 7/8"	
EM562A	1'-3 1/2"	1'-1 1/8"					1'-1 1/8"	1'-8 1/2"	1'-11 3/8"	
EM563A	1'-3 3/8"	1'-0 1/2"					1'-0 1/2"	1'-8 3/8"	1'-11"	
EM564A	1'-3 1/4"	1'-0"					1'-0"	1'-8 1/4"	1'-10 1/2"	
EM565A	1'-3 1/8"	0'-11 3/8"					0'-11 3/8"	1'-8 1/8"	1'-10"	
EM566A	1'-3"	0'-10 7/8"					0'-10 7/8"	1'-8"	1'-9 1/2"	
EM567A	1'-2 7/8"	0'-10 1/4"					0'-10 1/4"	1'-7 7/8"	1'-9 1/8"	
EM568A	1'-2 3/4"	0'-9 3/4"					0'-9 3/4"	1'-7 3/4"	1'-8 5/8"	
EM569A	1'-2 5/8"	0'-9 1/8"					0'-9 1/8"	1'-7 5/8"	1'-8 1/8"	
EM570A	1'-2 1/2"	0'-8 1/2"					0'-8 1/2"	1'-7 1/2"	1'-7 3/4"	
EM571A	1'-2 3/8"	0'-8"					0'-8"	1'-7 3/8"	1'-7 1/4"	
EM572A	1'-2 1/8"	0'-7 3/8"					0'-7 3/8"	1'-7 1/8"	1'-6 3/4"	
EM573A	1'-2"	0'-6 7/8"					0'-6 7/8"	1'-7"	1'-6 1/4"	
EM574A	1'-1 7/8"	0'-6 1/4"					0'-6 1/4"	1'-6 7/8"	1'-5 3/4"	
EM575A	1'-1 3/4"	0'-5 3/4"					0'-5 3/4"	1'-6 3/4"	1'-5 3/8"	
EM576A	1'-1 5/8"	0'-5 1/8"					0'-5 1/8"	1'-6 5/8"	1'-4 7/8"	
EM577A	1'-1 1/2"	0'-4 5/8"					0'-4 5/8"	1'-6 1/2"	1'-4 3/8"	
Grand total: 569							2366'-0 1/4"			

RAIL VERT TYPE NOTES

1. RAIL "PO1V" ELEVATIONS SHALL BE USED FOR VERTICAL ALIGNMENT OF MEMBERS DURING SHOP ASSEMBLY.

2. VERTICAL DIMENSIONS OR ELEVATIONS STATED IN *RAIL VERT* SCHEDULES ARE TO *BASELINE ELEVATION* FOR EACH *RAIL RUN*. *THE BASELINE ELEVATION* IS ARBITRARILY SET TO 1'-0" BELOW THE LOWEST POINT OF EACH *RAIL RUN* AND IS UNIQUE TO EACH *RAIL RUN*.

3. *ANCHORAGE* SPACING LOGIC IS SPECIFIED IN DOCUMENTS, BUT *ANCHORAGE* IS NOT PRESENT AT EVERY *RAIL VERT*. BECAUSE SPECIFIC *ANCHORAGE* PLAN LOCATIONS ARE LAID OUT BY FABRICATOR, "ANV" ELEVATION HAS BEEN PROVIDED FOR ALL *RAIL VERTS*.

RAIL VERT TYPE LEGEND

"#" SYMBOL REPRESENTS A NUMBER

P0# - POINT AT CENTERPOINT OF *RAIL VERT* SEGMENT, LOCATED AT EITHER: *RAIL VERT ENDS* (TOP/BOTTOM) OR *RAIL VERT BREAKS*.

P0#V - POINT VERTICAL DISTANCE TO *BASELINE ELEVATION*

L0# - *RAIL VERT* SEGEMENT (LEG) OR LENGTH OF SEGMENT (LEG)

H0# - *RAIL HORIZONTAL*

H0#V - *RAIL HORIZONTAL* VERTICAL DISTANCE TO *BASELINE ELEVATION*

A0# - ANGLE BETWEEN ADJACENT *RAIL VERT* SEGMENTS

AN01 - CENTERLINE OF *ANCHORAGE*

ANV - *ANCHORAGE* VERTICAL DISTANCE TO *BASELINE ELEVATION*

RAIL REFERENCE

1. RE: A01.00 FOR PROJECT TERMINOLOGY.

2. RE: RAIL ELEVATIONS FOR:
   a. *RAIL VERT LAYOUT*
   b. *RAIL HORIZONTAL* LAYOUT
   c. *RAIL VERT BREAK* LAYOUT.

3. RE: 1 / A06.10 FOR:
   a. *RAIL VERT* CONFIGURATION TYPES.

4. RE: RAIL SCHEDULES FOR:
   a. *RAIL VERT* VERTICAL LOCATION RELATIVE TO EACH RAIL RUN BASELINE ELEVATION
   b. *RAIL VERT* LEG LENGTHS
   c. *RAIL VERT BREAK* ANGLES
   d. *ANCHORAGE* LOCATIONS
   e. *RAIL HORIZONTAL* LOCATIONS

RAIL VERT ID LOGIC

WN134B

BRIDGE CODE:
W = WEST
E = EAST

RAIL RUN CODE:
N = NORTH
S = SOUTH
M = MIDDLE

NUMBER IN SEQUENCE (LEFT TO RIGHT)

RAIL VERT TYPE
RE: 1 / A06.10

RELEASE FOR CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/05/2021

GBA
9801 Renner Blvd. Ste. 300
Lenexa, KS 66219
913.492.0400
gbateam.com

EAST BRIDGE PLANS

View High Dr, View High Pkwy, River Rd
Lee's Summit, MO

REV	DATE	DESCRIPTION

STATE OF MISSOURI
CRAIG DEROY ROGGE
NUMBER A-905244
REGISTERED ARCHITECT
10.13.2020

PROJECT NUMBER
12720.62

DATE
2020.10.13
ISSUE FOR CONSTRUCTION

DESIGNED: NJC
DRAWN: NJC
REVIEWED: CLR

SHEET TITLE
SCHEDULE - EAST BRIDGE RAIL VERTS - MIDDLE RAIL RUN

SHEET NUMBER
A06.16

Plotted 10/13/2020 10:35:55 AM -- BIM 360://12720.62 ParagonStar_Bridges/12720.61_ParagonStar_Bridges_Site.rvt