



RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/08/2021




ROOF PLAN
1/8" = 1'-0"
SIDE TO SIDE 9/12
FRONT TO BACK 8/12
RAFTERS 2 X 6 DF NO 2 @ 16" OC
HIPS AND RIDGES 2 X 8 DF NO 2



FRONT EL.
STUCCO AND STONE




REAR EL.
1/8" = 1'-0"



LEFT EL.
1/8" = 1'-0"

3 SIDES LP PANEL
SIDING



RIGHT EL.
1/8" = 1'-0"



BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.


TRUMARK HOMES
KYLE VIII
LOT 69 WOODSIDE RIDGE
2038 NW O BRIEN
LEE SUMMIT MO

SCALE
1/4" = 1'-0"

DATE
2-26-21

PLAN NO.
3417

SHEET NO.
1 OF 6



**BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.**

TRUMARK HOMES
KYLE VIII
LOT 69 WOODSIDE RIDGE
2038 NW O BRIEN
LEE SUMMIT MO

SCALE
1/4" = 1'-0"


DATE
2-26-21

PLAN NO.


3417

SHEET NO.

2 OF 6




THE GREAT SEAL OF THE STATE OF MISSISSIPPI
1821



- DETAIL NOTES:
1. FLOORWALL FRAMING AND ANCHORAGE ABOVE PER STRUCTURAL PLAN.
 2. MIN. 3/4" COVER FOR FOUNDATION WALL REINFORCEMENT.
 3. FOOTING TO BEAR ON UNEXCAVATED EARTH OR WELL COMPACTED FILL PER STRUCTURAL PLAN.
 4. EXPANSION JOINT(S) PER TYPICAL PRACTICE.

HELIX REINFORCED CONCRETE.
SEE NOTES ON FOUNDATION
PLAN
FOUNDATION WALL
PER STRUCTURAL PLAN

SLAB PER STRUCTURAL
PLAN
GRAVEL FILL PER STRUCTURAL
PLAN




1 TYPICAL FOUNDATION WALL

S101

- DETAIL NOTES:
1. FLOORWALL FRAMING AND ANCHORAGE ABOVE PER STRUCTURAL PLAN.
 2. MIN. 3/4" COVER FOR FOUNDATION WALL REINFORCEMENT.
 3. FOOTING TO BEAR ON UNEXCAVATED EARTH OR WELL COMPACTED FILL PER STRUCTURAL PLAN.
 4. EXPANSION JOINT(S) PER TYPICAL PRACTICE.

HELIX REINFORCED CONCRETE.
SEE NOTES ON FOUNDATION
PLAN
FOUNDATION WALL
PER STRUCTURAL PLAN

SLAB PER STRUCTURAL
PLAN
GRAVEL FILL PER STRUCTURAL
PLAN



2 TYPICAL FOUNDATION WALL w/ STRUCTURAL SLAB ADJACENT

S101


RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
03/08/2021

STRUCTURAL SLAB DOWEL CONNECTION:
#4 DOWELS AT 12" O.C. DRILL INTO WALL MIN.
5" AND EPOXY
TOP OF SLAB TO BE FIELD DETERMINED OR
PER THE ARCHITECTURAL DRAWINGS
IF PRESENT, SLAB/GRAVEL FILL PER THE
STRUCTURAL PLAN

FOOTING PER STRUCTURAL PLAN WITH:
MIN. 24" LONG #4 DOWELS EMBED MIN. 6"
INTO FOOTING @ MAX. 24" O.C.
CONTINUOUS REINFORCEMENT IF/AS
NEEDED PER LOCAL JURISDICTIONAL
REQUIREMENTS
FOOTING TO
EXTEND BELOW
FROST LINE

- DETAIL NOTES:
1. FLOORWALL FRAMING AND ANCHORAGE ABOVE PER STRUCTURAL PLAN.
 2. MIN. 3/4" COVER FOR FOUNDATION WALL REINFORCEMENT.
 3. FOOTING TO BEAR ON UNEXCAVATED EARTH OR WELL COMPACTED FILL PER STRUCTURAL PLAN.
 4. EXPANSION JOINT(S) PER TYPICAL PRACTICE.

HELIX REINFORCED CONCRETE.
SEE NOTES ON FOUNDATION
PLAN
FOUNDATION WALL
PER STRUCTURAL PLAN



3 TYPICAL STEM WALL w/ STRUCTURAL SLAB ADJACENT


S101

STRUCTURAL SLAB DOWEL CONNECTION:
#4 DOWELS AT 12" O.C. DRILL INTO WALL MIN.
5" AND EPOXY
TOP OF SLAB TO BE FIELD DETERMINED OR
PER THE ARCHITECTURAL DRAWINGS
IF PRESENT, SLAB/GRAVEL FILL PER THE
STRUCTURAL PLAN

FOOTING PER STRUCTURAL PLAN WITH:
MIN. 24" LONG #4 DOWELS EMBED MIN. 6"
INTO FOOTING @ MAX. 24" O.C.
CONTINUOUS REINFORCEMENT IF/AS
NEEDED PER LOCAL JURISDICTIONAL
REQUIREMENTS
FOOTING TO
EXTEND BELOW
FROST LINE

- DETAIL NOTES:
1. FLOORWALL FRAMING AND ANCHORAGE ABOVE PER STRUCTURAL PLAN.
 2. MIN. 3/4" COVER FOR FOUNDATION WALL REINFORCEMENT.
 3. FOOTING TO BEAR ON UNEXCAVATED EARTH OR WELL COMPACTED FILL PER STRUCTURAL PLAN.
 4. EXPANSION JOINT(S) PER TYPICAL PRACTICE.

HELIX REINFORCED CONCRETE.
SEE NOTES ON FOUNDATION
PLAN
FOUNDATION WALL
PER STRUCTURAL PLAN



4 TYPICAL STEM WALL w/ MULTIPLE STRUCTURAL LEDGES


S101

STRUCTURAL SLAB DOWEL CONNECTION:
#4 DOWELS AT 12" O.C. DRILL INTO WALL MIN.
5" AND EPOXY
TOP OF SLAB TO BE FIELD DETERMINED OR
PER THE ARCHITECTURAL DRAWINGS
IF PRESENT, SLAB/GRAVEL FILL PER THE
STRUCTURAL PLAN

FOOTING PER STRUCTURAL PLAN WITH:
MIN. 24" LONG #4 DOWELS EMBED MIN. 6"
INTO FOOTING @ MAX. 24" O.C.
CONTINUOUS REINFORCEMENT IF/AS
NEEDED PER LOCAL JURISDICTIONAL
REQUIREMENTS
FOOTING TO
EXTEND BELOW
FROST LINE

- DETAIL NOTES:
1. FLOORWALL FRAMING AND ANCHORAGE ABOVE PER STRUCTURAL PLAN.
 2. MIN. 3/4" COVER FOR FOUNDATION WALL REINFORCEMENT.
 3. FOOTING TO BEAR ON UNEXCAVATED EARTH OR WELL COMPACTED FILL PER STRUCTURAL PLAN.
 4. EXPANSION JOINT(S) PER TYPICAL PRACTICE.

HELIX REINFORCED CONCRETE.
SEE NOTES ON FOUNDATION
PLAN
FOUNDATION WALL
PER STRUCTURAL PLAN




5 TYPICAL STEM WALL w/ SLAB-ON-GRADE ADJACENT

S101

SLAB PER STRUCTURAL PLAN:
TOP OF SLAB TO BE FIELD DETERMINED OR
PER THE ARCHITECTURAL DRAWINGS
GRAVEL FILL PER STRUCTURAL PLAN
SLAB TO BEAR ON UNEXCAVATED EARTH OR
WELL COMPACTED FILL PER STRUCTURAL
PLAN

FOOTING PER STRUCTURAL PLAN WITH:
MIN. 24" LONG #4 DOWELS EMBED MIN. 6"
INTO FOOTING @ MAX. 24" O.C.
CONTINUOUS REINFORCEMENT IF/AS
NEEDED PER LOCAL JURISDICTIONAL
REQUIREMENTS
FOOTING TO
EXTEND BELOW
FROST LINE




6 TYPICAL THICKENED SLAB

S101

- DETAIL NOTES:
1. FLOORWALL FRAMING AND ANCHORAGE ABOVE PER STRUCTURAL PLAN.
 2. MIN. 3/4" COVER FOR FOUNDATION WALL REINFORCEMENT.
 3. FOOTING TO BEAR ON UNEXCAVATED EARTH OR WELL COMPACTED FILL PER STRUCTURAL PLAN.
 4. EXPANSION JOINT(S) PER TYPICAL PRACTICE.

HELIX REINFORCED CONCRETE.
SEE NOTES ON FOUNDATION
PLAN
FOUNDATION WALL
PER STRUCTURAL PLAN

SLAB PER STRUCTURAL
PLAN
GRAVEL FILL PER STRUCTURAL
PLAN



7 TYPICAL FOUNDATION WALL w/ STRUCTURAL SLAB BEARING ALTERNATIVE

S101

STRUCTURAL SLAB BEARING CONDITION:
TOP OF SLAB TO BE FIELD DETERMINED OR
PER THE ARCHITECTURAL DRAWINGS
IF PRESENT, SLAB/GRAVEL FILL PER THE
STRUCTURAL PLAN

FOOTING PER STRUCTURAL PLAN WITH:
MIN. 24" LONG #4 DOWELS EMBED MIN. 6"
INTO FOOTING @ MAX. 24" O.C.
CONTINUOUS REINFORCEMENT IF/AS
NEEDED PER LOCAL JURISDICTIONAL
REQUIREMENTS
FOOTING TO
EXTEND BELOW
FROST LINE

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.

TRUMARK HOMES
KYLE VILL
LOT 69 WOODSIDE RIDGE
2038 NW O BRIEN
LEE SUMMIT MO

SCALE
1/4" = 1'-0

DATE
2-26-21


PLAN NO.
3417

SHEET NO.
3 OF 6





4 OF 6



ALL POINT LOADS SHALL HAVE A MINIMUM OF 2 STUDS UNLESS NOTED OTHERWISE

OF 6







TABLE R602.10.3(1) BRACING REQUIREMENTS BASED ON WIND SPEED					
EXPOSURE CATEGORY 2 30-FOOT MEAN ROOF HEIGHT 10-FOOT WALL HEIGHT 2 BRACED WALL LINES		MINIMUM TOTAL LENGTH (FEET) OF BRACED WALL PANELS REQUIRED ALONG EACH BRACED WALL LINE ^a			
Ultimate Design Wind Speed (mph)	Story Location	Braced Wall Line Spacing (feet)	Method LFB ^b	Method GB	Methods DWB, WSP, SFB, PBS, FCP, HPS, BV-WSP, ABW, PFH, FPG, CS-SFB
≤ 115		10	3.5	3.5	2.0
		20	6.5	6.5	3.5
		30	9.5	9.5	5.5
		40	12.5	12.5	7.0
		50	15.0	15.0	9.0
		60	18.0	18.0	10.5
		10	7.0	7.0	4.0
		20	12.5	12.5	7.5
		30	18.0	18.0	10.5
		40	23.5	23.5	13.5
		50	29.0	29.0	16.5
		60	34.5	34.5	20.0
		10	NP	10.0	6.0
		20	NP	18.5	11.0
		30	NP	27.0	15.5
		40	NP	35.0	20.0
		50	NP	43.0	24.5
		60	NP	51.0	29.0





FIGURE R602.10.6.1
METHOD ABW—ALTERNATE BRACED WALL PANEL



4 mm, 1 foot = 304.8 mm.

FIGURE R602.10.8.2
METHOD PFH—PORTAL FRAME WITH HOLD-DOWNS


TABLE R602.10.4 BRACING METHODS				
METHODS, MATERIAL	MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA ^a	
			Fasteners	Spacing
LFB Let-in-bracing	1 x 4 wood or approved metal strips at 45° to 60° angles for maximum 16" stud spacing		Wood: 2-8d common nails or 3-8d (2 1/2" long x 0.113" dia.) nails Metal strap: per manufacturer	Wood: per stud and top and bottom plates Metal: per manufacturer
DWB Diagonal wood boards	1/2" (1" nominal) for maximum 24" stud spacing		2-8d (2 1/2" long x 0.113" dia.) nails or 2 - 1 1/2" long staples	Per stud
WSP Wood structural panel (See Section R604)	1/4"		Exterior sheathing per Table R602.3(2) Interior sheathing per Table R602.3(1) or R602.3(2)	6" edges 12" field Varies by fastener
BV-WSP Wood structural panels with stone or masonry veneer (See Section R602.10.6.5)	1/16"	See Figure R602.10.6.5	8d common (2 1/4" x 0.131) nails or	4" at panel edges 12" at intermediate supports 4" at braced wall panel end posts
SFB Structural fiberboard sheathing	1/2" or 3/4" for maximum 16" stud spacing		1 1/2" long x 0.12" dia. (for 1/2" thick sheathing) 1 1/2" long x 0.12" dia. (for 3/4" thick sheathing) galvanized roofing nails	3" edges 6" field
GB Gypsum board	1/2"		Nails or screws per Table R602.3(1) for exterior locations Nails or screws per Table R702.3.5 for interior locations	For all braced wall panel locations: 7" edges (including top and bottom plates) 7" field
PBS Particleboard sheathing (See Section R605)	3/8" or 1/2" for maximum 16" stud spacing		For 3/8" 6d common (2" long x 0.113" dia.) nails For 1/2" 8d common (2 1/2" long x 0.131" dia.) nails	3" edges 6" field
FCP Portland cement plaster	See Section R703.7 for maximum 16" stud spacing		1 1/2" long, 11 gage, 1/8" dia. head nails or 1/4" long, 16 gage staples	6" o.c. on all framing members
HPS Hardboard panel siding	1/16" for maximum 16" stud spacing		0.092" dia., 0.225" dia. head nails with length to accommodate 1 1/4" penetration into studs	4" edges 8" field
ABW Alternate braced wall	1/4"		See Section R602.10.6.1	See Section R602.10.6.1

TABLE R602.10.5 MINIMUM LENGTH OF BRACED WALL PANELS						
METHOD (See Table R602.10.4)	MINIMUM LENGTH ^a (inches)					CONTRIBUTING LENGTH (inches)
	8 feet	9 feet	10 feet	11 feet	12 feet	
DWB, WSP, SFB, PBS, FCP, HPS, BV-WSP	48	48	48	53	58	Actual ^b
GB	48	48	48	53	58	Double sided = Actual Single sided = 0.5 x Actual
LFB	55	62	69	NP	NP	Actual ^b
ABW	SDC A, B and C, ultimate design wind speed < 140 mph	28	32	34	38	42
	SDC D ₁ , D ₂ and D ₃ , ultimate design wind speed < 140 mph	32	32	34	NP	NP
CS-G	Adjacent clear opening height (inches)	24	27	30	33	36
CS-WSP, CS-SFB	≤ 64	24	27	30	33	36
	68	26	27	30	33	36
	72	27	27	30	33	36
	76	30	29	30	33	36
	80	32	30	30	33	36
	84	35	32	32	33	36
	88	38	35	33	33	36
	92	43	37	35	35	36
	96	48	41	38	36	36
	100	—	44	40	38	38
	104	—	49	43	40	39
	108	—	54	46	43	41
	112	—	—	50	45	43
	116	—	—	55	48	45
	120	—	—	60	52	48
	124	—	—	—	56	51
	128	—	—	—	61	54
	132	—	—	—	66	58
METHOD (See Table R602.10.4)	Portal header height					
	8 feet	9 feet	10 feet	11 feet	12 feet	
PFH	Supporting roof only	16	16	16	Note c	Note c
	Supporting one story and roof	24	24	24	Note c	Note c
FPG		24	27	30	Note d	Note d
CS-PF	SDC A, B and C	16	18	20	Note c	Note e
	SDC D ₁ , D ₂ and D ₃	16	18	20	Note c	Note e

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s.
NP = Not Permitted.
a. Linear interpolation shall be permitted.
b. Use the actual length where it is greater than or equal to the minimum length.
c. Maximum header height for PFH is 10 feet in accordance with Figure R602.10.6.2, but wall height shall be permitted to be increased to 12 feet with pony wall.
d. Maximum header height for FPG is 10 feet in accordance with Figure R602.10.6.3, but wall height shall be permitted to be increased to 12 feet with pony wall.
e. Maximum header height for CS-PF is 10 feet in accordance with Figure R602.10.6.4, but wall height shall be permitted to be increased to 12 feet with pony wall.

TABLE R602.10.4—continued BRACING METHODS				
METHODS, MATERIAL	MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA ^a	
			Fasteners	Spacing
PFH Portal frame with hold-downs	1/4"		See Section R602.10.6.2	See Section R602.10.6.2
FPG Portal frame at garage	1/16"		See Section R602.10.6.3	See Section R602.10.6.3
CS-WSP Continuously sheathed wood structural panel	1/4"		Exterior sheathing per Table R602.3(2) Interior sheathing per Table R602.3(1) or R602.3(2)	6" edges 12" field Varies by fastener
CS-G ^b Continuously sheathed wood structural panel adjacent to garage openings	1/8"		See Method CS-WSP	See Method CS-WSP
CS-PF Continuously sheathed portal frame	1/8"		See Section R602.10.6.4	See Section R602.10.6.4
CS-SFB ^c Continuously sheathed structural fiberboard	1/2" or 3/4" for maximum 16" stud spacing		1 1/2" long x 0.12" dia. (for 1/2" thick sheathing) 1 1/2" long x 0.12" dia. (for 3/4" thick sheathing) galvanized roofing nails	3" edges 6" field

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 degree = 0.0175 rad, 1 pound per square foot = 47.8 N/m², 1 mile per hour = 0.447 m/s.
a. Adhesive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Categories C, D₁, D₂ and D₃.
b. Applies to panels next to garage door opening where supporting gable end wall or roof load only. Shall only be used on one wall of the garage. In Seismic Design Categories D₁, D₂ and D₃ roof covering dead load shall not exceed 3 psf.
c. Garage openings adjacent to a Method CS-G panel shall be provided with a header in accordance with Table R602.7(1). A full-height clear opening shall not be permitted adjacent to a Method CS-G panel.
d. Method CS-SFB does not apply in Seismic Design Categories D₁, D₂ and D₃.
e. Method applies to detached one- and two-family dwellings in Seismic Design Categories D₁ through D₃ only.



For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

FIGURE R602.10.6.4
METHOD CS-PF—CONTINUOUSLY SHEATHED PORTAL FRAME PANEL CONSTRUCTION

BUILD IN ACCORDANCE WITH
2018 INTERNATIONAL
RESIDENTIAL CODE AND
LOCAL CODES.

TRUMARK HOMES
KYLE VITI
LOT 69 WOODSIDE RIDGE
2038 NW O BRIEN
LEE SUMMIT MO

SCALE
1/4" = 1'-0"

DATE
2-26-21

PLAN NO.

3417

SHEET NO.

6 OF 6

