



Automotive Sales and Detail Center
2100 NE Independence Ave.
Lee's Summit, Missouri 64064

a new facility for

copyright:

The following documents are the sole property of davidson architecture & engineering, llc for the specific purpose of construction of said building. These documents are considered confidential and subject to davidson architecture & engineering llc's copyright protection. Neither receipt nor possession transfers any rights to reproduce these documents or any part thereof. Any re-use of these documents without the express written permission of davidson architecture & engineering, llc is strictly prohibited and shall confer no liability to davidson architecture & engineering, llc.

disclaimer:

These documents are accurate to the best of davidson architecture & engineering, llc's professional knowledge. In the event a discrepancy in the documents is encountered, it is the responsibility of that party to notify davidson architecture & engineering in a timely manner, for corrections and/or explanation of the documents.

project description:

New building for used automotive sales and detailing

code review:

governing municipality: Lee's Summit, Missouri
governing code: 2018 IBC, 2018 IMC, 2018 IPC, 2018 IFGC, 2018 IFC, 2017 NEC, ADA.ANSI 117.1

zoning: CP-2
site area: 175,306 sq. ft. (±4.02 acres)
first floor building area: 12,475 sq. ft.
building mezzanine area: 1,385 sq. ft.
total building area: 13,860 sq. ft.
floor area ratio: 0.08
business description: automobile sales and detailing
construction type: IIB
occupancy type: B (Business, S-1 (Auto Shop))
stories: 1 story with mezzanine
building height: 28'-8"
fire suppression: yes
tabular area: 17,500 sq. ft. (S-1)
sprinkler increase: 300% = 52,500 sq. ft.
total allowable area: 70,000 sq. ft.
total building area: 14,376 sq. ft.
first floor area: 12,944 sq. ft.
mezzanine area: 1,432 sq. ft.

occupant load:
first floor:
B 4,215 sq. ft. / 150 = 28 occ.
S-1 8,729 sq. ft. / 300 = 29 occ.
first floor total: 57 occupants
mezzanine
B 930 sq. ft. / 150 = 7 occ.
training rm. 502 sq. ft. / 15 = 34 occ.
mezz. total: 41 occupants

Total building occupants: 98 occupants

plumbing fixtures required:
B 2 water closets
2 lavatories
1 drinking fountains
1 mop sink

S-1 1 water closet
1 lavatory
1 drinking fountain
1 mop sink

req'd plumbing fixtures: 3 water closets
3 lavatories
2 drinking fountains
1 mop sink

plumbing fixtures provided: 4 water closets
4 lavatories
2 drinking fountains
2 mop sinks

exit width required: 98 x 0.2" = 20"
exit width provided: 1 main exit = 68" clear
6 man doors @ 34" = 204"

max. exit access travel distance with sprinkler system (2018 IBC table 1017.2):
B: 300'
S-1: 250'
all paths in building are less than the max. allowable distance

exit from mezzanine - 41 occupants (less than 49), 1 stair required and provided

sheet index:

A0.0	cover sheet
<u>Civil</u>	
C1.0	civil cover sheet
C1.1	notes
C1.2	site plan
C1.3	utility plan
C2.1	grading plan
C2.2	erosion control plan
C2.3	erosion control plan
C2.4	spot elevation plan
C2.5	details
C2.6	details
C3.1	existing drainage map
C3.2	proposed drainage map
C3.3	storm plan
C4.1	details
C4.2	details
C4.3	details
C4.4	details
<u>Architecture</u>	
L1.1	landscape plan and details
A1.1	site plan
A2.1	floor plan
A2.2	mezzanine floor plan
A2.3	roof plan
A2.4	reflected ceiling plan
A2.5	reflected mezzanine ceiling plan
A3.1	exterior elevations
A3.2	details
A4.1	building sections
A4.2	wall sections
A4.3	wall sections
A4.4	wall sections
A4.5	wall sections
A4.6	stair section and details
A4.7	details
A5.1	door schedule and details
A5.2	room finish schedule and elevations
A5.3	interior elevations and details
A5.4	details and door hardware schedule
A5.5	interior finish plans
<u>Structural</u>	
S0.0	general notes
S0.1	isometric
S0.01	general notes
S1.1	foundation plan
S2.1	mezzanine framing plan
S2.2	roof framing plan
S3.1	typical foundation details
S3.2	foundation details
S4.1	typical framing details
S4.2	typical framing details
S4.3	typical framing details
S4.4	typical framing details
S4.5	framing details
S4.6	masonry elevations
S4.7	masonry elevations
<u>Mechanical/Plumbing</u>	
MP0.0	mechanical and plumbing specifications
MP0.1	mechanical and plumbing specifications
P1.0	plumbing first floor waste and vent plan
P1.1	plumbing mezzanine waste and vent plan
P2.0	plumbing water and gas plan
P3.0	plumbing schedule and details
M1.0	mechanical first floor plan
M1.1	mechanical mezzanine plan
M2.0	mechanical schedules and details
<u>Electrical</u>	
E100	electrical site plan
E101	lighting plans
E102	power plans
E103	electrical roof plan
E201	electrical schedules

client:

Lee's Summit Town Center, LLC
Bob Balderston
3200 NW South Outer Road
Lee's Summit, MO 64105

architect:

Powell Minnis, RA
Davidson Architecture & Engineering
4301 Indian Creek Parkway
Overland Park, Kansas 66207
p: 913.451.9390 f: 913.451.9391

civil engineer:

Paul A. Miller, P.E.
Davidson Architecture & Engineering
4301 Indian Creek Parkway
Overland Park, Kansas 66207
p: 913.451.9390 f: 913.451.9391

structural engineer:

Ryan Shafer, P.E.
BSE Structural Engineers
11320 W. 79th Street
Overland Park, Kansas 66214
p: 913.492.7400

mechanical:

Mark Bessmer
Henry Miller Mechanical
6609 Royal Street
Pleasant Valley, Missouri 64068
p: 816.883.8818

plumbing:

Mark Miller
Henry Miller Mechanical
6609 Royal Street
Pleasant Valley, Missouri 64068
p: 816.883.8818

electrical:


Ernie Cota
KASA Electric, LLC
1206 NW Valley Ridge Drive
Grain Valley, Missouri 64029
p: 816.228.4886

general contractor

Rothwell Construction, Inc.
1500 NW Hwy 7
Blue Springs, Missouri 64014
p: 816.228.8808 f: 816.228.8843



Commercial Development Plan for Detail Facility – Balderston Section 29, Township 48 North, Range 31 West City of Lee's Summit, Jackson County, Missouri



2 Vicinity Map
 No Scale

- Local Benchmarks:** BM-#
- BM-1:** Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656
 - BM-2:** Storm Structure, Manhole Cover
 Elevation: 982.06'
 N: 101382.1725
 E: 2827403.8100

- Utility Contacts**
- Sanitary – City of Lee's Summit – phone (816) 969-1900
 - Water – City of Lee's Summit – phone (816) 969-1900
 - Storm Sewer – City of Lee's Summit – phone (816) 969-1800
 - Electric – Evergy – phone (888) 471-5275
 - Gas – Spire – phone (816) 756-5252
 - Telephone – At&T – phone (800) 464-7928
 - Cable – Spectrum – phone (816) 358-8833

Floodplain Note:
 The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C0430G, Revision Date: January 20, 2017.


- Property Legend**
- right of way
 - property lines
 - easements
 - setbacks

- Grading Legend**
- existing minor contour
 - existing major contour
 - proposed minor contour
 - proposed major contour

- Utility Legend**
- existing
 - proposed

- Linetypes**
- sanm sanitary main
 - sans sanitary service
 - ssm storm sewer (existing)
 - ssms storm sewer (solid wall, proposed)
 - stms storm sewer (solid wall, proposed)
 - stms storm sewer (perforated, proposed)
 - wrm water main
 - wrf water service (fire)
 - wrd water service (domestic)
 - wri water service (irrigation)
 - gasm natural gas main
 - gass natural gas service schematic
 - elpu underground primary electric
 - elsu underground secondary electric
 - elpo overhead electric
 - datu underground cable/phone/data
 - datu underground cable/phone/data service
 - fence-chainlink
 - fence-wood
 - fence-barbed wire
 - treeline

- Symbols**
- sanitary manhole
 - service cleanout
 - force main release valve
 - rectangular structure
 - circular structure
 - fire hydrant
 - water valve
 - water meter
 - backflow preventer
 - natural gas meter
 - service transformer (pad mount)
 - primary switch gear
 - light pole
 - cable/phone/data junction box
 - street light
 - pedestrian street light
 - electric pole
 - guy wire
 - end section



1 Location Map
 1"=60'

- General Notes**
- All work within the road right-of-way shall conform to the technical specifications and design criteria for public improvement projects of the city of Lee's Summit, MO.
 - Erosion Control shall be per the Erosion and Sediment Control Program Manual of the City of Lee's Summit, MO.
 - All work and materials shall be subject to inspection and approval by the owner or the owner's representative. Any change or deviation from these plans must be authorized by the owner or the owner's representative.
 - All traffic control in connection with construction in the right-of-way shall be in conformance with the Manual of Uniform Traffic Control Devices.
 - The contractor shall be required to provide a stabilized construction entrance to prevent mud from being deposited onto adjacent roads.
 - The contractor shall be responsible for obtaining all required permits, paying all fees, and otherwise complying with all applicable regulations governing the project.
 - The contractor shall protect from damage or injury all property including survey monuments, property markers, benchmarks, etc. Items damaged shall be reset by a professional land surveyor licensed in the state of Missouri, at the contractor's expense.
 - The contractor shall be responsible for the restoration of the right-of-way and for damaged improvements such as curbs, sidewalks, street light and traffic signal junction boxes, traffic signal loop lead-ins, signal poles, etc. Damaged improvements shall be repaired in conformance with the latest city standards and to the city's satisfaction.
 - The contractor shall sod all disturbed areas within the public street right-of-way.
 - Paving shall conform to the soils report, and these drawings, any identified discrepancies shall be brought to the attention of the engineer.
 - Contractor shall provide 48-hour notification to the city engineering division to schedule all required inspections.
 - All concrete for public improvements shall comply with the Standards and Specifications of the Kansas City Metropolitan Materials Board (KCMMB). Structural concrete shall be 5,000 psi and nonstructural concrete shall be 4,000 psi.
 - A right-of-way work permit and/or street excavations permit shall be obtained by the contractor to complete all utility work within the public street right-of-way.

Sheet Index

- C1.0 – Cover Sheet
- C1.1 – Civil Notes
- C1.2 – Site Plan
- C1.3 – Utility Plan
- C2.1 – Grading Plan
- C2.2 – Erosion Control Plan – Phase I
- C2.3 – Erosion Control Plan – Phase II
- C2.4 – Spot Elevation Plan
- C2.5 – ADA Spot Elevation Plan
- C3.1 – Existing Drainage Area Map
- C3.2 – Proposed Drainage Area Map
- C3.3 – Storm Sewer Plan & Profile
- C3.4 – Storm Network Calculations
- C4.1 – Details
- C4.2 – Details
- C4.3 – Details
- C4.4 – Details
- C4.5 – Details

Civil Engineer:

Davidson Architecture & Engineering, LLC
 Mr. Paul A. Miller, P.E.
 4301 Indian Creek Pkwy.
 Overland Park, KS 66207
 Phone: (913) 451-9390
 Email: Paul@davidsonae.com

Owner Information

Lee's Summit Town Center, LLC
 Bob Balderston
 3200 NW South Outer Road
 Lee's Summit, MO 64105
 Phone: 816-229-4400
 Email: bob@hifolksbob.com

Utility Notes

- Boundary information, existing utilities and topographic features shown are based on information supplied by owner, surveyor, and others.
- The existing utility locations shown on these plans are approximate and may not include all utility lines present. The contractor shall be responsible to make One Call and coordinate field location of all existing underground utilities prior to beginning excavation/construction activities.
- The contractor shall be responsible for any damage to any utilities or their structures during excavation/construction activities.
- The contractor shall coordinate and be responsible for connection fees, system development fees, taxes, etc. for all main connections and/or extensions with and from the city and/or respective utility unless otherwise coordinated with the Owner. All utility services for this project shall be coordinated with respective utility company by contractor.
- The contractor shall be responsible for adjusting all at-grade utilities such as manhole covers, valve box covers, etc. to finish grade, whether specifically indicated in these plans or not.
- Utilities shown on the plan with specific elevations and/or structure locations are SUE quality level "B", ie: storm sewer, sanitary sewer, water hydrants & valves, utility poles, etc. All other existing utility information shown is SUE quality level "D", primarily retracement of one-call and city records.

Project Information

governing municipality:	Lee's Summit, Missouri
zoning:	CP-2
site area:	~175,306 s.f. or ~4.02 acres
impervious area:	124,303 s.f. 71% < 80%
green area:	51,003 s.f. 29% > 20%
total building area:	15,993 s.f.
required parking:	service establishment 5 parking spaces per 1,000 s.f. 5 x 16,000 s.f. = 80 parking spaces
actual parking on site:	232 parking spaces

Legal description:

A part of the Northeast Quarter of the Northwest Quarter, Section 29, Township 48 North, Range 31 West, Lee's Summit, Jackson County, Missouri, described as follows:
 Commencing at the Northeast corner of the Northwest Quarter of said Section 29; thence S 1°35'52"W along the East line of the Northeast Quarter of the Northwest Quarter for 991.63 feet to the Point of Beginning; thence S 1°35'52"W continuing along said East line for 330.00 feet to the Southeast corner of the Northeast Quarter of the Northwest Quarter; thence N 88°15'22"W along the South line of the Northeast Quarter of the Northwest Quarter for 561.55 feet to the Southeast corner of LEE'S SUMMIT TOWN CENTRE, LOT 1 & LOT 2, a subdivision of record; thence N 1°42'31"E along the East line of said subdivision for 330.00 feet; thence S 88°15'22"E for 560.91 feet to the Point of Beginning. Subject to the road right-of-way of Independence Avenue. Containing 4.25 acres more or less.

Per Missouri Department of Natural Resources, there are no open permits for Section 29, Township 48 North, Range 31 West, City of Lee's Summit, Jackson County, Missouri for any oil and gas wells under construction, active, inactive, plugged and/or abandoned.

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date: 02.21.2020
 drawn by: SLM
 checked by: PAM
 revisions:
 02.16.2021 FDP

sheet number:
C1.0
 drawing type: fdp
 project number: 19076

General Notes:

- The Contractor shall be responsible for obtaining all required permits, paying all fees, and otherwise complying with all applicable regulations governing the project.
- All materials, workmanship, and construction shall meet or exceed the city standards. Where there is conflict between these plans and standards, the higher quality standard as determined by the engineer shall apply. All work shall be inspected and approved by contractor.
- All work and materials shall be subject to inspection and approval by the owner or the owner's representative. Any change or deviation from these plans must be authorized in writing by the owner or the owner's representative prior to work being completed.
- The work associated with and based on these plans, shall be subject to the requirements of, and conform to, the Municipal Code of Lee's Summit, MO, and the standards and specifications in current use. The standards, specifications, details, and procedures sub-referenced therein are hereby incorporated by reference.
- Lineal foot measurements shown on the plans are horizontal measurements, not slope measurements. All payments shall be made on horizontal measurements.
- No geological information is shown in these plans.
- Prior to commencement of work, the contractor shall notify all utility companies which have facilities in the near vicinity of the construction to be performed.
- All waste material resulting from the project shall be disposed of off-site in an approved landfill. All excavation shall be unclassified. No separate payment will be made for rock excavation. Contractor is responsible for all haul off material.
- The Contractor shall be required to provide a stabilized construction entrance to prevent mud from being deposited onto adjacent roads.
- All mud, dirt, and debris tracked onto the parking lot or any roadway shall be removed immediately by the contractor.
- The Contractor shall be responsible for keeping the public streets in the vicinity of the job site clean and free of rocks, soil and debris. Streets and/or parking areas will be scraped and swept on a daily basis by the general contractor.
- The Contractor shall protect from damage all survey monuments, property markers, benchmarks, etc. Items damaged shall be reset by a professional land surveyor licensed in the state of Missouri, at the contractor's expense.
- Paving shall conform to the geotechnical report and these drawings, any identified discrepancies shall be brought to the attention of the engineer immediately. If no geotech. report is provided for the project, the contractor shall use the minimum design standards as required by the city.
- The Contractor shall notify the City of Lee's Summit Development Engineering Inspection at (816) 969-1200 at least 48 hours prior to commencement of any construction.
- All concrete for public improvements shall comply with the city standards and specifications. If no city standards and specifications are provided, then the contractor shall comply with the standards and specifications of the Kansas City Metropolitan Materials Board (KCMMB) unless otherwise noted. Structural concrete shall be 5,000 psi and nonstructural concrete shall be 4,000 psi.
- The contractor shall be responsible for the restoration of the right-of-way and for damaged improvements such as curbs, sidewalks, street light and traffic signal junction boxes, traffic signal loop lead-ins, signal poles, etc (offsite and onsite). Damaged improvements shall be repaired in conformance with the latest city standards and to the city's satisfaction.
- All work within the road right-of-way shall conform to the technical specifications and design criteria for public improvement projects of the city of Lee's Summit, MO or the transportation department of Missouri. A right-of-way work permit and/or street excavations permit shall be obtained by the contractor if required to complete all work within the public right-of-way.
- All traffic control in connection with construction in the right-of-way shall be in conformance with the Manual of Uniform Traffic Control Devices and/or the jurisdictional authority. It is the contractor's responsibility to obtain a traffic control permit if required.
- All waste materials, trash and construction debris shall be collected and stored in dumpsters. No construction waste shall be buried on site. All hazardous waste materials will be disposed of in the manner specified by local, state and federal regulations. Site personnel shall be instructed in these practices, and the construction manager shall be responsible for seeing that these practices are followed.
- Recommendations made by the geotechnical engineer, to be retained by the owner, and contained in the geotechnical report shall govern project conditions unless noted otherwise. Paving shall conform to the geotechnical report, which itself meets or exceeds City's requirements. Any discrepancies shall be brought to the attention of the engineer.
- The Contractor shall grade areas to provide positive drainage.
- The contractor shall be responsible for the coordination of work between suppliers and subcontractors involved in the project, including staging of construction details.
- All disturbed areas shall be maintained for dust control. Sprinkling tank trucks shall be available at all times & used on on-site disturbed areas, and other areas where dust becomes a problem as a result of construction activity.
- Nothing indicated on these drawings shall relieve the contractor from complying with appropriate safety regulations.

Utility Notes:

- Boundary information, existing utilities and topographic features shown are based on information supplied by owner, surveyor, and others.
- The existing utility locations shown on these plans are approximate and may not include all utility lines present. The contractor shall be responsible to contract "One Call" and coordinate field location of all existing underground utilities prior to beginning excavation/construction activities.
- The contractor shall be responsible for any damage to any utilities or their structures during excavation/construction activities. Utilities include but are not limited to a service such as electricity, communication, water, public transportation (including traffic signals), storm systems, and items provided by a public utility.
- The contractor shall coordinate and be responsible for connection fees, system development fees, taxes, etc. for all main connections and/or extensions with and from the city and/or respective utility unless otherwise coordinated with the Owner. All utility services for this project shall be coordinated with respective utility company by contractor.
- The contractor shall be responsible for adjusting all at-grade utilities such as manhole covers, valve box covers, etc. to finish grade, whether specifically indicated in these plans or not.
- Utilities shown on the plan with specific elevations and/or structure locations are SUE quality level "B", ie: storm sewer, sanitary sewer, water hydrants & valves, utility poles, etc. All other existing utility information shown is SUE quality level "D", primarily retracement of one-call and city records.
- Refer to mechanical, electrical, and plumbing (MEP) plans for utility service sizes and exact locations. Refer to site electric plans for electric construction details.
- Provide temporary support for existing utility lines that are encountered during construction until backfilling is complete.
- Backfill all utility trenches according to the most recent edition of the jurisdictional standards.
- All utilities shall be brought within 5' of the building to connect to plumbing contractors work unless otherwise specified.
- The Contractor shall adjust all utility fixtures, manholes and inlets to finished grade as required.
- The Contractor shall maintain 18" minimum vertical clearance between storm sewer and sanitary sewer pipes and 18" minimum vertical clearance between sanitary sewer and water main unless otherwise specified.
- Contractor shall prevent entry of mud, dirt, debris, and other material into new and existing storm sewer systems. Should any contamination occur during construction, the contractor shall clean at contractor's expense. Upon completion of all storm sewer improvements, all new and existing pipe and structures shall be cleaned out.
- Electrical, lighting, and data conduit layout shown is for graphical purposes only. See MEP plans for more detail.
- The Contractor shall provide all temporary power, process, and utility service bypasses and connections as required.

Erosion Control Notes:

- The installation of the silt fencing, the maintenance of the drainage swales, and the construction of the stabilized entrance shall be completed prior to any clearing and grading of any portions of the site. Disturbed portions of the site where construction activities have permanently ceased shall be stabilized with permanent seeding no later than 14 days after the last construction activity, refer to SWPPP. Roadway swales shall be stabilized with Erosion Control Devices. Once construction activity ceases permanently in an area, that area shall be stabilized with permanent seed and mulch. Only after the entire site has been stabilized, the silt fencing shall be removed.
- The general contractor, or designated Erosion Control Contractor, shall be responsible for construction and maintenance of erosion control devices and practices. The contractor shall be responsible for implementation of, and ensuring compliance of, the project Storm Water Pollution Prevention Plan (SWPPP), a copy of which shall be obtained from the Design Engineer. The SWPPP shall be maintained on site per NPDES requirements and shall be available for review at any time, by any authorized Federal, State, or local review official, as well as the Design Engineer. The general contractor, or designated Erosion Control Contractor, shall also be responsible for ensuring compliance with, and paying any fees associated with, the State of Missouri General Permit for Stormwater Runoff associated with construction activities, a copy of which shall be maintained in the aforementioned SWPPP.
- This project shall be constructed in compliance with the soil erosion and sedimentation control permit, and conform to the standards and specifications of the city of Lee's Summit, MO, prior to any land disturbance changes.
- Erosion and any sedimentation from work on this site shall be contained on the site and not allowed to collect on any offsite areas or in waterways. Waterways include both natural and man-made open ditches, streams, storm drains, lakes and ponds. Refer to erosion control plans for more information.
- The contractor shall be responsible to control downstream erosion and siltation during all phases of construction. Erosion Control work and procedures shall be in place prior to beginning excavation/construction activities. To ensure progressive stabilization of disturbed earth, Erosion control devices shall be staged, installed and maintained throughout land disturbance activities as directed in the drawings, project manual and in accordance with all federal, state and local standards until the site is stabilized.
- The contractor shall implement and maintain Erosion Control Devices as shown in the drawings and project manual before, and at all times during the construction of this project. Any modifications to the devices due to construction or changed conditions shall be complied with as required or as directed by the city of Lee's Summit, MO.
- The contractor shall be responsible for installation and maintenance of all Erosion Control Devices. This includes providing berms, silt fence, or other means to prevent erosion from reaching the right of way and offsite boundaries. In the event the prevention measures are not effective, the contractor shall remove any debris and erosion, restoring the right of way to original or better condition.
- Contractor is to provide erosion protection for all storm sewer inlets.
- If any of the Erosion Control Devices on the site are deemed inadequate or ineffective, the city of Lee's Summit, MO has the right to require additional Erosion Control measures at the expense of the general contractor.
- If any pump-driven dewatering is needed, it shall be discharged through a filter bag over a well-vegetated area. The pump must discharge at a non-erosive velocity. If necessary, an approved energy dissipater may be used.
- Permanent BMP's for any disturbed land area shall be completed by the general contractor within 5 calendar days after final grading or the final earth change has been completed. When it is not possible to permanently stabilize a disturbed area after land disturbance activity ceases, temporary Erosion control devices shall be implemented immediately. All temporary Erosion Control Devices shall be maintained until permanent BMP devices are implemented. All permanent BMP's will be implemented and established before a certificate of compliance is issued.
- Strip topsoil only from those areas that will be disturbed by excavation, filling, road building, or compaction by equipment. Refer to the geotechnical report for depths of stripping. Put sediment basins, diversions, and other controls into place before stripping.
- When topsoiling, maintain needed erosion control practices such as diversions, grade stabilization structures, berm, dikes, level spreaders, waterways and sediment basins.
- Grades on the areas to be topsoiled which have been previously established shall be maintained.
- Bonding - Immediately prior to dumping and spreading of topsoil, loosen the subgrade by discing or scarifying to a depth of at least 4", to permit bonding of the topsoil and subsoil.
- The general contractor shall inspect the Erosion Control Devices once every 14 days under any circumstances, within 24 hours of rainfall, and daily during a prolonged rain event unless otherwise noted in the SWPPP or by the jurisdictional authority. A log of inspection report shall be maintained and accessible in accordance with National Pollution Discharge Elimination System (NPDES) requirements. Any required maintenance shall be provided within 72 hours.
- Install silt fence, inlet filters, and other Erosion Control Devices as indicated in the drawings, per APWA and authority regulations, and at additional affected areas as necessary. Build-up of sediment shall be removed promptly per authorities regulations. If silt fence decomposes or becomes ineffective prior to the end of expected usable life and the barrier is still required, the silt fence shall be replaced promptly. Sediment shall be removed from sediment traps or basins when design capacity has been reduced to 50%. Contractor shall flare the ends of the silt fence uphill in order to temporarily impound runoff.
- Earthen berms shall be regularly inspected, and inspected after each rainfall event. Repairs to earthen berms shall be made immediately. If the earthen berm shows signs of erosion, and it is determined that material must be added to fix the berm, the material shall be properly placed, compacted and reseeded. The berm shall be reseeded and stabilized, as needed, to maintain its soundness whether or not there has been any rainfall.
- Drainage swales shall be inspected regularly and after every rainfall event. Repairs to drainage swales shall be made immediately. If the flow channel and/or outlets show signs of deficiency, the damaged area(s) shall be restabilized and reseeded, as needed, to prevent further damage. If additional measures are needed to eliminate issues, contractor shall notify the engineer for possible modifications.
- Refer to the jurisdictional authority for temporary gravel construction entrance details. If not specified, refer to APWA standards. The entrance and exit areas of the project shall be cleared of all vegetation, roots, and other objectionable material. The gravel shall be placed to the proper dimensions and graded to a smooth and even slope. Construction entrance drainage shall be provided to carry water to a sediment trap or other suitable outlet.

Stockpiling Notes:

- Select stockpile location to avoid slopes and natural drainageways, avoiding traffic routes. On large sites, re-spreading is easier and more economical where topsoil is stockpiled in small piles located near areas where they will be used.
- Sediment Barriers - Use sediment fences or other barriers where necessary to retain sediment.
- Temporary Seeding - Protect topsoil stockpiles by temporarily seeding as soon as possible, not to exceed 14 days, weather permitting, after the formation of the stockpile.
- Permanent Vegetation - If stockpiles will not be used within 12 months, they must be stabilized with permanent vegetation to control erosion and weed growth.
- All stockpiled soils shall be maintained in such a way as to prevent erosion from leaving the site. Silt fence must be installed around the perimeter of the stockpile.

Seeding Notes:

- Seeding shall be as follows unless otherwise stated in the landscape plans.
- Annual rye grass, wheat, or oats should be used for temporary seeding. Apply rye grass at 120lbs. per acre, wheat or oats at 100lbs. per acre.
- A mixture of 65% kentucky bluegrass and 35% chewing fescue or creeping red fescue should be used for permanent seeding. Apply the mixture at 2lbs. per 1000ft².
- Seedbed preparation-Install necessary mechanical erosion and sedimentation control practices before seeding, and complete grading according to the approved plan. Lime and fertilizer needs should be determined by soil test. Apply the lime and fertilizer evenly and incorporate into the top 4"-6" of soil by discing or other suitable means.
- All seeding shall be performed during favorable weather conditions and only during normal and accepted planting seasons when satisfactory growing conditions exist. The planting operations shall not be performed during times of extreme drought, when ground is frozen or during times of other unfavorable climatic conditions unless otherwise approved by owner's representative. The contractor assumes full and complete responsibility for all such plantings and operations.
- Seed should be labeled in accordance with U.S. Department of Agriculture rules and regulations under the federal seed act and comply with the requirements of the Missouri seed law. Labels contain important information on seed purity, germination, and presence of weeds. Weed seed should not exceed 1.0% by weight of the mixture.
- Apply seed uniformly with a cyclone seeder, drill, cultipacker seeder, or hydroseeder. Small grains should be planted no more than 1" deep, and grasses and legumes no more than 1/2".
- Generally, a permanent stand of vegetation cannot be determined to be fully established until soil cover has been maintained for one full year from planting. Inspect seeded areas for failure and make necessary repairs and re-seedings within the same season, if possible.
- The Contractor shall seed all disturbed areas unless otherwise noted by landscape plans. Immediately after seeding, mulch all seeded areas with unweathered small grain straw, spread uniformly at the rate of 1-2 tons per acre or 100lbs (2-3 bales) per 1000ft². The mulch should be anchored with disc type mulch anchoring tool or other means as approved by the jurisdictional authority. Mulch matting may be used in lieu of loose mulch.
- The Contractor shall sod all disturbed areas within the public street right-of-way. Refer to city and state standards for proper installation.

Demolition Notes:

- At the site, the Contractor shall maintain the required documents for immediate review, included but not limited to: Site Safety Plan, Demolition Permits, Street Closure Permits, Contract Documents, Demolition Plans, Salvage Verification Forms, SWPPP Etc.
- The Contractor shall notify all utility companies for field verification and disconnection of utilities prior to any work. Coordination is required for both temporary and permanent utility services that serve the site including, but not limited to: water lines, power, telephone, cable, storm sewer, sanitary sewer with the city and/or respective utility.
- The Contractor is specifically cautioned that the locations and/or elevation of existing utilities as shown on these plans are based on records of the various utility companies, and where possible, measurements taken in the field. The information is not to be relied on as being exact or complete. Contractor shall contact One Call utility information service for utility locates. The Contractor must call the appropriate utility companies at least 72 hours before any excavation to request exact field location of utilities. The Contractor shall also coordinate and allow access for utility companies to perform any disconnection or relocation activities. It shall be the responsibility of the Contractor to relocate all existing utilities which conflict with the proposed improvements shown on the plans.
- Remaining building structures and remaining utility services shall be protected from damage. Damage to any existing features to remain will be replaced at the Contractor's expense.
- Areas disturbed during demolition shall be thoroughly evaluated by the geotechnical engineer responsible for site preparation prior to placement of structural fill. All disturbed soils shall be undercut prior to placement of structural fill, per the geotechnical recommendations. Contractor shall notify the geotechnical engineer at least 72 hours prior to placement of structural fill.
- Excavations created by the removal of any existing utility lines that extend below design grades shall be cut wide enough to allow use of heavy construction equipment to compact the fill. Base of the excavations shall be thoroughly evaluated by the geotechnical engineer prior to placement of fill. If existing utilities are to be left in-place, existing trench backfill shall be evaluated in accordance with the recommendations of evaluation of existing fill.
- The Contractor shall be responsible for obtaining all Federal, State, and local permits, obtaining all inspections, and shall conform to all governing codes and regulations required to perform necessary abatement during demolition, should hazardous materials be encountered.
- Contractor is responsible for legally disposing of all materials and associated cost of interim storage facilities.
- For tree & stump removal, the Contractor shall remove all root systems from the site not designated to be saved. Materials disturbed during removal of stumps shall be undercut and replaced with structural fill. A zone of desiccated soils may exist in the vicinity of the trees. The desiccated soils have a higher swell potential and shall be undercut and replaced with structural fill.
- No construction waste shall be buried on site. All hazardous waste materials will be disposed of in the manner specified by local, state and federal regulations.

Retaining Wall Notes:

- Site retaining wall improvements shall be designed by a licensed professional engineer retained by the contractor. The wall engineer and contractor shall satisfy themselves of the conditions of the surrounding site features and any interactions with the proposed improvements.
- Retaining wall design drawings and specifications shall be provided to the owner and owner's representative for review and approval. All retaining wall designs shall be signed and sealed by a registered Professional Engineer licensed in the state of Missouri. Design services shall be included in retaining wall pricing.
- Refer to Retaining Wall drawings for wall information. Civil plan set shall only be used for general location and spot elevations.
- The Contractor is responsible for coordinating all inspections, certifications, permits, fees and close out of the wall unless otherwise determined. Contractor shall notify wall design engineer for final inspection. Contractor shall include in construction cost for all of the above items related to the installation of the retaining wall.
- Any wall shown is a schematic representation of the proposed walls. The spot elevations denoting retaining walls are provided on the site grading plan.
- If the wall is greater than 30" and is in an accessible area, guard rails are required per code.

Americans with Disabilities Act (ADA) Notes:

- The running and cross slopes for all sidewalks, accessible paths, ramps, designated parking stalls, etc., shall be in compliance with latest Federal ADA guidelines, in addition to any accessibility standards adopted by the governing municipality. Prior to installation/construction, if any discrepancies are found within the plans, the Engineer shall be notified.



4301 Indian Creek Parkway
Overland Park, KS 66067
phone: 813.451.9390
fax: 813.451.9391
www.davidsonae.com



02/16/2021

A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064


date 02.21.2020
drawn by SLM
checked by PAM
revisions

02.16.2021 FDP

sheet number

C1.1

drawing type fdp
project number 19076



A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date: 02.21.2020
 drawn by: SLM
 checked by: PAM
 revisions:
 02.16.2021 FDP

sheet number:
C1.2
 drawing type: fdp
 project number: 19076

Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Floodplain Note:

The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C0430G, Revision Date: January 20, 2017.

Fire Protection Notes:

- Plans and specifications, in accordance with NFPA 24, for the private fire line shall be submitted for review and approval prior to installation.
- Underground fire line installation including thrust blocks shall be inspected prior to being backfilled.
- Hydrostatic testing and flushes shall be completed with the fire department as a witness.

Utility Legend

	existing
	proposed
Linetypes	
	sanitary main
	sanitary service
	storm sewer (existing)
	storm sewer (solid wall, proposed)
	storm sewer (solid wall, proposed)
	storm sewer (perforated, proposed)
	water main
	water service (fire)
	water service (domestic)
	water service (irrigation)
	natural gas main
	natural gas service schematic
	underground primary electric
	underground secondary electric
	overhead electric
	undgrnd cable/phone/data
	undgrnd cable/phone/data service
	fence-chainlink
	fence-wood
	fence-barbed wire
	treeline

Symbols

	sanitary manhole
	service cleanout
	force main release valve
	rectangular structure
	circular structure
	fire hydrant
	water valve
	water meter
	backflow preventer
	natural gas meter
	service transformer (pad mount)
	primary switch gear
	light pole
	cable/phone/data junction box
	street light
	pedestrian street light
	electric pole
	guy wire
	end section

Demolition Notes

- Contractor will coordinate with respective utility all existing utilities that serve the site including but not limited to water lines, power, telephone, cable, storm sewer, sanitary sewer.
- The Contractor is specifically cautioned that the locations and/or elevation of existing utilities as shown on these plans are based on records of the various utility companies, and where possible, measurements taken in the field. The information is not to be relied on as being exact or complete. The Contractor must call the appropriate utility companies at least 72 hours before any excavation to request exact field location of utilities. It shall be the responsibility of the Contractor to relocate all existing utilities which conflict with the proposed improvements shown on the plans.
- The Contractor shall protect offsite improvements (including but not limited to sidewalks, drives, utilities, existing streets, curbs and paving) surrounding the project boundary from demolition damage.
- The Contractor shall notify all utility companies for field verification and disconnection of utilities prior to any work. The Contractor shall contact the One Call utility information service & utility companies for utility locates. The Contractor shall coordinate and allow access for utility companies to perform any disconnection or relocation activities.
- The Contractor shall maintain at the demolition site the required documents for immediate review (IE. Site Safety Plan, Demolition Permits, Street Closure Permits, Contract Documents, Demolition Plans, Salvage Verification Forms, SWPPP Etc.). Inspections of erosion control devices after any rainfall event that causes runoff. Development Engineering Inspection requires copies of the inspections after the site is stabilized.
- Prior to demolition, all applicable erosion control devices are to be installed.
- Damage to any existing features to remain will be replaced at the Contractors expense to exiting or better condition.
- All broken concrete and other debris from demolition shall be removed from the site. Areas disturbed during demolition shall be thoroughly evaluated by the geotechnical engineer responsible for site preparation prior to placement of structural fill. All disturbed soils shall be undercut prior to placement of structural fill, per the geotechnical recommendations.
- The Contractor shall strip all remaining vegetation, topsoil, debris and other unsuitable materials from the proposed construction areas. Stripping depths shall be adjusted to remove all vegetation and root systems. The actual stripping depth shall be based on visual examination by the Geotechnical Engineer. Topsoil removed during stripping operations can be used for final site grading within the landscaped areas. Care shall be exercised to separate these materials to avoid incorporation of the organic matter in structural fill sections.
- For tree & stump removal, the Contractor shall remove all root systems from the site not designated to be saved. Materials disturbed during removal of stumps shall be undercut and replaced with structural fill. A zone of desiccated soils may exist in the vicinity of the trees. The desiccated soils have a higher swell potential and shall be undercut and replaced with structural fill.
- Excavations created by the removal of any existing utility lines that extend below design grades shall be cut wide enough to allow use of heavy construction equipment to compact the fill. Base of the excavations shall be thoroughly evaluated by the geotechnical engineer prior to placement of fill. If existing utilities are to be left in-place, existing trench backfill shall be evaluated in accordance with the recommendations of evaluation of existing fill.

Construction Legend

	concrete pavement
	standard asphalt
	heavy duty asphalt
	concrete sidewalk
	CG-1 standard curb & gutter
	CG-1 standard dry curb & gutter
	CG-2 standard curb & gutter
	CG-2 standard dry curb & gutter

Demolition Legend


	Remove curb
--	-------------

Property Legend

	right of way
	property lines
	easements
	setbacks

Grading Legend

	existing minor contour
	existing major contour
	proposed minor contour
	proposed major contour



Construction Notes:

- Construct standard CG-1 wet or dry concrete curb & gutter per City of Lee's Summit, MO where indicated (see legend). Dry curb is pitched out to not hold water.
- Construct standard CG-2 wet or dry concrete curb & gutter per City of Lee's Summit, MO where indicated (see legend). Dry curb is pitched out to not hold water.
- Construct heavy-duty asphalt pavement, Re: C4.3. (see legend)
- Construct standard-duty asphalt pavement, Re: C4.3 (see legend)
- Construct concrete pavement, Re: C4.3. (see legend)
- Construct concrete sidewalk, Re: C4.2. (see legend)
- Parking, hatching, accessible aisles, and universal symbol to be painted blue with 4" stroke as applicable, typ.
- Construct ADA accessible sidewalk ramp, ramps shall comply with City Standards and Details. Re: C2.5 & C4.5.
- Install ADA parking signage, with one van accessible sign.
- Proposed striping: parking, etc., typ., 4" white stripe per arch plans.
- Trash enclosure, Re: Arch. Plans.
- Match existing pavement elevation
- Remove existing flared end section on 72" CMP storm pipe
- Proposed site lighting by others.
- Construct commercial entrance, per City's standards.
- Construct ~167 L.F. modular block retaining wall. Designed by others.
- Proposed storm sewer see sheet C3.3 for detail (private).

General Notes

- All work and materials shall be subject to inspection and approval by the owner or the owner's representative. Any change or deviation from these plans must be authorized by the owner or the owner's representative.
- All traffic control in connection with construction in the right-of-way shall be in conformance with the Manual of Uniform Traffic Control Devices.
- The contractor shall be required to provide a stabilized construction entrance to prevent mud from being deposited onto adjacent roads.
- The contractor shall be responsible for obtaining all required permits, paying all fees, and otherwise complying with all applicable regulations governing the project.
- The contractor shall protect from damage or injury all property including survey monuments, property markers, benchmarks, etc. Items damaged shall be reset by a professional land surveyor licensed in the state of Missouri, at the contractor's expense.
- The contractor shall be responsible for the restoration of the right-of-way and for damaged improvements such as curbs, sidewalks, street light and traffic signal junction boxes, traffic signal loop lead-ins, signal poles, etc. Damaged improvements shall be repaired in conformance with the latest city standards and to the city's satisfaction.
- The contractor shall sod all disturbed areas within the public street right-of-way.
- Paving shall conform to the soils report, and these drawings, any identified discrepancies shall be brought to the attention of the engineer.
- Contractor shall provide 48-hour notification to the city engineering division to schedule all required inspections.
- All concrete for public improvements shall comply with the Standards and Specifications of the Kansas City Metropolitan Materials Board (KCMMB). Structural concrete shall be 5,000 psi and nonstructural concrete shall be 4,000 psi.
- A right-of-way work permit and/or street excavations permit shall be obtained by the contractor to complete all utility work within the public street right-of-way.

Americans with Disabilities Act (ADA) Notes:

- The running and cross slopes for all sidewalks, accessible paths, ramps, designated parking stalls, etc., shall be in compliance with latest Federal ADA guidelines, in addition to any accessibility standards adopted by the governing municipality. Prior to installation/construction, if any discrepancies are found within the plans, the Engineer shall be notified.





A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.21.2020
 drawn by SLM
 checked by PAM
 revisions
 02.16.2021 FDP
 sheet number
C1.3
 drawing type fdp
 project number 19076

Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Property Legend

- right of way
- - - property lines
- - - easements
- - - setbacks

Grading Legend

- - - existing minor contour
- - - existing major contour
- - - proposed minor contour
- - - proposed major contour

Utility Legend

- existing
- - - proposed

Linetypes

- sanm sanitary main
- sans sanitary service
- ssm storm sewer (existing)
- ssms storm sewer (solid wall, proposed)
- ssms storm sewer (solid wall, proposed)
- ssms storm sewer (perforated, proposed)
- wtrm water main
- wtrf water service (fire)
- wtrd water service (domestic)
- wtri water service (irrigation)
- gasm natural gas main
- gass natural gas service schematic
- elpu underground primary electric
- elss underground secondary electric
- elpo overhead electric
- datu underground cable/phone/data
- datu underground cable/phone/data service
- fence-chainlink
- fence-wood
- fence-barbed wire
- treeline

Symbols

- ⊙ sanitary manhole
- ⊙ service cleanout
- ⊙ force main release valve
- rectangular structure
- circular structure
- ⊕ fire hydrant
- ⊕ water valve
- ⊕ water meter
- ⊕ backflow preventer
- ⊕ natural gas meter
- ⊕ service transformer (pad mount)
- ⊕ primary switch gear
- ⊕ light pole
- ⊕ cable/phone/data junction box
- ⊕ street light
- ⊕ pedestrian street light
- ⊕ electric pole
- ⊕ guy wire
- ⊕ end section

Floodplain Note:


The site lies entirely within "Zone X", areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C0430G, Revision Date: January 20, 2017.

Fire Protection Notes:

- a. Plans and specifications, in accordance with NFPA 24, for the private fire line shall be submitted for review and approval prior to installation.
- b. Underground fire line installation including thrust blocks shall be inspected prior to being backfilled.
- c. Hydrostatic testing and flushes shall be completed with the fire department as a witness

Utility Contacts

- Sanitary - City of Lee's Summit - phone (816) 969-1900
- Water - City of Lee's Summit - phone (816) 969-1900
- Electric - Evergy - phone (888) 471-5275
- Gas - Spire - phone (816) 756-5252
- Telephone - At&T - phone (800) 464-7928
- Cable - Spectrum - phone (816) 358-8833
- Storm Sewer - City of Lee's Summit - phone (816) 969-1800



Utility Notes:

1. Proposed storm sewer see sheet C3.3 for detail (private).
2. Proposed sanitary sewer service
 - Install approx. 116 L.F. 4" PVC SDR-26 from service connection to grinder pump at 2% minimum slope. FL at Bldg = 991.00'
 - Install approx. 49 L.F. 1.25" PVC SDR-11 sanitary sewer service pipe with (2) 45' horiz. and sampling cleanout, from grinder pump to existing public gravity sanitary sewer main. F/L at Pump = 988.68'
 - F/L at public gravity main connection = ~999.32' to be field verified by Contractor.
3. Install E-ONE W Series 48" fiberglass Triplex grinder pump station per manufacturer standards. Install associated uni-strut mounted alarm/disconnect panel adjacent to pump station.
 - Top Elev. = 1001.86'
 - Invert Elev. = 988.68'
4. Install E-ONE Uni-Lateral stainless steel lateral valve on 1.25" force service line per manufacturer standards with heavy duty traffic rated removable cover.
5. Proposed grease/oil interceptor. Install 1,000 gallon precast grease interceptor, with traffic rated line, that meets the requirements set by the City of Lee's Summit Public Works Department. Install approx. 16 L.F. 4" PVC SDR-26 at 2.0% min., from building to grease interceptor. From interceptor, install approx. 10 L.F. 4" PVC SDR-26 at 2.0% min. to WYE on primary waste service line. Install 2" PVC vent pipe from sampling cleanout back to building, see MEP plans for continuation.
 - F/L at Bldg = 991.50'
 - F/L at GI (In) = 991.18'
 - F/L at GI (Out) = 991.00'

Utility Notes:

6. Coordinate with City of Lee's Summit 2" domestic service taps using corporation stop to connect to existing main, by City.
 - Service line from water main shall be 2" Type K soft copper (ASTM B 88) from water main to a distance of 10' beyond the proposed water meter.
 - Install 2" PVC pipe from a distance of 10' beyond the proposed water meter to service connection at building.
 - Re: MEP Plans for continuation at building.
7. Install 1-1/2" water meter as shown in meter pit with gravel bottom for drainage. (private).
8. Install approx. 160 L.F. of 6" C900 private fireline. Connect with 12"x6" TEE and restrained gate valve
 - (1) TEE fitting and (1) fire hydrant & valve assemblies. Thrust blocks to be installed on all fittings
 - Exterior double check detector backflow prevention device to be installed in vault with gravel bottom for drainage
 - Re: MEP Plans for continuation at building.
9. Connect to 6"x6" Tee on private fire line and install approx. 6' C900 fire protection to building.
 - Install Fire Department Connection (FDC) on building at this location
 - Re: MEP Plans for continuation at building.
10. Proposed electrical service. Install approx. 310 L.F. of primary conduit from existing line to transformer pad and 87 L.F. of secondary conduit from transformer to building as shown, per City Standards. Contractor to coordinate with Evergy for electrical service.
11. Proposed natural gas service. Contractor to coordinate with Spire for gas service. Contractor to field verify location of gas main, location shown is approximate.
12. Coordinate telephone and data service with Utility.

Field Survey identified no evidence suggesting presence of any active, inactive or capped oil and/or gas wells on the property





A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.21.2020
 drawn by SLM
 checked by PAM
 revisions
 02.16.2021 FDP

sheet number
C2.1
 drawing type fdp
 project number 19076

Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Grading Legend

- existing minor contour
- - - existing major contour
- proposed minor contour
- - - proposed major contour

Utility Legend

- existing
- - - proposed

Property Legend



- right of way
- - - property lines
- - - easements
- - - setbacks

Linetypes

- sanm sanitary main
- sans sanitary service
- ssm storm sewer (existing)
- ssms storm sewer (solid wall, proposed)
- stms storm sewer (solid wall, proposed)
- stms storm sewer (perforated, proposed)
- wtrm water main
- wtrf water service (fire)
- wtrd water service (domestic)
- wtri water service (irrigation)
- gasm natural gas main
- gass natural gas service schematic
- alpu underground primary electric
- alsu underground secondary electric
- elpe overhead electric
- datu underground cable/phone/data
- datu underground cable/phone/data service
- fence-chainlink
- fence-wood
- fence-barbed wire
- treeline

Symbols

- ⊙ sanitary manhole
- ⊙ service cleanout
- ⊙ force main release valve
- rectangular structure
- circular structure
- ⊕ fire hydrant
- ⊕ water valve
- ⊕ water meter
- ⊕ backflow preventer
- ⊕ natural gas meter
- ⊕ service transformer (pad mount)
- ⊕ primary switch gear
- ⊕ light pole
- ⊕ cable/phone/data junction box
- ⊕ street light
- ⊕ pedestrian street light
- ⊕ electric pole
- guy wire
- ⊔ end section





A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date 02.21.2020
drawn by SLM
checked by PAM
revisions
02.16.2021 FDP

sheet number
C2.2
drawing type fdp
project number 19076

Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
Elevation: 983.62'
N: 1013823.1758
E: 2827361.8695

BM-2: Storm Structure, Manhole Cover
Elevation: 1001.21'
N: 1013384.7454
E: 2827199.0101

Grading Legend

- existing minor contour
- existing major contour
- proposed minor contour
- proposed major contour

Utility Legend

- existing
- proposed

Linetypes

- sanm sanitary main
- sans sanitary service
- sans (existing) storm sewer (existing)
- stm storm sewer (solid wall, proposed)
- stm (solid wall, proposed) storm sewer (solid wall, proposed)
- wtrm storm sewer (perforated, proposed)
- wtrm water main
- wtrf water service (fire)
- wtrd water service (domestic)
- wtri water service (irrigation)
- gasm natural gas main
- gass natural gas service schematic
- elpu underground primary electric
- elsu underground secondary electric
- elpo overhead electric
- datu underground cable/phone/data
- datu underground cable/phone/data service
- fence-chainlink fence-chainlink
- fence-wood fence-wood
- fence-barbed wire fence-barbed wire
- treeline treeline

Erosion Control Legend

- Phase I Silt fence
- Phase I Inlet protection
- limits of disturbance
- construction entrance
- topsoil stockpile area
- concrete washout area

Property Legend

- right of way
- property lines
- easements
- setbacks

Note:


Contractor to construct stormwater management facilities, specifically those features related to detention, prior to any land disturbance of the site and prior to the construction of any other site development work as not to effect downstream neighbors with undetained stormwater discharge.

Symbols

- sanitary manhole
- service cleanout
- force main release valve
- rectangular structure
- circular structure
- fire hydrant
- water valve
- water meter
- backflow preventer
- natural gas meter
- service transformer (pad mount)
- primary switch gear
- light pole
- cable/phone/data junction box
- street light
- pedestrian street light
- electric pole
- guy wire
- end section

Erosion and Sediment Control Staging Chart

Project Stage	Description	Remove after Stage:	Notes:
Phase I	Inlet Protection	F	Install inlet protection on existing area inlets.
	Temporary Construction Entrance and Staging Area	E	Install per ESC-01 detail on Sheet C4.1
	Phase I Sediment Fence	C	Install Sediment fence as shown per manufacturer instructions
	Perimeter Sediment Fence	F	Install per city of Lee's Summit standard detail
Phase II	Phase II Area Storm Pipe Inlet & Outlet Protection within Proposed Sediment Basin	N/A	At time of sediment basin construction, install stabilized buffer and utilize skimmer at sediment basin outlet structure.
	Concrete Washout	E	Remove only when graded areas have permanent stabilization established.
	Stockpile Topsoil	E	Install sediment fence a minimum of 5' beyond toe of slope for all stockpile areas.
	Phase II Sediment Fence	F	Install as needed for intermediate sediment control during mass grading
	Remove Existing Pond	N/A	Reference Soil Stabilization notes on Sheet C2.2 for recommended stabilization procedures
D - Storm Sewer Installation	Phase II Area and Curb Inlets Protection	F	Install sediment fence around all area inlets and open junction boxes. Install excavated area and throat protection on all curb inlets.
	Temporary Stabilization	N/A	Seed and mulch future development area. Temporarily stabilize with hydromulch if out of seeding season.
Building Phase	Convert Sediment Basin to Detention Pond	N/A	Install inlet/outlet storm structures. Grade Detention Area per Construction Drawings.
	Phase II Area and Curb Inlets Protection	F	Following installation of storm structures and curb and gutter, install inlet filter bag
	Sediment Log/Wattle	F	To be placed at back of curb and installed per manufacturer instructions.
F - Final Grading & Stabilization	Establish Perennial Vegetation and Landscaping per landscape plan. Install Native Vegetation in designated areas using approved seed mix.	N/A	Redistribute topsoil and seed and mulch all disturbed areas. Sod right-of-way. Stabilization complete when 100% of disturbed area is established with perennial vegetation with a density of 70%. All plantings shall be during approved planting season. Planting shall be per approved landscape plan.



Install perimeter pre-clearing silt fence prior to any land disturbance activities, as shown. The elevation of the silt fence shall not vary more than 24" throughout its run. Ends of the silt fence shall be returned uphill a minimum of 6" (vertical), typ. Silt fence shall remain in place and be maintained throughout entire construction duration. Only when tributary area to silt fence is stabilized shall the fence be removed, or when dictated by site improvements.

Existing property line


Existing pond to be removed

Concrete washout area, final location to be at contractor's discretion.

Prior to land disturbance activities, install and maintain temporary construction entrance/exit, as shown. Construction entrance shall remain in place indefinitely, but must be cleaned of accumulated silt and rock, and removed for project close-out.

Materials stockpile area, final location to be at contractor's discretion

Prior to land disturbance, contractor shall install inlet protection around all existing inlets per City standards, Typ.



Soil Stabilization:

- In the event moisture sensitive soils are observed, PSI recommends the following procedures be considered to further stabilize wet/soft areas if typical moisture conditioning/disking/recompacting methods are not affective
- Scarify, dry, and recompact the soils to a moisture content that will facilitate compaction in accordance with the structural fill requirements of the geotechnical report "03382128 - Proposed Detail Center".
 - If scarifying, drying and recompaction of the soils does not stabilize the soils, removing and replacement with new structural fill or treating the soils with class "C" fly ash, portland cement or lime-treatment of the clay soils may need to be performed. The amount of these materials will likely range between 10 to 15 percent by weight for fly ash, 5 to 8 percent by weight for portland cement and 4 to 8 percent for lime.
 - Track 3 to 5-inch minimum well-graded crushed limestone or similar material into the failing areas to attempt to bridge the soft zones. These materials should be placed in loose lifts of no more than 10 inches and tacked in with a loaded rubber tire truck or beat in with a backhoe bucket. Once the areas are stabilized, onsite soils can then be placed to the recommended low volume change material subgrade elevations for pavements. If for some reason areas do not stabilize with 1 to 2 lifts of stone, a later of grid or fabric may need to be incorporated into those areas at that time, followed by additional lifts of stone consisting of 3/4" minus material (AB-3).
 - A fourth option would be to place a geo-grid similar to Tensor BX1100 and then place new granular fill similar to 3/4" minus material in compacted lifts. The grid should extend at least 10 feet past the perimeter of the failing areas and should be overlapped according to the manufacturers requirements. If the area does not stabilize by the second lift of 3/4" minus material an additional later of grid should then be placed and the process should be repeated until it is stabilized.
- PSI recommends a test section be performed to verify the selected remediation method.





A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.21.2020
 drawn by SLM
 checked by PAM
 revisions
 02.16.2021 FDP

sheet number
C2.3
 drawing type fdp
 project number 19076

Local Benchmarks: BM-#
 BM-1: Storm Structure, Manhole Cover
 Elevation: 983.62'
 N: 1013823.1758
 E: 2827361.8695
 BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Erosion Control Legend
 Phase I Silt fence
 Phase I Inlet protection
 Phase II Silt fence
 Phase II Inlet protection
 limits of disturbance
 rock check dam
 seeding & stabilization

Property Legend
 right of way
 property lines
 easements
 setbacks

Grading Legend
 existing minor contour
 existing major contour
 proposed minor contour
 proposed major contour


Utility Legend
 existing
 proposed

Linetypes
 sanitary main
 sanitary service
 storm sewer (existing)
 storm sewer (solid wall, proposed)
 storm sewer (solid wall, proposed)
 storm sewer (perforated, proposed)
 water main
 water service (fire)
 water service (domestic)
 water service (irrigation)
 natural gas main
 natural gas service schematic
 underground primary electric
 underground secondary electric
 overhead electric
 underground cable/phone/data
 underground cable/phone/data service
 fence-chainlink
 fence-wood
 fence-barbed wire
 treeline

Symbols
 sanitary manhole
 service cleanout
 force main release valve
 rectangular structure
 circular structure
 fire hydrant
 water valve
 water meter
 backflow preventer
 natural gas meter
 service transformer (pad mount)
 primary switch gear
 light pole
 cable/phone/data junction box
 street light
 pedestrian street light
 electric pole
 guy wire
 end section

Note:
 Contractor to construct stormwater management facilities, specifically those features related to detention, prior to any land disturbance of the site and prior to the construction of any other site development work as not to effect downstream neighbors with undetained stormwater discharge.

Erosion and Sediment Control Staging Chart				
	Project Stage	Description	Remove after Stage:	Notes:
Phase I	A - Prior to Land Disturbance	Inlet Protection	F	Install inlet protection on existing area inlets.
		Temporary Construction Entrance and Staging Area	E	Install per ESC-01 detail on Sheet C4.1
		Phase I Sediment Fence	C	Install Sediment fence as shown per manufacturer instructions
		Perimeter Sediment Fence	F	Install per city of Lee's Summit standard detail
Phase II	B - Construct Sediment Basin	Phase II Area Storm Pipe Inlet & Outlet Protection within Proposed Sediment Basin	N/A	At time of sediment basin construction, install stabilized buffer and utilize skimmer at sediment basin outlet structure.
		Concrete Washout	E	Remove only when graded areas have permanent stabilization established.
	C - Mass Grading	Stockpile Topsoil	E	Install sediment fence a minimum of 5' beyond toe of slope for all stockpile areas.
		Phase II Sediment Fence	F	Install as needed for intermediate sediment control during mass grading
		Remove Existing Pond	N/A	Reference Soil Stabilization notes on Sheet C2.2 for recommended stabilization procedures
	D - Storm Sewer Installation	Phase II Area and Curb Inlets Protection	F	Install sediment fence around all area inlets and open junction boxes. Install excavated area and throat protection on all curb inlets.
		Temporary Stabilization	N/A	Seed and mulch future development area. Temporarily stabilize with hydromulch if out of seeding season.
Building Phase	E - Construction of Detention Pond, Building, and Pavements	Convert Sediment Basin to Detention Pond	N/A	Install inlet/outlet storm structures. Grade Detention Area per Construction Drawings.
		Phase II Area and Curb Inlets Protection	F	Following installation of storm structures and curb and gutter, install inlet filter bag
	F - Final Grading & Stabilization	Sediment Log/Wattle	F	To be placed at back of curb and installed per manufacturer instructions.
		Establish Perennial Vegetation and landscaping per landscape plan. Install Native Vegetation in designated areas using approved seed mix.	N/A	Redistribute topsoil and seed and mulch all disturbed areas. Sod right-of-way. Stabilization complete when 100% of disturbed area is established with perennial vegetation with a density of 70%. All plantings shall be during approved planting season. Planting shall be per approved landscape plan.



Erosion Control Plan - Phase II
 north
 1" = 40'
 0 20 40 80





Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Linetypes

sanm	sanitary main
sans	sanitary service
ssm	storm sewer (existing)
ssm	storm sewer (solid wall, proposed)
ssm	storm sewer (solid wall, proposed)
ssm	storm sewer (perforated, proposed)
wrm	water main
wtrf	water service (fire)
wtrd	water service (domestic)
wtri	water service (irrigation)
gasm	natural gas main
gass	natural gas service schematic
elpu	underground primary electric
elsu	underground secondary electric
elpo	overhead electric
datu	undgrnd cable/phone/data
datsu	undgrnd cable/phone/data service
fc	fence-chainlink
fw	fence-wood
fbw	fence-barbed wire
tr	treenline

Grading Legend

---	existing minor contour
---	existing major contour
---	proposed minor contour
---	proposed major contour

Utility Legend


---	existing
---	proposed

Property Legend


---	right of way
---	property lines
---	easements
---	setbacks

Americans with Disabilities Act (ADA) Notes:

- The running and cross slopes for all sidewalks, accessible paths, ramps, designated parking stalls, etc., shall be in compliance with latest Federal ADA guidelines, in addition to any accessibility standards adopted by the governing municipality. Prior to installation/construction, if any discrepancies are found within the plans, the Engineer shall be notified.



2 ADA Spot Elevation Plan
 1"=10'




1 Spot Elevation Plan
 1"=40'

Symbols

⊙	sanitary manhole	⊗	natural gas meter
⊙	service cleanout	⊞	service transformer (pad mount)
⊙	force main release valve	⊞	primary switch gear
⊞	rectangular structure	⊞	light pole
⊞	circular structure	⊞	cable/phone/data junction box
⊞	fire hydrant	⊞	street light
⊞	water valve	⊞	pedestrian street light
⊞	water meter	⊞	electric pole
⊞	backflow preventer	⊞	guy wire
		⊞	end section

Spot Elevation Legend


br	= bottom of ramp	ti	= top of inlet
tr	= top of ramp	tv	= top of vault
me	= match existing	hp	= high-point
pv	= pavement	lp	= low-point
bw	= bottom of wall	blgd	= building
tw	= top of wall	FFE	= finished floor elevation
tc	= top of curb	ex	= existing
sw	= sidewalk	mp	= match pavement
		fg	= finished grade



3 Drainage Swale Cross-Section
 not to scale

Flat Cut Slope: 4.00:1
 Flat Cut Max Height: 1.00'
 Medium Cut Slope: 4.00:1
 Medium Cut Max Height: 5.00'
 Steep Cut Slope: 3.00:1

Flat Fill Slope: 6.00:1
 Flat Fill Max Height: 5.00'
 Medium Fill Slope: 4.00:1
 Medium Fill Max Height: 10.00'
 Steep Fill Slope: 3.00:1



A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.21.2020
 drawn by SLM
 checked by PAM
 revisions

02.16.2021 FDP

sheet number

C2.4

drawing type fdp
 project number 19076



Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
Elevation: 982.05'
N: 1013823.1378
E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
Elevation: 1001.21'
N: 1013384.7454
E: 2827199.0101

- Grading Legend**
- - - - - existing minor contour
 - - - - - existing major contour
 - - - - - proposed minor contour
 - - - - - proposed major contour

- Utility Legend**
- - - - - existing
 - - - - - proposed

- Property Legend**
- - - - - right of way
 - - - - - property lines
 - - - - - easements
 - - - - - setbacks


- Linetypes**
- sanm sanitary main
 - sans sanitary service
 - sswm storm sewer (existing)
 - ssws storm sewer (solid wall, proposed)
 - stms storm sewer (solid wall, proposed)
 - stmp storm sewer (perforated, proposed)
 - wtrm water main
 - wtrf water service (fire)
 - wtrd water service (domestic)
 - wtri water service (irrigation)
 - gasm natural gas main
 - gass natural gas service schematic
 - alpu underground primary electric
 - alsu underground secondary electric
 - alpo overhead electric
 - datu undgrnd cable/phone/data
 - datu undgrnd cable/phone/data service
 - fence-chainlink
 - fence-wood
 - fence-barbed wire
 - treeline

- Symbols**
- ⊙ sanitary manhole
 - co service cleanout
 - fmv force main release valve
 - rectangular structure
 - circular structure
 - ⊕ fire hydrant
 - ⊕ water valve
 - ⊕ water meter
 - BFP backflow preventer
 - ⊕ natural gas meter
 - T service transformer (pad mount)
 - S primary switch gear
 - ⊕ light pole
 - C cable/phone/data junction box
 - ⊕ street light
 - ⊕ pedestrian street light
 - ⊕ electric pole
 - guy wire
 - ▽ end section


- Spot Elevation Legend**
- br = bottom of ramp
 - tr = top of ramp
 - me = match existing
 - pv = pavement
 - bw = bottom of wall
 - tw = top of wall
 - tc = top of curb
 - sw = sidewalk
 - ti = top of inlet
 - mi = mid-point
 - hp = high-point
 - lp = low-point
 - pc = point of curvature
 - pt = point of tangency
 - bdg = building
 - FFE = finished floor elevation
 - ex = existing
 - mp = match pavement

Americans with Disabilities Act (ADA) Notes:


- The running and cross slopes for all sidewalks, accessible paths, ramps, designated parking stalls, etc., shall be in compliance with latest Federal ADA guidelines, in addition to any accessibility standards adopted by the governing municipality. Prior to installation/construction, if any discrepancies are found within the plans, the Engineer shall be notified.



1 ADA Ramp 1 Detail
1"=5'
0 2.5 5 10
Note:
• Refer to city details on Sheet C4.5



3 ADA Ramp 3 Detail
1"=5'
0 2.5 5 10
Note:
• Refer to city details on Sheet C4.5



2 ADA Ramp 2 Detail
1"=5'
0 2.5 5 10
Note:
• Refer to city details on Sheet C4.5

A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date 02.21.2020
drawn by SLM
checked by PAM
revisions
02.16.2021 FDP

sheet number
C2.5
drawing type fdp
project number 19076





A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date
 drawn by
 checked by
 PAM
 revisions
 02.16.2021
 FDP

sheet number
C3.1
 drawing type
 fdp
 project number
 19076

Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Floodplain Note:

The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C0430G, Revision Date: January 20, 2017.

Drainage Legend

- drainage area
- existing flow direction

Property Legend

- right of way
- property lines
- easements
- setbacks

Grading Legend

- existing minor contour
- existing major contour
- proposed minor contour
- proposed major contour

Utility Legend

- existing
- proposed

Linetypes


- sanm sanitary main
- sans sanitary service
- ssm (existing) storm sewer (existing)
- ssm (solid wall, proposed) storm sewer (solid wall, proposed)
- ssm (perforated, proposed) storm sewer (perforated, proposed)
- wtrm water main
- wtrf water service (fire)
- wtrd water service (domestic)
- wtri water service (irrigation)
- gasm natural gas main
- gass natural gas service schematic
- elpu underground primary electric
- elsu underground secondary electric
- elpo overhead electric
- datu underground cable/phone/data
- datsu underground cable/phone/data service
- fence-chainlink
- fence-wood
- fence-barbed wire
- treeline

Symbol Legend

- sanitary manhole
- service cleanout
- force main release valve
- rectangular structure
- circular structure
- fire hydrant
- water valve
- water meter
- backflow preventer
- natural gas meter
- service transformer (pad mount)
- primary switch gear
- light pole
- cable/phone/data junction box
- street light
- pedestrian street light
- electric pole
- guy wire
- end section



2 Vicinity Map
 No Scale



1 Existing Drainage Area Map
 1"=80'

Pre-Construction Impervious Area Calculations

Area of Site	Square Feet	Acres
Impervious Area	1,252,503	28.75
Pervious Area	25,983	0.60
	1,278,486	29.35

Q:	2 year	34.18 cfs
	10 year	47.72 cfs
	100 year	71.89 cfs



Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
 Elevation: 982.05'
 N: 1013823.1378
 E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
 Elevation: 1001.21'
 N: 1013384.7454
 E: 2827199.0101

Floodplain Note:

The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C04306, Revision Date: January 20, 2017.

Drainage Legend


- drainage area
 existing flow direction
 proposed flow direction
- Property Legend**
- right of way
 property lines
 easements
 setbacks
- Grading Legend**
- existing minor contour
 existing major contour
 proposed minor contour
 proposed major contour
- Utility Legend**
- existing
 proposed

Symbol Legend

- sanitary manhole
 service cleanout
 force main release valve
 rectangular structure
 circular structure
 fire hydrant
 water valve
 water meter
 backflow preventer
 natural gas meter
- service transformer (pad mount)
 primary switch gear
 light pole
 cable/phone/data junction box
 street light
 pedestrian street light
 electric pole
 guy wire
 end section

Linetypes

- sanitary main
 sanitary service
 storm sewer (existing)
 storm sewer (solid wall, proposed)
 storm sewer (perforated, proposed)
 water main
 water service (fire)
 water service (domestic)
 water service (irrigation)
- natural gas main
 natural gas service schematic
- underground primary electric
 underground secondary electric
 overhead electric
- underground cable/phone/data
 underground cable/phone/data service
- fence-chainlink
 fence-wood
 fence-barbed wire
 treeline



1 Proposed Drainage Area Map
 north
 1"=80'

Post-Construction Impervious Area Calculations

	Square Feet	Acres
Area of Site	1,278,486	29.35
Impervious Area	125,453	2.88
Pervious Area	1,153,033	26.47

Q: 2 year 1.81 cfs
 10 year 9.18 cfs
 100 year 24.56 cfs

2 Proposed Drainage Area Map Detail
 north
 1"=60'





Local Benchmarks: BM-#

BM-1: Storm Structure, Manhole Cover
Elevation: 982.05'
N: 1013823.1378
E: 2827361.8656

BM-2: Storm Structure, Manhole Cover
Elevation: 1001.21'
N: 1013384.7454
E: 2827199.0101

Property Legend

- right of way
- - - property lines
- - - easements
- - - setbacks

Grading Legend

- - - existing minor contour
- - - existing major contour
- - - proposed minor contour
- - - proposed major contour

Utility Legend


- - - existing
- - - proposed

Linetypes



- sanm sanitary main
- sans sanitary service
- ssm storm sewer (existing)
- ssm storm sewer (solid wall, proposed)
- ssm storm sewer (solid wall, proposed)
- ssm storm sewer (perforated, proposed)
- wrm water main
- wrf water service (fire)
- wrd water service (domestic)
- wri water service (irrigation)
- gasm natural gas main
- gass natural gas service schematic
- elpu underground primary electric
- elss underground secondary electric
- elpo overhead electric
- datu underground cable/phone/data
- datss underground cable/phone/data service
- fence-chainlink
- fence-wood
- fence-barbed wire
- treeline

Symbols

- ⊙ sanitary manhole
- ⊙ service cleanout
- ⊙ force main release valve
- ⊙ rectangular structure
- ⊙ circular structure
- ⊙ fire hydrant
- ⊙ water valve
- ⊙ water meter
- ⊙ backflow preventer
- ⊙ natural gas meter
- ⊙ service transformer
- ⊙ primary switch gear
- ⊙ light pole
- ⊙ data junction box
- ⊙ street light
- ⊙ pedestrian street light
- ⊙ electric pole
- ⊙ guy wire
- ⊙ end section





Note:
Compacted fill shall be placed to a minimum 18" above the top of the pipe prior to installation.



Storm Line 1

Storm Line 2



A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date 02.02.2020
drawn by SLM
checked by PAM
revisions
02.16.2021 FDP

sheet number
C3.3
drawing type fdp
project number 19076



Storm Line 1 Pipe Calculations

10-year Rain Event																				
Pipe Segment	DrainageArea (ac)	RunoffCoeff (C)	TotalCxA	iSys (in/hr)	TotalRunoff (cfs)	LineSize (in)	LineSlope (%)	n-valuePipe	CapacityFull (cfs)	DepthDn (ft)	DepthUp (ft)	HGLDn (ft)	HGLUp (ft)	VelAve (ft/s)	EGLDn (ft)	EGLUp (ft)	EnergyLoss (ft)	LineLength (ft)	PipeTravel (min)	Rim-Hw (ft)
1-1 to 1-2	0.50	0.88	1.25	6.86	8.57	24	1.66	0.012	31.82	0.71	1.04**	981.26	983.29	6.85	981.68	983.71	0.000	102.641	0.25	7.75
1-2 to 1-3	1.05	0.65	0.81	6.99	5.65	18	2.00	0.012	16.24	0.61	0.92**	983.37	987.55	6.64	983.76	987.93	0.000	193.926	0.49	5.69
1-3 to 1-4	0.20	0.63	0.13	7.24	0.91	15	1.70	0.012	9.10	0.66	0.37**	987.55	989.20	2.18	987.68	989.34	0.000	113.844	0.87	4.27

100-year Rain Event																				
Pipe Segment	DrainageArea (ac)	RunoffCoeff (C)	TotalCxA	iSys (in/hr)	TotalRunoff (cfs)	LineSize (in)	LineSlope (%)	n-valuePipe	CapacityFull (cfs)	DepthDn (ft)	DepthUp (ft)	HGLDn (ft)	HGLUp (ft)	VelAve (ft/s)	EGLDn (ft)	EGLUp (ft)	EnergyLoss (ft)	LineLength (ft)	PipeTravel (min)	Rim-Hw (ft)
1-1 to 1-2	0.50	0.88	1.25	9.41	11.75	24	1.66	0.012	31.82	0.84	1.23**	981.39	983.48	7.54	981.92	984.00	0.000	102.641	0.23	7.56
1-2 to 1-3	1.05	0.65	0.81	9.56	7.73	18	2.00	0.012	16.24	0.73	1.07**	983.49	987.70	7.34	983.99	988.21	0.000	193.926	0.44	5.54
1-3 to 1-4	0.20	0.63	0.13	9.83	1.24	15	1.70	0.012	9.10	0.81	0.44**	987.70	989.27	2.34	987.87	989.43	0.000	113.844	0.81	4.20

Str. 1-2
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
4.33	4.33	4.91	100	4.91	15.95

Str. 1-3
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
6.71	6.71	6.33	100	6.21	21.87

Str. 1-4
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
1.24	1.24	2.54	100	2.54	6.09

Storm Line 2 Pipe Calculations

10-year Rain Event																				
Pipe Segment	DrainageArea (ac)	RunoffCoeff (C)	TotalCxA	iSys (in/hr)	TotalRunoff (cfs)	LineSize (in)	LineSlope (%)	n-valuePipe	CapacityFull (cfs)	DepthDn (ft)	DepthUp (ft)	HGLDn (ft)	HGLUp (ft)	VelAve (ft/s)	EGLDn (ft)	EGLUp (ft)	EnergyLoss (ft)	LineLength (ft)	PipeTravel (min)	Rim-Hw (ft)
2-1 to 2-2	0.28	0.86	1.52	6.92	10.55	24	2.30	0.012	37.50	0.73	1.16**	982.23	983.42	7.87	982.71	983.90	0.000	33.035	0.07	5.29
2-2 to 2-3	0.24	0.90	1.28	7.00	8.98	24	1.30	0.012	28.20	1.06	1.07**	983.42	984.58	5.27	983.85	985.01	0.000	88.371	0.28	6.64
2-3 to 2-4	0.37	0.85	1.07	7.05	7.52	18	2.00	0.012	16.24	0.72	1.06**	984.73	986.69	7.28	985.22	987.18	0.000	81.110	0.19	5.75
2-4 to 2-5	0.99	0.76	0.75	7.24	5.45	15	1.01	0.012	7.00	0.83	0.95**	986.71	989.20	5.90	987.17	989.66	0.000	235.304	0.67	4.32

100-year Rain Event																				
Pipe Segment	DrainageArea (ac)	RunoffCoeff (C)	TotalCxA	iSys (in/hr)	TotalRunoff (cfs)	LineSize (in)	LineSlope (%)	n-valuePipe	CapacityFull (cfs)	DepthDn (ft)	DepthUp (ft)	HGLDn (ft)	HGLUp (ft)	VelAve (ft/s)	EGLDn (ft)	EGLUp (ft)	EnergyLoss (ft)	LineLength (ft)	PipeTravel (min)	Rim-Hw (ft)
2-1 to 2-2	0.28	0.86	1.52	9.48	14.44	24	2.30	0.012	37.50	0.86	1.37**	982.36	983.63	8.69	982.98	984.24	0.000	33.035	0.06	5.08
2-2 to 2-3	0.24	0.90	1.28	9.56	12.27	24	1.30	0.012	28.20	1.27	1.26**	983.63	984.77	5.86	984.17	985.31	0.000	88.371	0.25	6.45
2-3 to 2-4	0.37	0.85	1.07	9.62	10.26	18	2.00	0.012	16.24	0.87	1.23**	984.88	986.86	8.11	985.55	987.53	0.000	81.110	0.17	5.58
2-4 to 2-5	0.99	0.76	0.75	9.83	7.40	15	1.01	0.012	7.00	1.10	1.24	986.98	989.49	6.25	987.63	990.06	2.427	235.304	0.63	3.46

Str. 2-2
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
2.37	2.37	3.52	100	3.52	10.18

Str. 2-3
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
2.48	2.48	3.61	100	3.61	10.54

Str. 2-4
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
3.09	3.09	4.07	100	4.07	12.44

Str. 2-5
Inlet Calculations

Q		Inlet		Gutter	
Total (cfs)	Captured (cfs)	Depth (in)	Efficiency (%)	Depth (in)	Spread (ft)
7.40	7.40	6.71	100	6.71	23.45

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.02.2020
 drawn by SLM
 checked by PAM
 revisions
 02.16.2021 FDP

Notes for Concrete Washout:

- Concrete washout areas shall be installed prior to any concrete placement on site.
- Concrete washout areas shall include a filter substructure all around relative to the amount of concrete to be placed on site. The slope leading out of the substructure pit shall be 2:1. The entire trapping pit shall be sloped towards the concrete washout area.
- Spillway openings are required at the access point to all concrete washout areas.
- Signs shall be placed at the construction site entrance, washout area, and elsewhere as necessary to clearly indicate the location(s) of the concrete washout area(s) to operators of concrete truck and pump rigs.
- A one-piece impervious liner may be required along the bottom and sides of the substructure pit in steep or gravity soils.

Maintenance for Concrete Washout:

- Concrete washout materials shall be removed once the materials have filled the washout to approximately 75% full.
- Concrete washout areas shall be enlarged as necessary to maintain capacity for washed concrete.
- Concrete washout water, wetted pieces of concrete and all other debris in the substructure pit shall be transported from the job site in a water-tight container and disposed of properly.
- Concrete washout areas shall remain in place until all concrete for the project is placed.
- When concrete washout areas are removed, excavations shall be filled with suitable compacted backfill and facing, any disturbed areas associated with the installation, maintenance, and/or removal of the concrete washout areas shall be stabilized.

Notes for Construction Entrance:

- Avoid loading on steep slopes, at curves on public roads, or downhill of disturbed areas.
- Remove all vegetation and other undesirable material from the foundation area, grade, and clear for positive drainage.
- If slope towards the public road exceeds 2%, construct a 6"-to 8"-high high ridge with 3/4" x 1/4" size slopes across the foundation approximately 15 feet from the edge of the public road to divert runoff from it.
- Install pipe under the entrance if needed to maintain drainage ditches along public roads.
- Place stone to dimensions and grade as shown on plans. Leave surface sloped for drainage.
- Divert all surface runoff and drainage from the entrance to a sediment control device.
- If conditions warrant, place geotextile fabric on the graded foundation to improve stability.

Maintenance for Construction Entrance:

- Re-stage entrance as needed to maintain function and integrity of installation. Top dress with clean aggregate as needed.

CONCRETE WASHOUT

AMERICAN PUBLIC WORKS ASSOCIATION
APWA KANSAS CITY METRO CHAPTER
 CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT
 STANDARD DRAWING NUMBER ESC-01
 ADOPTED: 10/24/2016

* Contractor shall field verify that Pooled Water Depth will not cause unintended flooding.

Notes:

- Immediately following inlet construction and prior to construction of curb and inlet throat, protect inlet opening by installing 2" x 10" (min.) board wrapped in silt fence. Structures shall have excavated storage area on all four sides to allow settling of sediment (Early Stage Curb Inlet).
- When inlet is completed and curb poured, filter socks or approved equivalent shall be used (Late Stage Curb Inlet). Straw wafers are not approved for curb inlet use.
- Contractor to field verify ponding water shall not create a traffic hazard.

Maintenance:

- Remove deposited sediment from excavated storage areas when available storage has been reduced by 25%.
- Remove deposited sediment from filter socks or similar when any accumulation of sediment is visible.
- Repair or replace as necessary to maintain function and integrity of installation.

CONCRETE WASHOUT

AMERICAN PUBLIC WORKS ASSOCIATION
APWA KANSAS CITY METRO CHAPTER
 CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT
 STANDARD DRAWING NUMBER ESC-01
 ADOPTED: 10/24/2016

Notes:

- In order to contain water, the ends of the silt fence must be turned uphill (Figure A).
- Long perimeter runs of silt fence must be limited to 100'. Runs should be broken up into several smaller segments to minimize water concentrations (Figure A).
- Long slopes should be broken up with intermediate rows of silt fence to slow runoff velocities.
- Attach fabric to upstream side of post.
- Install posts a minimum of 2' into the ground.
- Trenching will only be allowed for small or difficult installation, where slicing machine cannot be reasonably used.

Maintenance:

- Remove and dispose of sediment deposits when the deposit approaches 1/2 the height of silt fence.
- Repair as necessary to maintain function and structure.








JOINING FENCE SECTIONS

AMERICAN PUBLIC WORKS ASSOCIATION
APWA KANSAS CITY METRO CHAPTER
 SILT FENCE
 STANDARD DRAWING NUMBER ESC-03
 ADOPTED: 10/24/2016

Modified from 2015 Overland Park Standard Details for Erosion and Sediment Control.

Construction Entrance modified from 2015 Overland Park Standard Details for Erosion and Sediment Control. Concrete Washout modified from 2009 City of Great Bend Standard Drawings.


Modified from 2015 Overland Park Standard Details for Erosion and Sediment Control.






A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064



date 02.21.2020
 drawn by SLM
 checked by PAM
 revisions
 02.16.2021 FDP





LEE'S SUMMIT MISSOURI
 PUBLIC WORKS ENGINEERING DIVISION | 1202 S GREEN STREET | LEE'S SUMMIT, MO 64083
 STANDARD DETAILS
 CITY OF LEE'S SUMMIT, MO
 LEE'S SUMMIT, JACKSON COUNTY, MO
 GEN-4



- Notes:**
- All pavements shall conform to Lee's Summit City Standard.
 - Refer to the geotech for site recommendations.
 - Where city pavement standards and geotech recommendations differ, contractor shall use the more stringent of the two.
 - Any discrepancies shall be brought to the attention of the engineer.



- Notes**
- Concrete shall be KCMMB-4K unless otherwise noted.
 - Key all construction joints or use tie bars #4 Epoxy coated @ 12" o.c.
 - Longitudinal joint spacing to match width of sidewalk.
 - Isolation joints shall be placed where walk abuts driveways and similar structures, and 250' centers max.
 - Install 18" tie bars #4 Epoxy coated @ 18" o.c.



Example: A 15" pipe has an exit velocity of 7.2 fps with a tail water depth of 30" and channel slope of 2%. Acceptable Riprap Size: $D_{50} = 0.58'$, $W = 19\text{lbs.}$, $KDOT \text{ Gradation} = \text{Light } 18"$.
 Max. Stress = $(62.4)(2.5)(.02) = 3.2 \text{ psf} < 5 \text{ psf O.K.}$

How to use this nomograph:

Method #1

- Find the exit velocity at the outlet.
- Intersect with Turning Line.
- Read top and bottom scales to determine approximate weight and size of stone.
- Read top scale to determine KDOT gradation of stone.
- Compare to see if design sizes meet or exceed the sizes calculated by method 2 on this sheet.

Method #2

- Calculate Maximum Shear Stress (Using Table).
- Compare Maximum Shear Stress to Allowable Shear Stress from Table. Maximum shear stress must be equal or less than allowable stress or larger stone is required.

General Notes:

- This nomograph allows the user to approximate the D₅₀ stone size of riprap for conduit outlet protection based on the exit velocity of the conduit.
- This nomograph is based on Figure 2.3.12-8a, "Guide for Estimating Stability of Channels and Large Rocks", KDOT Design Manual, Volume III, Bridge Section.
- Conduit velocity as calculated by Manning's Equation.
- Estimations based on this nomograph are only valid for velocities between 5 fps and 15 fps. Outlets with higher velocities should be investigated further.
- Riprap is not normally required for velocity below 5 f.p.s. Consider grass lining materials.

KDOT Gradations are based on the stone specifications from the KDOT Standard Specifications for State Road and Bridge Construction (1990) - * Table 12b Stone for Aggregate Ditch Lining, and ** Table 11 Stone for Riprap.

METHOD #2 - MAX. SHEAR STRESS

$\tau_c = \gamma ds$
 $\gamma = 62.4 \text{ pcf}$
 $d = \text{depth of tailwater (ft)}$
 $s = \text{slope at exit (ft/ft)}$


Heavy Series	Allowable Shear Stress for KDOT Standard Gradations
4 Ton	27 psf
2 Ton	21 psf
1 Ton	16 psf
1/2 Ton	13 psf
1/4 Ton	10 psf
Light Series	
Light 24"	6 psf
Light 18"	5 psf
Stone for Ditch Lining	
6"	3 psf
5"	2 psf




A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.21.2020
 drawn by SLM
 checked by PAM
 revisions
 02.16.2021 FDP


sheet number
C4.4
 drawing type fdp
 project number 19076




Detention Basin Outlet Detail
not to scale



Detention Basin Outlet Structure (Str. 3-2)
not to scale







Junction Box Detail
not to scale



Junction Box Structure (Str. 3-3)
not to scale

RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW
DATE OF PLAN REVIEW: 02/16/2021
LEE'S SUMMIT, MISSOURI
4301 Indian Creek Parkway
Overland Park, KS 66207
phone: 813.451.9390
fax: 813.451.9391
www.davidsonae.com

STATE OF MISSOURI
SKYLER LEE MARTIN
Professional Engineer
NUMBER PE-2018021221
02/16/2021



A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date 02.21.2020
drawn by SLM
checked by PAM
revisions
02.16.2021 FDP

sheet number
C4.5
drawing type fdp
project number 19076




2 Vicinity Plan
no scale

Site Criteria


zone:	CP-2
site area:	approx. 175,306 s.f. or 4.02 acres
impervious site area:	124,303 s.f. <80%
green space:	51,003 s.f. >20%
setbacks:	front yard 15' side yard 10' rear yard 20'
building footprint:	12,944 s.f.
mezzanine:	1,480 s.f.
total building area:	14,424 s.f.
number of stories:	3 stories max., 2 stories actual
floor area ratio:	14,424 / 175,306 = 0.08
parking required:	5 per 1,000 s.f., 16 x 5 = 80 spaces required including 4 accessible spaces
actual parking onsite:	248 parking spaces
Legal Description:	refer to civil drawings

construction notes

- Furnish and install new concrete curb and gutter per Civil.
- Parking lot striping shall be white w/ 4" stroke.
- 4" white diagonal striping at 2'-0" on center max. contained in area as shown on plan.
- Saw cut and remove existing curb & gutter and install new drive entrance. Match new drive elevation with existing street pavement. Re: civil.
- Trash enclosure to be constructed using materials matching building, per details.
- Install new asphalt pavement per civil.
- Install new concrete pavement per civil.
- Install concrete walk 4" thick, with 6x6 10/10 wwf steel mesh. Control joints at 6'-0" o.c. Broom finish for non-slip surface.
- Install handicap signage. Mount sign at not more than 60" a.f.g. to bottom. Sign to contain the universal handicap symbol and "van accessible" as required per ADA. See detail.
- Furnish and install ADA accessible ramp per detail and per civil.
- Handicap p and universal symbol painted white with 4" stroke.
- Furnish and install bollards in conc. footings - 4' high, 6" diameter pea gravel concrete filled pipe bollards, paint.
- Pole mounted LED site lighting on steel pole with concrete base not to exceed 25' in total height measured from finish grade. Specific fixture by electrical engineer and contractor.
- Pole mounted LED site lighting on steel pole with concrete base not to exceed 18' in total height measured from finish grade. Specific fixture by electrical engineer and contractor.
- Building mounted LED site lighting to match pole mounted fixture. Specific fixture by electrical engineer and contractor.
- Furnish and install segmented retaining wall, color: charcoal blend. Wall design shall be performed by contractor's supplier.
- Furnish and install new conc. sidewalk in right-of-way, per civil.
- Furnish and install ADA accessible sidewalk ramp, per civil.



2 ada details
no scale



1 Site Plan
scale: 1" = 30'-0"


A New Facility For
Automotive Sales & Detail Center
2100 NE Independence Ave.
Lee's Summit, Missouri 64064

date 03.25.2019
drawn by jed
checked by DAE
revisions

09.10.2019	
01.17.2020	
02.21.2020	pdp
03.24.2020	1
11.13.2020	FDP
01.25.2021	FDP
02.22.2021	permit



02.22.2021



symbol legend:

- door tag
- construction note
- partition type
- room name
- elevation
- wall section
- enlarged detail

general notes:

- Double keyed locks are not permitted on any required or marked exit.
- Exit/emergency lighting are subject to an on site inspection.
- HVAC system to have approved interconnected, smoke detector activated, automatic shutoffs with the detectors located in the return duct.
- Furnish and install approved address numbers on front and rear of building per governing jurisdiction.
- Building construction must fully comply with all requirements of ADA/ANSI accessibility guidelines.
- Provide 44" min. clear in all exit passageways.
- Exit doors shall be operable from the inside without the use of a key or any special knowledge or effort.
- Any new exterior utility service equipment shall be painted to match the building standard colors.
- Furnish and install horns & strobes as required.
- Construction materials exposed within plenums shall be non-combustible or shall have a flame spread rating of not more than 25 and a smoke developed rating of not more than 50.
- All low voltage wire and cable, optical fiber, pneumatic tubing, and all ducts and duct coverings, linings and connectors install within plenum areas must be rated for plenum use.
- Furnish and install data/voice rough-in throughout per owner's requirements.

construction notes:

1. Furnish and install 3A-40BC rated F.E. min. 5lb. (surface mounted) with approved mounting @ 48" a.f.f. - verify quantity and location with Fire Marshall.
2. Furnish and install semi-recessed fire extinguisher cabinet with white finish and vision panel in door, with (min. 5lb.) 3A-40BC fire extinguisher, bottom at 36" a.f.f. Coordinate location as directed by Fire Marshall.
3. Furnish and install 4" high, 6" diameter pea gravel concrete filled pipe bollards at interior and exterior (galv.) sides of all overhead doors per details - to be painted safety yellow.
4. Furnish and install concrete stoop at exterior doors per structural.
5. Install trench and floor drain system per MEP drawings. Slope slab to drain.
6. Furnish and install power operated insulated sectional overhead door, tracks and controls for 12' x 14' doors.
7. Furnish and install power operated aluminum/glass sectional overhead door, tracks and controls for 12' x 14' doors.
8. Furnish and install 1" clear, insulated glass in thermally broken, clear anodized aluminum storefront frames per details. Caulk around all interior and exterior perimeter joints.
9. Furnish and install Knox Box. Verify location and height with local fire department prior to installation.
10. See detail sheet A4 for top of CMU wall detail.
11. Install new hilo drinking fountain per MEP and per ADA/ANSI.
12. Furnish and install casework reception desk per details noted on drawings with plastic laminate and solid surfaces at various heights. Provide grommets in countertops per owner requirements. Quantity and location per owner.
13. Furnish and install restrooms with a 67" turning radius w/10" max. overlap for knee and toe clearance per ADA, wall mounted sink with gooseneck/wrist blade faucet at 34" a.f.f., 36" and 42" grab bars, 6" and 12" from corner respectively and 18" vertical grab bar per detail. Include toilet accessories and stainless steel framed mirror in each restroom per drawings. Install blocking for all wall mounted accessories.
14. Furnish and install casework per details in waiting with solid surface countertop at 2'-10" a.f.f. and plastic laminate base cabinets.
15. Furnish and install bank style transaction window, clear anod. alum. with tempered clear glass, voice hole and slide under document tray. Furnish and install plastic laminate sill on both sides of window per detail.
16. Furnish and install blocking and electrical for owner supplied TVs. Verify final location with owner.
17. Furnish and install janitor mop basin with shelf above. Provide blocking as required.
18. Install 4" x 8" plywood on utility walls for MEP and voice/data installation.
19. Furnish and install push button ADA control for doors 01 and 02. Refer also to electrical.
20. Furnish and install eye wash sink, per MEP.
21. Install hand wash sink with soap and towel dispensers.

partition legend:

- full height 12" thick CMU wall:
full height 12" thick CMU wall to deck
*reinforcing and grouting per structural, epoxy painted.
- full height 8" thick CMU wall:
8" thick CMU wall infill existing opening
*reinforcing and grouting per structural, epoxy painted.
- full height insulated partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on each side full height to underside of structure with deep leg slip track per detail and sound attenuation batt insulation full height. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- full height partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on each side full height to underside of structure with deep leg slip track per detail. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- furred partition:
3-5/8" metal studs at 16" o.c. with 5/8" gypsum on exposed side to 6" above ceiling or to deck where there is no ceiling. Install batt insulation full height. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- furred partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on exposed side to 6" above ceiling or to deck where there is no ceiling. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- 8" thick CMU wall:
8" thick CMU wall to 10'-8"
*reinforcing and grouting per structural, epoxy painted
- partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on both sides to 6" above ceiling. Install batt insulation. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.

1 Floor Plan
scale: 1/8" = 1'-0"



- Wall height note: Utilize 3 5/8" metal studs @ 16" o.c. to an unbraced height of 13'-8", at heights to 26' use 6" 20 ga. studs @ 16" o.c. - adjust stud size & spacing as req'd. for allowable L/240 deflection for 5 psf wind load. Verify stud gage with supplier.
- Expansion joint note: Expansion joints shall be installed at a max. of 30'-0". Joints shall also be located to coord. w/ anticipated building movement, structural elements, and substrate transitions.
- Wet wall note: Utilize Dens-Armour Plus in all plumbing wet walls, walls receiving ceramic tile, and all walls adjacent to plumbing walls, restrooms and locker rooms or where anticipated to be in contact with moisture. Utilize Dens-Shield at all wet walls and skimoat, if not receiving tile.
- Install slip track per detail where required.

A New Facility for

Automotive Sales & Detail Center

2100 NE Independence Ave
Lee's Summit, Missouri 64064

date: 11.13.2021
drawn by: DAE
checked by: DAE
revisions:
01.25.2021 FDP
02.03.2021 FDP
02.22.2021 permit

sheet number:
A2.1
drawing type:
permit
project number:
19076



03.09.2021

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 11.13.2021
 drawn by DAE
 checked by DAE
 revisions
 01.25.2021 FDP
 02.03.2021 FDP
 02.22.2021 permit
 03.09.2021 01

sheet number
A2.2
 drawing type permit
 project number 19076

general notes:

- Double keyed locks are not permitted on any required or marked exit.
- Exit/emergency lighting are subject to an on site inspection.
- HVAC system to have approved interconnected, smoke detector activated, automatic shutoffs with the detectors located in the return duct.
- Furnish and install approved address numbers on front and rear of building per governing jurisdiction.
- Building construction must fully comply with all requirements of ADA/ANSI accessibility guidelines.
- Provide 44" min. clear in all exit passageways.
- Exit doors shall be operable from the inside without the use of a key or any special knowledge or effort.
- Any new exterior utility service equipment shall be painted to match the building standard colors.
- Furnish and install horns & strobes as required.
- Construction materials exposed within plenums shall be non-combustible or shall have a flame spread rating of not more than 25 and a smoke developed rating of not more than 50.
- All low voltage wire and cable, optical fiber, pneumatic tubing, and all ducts and duct coverings, linings and connectors install within plenum areas must be rated for plenum use.
- Furnish and install data/voice rough-in throughout per owner's requirements.




partition legend:

- P1** full height 12" thick CMU wall:
full height 12" thick CMU wall to deck
*reinforcing and grouting per structural, epoxy painted.
- P2** full height 8" thick CMU wall:
8" thick CMU wall infill existing opening
*reinforcing and grouting per structural, epoxy painted.
- P3** full height insulated partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on each side full height to underside of structure with deep leg slip track per detail and sound attenuation batt insulation full height. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- P4** full height partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on each side full height to underside of structure with deep leg slip track per detail. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- P5** furred partition:
3-5/8" metal studs at 16" o.c. with 5/8" gypsum on exposed side to 6" above ceiling or to deck where there is no ceiling. Install batt insulation full height. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- P6** furred partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on exposed side to 6" above ceiling or to deck where there is no ceiling. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.
- P7** 8" thick CMU wall:
8" thick CMU wall to 10'-8"
*reinforcing and grouting per structural, epoxy painted
- P8** partition:
3 5/8" metal studs at 16" o.c. with 5/8" gypsum on both sides to 6" above ceiling. Install batt insulation. Stud gage per supplier. Utilize Dens-Armour Plus at all restroom walls.

- Wall height note: Utilize 3 5/8" metal studs @ 16" o.c. to an unbraced height of 13'-8", at heights to 26' use 6" 20 ga. studs @ 16" o.c. - adjust stud size & spacing as req'd. for allowable L/240 deflection for 5 psf wind load. Verify stud gage with supplier.
- Expansion joint note: Expansion joints shall be installed at a max. of 30'-0". Joints shall also be located to coord. w/ anticipated building movement, structural elements, and substrate transitions.
- Wet wall note: Utilize Dens-Armour Plus in all plumbing wet walls, walls receiving ceramic tile, and all walls adjacent to plumbing walls, restrooms and locker rooms or where anticipated to be in contact with moisture. Utilize Dens-Shield at all wet walls and skimcoat, if not receiving tile.
- Install slip track per detail where required.

construction notes:

1. Furnish and install 3A-40BC rated F.E. min. 5lb. (surface mounted) with approved mounting @ 48" a.f.f. - verify quantity and location with Fire Marshall.
2. Furnish and install semi-recessed fire extinguisher cabinet with white finish and vision panel in door, with (min. 5lb.) 3A-40BC fire extinguisher, bottom at 36" a.f.f. Coordinate location as directed by Fire Marshall.
3. Furnish and install 4" high, 6" diameter pea gravel concrete filled pipe bollards at interior and exterior (galv.) sides of all overhead doors per details - to be painted safety yellow.
4. Furnish and install concrete stoop at exterior doors per structural.
5. Install trench and floor drain system per MEP drawings. Slope slab to drain.
6. Furnish and install power operated insulated sectional overhead door, tracks and controls for 12' x 14' doors.
7. Furnish and install power operated aluminum/glass sectional overhead door, tracks and controls for 12' x 14' doors.
8. Furnish and install 30" x 36" roof hatch and ladder per detail. Coordinate final location with roof joist layout.
9. Furnish and install 1" clear, insulated glass in thermally broken, clear anodized aluminum storefront frames per details. Caulk around all interior and exterior perimeter joints.
10. Furnish and install Knox Box. Verify location and height with local fire department prior to installation.
11. See detail sheet A4 for top of CMU wall detail.
12. Install new h/lo drinking fountain per MEP and per ADA/ANSI.
13. Furnish and install casework reception desk per details noted on drawings with plastic laminate and solid surfaces at various heights. Provide grommets in countertops per owner requirements. Quantity and location per owner.
14. Furnish and install restrooms with a 67" turning radius w/10" max. overlap for knee and toe clearance per ADA, wall mounted sink with gooseneck/wrist blade faucet at 34" a.f.f., 36" and 42" grab bars, 6" and 12" from corner respectively and 18" vertical grab bar per detail. Include toilet accessories and stainless steel framed mirror in each restroom per drawings. Install blocking for all wall mounted accessories.
15. Furnish and install casework per details in break room with solid surface countertop at 2'-10" a.f.f. and stainless steel sink with gooseneck/wrist blade faucet and plastic laminate base and wall cabinets.
16. Furnish and install casework per details in waiting with solid surface countertop at 2'-10" a.f.f. and plastic laminate base cabinets.
17. Furnish and install bank style transaction window, clear anod. alum. with tempered clear glass, voice hole and slide under document tray. Furnish and install plastic laminate sill on both sides of window per detail.
18. Furnish and install blocking and electrical for owner supplied TVs. Verify final location with owner.
19. Furnish and install janitor mop basin with shelf above. Provide blocking as required.
20. Install 4' x 8' plywood on utility walls for MEP and voice/data installation.
21. Furnish and install push button ADA control for doors 01 and 02. Refer also to electrical.
22. Furnish and install eye wash sink, per MEP.
23. Install hand wash sink with soap and towel dispensers.







A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date: 02.22.2021
drawn by: DAE
checked by: DAE
revisions:
DATE: 02.22.2021


sheet number
A2.4
drawing type: permit
project number: 19076



1 First Floor Reflected Ceiling Plan
scale: 1/8" = 1'-0"



2 head detail
scale: 3/4" = 1'-0"



3 head detail
scale: 3/4" = 1'-0"

reflected ceiling notes:

1. Refer to general notes and specifications for more information.
2. Refer to engineering drawings for HVAC and electrical fixtures, specifications and details.
3. Refer to engineering drawings for emergency fixture locations and specifications.
4. Refer to engineering drawings for light fixture specifications.
5. All soffits and headers to be painted per finish schedule and reflected ceiling plan.
6. Acoustical ceiling tile and grid per room finish legend and reflected ceiling notes.

reflected ceiling legend:

- 2x4 lay-in LED light fixture with direct/indirect lens
- LED high bay light fixture
- recessed can LED light fixture
- 4'-0" long strip LED light fixture, hung from structure
- CLG-1: Armstrong, Fine Fissured, 1732, 24" x 24" x 5/8", with 15/16" angled tegular edge, white grid
- CLG-2: gypsum board ceiling, painted




03.09.2021

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date: 02.22.2021
 drawn by: DAE
 checked by: DAE
 revisions:

sheet number:
A2.5
 drawing type: permit
 project number: 19076



1 Mezzanine Reflected Ceiling Plan
 scale: 1/8" = 1'-0" north

reflected ceiling notes:

1. Refer to general notes and specifications for more information.
2. Refer to engineering drawings for HVAC and electrical fixtures, specifications and details.
3. Refer to engineering drawings for emergency fixture locations and specifications.
4. Refer to engineering drawings for light fixture specifications.
5. All soffits and headers to be painted per finish schedule and reflected ceiling plan.
6. Acoustical ceiling tile and grid per room finish legend and reflected ceiling notes.






reflected ceiling legend:

- 2x4 lay-in LED light fixture with direct/indirect lens
- LED high bay light fixture
- recessed can LED light fixture
- 4'-0" long strip LED light fixture, hung from structure
- CLG-1: Armstrong, Fine Fissured, 1732, 24" x 24" x 5/8", with 15/16 angled tegular edge, white grid
- CLG-2: gypsum board ceiling, painted




02.22.2021


Exterior Materials and Colors:

-  EIFS-1
3" drainable EIFS system, fine finish with standard "V" groove color: light gray (Sherwin Williams SW7064 Passive)
-  EIFS-2
2" drainable EIFS system, fine finish with standard "V" groove color: medium gray (Sherwin Williams SW7066 Gray Matters)
-  CMU-1
smooth face exterior concrete masonry units, painted, color: Sherwin Williams SW7067 "Cityscape", Pro Industrial High Performance Epoxy, semi-gloss, (1 coat primer, 2 coats paint to cover)
-  CMU-2
smooth face exterior concrete masonry units, painted accent color: Sherwin Williams SW9177 "Salty Dog" w/ medium, 2 coat, textured paint system w/ primer. cmu and mortar shall include integral water repellent
-  MP-1
prefinished metal wall panel, MBCI 7.2 Panel, prefinished, bold corrugated rib color: silver metallic


- storefront:**
thermally broken anodized aluminum frame, color: clear
- glass:**
1 insulated clear glass with low-E coating and argon fill *use SOLARBAN 60 as basis
- F-1 flashing:**
prefinished, color: silver metallic
- caulk:**
color to match adjacent walls
- exterior hollow metal doors, frames, trash enclosure gates:**
paint to Sherwin Williams SW7067 "Cityscape", Pro Industrial High Performance Epoxy, semi-gloss, (1 coat primer, 2 coats paint to cover)
- bollards:**
galvanized, paint safety yellow
- overhead doors:**
prefinished to match EIFS-2
- prefinished metal canopies:**
pre-finished Super Lumideck Flat Soffit Canopy, Mapes, color: Interstate Blue




1 East Elevation
 scale: 1/8" = 1'-0"



2 South Elevation
 scale: 1/8" = 1'-0"



3 West Elevation
 scale: 1/8" = 1'-0"



4 North Elevation
 scale: 1/8" = 1'-0"

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date: 11.13.2020
 drawn by: DAE
 checked by: DAE
 revisions:
 1/25/2021
 02.03.2021
 02.22.2021

sheet number:
A3.1
 drawing type:
 permit
 project number:
 19076




02.22.2021


A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 11.13.2020
 drawn by DAE
 checked by DAE
 revisions
 02.22.2021 permit

sheet number
A3.2
 drawing type permit
 project number 19076




2 Section @ Trash Encl.
 scale 3/4" = 1'-0"




1 Trash Enclosure
 scale: 1/4" = 1'-0"




02.22.2021




4 Building Section
 scale: 1/8" = 1'-0"



3 Building Section
 scale: 1/8" = 1'-0"



2 Building Section
 scale: 1/8" = 1'-0"



1 Building Section
 scale: 1/8" = 1'-0"

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.22.2021
 drawn by DAE
 checked by DAE
 revisions

sheet number
A4.1
 drawing type permit
 project number 19076




02.22.2021


A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date 02.22.2021
drawn by DAE
checked by DAE
revisions


sheet number
A4.2
drawing type permit
project number 19076




4 Wall Section
scale: 1/2" = 1'-0"



3 Wall Section
scale: 1/2" = 1'-0"



2 Wall Section
scale: 1/2" = 1'-0"



1 Wall Section
scale: 1/2" = 1'-0"

*all cmu sub-straight & cmu mortar shall include integral water repellent
*refer to structural drawings to verify all bearing heights (typical)




02.22.2021


A New Facility for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lee's Summit, Missouri 64064

date 02.22.2021
drawn by DAE
checked by DAE
revisions


sheet number
A4.3
drawing type permit
project number 19076




8 Wall Section
scale: 1/2" = 1'-0"



7 Wall Section
scale: 1/2" = 1'-0"



6 Wall Section
scale: 1/2" = 1'-0"



5 Wall Section
scale: 1/2" = 1'-0"




02.22.2021


A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.22.2021
 drawn by DAE
 checked by DAE
 revisions


sheet number
A4.4
 drawing type permit
 project number 19076




12 Wall Section
 scale: 1/2" = 1'-0"




11 Wall Section
 scale: 1/2" = 1'-0"




10 Wall Section
 scale: 1/2" = 1'-0"




9 Wall Section
 scale: 1/2" = 1'-0"



15 Wall Section
 scale: 1/2" = 1'-0"



14 Wall Section
 scale: 1/2" = 1'-0"



13 Wall Section
 scale: 1/2" = 1'-0"


A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date: 02.22.2021
 drawn by: DAE
 checked by: DAE
 revisions:


sheet number
A4.5
 drawing type: permit
 project number: 19076



02.22.2021



2 Railing Elevation
 scale: 1" = 1'-0"



1 Stair Section
 scale: 1/2" = 1'-0"


A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date
 02.22.2021
 drawn by
 DAE
 checked by
 DAE
 revisions


sheet number
A4.6
 drawing type
 permit
 project number
 19076




02.22.2021




14 Detail
 scale: 1 1/2" = 1'-0"




15 Detail
 scale: 1 1/2" = 1'-0"




17 Detail
 scale: 1 1/2" = 1'-0"




16 Detail
 scale: 1 1/2" = 1'-0"




11 Detail
 scale: 1 1/2" = 1'-0"




12 Detail
 scale: 1 1/2" = 1'-0"




13 Detail
 scale: 1 1/2" = 1'-0"




6 Detail
 scale: 1 1/2" = 1'-0"




7 Detail
 scale: 1 1/2" = 1'-0"




8 Detail
 scale: 1 1/2" = 1'-0"




9 Detail
 scale: 1 1/2" = 1'-0"




10 Detail
 scale: 1 1/2" = 1'-0"




1 Detail
 scale: 1 1/2" = 1'-0"




2 Detail
 scale: 1 1/2" = 1'-0"



3 Detail
 scale: 1 1/2" = 1'-0"



4 Detail
 scale: 1 1/2" = 1'-0"



5 Detail
 scale: 1 1/2" = 1'-0"

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.22.2021
 drawn by DAE
 checked by DAE
 revisions

sheet number
A4.7
 drawing type permit
 project number 19076





A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date 02.22.2021
 drawn by DAE
 checked by DAE
 revisions


sheet number
A5.1
 drawing type permit
 project number 19076

* furnish and install tempered glass at all interior door and window locations. (typical at all glazing openings)


* field verify all openings prior to installation.




1 Door Types
 scale: 1/4" = 1'-0"



2 Frame Types
 scale: 1/4" = 1'-0"



3 Window Types
 scale: 1/4" = 1'-0"



4 Threshold Types
 scale: 1 1/2" = 1'-0"


door & hardware notes:

- Door frames shall be 16 ga. with mitered and welded corners.
- All hinges at exterior doors shall have non-removable pins.
- Doors with closers shall have ball bearing hinges.
- Wood doors shall be solid core wood, plain sliced red oak "select" and "clear". Stain to match sample.
- Thresholds shall coordinate with adjacent floor finish at either side.
- Hardware shall be heavy-duty, commercial grade, level 1 with lever handle.
- Hardware shall be manufactured by Schlage or approved equal.
- Finish hardware shall meet article III of the ADA.
- Keying shall be coordinated with owner prior to order of hardware.
- All interior storefront systems shall be clear anodized aluminum finish.
- All hardware sets shall be fitted with Schlage "C" keyway compatible cylinders - 6 pin - "0" bit. and shall have interchangeable cores.
- All hollow metal door frames shall be caulked around entire perimeter and at the inside corners.
- All exterior hollow metal doors shall include a rain guard.
- All overhead doors shall have 3" tracks, 100,000 cycle spring counterbalance.

glazing notes:

- Furnish and install tempered glass at all doors and at a minimum of 24" either side of doors to a minimum height of 60". Tempered glass shall also be installed at all glass within 18" of finish floor adjacent to sidewalk areas. (typical at all glazing locations)
- Tempered glass shall conform to safety glazing in hazardous locations requirements as outlined per 2012 IBIC, 2406 and 2406.3
- Field verify all openings prior to installation.

door #	doors						frames					fire rating	hardware group	access control	remarks	
	type	mat.	finish	size			type	material	finish	details						
				width	height	thick				head	jamb					sill
01	C	alum./gl.	clr.anod.	pr. 3'-0"	7'-0"	1 3/4"	1	alum.	clr. anod.	-	-	t-3	-	1	-	
02	C	alum./gl.	clr.anod.	pr. 3'-0"	7'-0"	1 3/4"	1	alum.	clr. anod.	-	-	t-3	-	3	-	
03	C	alum./gl.	clr.anod.	3'-0"	7'-2"	1 3/4"	1	alum.	clr. anod.	-	-	t-3	-	2	-	
04	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	
05	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	
06	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	
07	C	alum./gl.	clr.anod.	3'-0"	7'-2"	1 3/4"	1	alum.	clr. anod.	-	-	t-3	-	2	-	
08	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	8	-	
09	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	9	-	
10	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	9	-	
11	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	
12	C	alum./gl.	clr.anod.	3'-0"	7'-2"	1 3/4"	1	alum.	clr. anod.	-	-	t-3	-	2	-	
13	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	
14	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	8	-	
15	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	7	-	
16	F	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-8	-	11	-	
17	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
18	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
19	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
20	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
21	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
22	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-2	t-1	4	-	
23	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	-	8	-	
24	D	insul. st.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-3	t-2	-	-	
25	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-2	-	8	-	
26	B	galv.h.m.	prefin.	pr. 3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	t-1	5	-	
27	D	insul. st.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-3	t-2	-	-	
28	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-2	t-1	4	-	
29	D	insul. st.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-3	t-2	-	-	
30	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-2	-	8	-	
31	B	galv.h.m.	prefin.	pr. 3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	t-1	5	-	
32	B	galv.h.m.	prefin.	pr. 3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	-	6	-	
33	D	insul. st.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-3	t-2	-	-	
34	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-2	t-1	4	-	
35	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
36	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
37	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
38	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
39	E	alum./gl.	prefin.	12'-0"	14'-0"	2"	-	-	-	-	-	j-6	t-2	-	-	
40	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	h.m.	paint	-	-	j-2	t-1	4	-	
41	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	-	8	-	
42	B	galv.h.m.	prefin.	pr. 3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	t-1	5	-	
43	B	insul. st.	paint	3'-0"	7'-0"	1 3/4"	2	galv. mtl.	paint	-	-	j-2	-	10	-	
201	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	8	-	
202	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	
203	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	1	h.m.	paint	-	-	j-1	-	9	-	
204	A	s.c. wood	stain/finish	3'-0"	7'-0"	1 3/4"	3	h.m.	paint	-	-	j-1	-	7	-	



5 Jamb Types
 scale: 1" = 1'-0"

finish legend













sc	sealed concrete with clear Ashford sealer 2 coats - concrete floors to be free of bumps, pits, scrapes, etc.
ef-1	epoxy flooring
b-1	standard cove 4" vinyl base, Roppe, color: TBD
ct-1	ceramic tile flooring, Premier Tile, Interceramic - Wilshire, color: Ash, finish: matte (contact Mariana Eastham at Mariana.Eastham@jaeckledistributors.com or 913.484.2691 for pricing and ordering)
ct-2	ceramic tile flooring, Premier Tile, Interceramic - Wilshire, color: Ash, finish: polished (contact Mariana Eastham at Mariana.Eastham@jaeckledistributors.com or 913.484.2691 for pricing and ordering)
cwt-1	ceramic wall tile, Interceramic, Seaside color: Glossy Blue (contact Mariana Eastham at Mariana.Eastham@jaeckledistributors.com or 913.484.2691 for pricing and ordering)
cpt-1	carpet tile, J+J flooring, collection: Schematic, color: Template, 24"x24" tile, install pattern: brick (contact Elizabeth Lester at elizabeth.lester@jjflooring.com or 816.605.3351 for pricing and ordering)
lv-1	luxury vinyl tile, Patcraft, collection: Set in Concrete - Aggregate, color: Fragment, 24"x24" tile, install pattern: ashlar (contact .com or for pricing and ordering)
pt-1	wall paint, sherwin williams, ProMar 200 Zero VOC Interior Latex Paint, color: SW7661 Reflection (1 coat primer, 2 coats paint - to cover) - level 4 finish
pt-2	wall paint, sherwin williams, color: SW7663 Monoral Silver (1 coat primer, 2 coats paint - to cover) - level 4 finish
pt-3	restroom wall paint, sherwin williams, Pro Industrial Pre-Catalyzed Waterbased Epoxy, color: SW6232 Misty (1 coat primer, 2 coats paint - to cover)
pt-4	ceiling dryfall paint, sherwin williams, Low VOC Waterborne Acrylic Dryfall, color: SW7009 Pearly White (1 coat primer, 2 coats paint - to cover) - level 5 finish
pt-5	trim paint, sherwin williams, ProMar 200 Alkyd Paint color: TBD, premium grade latex semi-gloss enamel, (1 coat primer, 2 coats paint - to cover) - for all hollow metal door frames - level 4 finish
pt-6	exterior metal, Pro Industrial High Performance Epoxy, semi-gloss, (1 coat primer, 2 coats paint - to cover)
ss-1	solid surface, LG Hausys HI MACS, color: Arcas T050 (contact Spenser Lehmann at slegmann@lghausy.com or 816.446.8225 for pricing and ordering)
ss-2	solid surface countertops, Wilsonart, color: TBD (contact Mandy Bridges at Mandy.Bridges@VirginiaTile.com or 913.484.2691 for pricing and ordering)
pl-1	plastic laminate, Wilsonart, Randolph Forest 8225, finish: Ridgewood with AEON (contact Mandy Bridges at Mandy.Bridges@VirginiaTile.com or 913.484.2691 for pricing and ordering)
pl-3	plastic laminate cabinets, Wilsonart, color: Beige Pampas 4170, finish: matte finish (contact Mandy Bridges at Mandy.Bridges@VirginiaTile.com or 913.484.2691 for pricing and ordering)
clg-1	acoustical ceiling tile, Armstrong, Ultima beveled tegular #1901, color: white, 24" x 24", beveled tegular tile, fine texture, Prelude XL 15/16" exposed tee grid
dr	solid core wood doors, plain sliced "select" and "clear" maple stain and finish, color:TBD
toilet part.	HDPE solid plastic, color: TBD
frp-1	fiberglass reinforced panels - Marlite, standard color light gray P151, pebbled surface

finish notes

- e.t.r. = existing to remain.
- All structural steel beams, columns and joists shall be primed gray.
- Temper all interior glass.
- Each material specified for application on the entire project shall be from the same dye lot.
- All surfaces shall be cleaned and conditioned to receive new finish as required by finish product manufacturer. Surfaces shall be smooth, free from depressions, protrusions, pits, slumps, streaks, flashing, and variation in texture. Installer/subcontractor shall notify general contractor prior to installation if conditions are not satisfactory.
- All wall mounted mechanical slots or grilles to be painted to match the wall on which they occur. Do not paint prefinished wall mullion end caps.
- Contractor shall be responsible for leveling of floor slabs to receive specified finishes.
- All patterned flooring to be centered in both directions and generated from center of room outward toward partitions, unless otherwise noted.
- All floor finish changes to occur under centerline of door in closed position.
- Combustible interior finish products shall be provided per the requirement of the International Building Code section 803.4.
- Finishes shall be bid as specified or as approved equal only.
- Utilize dens-armour plus in all plumbing wet walls, walls anticipated to be in contact with moisture, and walls to receive ceramic tile.
- Refer to finish legend for level of gypsum board finish as defined by the gypsum association.


room finish schedule

room no.	room name	floor								base				wall				ceiling			remarks
		sc	ef-1	cpt-1	ct-1	ct-2	lv-1	b-1	ct-2	ef-1	none	north	south	east	west	clg-1	open dryfall	gyp. bd. pt.	none		
101	vestibule										pt-1	pt-1	pt-1	pt-1						9'-2"	
102	lobby										pt-1	pt-1	pt-1	pt-1						open	
103	waiting										pt-1	pt-1	pt-1	pt-1						9'-0"	
104	sales office										pt-2	pt-1	pt-2	pt-1						9'-0"	
105	office										pt-1	pt-1	pt-1	pt-2						9'-0"	
106	office										pt-1	pt-1	pt-1	pt-2						9'-0"	
107	office										pt-1	pt-1	pt-2	pt-1						9'-0"	
108	stairs										pt-1	pt-1	pt-1	pt-1						9'-0"	
109	corridor										pt-1	pt-1	pt-1	pt-1						9'-0"	
110	janitor										frp-1/pt-1	pt-1	pt-1	frp-1/pt-1						open (install frp panels behind mop sink and extend 24" on both side walls, up to 48")	
111	men's										cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3						9'-0"	
112	women's										cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3						9'-0"	
113	men's										cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3						9'-0"	
114	detail office										pt-1	pt-2	pt-1	pt-1						9'-0"	
115	corridor										pt-1	pt-1	pt-1	pt-1						9'-0"	
116	storage										pt-1	pt-1	pt-1	pt-1						9'-0"	
117	tech break room										pt-1	pt-1	pt-1	pt-1						9'-0"	
118	corridor										pt-1	pt-1	pt-1	pt-1						10'-1"	
119	storage										pt-1	pt-1	pt-1	pt-1						-	
120	detail bay										pt-1	-	pt-1	-						-	
121	detail bay										-	pt-1	pt-1	-						-	
122	detail bay										pt-1	-	-	-						-	
123	detail bay										pt-1	-	-	-						-	
124	detail bay										pt-1	-	-	-						-	
125	detail bay										-	pt-1	-	-						-	
126	detail bay										-	pt-1	-	-						-	
127	detail bay										pt-1	-	-	-						-	
128	reconditioning										pt-1	-	-	pt-1						-	
129	reconditioning										-	pt	-	pt-1						-	
130	hand wash bay										pt-1	pt-1	pt-1	pt-1						-	
131	car wash equipment										pt-1	pt-1	pt-1	pt-1						-	
132	utility										pt-1	pt-1	pt-1	pt-1						-	
133	mechanical car wash bay										pt-1	pt-1	pt-1	pt-1						-	
201	corridor										pt-1	pt-1	pt-1	pt-1						9'-0"	
202	IT										pt-1	pt-1	pt-1	pt-1						open	
203	office										pt-1	pt-1	pt-1	pt-2						9'-0"	
204	restroom										cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3	cwt-1/pt-3						9'-0"	
205	training room										pt-1	pt-1	pt-1	pt-1						9'-0"	





02.22.2021




door hardware schedule				
set no.	item	description	finish	remarks
1	3 pair hw hinges	5bb1 4.5 x 4.5 nrp - ives	652	door part of storefront system - verify with supplier required hardware application
	2 panic hardware	33a-nl-op - von w/ Schlage cylinder	626	
	2 10" door pull	8103HD-0 - ives	630	
	2 surface closer	4110 cush w/ drop plate & mtg. bkts. - lcn	689	
	1 perimeter seal	by door mfr.	gray	
	2 door sweep	101na - ngp	aluminum	
2	1 threshold	425 - ngp	aluminum	door part of storefront system - verify with supplier required hardware application
	1-1/2 pair hw hinges	5bb1 4.5 x 4.5 nrp - ives	652	
	1 panic hardware	33a-nl-op - von w/ Schlage cylinder	626	
	1 10" door pull	8103HD-0 - ives	630	
	1 surface closer	4110 cush w/ drop plate & mtg. bkts. - lcn	689	
	1 perimeter seal	by door mfr.	gray	
3	1 door sweep	101na - ngp	aluminum	door part of storefront system - verify with supplier required hardware application
	1 threshold	425 - ngp	aluminum	
	3 pair hw hinges	5bb1 4.5 x 4.5 - ives	652	
	2 90° push and pull set - 33"	9190E2HD - ives	630	
	2 surface closer	4110 cush w/ drop plate & mtg. bkts. - lcn	689	
	6 silencers	sr64 - ives	gray	
4	1-1/2 pair hw hinges	5bb1 hw 4.5 x 4.5 nrp - ives	652	
	1 storeroom lock	nd96pd rho - sch	626	
	1 surface closer	4050 scush - lcn	689	
	1 drip cap	16a - ngp	aluminum	
	1 perimeter seal	700na - ngp	gray	
	1 door sweep	101na - ngp	aluminum	
5	1 threshold	425 - ngp	aluminum	
	1 kickplate	8400 10" - ives	630	
	3 pair hw hinges	5bb1 hw 4.5 x 4.5 nrp - ives	652	
	1 storeroom lock	nd96pd rho - sch	626	
	1 dummy	nd170 rho - sch	626	
	1 surface closer	4050 scush - lcn	689	
6	1 set up/down manual flush bolts	FB458 - ives	626	include strike
	2 drip cap	16a - ngp	aluminum	
	1 perimeter seal	700na - ngp	gray	
	2 door sweep	101na - ngp	aluminum	
	1 threshold	425 - ngp	aluminum	
	1 kickplate	8400 10" - ives	630	
7	3 pair hw hinges	5bb1 4.5 x 4.5 - ives	652	
	1 storeroom lock	nd80pd rho - sch	626	
	1 dummy	nd170 rho - sch	626	
	1 set up/down manual flush bolts	FB458 - ives	626	
	6 silencers	sr64 - ives	gray	
	1 1/2 pair hw hinges	5bb1 - 4.5 x 4.5 - ives	652	
8	1 office lockset	nd50rd rho - schlage	626	
	3 silencers	sr64 - ives	gry	
	1 wall stop	ws407ccv - ives	630	
	1 1/2 pair hw hinges	5bb1 - 4.5 x 4.5 - ives	652	
	1 storeroom lockset	nd80rd rho - schlage	626	
	3 silencers	sr64 - ives	gry	
9	1 wall stop	ws407ccv - ives	630	
	1 1/2 pair hw hinges	5bb1 - 4.5 x 4.5 - ives	652	
	1 privacy lockset	nd40s rho - schlage	626	
	3 silencers	sr64 - ives	gry	
	1 wall stop	ws407ccv - ives	630	
	1 coat/purse hook	B-6727 - Bobrick	630	
10	1 1/2 pair hw hinges	5bb1 4.5 x 4.5 - ives	652	
	1 push plate	8200 4" x 16" - ives	630	
	1 pull plate	8303 4" x 16" - ives	630	
	1 closer	1461 cush - lcn	689	
	3 silencers	sr64 - ives	gry	
	1 kickplate	8400 10" - ives	630	
11	1 1/2 pair hw hinges	5bb1 4.5 x 4.5 - ives	652	
	1 classroom lockset	nd70rd rho - schlage	626	
	1 closer	1461 cush - lcn	689	
	3 silencers	sr64 - ives	gry	
	1 wall stop	ws407ccv - ives	630	
	1 kickplate	8400 10" - ives	630	

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064







date
 02.22.2021
 drawn by
 DAE
 checked by
 DAE
 revisions


sheet number
A5.4
 drawing type
 permit
 project number
 19076



1 First Floor Finish Plan
 scale: 1/8" = 1'-0" north

flooring legend:

-  sc - refer to finish legend sealed concrete
-  ef-1 - refer to finish legend epoxy flooring
-  ct-1 - refer to finish legend ceramic floor tile
-  ct-2 - refer to finish legend ceramic floor tile
-  lvt-1 - refer to finish legend luxury vinyl tile
-  cpt-1 - refer to finish legend carpet tile



2 Mezzanine Finish Plan
 scale: 1/8" = 1'-0" north

A New Facility for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lee's Summit, Missouri 64064

date: 02.22.2021
 drawn by: DAE
 checked by: DAE
 revisions:

sheet number
A5.5
 drawing type: permit
 project number: 19076

Governing Building Code: 2018 IBC

Design Specifications:

- ASCE 7-16
ACI 318-14
ACI 530-16
AISC 360-16
AISC 341-16
AISI S100-16
ANSI / AWC NDS-18

Roof Loads:

- Dead Load: 15 psf
Live Load: 20 psf
Velocity: 110 mph
Exposure: C
Iw: 1.0

Wind Loads:


- Occupancy: II
Velocity: 110 mph
Exposure: C
Iw: 1.0

Seismic Loads:

- Ie: 1.0
Ss: 0.099 g
S1: 0.068 g
Site Class: D
Sds: 0.106 g
Sd1: 0.109 g

Design Loading Notes:

- Dead load shown includes collateral load of 3 psf.
Dead load at Service Bay area collateral of 7 psf for Solar Panels.
See components and cladding table for design wind pressures.
See net uplift diagram for roof framing due to wind pressures.




COMPONENTS AND CLADDING WIND PRESSURES

Table with columns: Zone, Effective Wind Area (sq ft), Max. +VE Pressure (psf), Max. -VE Pressure (psf). Rows include Roof Interior, Roof Edge, Roof Corner, Wall Interior, Wall Edge for various zones.

Components & Cladding Wind Zone Diagram

- The components & cladding (C&C) wind pressures shown assume a mean roof height of 28'-0" above finished floor elevation.
The components & cladding wind zone diagram is generalized to show all possible conditions.
a = 8'-0"



General:

- The structural systems shown on these documents have been designed for the final, in place usage of the structure based on the intended occupancy and code requirements.
The Contractor shall field verify all existing dimensions prior to fabrication.
The Contractor shall notify the Engineer of any observed discrepancies in dimensions, detailing, or other items as shown on the plans or specified prior to proceeding with work relating to said discrepancies.

Structural Engineer Site Observations:

- The contract structural drawings & specifications represent the finished structure, and, except where specifically shown, do not indicate the method or means of construction.
The Engineer shall not have control nor charge of and shall not be responsible for, construction means, methods, techniques, sequences, or procedures, for safety precautions & programs in connection with the work.

Slab On Grade:

- Welded wire fabric shall be supplied in sheets only. Rolls will not be permitted.
Welded wire fabric shall be supported on chairs or blocks prior to concrete placement.
Welded wire fabric shall have end and edge laps of one full mesh plus 2" between cross wires.

- Foundations: Foundations for this project have been designed in accordance with requirements set forth in a geotechnical report prepared by Intertek PSI in Report No. 03382128 dated October 2, 2020.
Anchor rods shall conform to ASTM F1554 Gr. 36 (U.N.O.) and shall be located by means of a template.

Concrete and Reinforcing Steel:

Table with columns: Location, Minimum Compressive Strength (psi), Max. Aggregate Size, Max. Water/Cement Ratio, Slump (in.), Air Entrainment (%). Rows include Interior Slabs, Exterior Slabs, Interior Foundations, Perimeter Foundations, Exterior Walls & Pedestals, Composite Floor Slab.

- Fly ash shall not be used unless approved in writing by the Engineer.
The use of admixtures to increase the slump shall not be used unless approved in writing by the Engineer.
All concrete is reinforced unless specifically called out as unreinforced.

- Reinforcing bars #4 and larger (except ties and stirrups) shall meet ASTM A615 with Supplementary Requirements (S1), Grade 60.
Concrete coverage of reinforcement shall have the following clear distances unless noted otherwise on the drawings: Cast against earth: 3"

- Embedded and all reinforcing bars marked continuous shall be embedded to develop the full tensile capacity of the bar.
Supply corner bars 4'-0" long (min. 2'-0" in each direction) in outside face of wall at corners of all walls and grade beams.

- Concrete placed during cold weather shall conform to the requirements of the most recent version of ACI 306R.
Concrete placed during hot weather shall conform to the requirements of the most recent version of ACI 305R.

- Do not add water to concrete during delivery, at Project Site, or during placement, unless approved by the Engineer.
All cold joints shall be roughened and cleaned unless noted otherwise.

- Vertical control joints in walls shall be placed at 30'-0" maximum spacing unless noted otherwise.
Refer to the geotechnical report for behind wall drainage recommendations.

Post-Installed Anchors:

- Post-Installed anchors shall only be used where specified in the construction documents or approved by the engineer.
The Contractor shall obtain written approval from the Engineer prior to installing post-installed anchors for misplaced-placed anchors.

- All adhesive anchoring systems referred to in these drawings shall be one of the following:
a. Hilti HIT HY 200
b. Powers AC108+ Gold
c. Simpson Strong-Tie SET-3G
d. Or Approved Equivalent

Masonry:

- Mortar shall be Type S for all masonry work and must achieve a minimum compressive strength of 1800 psi at the 28-day test.
Masonry grout shall be a coarse-type grout and must achieve a minimum compressive strength of 2000 psi at the 28-day test.

- Foundations for this project have been designed in accordance with requirements set forth in a geotechnical report prepared by Intertek PSI in Report No. 03382128 dated October 2, 2020.
Anchor rods shall conform to ASTM F1554 Gr. 36 (U.N.O.) and shall be located by means of a template.

- Concrete mix designs shall meet the following requirements:
Location, Minimum Compressive Strength (psi), Max. Aggregate Size, Max. Water/Cement Ratio, Slump (in.), Air Entrainment (%)

- Connection Bolts: ASTM A325
Anchor Rods: ASTM F1554, Grade 36
Shear Studs: ASTM A108, Grade 1015 through 1020

- Welding shall conform to the latest publication of applicable codes set forth by the American Welding Society.
Welding electrodes shall be E70XX.

- All exterior steel exposed to weather shall be hot-dipped galvanized and/or painted per Architect unless noted other wise.

- Weld all joists to supporting members with 1/8" x 2" long fillet welds on each side of the joist.
All roof bar joists shall be designed for uplift as stipulated by the applicable building code.

- All pipe hangers supporting more than 100 lbs. and being supported from steel bar joists or joist girders shall be hung from top chords and within 2" of web panel points.
All openings in the roof shall be framed with a 4 x 4 x 1/4 angle minimum, unless noted otherwise.

- Concrete placed during cold weather shall conform to the requirements of the most recent version of ACI 306R.
Concrete placed during hot weather shall conform to the requirements of the most recent version of ACI 305R.

- Do not add water to concrete during delivery, at Project Site, or during placement, unless approved by the Engineer.
All cold joints shall be roughened and cleaned unless noted otherwise.

- Vertical control joints in walls shall be placed at 30'-0" maximum spacing unless noted otherwise.
Refer to the geotechnical report for behind wall drainage recommendations.

Post-Installed Anchors:

- Post-Installed anchors shall only be used where specified in the construction documents or approved by the engineer.
The Contractor shall obtain written approval from the Engineer prior to installing post-installed anchors for misplaced-placed anchors.

- All adhesive anchoring systems referred to in these drawings shall be one of the following:
a. Hilti HIT HY 200
b. Powers Wedge Bolt+
c. Simpson Strong-Tie Titan HD
d. Or Approved Equivalent

ABBREVIATIONS LIST

Table with columns: Symbol, AND, DEGREES, FEET, GREATER THAN, LESS THAN, PLUS, MINUS, EQUALS, ISOMETRIC, GENERAL NOTES, FOUNDATION PLAN, MEZZANINE FRAMING PLAN, TYPICAL FOUNDATION DETAILS, FOUNDATION DETAILS, TYPICAL FRAMING DETAILS, TYPICAL FRAMING DETAILS, TYPICAL FRAMING DETAILS, FRAMING DETAILS, MASONRY ELEVATIONS, MASONRY ELEVATIONS, MATERIALS LEGEND, SYMBOLS LEGEND.

Table with columns: Sheet Number, Sheet Name, ALUMINUM, CONCRETE, EARTH, GRAVEL, GYPSUM, INSULATION - RIGID, MASONRY - BRICK, MASONRY - CMU, PLYWOOD, STEEL, TILT / PRE-CAST, DETAIL, ELEVATION, SECTION, BEAM DESIGNATION, COLUMN DESIGNATION, FOOTING DESIGNATION, PIER DESIGNATION, COLUMN GRID, MOMENT CONNECTION, NORTH ARROW, REVISION DESIGNATION, JOIST BEARING ELEVATION, SLAB THICKNESS TRANSITION.

4301 Indian Creek Parkway
Overland Park, KS 66207
phone: 913.451.9390
fax: 913.451.9391
www.davidsonae.com

BSE STRUCTURAL ENGINEERS
11320 West 79th Street
Lenexa, Kansas 66214
Phone 913.492.7400
www.BSEstructural.com
Project Number 20-467



Automotive Sales & Detail Center
2100 NE Independence Ave
Lees Summit, Missouri 64064

date 02.23.2021
drawn by ZNP
checked by RS
revisions

sheet number SO.0
GENERAL NOTES
drawing type project number

4301 Indian Creek Parkway
Overland Park, KS 66207
phone: 913.451.9390
f a x : 913.451.9391
www.davidsonae.com



11320 West 79th Street
Lenexa, Kansas 66214
Phone 913.492.7400
www.BSEstructural.com
Project Number 20-467



a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees's Summit, Missouri 64064

date
02.23.2021
drawn by
Author
checked by
Checker
revisions

sheet number
SO.01
GENERAL NOTES

drawing type
project number

Special Inspector:

- The following items require special inspection in accordance with the building code.
 - Reinforced masonry construction - level 1 inspection
 - Concrete & masonry grout design mix
 - Placing of concrete & reinforcing steel
 - Bolts & anchors embedded in concrete & masonry
 - Concrete formwork
 - Structural steel fabrication
 - Structural steel bolting & welding
 - Inspection of roof & deck attachment
 - Post installed anchors in masonry & concrete
 - In-situ soils, excavations, filling & compaction
- The Contractor shall request special inspection of the items listed above prior to those items becoming inaccessible & unobservable due to progression of the work.
- The Special Inspector shall be a qualified person who shall demonstrate competence, to the satisfaction of the building official, for inspection of the particular type of construction or operation requiring special inspection.
- The Special Inspector shall observe the work assigned for conformance with the approved design drawings and specifications.
- The Special Inspector shall furnish inspection reports to the Building Official, the Engineer and Architect of record, and other designated persons. All discrepancies shall be brought to the immediate attention of the Contractor for correction, then if uncorrected, to the proper design authority and to the Building Official.
- The Special Inspector shall submit a final signed report stating whether the work requiring special inspection was, to the best of the inspector's knowledge, in conformance with the approved plans and specifications and the applicable workmanship provisions of the governing building codes.

Earthwork:

- The Inspector must verify that the preparation of the natural ground and the placement of engineered fill is performed in accordance with the GEOTECHNICAL engineer's recommendations as stated in the GEOTECHNICAL report.
- The Inspector must monitor the placement of all fill to determine whether the type of material, moisture content, and degree of compaction are within the recommended limits contained in the GEOTECHNICAL report. Proceed with subsequent earthwork only after test results for previously completed work comply with recommended limits contained in the GEOTECHNICAL report.
- All Subgrade supporting footings and slabs must be inspected immediately prior to the placement of reinforced concrete.
- Paved and building slab areas shall be tested at Subgrade and at each compacted fill and backfill layer, at least once for every 2000 sq. ft. or less of paved or building slab areas, but in no case fewer than 3 tests.
- Foundation wall backfill shall be tested at each compacted initial and final backfill layer, at least once for each 100 ft. or less of wall length, but no fewer than 2 tests.
- Trench backfill shall be tested at each compacted initial and final backfill layer, at least once for each 150 ft. or less of trench length, but no fewer than 2 tests.
- Test compaction of soils-in-place in accordance with ASTM D 1556, ASTM D 2167, ASTM D 2922, and ASTM D 2937, as applicable.
- Test Reporting: Test results must be reported to BSE and the general contractor in writing within 24 hours after testing, via fax. Reports must contain the project name, the date of the test and the location of the test.

Concrete:

- Strength test cylinders shall be prepared for each day's pour of each concrete mix and at a minimum frequency of every 50 cu. yd. on all concrete placed. Conform to ASTM C39.
- Four (4) test cylinders are to be made and cured on site for the first 24 hours. Test one of the specimens at 7 days and two at 28 days. Hold the fourth specimen in reserve for later testing if needed.
- Slump, air content and temperature tests shall be conducted at a minimum when strength specimens are made and at any other times as specified by the Engineer.
- Perform slump tests on a representative concrete sample at the point of discharge. Perform additional tests when concrete consistency seems to have changed. The maximum allowable field slump is 5 inches. Conform to ASTM C143.
- Perform air content tests on all concrete specified to be air-entrained. Conform to ASTM C231.
- Perform a temperature test every hour when air temperature is 40°F and below, or when air temperature is 80°F and above. Conform to ASTM C 1064.
- Prior to the closing of forms or the delivery of concrete to the job site, the inspector shall verify that the reinforcing steel is in conformance with the city-approved plans, specifications and shop drawings. The inspector shall confirm that the reinforcing steel is of the correct size and grade and ensure that the proper spacing, clearances, splice lengths and embedded items have been provided. All reinforcing steel shall be in place prior to the placement of concrete and be secured against displacement.
- The Inspector shall verify that the bolt size, location and embedment length of all anchor bolts are in conformance with the city-approved plans, specifications and shop drawings.
- Anchor rods 3/4"Ø or smaller may be floated in place following concrete placement, provided that anchor bolts are worked easily by hand into the fresh concrete to allow for full contact with the shank of the bolt. Bolts shall be placed by means of a template and shall be worked into concrete in vertical alignment.
- Test Reporting: Test results must be reported to BSE and the General Contractor in writing within 24 hours after testing, via fax or email. Reports of compressive strength tests must contain the project name, the date of concrete placement, the location of concrete placement within the structure and the concrete mix design being used.

Structural Steel:

- Bolts: Bolts that are not identified as being slip-critical nor in direct tension need not be inspected other than to verify that the piles of connected elements are brought into snug-tight condition in properly-aligned holes.
- Field Welding: Inspection is required for single-pass fillet welds, multi-pass fillet welds, complete- and partial-penetration groove welds, floor and roof deck welding, and stairs and railing systems. Prior to the start of the work, materials, qualifications of welding procedures and welder qualifications shall be verified. Provide continuous or periodic inspection of the structural welding as indicated in Table 1705.3 of the referenced IBC. Inspections may occur periodically, as defined below. A visual inspection to ensure proper type, size, length and quality of all field welds is required prior to work being concealed by other materials.
- Periodic inspection: "Periodic" is defined as generally once a week at a minimum, and more often as needed to observe work requiring inspections, as outlined above, prior to being covered by subsequent construction.
- Shear connector stud welds will be inspected and tested according to AWS D1.1 for stud welding. Shear connector stud welds shall be visually inspected. Bend tests shall be performed if visual inspections reveal less than a 360-degree flash or welding repairs to any shear connector stud.
- Structural steel bar joists and metal buildings fabricated on the premises of a facility/plant not certified by a nationally recognized organization, shall have in-plant special inspections. AISC, ICBO, CWB and SJI are certified fabricators.
- Test Reporting: Test results must be reported to BSE and the General Contractor in writing within 24 hours of testing, via fax or email. Reports must contain the project name, the date of the test and the location of the test.

Masonry:

- Mortar properties, grout, brick, concrete masonry unit and prism tests and evaluations are to be performed during construction for each 5,000 sq. ft. of wall area or portion thereof.
- Mortar properties are to be tested per ASTM C 780.
- Grout will be sampled and tested for compressive strength per ASTM C 1019.
- Brick tests for each type and grade of brick indicated are to be performed according to ASTM C 67.
- Concrete masonry unit tests for each type of concrete masonry unit indicated are to be performed per ASTM C 140.
- Masonry prisms are to be tested per ASTM C 1314. Prepare one (1) set of prisms for testing at 7 days and one (1) set for testing at 28 days.
- Special inspection of masonry construction is required during preparation and taking of any required prisms or test specimens, placing of all masonry units, placement of reinforcement and inspection of grout space immediately prior to closing cleanouts, and during all grouting operations.
- Test Reporting: Test results must be reported to BS and the general contractor in writing within 24 hours of testing, via fax. Reports must contain the project name, the date of the test and the location of the test.

Structural Wood:

- Special inspections of structural wood framing to be performed in accordance with section 1705.11.2. of the referenced IBC.
 - Periodic special inspection is required for nailing, bolting, anchoring and other fastening of components within the seismic force resisting system, including wood shear walls, wood diaphragms, drag struts, braces, shear panels, and hold-downs.
 - Periodic special inspection is required for nailing, bolting, anchoring and other fastening of components within the wind force resisting system, including wood shear walls, wood diaphragms, drag struts, braces, shear panels, and hold-downs.
 - Test Reporting: Test results must be reported to BSE and the general contractor in writing within 24 hours of testing, via fax. Reports must contain the project name, the date of the test and the location of the test.
- [ENGINEER TO VERIFY IF SECTION IS REQ'D]**

Required Verification and Inspection of Steel Construction Other Than Structural Steel Per IBC Table 1705.2.2

Type	Continuous Special Inspection	Periodic Special Inspection	Referenced Standard
1. Material verification of cold-formed steel deck:			
a. Identification markings to conform to ASTM standards specified in the approved construction documents.	-	X	Applicable ASTM material standards
b. Manufacturer's certified test reports.	-	X	
2. Inspection of welding and attachment:			
a. Cold-formed steel deck:			
1. Floor and roof deck welds and other means of attachment.	-	X	AWS D1.3
b. Reinforcing steel:			
1. Verification of edibility of reinforcing steel other than ASTM A 706.	-	X	AWS D1.4 ACI 318: Section 3.5.2
2. Reinforcing steel resisting flexural and axial forces in intermediate and special moment frames, and boundary elements of special structural walls of concrete and shear reinforcement.	X	-	
3. Shear reinforcement.	-	X	
4. Other reinforcing steel.	-	X	

a. Where applicable, see also Section 1705.11 Special inspections for seismic resistance.

Required Special Inspections of Open-Web Steel Joists and Joist Girders Per IBC Table 1705.2.3

Type	Continuous Special Inspection	Periodic Special Inspection	Referenced Standard
1. Installation of open web steel joist and joist girders:			
a. End Connections - welding or bolted.	-	X	SJI Specifications listed in Section 2207.1.
b. Bridging - horizontal or diagonal.	-	-	
1. Standard bridging.	-	X	SJI Specifications listed in Section 2207.1.
2. Bridging that differs from the SJI specifications listed in Section 2207.1.	-	X	

a. Where applicable, see also Section 1705.12. Special inspections for seismic resistance.

Required Special Inspections and Tests of Concrete Construction Per IBC Table 1705.3

Type	Continuous Special Inspection	Periodic Special Inspection	Referenced Standard
1. Inspect reinforcement, including prestressing tendons, and verify placement.	-	X	ACI 318 Chp. 20, 25.2, 25.3, 26.6.1.-26.6.3.
2. Reinforcing bar welding:			
a. Adhesive anchors installed in horizontally or upwardly inclined orientations to resist sustained tension loads.	X	-	ACI 318: 17.8.2.4
b. Mechanical anchor and adhesive anchors not defined in 4.a.	-	X	ACI 318: 17.8.2.
3. Verify use of required design mix.	-	X	ACI 318: Chp. 19, 26.4.3, 26.4.4
4. Prior to concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete.	X	-	ASTM C172 ASTM C31 ACI 318: 26.4, 26.12
5. Inspect concrete and shotcrete placement for proper application techniques.	X	-	ACI 318: 26.5
6. Verify maintenance of specified curing temperatures and techniques.	-	X	ACI 318: 26.5.3-26.5.5
7. Inspect prestressed concrete for:			
a. Application of prestressing forces; and	X	-	ACI 318: 26.10
b. Grouting of bonded prestressing tendons.	X	-	
8. Inspect erection of precast concrete members.	-	X	ACI 318: Chp. 26.8
9. Verify in-situ concrete strength, prior to stressing of tendons in post-tensioned concrete and prior to removal of shores and forms from beams and structural slabs.	-	X	ACI 318: 26.11.2
10. Inspect framework for shape, location and dimensions of the concrete member being formed.	-	X	ACI 318: 26.11.1.2(B)

a. Where applicable, see also Section 1705.12. Special inspections for seismic resistance.
b. Specific requirements for special inspection shall be included in the research report for the anchor issued by an approved source in accordance with 17.8.2 in ACI 318, or other qualification procedures. Where specific requirements are not provided, special inspection requirements shall be specified by the registered design professional and shall be approved by the building official prior to the commencement of the work.

Required Special Inspections and Tests of Soils Per IBC Table 1705.6		
Type	Continuous Special Inspection	Periodic Special Inspection
1. Verify materials below shallow foundations are adequate to achieve the design bearing capacity.	-	X
2. Verify excavations are extended to proper depth and have reached proper material.	-	X
3. Perform classification and testing of compacted fill materials.	-	X
4. Verify use of proper materials, densities and lift thicknesses during placement and compaction of compacted fill.	X	-
5. Prior to placement of compacted fill, inspect subgrade and verify that site has been prepared properly.	-	X

Required Special Inspections and Tests of Driven Deep Foundation Elements Per IBC Table 1705.7		
Type	Continuous Special Inspection	Periodic Special Inspection
1. Verify element materials, sizes and lengths comply with the requirements.	X	-
2. Determine capacities of test elements and conduct additional load tests, as required.	X	-
3. Inspect driving operations and maintain complete and accurate records for each element.	X	-
4. Verify placement locations and plumbness, confirm type size of hammer, record number of blows per foot of penetration, determine required penetrations to achieve design capacity, record tip and butt elevations and document any damage to foundation element.	X	-
5. For steel elements, perform additional special inspections in accordance with Section 1705.2.	-	-
6. For concrete elements and concrete-filled elements, perform tests and additional special inspections in accordance with Section 1705.3.	-	-
7. For specialty elements, perform additional inspections as determined by the registered design professional in responsible charge.	-	-


Required Special Inspections and Tests of Cast-in-Place Deep Foundation Elements Per IBC Table 1705.8		
Type	Continuous Special Inspection	Periodic Special Inspection
1. Inspect drilling operations and maintain complete and accurate records for each element.	X	-
2. Verify placement locations and plumbness, confirm element diameters, bell diameters (if applicable), lengths, embedment into bedrock (if applicable) and adequate end-bearing strata capacity. Record concrete or grout volumes.	X	-
3. For concrete elements, perform tests and additional special inspections in accordance with Section 1705.3.	-	-

Required Quality Control Inspections (QCI) & Quality Assurance Inspections (QAI) of Steel Construction Per AISC 360, Specification Chapter M & N

Type	Frequency of Inspections	Referenced Standard
1. The fabricator's QCI shall inspect the following as a minimum, as applicable:		AISC 360 Chp. M & N
a. Shop welding, high strength bolting and details in accordance with AISC 360, Section N5.	Per AISC	TABLE N5.4-1 TABLE N5.4-2 TABLE N5.4-3
b. Shop cut and finished surfaces in accordance with AISC 360, section M2.	Per AISC	TABLE N5.6-1 TABLE N5.6-2
c. Shop heating for straightening, cambering and curving in accordance with AISC 360, Section M2.1.	Per AISC	TABLE N5.6-3 TABLE N6.1
d. Tolerances for shop fabrication in accordance with the Code of Standard Practice, Section 6.	Per AISC	Code of Standard Practice Sec. 6
2. The erector's QCI shall inspect the following as a minimum, as applicable:		AISC 360 Chp. M&N
a. Field welding, high strength bolting and details in accordance with AISC 360, Section N5.	Per AISC	TABLE N5.4-1
b. Steel deck and headed steel stud anchor placement and attachment in accordance with AISC 360, Section N6.	Per AISC	TABLE N5.4-2 TABLE N5.4-3
c. Field cut surfaces in accordance with AISC 360, Section M2.2.	Per AISC	TABLE N5.6-1 TABLE N5.6-2 TABLE N5.6-3
d. Field heating for straightening in accordance with AISC 360, Section M2.1.	Per AISC	TABLE N6.1
e. Tolerances for field erection in accordance with the Code of Standard Practice, Section 7.13.	Per AISC	Code of Standard Practice Sec. 6
3. QAI shall be performed by others. All required inspection and non-destructive testing, as applicable, shall be in accordance with AISC 360	Per AISC & IBC	AISC 360 Chp. M&N


4301 Indian Creek Parkway
Overland Park, KS 66207
phone: 913.451.9390
f a x : 913.451.9391
www.davidsonae.com

BSE STRUCTURAL ENGINEERS
11320 West 79th Street
Lenexa, Kansas 66214
Phone 913.492.7400
www.BSEstructural.com
Project Number 20-467




NOTES:
1.) ISOMETRIC VIEWS ARE SHOWN FOR SCHEMATIC PURPOSES ONLY. ACTUAL CONSTRUCTION TO MATCH CONSTRUCTION DOCUMENTS. REFERENCE ARCHITECTURAL, MECHANICAL, CIVIL, & STRUCTURAL DOCUMENTS.

ISOMETRIC | 01
S0.1



BUILDING SECTION | 02
1/4" = 1'-0" | S0.1



NOTES:
1.) BUILDING SECTIONS ARE SHOWN FOR SCHEMATIC PURPOSES ONLY. ACTUAL CONSTRUCTION TO MATCH CONSTRUCTION DOCUMENTS. REFERENCE ARCHITECTURAL, MECHANICAL, CIVIL, & STRUCTURAL DOCUMENTS.

BUILDING SECTION | 03
1/4" = 1'-0" | S0.1

a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees Summit, Missouri 64064


date
02.23.2021
drawn by
Author
checked by
Checker
revisions

sheet number
S0.1
ISOMETRIC
drawing type
project number

a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees's Summit, Missouri 64064

date 02.23.2021
drawn by CB
checked by RJS
revisions


sheet number
S1.1
FOUNDATION PLAN
drawing type
project number



MARK	DIMENSIONS	REINFORCEMENT	F.B.E.	COMMENTS
F1	5'-0" x 5'-0" x 1'-0"	#5 @ 12" SPA. EA. WAY BOTT. & #4 @ 12" SPA. EA. WAY TOP	98.33	
F2	8'-0" x 8'-0" x 1'-0"	#5 @ 12" SPA. EA. WAY BOTT. & #4 @ 12" SPA. EA. WAY TOP	98.00	
F3	4'-0" x 4'-0" x 2'-10"	#5 @ 10" SPA. EA. WAY TOP & BOTT	96.50	
F4	4'-0" x 4'-0" x 1'-0"	#5 @ 12" SPA. EA. WAY BOTT. & #4 @ 12" SPA. EA. WAY TOP	99.00	
F5	5'-0" x 5'-0" x 2'-10"	#5 @ 10" SPA. EA. WAY TOP & BOTT	96.50	

- NOTES:
- SEE DRAWING S0.0 FOR GENERAL NOTES, SYMBOLS LEGEND, MATERIALS LEGEND, & ABBREVIATION LIST.
 - REFERENCE DRAWING S3.1 FOR TYPICAL FOUNDATION DETAILS INCLUDING ANCHOR ROD DETAILS, FOOTING STEP DETAILS, CONTROL JOINT & CONSTRUCTION JOINT DETAILS, REINF. LAP LENGTH TABLE, ETC.
 - SEE DRAWING S0.1 FOR ISOMETRIC VIEW & FULL BUILDING SECTIONS.
 - EXTERIOR MASONRY CMU WALLS ARE 12" U.N.O. INTERIOR NON LOAD BEARING CMU TO BE 8" U.N.O.
 - REFER TO GEOTECHNICAL REPORT FOR BEHIND WALL DRAINAGE RECOMMENDATIONS. COORD. W/ CIVIL AS REQ'D. REFER TO ARCHITECTURAL DRAWINGS FOR FOUNDATION WATERPROOFING & INSULATION REQUIREMENTS.

FOUNDATION PLAN | 01
3/32" = 1'-0" S1.1






a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees's Summit, Missouri 64064


date
02.23.2021
drawn by
CB
checked by
RJS
revisions

sheet number
S2.1
MEZZANINE FRAMING PLAN
drawing type
project number



NOTES:



- 1.) SEE DRAWING S0.0 FOR GENERAL NOTES, SYMBOLS LEGEND, MATERIALS LEGEND, & ABBREVIATION LIST.
- 2.) REFERENCE DRAWING S4.1 FOR TYPICAL FRAMING DETAILS.
- 3.) SEE DRAWING S0.1 FOR ISOMETRIC VIEW & FULL BUILDING SECTIONS.
- 4.) REFERENCE ARCHITECTURAL DRAWINGS TO VERIFY SIZE & LOCATIONS OF ALL FLOOR & WALL OPENINGS.
- 5.) PROVIDE JOIST BRIDGING PER SII REQUIREMENTS.
- 6.) MASONRY CMU WALLS ARE 8" U.N.O.
- 7.) REFERENCE DRAWING S4.1 FOR TYPICAL MASONRY LINTEL DETAILS.
- 7.) ALL EXTERIOR LINTELS SUPPORTING STONE OR BRICK SHALL BE GALVANIZED U.N.O. ON ARCHITECTURAL DRAWINGS.
- 8.) PROVIDE 3/4" x 4" LONG HEADED SHEAR STUDS FOR COMPOSITE BEAMS. SEE TYPICAL FRAMING DETAILS SHEET S4.1 FOR ADDITIONAL DETAILS.
- 9.) ATTACH COMPOSITE METAL DECK W/ 5/8" PUDDLE WELD IN A 36/4 PATTERN & (2) WELDED SIDE LAP FASTENERS PER SPAN.



a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees Summit, Missouri 64064

date
02.23.2021
drawn by
Author
checked by
Checker
revisions

sheet number
S2.2
ROOF FRAMING PLAN
drawing type
project number



SNOW DRIFT DIAGRAM
3/8" = 1'-0"


BOND BEAM SCHEDULE					
TAG	MAX. SPAN	GROUTED BOND BEAM DEPTH	BOTT. REINF.	TOP REINF.	# OF BRG. CELLS
B1	4'-0"	8"	(2) #5	N/A	2
B2	6'-0"	12"	(2) #5	N/A	2
B3	8'-0"	16"	(2) #5	N/A	2
B4	12'-0"	24"	(2) #6	(2) #5	2

BOND BEAM SCHEDULE | 02
1/2" = 1'-0" S2.2


- NOTES:
- SEE DRAWING S0.0 FOR GENERAL NOTES, SYMBOLS LEGEND, MATERIALS LEGEND, & ABBREVIATION LIST.
 - REFERENCE DRAWING S4.3 FOR TYPICAL FRAMING DETAILS.
 - SEE DRAWING S0.2 FOR ISOMETRIC VIEW & FULL BUILDING SECTIONS.
 - REFERENCE ARCHITECTURAL DRAWINGS TO VERIFY SIZE & LOCATIONS OF ALL ROOF & WALL OPENINGS.
 - PROVIDE JOIST BRIDGING PER SJI REQUIREMENTS.
 - * = JOIST TO BE DESIGNED FOR ADDITIONAL SNOW DRIFT - SEE SNOW DRIFT DETAIL
 - MASONRY CMU WALLS ARE 12" U.N.O.
 - REFERENCE DRAWING S4.1 & S4.2 FOR TYPICAL MASONRY LINTEL DETAILS.
 - ALL EXTERIOR LINTELS SUPPORTING STONE OR BRICK SHALL BE GALVANIZED U.N.O. ON ARCHITECTURAL DRAWINGS. REFER TO DETAILS FOR SIZES, COORD. LOCATIONS W/ ARCHITECTURAL DRAWINGS.
 - ROOF JOIST TO BE DESIGNED FOR ADDITIONAL ROOF EQUIPMENT LOAD AS SHOWN.

ROOF FRAMING PLAN | 01
3/32" = 1'-0" S2.2


NOTES:
 1.) FOR STANDARD SIZE HOLES, PROVIDE ASTM F844 (USS STANDARD) WASHERS. FOR HOLES THAT ARE MORE THAN 5/16" LARGER THAN ANCHOR ROD DIAMETER, PROVIDE PLATE WASHERS BETWEEN NUT & PLATE PER TABLE 14-2 IN AISC STANDARD.
 2.) FOR ANCHORS RODS 1" DIAMETER AND LARGER, PROVIDE PLATE WASHERS BETWEEN NUT & PLATE PER TABLE 14-2 IN AISC STANDARD. WELD WASHER TO TOP OF BASE PLATE WITH 3/16" FILLET WELD.



TYP. ANCHOR ROD & BASE PLATE DETAIL | 01
 1 1/2" = 1'-0" S3.1




TYP. SLAB OPENING DETAIL | 02
 1/2" = 1'-0" S3.1




TYP. GRADE BEAM DETAILS | 03
 3/4" = 1'-0" S3.1


STANDARD 90° HOOK TABLE | 04



TYP. RE-ENTRANT CORNER REINF. DETAIL | 05
 3/4" = 1'-0" S3.1



TYP. SLAB REINF. @ DOOR DETAIL | 06
 3/4" = 1'-0" S3.1



TYP. FOOTING STEP DETAIL | 07
 3/4" = 1'-0" S3.1

TENSION LAP SPICE LENGTHS (in) GRADE 60 UNCOATED BARS f'c=3000 psi					
BAR SIZE	LAP CLASS	TOP BARS		OTHER BARS	
		CASE 1	CASE 2	CASE 1	CASE 2
#3	A	22	32	17	25
	B	28	42	22	32
#4	A	29	43	22	33
	B	37	56	29	43
#5	A	36	54	28	41
	B	47	70	36	54
#6	A	43	64	33	50
	B	56	84	43	64
#7	A	63	94	48	72
	B	81	122	63	94
#8	A	72	107	55	82
	B	93	139	72	107
#9	A	81	121	62	93
	B	105	157	81	121
#10	A	91	136	70	105
	B	118	177	91	136
#11	A	101	151	78	116
	B	131	196	101	151

NOTES:
 1. TABULATED VALUES ARE BASED ON GRADE 60 REINFORCING BARS AND NORMAL-WEIGHT CONCRETE.
 2. TENSION DEVELOPMENT LENGTHS AND TENSION LAP SPICE LENGTHS ARE BASED ON ACI 318, SECTIONS 12.2.2 AND 12.15, RESPECTIVELY.
 3. TABULATED VALUES FOR BEAMS OR COLUMNS ARE BASED ON TRANSVERSE REINFORCEMENT AND CONCRETE COVER MEETING MINIMUM CODE REQUIREMENTS. LENGTHS ARE IN INCHES.
 4. CASES 1 AND 2, WHICH DEPEND ON THE TYPE OF STRUCTURAL ELEMENT, CONCRETE COVER, AND THE CENTER-TO-CENTER SPACING OF THE BARS ARE DEFINED AS:
 BEAMS OR COLUMNS:
 CASE 1: COVER AT LEAST (1) BAR DIAMETER AND C-C. SPACING AT LEAST (2) BAR DIAMETERS
 CASE 2: COVER LESS THAN (1) BAR DIAMETER AND C-C. SPACING LESS THAN (2) BAR DIAMETERS
 ALL OTHERS:
 CASE 1: COVER AT LEAST (1) BAR DIAMETER AND C-C. SPACING AT LEAST (3) BAR DIAMETERS
 CASE 2: COVER LESS THAN (1) BAR DIAMETER AND C-C. SPACING LESS THAN (3) BAR DIAMETERS
 5. LAP CLASS A VALUES ARE THE REQUIRED TENSION DEVELOPMENT LENGTHS, l_d; LAP SPICE LENGTHS ARE MULTIPLES OF TENSION DEVELOPMENT LENGTHS; CLASS A - 1.0l_d AND CLASS B = 1.3l_d (ACI 318, SECTION 12.15.1)
 6. LAP CLASS B SHALL BE USED FOR ALL CASES UNLESS APPROVED BY E.O.R
 7. TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.
 8.) LENGTHS SHOWN ARE FOR UNCOATED BARS. LENGTHS SHOWN SHALL BE MULTIPLIED BY 1.2 FOR ALL EXPOXY COATED BARS (ACI 318 SECTION 12.2.4)
 9.) WHEN BARS OF DIFFERENT SIZES ARE LAP SPICED, THE SPICE LENGTH FOR THE LARGER BAR SHALL BE USED.


TENSION LAP SPICE LENGTHS (in) GRADE 60 UNCOATED BARS f'c=4000 psi					
BAR SIZE	LAP CLASS	TOP BARS		OTHER BARS	
		CASE 1	CASE 2	CASE 1	CASE 2
#3	A	19	28	15	22
	B	24	36	19	28
#4	A	25	37	19	29
	B	32	48	25	37
#5	A	31	47	24	36
	B	40	60	31	47
#6	A	37	56	29	43
	B	48	72	37	56
#7	A	54	81	42	63
	B	70	106	54	81
#8	A	62	93	48	72
	B	80	121	62	93
#9	A	70	105	54	81
	B	91	136	70	105
#10	A	79	118	61	91
	B	102	153	79	118
#11	A	87	131	67	101
	B	113	170	87	131

NOTES:
 1. TABULATED VALUES ARE BASED ON GRADE 60 REINFORCING BARS AND NORMAL-WEIGHT CONCRETE.
 2. TENSION DEVELOPMENT LENGTHS AND TENSION LAP SPICE LENGTHS ARE BASED ON ACI 318, SECTIONS 12.2.2 AND 12.15, RESPECTIVELY.
 3. TABULATED VALUES FOR BEAMS OR COLUMNS ARE BASED ON TRANSVERSE REINFORCEMENT AND CONCRETE COVER MEETING MINIMUM CODE REQUIREMENTS. LENGTHS ARE IN INCHES.
 4. CASES 1 AND 2, WHICH DEPEND ON THE TYPE OF STRUCTURAL ELEMENT, CONCRETE COVER, AND THE CENTER-TO-CENTER SPACING OF THE BARS ARE DEFINED AS:
 BEAMS OR COLUMNS:
 CASE 1: COVER AT LEAST (1) BAR DIAMETER AND C-C. SPACING AT LEAST (2) BAR DIAMETERS
 CASE 2: COVER LESS THAN (1) BAR DIAMETER AND C-C. SPACING LESS THAN (2) BAR DIAMETERS
 ALL OTHERS:
 CASE 1: COVER AT LEAST (1) BAR DIAMETER AND C-C. SPACING AT LEAST (3) BAR DIAMETERS
 CASE 2: COVER LESS THAN (1) BAR DIAMETER AND C-C. SPACING LESS THAN (3) BAR DIAMETERS
 5. LAP CLASS A VALUES ARE THE REQUIRED TENSION DEVELOPMENT LENGTHS, l_d; LAP SPICE LENGTHS ARE MULTIPLES OF TENSION DEVELOPMENT LENGTHS; CLASS A - 1.0l_d AND CLASS B = 1.3l_d (ACI 318, SECTION 12.15.1)
 6. LAP CLASS B SHALL BE USED FOR ALL CASES UNLESS APPROVED BY E.O.R
 7. TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.
 8.) LENGTHS SHOWN ARE FOR UNCOATED BARS. LENGTHS SHOWN SHALL BE MULTIPLIED BY 1.2 FOR ALL EXPOXY COATED BARS (ACI 318 SECTION 12.2.4)
 9.) WHEN BARS OF DIFFERENT SIZES ARE LAP SPICED, THE SPICE LENGTH FOR THE LARGER BAR SHALL BE USED.

COMPRESSION DEVELOPMENT AND LAP SPICE LENGTHS GRADE 60 REINFORCEMENT, NORMAL WEIGHT CONCRETE						
BAR SIZE	CONCRETE COMPRESSIVE STRENGTH					
	3000 PSI		4000 PSI		5000 PSI	
	DEV	SPICE	DEV	SPICE	DEV	SPICE
#3	9	12	8	12	7	12
#4	11	15	10	15	9	15
#5	14	19	12	19	12	19
#6	17	23	15	23	14	23
#7	20	27	17	27	16	27
#8	22	30	19	30	18	30
#9	25	34	22	34	21	34
#10	28	39	25	39	23	39
#11	31	43	27	43	26	43


NOTES:
 1.) TABULATED VALUES ARE BASED ON GRADE 60 REINFORCING BARS AND NORMAL WEIGHT CONCRETE.
 2.) COMPRESSION DEVELOPMENT LENGTHS AND COMPRESSION SPICE LENGTHS ARE BASED ON ACI 318, SECTIONS 12.3 AND 12.16, RESPECTIVELY.
 3.) ALL VALUES ARE SHOWN IN INCHES
 4.) COMPRESSION SPICE PERMISSIBLE ONLY WHERE SPECIFICALLY NOTED
 5.) TABLE IS NOT APPLICABLE FOR EPOXY-COATED REINFORCEMENT.
 6.) "SIDE LAP" ALL LAP SPICES TO MAINTAIN SPECIFIED CONCRETE COVER.
 7.) WHEN BARS OF A DIFFERENT SIZE ARE LAP SPICED, THE SPICE LENGTH SHALL BE THE LARGER OF THE DEVELOPMENT LENGTH OF THE LARGER BAR, OR THE SPICE LENGTH OF THE SMALLER BAR.

COMPRESSION DEVEL. & LAP SPICE TABLE | 10
 1/2" = 1'-0" S3.1




TYP. SHALLOW FOOTING STEP DETAIL | 12
 3/4" = 1'-0" S3.1

LAP SPICE LENGTHS f'c=3000 psi | 08
 1/2" = 1'-0" S3.1




TYP. TRASH ENCLOSURE WALL DETAIL | 14
 3/4" = 1'-0" S3.1


LAP SPICE LENGTHS f'c=4000 psi | 09
 1/2" = 1'-0" S3.1




TYP. FLOOR DRAIN DETAIL | 15
 3/4" = 1'-0" S3.1



TYP. CONTROL & CONST. JOINT DETAIL | 11
 3/4" = 1'-0" S3.1



TYPICAL GRADE BEAM PENETRATION DETAILS | 13
 3/4" = 1'-0" S3.1














STEEL STAIR STRINGER | 16
 3/4" = 1'-0" S3.1

a redevelopment for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lees Summit, Missouri 64064

date 02.23.2021
 drawn by
 Author
 checked by
 Checker
 revisions

sheet number
S3.1
 TYPICAL FOUNDATION
 DETAILS
 drawing type
 project number




a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees Summit, Missouri 64064


date 02.23.2021
drawn by
Author
checked by
Checker
revisions

sheet number
S3.2
FOUNDATION DETAILS


drawing type
project number




TYP. JOIST REINFORCEMENT DETAIL | 01
 3/4" = 1'-0" | S4.1



EDGE ANGLE SPlice DETAIL | 02
 3/4" = 1'-0" | S4.1




TYP. ROOF OPENING & EQUIP. SUPPORT FRAMING DETAIL | 03
 3/4" = 1'-0" | S4.1




BEAM DEPTH	# OF (n) A325 BOLTS	BOLT Ø	SHEAR TAB THICKNESS
12"	3	3/4"	3/8"
14"	3	3/4"	3/8"
16"	4	3/4"	3/8"
18"	5	3/4"	3/8"
21"	6	1"	7/16"
24"	7	1"	7/16"
27"	8	1"	7/16"
30"	9	1"	7/16"
34"	10	1"	7/16"
36"	11	1"	7/16"

TYP. SHEAR TAB CONNECTION DETAIL | 04
 1 1/2" = 1'-0" | S4.1



TYP. BEAM BOTTOM FLANGE BRACE DETAIL - JOIST | 05
 3/4" = 1'-0" | S4.1




TYP. MOMENT CONN. DETAIL | 06
 1" = 1'-0" | S4.1

TYPICAL SPLICE LENGTHS FOR MASONRY BLOCK - STRENGTH DESIGN


BLOCK WIDTH	CASE A - BARS CENTERED					CASE B - (2) BARS						
	#3	#4	#5	#6	#7	#3	#4	#5	#6	#7		
6" BLOCK	14"	18"	28"	53"	-	-	-	-	-	-		
8" BLOCK	14"	18"	22"	38"	52"	72"	*	15"	25"	39"	54"	63"
10" BLOCK	14"	18"	22"	35"	40"	61"	*	15"	25"	39"	54"	63"
12" BLOCK	14"	18"	22"	35"	40"	61"	*	14"	22"	35"	54"	63"

SYMBOLS:
 - REINFORCING CONFIGURATION NOT PERMISSIBLE
 * MECHANICAL TENSION SPLICE REQ'D

NOTES:
 1) MECH. TENSION SPLICE CAN BE FOR ANY BAR SIZE IF NOT NOTED.
 2) FOR USE WITH FM=2,000 psi & fy = 60,000 psi



MASONRY SPLICE TABLE | 07
 3/4" = 1'-0" | S4.1



TYP. SPLICE DETAIL | 08
 3/4" = 1'-0" | S4.1

a redevelopment for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lees's Summit, Missouri 64064

date
 02.23.2021
 drawn by
 Author
 checked by
 Checker
 revisions

4301 Indian Creek Parkway
Overland Park, KS 66207
phone: 913.451.9390
f a x : 913.451.9391
www.davidsonae.com

BSE STRUCTURAL ENGINEERS




11320 West 79th Street
Lenexa, Kansas 66214
Phone 913.492.7400
www.BSEStructural.com
Project Number 20-467




a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees's Summit, Missouri 64064

date
02.23.2021
drawn by
Author
checked by
Checker
revisions


sheet number
S4.2
TYPICAL FRAMING
DETAILS
drawing type
project number




TYP. MASONRY WALL LINTEL DETAIL - BOND BEAM | 01
3/4" = 1'-0" S4.2



CORNER HORIZ. JOINT REINF. | 02
3/4" = 1'-0" S4.2




MASONRY JOINT DETAILS | 03
3/4" = 1'-0" S4.2




TYP. MASONRY WALL WINDOW OPENING DETAIL | 04
3/4" = 1'-0" S4.2

BOND BEAM SCHEDULE					
TAG	MAX. SPAN	GROUTED BOND BEAM DEPTH	BOTT. REINF.	TOP REINF.	# OF BRG. CELLS
B1	4'-0"	8"	(2) #5	N/A	2
B2	6'-0"	12"	(2) #5	N/A	2
B3	8'-0"	16"	(2) #5	N/A	2
B4	12'-0"	24"	(2) #6	(2) #5	2














TYP. BOND BEAM DETAIL | 05
1 1/2" = 1'-0" S4.2

LINTEL SCHEDULE	
OPENING WIDTH	BRICK LINTEL SIZE
4'-0"	L5X5X3/8




TYP. BRICK LINTEL DETAIL | 06
3/4" = 1'-0" S4.2




FASTENERS @ CONCRETE	
LOCATION	NUMBER OF FASTENERS REQUIRED
TYPICAL FRAMING	(1) 0.157"Ø P.D.F @ 8" O.C.
JAMB STUDS	(2) 0.157"Ø P.D.F @ EACH JAMB (SEE NOTE #3)

FASTENERS @ STEEL	
LOCATION	NUMBER OF FASTENERS REQUIRED
TYPICAL FRAMING	(2) 0.157"Ø P.D.F @ 8" O.C.
JAMB STUDS	(4) 0.157"Ø P.D.F @ EACH JAMB


- NOTE:**
1) 1" MIN. EMBED REQ'D FOR ALL P.D.F'S
2) MAINTAIN 4" MIN. FASTENER SPACING FOR ALL FASTENERS
3) FOR OPENINGS 3'-6" PROVIDE TSN CL CLIP (OR EQ.)
4) REFER TO DETAILS FOR ADD'L BOTT. TRACK-TO-STRUCTURE FASTENER REQUIREMENTS




TYP. BEAM BOTTOM FLANGE BRACE DETAIL | 01
3/4" = 1'-0" S4.4



TYP. COMP. FLR. REINF. @ OPENING DETAIL | 02
3/4" = 1'-0" S4.4




TYP. COMP. MTL. DECK @ CORNER COL. DETAIL | 03
3/4" = 1'-0" S4.4




TYP. COMP. DECK @ EXTERIOR COL. DETAIL | 04
3/4" = 1'-0" S4.4


TYP. STUD PLACEMENT DETAIL | 05
3/4" = 1'-0" S4.4




TYP. STUD POSITION DETAIL | 06
3/4" = 1'-0" S4.4




TYP. COMP. FLR. JOINT DETAIL | 07
3/4" = 1'-0" S4.4




TYP. COMP. BEAMS W/ SHEAR STUDS DETAIL | 08
3/4" = 1'-0" S4.4




TYP. COMPOSITE DECK SLAB CONSTRUCTION JOINT | 09
3/4" = 1'-0" S4.4



TYP. COMP. STEEL DECK SLAB OPENING | 10
3/4" = 1'-0" S4.4




STEEL DECK DEFLECTION COMPENSATION DETAIL | 12
3/4" = 1'-0" S4.4




TYP. STEEL DECK SLAB OPENING | 13
3/4" = 1'-0" S4.4

NOTES:
1.) COMPOSITE STEEL BEAMS HAVE BEEN DESIGNED AS AN UNSHORED CONSTRUCTION CONDITION. THE MAX EXPECTED DEFLECTION FOR EACH BEAM IS L/360 OR 3/4" (WHICH EVER IS SMALLER) FOR CONSTRUCTION WET CONCRETE PLACEMENT LOADING CONDITION.
2.) COMPOSITE STEEL BEAMS W/ CAMBER ARE DESIGNED SO THAT THE CAMBER IS TO DIMINISH DUE TO DEFLECTION UNDER THE CONSTRUCTION WET CONCRETE PLACEMENT LOADING CONDITION. SPECIAL CARE SHALL BE TAKEN DURING CONSTRUCTION TO ENSURE DEFLECTION IS ABLE TO HAPPEN.


CAMBER AND DEFLECTION NOTES | 11
1 1/2" = 1'-0" S4.4



SECTION 01 3/4" = 1'-0" S4.5
SECTION 02 3/4" = 1'-0" S4.5
SECTION 03 3/4" = 1'-0" S4.5
SECTION 04 3/4" = 1'-0" S4.5
SECTION 05 3/4" = 1'-0" S4.5
SECTION 06 3/4" = 1'-0" S4.5



SECTION 07 3/4" = 1'-0" S4.5
SECTION 08 3/4" = 1'-0" S4.5
SECTION 09 3/4" = 1'-0" S4.5
SECTION 10 3/4" = 1'-0" S4.5




SECTION 11 3/4" = 1'-0" S4.5
SECTION 12 3/4" = 1'-0" S4.5
SECTION 13 3/4" = 1'-0" S4.5
SECTION 14 3/4" = 1'-0" S4.5
SECTION 15 3/4" = 1'-0" S4.5


a redevelopment for
Automotive Sales & Detail Center
2100 NE Independence Ave
Lees Summit, Missouri 64064

date 02.23.2021
drawn by
checked by
revisions


sheet number
S4.5
FRAMING DETAILS
drawing type
project number



NORTH INTERIOR ELEVATION | 01
 3/16" = 1'-0" | S4.6



NORTH INTERIOR ELEVATION | 02
 3/16" = 1'-0" | S4.6




EAST INTERIOR ELEVATION | 03
 3/16" = 1'-0" | S4.6

a redevelopment for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lees's Summit, Missouri 64064

date
 02.23.2021
 drawn by
 Author
 checked by
 Checker
 revisions

sheet number
S4.6
 MASONRY ELEVATIONS
 drawing type
 project number



SOUTH INTERIOR ELEVATION | 01
 3/16" = 1'-0" 54.7

a redevelopment for
Automotive Sales & Detail Center
 2100 NE Independence Ave
 Lees's Summit, Missouri 64064

date
 02.23.2021
 drawn by
 Author
 checked by
 Checker
 revisions

sheet number
S4.7
 MASONRY ELEVATIONS


drawing type
 project number

MECHANICAL SPECIFICATIONS

- 11. FLEXIBLE DUCT:
A. ATCO 1056 (R-6) OR EQUAL.
B. FACTORY APPLIED INSULATION AND VAPOR BARRIER, 1-1/2" THICK.
C. MAXIMUM LENGTH OF 9'-0".
12. FLUES AND ACCESSORIES:
A. FLUE FOR GAS FIRED CONDENSING BOILER SHALL BE AS RECOMMENDED BY THE GAS APPLIANCE MANUFACTURER. FLUES SHALL BE SCHEDULE 40, PVC OR CPVC PIPE PER THE MANUFACTURER'S INSTALLATION REQUIREMENTS.
B. PROVIDE MANUFACTURER'S STANDARD ACCESSORY ITEMS INCLUDING BIRD PROOF TOP, STORM COLLAR, ROOF THIMBLE, ETC. AS REQUIRED FOR A COMPLETE INSTALLATION. ROOF THIMBLES THROUGH THE BUILDING ROOF SHALL BE SUITABLE FOR USE WITH THE ROOF PROVIDED.
C. FLUES SHALL BE DOUBLE WALL TYPE B EQUAL TO METALBESTOS. PROVIDE MANUFACTURER'S STANDARD FITTINGS AND ACCESSORIES (ROOF THIMBLE, STORM COLLAR, GOUNT/WASHING, ETC.) AS REQUIRED FOR A COMPLETE INSTALLATION.
13. EXHAUST FANS:
A. CENTRIFUGAL TYPE FAN WITH CHARACTERISTICS AND CAPACITY AS SCHEDULED, ELECTRICALLY POWERED, SUITABLE FOR MOUNTING ON ROOF CURB, DIRECT OR BELT DRIVEN, HEAVY GAUGE SPUN-ALUMINUM WEATHERPROOF HOUSINGS OF THE HOODED DOME OR UP/SLANT TYPE. PROVIDE PERMANENT SPLIT CAPACITOR TYPE MOTOR FOR DIRECT DRIVEN FANS, AND CAPACITOR-START, INDUCTION-RUN TYPE MOTOR FOR BELT DRIVEN FANS.
B. CENTRIFUGAL CEILING EXHAUSTERS SHALL BE ELECTRICALLY POWERED CENTRIFUGAL TYPE FAN SUITABLE FOR MOUNTING IN THE CEILING WITH A PERFORATED OFF-WHITE METAL GRILLE WITH A THUMBSCREW ATTACHMENT FOR EASY ACCESS TO FAN HOUSING. UNIT SHALL CONSIST OF A GALVANIZED STEEL HOUSING LINED WITH ACoustICAL INSULATION AND SHALL INCLUDE AN INTEGRAL BACKDRAFT DAMPER ON FAN DISCHARGE. MOTOR SHALL BE A PERMANENT SPLIT-CAPACITOR TYPE MOTOR, PERMANENTLY LUBRICATED, WITH THERMAL OVERLOAD PROTECTION. PROVIDE DISCONNECT SWITCH OR OTHER MEANS OF DISCONNECT AT MOTOR IN FAN HOUSING.
14. ROOFTOP UNITS:
A. UNIT SHALL BE FACTORY-ASSEMBLED AND TESTED, DESIGNED FOR ROOF INSTALLATION, AND SHALL CONSIST OF SCROLL TYPE COMPRESSOR(S), CONDENSERS, EVAPORATOR COILS, THERMAL EXPANSION VALVE, CONDENSATE DRAIN PAN, CONDENSER AND EVAPORATOR FANS, CONDENSER FANS TO BE SEQUENCED REFRIGERATION CONTROLS, GAS FIRED HEAT EXCHANGER OR ELECTRIC HEATING SECTION, FILTERS, AND DAMPERS. CAPACITIES AND ELECTRICAL CHARACTERISTICS SHALL BE AS SCHEDULED ON THE DRAWINGS.
B. COMPRESSOR(S): UNIT SHALL INCLUDE VIBRATION ISOLATORS AND CRANKCASE HEATER. REFRIGERANT CIRCUIT SHALL INCLUDE A FILTER DRYER, SIGHT GLASS, COMPRESSOR SERVICE VALVES, AND LIQUID LINE SERVICE VALVES.
C. SAFETY CONTROLS SHALL INCLUDE:
a) LOW PRESSURE CUTOFF, MANUAL RESET.
b) HIGH PRESSURE CUTOFF, MANUAL RESET.
c) COMPRESSOR MOTOR OVERLOAD PROTECTION, MANUAL RESET.
d) ANTI-RECYCLING THING DEVICE.
e) ADJUSTABLE LOW-AMBIENT LOCKOUT.
f) OIL PRESSURE SWITCH.
D. REFRIGERANT COIL: ALUMINUM FINS BONDED TO SEAMLESS COPPER TUBE BY MEANS OF MECHANICAL EXPANSION. AN EQUALIZING TYPE VERTICAL DISTRIBUTOR SHALL ENSURE EACH COIL CIRCUIT RECEIVES THE SAME AMOUNT OF REFRIGERANT.
E. ECONOMIZER SHALL CONSIST OF RETURN AIR DAMPER, OUTDOOR AIR DAMPER, AND BAROMETRIC RELIEF DAMPER. PROVIDE POWERED EXHAUST FAN WITH MANUFACTURER'S STANDARD CONTROLS FOR UNITS SCHEDULED ON THE DRAWINGS.
F. GAS HEAT: INDIRECT FIRED, GAS HEAT EXCHANGER, AUTOMATIC SPARK IGNITION, MANUFACTURER'S STANDARD GAS TRAIL WITH REGULATOR (IF REQUIRED), ASA APPROVED. VERIFY GAS SERVICE PRESSURE TO INDIVIDUAL ROOFTOP UNITS.
G. ROOFTOP UNITS SHALL BE WIRED TO SHUTDOWN ON A SIGNAL FROM THE SMOKE DETECTORS AND SHALL AUTOMATICALLY RESET WHEN THE SMOKE DETECTORS ARE RESET.
15. SINGLE-ZONE MINI SPLIT SYSTEM WITH HEAT PUMP CONDENSING UNIT:
A. AIR HANDLING UNIT SHALL BE FACTORY ASSEMBLED, PRE-WIRED UNIT CONSISTING OF WIRING, PIPING, ELECTRONIC EXPANSION VALVE, AND CONTROLS. CAPACITY SHALL BE AS SCHEDULED.
1) THE UNIT SHALL BE EQUIPPED WITH THE MANUFACTURER'S STANDARD CONTROLS INCLUDING 24 VOLT CONTROL TRANSFORMER AND A WIRELESS OR WIRED REMOTE CONTROLLER.
2) UNIT SHALL BE EQUIPPED WITH A FILTER THAT IS EASILY REMOVABLE AND WASHABLE.
3) FAN SHALL BE A DC MOTOR, CAPABLE OF OPERATING AT 3 FAN GRADES: LOW, MEDIUM AND HIGH. MOTOR SHALL BE PROVIDED WITH THERMAL OVERLOAD PROTECTION.
4) CONNECTIONS: UNIT SHALL BE EQUIPPED WITH LIQUID AND GAS FLARE FITTINGS. SHALL HAVE CONNECTIONS FOR BOTH REFRIGERANT PIPING AND DRAINAGE ON BOTH SIDES OF UNIT. UNIT SHALL OFFER MULTIPLE ACCESS POINTS FOR REFRIGERANT OUTLET PIPES.
B. HEAT PUMP CONDENSING UNIT SHALL BE FACTORY-ASSEMBLED, PRE-WIRED AND TESTED AIR-COOLED CONDENSING UNIT, COMPRESSOR, CONDENSER COIL, FAN, MOTOR, REVERSING VALVE, SOLID-STATE DEFROST CONTROL UTILIZING THERMISTERS, REFRIGERANT RESERVOIR, OPERATING CONTROLS, ETC. CAPACITY AND ELECTRICAL CHARACTERISTICS SHALL BE AS SCHEDULED.
1) HERMETICALLY SEALED COMPRESSOR WITH BUILT-IN OVERLOADS AND VIBRATION ISOLATION, COMPRESSOR MOTOR, SHALL HAVE THERMAL AND CURRENT SENSITIVE OVERLOAD DEVICES, INTERNAL HIGH-PRESSURE PROTECTION, HIGH AND LOW PRESSURE CUTOFF SWITCHES, START CAPACITOR AND RELAY, 2-POLE CONTACTOR, CRANKCASE HEATER, AND TEMPERATURE ACTIVATED SWITCH AND THER TO PREVENT COMPRESSOR RAPID CYCLE.
2) COIL SHALL BE COPPER TUBING WITH ALUMINUM FINS, A GRILLE GUARD SHALL BE INCLUDED. COIL SHALL BE FACTORY COATED FOR INCREASED CORROSION RESISTANCE.
3) ALUMINUM PROPELLER FAN SHALL BE DIRECT DRIVEN, WITH PERMANENTLY LUBRICATED FAN MOTOR HAVING THERMAL OVERLOAD PROTECTION.
4) UNIT SHALL HAVE AN OPERATING COOLING RANGE OF AT LEAST 5°F TO 122°F AND AN OPERATING HEATING RANGE OF AT LEAST -15°F TO 96°F.
16. SMOKE DETECTORS:
A. DUCT DETECTOR REMOTE TEST STATION SHALL BE SIMPLEX #426-4642 WITH REMOTE ALARM INDICATOR, POWER-ON INDICATOR, TONE-ALERT, TONE-ALERT SILENCE SWITCH, AND TEST/RESET SWITCH.
1) DEVICES SHALL BE MOUNTED IN APPROVED LOCATION AS INDICATED ON THE FLOOR PLANS OR AS DIRECTED BY LOCAL AUTHORITY HAVING JURISDICTION.
B. SMOKE DETECTORS SHALL BE INTERLOCKED. IN ALARM CONDITION OF A SINGLE DETECTOR ALL UNITS SHALL SHUT DOWN.
17. CONTROL WIRING:
A. ELECTRICAL WIRING AND WIRING CONNECTIONS REQUIRED FOR THE INSTALLATION OF THE TEMPERATURE CONTROL SYSTEM, SHALL BE PROVIDED BY THIS CONTRACTOR, UNLESS SPECIFICALLY SHOWN ON THE ELECTRICAL DRAWINGS OR SPECIFICATIONS.
B. INSTALL CONTROL WIRING, WITHOUT SPLICES BETWEEN TERMINAL POINTS, COLOR CODED. INSTALL IN NEAT WORKMANLIKE MANNER, SECURELY FASTENED. INSTALL IN ACCORDANCE WITH NATIONAL ELECTRICAL CODES AND THE ELECTRICAL SPECIFICATIONS.
1) INSTALL CIRCUITS OVER 25 VOLT WITH COLOR CODED NUMBER 12 WIRE.
2) INSTALL CIRCUITS UNDER 25 VOLT WITH COLOR CODED NUMBER 18 WIRE WITH 0.031 INCH HIGH TEMPERATURE 105 DEGREE F PLASTIC INSULATION ON EACH CONDUCTOR AND PLASTIC SHEATH OVER ALL.
3) INSTALL ELECTRONIC CIRCUITS WITH COLOR CODED NUMBER 22 WIRE WITH 0.025 INCH POLYETHYLENE INSULATION ON EACH CONDUCTOR WITH PLASTIC JACKETED COPPER SHIELD OVER ALL.
4) INSTALL LOW VOLTAGE CIRCUITS, LOCATED IN CONCRETE SLABS AND MASONRY WALLS, OR EXPOSED IN OCCUPIED AREAS, IN ELECTRIC CONDUIT.
5) ALL WIRING IN AREAS USED AS AIR FLEUMS SHALL BE IN ELECTRIC CONDUIT EXCEPT THAT LOW VOLTAGE WIRING MAY BE TEFLON COATED, ALUMINUM SHEATHED CABLE OR OTHER WIRE SPECIFICALLY APPROVED FOR INSTALLATION IN AIR FLEUMS, WHERE ACCEPTABLE BY LOCAL CODES.
6) ALL WIRING IN AREAS NOT USED FOR AIR MOVEMENT SHALL BE IN ELECTRIC METALLIC TUBING EXCEPT LOW VOLTAGE WIRING MAY BE IN APPROVED SIGNAL CABLE WHERE ACCEPTED BY LOCAL CODES.
C. THERMOSTATIC CONTROLS TO HAVE A 5°F DEADBAND AND SETPOINT OVERLAP RESTRICTIONS.
1) TEMPERATURE CONTROLS SETBACK TO BE 55°F (HEAT) AND 55° (COOL), 2-HOUR OCCUPANT OVERRIDE, 10-HOUR BACKUP.

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.

RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI



This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782




A New Facility for AUTOMOTIVE SALES & DETAIL CENTER 2150 NE Independence Ave Lee's Summit, Missouri 64064

Table with 2 columns: ISSUE DATE, REVISION. Row 1: 2/22/21

SHEET TITLE MECHANICAL / PLUMBING SPECIFICATIONS

MP0.1



ENGINEERS INCORPORATED
 5720 Reeder
 Shawnee, Ks. 66203
 (913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
 © 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782



A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
 2150 NE Independence Ave
 Lee's Summit, Missouri 64064


ISSUE DATE: 2/22/21

REVISION:

SHEET TITLE
 FIRST FLOOR
 WASTE & VENT PLAN

P1.0

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.



FIRST FLOOR WASTE & VENT PLAN
 SCALE: 1/8" = 1'-0"
 FFE-100.0

PLUMBING SYMBOLS

— —	SOIL AND WASTE PIPING BELOW FLOOR/GRADE
— —	SOIL AND WASTE PIPING ABOVE FLOOR/GRADE
—OS—	OIL/SAND WASTE PIPING TO OIL/SAND INTERCEPTOR
— ST—	STORM PIPING BELOW FLOOR/GRADE
— ST—	STORM PIPING ABOVE FLOOR/GRADE
— V—	SANITARY VENT PIPING ABOVE GRADE
— V—	SANITARY VENT PIPING BELOW GRADE
— —	DOMESTIC COLD WATER PIPING
— —	DOMESTIC HOT WATER PIPING
— G—	GAS PIPING
— VAC—	VACUUM PIPING
— D—	EQUIPMENT DRAIN LINE
— F—	FIRE LINE
— —	PIPING TURNING DOWN
— —	PIPING TURNING UP
— —	TEE TOP CONNECTION
— —	UNION
— —	BACKFLOW PREVENTER
FD	FLOOR DRAIN
FCD	FLOOR CLEAN OUT
MCO	MALL CLEAN OUT
GCO	GRADE CLEAN OUT
	VALVE
	BALANCING VALVE
	SOLENOID VALVE
	PRESSURE REGULATOR
	CHECK VALVE
	CONNECT TO EXISTING
I.E.	INVERT ELEVATION OF PIPE
△	MATCH MARKS ON PLUMBING RISER DIAGRAM
— HS—	HYDRONIC SUPPLY PIPING
— HR—	HYDRONIC RETURN PIPING

PLUMBING GENERAL NOTES:

- INSTALL ALL PIPE, ETC. AS HIGH AS POSSIBLE.
- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS AND MOUNTING HEIGHTS OF FIXTURES.
- REFER TO ARCHITECTURAL & STRUCTURAL DRAWINGS FOR REQUIREMENTS FOR SUPPORTING PIPING, EQUIPMENT, ETC. FROM THE STRUCTURE. PROVIDE ADDITIONAL STEEL AS REQUIRED TO PROPERLY SUPPORT SYSTEMS FROM THE STRUCTURE.
- PROVIDE 1" SCHEDULE 40 PVC CONDENSATE DRAIN PIPE FOR EACH ROOFTOP AS DETAILED.
- NO PIPING SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- CONTRACTOR TO TEST WATER PRESSURE ON SITE AND PROVIDE PRESSURE REDUCING VALVE ON WATER SERVICE IF PRESSURE IS OVER 80 PSI.

PLUMBING PLAN NOTES:

- SEE CIVIL FOR CONTINUATION OF 4" WASTE. MAINTAIN MINIMUM 30" COVER.
- LOCATION OF 3" VTR. VERIFY 10' CLEARANCE FROM ALL OUTDOOR AIR INTAKES. SEAL PENETRATION WEATHERTIGHT.
- STORM PIPING A MIN. OF 24" COVER. REFER TO CIVIL PLAN FOR CONTINUATION.
- ROUTE DRAIN FROM RPZ BFFS THRU WALL TO DAYLIGHT AS REQUIRED.
- CONNECT CONDENSATE TO RTU AS REQUIRED AND AS DETAILED.
- ROUTE DRAIN FROM EQUIPMENT TO FLOOR DRAIN AND DISCHARGE WITH AIR GAP.
- CONNECT 3/4" CONDENSATE TO AIR HANDLER CONDENSATE PUMP AND ROUTE UP THRU ROOF AND DISCHARGE AS PER MANUFACTURER'S RECOMMENDATIONS.
- ROUTE 2" VENT UP, SEE P1.1 FOR CONTINUATION.
- 3" WASTE DOWN FROM MEZZANINE. PROVIDE CLEANOUT AT BASE OF RISER. SEE P1.1 FOR CONTINUATION.
- COORDINATE WITH CAR WASH EQUIPMENT TO ROUTE 2" OVERFLOW DRAIN FROM REVERSE OSMOSIS TO TRENCH DRAIN.
- 3/4" DRAIN FROM AIR HANDLER. ON MEZZANINE DOWN TO 18" ABOVE GRADE. ROUTE PIPING THRU WALL AND ELBOW DOWN 90°.
- COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER TO ROUTE 2" VACUUM DOWN TO VACUUM HOSE ASSEMBLY.
- SUPPORT VACUUM PIPING FROM STRUCTURE AS REQUIRED.
- COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER TO CONNECT 6" VACUUM PIPING TO VACUUM SEPARATOR AND VACUUM PRODUCER AS EQUIRED.
- CONNECT 4" EXHAUST TO VACUUM EQUIPMENT AND ROUTE UP THRU ROOF TO VENT TERMINATION AS REQUIRED. OFFSET AS REQUIRED TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782



A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
2150 NE Independence Ave
Lee's Summit, Missouri 64064


ISSUE DATE: 2/22/21

REVISION:


SHEET TITLE
MEZZANINE
WASTE & VENT PLAN

P1.1

- PLUMBING PLAN NOTES:**
- ① 3" WASTE DOWN. SEE P1.0 FOR CONTINUATION.
 - ② 2" VENT DOWN UP TO 3" VTR. VERIFY 10' CLEARANCE FROM ALL OUTDOOR AIR INTAKES. SEAL PENETRATION WEATHERTIGHT.
 - ③ CONNECT 3/4" DRAIN TO AIR HANDLING UNIT AND ROUTE DOWN IN WALL TO 18" ABOVE GRADE AND DISCHARGE ONTO GRADE. SEE P1.0 FOR CONTINUATION.
 - ④ ROUTE 1/4" DRAIN FROM FREEZE PROOF ROOF HYDRANT DOWN IN WALL AND DISCHARGE AT FLOOR DRAIN WITH AIR GAP AS PER MANUFACTURER'S RECOMMENDATIONS.



MEZZANINE WASTE & VENT PLAN
SCALE: 1/8" = 1'-0"
NORTH



PLUMBING RISER DIAGRAMS
SCALE: NONE

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.




**ENGINEERS
 INCORPORATED**
 5720 Reeder
 Shawnee, Ks. 66203
 (913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Rights Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
 © 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782



A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
 2150 NE Independence Ave
 Lee's Summit, Missouri 64064


ISSUE DATE:

2/22/21

REVISION:

SHEET TITLE
 FIRST FLOOR
 WATER & GAS PLAN

P2.0



DOMESTIC WATER & GAS PLAN
 SCALE: 1/8" = 1'-0"
 NORTH

PLUMBING PLAN NOTES:

- 1 INSTALL WALL HYDRANT 18" ABOVE GRADE / FINISHED FLOOR.
- 2 CONNECT GAS TO EQUIPMENT WITH REGULATOR AS REQUIRED AND AS DETAILED. REGULATOR TO BE VENTED TO EXTERIOR.
- 3 COORDINATE WITH GAS COMPANY FOR INSTALLATION OF A METER WITH CAPACITY FOR 2201 CFH @ 2 PSI. ROUTE PIPING UP INSIDE THE EXTERIOR WALL AND PENETRATE THE PARAPET WALL ONTO ROOF. ALL CONCEALED JOINTS ARE TO BE WELDED OR USE FITTINGS APPROVED FOR CONCEALED USE. VERIFY ALL EQUIPMENT GAS CAPACITIES AND OPERATING PRESSURES PRIOR TO INSTALLATION OF ANY PIPING. OBTAIN APPROVAL FROM GAS COMPANY FOR ELEVATED PRESSURE BEFORE INSTALLING ANY GAS PIPING.
- 4 PROVIDE 2" RPZ BACKFLOW PREVENTER AND INSTALL 24" A.F.F. ± 6" FROM WALL. PROVIDE 1" RPZ FOR IRRIGATION LOCATED ABOVE 2" RPZ.
- 5 SEE CIVIL PLAN FOR CONTINUATION OF 2" DOMESTIC C/W. MAINTAIN MIN 48" COVER.
- 6 CONNECT C/W TO EQUIPMENT WITH BACKFLOW PREVENTER AS REQUIRED.
- 7 PROVIDE ICE MAKER BOX WITH VALVE FOR CONNECTION TO REFRIGERATOR BY OTHERS.
- 8 ROUTE 1-1/4" C/W AND 1/2" H/W UP TO FIXTURES ON MEZZANINE.
- 9 CAP 1" IRRIGATION FOR FUTURE CONNECTION. MAINTAIN MINIMUM 48" COVER.
- 10 PROVIDE 1" C/W WITH SHUT OFF VALVE DOWNSTREAM OF BACKFLOW PREVENTOR FOR CONNECTION TO CAR WASH EQUIPMENT. COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER FOR EXACT LOCATION AND REQUIREMENTS.
- 11 ROUTE 1" PVC PIPE FROM REVERSE OSMOSIS TO RINSE ARCH WITH SHUT OFF VALVE. COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER FOR EXACT LOCATION AND REQUIREMENTS.
- 12 CONNECT 1" C/W TO REVERSE OSMOSIS DOWNSTREAM OF BACKFLOW PREVENTOR AS REQUIRED. COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER FOR EXACT LOCATION AND REQUIREMENTS.
- 13 PROVIDE 1" BYPASS (NORMALLY CLOSED) FROM REVERSE OSMOSIS TO RINSE ARCH AS REQUIRED. COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER FOR EXACT REQUIREMENTS.
- 14 COORDINATE WITH CAR WASH EQUIPMENT SUPPLIER FOR EXACT LOCATION OF HOSE BIB IN WASH BAY.
- 15 ROUTE 1" C/W DOWN WITH BACKFLOW PREVENTOR AND CONNECT 3/4" C/W TO EACH HOTSY AS REQUIRED. COORDINATE WITH CAR WASH EQUIPMENT TO ROUTE PIPING FROM EQUIPMENT TO OVERHEAD BOOM TO HAND WASH BAY.
- 16 SUPPORT ENH2 FROM WALL ABOVE MOP BASIN, COORDINATE WITH GC FOR WALL SUPPORT.

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Rights Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782



A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
2150 NE Independence Ave
Lee's Summit, Missouri 64064

ISSUE DATE: 2/22/21


REVISION:

SHEET TITLE
MEZZANINE
WATER & GAS PLAN


P2.1

- PLUMBING PLAN NOTES:**
- ① 1-1/2" CM AND 1/2" HM UP FROM BELOW, SEE P1.0 FOR CONTINUATION.
 - ② 3/4" CM UP TO FREEZE PROOF ROOF HYDRANT.

9 10 11 12 13



DOMESTIC WATER & GAS PLAN
SCALE: 1/8" = 1'-0"
NORTH



HOT & COLD WATER


THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.

PROVIDE PRESSURE REDUCING VALVE IF SUPPLY PRESSURE EXCEEDS 80 PSI.


REFER TO CIVIL CAP FOR IRRIGATION

PLUMBING FIXTURE SCHEDULE: (OR EQUAL)


- HWC** WATER CLOSET (HANDICAPPED): AMERICAN STANDARD, #3043.001 "MADERA ADA", VITREOUS CHINA, FLOOR MOUNTED, FLOOR OUTLET, 17-1/2" HIGH ELONGATED BOWL, SIPHON-JET ACTION, #6147.161.002 MANUAL FLUSH VALVE, 1.6 GAL/FLUSH, CENTOCO #ST5CC-001 OPEN FRONT ELONGATED SEAT WITH CHECK HINGE, HANDLE ON WIDE SIDE OF FIXTURE.
- HWC2** WATER CLOSET (HANDICAPPED): AMERICAN STANDARD, #3043.001 "MADERA ADA", VITREOUS CHINA, FLOOR MOUNTED, FLOOR OUTLET, 17-1/2" HIGH ELONGATED BOWL, SIPHON-JET ACTION, #6147.161.002 MANUAL FLUSH VALVE, 1.6 GAL/FLUSH, CENTOCO #ST5CC-001 OPEN FRONT ELONGATED SEAT WITH CHECK HINGE, HANDLE ON WIDE SIDE OF FIXTURE.
- U1** URINAL, WALL HUNG: AMERICAN STANDARD, #6561.011 "TRIMBROOK", VITREOUS CHINA, 0.5 GPM WASH OUT ACTION, WALL HUNG URINAL WITH 3/4" TOP SPUD, ULTIMA SELECTRONIC #6063051 BATTERY-POWERED EXPOSED FLUSH VALVE, FLOOR MOUNTED FIXTURE SUPPORT. SET RIM HEIGHT PER ARCHITECTURAL DRAWINGS.
- L1** HANDICAP LAVATORY, WALL HUNG: AMERICAN STANDARD #03553012 "LUCERN", 20" X 18", VITREOUS CHINA, FRONT OVERFLOW, #6055.205.002 BATTERY-POWERED FAUCET, OFFSET GRID ELBOW DRAIN AND 1-1/4" TAILPIECE, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT (MOUNTED PARALLEL WITH WALL), CHROME PLATED LOOSE KEY ANGLE STOPS AND RISERS, FLOOR MOUNTED CONCEALED ARM LAVATORY SUPPORT, INSULATE EXPOSED DRAIN, WATER SUPPLIES, AND VALVES WITH PROWRAP SEAMLESS MOLDED CLOSED CELL VINYL INSULATION.
- L2** HANDICAP LAVATORY, WALL HUNG: AMERICAN STANDARD #03553012 "LUCERN", 20" X 18", VITREOUS CHINA, FRONT OVERFLOW, #2175.205.002 MANUAL FAUCET WITH SINGLE METAL LEVER FAUCET, OFFSET GRID ELBOW DRAIN AND 1-1/4" TAILPIECE, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT (MOUNTED PARALLEL WITH WALL), CHROME PLATED LOOSE KEY ANGLE STOPS AND RISERS, FLOOR MOUNTED CONCEALED ARM LAVATORY SUPPORT, INSULATE EXPOSED DRAIN, WATER SUPPLIES, AND VALVES WITH PROWRAP SEAMLESS MOLDED CLOSED CELL VINYL INSULATION.
- S1** SINK: ELKAY, #D12522, 21"X15-3/4" X 6-1/2" DEEP BOWL, 24-3/8"X21-3/8" CUT-OUT, SINGLE COMPARTMENT, SELF-RIMMING STAINLESS STEEL SINK WITH SATIN FINISH AND SOUND DAMPENING UNDERCOATING, AMERICAN STANDARD #41175.500.002 FAUCET, SWING SPOUT, AERATOR, SINGLE LEVER HANDLE, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT, CHROME PLATED ANGLE STOPS AND RISERS.
- WB** WASHER BOX: GUY GRAY 1B-150, WASHER BOX WITH 1-1/2" DRAIN OUTLET AND TAILPIECE, AND 1/2" HOSE BIBBS.
- MB** MOP BASIN: FIAT, #MSB-2424, MOLDED STONE MOP BASIN, 2" DRAIN, 24" X 24" BASIN, VINYL BUMPER GUARD, STERN WILLIAMS #T-10-VB FAUCET, SPRING CHECKS, VACUUM BREAKER, INTEGRAL STOPS, WALL BRACE & PAIL HOOK, WALL BRACKET WITH 30" HOSE.
- EWK** ELECTRIC WATER COOLER: ELKAY, #EZ5TL9N, BARRIER FREE TWO-STATION WATER COOLER WITH BOTTLE FILLING STATION, 8.0 GPH, 80 DEGREES F WATER WITH 40 DEGREES F AIR TEMPERATURE, 120 VOLT, COLOR TO BE SELECTED BY ARCHITECT AFTER AWARD OF CONTRACT, FRONT AND SIDE PUSH BARS, CHROME PLATED CAST BRASS P-TRAP WITH CLEANOUT, CHROME PLATED LOOSE KEY ANGLE STOP, FLOOR MOUNTED CARRIER AND CANE APRON.
- FPVH** FREEZEPROOF WALL HYDRANT: WOODFORD #11, 3/4" HOSE NOZZLE OUTLET, BRASS FACE, HANDWHEEL OPERATED, INTEGRAL VACUUM BREAKER.
- FFRH** FREEZEPROOF ROOF HYDRANT: JR SMITH #5906, 3/4" SIZE, NICKEL-BRONZE FACE, HANDLE OPERATED, INTEGRAL VACUUM BREAKER AND DRAIN DOWN.
- HB** HOSE BIBB: WOODFORD, #24, 3/4" HOSE NOZZLE OUTLET, BRASS FINISH, HANDWHEEL OPERATED, INTEGRAL VACUUM BREAKER.
- TD** TRENCH DRAIN: ZURN #Z-086-C6-SL, HEAVY DUTY .75% PRE-SLOPED FIBERGLASS TRENCH DRAIN, VERIFY LENGTH WITH CONTRACTOR, 6" WIDE, CLASS C HEAVY DUTY CAST IRON GRATE.
- TD-1** TRENCH DRAIN: ZURN #Z-082-C6-SL, HEAVY DUTY .75% PRE-SLOPED FIBERGLASS TRENCH DRAIN, VERIFY LENGTH WITH CONTRACTOR, 12" WIDE, CLASS C HEAVY DUTY CAST IRON GRATE.
- TD-2** TRENCH DRAIN: ZURN #Z-082-C6-SL, HEAVY DUTY .75% PRE-SLOPED FIBERGLASS TRENCH DRAIN, VERIFY LENGTH WITH CONTRACTOR, 12" WIDE, CLASS C HEAVY DUTY CAST IRON GRATE.
- FD** FLOOR DRAIN: JR SMITH, #2005-A, CAST IRON FLOOR DRAIN WITH ADJUSTABLE TOP AND 6" NIKALLOY STRAINER.
- FD-1** FLOOR DRAIN: JR SMITH, #2005-F31, CAST IRON FLOOR DRAIN WITH RECESSED CAST IRON STRAINER.
- MY** MIXING VALVE: WATTS, #LFUS6-B, THERMOSTATIC CONTROLLED MIXING VALVE, LEAD FREE BRONZE BODY, LOCKED TEMPERATURE ADJUSTMENT CAP (VANDAL RESISTANT), COPPER ENCAPSULATED THERMOSTAT ASSEMBLY WITH BRASS SHUTTLE, STAINLESSSTEEL SPRINGS, INTEGRAL CHECK VALVES ON HOT AND COLD INLETS. (SET TO 110°F). ASSE 1070 LISTED.
- O1** OIL INTERCEPTOR: ALLIED OR RELIABLE CONCRETE PRODUCTS, 1000 GALLON CONCRETE PRECAST OIL INTERCEPTOR WITH TRAFFIC-RATED LIDS AND ASSOCIATED PIPING PER CODE REQUIREMENTS AND AS DETAILED.
- ENH1** HOT WATER HEATER: AO SMITH #ECL-30, 30 GALLON STORAGE, 208 VOLT, 4500 WATT ELEMENT, ASME TEMPERATURE AND PRESSURE RELIEF VALVE.
- ET1** HOT WATER EXPANSION TANK: AMTROL, #5T-8, 3.2 GALLON EXPANSION TANK WITH DIAPHRAGM.
- ENH2** HOT WATER HEATER: AO SMITH #ECL-30, 30 GALLON STORAGE, 208 VOLT, 4500 WATT ELEMENT, ASME TEMPERATURE AND PRESSURE RELIEF VALVE.
- ET2** HOT WATER EXPANSION TANK: AMTROL, #5T-8, 3.2 GALLON EXPANSION TANK WITH DIAPHRAGM.
- LT** LAUNDRY TUB: FIAT, #TAT1, HEAVY-DUTY POLYETHYLENE TUB WITH LEGS, 2" DRAIN, 20"X28-7/8"X14-3/8" DEEP BASIN, A1 CHROME PLATED FAUCET WITH RING HANDLES AND SPRING SPOUT, AERATOR AND HOSE ADAPTER, SPRING CHECK VALVES, VACUUM BREAKER, INTEGRAL STOPS.
- RPZ** REDUCED ZONE PRESSURE BACKFLOW PREVENTOR: WATTS #LF009, LEAD FREE BRONZE BODY CONSTRUCTION, TWO, IN-LINE INDEPENDENT CHECK VALVES, REPLACEABLE CHECK SEATS WITH AN INTERMEDIATE RELIEF VALVE, AND BALL VALVE TEST COCKS.
- BFP** BACKFLOW PREVENTOR: WATTS #LF007, LEAD FREE DUAL CHECK VALVE WITH ATMOSPHERIC PORT & STRAINER.
- RD** ROOF DRAIN: JR SMITH, #1010-CR, CAST IRON BODY, FLASHING CLAMP, GRAVEL STOP, UNDERDECK CLAMP, SUMP RECEIVER, AND POLYETHYLENE DOME.
- WH** WATER HAMMER ARRESTOR: JR SMITH HYDROTROL, #5000 LEAD-FREE WATER HAMMER ARRESTOR, SIZED AS PER MANUFACTURER'S RECOMMENDATIONS.




CONDENSATE DRAIN DETAIL
SCALE: NONE



ROOF PIPE SUPPORT DETAIL
SCALE: NONE




GAS CONNECTION DETAIL
SCALE: NONE



GAS CONNECTION DETAIL
SCALE: NONE

GAS CONNECTION DETAIL

SCALE: NONE
FOR ROOFTOP UNITS, MAKE-UP AIR UNITS, ETC. WITH 2 PSI GAS PRESSURE



1000 GALLON OIL SEPARATOR TRAP DETAIL

SCALE: NONE

PLUMBING DRAINAGE CALCULATIONS

FIXTURE	QUANTITY	FU	TOTAL FU
WATER CLOSETS	4	4	20
URINAL	2	4	8
LAVATORIES	4	1	4
SINKS	3	2	6
FLOOR DRAIN	5	2	10
TRENCH DRAIN	4	2	8
MOP SINK	2	2	4
TOTAL			61 FU

VENT MAINS - 3"
WASTE MAIN - 4"

PLUMBING FIXTURE WATER COUNT

FIXTURE	QUANTITY	GW FU	CW TOTAL FU	HW FU	TOTAL FU	COMBINED FU	COMBINED TOTAL FU
WATER CLOSETS	4	10	40	0	0	10	40
URINAL	2	5	10	0	0	5	10
LAVATORIES	4	1.5	6.0	1.5	6.0	2	8
SINKS	3	2.25	6.75	2.25	6.75	3	9
MOP SINK	2	2.25	4.5	2.25	4.5	3	6
HOSE BIBB	12	2.5	27	0	0	2.5	27
WASHING MACHINE	1	1	1	1	1	1.4	1.4
			95.25 FU		18.25 FU		101.4 FU

COLD WATER MAIN - 2"
HOT WATER MAIN - 1"


PLUMBING FIXTURE BRANCH PIPING SCHEDULE

FIXTURE	WASTE	VENT	GW	HW
WATER CLOSET (FLUSH VALVE)	4"	2"	1"	--
URINAL	2"	1-1/2"	3/4"	--
LAVATORY	1-1/4"	1-1/4"	1/2"	1/2"
SINK	1-1/2"	1-1/2"	1/2"	1/2"
FLOOR DRAIN	2"	2"	--	--
MOP BASIN	2"	2"	1/2"	1/2"
ELECTRIC WATER COOLER (BI-LEVEL)	1-1/2"	1-1/2"	1/2"	--
WASHER BOX	1-1/2"	1-1/2"	1/2"	1/2"
FLOOR SINK	3"	2"	--	--
TRENCH DRAIN	4"	--	--	--

NOTE: INDIVIDUAL VENTS FOR FIXTURES ON PLANS AND RISER DIAGRAMS HAVE BEEN INCREASED WHERE HORIZONTAL VENT LENGTH IS IN EXCESS OF THE MAXIMUM DISTANCE INDICATED BY THE CODE.

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
© 2021 BC Engineers, Inc.

PE COA #2009003629



BC PROJECT #20782



A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
2150 NE Independence Ave
Lee's Summit, Missouri 64064

ISSUE DATE: 2/22/21

REVISION:


SHEET TITLE
PLUMBING
DETAILS

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.


This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Rights Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing herein, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without the prior written consent of the Engineer is strictly prohibited.
© 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782



FIRST FLOOR MECHANICAL PLAN
SCALE: 1/8" = 1'-0"
NORTH

MECHANICAL GENERAL NOTES:

- COORDINATE ALL WORK WITH OTHER TRADES AND EXISTING CONDITIONS AS REQUIRED TO PROPERLY INSTALL ALL SYSTEMS AS INTENDED, WITHIN THE CONFINES OF THE SPACES AVAILABLE, AND WITHOUT INTERFERENCES.
- THIS CONTRACTOR SHALL PERFORM ALL WORK INDICATED AND/OR AS REQUIRED FOR THE PROPER INSTALLATION AND OPERATION OF THE MECHANICAL SYSTEMS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF DIFFUSERS.
- INSTALL ALL DUCT, PIPE, ETC. AS HIGH AS POSSIBLE.
- DUCT SIZES SHOWN ARE ACTUAL SHEET METAL SIZES AND INCLUDE AN ALLOWANCE FOR DUCT LINER WHERE APPLICABLE.
- PROVIDE FLEXIBLE CONNECTION BETWEEN DUCTWORK AND ROOFTOP UNITS, EXHAUST FANS, AND OTHER MOTORIZED EQUIPMENT.
- NO DUCT SHALL BE ROUTED OVER THE TOP OF ELECTRICAL PANELS.
- ALL MATERIALS WITHIN PLENUMS SHALL BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84.
- ALL MECHANICAL SYSTEMS SHALL BE BALANCED BY A QUALIFIED BALANCING CONTRACTOR. REFER TO SPECIFICATIONS FOR DETAILS.
- ALL EQUIPMENT LOCATED WITHIN 10'-0" FROM EDGE OF BUILDING TO HAVE MINIMUM 42" PARAPET OR MINIMUM 42" GUARD RAILING.

MECHANICAL SYMBOLS

- NEW SUPPLY DIFFUSER
- NEW RETURN AIR GRILLE
- EXHAUST GRILLE/FAN
- REMOTE TEMPERATURE SENSOR
- THERMOSTAT, MOUNTED AT 48" AFF
- UNIT-MOUNTED SMOKE DETECTOR
- AIR QUALITY SENSOR - CO/ NO2
- MOTORIZED DAMPER/LOUVER
- NEW DUCTWORK
- 32"x14" SIZE OF RECTANGULAR DUCT
- 6"φ SIZE OF ROUND DUCT
- FLEXIBLE DUCTWORK
- FLEXIBLE CONNECTION TO FAN
- FLOOR PLAN NOTE DESIGNATION
- S.A. SUPPLY AIR
- R.A. RETURN AIR
- EXH. EXHAUST AIR
- TRANSITION IN DUCT SIZE
- ELBOW WITH TURNING VANES
- MANUAL VOLUME DAMPER
- MOTORIZED CONTROL DAMPER
- SPLITTER DAMPER WITH HORIZONTAL REGULATOR
- SUPPLY AIR DUCT UP/DOWN
- RETURN AIR DUCT UP/DOWN
- EXHAUST AIR DUCT UP/DOWN
- CHANGE IN ELEVATION UP (UP) DOWN (DN) IN DIRECTION OF FLOW
- SCHEDULED MECHANICAL EQUIPMENT

MECHANICAL PLAN NOTES:

- CONNECT 3"φ COMBUSTION AIR AND 3"φ FLUE UP TO SNOWMELT BOILER AND ROUTE PIPING UP THRU ROOF TO TERMINATION AS REQUIRED BY MANUFACTURER. OFFSET AS REQUIRED TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES. SEAL PENETRATION WEATHERTIGHT.
- HIGH/LOW RETURN AIR GRILLES - OFFICE SIDE GRILLE LOCATED AT 12" AFF. CENTRAL AREA SIDE LOCATED AT 8" AFF. INSTALL TG-1 ON BOTH SIDES OF WALL.
- SUPPORT UNIT HEATER FROM STRUCTURE AS REQUIRED.
- SUPPORT RADIANT HEATER FROM STRUCTURE AS REQUIRED. ROUTE 4"φ COMBUSTION AND 4"φ FLUE UP THRU ROOF TO MANUFACTURER'S TERMINATION AS REQUIRED. SEAL PENETRATION WEATHERTIGHT.
- RETURN AIR OPENING TURNED UP TO 14" BELOW STRUCTURE.
- ROUTE 10"x10" EXHAUST DUCT UP THRU ROOF TO EXHAUST FAN. SEE M1.1 FOR CONTINUATION.
- SUPPORT UNIT FROM STRUCTURE AS REQUIRED.
- CONNECT 4"φ DRYER VENT TO DRYER AS REQUIRED AND ROUTE UP THRU ROOF TO GOOSENECK AS REQUIRED. OFFSET AS REQUIRED TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- CONNECT 4"φ TYPE 'B' FLUE TO UNIT HEATER AND ROUTE UP THRU ROOF TO WEATHERHEAD AS REQUIRED. OFFSET AS REQUIRED TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- SUPPORT FAN FROM STRUCTURE AS REQUIRED BY THE MANUFACTURER.
- SEE M1.1 FOR CONTINUATION OF 28"x12" RETURN AIR, AND 18"x18" SUPPLY AIR FROM ROOFTOP UNIT.
- CONNECT TYPE 'B' FLUE TO HOTSYS EQUIPMENT AND ROUTE UP THRU ROOF TO VENT TERMINATION AS REQUIRED BY MANUFACTURER. MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- ROUTE 14"x14" EXHAUST DUCT FROM EXHAUST FAN DOWN THRU ROOF TO 14" BELOW STRUCTURE AS REQUIRED.
- ROUTE 10"x10" EXHAUST DUCT FROM EXHAUST FAN DOWN THRU ROOF TO 14" BELOW STRUCTURE AS REQUIRED.
- ROUTE 12"x10" EXHAUST DUCT FROM EXHAUST FAN DOWN THRU ROOF TO 14" BELOW STRUCTURE AS REQUIRED.
- ROUTE 16"x16" EXHAUST DUCT FROM EXHAUST FAN DOWN THRU ROOF TO 14" BELOW STRUCTURE AS REQUIRED.

SEQUENCE OF OPERATION

EF	CARBON MONOXIDE DETECTION: UPON DETECTION OF CARBON MONOXIDE/ NITROUS OXIDE BY ANY OF THE SPACE SENSORS, THE GAS SENSING CONTROL PANEL SHALL CLOSE A RELAY TO ENERGIZE EXHAUST FAN. THE SYSTEM SHALL REMAIN ENERGIZED UNTIL SENSORS INDICATE REMOVAL OF CARBON MONOXIDE.
CONTROL SEQUENCE FOR EXHAUST FANS, AND DAMPERS	
WHEN THE GAS SENSING CONTROL PANEL CALLS FOR EF-6 TO OPERATE AND VENTILATE THE SPACE, THE FAN SHALL RUN WHEN WHEN THE DAMPER IS OPEN.	
MECHANICAL CONTRACTOR TO PROVIDE AND INSTALL 14 AWG LOW VOLTAGE CONTROL WIRING BETWEEN GAS SENSOR PANEL, FAN STARTERS, AND DAMPERS. COORDINATE WITH ELECTRICAL CONTRACTOR FOR CONDUIT BETWEEN DEVICES.	
25 PPM CO - ENGAGE EXHAUST FAN, 100 PPM CO - ENGAGE EXHAUST FAN AND LOCAL HORN/STROBE	
0.75 PPM NO2 - ENGAGE EXHAUST FAN, 2 PPM NO2 - ENGAGE EXHAUST FAN AND LOCAL HORN/STROBE	

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.


A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
2150 NE Independence Ave
Lee's Summit, Missouri 64064

ISSUE DATE: 2/22/21

REVISION:

SHEET TITLE: FIRST FLOOR MECHANICAL PLAN

M1.0



ENGINEERS INCORPORATED
 5720 Reeder
 Shawnee, Ks. 66203
 (913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Architectural Works Copyright Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited.
 © 2021 BC Engineers, Inc.

PE COA #2009003629

2/19/2021



BC PROJECT #20782



A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
 2150 NE Independence Ave
 Lee's Summit, Missouri 64064

ISSUE DATE: 2/22/21


REVISION:

SHEET TITLE
 MEZZANINE
 MECHANICAL PLAN

M1.1


MECHANICAL PLAN NOTES:

- ① SEE M1.0 FOR CONTINUATION OF 28"x12" RETURN AIR, AND 18"x18" SUPPLY AIR DOWN TO FIRST FLOOR.
- ② SEE M1.0 FOR CONTINUATION OF 10"x10" EXHAUST AIR. ROUTE EXHAUST DUCT UP THRU ROOF TO EXHAUST FAN AS REQUIRED, OFFSET AS REQUIRED TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- ③ SUPPORT FAN FROM STRUCTURE AS REQUIRED. ROUTE 6"Ø EXHAUST DUCT UP THRU ROOF TO WEATHERHEAD AS REQUIRED, OFFSET AS REQUIRED TO MAINTAIN 10'-0" CLEARANCE FROM ALL OUTDOOR AIR INTAKES.
- ④ REFRIGERANT PIPING THROUGH ROOF TO AIR HANDLING UNIT AS REQUIRED. CONNECT REFRIGERANT PIPING TO CONDENSING UNIT & COIL AS REQUIRED BY THE MANUFACTURER. PROVIDE AND INSTALL REFRIGERANT PIPING FOR CONDENSING UNIT AS REQUIRED BY MANUFACTURER.
- ⑤ SUPPORT UNIT FROM STRUCTURE AS REQUIRED. PROVIDE VIBRATION ISOLATION AND ADDITIONAL STEEL BRACING AS REQUIRED.



MEZZANINE MECHANICAL PLAN
 SCALE: 1/8" = 1'-0"
 NORTH

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.



5720 Reeder Shawnee, Ks. 66203 (913)262-1772

This drawing has been prepared by the Engineer, or under his supervision. This drawing is provided as an instrument of service by the Designer/Engineer and is intended for the use on this project only. Pursuant to the Intellectual Property Protection Act of 1990, all drawings, specifications, ideas and designs, including the overall form, arrangement and composition of spaces and elements appearing hereon, constitute the original, copyrighted work of the Designer/Engineer. Any reproduction, use, or disclosure of information contained herein without prior written consent of the Engineer is strictly prohibited. © 2021 BC Engineers, Inc.

PE COA #2009003629


2/19/2021



BC PROJECT #20782



DIFFUSER SCHEDULE									
MARK	MFGR	MODEL	BORDER TYPE	NECK SIZE	FACE SIZE	FINISH	DAMPER	ACCESSORIES	NOTES
SD-1	TITUS	TMS	3	10"Φ	24"x24"	WHITE	-	-	-
SD-2			3	8"Φ		WHITE	-	-	-
SD-3			3	6"Φ		WHITE	-	-	-
SD-4		TMS	3	↑	12"x12"	WHITE	-	TRM FRAME	-
SR-1	S300FL	-	-	18"x8"	-	ANODIZED	AIR SCOOP	-	-
SR-2	300RL	-	-	18"x14"	-	ANODIZED	OPPOSED BLADE	-	-
RG-1	PAR	3	3	22"x22"	24"x24"	WHITE	-	-	-
RG-2	PAR	3	3	12"Φ	24"x24"	WHITE	-	-	-
TG-1	350RL	-	-	14"x8"	-	WHITE	-	-	-
EG-1		PAR	3	6"Φ	12"x12"	WHITE	-	TRM FRAME	-
EG-2			3	Φ	24"x24"	WHITE	-	-	-




DIFFUSER DETAIL SCALE: NONE


EXHAUST FAN SCHEDULE										
MARK	MFGR	MODEL	CFM	EXTERNAL STATIC P. IN. WG.	RPM	ELECTRICAL		FAN TYPE	CONTROLS	NOTES
						VOLT/Φ/HZ	PHR			
EF-1	COOK	6C-12b	75	0.1	750	120/1/60	29 W	CEILING EXHAUST	SWITCH	1
EF-2		90C15DH	450	0.375	1550		1/8HP	ROOF EXHAUST	TIME CLOCK	2
EF-3		120C13D	1200	0.1	1300		1/4HP	ROOF EXHAUST	SENSOR	2,3
EF-4		90C15DM	500	0.1	1670		117W	ROOF EXHAUST	THERMOSTAT	2,4
EF-5		90C15DH	700	0.1	1550		134W	ROOF EXHAUST	SENSOR	2,3
EF-6		180C10D	3750	0.1	1075		3/4HP	ROOF EXHAUST	SENSOR	2,3

- NOTES:
1. PROVIDE CEILING GRILLE, INTEGRAL BACK DRAFT DAMPER, VARI-SPEED CONTROLLER (NEAR FAN AND ABOVE CEILING), AND WEATHER HEAD.
 2. PROVIDE INSULATED 14" HIGH (AT LOWEST POINT) PREFABRICATED ROOF CURB, BACKDRAFT DAMPER, BIRD SCREEN, UNIT MOUNTED VARIABLE SPEED CONTROLLER.
 3. INTERLOCK WITH GAS DETECTION SYSTEM.
 4. PROVIDE LINE VOLTAGE COOLING ONLY THERMOSTAT FOR CONTROL OF FAN. SET TO 80°F.

OUTDOOR AIR CALCULATIONS									
UNIT	Area (sqft)	OCCUPANCY CLASSIFICATION	Occupant Density #/1000 sqft	People outdoor airflow rate in breathing zone, (Rp) cfm/person	Area outdoor airflow rate in breathing zone, (Ra) cfm/sqft	Exhaust airflow rate cfm/sqft	Breathing zone outdoor airflow (Ybz)	Zone air distribution effectiveness (Es)	Zone outdoor airflow (dm)
EF-3	1100	Storage Repair garages, enclosed parking garages	0	0	0	.75	0	0.8	(825)
EF-5	890	Storage Repair garages, enclosed parking garages	0	0	0	.75	0	0.8	(668)
EF-6	5000	Storage Repair garages, enclosed parking garages	0	0	0	.75	0	0.8	(3750)
RTU-1		Offices 810 Office spaces 105 Break Room	5	5	0.06		69	0.8	86
RTU-1		Public spaces 750 Corridors 240 Toilet rooms public	0	0	0.06		45	0.8	56
RTU-1		Storage 170 Warehouses	0	0	0.06	50%	10	0.8	13
RTU-2		Offices 125 Office spaces	5	5	0.06		62	0.8	77
RTU-2		Public spaces 320 Corridors 60 Toilet rooms public	0	0	0.06		19	0.8	24
RTU-3		Offices 110 Reception areas 1050 Main entry lobbies	30	5	0.06		23	0.8	29
RTU-3			10	5	0.06		116	0.8	144



SUPPLY REGISTER DETAIL SCALE: NONE



SUPPLY REGISTER DETAIL SCALE: NONE

MINI SPLIT SYSTEM AC/HEAT PUMP CONDENSING UNIT SCHEDULE									
MARK	MFGR	MODEL NO.	NOMINAL TONS	COOLING BTU/H	ELECTRICAL		SEER	NOTES	
					VOLT/Φ/HZ	BREAKER SIZE (AMPS)			
CU-1	MITSUBISHI	FUZ-A18NHA6	1.0	12,000	208/1/60	15	14.2	HEAT PUMP	
CU-2	MITSUBISHI	FUY-A42NKA7	3.5	42,000	240/1/60	30	16.1	COOLING ONLY	

- NOTES:
1. MECHANICAL CONTRACTOR SHALL COORDINATE ALL UNIT MOCPS OF ACTUAL INSTALLED EQUIPMENT WITH ELECTRICAL CONTRACTOR.
 2. PROVIDE HAIL GUARDS FOR EACH UNIT.

MINI SPLIT SYSTEM AC/HEAT PUMP INDOOR UNIT SCHEDULE									
MARK	MFGR	INDOOR UNIT MODEL NO.	EVAP. CFM	NOMINAL TONS	ELECTRICAL		AHU WEIGHT (LBS)	OUTDOOR UNIT	REMARKS
					MCA (A)	VOLT/Φ/HZ			
AHU-1	MITSUBISHI	PLA-A18BA6	390	1.0	1	208/1/60	49	CU-1	1
AHU-2	MITSUBISHI	PEAD-A42AA7	1483	4.0	3.5	240/1/60	91	CU-2	1,2

- NOTES:
1. PROVIDE WIRED THERMOSTAT CONTROL, REFRIGERANT LINESETS, ELECTRICAL WHIPS. COORDINATE UNIT MOCPS WITH ELECTRICAL CONTRACTOR.
 2. PROVIDE WATER TIGHT DRAIN PAN AND CONDENSATE FLOAT SWITCH TO DE-ENERGIZE THE UNIT IF THE DRAIN PAN FILLS WITH WATER.

GAS FIRED INFRARED HEATER SCHEDULE							
MARK	MFGR	MODEL	HEATING (GAS)	ELECTRICAL	LENGTH	REMARKS	NOTES
			BTUH INPUT	VOLT/Φ/HZ			
RH-1	ROBERTS GORDON	HEV	80,000	120/1/60	40'-0"	TUBULAR, LOW INTENSITY	1,2
RH-2							1,2

- NOTES:
1. PROVIDE CONTROL TRANSFORMER, THERMOSTAT, 4"Ø COMBUSTION AIR INTAKE & WEATHERPROOF CAP, 4"Ø FLUE & WEATHERPROOF CAP, ETC., REQUIRED FOR A COMPLETE SYSTEM.
 2. GAS FIRED INFRARED HEATER TO BE DESIGNED FOR HARSH ENVIRONMENTS.

ELECTRIC UNIT HEATER SCHEDULE							
MARK	MFGR	MODEL NO.	BTUH	ELECTRICAL		NOTES	
				VOLT/Φ/HZ	WATTS		
EUH-1	RAYNALL	AFA130D	10,350	277/1/60	3 KW	1	
EUH-2		AFA148D	17,060		4.8 KW	1	

- NOTES:
1. PROVIDE INTEGRAL DISCONNECT & INTEGRAL THERMOSTAT FOR EACH UNIT.

GAS FIRED UNIT HEATER SCHEDULE											
MARK	MFGR	MODEL	CFM	HEATING (GAS)		ELECTRICAL		HP	NOTES		
				BTUH INPUT	BTUH OUTPUT	VOLT/Φ/HZ	HP				
UH-1	LENOX	LF25-075A1	1200	75,000	62,550	120/1/60	1/15	1,2			

- NOTES:
1. PROVIDE EACH UNIT ELECTRONIC PILOT IGNITION & ALUMINIZED STEEL HEAT EXCHANGER.
 2. PROVIDE EACH UNIT WITH REMOTE MOUNTED THERMOSTAT & CONTROL VOLTAGE TRANSFORMER.

ROOFTOP UNIT SCHEDULE																				
MARK	MFGR	MODEL NO.	NOM. TONS	EVAP. CFM	EXT. STATIC P. IN. WG. (NOTE 2)	COOLING			HEATING (GAS)		ELECTRICAL			MINIMUM OUTDOOR AIR (CFM)	TOTAL WEIGHT (LBS)	SEER / EER	FREON	NOTES		
						TOTAL BTUH	SENS. BTUH	AMB.	EVAP. EAT DB/ΔE	BTUH INPUT	BTUH OUTPUT	VOLT/Φ/HZ	BLOWER MOTOR						MIN. MCA (AMPS)	MIN. MOCPS (AMPS)
RTU-1	LENOX	KGB060S4B	5	1,990	1.0	59,700	44,700	105	80/67	108,000	86,000	480/3/60	2 HP	14	20	400	925	14.0 / -	R-410a	1,2,3,4,5,6
RTU-2		KGB060S4B	5	1,990	1.0	59,700	44,700			108,000	86,000		2 HP	14	20	150	925	14.0 / -		
RTU-3		KGB120S4B	10	4,000	0.5	108,800	80,500			180,000	144,000		2 HP	24	30	200	1600	- / 11.0		
RTU-4		KGB180S4B	15	6,000	0.5	169,100	126,800			360,000	288,000		3 HP	30	35	1200	1660	- / 10.8		
RTU-5		KGB180S4B	15	6,000	0.5	169,100	126,800			360,000	288,000		3 HP	30	35	1200	1660	- / 10.8		

- NOTES:
1. PROVIDE OUTDOOR AIR ECONOMIZER WITH STANDARD PERFORMANCE ECONOMIZER CONTROLLER, FIXED DRY BULB CONTROL, BAROMETRIC RELIEF DAMPER, CONSTANT-STAGE AIR VOLUME, SCROLL COMPRESSORS WITH CRANKCASE HEATER, HIGH PRESSURE SWITCHES, FREEZE/STAT, HAIL GUARDS, STANDARD COOLING DOWN TO 30°F. OUTDOOR AIR DAMPER TO FULLY CLOSE w/ FAN SHUTDOWN FOR ALL UNITS. MULTI STAGE HEATING.
 2. EXTERNAL STATIC PRESSURE LISTED REPRESENTS STATIC PRESSURE REQUIRED FOR DUCTWORK AND DIFFUSERS OUTSIDE THE HVAC UNIT COMPLETELY INDEPENDENT OF ANY PRESSURE DROP THROUGH THE HVAC EQUIPMENT INCLUDING BUT NOT LIMITED TO FILTERS, COILS AND ECONOMIZERS. THE FAN AND MOTOR SHALL BE SIZED APPROPRIATELY TO MEET THIS DEFINITION OF EXTERNAL STATIC PRESSURE.
 3. PROVIDE COMMERCIAL 7-DAY PROGRAMMABLE HEAT/COOL/AUTO CHANGE/OVER TOUCHSCREEN THERMOSTAT WITH OPTIMUM START CONTROLS, AND ECONOMIZER OUTPUT FOR EACH UNIT. ECONOMIZER/OUTDOOR AIR DAMPER IS TO CLOSE DURING UNOCCUPIED HOURS.
 4. PROVIDE 14" HIGH (AT LOWEST POINT) PRE-FABRICATED INSULATED ROOF CURB WITH SLOPE TO MATCH SLOPE OF ROOF FOR EACH UNIT.
 5. PROVIDE FACTORY MOUNTED SMOKE DETECTOR IN RETURN OF UNIT.
 6. MECHANICAL CONTRACTOR SHALL COORDINATE ALL UNIT MOCPS OF ACTUAL INSTALLED EQUIPMENT WITH ELECTRICAL CONTRACTOR.

THIS DRAWING IS THE PROPERTY OF HENRY MILLER MECHANICAL. IT MUST NOT BE REPRODUCED IN ANY MANNER, NOR SHALL IT BE SUBMITTED TO OUTSIDE PARTIES FOR ANY REASON WITHOUT WRITTEN CONSENT OF HENRY MILLER MECHANICAL. IT SHALL BE USED ONLY AS A MEANS OF REFERENCE OF WORK DESIGNED, FURNISHED, AND INSTALLED BY HENRY MILLER MECHANICAL.

A New Facility for
AUTOMOTIVE SALES & DETAIL CENTER
 2150 NE Independence Ave
 Lee's Summit, Missouri 64064

ISSUE DATE: 2/22/21

REVISION:

SHEET TITLE: MECHANICAL SCHEDULES


M2.0

GENERAL NOTES:

1. ALL WIRE SIZES BASED ON COPPER CONDUCTORS UNLESS NOTED OTHERWISE.
2. PRIOR TO ROUGH IN, COORDINATE EXACT CONNECTION REQUIREMENTS WITH THE CAR WASH EQUIPMENT FURNISHED. PROVIDE INTERCONNECTIONS BETWEEN EQUIPMENT AS DETAILED ON THE CAR WASH SYSTEM DRAWINGS FURNISHED BY THE MANUFACTURER.


PLAN NOTES:

- 1 MOUNT STRUCTURE ABOVE FOR CORD REEL. CORD REEL FURNISHED BY OWNER.
- 2 MOUNT AT STRUCTURE ABOVE FOR LIGHTED REEL. CORD REEL FURNISHED BY OWNER.
- 3 CONNECT TO OVERHEAD DOOR.
- 4 MOUNT ABOVE WINDOW.
- 5 COORDINATE MOUNTING HEIGHT AND LOCATION WITH TV.
- 6 CONNECT TO BLOWER. CIRCUIT TO THE BLOWER SYSTEM CONTROL PANEL/DISCONNECT SWITCH PER THE MANUFACTURER'S INSTALLATION DRAWINGS.
- 7 CONNECT TO AUXILIARY RELAY ON ROOM OCCUPANCY SENSOR FOR CONTROL.
- 8 PROVIDE 4-POLE ELECTRICALLY HELD CONTACTOR 'LC-1' AND 7-DAY MECHANICAL TIMECLOCK FOR CONTROL OF EXTERIOR LIGHTING. REFER TO THE EXTERIOR LIGHTING CONTROL DETAIL.




RELEASE FOR CONSTRUCTION
 AS PREPARED BY KASA ELECTRIC, LLC
 DEVELOPMENT SERVICES
 LEE'S SUMMIT, MISSOURI
 03/14/2024

PROJECT NO.	REVISIONS	NOTE



2 MEZZANINE FLOOR PLAN - POWER
 1/8"=1'-0"



1 MEZZANINE FLOOR PLAN - POWER
 1/8"=1'-0"

PROJECT: A New Facility for
Automotive Sales and Detail Center
 2150 NE Independence Avenue
 Lee's Summit, Missouri 64064

THIS DRAWING HAS BEEN PRODUCED BY KASA ELECTRIC, LLC FOR THEIR COORDINATION OF THE ELECTRICAL INSTALL AND MAY NOT BE USED FOR ANY OTHER PURPOSE. COPYRIGHT 2010. KASA ELECTRIC, LLC

1206 NW Valley Ridge Rd
 Grain Valley, MO 64029
 Office: (816) 228-4886
 Fax: (816) 228-1060
 www.KASAELECTRIC.COM
 Residential
 Commercial

SCALE:

DRAWN BY:	
ENGINEER:	CAM
CHECK BY:	
DATE:	2/22/21
CAD FILE:	
DRAWING TITLE:	POWER PLAN

DRAWING SHEET NO.
E102

