



BRANDON LOGAN P.O. BOX 6423

A2 1st FLOOR PLAN

G1 GENERAL NOTES

GENERAL DETAILS

GENERAL DETAILS

G4 BRACED WALL DETAILS

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI

03/16/2021

A3 ROOF PLAN

A4 ELEVATIONS

A5 ELEVATIONS



DRAWN BY: MP
DATE: 2-23-21
PROJECT NO: 15-016-04



DESCRIPTION	ON	SYMBOL
INTERIOR LO	***************************************	
STONE OR B	RICK VENEER	7//////////
JOIST SIZE A	ND DIRECTION	FJ-XX
HEADER/ BEAM	SIZE OF MEMBER PER HEADER/ BEAM SCHEDULE - NUMBER OF PLYS "U" IF UPSET	<u>A 2</u> u
CENTERLINE		
POINT LOAD		❸
	VINDOW FRAME SIZE IN INCHES RAL NOTES BELOW)	2941
SMOKE ALAF		(3)
SMOKE & CA	RBON MONOXIDE ALARM	ÍSCI

HEADE	HEADER / BEAM SCHEDULE						
MARK	LUMBER SIZE	CRIPPLE STUDS	TRIMMERS				
A	2 x 6	1	1				
B	2 x 8	1	1				
S	2 x 10	1	1				
9	2 x 12	2	1				
E	134" x 714" L.V.L.	2	1				
F	134" x 91/2" L.V.L.	2	1				
G	1 ³ 4" × 11½" L.∨.L.	2	1				
\oplus	1 ³ 4" × 14" L.V.L.	2	1				
	134" x 16" L.V.L.	3	1				
K	134" x 18" L.V.L.	3	1				
	134" x 91/2" L.S.L.	1	1				
M	134" x 1176" L.S.L.	2	1				
1	·	·					

TRIMMERS UNDER EACH END. SOLID BLOCK BELOW.

1. BEAMS SHALL HAVE TOTAL NUMBER OF CRIPPLES AND

2. FOR L.Y.L. BEAMS IN 2XIØ FLOORS, USE 9 1/4" L.Y.L.

MARK	TYPE	SUB-TYPE	SIZE	SPACING	MAX. SPAN
FJ-1	"I" JOIST (SEE NOTE)	9 1/2"	PER MAN	NUFACTURER
FJ-2	"I" JOIST (SEE NOTE)	11 7/8"	PER MAN	NUFACTURER
FJ-3	"I" JOIST (SEE NOTE)	14"	PER MAN	NUFACTURER
FJ-4	OPEN WEE	3 TRUSSES	14"	PER MAN	NUFACTURE
FJ-5	OPEN WEE	3 TRUSSES	16"	PER MAN	NUFACTURE
FJ-2Ø	LUMBER	ACQ. TREATED	2x1Ø	12" O.C.	16'-2"
FJ-21	LUMBER	ACQ. TREATED	2x1Ø	16" O.C.	14'
FJ-22	LUMBER		2x8	12" O.C.	14'-2"
FJ-23	LUMBER		2x8	16" O.C.	12'-7"
FJ-24	LUMBER		2x1Ø	12" O.C.	17'-9"
FJ-25	LUMBER		2x1Ø	16" O.C.	15'-5"
FJ-26	LUMBER		2-2x1Ø	16" O.C.	

| DEAD LOAD) WITH A MAX. DEFLECTION OF L/360, EXCEPT BELOW BATHROOMS AND TILED AREAS WHERE THE DEFLECTION SHALL BE L/480 MAX.

CONC	CONCRETE WALL SCHEDULE						
MARK	CONCRET	E WALL	REINFORCING	GRADE 40			
	THICKNESS	HEIGHT	VERTICAL	HORIZONTAL			
\bigcirc	8"	4' OR LESS	*4's AT 36" O.C.	2 - *4's			
(\$)	8"	4' TO 6'	*4's AT 36" O.C.	3 - #4's			
\$	8"	6' TO 8'	*4's AT 16" O.C.	4 - #4's			
♦	8"	8'	*4's AT 16" O.C.	4 - #4's			
(8"	9'	*4's AT 12" O.C.	5 - #4's			
(1)	10"	4'	#4's AT 36"O.C.	2 - #4's			
©	10"	8'	*4's AT 36" O.C.	4 - #4's			
\bigoplus	10"	9'	*4's AT 16" O.C.	5 - #4's			
	10"	100'	#4's AT 12" OC	6 - #4'6			

		*4 BARS REQ'D	COLUMN SIZE	MAX.
MARK	PAD SIZE	EACH WAY	(SCHEDULE 40)	LOAD
А	36"x36"x12"	6	3"	13.5 K
В	48"x48"x16"	8	3"	24.Ø K
m C	60"x60"x18"	100	3.5"	37.5 K
D	72"x72"x18"	12	5"	54.Ø K

	$oldsymbol{\square}$	OD NOD NO	110	2.0	
	D	72"x72"x18"	12	5"	54.Ø K
	PIER	SCHEDULE		•	·
•	1ARK	PIER DIAMETE	R POST (ACQ O	R CEDAR UN.O.)	MAX. LOAI
	E	12"	6x6	U.N.O.	1.1 K
	G	18"	6x6	U.N.O.	2.6 K
	田	24"	6x6	LINO	47 K


- 1. PAD AND PIER SIZES ASSUME 1500 P.S.F. SOIL BEARING CAPACITY.
- 2. 10' MAX. STEEL COLUMN HEIGHT FROM BASE PLATE TO TOP OF COLUMN. CONSULT ARCHITECT IF SITE CONDITIONS REQUIRE TALLER COLUMNS.

GENERAL NOTES:

- A. EXTERIOR FRAMED WALLS ARE 2x4 STUDS AT 16" O.C. UNLESS NOTED OTHERWISE.
- B. FURNACE IS DIRECT VENT AND USES OUTSIDE AIR FOR COMBUSTION
- C. FOR DECK OR COVERED DECK FRAMING SEE DETAIL 1/G3
- D. 1/2" MIN. GYPSUM BOARD SHALL BE APPLIED TO THE GARAGE SIDE OF THE WALL SEPARATING THE GARAGE FROM ANY LIVING AREA'S
- E. SEE G4 SHEET FOR LOCATION OF HOLD-DOWN TIES FOR BRACED WALL CONSTRUCTION

FOUNDATION PLAN NOTES

- . CONCRETE SLAB, CONCRETE PIER AND PAD SEE DETAIL 3/G2
- 2. 16" WIDE \times 8" DEEP CONCRETE FOOTING W/2-*4 BARS CONTINUOUS
- 3. 2x4 STUDS @ 16" O.C. WITH TREATED SILL PLATE.




NOTE:

AS AN ALTERNATE TO REBAR IN THE CONCRETE HELIX MICRO REBAR CAN BE ADDED TO CONCRETE MIX PER MANUFACTURERS REQUIREMENTS.

SEE SHEET A2 FOR CEILING SCHEDULE


- 4. EXTEND FLOOR FRAMING AND INSULATE SOFFIT
- 5. FLOOR LINE ABOVE
- 6. 36" GAS FIREPLACE
- 1. PROVIDE THERMAL EXPANSION CONTROL DEVICE.
- 8. RETURN WALL SEE DETAIL 8/G2
- 9. HVAC CHASE
- 10. 7 STUDS FOR BEARING
- 11. MANUFACTURED STONE VENEER SEE ELEVATIONS
- 12. 4 STUDS FOR BEARING
- 13. 2x6 STUDS AT 12" O.C. FOR UNINTERRUPTED 17'-8"
- 14. 5 STUDS FOR BEARING



51'-8"



CREEK AGLE 346 9. EE's L in m



PROJECT NO: 15-016-04



FOUNDATION PLAN

DESCRIPTION	SYMBOL	
INTERIOR LO	***************************************	
STONE OR B	RICK YENEER	7111111111111
JOIST SIZE A	ND DIRECTION	FJ-XX
HEADER/ BEAM	SIZE OF MEMBER PER HEADER/ BEAM SCHEDULE - NUMBER OF PLYS "U" IF UPSET	<u>A</u> 2) u
CENTERLINE		
POINT LOAD		❸
	JINDOW FRAME SIZE IN INCHES RAL NOTES BELOW)	2941
SMOKE ALAF	(\$)	
SMOKE & CA	RBON MONOXIDE ALARM	ŚĊ

MARK	LUMBER SIZE	CRIPPLE STUDS	TRIMMERS
A	2 x 6	1	1
B	2 x 8	1	1
(C)	2 × 10	1	1
Ф	2 x 12	2	1
E	134" x 714" L.V.L.	2	1
F	134" x 91/2" L.V.L.	2	1
G	1 ³ 4" x 11 ⁷ 6" L.V.L.	2	1
H	134" × 14" L.V.L.	2	1
	134" × 16" L.V.L.	3	1
K	134" x 18" L.V.L.	3	1
	134" × 91/2" L.S.L.	1	1
(M)	134" x 111/2" L.S.L.	2	1

I. BEAMS SHALL HAVE TOTAL NUMBER OF CRIPPLES AND TRIMMERS UNDER EACH END. SOLID BLOCK BELOW.

2. FOR L.V.L. BEAMS IN 2XIØ FLOORS, USE 9 1/4" L.V.L.

MARK	TYPE	SUB-TYPE	SIZE	SPACING	MAX. SPAN
FJ-1	"I" JOIST (SEE NOTE)	9 1/2"	PER MAN	UFACTURER
FJ-2	"I" JOIST (SEE NOTE)	11 7/8"	PER MAN	UFACTURER
FJ-3	"I" JOIST (SEE NOTE)	14"	PER MAN	UFACTURER
FJ-4	OPEN WEE	3 TRUSSES	14"	PER MAN	UFACTURER
FJ-5	OPEN WEE	3 TRUSSES	16"	PER MAN	UFACTURER
FJ-2Ø	LUMBER	ACQ. TREATED	2x1Ø	12" O.C.	16'-2"
FJ-21	LUMBER	ACQ. TREATED	2x1Ø	16" O.C.	14'
FJ-22	LUMBER		2x8	12" O.C.	14'-2"
FJ-23	LUMBER		2x8	16" O.C.	12'-7"
FJ-24	LUMBER		2x1Ø	12" O.C.	17'-9"
FJ-25	LUMBER		2x1Ø	16" O.C.	15'-5"
FJ-26	LUMBER		2-2×1Ø	16" O.C.	
NOTE:	DESIGN I	-JOISTS (LOAD	ED W/	TOTAL L	IVE AND
DEAD	LOAD) W	ITH A MAX. DEF	FLECTI	ON OF L	/360,
EXCEF	T BELOW	BATHROOMS,	AND TI	LED AR	EAS

WHERE THE DEFLECTION SHALL BE L/480 MAX.

CEILING	JOISTS	SCHEDUL	.E - LIVE LOAD 10 P.S.F.
MARK	SIZE	SPACING	MAXIMUM SPAN - DOUGLAS FIR *2
CJ-1	2x6	12"	19'-6"
CJ-2	2x6	16"	17'-8"
CJ-3	2x8	12"	25'-8"
CJ-4	2x8	16"	23'-Ø"
CJ-5	2x1Ø	12"	26'-Ø"
CJ-6	2x1Ø	16"	26'-Ø"
CJ-T	2×4	24"	9'-10"
CJ-8	2x6	24"	14'-10"
CJ-9	2x8	24"	18'-9"
CJ-10	2×10	24"	22'-11"

SQUARE FOOTAGE TABLE		
LOCATION	AREA (S.F.)	
UPPER LEVEL	1433	
LOWER LEVEL	392	
BASEMENT	351	
TOTAL	2176	
GARAGE	695	
BASEMENT (UNFINISHED)	183	

GENERAL NOTES:

A. EXTERIOR WALLS ARE 2x4 STUDS AT 16" O.C. UNLESS OTHERWISE NOTED.


B. SOLID BLOCKING BELOW STUDS SUPPORTING BEAMS AND HEADERS.


C. FOR DECK OR COVERED DECK FRAMING - SEE DETAIL 1/G3

FLOOR PLAN NOTES

1. 4x4 PARALLAM COLUMN BETWEEN 1ST FLOOR AND UPPER LEVEL FLOOR

- 2. INSULATE CANTILEVERED FLOOR
- 3. 3 STUDS FOR BEARING, SOLID BLOCKING BELOW
- 4. TOP OF BEAM TO MATCH TOP OF MASTER BEDROOM WALL.
- 5. 6×6 PRESSURE TREATED OR CEDAR POST.
- 6. 2×6 STUDS AT 12" O.C. FOR UNINTERRUPTED 17'-8" TALL WALL
- 7. (2) 2×6 UPSET BEAM (OR $3 2 \times 4$) FOR VALLEY SUPPORT.






EAGLE CREEK LOT 72 2346 SW OLD PORT RE LEE's SUMMIT, MO

BRANDON LOGAN
P.O. BOX 6423
LEE'S SUMMIT, MO 64064







FIRST FLOOR PLAN

ROOF PLAN LEGEND	
DESCRIPTION	SYMBOL
RIDGES AND HIPS	
VALLEYS	
EAVES, RAKE & GABLE	
HOUSE WALLS	
PURLIN	
TOP OF PURLIN STRUT OR RIDGE POLE	0
BOT. OF PURLIN STRUT OR RIDGE POLE	-
JOIST SIZE AND SPACING	RJ-X
UPLIFT VALUE	000*

ROOF RAFTER SCHEDULE	
----------------------	--


MARK	SIZE	SPACING	MAXIMUM 5	PAN
			FLAT CEILING	YAULTED CEILING
RJ-I	2×6	12"	16'-7"	14'-9"
RJ-2	2×6	16"	14'-4"	12'-9"
RJ-3	2×6	24"	11'-9"	10'-5"
RJ-4	2x8	12"	21'-Ø"	18'-8"
RJ-5	2x8	16"	18'-2"	16'-2"
RJ-6	2×8	24"	14'-10	13'-2"
RJ-T	2×10	12"	25'-8"	22'-9"
RJ-8	2×1Ø	16"	22'-3"	19'-9"
RJ-9	2x1Ø	24"	18'-2"	16'-1"
RJ-10	2×12	16"	25'-9"	26'-5"
RJ-11	2×12	24"	18'-2"	22'-10"

GENERAL NOTES:


- A. WHERE POSSIBLE, BRACE ALL RIDGES TO BEARING WALLS OR BEAMS BELOW, AT 4' O.C.
- B. STRUTS TO BEAR ON WALLS AS INDICATED.
 CONTACT ARCHITECT WITH ANY PROPOSED CHANGE
 TO STRUT BEARING LOCATIONS. ARCHITECT MAY
 NEED TO VERIFY THAT BEAMS BELOW NEW STRUT
 LOCATION CAN SUPPORT ADDED LOADS.
- C. SEE SHEET GI FOR LOAD AND DEFLECTION LIMITATIONS
- D. SEE SHEET G3 FOR ROOF FRAMING DETAILS 3\$4/G3
- E. ROOFING TO BE COMPOSITION-40 YR. ON 30# FELT ON 7/16" O.S.B. SHEATHING:

ROOF PLAN NOTES

- 1. BEARING WALL OR BEAM BELOW
- 2. 2x8 PURLIN WITH 2x6 "T" BRACES AT 4' O.C. TO BEARING WALL/ BEAM BELOW
- 3. 2x6 "T" BRACE TO BEARING WALL OR BEAM BELOW. BRACE SHALL BE CONNECTED TO STRUCTURE AT ROOF AND CEILING WITH MINIMUM (5) 16d NAILS.
- 4. CUT BACK SOFFIT EAVE TO CLEAR WINDOW
- 5. BRACE RIDGE TO BEARING WALL WITH 2x6's AT 4'
- 6. 3) 2x6 STRUT
- 7. TIGHT BARGE
- 8. OVERFRAME THIS AREA
- 9. 4-2x6 RAFTERS
- 10. (3)2x6 BEAM
- 11. 2×6 RAFTER TIES AT 32" O.C. INSTALLED 10'-8" FROM DECK TO BOTTOM OF TIE







EAGLE CREEK LOT 723
2346 SW OLD PORT RD.
LEE's SUMMIT, MO.

BRANDON LOGAN
P.O. BOX 6423
LEE'S SUMMIT, MO 64064










ELEVATION NOTES

- 1. ROOFING TO BE "TIMBERLINE" SHINGLES OR EQUAL ON 15# FELT ON 7/16" O.S.B. SHEATHING.
- 2. SIDING TO BE 3/8" MIN. STRUCTURAL WOOD PANEL SIDING, "SMART PANEL" SIDING OR EQUAL, INSTALLED PER MANUFACTURER'S INSTRUCTIONS. PROVIDE "Z" FLASHING BETWEEN VERTICAL PANELS. IX4 SMART TRIM AT ALL CORNERS AND AROUND WINDOWS.
- 3. SMART LAP SIDING WITH 6" EXPOSURE AND 5/4x6 SMART TRIM AT CORNERS, DOORS AND WINDOWS
- 4. MANUFACTURED STONE
- 5. TIGHT BARGE
- 6. BOARD & BATTEN SHUTTERS
- 7. METAL EGRESS WINDOW WELL. WINDOW SET AT MAX. 44" FROM FINISH FLOOR TO SILL
- 8. SHAKES



RIGHT SIDE ELEVATION





EAGLE CREEK LOT 723
2346 SW OLD PORT RD.
LEE's SUMMIT, MO.

BRANDON LOGAN P.O. BOX 6423




DRAWN BY: MP
DATE: 2-23-21
PROJECT NO: 15-016-04




ELEVATION NOTES

- . ROOFING TO BE "TIMBERLINE" SHINGLES OR EQUAL ON 15# FELT ON 7/16" O.S.B. SHEATHING.
- 2. SIDING TO BE 3/8" MIN. STRUCTURAL WOOD PANEL SIDING, "SMART PANEL" SIDING OR EQUAL, INSTALLED PER MANUFACTURER'S INSTRUCTIONS. PROVIDE "Z" FLASHING BETWEEN VERTICAL PANELS. 1x4 SMART TRIM AT ALL CORNERS AND AROUND WINDOWS.
- 3. SMART LAP SIDING WITH 6" EXPOSURE AND 5/4x6 SMART TRIM AT CORNERS, DOORS AND WINDOWS
- 4. MANUFACTURED STONE
- 5. TIGHT BARGE
- 6. BOARD & BATTEN SHUTTERS
- 7. METAL EGRESS WINDOW WELL. WINDOW SET AT MAX. 44" FROM FINISH FLOOR TO SILL
- 8. SHAKES



LEFT SIDE ELEVATION



REAR ELEVATION
1/4" = 1'-@"



723 RD. LOT CREEK W OLD EAGLE (2346 SVLEE's

0GAN 6423 064064 BRAI P.O. LEE'S



DATE: 2-23-21 PROJECT NO: 15-016-04



DISCLAIMER

THESE DRAWINGS ARE CONSIDERED A "BUILDER'S SET" AND BY BEGINNING CONSTRUCTION THE CONTRACTOR WARRANTS TO THE ARCHITECT, THAT HE HAS THE COMPETENCE AND SKILL IN CONSTRUCTION NECESSARY TO BUILD THE PROJECT WITHOUT FULL ENGINEERING AND DESIGN SERVICES. THE CONTRACTOR WILL BE REQUIRED TO ADAPT THE DRAWINGS TO ACTUAL FIELD CONDITIONS AND MAKE LOGICAL ADJUSTMENTS IN FIT, FORM, DIMENSION AND QUANTITY. IN THE EVENT, ADDITIONAL DETAIL OR GUIDANCE IS NEEDED, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY WEBSTER ARCHITECTS. FAILURE TO GIVE NOTICE SHALL RELIEVE WEBSTER ARCHITECTS OF THE ALL RESPONSIBILITY FOR THE CONSEQUENCES. ALTHOUGH WEBSTER ARCHITECTS HAVE PERFORMED THEIR SERVICES WITH DUE CARE AND DILIGENCE, PERFECTION CAN'T BE GUARANTEED. IT IS UNDERSTOOD AND AGREED THAT IF WEBSTER ARCHITECTS IS NOT HIRED TO DO PROJECT OBSERVATION OR ANY OTHER CONSTRUCTION PHASE SERVICES, THAT THE CLIENT WILL PERFORM SUCH SERVICES. THE CLIENT ASSUMES ALL RESPONSIBILITY FOR INTERPRETATION OF THE CONTRACT DOCUMENTS AND FOR CONSTRUCTION OBSERVATION, AND THE CLIENT WAIVES ANY CLAIMS AGAINST WEBSTER ARCHITECTS THAT MAY BE IN ANY WAY CONNECTED THERETO. THESE DRAWINGS ARE NOT TO BE SCALED. IF A CRITICAL DIMENSION IS MISSING THE ARCHITECT SHOULD BE CONSULTED.

ABBREVIATIONS ABOYE FINISH FLOOR CHROMATED COPPER ARSENATE C.C.A. CONTROL JOINT CLG. CEILING C.O. CASED OPENING DRYER DOUBLE HUNG DIAMETER DOWN DISHWASHER EXPANSION JOINT EQ. EQUAL F.D. FLOOR DRAIN GAUGE OR GAGE GROUND FAULT CIRCUIT INTERRUPTER HOSE BIB HEIGHT KNEE SPACE POUND LAMINATED VENEER LUMBER MAXIMUM MAX. MIN. MINIMUM MICROWAYE OVEN MICRO. ON CENTER OVERHEAD/ OVERHANG O.H. PAIR RISER REFRIGERATOR ROOM ROUGH OPENING SQUARE FEET

SIM.

SQ.

TYP.

ww.f.

SIMILAR

SQUARE

TYPICAL

WASHER

WITH

TELEVISION

WALK IN CLOSET

WELDED WIRE FABRIC

WATER HEATER

TRASH COMPACTOR

LOAD A	ND DEFLECTION LIMIT	ATION	S
		M	IN. LOADS (P.S.F.)
AREA	CONDITION	LIVE	DEAD
DECKS	-	40	10
CEILING JOISTS	NO STORAGE	10	10
CEILING JOISTS	STORAGE ALLOWED	20	10
FLOORS	NON-SLEEPING	40	10 (20 FOR TILED FLRS
FLOORS	SLEEPING AREAS	3Ø	10 (20 FOR TILED FLRS
POOES	WOOD OR COMPOSIT.	20	10 (20 IN LEAWOOD)
ROOFS	TILE OR CONCRETE	20	20
STAIRS	-	40	10
HANDRA	IL/ GUARDRAIL	200*	IN ANY DIRECTION

- WIND SPEED 90 MPH (CATAGORY AS DEFINED BY R3Ø1.2.1.4)

* TILE FLOOR LOAD BASED ON THINSET METHOD.

OPENIN	G MAXIMUM U-VALUE	
WINDOWS)	.32
<i>OPAQUE</i>	DOORS	20
GLASS D	DOORS	.35
SKYLIGH	T	.55
GLAZED	FENESTRATION SHGC	.40
BULDIN	G COMPONENT MINIMUM R-VALUE	
CEILING		
	WITH ATTIC	49
	CATHEDRAL	3Ø
WALL		
	EXTERIOR (CAVITY or CAVITY / CONTINUOUS)	20 or 13 + 5
	BASEMENT (CAVITY or EXTERIOR)	13 or 10
	CRAWL SPACE	10/13
FLOORS		
	SLABS FOR 2' DEPTH ON FOUNDATION)	10
	TRENCH FOOTINGS - HEATED SLAB	15
	TRENCH FOOTINGS	10
	OVER UNHEATED SPACES	19
	OVER OUTSIDE AIR	30
DUCTS IN	NUNHEATED SPACES - SUPPLY AND RETURN	8
DUCTS IN U	NHEATED SPACES - IN FLOOR AND CEILING ASSEMBLY	6
HOT WAT	ER SYSTEM PIPING	3
FURNACE	(AFUE)	80% MINIMUM
AIR CON	DITIONING (SEER)	13 MINIMUM

CODE COMPLIANCE

. BUILDING CONSTRUCTION: REGARDLESS OF WHAT IS SHOWN ON THE PLANS, THE BUILDING SHALL COMPLY WITH THE 2018 INTERNATIONAL RESIDENTIAL CODE AND ANY OTHER CITY REQUIREMENTS.

B. FOUNDATION WALLS ARE DESIGNED TO COMPLY WITH THE JOHNSON COUNTY FOUNDATION GUIDELINES.

. BUILDING DESIGNED FOR SEVERE CLIMATIC AND GEOGRAPHIC DESIGN CRITERIA OF WEATHERING CONDITIONS, MODERATE TO SEVERE TERMITE CONDITIONS, MODERATE DECAY CONDITIONS, 6 DEGREES FAHRENHEIT AND 5,333 HEATING DEGREE DAYS WINTER DESIGN TEMPERATURE CONDITIONS, 36 INCHES FROST LINE DEPTH CONDITIONS AND FLOOD HAZARDS BASED UPON THE LATEST ADOPTED FIRM. AND F.B.F.M. DOCUMENTS IN ACCORDANCE WITH L.B.C. ARTICLE 4-905.

A. GLASS: PROVIDE SAFETY GLAZING WHERE REQUIRED BY IRC R308 AND IN THE FOLLOWING LOCATIONS: 1. STORM DOORS, 2. INDIVIDUAL FIXED OR OPERABLE PANELS ADJACENT TO A DOOR WHERE THE NEAREST VERTICAL EDGE IS WITHIN A 24" ARC OF THE DOOR IN A CLOSED POSITION AND WHOSE BOTTOM EDGE IS WITHIN 60" OF THE FLOOR, 3. WALLS ENCLOSING STAIRWAYS AND LANDINGS WHERE THE GLAZING IS WITHIN 60" OF THE TOP OR BOTTOM OF THE STAIR, 4. ENCLOSURES FOR HOT TUBS, SAUNAS, STEAM ROOMS, SPAS, BATH TUBS, SHOWERS AND WHIRLPOOLS, 5. FIXED OR OPERABLE PANELS EXCEEDING SQUARE FOOT AND WHOSE BOTTOM EDGE IS LESS THAN 18" ABOVE THE FLOOR AND WALKING SURFACE WITHIN 36"

. EXTERIOR WINDOWS AND DOORS SHALL BE DESIGNED O RESIST WIND LOADS SPECIFIED IN IRC TABLE R3Ø1.2(4)A. EXTERIOR OVERHEAD DOORS SHALL MEET D.A.S.M.A. 90 MPH REQUIREMENTS.

BEDROOM EGRESS: AT LEAST ONE WINDOW FROM EACH BEDROOM AND FROM THE BASEMENT SHALL HAVE AN OPERABLE AREA OF 5.7 SQUARE FEET WITH A MINIMUM OPERABLE HEIGHT OF 24" AND A WIDTH OF 21" AND WITH THE BOTTOM OF THE OPERABLE PORTION NO MORE THAN 44" A.F.F. WINDOWS WHOSE SILL IS 72" OR MORE ABOVE FINISHED GRADE AND WHOSE SILL IS LESS THAN 24" ABOYE FINISHED FLOOR SHALL HAVE WINDOW GUARDS OR OPENING CONTROL DEVICES WHICH RESTRICT A 4" SPHERE FROM PASSING THRU.

D. STAIRWAYS: MAXIMUM RISE 734", MINIMUM RUN 10", MINIMUM HEADROOM 6'-8", MINIMUM WIDTH 36". HANDRAILS ARE REQUIRED WHEN STAIRS HAVE 4 OR MORE RISERS. HANDRAIL TO HAVE ENDS RETURNED OR TERMINATED IN A NEWEL POST OR SAFETY TERMINAL AND PLACED MINIMUM 34", MAXIMUM 38" ABOVE TREAD NOSING. THE HAND GRIP PORTION OF HANDRAIL SHALL BE NOT LESS THAN 1-1/4" NOR MORE THAN 2 5/8" IN CROSS SECTION DIMENSION. HANDRAILS PROJECTING FROM A WALL SHALL HAVE A SPACE OF NOT LESS THAN 1-1/2" BETWEEN THE WALL AND THE HANDRAIL. INSTALL FIRE BLOCKING AT TOP AND BOTTOM OF STAIR RUN. THE CEILING AND WALLS OF USEABLE SPACE UNDER STAIRS SHALL BE SURFACED WITH 1/2" GYPSUM BOARD, TAPED AND FINISHED.

GUARDRAILS: ALL UNENCLOSED FLOOR AREAS, STAIRS AND EXTERIOR DECKS OVER 30" ABOVE GRADE SHALL HAVE 36" HIGH GUARDRAILS WITH A MAXIMUM OPENING OF 4" BETWEEN BALLUSTERS. BALLUSTERS SHALL NOT CREATE A LADDER.

. DOOR BETWEEN THE GARAGE AND DWELLING SHALL BE 3/8" THICK SOLID WOOD, I 3/8" THICK MINIMUM SOLID CORE OR HONEY COMBED STEEL DOOR OR 20-MINUTE FIRE RATED, EQUIPPED WITH AUTOMATIC OR SELF-CLOSING DEVICE.

G. ATTACHED GARAGE: CEILINGS AND BEAMS WITHIN THE GARAGE WILL BE COVERED WITH 5/8" TYPE "X" GYPSUM BOARD, IF SPACE ABOVE GARAGE IS LIVING SPACE.

4. BUILDER TO PROVIDE DECK OR LANDING PRIOR TO OWNER OCCUPANCY.

. CRAWL SPACE: THE MINIMUM NET AREA OF VENTILATION OPENINGS WILL NOT BE LESS THAN I SQUARE FOOT FOR EACH 150 SQUARE FEET OF UNDER-FLOOR AREA. ONE SUCH VENTILATING OPENING WILL BE WITHIN 3 FEET OF EACH CORNER. AN 18"x24" MINIMUM ACCESS OPENING SHALL BE PROVIDED TO CRAWL SPACE.

C. ALL EXTERIOR DOORS, INCLUDING THE DOOR BETWEEN THE GARAGE AND THE HOUSE, SHALL INCORPORATE THE PHYSICAL SECURITY PROVISIONS OF SECTION MUNICIPAL CODE OF THE CITY IN WHICH THIS PROJECT IS LOCATED. FOR CITY OF RAYMORE SEE SECTION R324 "PHYSICAL SECUTITY" OF MUNICIPAL CODE.

MECHANICAL, ELECTRICAL NOTES

A. SMOKE DETECTORS: INSTALL ONE IN EACH BEDROOM, OUTSIDE OF EACH BEDROOM AREA, AT LEAST ONE ON EACH STORY INCLUDING THE BASEMENT. ALL ALARMS ARE TO BE INTERCONNECTED SO THAT ACTIVATING ONE ALARM ACTIVATES THEM ALL.

B. CARBON MONOXIDE ALARMS: IN DWELLING UNITS USING FUEL-FIRED APPLIANCES OR IN DWELLING UNITS WITH ATTACHED GARAGES, INSTALL CARBON MONOXIDE ALARMS OUTSIDE EACH SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS .

C. GROUND FAULT CIRCUIT INTERRUPTER PROTECTION (GFCI) SHALL BE INSTALLED IN RECEPACLES IN BATHROOMS, KITCHENS, GARAGES, UNFINISHED BASEMENTS, OUTDOORS, CRAWL SPACES, AND WITHIN 6' OF ANY SINK. BATHROOM RECEPTACLES REQUIRE SEPARATE 20-AMP CIRCUIT. PROVIDE ARC-FAULT CIRCUIT INTERRUPTERS AS REQUIRED BY IRC E3902.12 OR AS REQUIRED BY MUNICIPALITY.

D. FIREPLACE: FACTORY-BUILT FIREPLACE WILL BE EQUIPPED WITH LISTED COMPONENT FOR OUTSIDE COMBUSTION AIR PER IRC 1005 AND SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS

. ALL BATHROOMS TO RECEIVE EXHAUST FANS-- 50 CFM DIRECTLY TO OUTSIDE. POINT OF DISCHARGE MIN. 3' FROM ANY OPENING.

MECHANICAL, ELECTRICAL NOTES CONT

HEAT PUMP THERMOSTATS MUST PREVENT BACK-UP ELECTRIC RESISTANCE HEAT WHEN THE HEAT PUMP CAN MEET THE LOAD.

G. DUCT SEALING MUST MEET THE REQUIREMENTS OF M 1601.3.1

H. ELECTRICAL CONDUCTORS SHALL BE COPPER AND THE PANEL BOX SHOULD BE 200 AMP

ANY DUCT PENETRATIONS OF THE WALLS OR CEILING SEPERATING THE DWELLING FROM THE GARAGE SHALL BE CONSTRUCTED OF 26 GAUGE SHEET METAL WITH NO OPENINGS IN THE GARAGE

CONCRETE NOTES

A. CONCRETE: ALL CONCRETE SHALL BE 5-7% AIR-ENTRAINED AND HAVE A MINIMUM COMPRESSIVE STRENGTH AS LISTED BELOW AT 28 DAYS: . BASEMENT AND INTERIOR FLOOR SLABS: 3,000 PSI (2,500 IN LENEXA)

. BASEMENT AND FOUNDATION WALLS: 3,000 PSI 3. PORCHES, CARPORT AND GARAGE FLOOR SLABS: 3,500

B. REINFORCING SHALL BE GRADE 40. SPLICES SHALL

LAP 24" MIN. UNLESS NOTED OTHERWISE.

C. FOOTINGS: FOOTINGS SHALL BEAR ON UNDISTURBED SOIL AND EXTEND A MINIMUM OF 36" BELOW FINISHED GRADE. FOOTINGS UNDER FOUNDATION WALLS SHALL HAVE A MINIMUM WIDTH OF 16" AND A MINIMUM DEPTH OF 8" AND SHALL HAVE 2 *4 BARS CONTINUOUS. TRENCH FOOTINGS SUPPORTING MORE THAN ONE FLOOR SHALL BE A MINIMUM OF 16" WIDE. FOOTINGS SHALL BE CONTINUOUS AROUND THE STRUCTURE AND FROM ONE LEVEL TO THE NEXT. MAXIMUM HORIZONTAL JUMPS FOR FOOTINGS SHALL BE 1'.

D. WALLS: HORIZONTAL BARS SHALL BE PLACED WITH THE TOP BAR WITHIN 8 INCHES OF THE TOP OF THE WALL AND OTHER BARS EQUALLY SPACED. BARS SHALL LAP A MINIMUM IS INCHES AT ENDS, SPLICES AND AROUND CORNERS, REINFORCEMENT SHALL BE CONTINUOUS AROUND WINDOWS, DOORS AND OTHER OPENINGS WITH SPLICES AS NOTED ABOVE TO MINIMIZE CRACKING AT CORNERS OF THE OPENINGS. BARS SHALL BE PLACED 2" FROM THE INSIDE FACE OF THE WALL.

E. DAMPPROOFING: DAMPROOFING REQUIRED FOR WALLS ENCLOSING BASEMENTS OR OTHER HABITABLE SPACE. A MINIMUM OF ONE COAT OF DAMPPROOFING SHALL BE APPLIED TO EXTERIOR WALL SURFACES BELOW GRADE. SEAL TIE HOLES, VOIDS AND HONEYCOMBED AREAS WITH | SEALANT BEFORE DAMPPROOFING.

F. WATERPROOFING: WATERPROOFING REQUIRED IN LIEU OF DAMPROOFING WHERE A HIGH WATER TABLE OR OTHER SEVERE WATER CONDITIONS EXIST.

G. DRAIN TILE: INSTALL CONTINUOUS 4" DRAIN TILE AROUND THE PERIMETER OF ALL FOUNDATIONS ENCLOSING HABITABLE SPACES LOCATED BELOW GRADE. INSTALL VERTICAL DRAINS TO THE PERIMETER DRAIN TILE AT ALL WINDOW WELLS. SET DRAIN TILE ON A 2" DEEP BY 12" WIDE GRAVEL BED AND COVER TILE WITH AT LEAST 6" OF COARSE, CLEAN ROCK AND A FILTER MEMBRANE MATERIAL. CONNECT THE DRAINS TO A 20-GALLON SUMP PIT OR DRAIN BY GRAVITY TO AN OUTLET WELL AWAY FROM THE HOUSE.

H. FOUNDATION ANCHORAGE: BASEMENT FOUNDATION SILL PLATES SHALL BE BOLTED TO THE FOUNDATION WITH 1/2" ANCHOR BOLTS EMBEDDED AT LEAST 1 INCHES INTO THE CONCRETE AND SPACED NOT MORE THAN 3 FEET ON CENTER AND WITHIN 12 INCHES OF THE END OF EACH PIECE.

BEAM POCKETS: RECESSED 4" INTO THE WALL. THE DEPTH AND WIDTH SHALL BE SIZED TO ACCOMMODATE THE DESIGNATED BEAM.

FLOOR SLABS: BASEMENT FLOOR SLABS SHALL BE A MINIMUM 4 INCHES THICK AND PLACED ON A 4-INCH GRAVEL BASE. THE BASEMENT FLOOR SHALL BE ISOLATED FROM COLUMN PADS, INTERIOR COLUMNS AND INTERIOR BEARING WALLS. INTERIOR COLUMNS AND BEARING WALLS SHALL BE SUPPORTED ON A SEPARATE INTERIOR FOOTING (NOT ON TOP OF THE FLOOR SLAB). THE GARAGE FLOOR SHALL SLOPE TOWARDS THE GARAGE DOORWAYS OR SLOPE TO A TRENCH OR UN-TRAPPED DRAIN THAT DISCHARGES DIRECTLY TO THE EXTERIOR ABOYE GRADE, OPTIONAL (EXCEPT IN LEAWOOD) 6 MIL. POLY VAPOR BARRIER SHOULD BE INSTALLED UNDER THE FLOOR SLAB.

SENERAL FRAMING NOTES

A. LUMBER: LUMBER IS #2 OR BETTER DOUGLAS FIR LARCH, EXCEPT FOR DECAY RESISTANT LUMBER WHICH IS SOUTHERN YELLOW PINE *2.

B. ALL EXTERIOR FRAMING LUMBER OR LUMBER IN CONTACT WITH CONCRETE OR MASONRY SHALL BE DECAY RESISTANT

C. L.Y.L. HEADERS & BEAMS ARE TO HAVE A MIN. MODULUS OF ELASTICITY OF 1.9 \times 10 PSI.

D. FLOOR, CEILING AND ROOF OPENINGS: TRIMMER JOISTS SHALL BE DOUBLED WHEN THE HEADER IS SUPPORTED MORE THAN 3 FEET FROM THE TRIMMER JOIST BEARING. TRIMMER AND HEADER JOISTS SHALL BE DOUBLED WHEN THE SPAN OF THE HEADER EXCEEDS 4 FEET. THE ENDS OF HEADER RAFTERS MORE THAN 6 FEET LONG SHALL BE SUPPORTED BY FRAMING ANCHORS OR RAFTER HANGERS UNLESS BEARING ON A BEAM, PARTITION OR WALL.

E. FRAMING AROUND OPENINGS: TRIMMER AND HEADER JOISTS SHALL BE DOUBLED WHEN THE SPAN OF THE HEADER EXCEEDS 4' THE ENDS OF HEADER JOISTS MORE THAN 6 FEET LONG SHALL BE SUPPORTED BY FRAMING ANCHORS OR JOIST HANGERS UNLESS BEARING ON A BEAM, PARTITION, OR WALL.

FRAMING NOTES- FLOORS

BEARING: THE ENDS OF EACH JOIST SHALL NOT HAVE LESS THAN 1-1/2 INCHES OF BEARING ON WOOD OR METAL. JOISTS FRAMING INTO BEAMS SHALL BE SUPPORTED BY METAL JOIST HANGERS. JOIST FRAMING FROM OPPOSITE SIDES OF A BEAM, GIRDER OR PARTITION SHALL BE LAPPED AT LEAST 3 INCHES OR STRAPPED TOGETHER JOISTS UNDER AND PARALLEL TO BEARING PARTITIONS SHALL BE DOUBLED.

B. LATERAL SUPPORT: JOISTS AT SUPPORTS SHALL BE SUPPORTED LATERALLY AT THE ENDS BY FULL-DEPTH SOLID BLOCKING NOT LESS THAN 2" NOMINAL THICKNESS OR BY ATTACHMENT TO A HEADER, BAND OR RIM JOIST OR TO AN ADJOINING STUD OR OTHERWISE PROVIDED WITH LATERAL SUPPORT TO PREVENT ROTATION. WHERE JOISTS ARE PERPENDICULAR TO BRACED WALL LINES, PROVIDE BLOCKING UNDER AND IN-LINE WITH THE BRACED WALL

. DECKING TO BE 34 " (MIN.) PLYWOOD OR ORIENTED STRAND BOARD INSTALLED PERPENDICULAR TO JOISTS.

D. TOP OF WALL SUPPORT CONNECTIONS: WHERE JOISTS RUN PARALLEL TO FOUNDATION WALLS, SOLID BLOCKING FOR A MINIMUM OF 2 JOIST SPACES SHALL BE PROVIDED AT A MAXIMUM OF 4 FEET CENTERS, AND SHALL BE SECURELY NAILED TO THE JOISTS AND FLOORING. IF DUCTS ARE INSTALLED IN THE FIRST JOIST SPACE(S), NAIL 2 BY 4'S FLAT AT 4-FOOT CENTERS WITHIN THE JOIST SPACE(S) AND THEN PROVIDE THE SOLID BLOCKING. SECURE EACH 2 BY 4 TO THE SILL PLATE WITH FOUR IOD

E. "I" JOISTS (IF USED) SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS.

PROVIDE BLOCKING OR BRIDGING AT CANTILEYERS

G. PROVIDE 1/2" DRYWALL ON CEILING OF UNFINISHED SPACES FOR FLOOR FRAMING USING "I" JOISTS OR TRUSSES.

FRAMING NOTES - WALLS

A. SIZE, HEIGHT AND SPACING: UNLESS OTHERWISE NOTED, STUDS SHALL BE 2x4 DF#2's SPACED AT 16" O.C.

FOR EXTERIOR WALLS SUPPORTING A ROOF ONLY, 2 x 6 STUDS SPACED 16" O.C SHOULD BE USED FOR ALL WALLS 14' TO 18' TALL AND 2 x 6 STUDS SPACED 12" O.C SHOULD BE USED FOR WALLS 18' TO 20' TALL.

FOR WALLS SUPPORTING A ROOF AND A FLOOR 2 x 6 STUDS SPACED 16" O.C SHOULD BE USED FOR WALLS 12' TO 18' TALL

STUDS SHALL BE CONTINUOUS FROM SOLE PLATE TO TOP PLATE OR CEILING DIAPHRAGM, EXCEPT FOR JACK STUDS, TRIMMER OR CRIPLE STUDS.

B. ANGLES: ANGLED WALLS ARE ASSUMED TO BE 45° UNLESS OTHERWISE NOTED.

C. FRAMING DETAILS: BEARING AND EXTERIOR WALL STUDS SHALL BE CAPPED WITH DOUBLE TOP PLATES INSTALLED TO PROVIDE OVER-LAPPING AT CORNERS AND AT INTERSECTIONS WITH OTHER PARTITIONS. END JOINTS IN DOUBLE TOP PLATES SHALL BE OFFSET AT LEAST 48 INCHES.

D. OPENINGS: UNLESS OTHERWISE NOTED, ALL HEADERS ARE TO BE TYPE "A" PER THE HEADER SCHEDULE. EACH END OF A HEADER SHALL HAVE A BEARING LENGTH OF NOT LESS THAN 1-1/2 INCHES FOR THE FULL WIDTH OF THE LINTEL. PROVIDE SOLID BLOCKING BELOW ALL STUDS SUPPORTING HEADERS AND BEAMS.

- UNLESS OTHERWISE DIMENSIONED, INTERIOR DOORS AND CASED OPENINGS ARE TO BE CENTERED IN THE WALL OR 3" FROM CORNERS AS INDICATED ON THE DRAWINGS.

E. FIRE BLOCKING OF NON-COMBUSTIBLE MATERIAL SHALL BE PROVIDED IN OPENINGS AROUND VENTS, PIPES, DUCTS, CHIMNEYS, FIREPLACES, AND LAUNDRY CHUTES AT CEILING AND FLOOR LEVEL.

F. CRIPPLE WALLS: FOUNDATION CRIPPLE WALLS SHALL BE FRAMED WITH 2 imes 4 STUDS WITH A MINIMUM LENGTH OF 14" OR SHALL BE FRAMED OF SOLID BLOCKING. WHEN EXCEEDING 4' IN HEIGHT ON 2 STORY STRUCTURES, WALLS SHALL BE 2×6 STUDS AT 16" O.C.

G. BASEMENT NONBEARING WALLS: NON-LOAD BEARING STUD WALLS EXTENDING FROM THE FLOOR SLAB TO THE STRUCTURE ABOVE SHALL BE PROVIDED WITH A MINIMUM 1-INCH EXPANSION JOINT.

H. GARAGE DOORS AND FRAMES SHALL BE DESIGNED AND INSTALLED TO MEET A 115 mph WIND LOAD. THE H-FRAME FOR ATTACHMENT OF TRACK AND COUNTER BALANCE SHALL CONSIST OF THE FOLLOWING: 2x6 YERTICAL JAMBS RUNNING FROM FLOOR TO CEILING ATTACHES WITH 3-1/4"x12@ NAILS @ 7" O.C. STAGGERED WITH 7) 3-1/4"x12@ NAILS THRU JAMB INTO HEADER, MINIMUM 2x8 HEADER FOR ATTACHMENT OF COUNTER BALANCE SYSTEM.

FRAMING NOTES- DECKS

. FOR DECK LEDGER ATTACHMENT AND DECK CONSTRUCTION REFER TO IRC SECTION 507.

FRAMING NOTES- CEILING

A. BLOCKING: ROOF RAFTERS AND CEILING JOISTS SHALL BE SUPPORTED LATERALLY TO PREVENT ROTATION AND LATERAL DISPLACEMENT.

B. JOISTS FRAMING INTO BEAMS SHALL BE SUPPORTED BY METAL JOIST HANGERS.

FRAMING NOTES- ROOF

A. FRAMING: RAFTERS SHALL BE FRAMED DIRECTLY OPPOSITE EACH OTHER AT THE RIDGE. THERE SHALL BE A RIDGE BOARD AT LEAST 1-INCH NOMINAL THICKNESS AT ALL RIDGES AND NOT LESS IN DEPTH THAN THE CUT END OF THE RAFTER. AT ALL VALLEYS AND HIPS THERE SHALL BE A SINGLE VALLEY OR HIP RAFTER NOT LESS THAN 2-INCH NOMINAL THICKNESS AND NOT LESS IN DEPTH THAN THE CUT END OF THE RAFTER.

B. BRACING: ALL PURLING AND HIPS, RIDGES, AND YALLEYS SHOWN TO BE SUPPORTED SHALL BE BRACED WITH A STRUT DOWN TO A BEARING WALL (WALLS LOCATED DIRECTLY ABOYE A BEAM LINE OR CONTINUOUS FOOTING). THE MINIMUM SLOPE OF THE STRUTS SHALL NOT BE LESS THAN 45° FROM THE HORIZONTAL.

C. RAFTER TIES: RAFTERS SHALL BE NAILED TO ADJACENT CEILING JOISTS TO FORM A CONTINUOUS TIE BETWEEN EXTERIOR WALLS WHEN SUCH JOISTS ARE PARALLEL TO THE RAFTERS. WHERE NOT PARALLEL RAFTERS SHALL BE TIED TO 2"x4" MINIMUM CROSSTIES AT EACH RAFTER AND LOCATED AS CLOSE TO THE CEILING JOISTS AS POSSIBLE (RE: DETAIL 3 & 4/G3).

D. RAFTER COLLAR TIES: PROVIDE 1x4 MIN. COLLAR TIES AT 48" O.C. (RE: DETAIL 3 & 4/G3). AT CATHEDRAL CEILINGS PROVIDE RIDGE STRAPS.

E. YAULTED CEILINGS: FOR RAFTERS SMALLER THAN A 2 X 10, FURRING MUST BE ADDED TO THE BOTTOM OF THE RAFTER TO OBTAIN A 9 1/4" MINIMUM DEPTH.

F. FLASH AND COUNTERFLASH ROOF RIDGES AND VALLEYS, ROOF PENETRATIONS, CHANGES IN ROOF PITCHES, RAKES, CHIMNEY BASES, WINDOW AND DOOR HEADS, ETC. TO PROVIDE WATER TIGHT CLOSURES. ALL EXPOSED FLASHING TO BE 26 GAUGE ALUMINUM. COUNTERFLASHING SHALL BE FABRICATED FROM 40* TERNE METAL.

G. ATTIC VENTILATION: THE NET FREE VENTILATION AREA SHALL BE NOT LESS THAN 1/150 OF THE AREA OF THE SPACE VENTILATED, EXCEPT THAT THE AREA MAY BE 1/300, PROVIDED AT LEAST 50 PERCENT OF THE REQUIRED VENTILATING AREA IS PROVIDED BY VENTILATOR LOCATED IN THE UPPER PORTION OF THE SPACE TO BE VENTILATED, AT LEAST 3 FEET ABOVE EAVES OR CORNICE VENTS, WITH THE BALANCE OF THE REQUIRED VENTILATION PROVIDED BY EAVE OR CORNICE VENTS. RAFTERS SPACES ENCLOSED BY CEILINGS DIRECTLY APPLIED TO UNDERSIDE OF RAFTERS SHALL BE SIZED TO ALLOW A MINIMUM I INCH CLEAR VENTED AIR SPACE ABOVE THE INSULATION AND EACH SPACE BETWEEN JOISTS SHALL BE VENTED.

H. ROOF SHEATHING: SHALL BE INSTALLED PERPENDICULAR TO THE ROOF JOISTS AND THE ENDS SHALL BE STAGGERED.

PREFABRICATED WOOD TRUSSES (IF USED)

A. ROOF AND FLOOR TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH TRUSS PLATE INSTITUTE (TPI) DESIGN SPECIFICATION FOR METAL PLATE CONNECTED WOOD TRUSSES AND THE NATIONAL DESIGN SPECIFICATION FOR ANSIMFOPA WOOD CONSTRUCTION. PROVIDE TEMPORARY AND PERMANENT BRACING ON ALL TRUSSES, AS REQUIRED TO PROVIDE MEMBER AND TRUSS STABILITY.

3. ROOF TRUSSES SHALL BE DESIGNED AND CONSTRUCTED FOR A MAXIMUM TOTAL LOAD DEFLECTION OF L/240, AND TO SAFELY SUPPORT THE FOLLOWING LOADS:

. TOP CHORD: a. LIVE LOAD SEE GENERAL NOTES

b. DEAD LOAD 15 PSF 2. BOTTOM CHORD:

3. WIND LOADS IN ACCORDANCE WITH THE APPROPRIATE BUILDING CODE. GABLED END TRUSSES SHALL HAVE VERTICAL MEMBERS SPACED AT 16" ON CENTER MAXIMUM. 4. TRUSSES SHALL ALSO BE DESIGNED TO SUPPORT ADDITIONAL OVERBUILD FRAMING TO FORM VALLEYS AND HIPS ON ROOFS.

5. TRUSSES SHALL BE DESIGNED TO SUPPORT DRIFTED SNOW LOADS IN ACCORDANCE WITH THE APPROPRIATE BUILDING CODE.

6. TRUSSES SHALL BE ATTACHED TO WALL ASSEMBLIES BY CONNECTIONS CAPABLE OF RESISTING UPLIFT FORCES AS SPECIFIED ON THE TRUSS DESIGN DRAWINGS PER IRC TABLE R802.11.

ENERGY REQUIREMENTS

THE BUILDING THERMAL ENEVELOPE IS REQUIRED TO BE SEALED (IRC NII02.4.1)

B. RECESSED LIGHTING SHALL BE SEALED TO PREVENT LEAKAGE BETWEEN CONDITIONED AND UNCONDITIONED

C. DUCTS, AIR HANDLERS, FILTER BOXES AND BUILDING CAVITIES USED AS DUCTS SHALL BE SEALED (IRC SECTION

D. PENETRATIONS IN AIR BARRIERS (HOUSE WRAP) SHALL BE TAPED AND SEALED AS REQUIRED BY AIR BARRIER MANUFACTURER, WINDOW/ DOOR MANUFACTURER AND ENERGY CODE.

D. FOR CITY OF OLATHE (BUILDER CHECK ONE):

THE ENERGY AUDIT METHOD OF COMPLIANCE FOR THE 2009 ENERGY CODE SHALL BE FOLLOWED.

THE PRESCRIPTIVE METHOD FOR COMPLIANCE WITH THE 2018 ENERGY CODE SHALL BE FOLLOWED.

CONNECTION	NAILS	LOCATION
JOIST TO SILL OR GIRDER	3-8d	TOENAI
	3 - 3" × Ø.131"	+0=1411
BRIDGING TO JOIST	2-8d 2 - 3" × Ø.131"	TOENAIL
SOLE PLATE TO JOIST OR BLOCKING		FACE NA
	3-3" x Ø.131 at 8" o.c.	
SOLE PLATE TO JOIST / BLOCKING	3-16d at 16" o.c.	FACE NA
AT BRACED WALL PANELS	4 -3" x Ø.131 at 16" o.c.	
TOP PLATE TO STUD	2-16d	END NA
STUD TO SOLE PLATE	3 - 3" x Ø.131"	TOENAIL
SIUD 10 SOLE PLAIE	4-8d 4 - 3" x Ø.131"	IOENAIL
	2-16d	FACE NA
	3 - 3" × Ø.131"	
DOUBLE STUDS	16d at 24" o.c.	FACE NA
	3" x Ø.131 at 8" o.c.	FACENA
DOUBLE TOP PLATES	16d at 24" o.c. 3" x 0.131 at 12" o.c.	FACE NA
	8-16d	LAP SPLIC
	12-3" × Ø.131	
BLOCKING BETWEEN JOISTS AND	3-8d	TOENAIL
RAFTERS TO TOP PLATE	3-3" x Ø.131 at 12" o.c.	
RIM JOIST TO TOP PLATE	8d at 6" o.c.	TOENAIL
TOP PLATE, LAPS AND INTERSECTIONS	3" x Ø.131 at 6" o.c. 2 - 16d	FACE NA
	3 - 3" × Ø.131"	
CONTINUOUS HEADER, 2 PIECES.	16d at 16" o.c.	FACE NA
	3" x Ø.131 at 12" o.c.	
CEILING JOISTS TO TOP PLATE	3-8d	TOENAIL
	5 - 3" x Ø.131	TOENAIL
CONTINUOUS HEADER TO STUD	4-8d 6 - 3" x Ø.131	IOENAIL
CEILING JOISTS, LAPS OVER PARTITIONS	3-16d	FACE NA
	4 - 3" × Ø.131	
CEILING JOISTS TO PARALLEL RAFTERS/ RAFTER TIES TO RAFTERS	RE: IRC TABLE R802.5.1 (9)	FACE NA
	3-8d	TOFN 411
RAFTER TO PLATE	3 - 3" × Ø.131"	TOENAIL
I" DIAGONAL BRACE TO EACH STUD		FACE NA
AND PLATE	2 - 3" × <i>Ø.</i> 131"	
BUILT UP CORNER STUDS		FACE NA
	3" x Ø.131" at 16" o.c.	EACE NA
BUILT UP BEAMS. STAGGER NAILS OF OPPOSITE SIDES	3" x Ø.131" at 24" o.c.	FACE NA
BUILT UP BEAMS AT ENDS AND	2-20d	FACE NA
SPLICES	3 - 3" x Ø.131"	
COLLAR TIE TO RAFTER	3-10d 4 - 3" × 0.131"	FACE NA
LACK BAFTER TO LUB	3-10d	TOE NAIL
JACK RAFTER TO HIP	4 - 3" × Ø.131"	IOE NAI
	2-16d	FACE NA
	3 - 3" × Ø.131"	
ROOF RAFTER TO 2 × RIDGE BEAM	2-16d	TOE NAIL
1001 101 ILIX 10 2 X NIDGE DEAT		FACE NA
	3 - 3" × Ø.131"	
	3-16d	
JOIST TO BAND JOIST		FACE NA
JOIST TO BAND JOIST	3-16d 4 - 3" × Ø.131"	FACE NA
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c.	FACE NA
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c.	FACE NA FACE NA INTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c.	FACE NA FACE NA INTERMEDIA EDGES INTERMEDIA
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 2 3/8" × Ø.113 AT 4" o.c.	FACE NATIONAL PROPERTY OF THE PACE N
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL	3-16d 4 - 3" x Ø.131" 3-16d 4 - 3" x Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" x Ø.13 AT 8" o.c. 2 3/8" x Ø.13 AT 4" o.c. 10d at 12" o.c.	FACE NATIONAL PROPERTY OF THE PACE N
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" x Ø.131" 3-16d 4 - 3" x Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" x Ø.13 AT 8" o.c. 2 3/8" x Ø.13 AT 4" o.c. 10d at 12" o.c.	FACE NAINTERMEDIA EDGES INTERMEDIA EDGES INTERMEDIA EDGES INTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.13 AT 8" o.c. 2 3/8" × Ø.13 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c.	FACE NA FACE NA NIERMEDIA EDGES NIERMEDIA EDGES NIERMEDIA EDGES NIERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO 1" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c. 8d at 12" o.c. 8d at 6" o.c. 2 3/8" × Ø.131 AT 4" o.c. 8d at 12" o.c.	FACE NA FACE NA INTERMEDIA EDGES INTERMEDIA EDGES INTERMEDIA EDGES INTERMEDIA EDGES INTERMEDIA EDGES INTERMEDIA
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I I/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 2 3/8" × Ø.113 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c. 10d at 12" o.c.	FACE NA FACE NA INTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I I/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.13 AT 8" o.c. 2 3/8" × Ø.13 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c. 10d at 12" o.c. 8d at 6" o.c. 10d at 12" o.c. 8d at 6" o.c. 10d at 12" o.c. 10d at 6" o.c. 10d at 6" o.c.	FACE NA FACE NA INTERMEDIA EDGES INTERMEDIA
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I I/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 2 3/8" × Ø.113 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c. 10d at 12" o.c.	FACE NA FACE NA INTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1 1/8" TO 1 1/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.13 AT 8" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.13 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 10d at 6" o.c.	FACE NA FACE NA INTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1 1/8" TO I 1/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING HARDBOARD SIDING	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.13 AT 8" o.c. 2 3/8" × Ø.13 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.13 AT 8" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 1/2" × Ø.131 AT 8" o.c. 3 1/2" o.c. 10d at 6" o.c. 3" × Ø.148 AT 8" o.c. 8d at 12" o.c. 8d at 6" o.c. 8d at 6" o.c. 8d at 6" o.c. 8d at 12" o.c. 6d at 8" o.c.	NTERMEDIA EDGES NTERMEDIA EDGES NTERMEDIA EDGES NTERMEDIA EDGES NTERMEDIA EDGES NTERMEDIA EDGES NTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1 1/8" TO 1 1/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING HARDBOARD SIDING 1/2" GYPSUM SHEATHING	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 2 3/8" × Ø.113 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c. 10d at 12" o.c. 8d at 12" o.c. 8d at 12" o.c. 8d at 12" o.c. 10d at 6" o.c. 3" × Ø.148 AT 8" o.c. 3" × Ø.148 AT 4" o.c. 8d at 12" o.c. 6d at 8" o.c. 6d at 8" o.c.	FACE NA FACE NA INTERMEDIA EDGES
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING: 1 1/8" TO I 1/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING:	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 2 3/8" × Ø.113 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 3" × Ø.148 AT 8" o.c. 3" × Ø.148 AT 4" o.c. 8d at 6" o.c. 8d at 6" o.c. 6d at 8" o.c. 6d at 8" o.c. 6d at 8" o.c. 8d at 8" o.c.	FACE NA FACE NA FACE NA INTERMEDIA EDGES INTERMEDIA
JOIST TO BAND JOIST LEDGER STRIP 3/4" OR LESS WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING. 1/8" TO I" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING. 1 1/8" TO I 1/4" WOOD STRUCTURAL PANEL WALL, SUBFLOOR, & ROOF SHEATHING. HARDBOARD SIDING. 1/2" GYPSUM SHEATHING.	3-16d 4 - 3" × Ø.131" 3-16d 4 - 3" × Ø.131" 6d at 12" o.c. 6d at 6" o.c. 2 3/8" × Ø.113 AT 8" o.c. 2 3/8" × Ø.113 AT 4" o.c. 10d at 12" o.c. 8d at 6" o.c. 2 1/2" × Ø.131 AT 8" o.c. 2 3/8" × Ø.131 AT 8" o.c. 10d at 12" o.c. 8d at 12" o.c. 8d at 12" o.c. 8d at 12" o.c. 10d at 6" o.c. 3" × Ø.148 AT 8" o.c. 3" × Ø.148 AT 4" o.c. 8d at 12" o.c. 6d at 8" o.c. 6d at 8" o.c.	FACE NA FACE NA INTERMEDIA EDGES

FASTENING SCHEDULE

I. ON ½" GYPSUM SHEATHING, 1½" TYPE W OR S SCREWS MAY BE USED IN LIEU OF NAILS. ON 1/8" SHEATHING, THE SCREWS ARE TO BE 1 3/8" LONG. THE SPACING IS THE SAME AS THE NAILS.


 \Box N 0 1 0 () S **–** 9 iii **Q** 4 ¥ფШ **上** 7

O 00 ر آ



DRAWN BY: DATE: 2-23-21 PROJECT NO: 15-016-04





723 RD. 0 1 0 CREEK . o o GL| 46 EE' A S I **上** 2 用

5 0

2/24/2021






A-DTW-06062-28

A-DTV-06100-07



EAGLE CREEK LOT 7
2346 SW OLD PORT F
64 LEE's SUMMIT, M

BRANDON LOGAN P.O. BOX 6423 LEE'S SUMMIT, MO 64064



DRAWN BY: MP

DATE: 2-23-21

PROJECT NO: 15-016-04

A-DTV-06100-04



PERPENDICUALR TO METHOD PFH,PFG, AND CS-PF BRACED WALL PANELS

MAXIMUM TOTAL

b. STRAP SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

EXTENT OF HEADER WITH SINGLE PORTAL FRAME (ONE BRACED WALL SEGMENT)

> 2' TO 18' FINISHED WIDTH OF OPENING FOR SINGLE OR DOUBLE PORTAL

> > MIN. 3" X 11 1/4" NET HEADER

STEEL HEADER PROHIBITED

- FASTEN SHEATHING TO HEADER WITH

NAILS IN 3" GRID PATTERN AS SHOWN

HEADER TO JACK- STUD STRAP PER TABLE -

- MIN. DOUBLE 2" X 4" FRAMING COVERED WITH MIN. 3/8" THICK WOOD STRUCTURAL PANEL SHEATHING WITH 8D COMMON OR GALVANIZED BOX NAILS AT 3" O.C. IN ALL FRAMING (STUDS,

- MIN. LENGTH OF PANEL PER TABLE R602.10.5

INSTALLED PER R403.1.6 WITH 2"x2"x3/16" PLATE

SHEATHED WITH WOOD STRUCTURAL PANELS —

NAIL SOLE PLATE TO

- WOOD STRUCTURAL PANEL SHEATHING CONTINUOUS OVER BAND OR RIM JOIST -

JOIST PER TABLE

A-DTE-06100-25 PF

-MIN. (2) 1/2" DIAMETER ANCHOR BOLTS

BRACED WALL LINE CONTINUOUSLY

FRONT ELEVATION

OVER CONCRETE OR MASONRY BLOCK FOUNDATION

SHEATHING CONTINUOUS

OVER BAND OR RIM JOIST

OVER RAISED WOOD FLOOR - OVERLAP OPTION (WHEN PORTAL SHEATHING LAPS OVER BAND OR RIM BOARD)

R602.10.6.4 ON BOTH SIDES OF OPENING

8d COMMON OR GALVANIZED BOX

OPPOSITE SIDE OF SHEATHING

BLOCKING, AND SILLS) TYP.

MAXIMUM PONY

WALL HEIGHT

MINIMUM WALL STUD

2 x 6 STUD GRADE

a. DR = DESIGN REQUIRED


•


AND GRADE

FRAMING NORMAL SIZE

MIN. 7/16" WOOD STRUCTURAL PANEL SHEATHING	BRACED WALL SCHEDULE	MINIMUM LENGTH	AS REQUIRED TO ALLOW BRACE TO BE CONTINUOUS FROM PLATE TO PLATE AND ANGLE BETWEEN 45° TO 60° FROM HORIZO
SECTION NAIL SOLE PLATE TO JOIST PER TABLE R602.3(1) APPROVED BAND OR RIM JOIST	BRACED	DESCRIPTION	LET-IN-BRACING: METAL STRAPS TO FORM "X" OR "V" INSTALLED PER MANUFACTURED (SIMPSON: WB126C, TWB12, WB143C) (USP: RWB114, WBT12)
		METHOD NUMBER	LIB

	BRACED \	WALL SCHEDULE	2-9
METHOD NUMBER	DESCRIPTION	MINIMUM LENGTH	FASTENERS
LIB	LET-IN-BRACING: METAL STRAPS TO FORM "X" OR "V" INSTALLED PER MANUFACTURED (SIMPSON: WB126C, TWB12, WB143C) (USP: RWB114, WBT12)	AS REQUIRED TO ALLOW BRACE TO BE CONTINUOUS FROM PLATE TO PLATE AND AT AN ANGLE BETWEEN 45° TO 60° FROM HORIZONTAL	PER MANUFACTURER'S REQUIREMENTS
WSP	WOOD STRUCTURAL PANEL- 3/8" THICK (MIN.) FOR STUDS AT 16" O.C. (APA EXP. I- PLYWOOD/ O.S.B./ ETC.)	MIN. 48"	6d COMMON NAILS, 6" O.C. AT EDGES AND 12" O.C. AT INTERMEDIATES
CS-WSP	CONTINUOUS SHEATHING- WOOD STRUCTURAL PANEL: 3/8" THICK (MIN.) (APA EXP. I- PLYWOOD/ O.S.B.)	CONTINUOUS ON ALL EXTERIOR WALLS	6d COMMON NAILS, 8d COMMON NAILS - 6" O.C. AT EDGES AND 12" O.C. AT INTERMEDIATES
GB	GYPSUM BOARD: 1/2" THICK MIN.	96" IF GYP. BOARD 1 SIDE 48" IF GYP. BOARD 2 SIDES (STUDS AT 16" O.C. MAX. FOR 48" LONG PANELS)	6d NAILS OR 1-1/4" SCREWS (TYPE W OR S)-7 O.C. AT EDGES AND 7" O.C. AT INTERMEDIAT (CAN SUBSTITUTE COOLER NAILS)
PFH/PFG	PORTAL FRAME GARAGE: WITH HOLD-DOWNS PFG MIN. 7/16" PFH MIN. 3/8"	SEE DETAIL 1/G3 FOR MIN. WALL LENGTH	PER DETAIL 1/G3
CS-PF	CONTINUOUS SHEATHING- PORTAL FRAME	SEE DETAIL 1/G3 FOR MIN. WALL LENGTH	PER DETAIL 1/G3
NOTES: A. SEE	XXX) ON BRACED WALL PLAN FOR BRACED WALL METHOD.		









723 RD.

LO OR

CR

S

46





LOWER FLOOR DIAGRAM

MAXIMUM

OPENING

EXPOSURE B EXPOSURE C 1,000 1,000 1,000 1,000 10 18 1,000 1,000 1,000 1,000 1,000 1,000 9 1,025 2,050 2,075 2,500 16 1,000 1,275 2,375 2,400 2,850 1,200 DR 18 1,000 1,000 1,500 1.875 1,475 9 1,775 2,175 3,525 3,550 4,125 DR 16 2 x 4 NO. 2 GRADE 2,075 2,500 3,950 3,975 DR DR 18 1,150 1,500 2,650 2,675 3,175 DR DR DR DR DR 2,875 3,375 16

12

16

18

16

18

EXTENT OF HEADER WITH DOUBLE PORTAL FRAMES (TWO BRACED WALL SEGMENTS)

WALL HEIGHT WIDTH (feet) 115 130 (feet) 115 130 110 1,050 1,750 3,950 3,125 12 3,975 DR DR DR DR 3,425 18 DR DR DR 2,275 2,750 DR

3,775

1,000

2,150

2,550

1,750

2,400

3,800

DR

1,700

3,225

3,725

2,700

DR

DR

• • • • • •

.

•

DR

1,700

3,225

3,750

2,725

DR

DR

DR

2,025

3,675

DR

3,125

DR

DR

3,050

DR

DR

DR

FASTEN TOP PLATE TO

ROWS OF 16d SINKER

NAILS AT 3" O.C. TYP.

HEADER WITH TWO

3,225

1,000

1,825

2,200

1,450

2,050

3,50

TENSION STRAP PER

SHEATHING)

TABLE 602.10.6.4 (ON

SHEATHED BRACED WALL

PANEL MEETING MINIMUM

LENGTH REQUIREMENTS OF TABLE R602.10.5

IF NEEDED, PANEL SPLICE

OVER AND BE NAILED TO

MID-HEIGHT. ONE ROW OF

TYPICAL PORTAL FRAME

CONSTRUCTION —

- MIN. DOUBLE 2x4 POST

(KING AND JACK STUD). NUMBER OF JACK STUDS PER TABLES R602.7 (1&2)

-ANCHOR BOLT PER SECTION R403.1.6 (TYP.)

ATTACH SHEATHING TO

BAND OR RIM JOIST WITH

O.C. TOP AND BOTTOM —

8D COMMON NAILS AT 3"

EDGES SHALL OCCUR

COMMON BLOCKING

WITHIN 24" OF WALL

3" O.C. NAILING IS REQUIRED AT EACH PANEL EDGE. ——

TENSION STRAP CAPACITY REQUIRED (pounds) a,b ULTIMATE DESIGN WIND SPEED (mph)

2-9-21

BRACED WALL LINE END CONDITION 1

END CONDITION 3

END CONDITION 5

10' MAX.

END CONDITION 2

END CONDITION 4

REQUIREMENTS

RETURN PANEL: 24" for braced wall lines sheathed with

DISTANCE D: 24" for braced wall lines sheathed with

HOLD DOWN

structural fiberboard

wood structural panels

structural fiberboard

wood structural panels
32" for braced wall lines sheathed with

32" for braced wall lines sheathed with

800 lbs capacity fastened to the edge of the

the foundation or floor framing below

braced wall panel closest to the corner and to