



RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

04/06/2021

RE: 210331  
Lot 102 RR

MiTek USA, Inc.  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**Site Information:**

Customer: Project Name: 210331  
Lot/Block:  
Address:  
City:

Model:  
Subdivision:  
State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2018/TPI2014  
Wind Code: N/A  
Roof Load: 45.0 psf

Design Program: MiTek 20/20 8.4  
Wind Speed: 115 mph  
Floor Load: N/A psf

This package includes 111 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I45167659	A1	3/12/2021	21	I45167679	C10	3/12/2021
2	I45167660	A2	3/12/2021	22	I45167680	D1	3/12/2021
3	I45167661	A3	3/12/2021	23	I45167681	D2	3/12/2021
4	I45167662	A4	3/12/2021	24	I45167682	D3	3/12/2021
5	I45167663	A5	3/12/2021	25	I45167683	D4	3/12/2021
6	I45167664	A6	3/12/2021	26	I45167684	E1	3/12/2021
7	I45167665	B1	3/12/2021	27	I45167685	E2	3/12/2021
8	I45167666	B2	3/12/2021	28	I45167686	E3	3/12/2021
9	I45167667	B3	3/12/2021	29	I45167687	E4	3/12/2021
10	I45167668	B4	3/12/2021	30	I45167688	E5	3/12/2021
11	I45167669	B5	3/12/2021	31	I45167689	G1	3/12/2021
12	I45167670	C1	3/12/2021	32	I45167690	G2	3/12/2021
13	I45167671	C2	3/12/2021	33	I45167691	G3	3/12/2021
14	I45167672	C3	3/12/2021	34	I45167692	G4	3/12/2021
15	I45167673	C4	3/12/2021	35	I45167693	G5	3/12/2021
16	I45167674	C5	3/12/2021	36	I45167694	G6	3/12/2021
17	I45167675	C6	3/12/2021	37	I45167695	G7	3/12/2021
18	I45167676	C7	3/12/2021	38	I45167696	G8	3/12/2021
19	I45167677	C8	3/12/2021	39	I45167697	G9	3/12/2021
20	I45167678	C9	3/12/2021	40	I45167698	G10	3/12/2021

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc under my direct supervision based on the parameters provided by Wheeler - Waverly. Truss Design Engineer's Name: Garcia, Juan My license renewal date for the state of Kansas is April 30, 2022. Kansas COA: E-943

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



March 12, 2021



**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI**

**04/06/2021**

RE: 210331 - Lot 102 RR

MiTek USA, Inc.  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**Site Information:**

Project Customer:    Project Name: 210331  
Lot/Block:  
Address:  
City, County:

Subdivision:

State:

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
41	I45167699	H1	3/12/2021	85	I45167743	J41	3/12/2021
42	I45167700	H2	3/12/2021	86	I45167744	J42	3/12/2021
43	I45167701	H3	3/12/2021	87	I45167745	J43	3/12/2021
44	I45167702	H4	3/12/2021	88	I45167746	J44	3/12/2021
45	I45167703	J1	3/12/2021	89	I45167747	J45	3/12/2021
46	I45167704	J2	3/12/2021	90	I45167748	J46	3/12/2021
47	I45167705	J3	3/12/2021	91	I45167749	J47	3/12/2021
48	I45167706	J4	3/12/2021	92	I45167750	J48	3/12/2021
49	I45167707	J5	3/12/2021	93	I45167751	LAY1	3/12/2021
50	I45167708	J6	3/12/2021	94	I45167752	LAY2	3/12/2021
51	I45167709	J7	3/12/2021	95	I45167753	LAY3	3/12/2021
52	I45167710	J8	3/12/2021	96	I45167754	LAY4	3/12/2021
53	I45167711	J9	3/12/2021	97	I45167755	LAY5	3/12/2021
54	I45167712	J10	3/12/2021	98	I45167756	LAY6	3/12/2021
55	I45167713	J11	3/12/2021	99	I45167757	LAY7	3/12/2021
56	I45167714	J12	3/12/2021	100	I45167758	LAY8	3/12/2021
57	I45167715	J13	3/12/2021	101	I45167759	LAY9	3/12/2021
58	I45167716	J14	3/12/2021	102	I45167760	R1	3/12/2021
59	I45167717	J15	3/12/2021	103	I45167761	V1	3/12/2021
60	I45167718	J16	3/12/2021	104	I45167762	V2	3/12/2021
61	I45167719	J17	3/12/2021	105	I45167763	V3	3/12/2021
62	I45167720	J18	3/12/2021	106	I45167764	V4	3/12/2021
63	I45167721	J19	3/12/2021	107	I45167765	V5	3/12/2021
64	I45167722	J20	3/12/2021	108	I45167766	V6	3/12/2021
65	I45167723	J21	3/12/2021	109	I45167767	V7	3/12/2021
66	I45167724	J22	3/12/2021	110	I45167768	V8	3/12/2021
67	I45167725	J23	3/12/2021	111	I45167769	V9	3/12/2021
68	I45167726	J24	3/12/2021				
69	I45167727	J25	3/12/2021				
70	I45167728	J26	3/12/2021				
71	I45167729	J27	3/12/2021				
72	I45167730	J28	3/12/2021				
73	I45167731	J29	3/12/2021				
74	I45167732	J30	3/12/2021				
75	I45167733	J31	3/12/2021				
76	I45167734	J32	3/12/2021				
77	I45167735	J33	3/12/2021				
78	I45167736	J34	3/12/2021				
79	I45167737	J35	3/12/2021				
80	I45167738	J36	3/12/2021				
81	I45167739	J37	3/12/2021				
82	I45167740	J38	3/12/2021				
83	I45167741	J39	3/12/2021				
84	I45167742	J40	3/12/2021				



RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

04/06/2021

RE: 210331  
Lot 102 RR

MiTek USA, Inc.  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**Site Information:**

Customer: Project Name: 210331  
Lot/Block:  
Address:  
City:

Model:  
Subdivision:  
State:

**General Truss Engineering Criteria & Design Loads (Individual Truss Design Drawings Show Special Loading Conditions):**

Design Code: IRC2018/TPI2014  
Wind Code: N/A  
Roof Load: 45.0 psf


Design Program: MiTek 20/20 8.4  
Wind Speed: 115 mph  
Floor Load: N/A psf

This package includes 111 individual, dated Truss Design Drawings and 0 Additional Drawings.

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
1	I45167659	A1	3/12/2021	21	I45167679	C10	3/12/2021
2	I45167660	A2	3/12/2021	22	I45167680	D1	3/12/2021
3	I45167661	A3	3/12/2021	23	I45167681	D2	3/12/2021
4	I45167662	A4	3/12/2021	24	I45167682	D3	3/12/2021
5	I45167663	A5	3/12/2021	25	I45167683	D4	3/12/2021
6	I45167664	A6	3/12/2021	26	I45167684	E1	3/12/2021
7	I45167665	B1	3/12/2021	27	I45167685	E2	3/12/2021
8	I45167666	B2	3/12/2021	28	I45167686	E3	3/12/2021
9	I45167667	B3	3/12/2021	29	I45167687	E4	3/12/2021
10	I45167668	B4	3/12/2021	30	I45167688	E5	3/12/2021
11	I45167669	B5	3/12/2021	31	I45167689	G1	3/12/2021
12	I45167670	C1	3/12/2021	32	I45167690	G2	3/12/2021
13	I45167671	C2	3/12/2021	33	I45167691	G3	3/12/2021
14	I45167672	C3	3/12/2021	34	I45167692	G4	3/12/2021
15	I45167673	C4	3/12/2021	35	I45167693	G5	3/12/2021
16	I45167674	C5	3/12/2021	36	I45167694	G6	3/12/2021
17	I45167675	C6	3/12/2021	37	I45167695	G7	3/12/2021
18	I45167676	C7	3/12/2021	38	I45167696	G8	3/12/2021
19	I45167677	C8	3/12/2021	39	I45167697	G9	3/12/2021
20	I45167678	C9	3/12/2021	40	I45167698	G10	3/12/2021

The truss drawing(s) referenced above have been prepared by MiTek USA, Inc under my direct supervision based on the parameters provided by Wheeler - Waverly. Truss Design Engineer's Name: Garcia, Juan My license renewal date for the state of Missouri is December 31, 2022. Missouri COA: 001193

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek. Any project specific information included is for MiTek customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.



March 12, 2021



**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI**

**04/06/2021**

RE: 210331 - Lot 102 RR

MiTek USA, Inc.  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017  
314-434-1200

**Site Information:**

Project Customer:    Project Name: 210331  
Lot/Block:  
Address:  
City, County:

Subdivision:

State:

No.	Seal#	Truss Name	Date	No.	Seal#	Truss Name	Date
41	I45167699	H1	3/12/2021	85	I45167743	J41	3/12/2021
42	I45167700	H2	3/12/2021	86	I45167744	J42	3/12/2021
43	I45167701	H3	3/12/2021	87	I45167745	J43	3/12/2021
44	I45167702	H4	3/12/2021	88	I45167746	J44	3/12/2021
45	I45167703	J1	3/12/2021	89	I45167747	J45	3/12/2021
46	I45167704	J2	3/12/2021	90	I45167748	J46	3/12/2021
47	I45167705	J3	3/12/2021	91	I45167749	J47	3/12/2021
48	I45167706	J4	3/12/2021	92	I45167750	J48	3/12/2021
49	I45167707	J5	3/12/2021	93	I45167751	LAY1	3/12/2021
50	I45167708	J6	3/12/2021	94	I45167752	LAY2	3/12/2021
51	I45167709	J7	3/12/2021	95	I45167753	LAY3	3/12/2021
52	I45167710	J8	3/12/2021	96	I45167754	LAY4	3/12/2021
53	I45167711	J9	3/12/2021	97	I45167755	LAY5	3/12/2021
54	I45167712	J10	3/12/2021	98	I45167756	LAY6	3/12/2021
55	I45167713	J11	3/12/2021	99	I45167757	LAY7	3/12/2021
56	I45167714	J12	3/12/2021	100	I45167758	LAY8	3/12/2021
57	I45167715	J13	3/12/2021	101	I45167759	LAY9	3/12/2021
58	I45167716	J14	3/12/2021	102	I45167760	R1	3/12/2021
59	I45167717	J15	3/12/2021	103	I45167761	V1	3/12/2021
60	I45167718	J16	3/12/2021	104	I45167762	V2	3/12/2021
61	I45167719	J17	3/12/2021	105	I45167763	V3	3/12/2021
62	I45167720	J18	3/12/2021	106	I45167764	V4	3/12/2021
63	I45167721	J19	3/12/2021	107	I45167765	V5	3/12/2021
64	I45167722	J20	3/12/2021	108	I45167766	V6	3/12/2021
65	I45167723	J21	3/12/2021	109	I45167767	V7	3/12/2021
66	I45167724	J22	3/12/2021	110	I45167768	V8	3/12/2021
67	I45167725	J23	3/12/2021	111	I45167769	V9	3/12/2021
68	I45167726	J24	3/12/2021				
69	I45167727	J25	3/12/2021				
70	I45167728	J26	3/12/2021				
71	I45167729	J27	3/12/2021				
72	I45167730	J28	3/12/2021				
73	I45167731	J29	3/12/2021				
74	I45167732	J30	3/12/2021				
75	I45167733	J31	3/12/2021				
76	I45167734	J32	3/12/2021				
77	I45167735	J33	3/12/2021				
78	I45167736	J34	3/12/2021				
79	I45167737	J35	3/12/2021				
80	I45167738	J36	3/12/2021				
81	I45167739	J37	3/12/2021				
82	I45167740	J38	3/12/2021				
83	I45167741	J39	3/12/2021				
84	I45167742	J40	3/12/2021				

Job 210331	Truss A1	Truss Type Half Hip Supported	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------------------	----------	----------	------------

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW**

J45167659

**DEVELOPMENT SERVICES**

**LEIF SUMMIT MISSOURI**

04/06/2021

Scale = 1:57.6

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-3802-01

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-9KxOPZMcUIMh\_wWuTt\_XZOC3LJ9dJo3Q5qifzbrX

0-10-8 22-0-5  
0-10-8 22-0-5

27-5-0  
5-4-11




Plate Offsets (X,Y)-- [9:0-3-8,0-3-0], [16:Edge,0-1-8], [17:Edge,0-1-8], [23:0-3-8,0-3-0]


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.40	Vert(LL)	-0.00	1	n/r	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	-0.00	1	n/r		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.15	Horz(CT)	-0.01	17	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						
								Weight: 160 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 13-16.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SPF No.2	WEBS 6-0-0 oc bracing: 23-24.
OTHERS 2x4 SPF No.2	1 Row at midpt 16-17, 13-20, 12-21, 14-19, 15-18
WEDGE Left: 2x3 SPF No.2	

**REACTIONS.** All bearings 27-5-0.  
 (lb) - Max Horz 2=410(LC 5)  
 Max Uplift All uplift 100 lb or less at joint(s) 17, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 19, 18  
 Max Grav All reactions 250 lb or less at joint(s) 17, 2, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 19, 18

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-364/37, 3-4=-315/30, 4-5=-291/28, 5-6=-266/25

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - Provide adequate drainage to prevent water ponding.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable requires continuous bottom chord bearing.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 17, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 19, 18.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	A2	Half Hip	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEAF SUMMIT MISSOURI**

J45162660

04/06/2021

Scale = 1:59.1

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-dWVmcvNEF3UYb4540bVD3nxIXeMYExI4qOF5zbrW




Plate Offsets (X, Y)--	[8:Edge,0-1-8]
------------------------	----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.74	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.60	Vert(LL) -0.25 10-12 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.64	Vert(CT) -0.44 10-12 >737 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.05 9 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.08 12 >999 240	Weight: 124 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF 2100F 1.8E  
WEBS 2x3 SPF No.2 \*Except\*  
8-9,7-10,7-9: 2x4 SPF No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-0-1 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 7-8.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
WEBS 1 Row at midpt 8-9, 4-10, 6-10, 7-9

**WEDGE**  
Left: 2x4 SPF No.2

**REACTIONS.** (size) 9=Mechanical, 2=0-3-8  
Max Horz 2=438(LC 5)  
Max Uplift 9=-206(LC 8), 2=-209(LC 8)  
Max Grav 9=1339(LC 2), 2=1351(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-2487/397, 3-4=-2228/319, 4-6=-1137/207, 6-7=-1098/296  
BOT CHORD 2-12=-509/2212, 10-12=-296/1549, 9-10=-144/407  
WEBS 3-12=-392/245, 4-12=-35/718, 4-10=-817/277, 6-10=-342/185, 7-10=-296/1386, 7-9=-1172/225

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=206, 2=209.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job 210331	Truss A3	Truss Type Half Hip	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)




Plate Offsets (X, Y)--	[3:0-1-6,Edge], [6:0-3-8,Edge], [9:Edge,0-3-8]
------------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.96	Vert(LL)	-0.36	3-14	>909	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.69	Vert(CT)	-0.63	3-14	>518		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.95	Horz(CT)	0.36	10	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.30	3-14	>999	Weight: 153 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 1-6: 2x6 SP 2400F 2.0E	TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.); 8-9.
BOT CHORD 2x4 SPF No.2 *Except* 3-13: 2x4 SPF 2100F 1.8E, 5-12: 2x3 SPF No.2	BOT CHORD Rigid ceiling directly applied or 9-4-4 oc bracing.
WEBS 2x3 SPF No.2 *Except* 9-10,3-15,8-11,8-10: 2x4 SPF No.2	WEBS 1 Row at midpt 9-10, 4-13, 7-11, 8-10

<b>REACTIONS.</b>	(size) 10=Mechanical, 2=0-3-8 Max Horz 2=470(LC 5) Max Uplift 10=-237(LC 8), 2=-207(LC 8) Max Grav 10=1317(LC 2), 2=1324(LC 2)
-------------------	---

<b>FORCES.</b>	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-871/0, 3-4=-3439/567, 4-5=-2051/337, 5-7=-1994/441, 7-8=-1089/318
BOT CHORD	3-14=-695/3302, 13-14=-694/3302, 5-13=-335/193
WEBS	4-14=0/269, 4-13=-1586/384, 11-13=-149/919, 7-13=-349/1380, 7-11=-1145/407, 8-11=-350/1443, 8-10=-1144/247

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=237, 2=207.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	A4	Half Hip	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 3055081**  
**04/06/2021**

J45167662

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 20061039255081  
 ID:Ej7EWovY\_94Pzt7UVy1gWAz\_l70-audW1bPungkFrNET8?Yh9C0aWZB5qPJElOUVJ\_zbkrU  
 0-10-8 2-3-8 7-1-13 13-4-0 19-1-14 26-9-14 27-5-0  
 0-10-8 2-3-8 4-10-5 6-2-4 5-9-14 7-8-1 0-7-2  
 3x4 = Scale = 1:71.0




Plate Offsets (X, Y)-- [3:0-1-6,Edge], [6:0-4-6,Edge], [8:0-2-0,Edge], [9:Edge,0-1-8], [11:0-2-8,0-1-8]


<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.96	Vert(LL)	-0.35 3-14	>919	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.73	Vert(CT)	-0.62 3-14	>525	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.83	Horz(CT)	0.36 10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.33 3-14	>986	240	Weight: 141 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2 *Except* 1-6: 2x6 SP 2400F 2.0E	TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 8-9.
BOT CHORD 2x4 SPF No.2 *Except* 3-13: 2x4 SPF 2100F 1.8E, 5-12: 2x3 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 9-10,3-15,7-10: 2x4 SPF No.2	WEBS 1 Row at midpt 9-10, 4-13, 7-10

**REACTIONS.** (size) 10=Mechanical, 2=0-3-8  
 Max Horz 2=470(LC 8)  
 Max Uplift 10=317(LC 8), 2=155(LC 8)  
 Max Grav 10=1305(LC 2), 2=1329(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed;  
 MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip  
 DOL=1.60  
 TOP CHORD 2-3=-708/0, 3-4=-3463/508, 4-5=-2058/232, 5-7=-1982/322  
 BOT CHORD 3-14=-893/3326, 13-14=-893/3326, 5-13=-277/161, 10-11=-243/965  
 WEBS 4-14=0/268, 4-13=-1608/446, 11-13=-220/951, 7-13=-366/1340, 7-11=0/303,  
 7-10=-1354/341

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=317, 2=155.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	A5	Monopitch	4	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45167663

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID: Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-25BvFwQ6Y\_s6SXprij3whPZIFyXKZswO\_232rQzbrT



Scale = 1:69.7




Plate Offsets (X, Y)--	[3:0-1-6,Edge], [6:0-3-8,Edge], [10:0-2-8,0-1-8]
------------------------	--


<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.96	Vert(LL)	-0.35	3-13	>920	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.73	Vert(CT)	-0.62	3-13	>525		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.84	Horz(CT)	0.36	9	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.33	3-13	>985		
								Weight: 142 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2 *Except* 1-6: 2x6 SP 2400F 2.0E	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SPF No.2 *Except* 3-12: 2x4 SPF 2100F 1.8E, 5-11: 2x3 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 8-9,3-14,7-9: 2x4 SPF No.2	WEBS 1 Row at midpt 8-9, 4-12, 7-9

**REACTIONS.** (size) 9=Mechanical, 2=0-3-8  
Max Horz 2=481(LC 8)  
Max Uplift 9=329(LC 8), 2=150(LC 8)  
Max Grav 9=1304(LC 2), 2=1329(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-714/0, 3-4=-3462/497, 4-5=-2057/220, 5-7=-1980/309  
BOT CHORD 3-13=-895/3326, 12-13=-895/3325, 5-12=-273/159, 9-10=-245/966  
WEBS 4-13=0/268, 4-12=-1610/448, 10-12=-221/952, 7-12=-364/1336, 7-10=0/302,  
7-9=-1359/344

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=329, 2=150.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	A6	Monopitch	1	1	


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUMMIT MISSOURI**

J45167664

04/06/2021

Scale = 1:65.4

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Lot 102 RR  
 ID: EJE7EWovY\_94Pzt7UVy1gWAz\_t70-25BvFw06Y\_s6SXprij3whPZoVyZTZsQO\_232rQzbrT



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.82	Vert(LL)	-0.26 9-11	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.59	Vert(CT)	-0.45 9-11	>720	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.87	Horz(CT)	0.06 8	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.08 9-11	>999	240		
								Weight: 115 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF 2100F 1.8E  
 WEBS 2x3 SPF No.2 \*Except\*  
 7-8,6-8: 2x4 SPF No.2


**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 2-8-1 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 9-7-10 oc bracing.  
 WEBS 1 Row at midpt 7-8, 4-9, 6-8

**WEDGE**  
 Left: 2x4 SPF No.2

**REACTIONS.** (size) 8=Mechanical, 2=0-3-8  
 Max Horz 2=478(LC 8)  
 Max Uplift 8=-329(LC 8), 2=-150(LC 8)  
 Max Grav 8=1329(LC 2), 2=1354(LC 2)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-2502/266, 3-4=-2238/181, 4-6=-1142/65  
 BOT CHORD 2-11=-656/2227, 9-11=-423/1549, 8-9=-239/1001  
 WEBS 3-11=-407/260, 4-11=-51/728, 4-9=-766/256, 6-9=-56/968, 6-8=-1411/336

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=329, 2=150.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	B1	Monopitch	7	1	

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEIF SUMMIT WBS COURT**  
**04/06/2021**

J45167665




Plate Offsets (X,Y)--	[1:Edge,0-2-12], [4:0-1-11,Edge]
-----------------------	----------------------------------


LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.60	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.42	Vert(LL) -0.07 7-8 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.88	Vert(CT) -0.13 8-9 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.03 5 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.05 7-8 >999 240	Weight: 66 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-7-5 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 9=0-3-8, 5=Mechanical  
 Max Horz 9=231(LC 5)  
 Max Uplift 5=-89(LC 8)  
 Max Grav 9=774(LC 1), 5=774(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-9=-732/83, 1-2=-1484/118, 2-3=-1430/133, 4-5=-702/54  
 BOT CHORD 7-8=-256/1428, 6-7=-196/1372  
 WEBS 1-8=-68/1258, 2-8=-402/105, 3-6=-1138/181, 4-6=-10/575

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	B2	Half Hip	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 2050481**  
**04/06/2021**

J45167666

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 2068042050481

ID: EJEVovY\_94Pzt7UVy1gWAZ\_t70\_TifgcRN4b6qirz1p85OmqeBKmly1shhRMY9wJzbrR

Job Reference (optional)





Plate Offsets (X, Y)--	[1:Edge,0-2-12]				
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc) l/defl L/d
TCLL 25.0	Plate Grip DOL	1.15	TC 0.54	Vert(LL) -0.07	8-9 >999 360
TCDL 10.0	Lumber DOL	1.15	BC 0.40	Vert(CT) -0.13	9-10 >999 240
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.44	Horz(CT) 0.02	6 n/a n/a
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL) 0.05	8-9 >999 240
					<b>PLATES</b> MT20
					<b>GRIP</b> 197/144
					Weight: 67 lb FT = 10%

<b>LUMBER-</b>		<b>BRACING-</b>	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 3-9-12 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD	2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x3 SPF No.2		

**REACTIONS.** (size) 10=0-3-8, 6=Mechanical  
 Max Horz 10=211(LC 5)  
 Max Uplift 6=-74(LC 8)  
 Max Grav 10=774(LC 1), 6=774(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-10=-731/84, 1-2=-1490/121, 2-3=-1405/129, 3-4=-1386/188, 5-6=-750/43  
 BOT CHORD 8-9=-251/1435, 7-8=-54/393  
 WEBS 1-9=-71/1266, 2-9=-404/106, 3-8=-320/101, 4-8=-176/1213, 4-7=-606/110, 5-7=-52/766

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6.
  - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	B3	Half Hip	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT #550481**  
**04/06/2021**

J45167667

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-Sgs1tyS?rvEhJ?YENrcdJ2BMPAeDmJwqg0HiSizbkrQ




Plate Offsets (X,Y)--	[1:Edge,0-2-12]
-----------------------	-----------------



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.52	Vert(LL)	-0.06	8-9	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.39	Vert(CT)	-0.13	9-10	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.44	Horz(CT)	0.03	6	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.06	8-9	>999	Weight: 65 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-10-9 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 8-3-6 oc bracing: 8-9.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 10=0-3-8, 6=Mechanical  
 Max Horz 10=239(LC 5)  
 Max Uplift 10=-79(LC 8), 6=-162(LC 8)  
 Max Grav 10=774(LC 1), 6=774(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-10=-731/194, 1-2=-1492/325, 2-3=-1396/319, 3-4=-1352/384, 5-6=-747/117  
 BOT CHORD 8-9=-503/1439, 7-8=-209/781  
 WEBS 1-9=-248/1269, 2-9=-407/181, 3-8=-254/138, 4-8=-254/806, 4-7=-597/195, 5-7=-107/674

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10 except (jt=lb) 6=162.
  - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss B4	Truss Type Half Hip	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**

J45167668

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068040550181

ID: EJEWovY\_94Pzt7UVy1gWAZ\_t70-wsQP4ITdcCMYx87QxZ7ssFkXaacvIzzvg1F\_BzbkrP




Plate Offsets (X,Y)--	[1:0-2-0,0-1-8]
-----------------------	-----------------


LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.56	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.45	Vert(LL) -0.07 7-8 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.45	Vert(CT) -0.14 7-8 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.03 5 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.06 7-8 >999 240	Weight: 63 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-0-15 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 8-4-12 oc bracing: 7-8.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 9=0-3-8, 5=Mechanical  
 Max Horz 9=211(LC 5)  
 Max Uplift 9=-80(LC 8), 5=-133(LC 8)  
 Max Grav 9=774(LC 1), 5=774(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-9=-732/187, 1-2=-1524/320, 2-3=-1282/242, 3-4=-377/67, 4-5=-703/116  
 BOT CHORD 7-8=-489/1480, 6-7=-275/1190  
 WEBS 1-8=-247/1308, 2-8=-405/192, 3-7=-8/290, 3-6=-730/196, 4-6=-114/630

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9 except (jt=lb) 5=133.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss B5	Truss Type GABLE	Qty 1	Ply 2	Lot 102 RR
---------------	-------------	---------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEIF SUMMIT, MISSOURI**  
**04/06/2021**

J45167669

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 20068040550181  
 ID: E|7EWovY\_94Pzt7UVy1gWAZ\_170-O2\_oleTFNWUPZlicUGe5OTgmuzLbECV78KmpXdzbrO




Plate Offsets (X, Y)-- [6:0-3-8,0-4-0], [7:0-3-8,0-4-0], [11:0-1-8,0-1-0], [12:0-1-1,0-0-8], [13:0-1-8,0-1-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.26	Vert(LL)	-0.05	7-8	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.27	Vert(CT)	-0.08	7-8	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.49	Horz(CT)	0.01	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.03	7-8	>999		
								Weight: 296 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD 2x6 SP 2400F 2.0E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	WEBS 1 Row at midpt 4-5, 3-5
OTHERS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-0, 8=Mechanical  
 Max Horz 8=342(LC 5)  
 Max Uplift 5=-393(LC 5), 8=-318(LC 8)  
 Max Grav 5=3309(LC 1), 8=3182(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-2764/287, 2-3=-1902/249, 1-8=-2603/299  
 BOT CHORD 7-8=-324/90, 6-7=-395/2485, 5-6=-264/1632  
 WEBS 2-7=-130/866, 2-6=-1152/209, 3-6=-262/2789, 3-5=-2946/341, 1-7=-248/2779

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
 Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.  
 Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
 Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
  - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
  - Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
  - Provide adequate drainage to prevent water ponding.
  - All plates are 2x4 MT20 unless otherwise indicated.
  - Gable studs spaced at 2-0-0 oc.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=393, 8=318.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss B5	Truss Type GABLE	Qty 1	Ply 2	Lot 102 RR	<b>RELEASE FOR CONSTRUCTION</b> <b>AS NOTED ON PLANS REVIEW</b> <b>DEVELOPMENT SERVICES</b> <b>LEFLO SUMMIT, MISSOURI</b> <b>04/06/2021</b>
Wheeler Lumber, Waverly, KS - 66871,		8.430 s Feb 12 2021 MiTek Industries, Inc. 16023 Swingley Ridge Rd Chesterfield, MO 63017			Job Reference (optional)	

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-O2\_oleTFNWUPZlicUGe5OTGmuzLbECV78KmpXdzbnkro

- NOTES-**
- 15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 619 lb down and 59 lb up at 2-0-0, 619 lb down and 63 lb up at 4-0-0, 619 lb down and 63 lb up at 6-0-0, 619 lb down and 63 lb up at 8-0-0, 619 lb down and 63 lb up at 10-0-0, 619 lb down and 63 lb up at 12-0-0, and 619 lb down and 63 lb up at 14-0-0, and 619 lb down and 63 lb up at 16-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 16) Studding applied to ply: 1(Front)

- LOAD CASE(S)** Standard
- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
  - Uniform Loads (plf)
    - Vert: 1-3=-70, 3-4=-70, 5-8=-20
  - Concentrated Loads (lb)
    - Vert: 7=-619(B) 6=-619(B) 26=-619(B) 27=-619(B) 28=-619(B) 29=-619(B) 30=-619(B) 32=-619(B)



Job 210331	Truss C1	Truss Type HALF HIP GIRDER	Qty 1	Ply <b>2</b>	Lot 102 RR
---------------	-------------	-------------------------------	----------	-----------------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 200804705 Page 2

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-LR6YjKVWv7k7ocs?chhZTuM?EnvKi7JQbeFwbWzbrM

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEO SUMMIT, MISSOURI**  
**04/06/2021**

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)
  - Vert: 1-4=-70, 4-6=-70, 2-13=-20, 3-10=-20, 7-8=-20
- Concentrated Loads (lb)
  - Vert: 10=-230(F) 12=-449(F) 14=-230(F) 15=-230(F) 16=-230(F)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	C2	Half Hip	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45162671  
 16952  
 04/08/2021

LEED SUBMIT 1650481

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. 16952  
 ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-pdgwwgW8gRs\_QmRBAOC0o5uAwBGSRXcZq!7T7yZbkrL  
 13-8-8 4-6-7 16-0-0 2-3-8  
 Scale = 1:30.8




Plate Offsets (X, Y)-- [3:0-0-11,0-0-15], [5:Edge,0-2-8], [8:0-3-8,0-1-8]



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.72	Vert(LL)	-0.28 3-10	>670	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.71	Vert(CT)	-0.55 3-10	>342	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.60	Horz(CT)	0.32 6	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.24 3-10	>789	240	Weight: 61 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x6 SPF 1650F 1.4E *Except* 4-5: 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-7-1 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD 2x4 SPF No.2 *Except* 7-9: 2x3 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 6-7.
WEBS 2x3 SPF No.2 *Except* 3-11,2-12: 2x4 SPF No.2	WEBS 1 Row at midpt 4-8

**REACTIONS.** (size) 6=0-3-8, 12=0-3-8  
 Max Horz 12=166(LC 5)  
 Max Uplift 6=-134(LC 4), 12=-216(LC 4)  
 Max Grav 6=700(LC 1), 12=859(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-263/11, 3-4=-1296/218, 6-8=-673/147, 2-12=-857/235  
 BOT CHORD 3-10=-212/1223, 9-10=-207/1229, 8-9=-215/1232  
 WEBS 4-10=0/317, 4-8=-1250/226

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=134, 12=216.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017



Job 210331	Truss C3	Truss Type Half Hip Girder	Qty 1	Ply <b>2</b>	Lot 102 RR
---------------	-------------	-------------------------------	----------	-----------------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 2008050250 Page 2

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-10nhLLXOB26if3aaHpEG5W\_cm\_\_TvXMsHcUaCrzbrk

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEWIS & CLARK MISSOURI  
04/06/2021**

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
- Uniform Loads (plf)
  - Vert: 1-2=-70, 2-4=-70, 4-6=-70, 9-11=-20, 7-8=-20
- Concentrated Loads (lb)
  - Vert: 12=-3162(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


**RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES**

Job 210331	Truss C4	Truss Type Half Hip	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. Ma

LEED SUBMIT 10/25/2021



Scale = 1:34.4




Plate Offsets (X, Y)--	[3:0-5-7,0-0-10]
------------------------	------------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.87	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.61	Vert(LL) -0.19 3-8 >888 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.58	Vert(CT) -0.38 3-8 >461 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.21 7 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.13 3-8 >999 240	Weight: 62 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x6 SPF No.2 *Except* 5-6: 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 3-9,2-10: 2x4 SPF No.2	WEBS 1 Row at midpt 4-7

**REACTIONS.** (size) 7=Mechanical, 10=0-3-8  
 Max Horz 10=168(LC 5)  
 Max Uplift 7=-39(LC 8), 10=-86(LC 4)  
 Max Grav 7=639(LC 1), 10=800(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-266/0, 3-4=-1338/61, 2-10=-795/103  
 BOT CHORD 3-8=-76/1271, 7-8=-75/1270  
 WEBS 4-8=0/287, 4-7=-1314/110

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 10.
  - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	C5	Monopitch	7	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEAD SUBMIT 5/15/2021**  
**04/06/2021**

J45162674

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Lot 102 RR  
 ID:Ej7EWovY\_94PztUVy1gWAZ\_170-hPvRm1ZeigNPuNkyPEHkAx3qhofwNLk9lwzhGjzbrH  
 Job Reference (optional) 14-8-0 6-5-11



Scale = 1:32.7




Plate Offsets (X,Y)--	[3:0-5-7,0-0-10]
-----------------------	------------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.87	Vert(LL)	-0.19	3-7	>894	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.61	Vert(CT)	-0.37	3-7	>463		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.59	Horz(CT)	0.21	6	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.13	3-7	>999	Weight: 59 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 3-8,2-9: 2x4 SPF No.2	WEBS 1 Row at midpt 4-6

**REACTIONS.** (size) 6=Mechanical, 9=0-3-8  
 Max Horz 9=174(LC 5)  
 Max Uplift 6=-43(LC 8), 9=-86(LC 4)  
 Max Grav 6=639(LC 1), 9=800(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-271/0, 3-4=-1347/62, 2-9=-795/102  
 BOT CHORD 3-7=-79/1281, 6-7=-78/1280  
 WEBS 4-7=0/287, 4-6=-1345/118

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 9.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	C6	Monopitch	3	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK MISSOURI**  
**04/06/2021**

J45162675

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional) 14-8-0 6-5-11




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.88	Vert(LL)	-0.09 6-7	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.46	Vert(CT)	-0.18 6-7	>934	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.43	Horz(CT)	0.02 5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.03 5-6	>999	240	Weight: 50 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 2-7: 2x6 SPF No.2	WEBS 1 Row at midpt 3-5

**REACTIONS.** (size) 5=Mechanical, 7=0-3-8  
 Max Horz 7=190(LC 5)  
 Max Uplift 5=-43(LC 8), 7=-89(LC 4)  
 Max Grav 5=634(LC 1), 7=803(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-928/38, 2-7=-715/134  
 BOT CHORD 6-7=-49/789, 5-6=-49/789  
 WEBS 3-6=0/317, 3-5=-873/89

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 7.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss C7	Truss Type Monopitch	Qty 5	Ply 1	Lot 102 RR
---------------	-------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162676

Scale = 1:17.5

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 200680540550181  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-dn1BBjavFHd78huLWfJCGM8IAcR2rOSSCESnLczbkrF




Plate Offsets (X, Y)--	[5:0-5-6,0-1-8]
------------------------	-----------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.36	Vert(LL)	-0.04	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.25	Vert(CT)	-0.08	4-5	>846		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999	Weight: 18 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-10-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 3-4: 2x3 SPF No.2	

**REACTIONS.** (size) 4=Mechanical, 5=0-3-8  
 Max Horz 5=120(LC 5)  
 Max Uplift 4=-49(LC 8), 5=-138(LC 4)  
 Max Grav 4=226(LC 1), 5=418(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-370/176

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=138.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss C8	Truss Type Half Hip	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT MISSOURI**  
 04/06/2021

J45162677

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-540550-01

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-dn1BBjavFHd78huLWfJCGM8AkcnkrJxSCESnLczbkrF



6x6 = 2x4 || Scale: 3/8"=1'




Plate Offsets (X,Y)-- [7:0-2-8,0-1-8]

<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.90	Vert(LL) -0.09 7-8 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.46	Vert(CT) -0.18 7-8 >933 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.35	Horz(CT) 0.01 6 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Wind(LL) 0.03 6-7 >999 240	Weight: 52 lb	FT = 10%


**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 2-8: 2x6 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 6=Mechanical, 8=0-3-8  
 Max Horz 8=220(LC 5)  
 Max Uplift 6=-129(LC 4), 8=-201(LC 4)  
 Max Grav 6=634(LC 1), 8=803(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-913/142, 3-4=-873/232, 2-8=-718/247  
 BOT CHORD 7-8=-141/772  
 WEBS 3-7=-439/240, 4-7=-210/826, 4-6=-573/133

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=129, 8=201.
  - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	C9	Roof Special	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK UNIVERSITY**  
**LEWIS & CLARK UNIVERSITY**  
**04/06/2021**

J45162678

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. ID: Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-6\_ba03bX0al\_rTX4MqRoahMd?gOan2bRuBLt2zkrE




Plate Offsets (X,Y)--	[2:0-0-8,0-1-8]									
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in	(loc)	l/defl	<b>L/d</b>	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15		TC 0.82	Vert(LL) -0.09	8-9	>999	360		MT20	197/144
TCDL 10.0	Lumber DOL 1.15		BC 0.69	Vert(CT) -0.16	8-9	>999	240			
BCLL 0.0 *	Rep Stress Incr YES		WB 0.30	Horz(CT) 0.02	7	n/a	n/a			
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL) 0.07	8-9	>999	240		Weight: 58 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2 *Except* 5-6: 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-2-2 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 2-10: 2x6 SP DSS	

**REACTIONS.** (size) 7=Mechanical, 10=0-3-8  
 Max Horz 10=203(LC 5)  
 Max Uplift 7=-130(LC 8), 10=-204(LC 4)  
 Max Grav 7=634(LC 1), 10=803(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-998/169, 3-4=-584/119, 4-5=-522/138, 2-10=-697/219  
 BOT CHORD 9-10=-180/869, 8-9=-180/869  
 WEBS 3-8=-385/126, 5-8=-110/563, 5-7=-600/144

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=130, 10=204.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss C10	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-----------------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUBMIT MISSOURI**  
**04/06/2021**

J45162679

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File Name: 210331.dwg

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-pdgwwgW8gRs\_QmRBAOC005u7dBH\_RUWZq!T7yZbkrL




Plate Offsets (X,Y)--	[7:0-2-8,0-4-4], [8:0-5-4,0-4-0]
-----------------------	----------------------------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.94	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.68	Vert(LL) -0.15 6-7 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.80	Vert(CT) -0.27 6-7 >629 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-S	Horz(CT) 0.02 6 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.14 6-7 >999 240	Weight: 60 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 1-3: 2x4 SPF 2100F 1.8E	TOP CHORD Structural wood sheathing directly applied or 3-8-6 oc purlins, except end verticals, and 2-0-0 oc purlins (4-3-13 max.): 3-4.
BOT CHORD 2x6 SPF 1650F 1.4E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 2-8: 2x10 SP DSS	

**REACTIONS.** (size) 6=Mechanical, 8=0-3-8  
Max Horz 8=204(LC 22)  
Max Uplift 6=-381(LC 8), 8=-345(LC 4)  
Max Grav 6=1404(LC 1), 8=1219(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-1995/494, 3-4=-1781/498, 2-8=-1098/378  
BOT CHORD 7-8=-464/1791, 6-7=-284/1107  
WEBS 3-7=-113/352, 4-7=-252/942, 4-6=-1415/419

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Provide adequate drainage to prevent water ponding.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=381, 8=345.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 503 lb down and 181 lb up at 7-11-1, 211 lb down and 76 lb up at 8-11-13, and 238 lb down and 83 lb up at 10-11-4, and 238 lb down and 83 lb up at 12-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-5=-70, 6-8=-20



March 12, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss C10	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-----------------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File Path: \\068014050182

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-pdgwwgW8gRs\_QmRBAOC005u7dBH\_RUWZql?T7ybkrl

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEAD SUBMITTER SOURCE  
04/06/2021**

**LOAD CASE(S)** Standard

Concentrated Loads (lb)

Vert: 7=-503(B) 9=-211(B) 10=-238(B) 11=-238(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss D1	Truss Type Hip Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	--------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS SUBJECT**

J45162680

04/06/2021

Scale = 1:28.9

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-aA9ycPc9nutrN\_2ke4LgLnDYtPxJJHRkfYxuPVzbrkD




Plate Offsets (X, Y)--	[4:0-3-8,0-2-5], [5:0-4-4,0-2-8]
------------------------	----------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.73	Vert(LL)	-0.15	9-10	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.90	Vert(CT)	-0.27	9-10	>570		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.10	Horz(CT)	0.02	8	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.14	9-10	>999	Weight: 46 lb	FT = 10%


LUMBER-	BRACING-
TOP CHORD 2x4 SPF 2100F 1.8E *Except* 4-5: 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-6-6 oc purlins, except end verticals, and 2-0-0 oc purlins (5-4-8 max.): 4-5.
BOT CHORD 2x4 SPF 2100F 1.8E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 2-12,6-8: 2x6 SP DSS	

**REACTIONS.** (size) 8=0-3-8, 11=0-3-8  
 Max Horz 11=22(LC 8)  
 Max Uplift 8=-269(LC 5), 11=-303(LC 4)  
 Max Grav 8=927(LC 1), 11=1021(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-982/207, 3-4=-1107/265, 4-5=-971/258, 5-6=-1259/292, 2-12=-370/71, 6-8=-813/284  
 BOT CHORD 11-12=-181/963, 10-11=-165/963, 9-10=-196/1118, 8-9=-196/1105  
 WEBS 5-9=-23/307, 3-11=-432/212

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 8=269, 11=303.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 79 lb down and 64 lb up at 7-0-0 on top chord, and 197 lb down and 86 lb up at 5-5-1, and 27 lb down at 7-0-0, and 197 lb down and 86 lb up at 8-6-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



March 12, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss D1	Truss Type Hip Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	--------------------------	----------	----------	------------

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW**

J45167680

**DEVELOPMENT SERVICES**

**LEAD SUBMITTER SOURCE**

**04/06/2021**

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210680.56 Page 1  
ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-aA9ycPc9nutrN\_2ke4LgLnDYtPxJJHRkfYxuPVzbrD

**LOAD CASE(S)** Standard

Uniform Loads (plf)

Vert: 1-2=-70, 2-4=-70, 4-5=-70, 5-6=-70, 6-7=-70, 8-12=-20

Concentrated Loads (lb)

Vert: 10=-197(F) 9=-197(F) 13=-28(F) 14=-12(F)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601





16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	D2	Common	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT MISSOURI**  
**04/06/2021**

J45167681




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.74	Vert(LL)	-0.10	5-6	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.55	Vert(CT)	-0.20	5-6	>760		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.01	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.06	5-6	>999		
								Weight: 38 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-6-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x6 SPF No.2 *Except* 2-6: 2x3 SPF No.2	

**REACTIONS.** (size) 7=0-3-8, 5=0-3-8  
 Max Horz 7=-46(LC 5)  
 Max Uplift 7=-81(LC 4), 5=-181(LC 5)  
 Max Grav 7=565(LC 1), 5=737(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-744/98, 2-3=-756/104, 1-7=-462/113, 3-5=-646/220  
 BOT CHORD 6-7=-26/630, 5-6=-26/630

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7 except (jt=lb) 5=181.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021



Job 210331	Truss D4	Truss Type Common	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

J45167683  
LEF0-SUMMIT-MS-0481  
04/06/2021  
Scale = 1:21.4




Plate Offsets (X,Y)--	[3:0-3-11,0-0-0]
-----------------------	------------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.59	Vert(LL)	-0.06	5-6	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.31	Vert(CT)	-0.14	5-6	>594		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.05	5-6	>999	Weight: 22 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 1-6: 2x4 SPF No.2	

**REACTIONS.** (size) 6=Mechanical, 4=0-3-8  
 Max Horz 6=99(LC 5)  
 Max Uplift 6=-51(LC 4), 4=-52(LC 4)  
 Max Grav 6=317(LC 1), 4=317(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 4.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.




March 12, 2021

Job 210331	Truss E1	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-----------------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK UNIVERSITY**  
 04/09/2021  
 Scale = 1:49.5

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70-OKWDsShwNkd?5vVt\_LS5a2TbMq1kjod2TOCd8zbr7  
 1-0-5 6-10-1 12-9-1 18-6-13 21-1-3 25-6-0 26-7-0 28-5-8  
 1-0-5 5-9-12 5-11-0 5-9-12 2-6-6 4-4-13 1-1-0 1-10-8



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.60	Vert(LL)	-0.16	14-15	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.77	Vert(CT)	-0.30	14-15	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.75	Horz(CT)	0.07	10	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.13	14	>999		
								Weight: 107 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2 \*Except\*  
 10-13: 2x6 SPF No.2  
 WEBS 2x3 SPF No.2


**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 3-8-14 oc purlins, except end verticals, and 2-0-0 oc purlins (3-5-10 max.): 2-5, 6-7.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.  
 WEBS 1 Row at midpt 6-11

**REACTIONS.** (size) 16=0-3-8, 10=0-3-8  
 Max Horz 16=-129(LC 6)  
 Max Uplift 16=-204(LC 5), 10=-360(LC 5)  
 Max Grav 16=1179(LC 1), 10=1255(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-2004/394, 3-4=-2002/392, 4-5=-2105/387, 5-6=-2323/409, 6-7=-483/114, 7-8=-546/130, 8-10=-1314/309  
 BOT CHORD 15-16=-61/357, 14-15=-454/2572, 12-14=-454/2573, 11-12=-437/2400  
 WEBS 2-15=-323/1872, 3-15=-450/181, 4-15=-645/123, 4-12=-698/157, 5-12=-57/607, 6-12=-360/147, 6-11=-2138/387, 2-16=-1215/298, 8-11=-182/1033

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 16=204, 10=360.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 29 lb down and 80 lb up at 25-6-0 on top chord, and 139 lb down and 746 lb up at 25-4-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15



March 12, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss E1	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-----------------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 16023 Swingley Ridge Rd Chesterfield, MO 63017

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70-OKWDsShwNkd?5vVt\_LS5a2TbMq1kjqod2TOCd8zbr7

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES**

J45167684

**LEAD SUBMITTER'S USE**

**04/06/2021**

**LOAD CASE(S)** Standard

Uniform Loads (plf)

Vert: 1-2=-70, 2-5=-70, 5-6=-70, 6-7=-70, 7-8=-70, 8-9=-70, 10-16=-20

Concentrated Loads (lb)

Vert: 7=22(F) 11=57(F)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

**ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss E2	Truss Type Roof Special	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45162685  
 LEFLO SUMMIT, MISSOURI  
 03/06/2021

Scale = 1:49.1




LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.79	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.65	Vert(LL) -0.13 11-13 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.50	Vert(CT) -0.25 11-13 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.06 9 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.10 11-13 >999 240	Weight: 104 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 4-5: 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-11-7 oc purlins, except end verticals, and 2-0-0 oc purlins (2-11-8 max.): 2-4, 5-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x3 SPF No.2	WEBS 1 Row at midpt 5-10

**REACTIONS.** (size) 15=0-3-8, 9=0-3-8  
 Max Horz 15=-130(LC 4)  
 Max Uplift 15=-176(LC 5), 9=-235(LC 5)  
 Max Grav 15=1182(LC 1), 9=1331(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-805/156, 2-3=-2037/394, 3-4=-2035/392, 4-5=-2124/357, 5-6=-968/154,  
 6-7=-1088/161, 1-15=-1185/178, 7-9=-1327/232  
 BOT CHORD 13-14=-96/753, 11-13=-278/1956, 10-11=-349/2207  
 WEBS 2-14=-728/202, 2-13=-263/1469, 3-13=-590/240, 4-13=-73/266, 4-11=-12/434,  
 5-11=-377/140, 5-10=-1448/270, 1-14=-167/1122, 7-10=-137/1202

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 15=176, 9=235.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job 210331	Truss E3	Truss Type Roof Special	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES**

J45167686

LEWIS & CLARK MISSOURI

04/06/2021

Scale = 1:49.3

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-pvBLVUjoff?oCh596157wAl3kRctETzbrk4

4-2-11 9-8-5 15-4-6 17-10-13 22-3-10 26-7-0  
4-2-11 5-5-10 5-8-2 2-6-6 4-4-13 4-3-6




Plate Offsets (X, Y)-- [1:0-2-0,0-1-8], [7:0-1-14,0-2-0], [9:Edge,0-2-8], [14:0-2-8,0-1-8]



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.44	Vert(LL)	-0.09	12-13	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.60	Vert(CT)	-0.20	10-12	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.80	Horz(CT)	0.05	9	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.07	12-13	>999		
								Weight: 108 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 4-5: 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-10-1 oc purlins, except end verticals, and 2-0-0 oc purlins (4-1-5 max.): 2-4, 5-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 15=0-3-8, 9=0-3-8  
 Max Horz 15=-128(LC 4)  
 Max Uplift 15=-153(LC 5), 9=-218(LC 5)  
 Max Grav 15=1182(LC 1), 9=1331(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-1053/187, 2-3=-1688/324, 3-4=-1686/323, 4-5=-1901/319, 5-6=-1203/194,  
 6-7=-1364/195, 1-15=-1149/173, 7-9=-1302/231  
 BOT CHORD 13-14=-105/944, 12-13=-222/1741, 10-12=-292/2005  
 WEBS 2-14=-539/151, 2-13=-171/991, 3-13=-465/186, 4-12=-42/485, 5-12=-446/154,  
 5-10=-1003/192, 6-10=0/264, 1-14=-147/1120, 7-10=-143/1304

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 15=153, 9=218.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job 210331	Truss E4	Truss Type Roof Special	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45167687  
 11/13/2021 10:55:01 AM  
 06/06/2021

Scale = 1:49.6




Plate Offsets (X,Y)--	[1:0-2-0,0-1-8], [2:0-4-3,Edge], [6:0-2-0,0-1-8], [8:Edge,0-2-8], [12:0-2-8,0-1-8]
-----------------------	--



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.74	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.88	Vert(LL) -0.24 9-11 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.97	Vert(CT) -0.50 9-11 >630 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.05 8 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.06 9-11 >999 240	Weight: 106 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except*	TOP CHORD Structural wood sheathing directly applied or 4-6-15 oc purlins, except end verticals, and 2-0-0 oc purlins (4-4-5 max.): 2-3, 4-5.
2-3: 2x4 SPF 2100F 1.8E, 3-4: 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 8-9.
BOT CHORD 2x4 SPF No.2	
WEBS 2x3 SPF No.2	

REACTIONS.
(size) 13=0-3-8, 8=0-3-8
Max Horz 13=-126(LC 4)
Max Uplift 13=-124(LC 5), 8=-206(LC 5)
Max Grav 13=1182(LC 1), 8=1331(LC 1)

FORCES.
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1221/188, 2-3=-1591/256, 3-4=-1784/248, 4-5=-998/117, 5-6=-1120/112, 1-13=-1134/152, 6-8=-1365/180
BOT CHORD 11-12=-93/1078, 9-11=-292/2188
WEBS 2-12=-390/142, 2-11=-94/681, 3-11=0/297, 4-11=-663/230, 4-9=-1391/256, 1-12=-129/1166, 6-9=-77/1246

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 13=124, 8=206.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021



Job 210331	Truss E5	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-----------------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068108 Page 2

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-DUtU7VihyaO8pry1LbZVqJjcJF5V7aWVQPPrXrozbk1

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEAD SUBMITTALS SUB  
04/06/2021**

J45167688

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-5=-70, 5-6=-70, 6-7=-70, 7-8=-70, 8-9=-70, 10-17=-20

Concentrated Loads (lb)

Vert: 7=22(B) 11=57(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017


Job 210331	Truss G1	Truss Type Half Hip Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45167689  
 LEED SUBMIT MISSOURI  
 04/06/2021

Scale = 1:46.0

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)  
 ID:EJ7EWovY\_94Pzt7UVy1gWAZ\_t70-9s?EYBnxUBes386QSOzbvkv72ihbTdoujKevhzbkr?



<b>LOADING</b> (psf)	<b>SPACING-</b>	<b>CSI.</b>	<b>DEFL.</b>	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	2-0-0	TC 0.87	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.96	Vert(LL) -0.30 10-11 >999 360	M18SHS	197/144
BCLL 0.0 *	Lumber DOL 1.15	WB 0.69	Vert(CT) -0.55 10-11 >551 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-S	Horz(CT) 0.09 6 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.26 10-11 >999 240	Weight: 124 lb	FT = 10%


**LUMBER-**  
 TOP CHORD 2x6 SPF No.2 \*Except\*  
 3-5: 2x6 SPF 1650F 1.4E  
 BOT CHORD 2x6 SPF No.2 \*Except\*  
 9-12: 2x6 SPF 1650F 1.4E  
 WEBS 2x4 SPF 2100F 1.8E \*Except\*  
 1-12: 2x4 SPF No.2, 2-11,4-10,5-8: 2x3 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 3-3-8 oc purlins, except end verticals, and 2-0-0 oc purlins (2-5-8 max.): 1-5.  
 BOT CHORD Rigid ceiling directly applied or 8-0-2 oc bracing.

**REACTIONS.** (size) 12=0-3-8, 6=0-3-8  
 Max Horz 12=-103(LC 27)  
 Max Uplift 12=-428(LC 4), 6=-397(LC 5)  
 Max Grav 12=2127(LC 1), 6=2050(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-12=-1963/487, 1-2=-4756/977, 2-4=-4756/977, 4-5=-6075/1252, 5-6=-4484/870  
 BOT CHORD 10-11=-1173/6072, 8-10=-743/4020, 6-8=-743/4045  
 WEBS 1-11=-985/4876, 2-11=-851/397, 4-11=-1389/297, 4-10=-469/304, 5-10=-455/2271, 5-8=-3/588

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - All plates are MT20 plates unless otherwise indicated.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 12=428, 6=397.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 115 lb down and 87 lb up at 0-9-8, 108 lb down and 90 lb up at 2-9-8, 108 lb down and 90 lb up at 4-9-8, 108 lb down and 90 lb up at 6-9-8, 108 lb down and 90 lb up at 8-9-8, 108 lb down and 90 lb up at 10-9-8, 108 lb down and 90 lb up at 12-9-8, 108 lb down and 90 lb up at 14-9-8, and 108 lb down and 90 lb up at 16-9-8, and 108 lb down and 90 lb up at 18-9-8 on top chord, and 74 lb down at 0-9-8, 67 lb down at 2-9-8, 67 lb down at 4-9-8, 67 lb down at 6-9-8, 67 lb down at 8-9-8, 67 lb down at 10-9-8, 67 lb down at 12-9-8, 67 lb down at 14-9-8, 67 lb down at 16-9-8, and 67 lb down at 18-9-8, and 354 lb down and 117 lb up at 20-2-3 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- On the CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss G1	Truss Type Half Hip Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 16023 Swingley Ridge Rd Chesterfield, MO 63017  
 ID:Ej7EWovY\_94Pzt7UVy1gWAz\_t70-e3ZdIXoZfVmjglhc0k6CSyL4tS2wKwsy6N3BR7zbr\_

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEAD SUBMIT MISSOURI  
**04/06/2021**

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-5=-70, 5-7=-70, 6-12=-20

Concentrated Loads (lb)

Vert: 11=-43(F) 2=-103(F) 8=-354(F) 13=-115(F) 14=-103(F) 15=-103(F) 16=-103(F) 17=-103(F) 18=-103(F) 19=-103(F) 20=-103(F) 21=-103(F) 22=-47(F)  
 23=-43(F) 24=-43(F) 25=-43(F) 26=-43(F) 27=-43(F) 28=-43(F) 29=-43(F) 30=-43(F)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	G2	Roof Special	1	1	


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEAD SUBMITTAL**  
**04/06/2021**

J45167690


Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 100681140550481

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-2dEINZqrYQ8IXmQBhsgv3aziWg9PXDUOoLr1Szbkqx



Scale = 1:47.0



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.33	Vert(LL)	-0.17 9-11	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.65	Vert(CT)	-0.35 9-11	>827	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.96	Horz(CT)	0.05 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.03 11-12	>999	240	Weight: 101 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2 *Except* 3-4: 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-2-15 oc purlins, except end verticals, and 2-0-0 oc purlins (4-10-15 max.): 4-5.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 7-9: 2x4 SPF No.2	WEBS 1 Row at midpt 2-13

**REACTIONS.** (size) 13=Mechanical, 9=0-3-8  
 Max Horz 13=110(LC 6)  
 Max Uplift 9=51(LC 9)  
 Max Grav 13=1077(LC 1), 9=1231(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-1084/64, 3-4=-1069/51, 4-5=-1389/64, 5-6=-1569/52, 6-7=-282/0, 7-9=-375/47  
 BOT CHORD 12-13=0/789, 11-12=0/1460, 9-11=-36/1450  
 WEBS 2-12=0/308, 3-12=0/467, 4-12=-709/83, 5-11=0/338, 2-13=-1160/22, 6-9=-1501/104

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9.
  - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	G3	Roof Special	1	1	


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUBMIT TO SUBJECT**

J45167691

04/06/2021

Scale = 1:45.7

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID: E7EWovY\_94Pzt7UVy1gWAZ\_t70-Wqo7bur4JkG99v?NFZB8coWnR3VgGg LX171OZuzbkqw



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.77	Vert(LL)	-0.10 10-12	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.59	Vert(CT)	-0.22 10-12	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.92	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.03 10-12	>999	240	Weight: 107 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2 \*Except\*  
4-5: 2x6 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
7-9: 2x6 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-3-14 oc purlins, except end verticals, and 2-0-0 oc purlins (4-7-12 max.): 3-4, 5-6.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 14=Mechanical, 9=0-3-8  
Max Horz 14=-110(LC 6)  
Max Uplift 9=-50(LC 9)  
Max Grav 14=1073(LC 1), 9=1233(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 1-2=-813/27, 2-3=-852/63, 3-4=-994/65, 4-5=-1133/47, 5-6=-1471/62, 6-7=-1709/40,  
1-14=-1045/8, 7-9=-1165/88  
BOT CHORD 12-13=0/947, 10-12=0/1626, 9-10=-69/416  
WEBS 2-13=-318/101, 3-13=-398/0, 3-12=-20/506, 5-12=-747/89, 5-10=-317/30, 6-10=0/351,  
1-13=0/984, 7-10=0/1068

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 9.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021



Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	G5	Roof Special	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUBMIT: MISSOURI**  
**04/06/2021**

J45167693






Plate Offsets (X,Y)--	[1:0-2-0,0-1-8], [12:0-2-8,0-1-8]				
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.55	Vert(LL) -0.11 9-11 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.67	Vert(CT) -0.25 9-11 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.70	Horz(CT) 0.04 8 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-S	Wind(LL) 0.04 9-11 >999 240	Weight: 98 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2 *Except* 2-3: 2x4 SPF 2100F 1.8E, 3-4: 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-2-13 oc purlins, except end verticals, and 2-0-0 oc purlins (4-9-15 max.): 2-3, 4-5.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 6-8: 2x4 SPF No.2	

**REACTIONS.** (size) 13=Mechanical, 8=0-3-8  
 Max Horz 13=-110(LC 6)  
 Max Uplift 13=-3(LC 4), 8=-39(LC 5)  
 Max Grav 13=1077(LC 1), 8=1231(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-1007/45, 2-3=-1396/48, 3-4=-1560/37, 4-5=-1489/21, 5-6=-1692/7, 1-13=-1040/22, 6-8=-1194/51  
 BOT CHORD 11-12=0/893, 9-11=0/2020  
 WEBS 2-12=-417/82, 2-11=-19/660, 4-11=-675/94, 4-9=-806/51, 5-9=0/459, 1-12=-8/1021, 6-9=0/1437

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 13, 8.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021


Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	G6	Roof Special	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT, MISSOURI**

J45167694

8.430 s Feb 12 2021 MiTek Industries, Inc. File Name: 210331\_102501.rvt  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-Pb2eRGuaMymaeXl9UPG4megZfhrNCVJ7yd?cjbzbkqs  
 19-7-8 21-7-8 24-3-14 26-2-6  
 5-10-6 2-0-0 2-8-6 1-10-8  
 04/06/2021

Scale = 1:45.6




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.37	Vert(LL)	-0.16 13-14	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.73	Vert(CT)	-0.34 13-14	>854	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.79	Horz(CT)	0.05 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.06 10-12	>999	240		
								Weight: 97 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 4-5: 2x6 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-7-6 oc purlins, except end verticals, and 2-0-0 oc purlins (4-6-3 max.): 2-4, 5-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 9-10.
WEBS 2x3 SPF No.2 *Except* 7-9: 2x4 SPF No.2	

**REACTIONS.** (size) 14=Mechanical, 9=0-3-8  
 Max Horz 14=-139(LC 4)  
 Max Uplift 14=-143(LC 4), 9=-189(LC 5)  
 Max Grav 14=1077(LC 1), 9=1231(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-1480/263, 3-4=-1478/261, 4-5=-1743/247, 5-6=-1321/122, 6-7=-1495/125, 7-9=-1223/173  
 BOT CHORD 13-14=-47/703, 12-13=-129/1564, 10-12=-244/2235  
 WEBS 2-13=-118/1025, 3-13=-429/173, 4-12=0/372, 5-12=-706/207, 5-10=-1182/227, 6-10=-17/450, 2-14=-1122/219, 7-10=-103/1417

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 14=143, 9=189.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	G7	Roof Special Girder	1	1	

**RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES**

J45167695


LEED SUBMIT 20210504

04/06/2021

Scale = 1:46.4

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331

ID: EJEVovY\_94Pzt7UVy1gWAZ\_170-tnb0ecvC7GuRFhtL26nJrDd?4CpxwWHBGf9F6zkbqr



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.78	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.65	Vert(LL) -0.33 14-15 >865 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.92	Vert(CT) -0.60 14-15 >480 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-S	Horz(CT) 0.29 10 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.24 14-15 >999 240	Weight: 114 lb	FT = 10%


**LUMBER-**  
 TOP CHORD 2x4 SPF No.2 \*Except\*  
 2-5: 2x4 SPF 2100F 1.8E, 5-6: 2x6 SPF No.2  
 BOT CHORD 2x3 SPF No.2 \*Except\*  
 16-17: 2x4 SPF No.2, 14-15: 2x4 SPF 2100F 1.8E  
 10-13: 2x6 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 2-15: 2x4 SPF No.2, 8-10: 2x6 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 4-9-4 oc purlins, except end verticals, and 2-0-0 oc purlins (3-1-0 max.): 2-5, 6-7.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 10-11.

**REACTIONS.** (size) 10=0-3-8, 17=Mechanical  
 Max Horz 17=140(LC 6)  
 Max Uplift 10=270(LC 5), 17=170(LC 4)  
 Max Grav 10=1170(LC 1), 17=1071(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-4023/663, 3-4=-4263/634, 4-5=-4207/632, 5-6=-1984/290, 6-7=-507/74, 7-8=-645/94, 8-10=-580/110  
 BOT CHORD 3-15=-480/169, 14-15=-544/4071, 11-12=-331/2430, 10-11=-82/556  
 WEBS 15-17=-50/469, 2-15=-533/3572, 12-14=-199/1972, 5-14=-378/2680, 5-12=-743/161, 6-12=-658/231, 6-11=-2133/387, 7-11=-88/322, 2-17=-1233/273

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=270, 17=170.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 55 lb down and 12 lb up at 23-2-11 on top chord, and 168 lb down and 874 lb up at 23-1-11 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).



March 12, 2021

**LOAD CASE(S)** Standard

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss G7	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-----------------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 145167695  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-L\_9Pryvqua0ltqSXbq1Ys3molUY2gNmQPwUjnYzkbqq  
 04/06/2021

**RELEASE FOR  
 CONSTRUCTION  
 AS NOTED ON PLANS REVIEW  
 DEVELOPMENT SERVICES  
 LEAD SUBMIT MISSOURI  
 04/06/2021**

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-5=-70, 5-6=-70, 6-7=-70, 7-8=-70, 8-9=-70, 16-17=-20, 14-15=-20, 10-13=-20

Concentrated Loads (lb)

Vert: 11=66(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017


Job 210331	Truss G8	Truss Type Half Hip	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEAD SUBMIT 210331**  
**04/06/2021**

J45167696

8.430 s Feb 12 2021 MiTek Industries, Inc. File Name: 210331.dwg  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-L\_9Pryvua0ltqSXbqlyS3muOUXcgQ?QPwUjnYzkbqq

Scale = 1:40.6



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.42	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.75	Vert(LL) -0.14 11-12 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.71	Vert(CT) -0.31 11-12 >859 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.05 8 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.05 9-11 >999 240	Weight: 79 lb	FT = 10%


**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 6-8: 2x4 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 4-3-11 oc purlins, except end verticals, and 2-0-0 oc purlins (4-0-11 max.): 1-5.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
 WEBS 1 Row at midpt 2-12

**REACTIONS.** (size) 12=Mechanical, 8=0-3-8  
 Max Horz 12=-104(LC 6)  
 Max Uplift 12=-50(LC 4), 8=-60(LC 5)  
 Max Grav 12=987(LC 1), 8=1141(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-4=-1834/57, 4-5=-1381/48, 5-6=-1577/39, 6-8=-1096/81  
 BOT CHORD 11-12=-52/1505, 9-11=-57/1969  
 WEBS 2-12=-1649/122, 2-11=0/501, 4-9=-729/85, 5-9=0/316, 6-9=-9/1244

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Refer to girder(s) for truss to truss connections.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 12, 8.
  - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021


Job 210331	Truss G9	Truss Type Roof Special	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUBMIT 2/25/21**

J45167697

8.430 s Feb 12 2021 MiTek Industries, Inc. 18-6-11 22-3-14 24-2-6  
 ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-HMH9Gdx5QBH068cwjFK0xUrDvIFq8LFjtEzqsQzbnkqo  
 3-6-1 4-1-2 4-8-3 11-7-7 18-6-11 22-3-14 24-2-6  
 3-6-1 0-7-1 0-7-1 6-11-4 6-11-4 3-9-3 1-10-8  
 04/06/2021

Scale = 1:41.3




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 25.0	Plate Grip DOL	1.15	TC 0.48	Vert(LL)	-0.15	12	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.57	Vert(CT)	-0.30	12-13	>889	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.67	Horz(CT)	0.05	9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.08	12	>999	240		
									Weight: 83 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* 2-3,3-4: 2x6 SPF No.2, 4-6: 2x4 SPF 2100F 1.8E	TOP CHORD Structural wood sheathing directly applied or 4-6-15 oc purlins, except end verticals, and 2-0-0 oc purlins (4-2-0 max.): 1-2, 4-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 7-9: 2x4 SPF No.2	

**REACTIONS.** (size) 14=Mechanical, 9=0-3-8  
 Max Horz 14=-83(LC 4)  
 Max Uplift 14=-11(LC 9), 9=-66(LC 5)  
 Max Grav 14=987(LC 1), 9=1141(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-1438/40, 3-4=-1511/57, 4-5=-2692/132, 5-6=-2693/133, 6-7=-1523/65, 7-9=-1115/77  
 BOT CHORD 13-14=0/1339, 12-13=-18/1723, 10-12=-22/1376  
 WEBS 2-14=-1565/27, 4-12=-64/1071, 5-12=-574/131, 6-12=-74/1380, 7-10=-32/1389, 3-13=-19/550, 4-13=-960/113, 2-13=-14/586

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14, 9.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017



Job 210331	Truss G10	Truss Type Roof Special Girder	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-----------------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-1305018

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-aRgNADppn60Rwcr?789gXNRNhGodoluFahYIV0zbnqy

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEAD SUBMITTER'S USE**  
**04/06/2021**

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-6=-70, 6-7=-70, 7-8=-70, 9-15=-20

Concentrated Loads (lb)

Vert: 10=14(B) 16=-2(B) 17=-2(B) 18=-2(B) 19=-2(B) 20=-2(B) 21=-250(B) 22=-0(B) 23=-0(B) 24=-0(B) 25=-0(B) 26=-0(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	H1	Common	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT MISSOURI**  
**04/06/2021**

J45167699

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-lzRXUzyjBVPtkIB6HyrFThOSMif9tyHs6ujNOTzkbqn




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.24	Vert(LL)	-0.03	5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.31	Vert(CT)	-0.06	5	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	5	>999		
								Weight: 23 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 2-5: 2x3 SPF No.2	

**REACTIONS.** (size) 6=Mechanical, 4=Mechanical  
 Max Horz 6=-27(LC 6)  
 Max Uplift 6=-4(LC 8), 4=-5(LC 9)  
 Max Grav 6=367(LC 1), 4=367(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-371/21, 2-3=-373/19, 1-6=-285/29, 3-4=-289/32  
 BOT CHORD 5-6=0/284, 4-5=0/284

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 4.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021





Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	H4	Hip Girder	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45162702

LEED SUBMIT 20200818

04/06/2021

Scale = 1:23.7

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-eK4ZJL?DFjvIDvUtWowBeXY2bJ2xpIRSOWhaXezbkqj





Plate Offsets (X, Y)--	[3:0-3-9,Edge], [4:0-3-9,Edge], [7:Edge,0-3-8]
------------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.61	Vert(LL)	-0.02	8-9	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	-0.04	8-9	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.09	Horz(CT)	0.00	7	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	-0.02	8-9	>999	Weight: 38 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x6 SPF No.2  
WEBS 2x3 SPF No.2 \*Except\*  
2-10,5-7: 2x4 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** (size) 10=0-3-8, 7=0-3-8  
Max Horz 10=24(LC 7)  
Max Uplift 10=397(LC 29), 7=397(LC 28)  
Max Grav 10=499(LC 45), 7=499(LC 44)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-401/415, 3-4=-350/289, 4-5=-395/413, 2-10=-303/225, 5-7=-309/232  
BOT CHORD 9-10=-348/375, 8-9=-297/380, 7-8=-336/362  
WEBS 3-9=-500/127, 4-8=-517/139

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=397, 7=397.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 45 lb down and 12 lb up at 1-2-13, 50 lb down and 12 lb up at 3-4-4, and 50 lb down and 12 lb up at 5-4-4, and 45 lb down and 12 lb up at 7-5-11 on top chord, and 141 lb down and 737 lb up at 1-2-13, 14 lb down and 16 lb up at 3-4-4, and 14 lb down and 16 lb up at 5-4-4, and 141 lb down and 737 lb up at 7-4-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-5=-70, 5-6=-70, 7-10=-20



March 12, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



Job 210331	Truss H4	Truss Type Hip Girder	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	--------------------------	----------	----------	------------

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210681205018 Page 2

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-eK42JL?DFjvIDvUtWowBeXY2bJ2xpIRS0WhaXezbkqj

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162702

**LOAD CASE(S)** Standard  
 Concentrated Loads (lb)  
 Vert: 9=53(B) 8=53(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J1	Diagonal Hip Girder	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 30550481**  
**04/06/2021**

J45162703

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. L16120681302550481  
 ID:Ej7EWovY\_94Pzt7UVy1gWAz\_i70-aiCok10UnL90SDeGdDyfiyeKc6d6HgMIUqAhbXzBkqh  
 2-4-0 2-4-0 2-10-0 2-10-0 8-5-0 5-7-0




Plate Offsets (X, Y)-- [3:0-5-9,Edge], [4:Edge,0-2-8], [5:Edge,0-2-8], [7:0-3-8,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.77	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.59	Vert(LL) -0.18 3 >544 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) -0.33 3 >300 240		
BCDL 10.0	Rep Stress Incr NO	Matrix-R	Horz(CT) 0.17 5 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.16 6 >604 240	Weight: 28 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF 2100F 1.8E	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2 *Except* 3-6: 2x3 SPF No.2, 3-5: 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 4-5: 2x3 SPF No.2	

**REACTIONS.** (size) 7=0-3-14, 5=Mechanical  
 Max Horz 7=109(LC 5)  
 Max Uplift 7=-161(LC 4), 5=-109(LC 8)  
 Max Grav 7=577(LC 1), 5=481(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-7=-563/174, 4-5=-260/100


- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=161, 5=109.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 72 lb down and 134 lb up at 2-1-6, 63 lb down and 36 lb up at 2-4-9, 108 lb down and 63 lb up at 4-11-5, and 97 lb down and 51 lb up at 5-3-12, and 98 lb down and 67 lb up at 7-6-1 on top chord, and 18 lb down and 21 lb up at 2-1-6, 3 lb down at 2-4-9, 3 lb down at 4-11-5, and 24 lb down at 5-3-12, and 63 lb down and 27 lb up at 7-6-1 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)  
 Vert: 1-2=-70, 2-3=-70, 3-4=-70, 6-7=-20, 3-5=-20

Concentrated Loads (lb)  
 Vert: 8=35(B) 9=-40(F) 10=-4(B) 11=-62(F) 14=-16(B) 15=-63(F)



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss J2	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS**  
**04/06/2021**

J45162704

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068130250481

ID:Ej7EWovY\_94Pzt7UVy1gWAz\_170-LFhqQm6Vu09uQSFo5u5X2ezr9LU59H7wK466t3zbnkqZ



Scale = 1:13.3

Plate Offsets (X,Y)--	[3:0-2-11,0-1-8]				
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.22	Vert(LL) -0.02 6 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.07	Vert(CT) -0.04 6 >925 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.01	Horz(CT) 0.02 5 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-P	Wind(LL) 0.03 6 >999 240	Weight: 11 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
WEDGE  
Left: 2x3 SPF No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-7-7 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** (size) 4=Mechanical, 2=0-3-8, 5=Mechanical  
Max Horz 2=75(LC 8)  
Max Uplift 4=-52(LC 8), 2=-34(LC 8)  
Max Grav 4=129(LC 1), 2=240(LC 1), 5=37(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J3	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 1550481**  
**04/06/2021**

145162705

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-1550481

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_l70-ebcTu9CuFy2uIWH8?TjAq7i0V9t2ISqyxf\_l\_d9zbnkqS



Scale = 1:13.8

Plate Offsets (X,Y)--	[3:0-2-4,0-1-12], [7:0-5-6,0-1-8]
-----------------------	-----------------------------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.28	Vert(LL)	-0.02	6	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	-0.04	6	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.02	Horz(CT)	0.02	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.02	6	>999		
								Weight: 14 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 4-0-14 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 3-6: 2x3 SPF No.2	

**REACTIONS.** (size) 7=0-3-8, 4=Mechanical, 5=Mechanical  
 Max Horz 7=79(LC 4)  
 Max Uplift 7=-117(LC 4), 4=-39(LC 8)  
 Max Grav 7=361(LC 1), 4=96(LC 1), 5=70(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-7=-329/128

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 7=117.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss J4	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUMMIT MISSOURI**  
**04/06/2021**

J45162706

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)




LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.08	Vert(LL) 0.00 5 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) 0.00 4-5 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Horz(CT) -0.00 3 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) -0.00 5 >999 240	Weight: 6 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 1-6-14 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=46(LC 4)  
 Max Uplift 5=-143(LC 4), 3=-22(LC 1), 4=-16(LC 1)  
 Max Grav 5=306(LC 1), 3=16(LC 4), 4=18(LC 4)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-262/142

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 5=143.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J5	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162707

Scale = 1:16.6

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Leas Summit Missouri  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-iU081HOliZxm2qx1OWVhxHtYYCwAJEo9NVRHfnzbkqD  
 5-2-10 2-11-2




Plate Offsets (X,Y)--	[3:0-0-0,0-0-1]
-----------------------	-----------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.48	Vert(LL)	-0.06	3	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.33	Vert(CT)	-0.10	3	>583		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.07	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.06	3	>966		
								Weight: 15 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2 \*Except\*  
 3-6: 2x3 SPF No.2


**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 5-2-10 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**WEDGE**  
 Left: 2x3 SPF No.2

**REACTIONS.** (size) 4=Mechanical, 2=0-3-8, 5=Mechanical  
 Max Horz 2=102(LC 8)  
 Max Uplift 4=-58(LC 8), 2=-44(LC 8), 5=-6(LC 8)  
 Max Grav 4=135(LC 1), 2=304(LC 1), 5=87(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2, 5.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021


Job 210331	Truss J6	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	-------------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUMMIT, MISSOURI  
**04/06/2021**

J45162708

Scale = 1:10.0

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.06	Vert(LL)	-0.00	2	>999	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.03	Vert(CT)	-0.00	2-4	>999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P	Wind(LL)	0.00	2	****	Weight: 6 lb	FT = 10%
	Code IRC2018/TPI2014							

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEDGE  
 Left: 2x3 SPF No.2


**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 2-0-4 oc purlins.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 3=Mechanical, 2=0-3-8, 4=Mechanical  
 Max Horz 2=48(LC 8)  
 Max Uplift 3=-33(LC 8), 2=-36(LC 4)  
 Max Grav 3=43(LC 1), 2=173(LC 1), 4=36(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J7	Truss Type Jack-Closed	Qty 3	Ply 1	Lot 102 RR
---------------	-------------	---------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUBMIT MISSOURI**  
**04/06/2021**

J45162709

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-AgaWFdOwTs3dg\_WDxE0wTVQgUcGT2h2Jc9AqCEzbnkqC



Scale = 1:18.1




Plate Offsets (X,Y)--	[3:0-2-12,0-2-9]
-----------------------	------------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.60	Vert(LL)	-0.10	6	>711	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.33	Vert(CT)	-0.17	6	>397		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.11	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.10	6	>705		
								Weight: 18 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-11-4 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2 *Except* 3-6: 2x3 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	
WEDGE Left: 2x3 SPF No.2	

**REACTIONS.** (size) 5=Mechanical, 2=0-3-8  
 Max Horz 2=104(LC 5)  
 Max Uplift 5=61(LC 8), 2=58(LC 8)  
 Max Grav 5=250(LC 1), 2=334(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 2.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss J8	Truss Type Jack-Closed	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	---------------------------	----------	----------	------------


**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**

J451627710

Scale = 1:18.2

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

ID: E|7EWovY\_94Pzt7UVy1gWAZ\_t70-es8vSzPYEABUI85QVxX90iyrD0cSn8HSrpwOkgzbkqB



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 25.0	Plate Grip DOL	1.15	TC 0.60	Vert(LL)	-0.06	2-4	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.35	Vert(CT)	-0.13	2-4	>544	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.00	2	****	240		
									Weight: 18 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
WEDGE  
Left: 2x3 SPF No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-11-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 4=Mechanical, 2=0-3-8  
Max Horz 2=120(LC 5)  
Max Uplift 4=-59(LC 8), 2=-60(LC 8)  
Max Grav 4=250(LC 1), 2=334(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J9	Jack-Closed	1	1	


**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK MISSOURI**  
**04/06/2021**

J451627711

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 2006120302050181

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-63iHgJQB?UJLwHfc3e2OZwV?nQyOWbXc3TfxG6zkbqA  
 5-11-4  
 5-11-4



Scale = 1:18.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.67	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.36	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 17 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2  
 WEDGE  
 Left: 2x3 SPF No.2


**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 5-11-4 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 3=5-11-4, 1=5-11-4  
 Max Horz 1=118(LC 5)  
 Max Uplift 3=62(LC 8), 1=36(LC 8)  
 Max Grav 3=263(LC 1), 1=263(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 1.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J10	Diagonal Hip Girder	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 1050481**  
**04/06/2021**

J45162712

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional) LEED SUBMIT 1050481  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-2vmByN16YeHt4NDSBwTuGAAUsW?b031ujUvF8zbbkqg  
 9-4-3 4-8-1



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.87	Vert(LL)	-0.05 5-6	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.45	Vert(CT)	-0.08 5-6	>999	240		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.29	Horz(CT)	0.00 5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.04 5-6	>999	240	Weight: 39 lb	FT = 10%


<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 2-7: 2x6 SPF No.2	

**REACTIONS.** (size) 7=0-4-11, 5=Mechanical  
 Max Horz 7=145(LC 5)  
 Max Uplift 7=-266(LC 4), 5=-149(LC 8)  
 Max Grav 7=715(LC 1), 5=535(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-7=-554/247, 2-3=-563/132  
 BOT CHORD 6-7=-165/481, 5-6=-165/481  
 WEBS 3-5=-490/167

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 7=266, 5=149.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 55 lb down and 94 lb up at 2-11-15, 78 lb down and 36 lb up at 3-0-9, and 79 lb down and 54 lb up at 5-6-11, and 102 lb down and 86 lb up at 8-1-6 on top chord, and 10 lb down and 16 lb up at 2-11-15, 9 lb down and 7 lb up at 3-0-9, 16 lb down and 2 lb up at 5-6-11, and 168 lb down and 75 lb up at 6-2-15, and 40 lb down at 8-1-6 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70, 2-4=-70, 5-7=-20  
 Concentrated Loads (lb)  
 Vert: 8=26(B) 10=-54(B) 11=7(F) 12=2(B) 13=-168(F) 14=-25(B)



March 12, 2021

Job 210331	Truss J11	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEIF SUMMIT MISSOURI**  
**04/06/2021**

J451627713

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 2106813205081

ID: Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-W5KZ9i2klyPkiXoele\_7oNjoXwPglas2x8fogPzbkqf



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.30	Vert(LL)	-0.02	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.20	Vert(CT)	-0.05	4-5	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.02	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	4-5	>999		
								Weight: 15 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-0-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=101(LC 8)  
Max Uplift 5=66(LC 4), 3=75(LC 8)  
Max Grav 5=388(LC 1), 3=138(LC 1), 4=88(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-340/110

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




Job 210331	Truss J12	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 3055081**  
**04/06/2021**

J45162714

Scale = 1:15.0

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70\_HuxN23M3GXbJgNrlLWMLbGzTKnsU16BAoOLCrzkbqe



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	Vert(LL)	-0.01	4-5	>999	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.08	Vert(CT)	-0.01	4-5	>999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Wind(LL)	0.00	4-5	>999		
	Code IRC2018/TPI2014						Weight: 11 lb	FT = 10%


LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-5-1 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=73(LC 8)  
 Max Uplift 5=71(LC 4), 3=48(LC 8)  
 Max Grav 5=330(LC 1), 3=77(LC 1), 4=57(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-289/94

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021


Job 210331	Truss J13	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK MISSOURI**  
**04/06/2021**

J45162715

Scale = 1:11.7

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-\_HuxN23M3GXbJgNrlWMLbGzTKnuU16BAoOLCrzbnkqe



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	Vert(LL)	0.00	4-5	>999	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.08	Vert(CT)	0.00	4-5	>999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	-0.01	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Wind(LL)	-0.00	5	>999		
	Code IRC2018/TPI2014						Weight: 7 lb	FT = 10%



LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 1-9-13 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=53(LC 5)  
 Max Uplift 5=-87(LC 4), 3=-14(LC 8), 4=-7(LC 1)  
 Max Grav 5=302(LC 1), 3=4(LC 4), 4=24(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-262/96

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J14	Truss Type Jack-Closed	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	---------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J451627716

Scale = 1:16.6

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210681340550481  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-SUSJaO3\_qZfSxqy1s31btoo86k59DUMKPS8vkizbkdq




Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]
-----------------------	-----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.29	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.20	Vert(LL) -0.03 4-5 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) -0.05 4-5 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Horz(CT) -0.00 4 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.01 4-5 >999 240	Weight: 17 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x4 SPF No.2 \*Except\*  
 3-4: 2x3 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 5-3-14 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
 Max Horz 5=112(LC 5)  
 Max Uplift 5=-136(LC 4), 4=-43(LC 8)  
 Max Grav 5=398(LC 1), 4=200(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-352/170

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=136.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J15	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------


**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUMMIT, MISSOURI  
 04/06/2021

J45162717

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No. 210331-01

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-xg?hok4cbtnJZ\_WDQmYqQ0LJ07SRyxUd6tSHkzkbq



Scale = 1:11.7


Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]								
<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.28	Vert(LL) 0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT) -0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT) -0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL) -0.00	4-5	>999	240	Weight: 9 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-9-14 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=62(LC 4)  
 Max Uplift 5=-124(LC 4), 3=-31(LC 8)  
 Max Grav 5=314(LC 1), 3=52(LC 1), 4=44(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-273/139

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 5=124.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J16	Jack-Closed	1	1	



**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS**

J45162718

04/06/2021

Scale = 1:20.6

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.38	Vert(LL)	-0.04	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.26	Vert(CT)	-0.09	4-5	>773		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	4-5	>999		
								Weight: 19 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-11-4 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 3-4: 2x3 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
 Max Horz 5=150(LC 5)  
 Max Uplift 5=-85(LC 8), 4=-56(LC 8)  
 Max Grav 5=423(LC 1), 4=231(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-373/129

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 4.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021


Job 210331	Truss J17	Truss Type Jack-Closed	Qty 2	Ply 1	Lot 102 RR
---------------	--------------	---------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK UNIVERSITY**  
**04/06/2021**

J451627719

Scale = 1:20.6

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID: E7EWovY\_94Pzt7UVy1gWAZ\_t70-PsZ3?45FMBVAA85Q\_U33yDuRGXILhOsdsmD0pAzbkqb



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.50	Vert(LL)	-0.05	3-4	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.28	Vert(CT)	-0.10	3-4	>707		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	3-4	>999		
								Weight: 17 lb	FT = 10%



LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-11-4 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 4=0-3-8, 3=Mechanical  
 Max Horz 4=133(LC 5)  
 Max Uplift 4=33(LC 8), 3=63(LC 8)  
 Max Grav 4=258(LC 1), 3=258(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J18	Diagonal Hip Girder	2	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS**  
**04/06/2021**

J45162720

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional) ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70-t37SCQ6tU11oIgcXBalVRQXOx5PQq5n5QMZLdzbkqa  
 6-1-12 6-1-12  
 Scale = 1:17.1



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0 Plate Grip DOL 1.15	TC 0.80	Vert(LL) -0.05	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.29	Vert(CT) -0.09	4-5	>764	240		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT) 0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.02	4-5	>999	240		
							Weight: 26 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x6 SPF 1650F 1.4E	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 3-4: 2x3 SPF No.2	

**REACTIONS.** (size) 5=0-5-10, 4=Mechanical  
 Max Horz 5=108(LC 5)  
 Max Uplift 5=-212(LC 4), 4=-54(LC 8)  
 Max Grav 5=926(LC 41), 4=229(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-849/249

- NOTES-**
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Refer to girder(s) for truss to truss connections.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=212.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Load case(s) 40, 41 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 78 lb down and 36 lb up at 3-0-9, and 68 lb down and 65 lb up at 3-0-14, and 67 lb down and 54 lb up at 5-7-10 on top chord, and 9 lb down and 7 lb up at 3-0-9, and 10 lb down and 16 lb up at 3-0-14, and 24 lb down at 5-7-10 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard Except:  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70, 2-3=-70, 4-5=-20  
 Concentrated Loads (lb)  
 Vert: 7=-20(B) 8=7(F) 9=-8(B)



March 12, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J18	Diagonal Hip Girder	2	1	

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 16023 Swingley Ridge Rd Chesterfield, MO 63017  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70-t37SCQ6t7U11oIgcXBalVRQXOx5PQq5n5QMZLdzbkqa

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEAD SUBMITTAL SUBJECT**  
**04/06/2021**

**LOAD CASE(S)**

- 40) Reversal: User defined: Lumber Increase=1.15, Plate Increase=1.15
  - Uniform Loads (plf)
    - Vert: 1-2=-70(F), 2-3=-70(F), 4-5=-20(F)
  - Concentrated Loads (lb)
    - Vert: 1=-250 6=1(B) 7=-20(B) 8=22(F=7, B=16) 9=-8(B)
- 41) User defined: Lumber Increase=1.15, Plate Increase=1.15
  - Uniform Loads (plf)
    - Vert: 1-2=-70(F), 2-3=-70(F), 4-5=-20(F)
  - Concentrated Loads (lb)
    - Vert: 1=-250 7=-20(B) 8=7(F) 9=-8(B)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss J19	Truss Type Jack-Open	Qty 2	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162721

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)  
 ID: EJEVovY\_94Pzt7UVy1gWAZ\_t70-t37SCQ6t7U11oIgcXBalVRQFTx8lQq5n5QMZLdzbkqa




LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	Vert(LL)	-0.01	4-5	>999	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.08	Vert(CT)	-0.01	4-5	>999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Wind(LL)	0.00	4-5	>999		
	Code IRC2018/TPI2014						Weight: 11 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-5-10 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=74(LC 8)  
 Max Uplift 5=71(LC 4), 3=49(LC 8)  
 Max Grav 5=332(LC 1), 3=79(LC 1), 4=58(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-290/95

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.




March 12, 2021

Job 210331	Truss J20	Truss Type Jack-Open	Qty 2	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162722  
 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068130250181  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-LFhqQm6Vuo9uQSFo5u5X2ezqDLU39HLwK466t3zbnkz

Scale = 1:11.8



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>	
TCLL 25.0	Plate Grip DOL	1.15	TC 0.28	Vert(LL)	0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	-0.00	5	>999	240		
									Weight: 7 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 1-10-7 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 3=Mechanical, 4=Mechanical, 5=0-3-8  
 Max Horz 5=53(LC 5)  
 Max Uplift 3=16(LC 8), 4=6(LC 1), 5=86(LC 4)  
 Max Grav 3=5(LC 19), 4=25(LC 3), 5=302(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-262/95

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4, 5.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J21	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW**

**DEVELOPMENT SERVICES**

**LEWIS & CLARK MISSOURI**

**04/06/2021**

Scale = 1:11.7

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. H:\Projects\210331\392155\Drawn  
ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-pRFCd677f6ll1bq?fdmasV?dmtukb3YkrgQVzbkqY




Plate Offsets (X,Y)--	[6:0-5-6,0-1-8]
-----------------------	-----------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.30	Vert(LL)	0.01	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.36	Vert(CT)	0.01	4-5	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.03	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	-0.01	4-5	>999	Weight: 9 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-9-14 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 3=Mechanical, 4=Mechanical, 5=0-3-8  
 Max Horz 5=62(LC 4)  
 Max Uplift 3=-25(LC 8), 4=-78(LC 1), 5=-187(LC 4)  
 Max Grav 3=25(LC 1), 4=55(LC 4), 5=430(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-6=-300/150

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 5=187.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017


Job 210331	Truss J22	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK MISSOURI**  
**04/06/2021**

J45162724

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-HeparRBIQPQcfIPBDJ8?732A18AcDbrDnObDyxbkqX



Scale = 1:11.7

Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]
-----------------------	-----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.07	Vert(LL) 0.00 4-5 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) -0.00 4-5 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Horz(CT) -0.00 3 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) -0.00 4-5 >999 240	Weight: 9 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-9-14 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=62(LC 4)  
 Max Uplift 5=-124(LC 4), 3=-31(LC 8)  
 Max Grav 5=314(LC 1), 3=52(LC 1), 4=44(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-273/139

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 5=124.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss J23	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE SUMMIT, MISSOURI**  
**04/06/2021**

J45162725

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)



LOADING (psf)	SPACING-	CSL.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.11	Vert(LL) -0.01 4-5 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) -0.02 4-5 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Horz(CT) -0.01 3 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.01 4-5 >999 240	Weight: 12 lb	FT = 10%



**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-11-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=82(LC 8)  
Max Uplift 5=69(LC 4), 3=57(LC 8)  
Max Grav 5=348(LC 1), 3=98(LC 1), 4=67(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-305/97

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J24	Diagonal Hip Girder	1	1	


**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUBMIT 10550481  
 04/06/2021

J45162726

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File Name: 210331.dwg

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-lqNy2n9NBjYSHv\_Nm1fEfhbGyYTNMe5M02KmUOzbkqW



Scale = 1:15.7




Plate Offsets (X,Y)-- [5:0-5-5,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.63	Vert(LL)	-0.03	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.23	Vert(CT)	-0.06	4-5	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	-0.02	4-5	>999	Weight: 18 lb	FT = 10%


LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-6-6 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 3-4: 2x3 SPF No.2	

**REACTIONS.** (size) 5=0-4-9, 4=Mechanical  
 Max Horz 5=88(LC 5)  
 Max Uplift 5=186(LC 4), 4=-31(LC 8)  
 Max Grav 5=485(LC 1), 4=186(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-429/217

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=186.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 70 lb down and 14 lb up at 2-9-8, and 70 lb down and 14 lb up at 2-9-8 on top chord, and 14 lb down and 16 lb up at 2-9-8, and 14 lb down and 16 lb up at 2-9-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70, 2-3=-70, 4-5=-20



March 12, 2021

Job 210331	Truss J25	Truss Type Jack-Open	Qty 2	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUMMIT 2025 COURT**  
**04/06/2021**

J45162727

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-D0wLG7A?y1gJu3ZaKkATCU7WFYrv55LWEI4K1qzbnqV




Plate Offsets (X, Y)--	[5:0-5-6,0-1-8]
------------------------	-----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.28	Vert(LL) 0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.08	Vert(CT) 0.00	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.00	5	>999	240		
							Weight: 7 lb	FT = 10%


**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x4 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=51(LC 4)  
 Max Uplift 5=-134(LC 4), 3=-13(LC 8), 4=-7(LC 1)  
 Max Grav 5=302(LC 1), 3=5(LC 18), 4=26(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-260/138

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 5=134.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J26	Truss Type Jack-Closed	Qty 2	Ply 1	Lot 102 RR
---------------	--------------	---------------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45162728  
**LEED SUBMIT MISSOURI**  
**04/06/2021**

Scale = 1:13.7

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-D0wLG7A?y1gJu3ZaKkAtCU7WFYra55LWEI4K1qzbkqV




Plate Offsets (X,Y)--	[5'-0-5-6,0-1-8]				
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defn L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.28	Vert(LL) -0.01 4-5 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.10	Vert(CT) -0.02 4-5 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00 4 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) 0.00 4-5 >999 240	Weight: 13 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2 \*Except\*  
3-4: 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
Max Horz 5=93(LC 5)  
Max Uplift 5=-132(LC 4), 4=-27(LC 8)  
Max Grav 5=348(LC 1), 4=131(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-308/154

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=132.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss J27	Truss Type Jack-Closed	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	---------------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**

J45162729  
LEED SUBMIT MISSOURI  
04/06/2021

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVVy1gWAZ\_t70-iDUjTTAejKoAWD8muShiligh?MCdqYafTLptZGzbkqU




Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]				
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.28	Vert(LL) -0.00 4-5 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.05	Vert(CT) -0.00 4-5 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00 4 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.00 5 >999 240	Weight: 11 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2 \*Except\*  
3-4: 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
Max Horz 5=78(LC 5)  
Max Uplift 5=-133(LC 4), 4=-17(LC 5)  
Max Grav 5=317(LC 1), 4=72(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-279/145

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=133.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J28	Jack-Closed	1	1	


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS SOURCE**  
**04/06/2021**

J45162730

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-AP25gpBGUew18NjyS9CxHvDvUmYiZ?qi?ZR5jzbkqT



Scale: 1"=1'


<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.10	Vert(LL)	-0.00 3-4	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	-0.01 3-4	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00 3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.00 4	>999	240	Weight: 8 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 4=0-3-8, 3=Mechanical  
Max Horz 4=63(LC 5)  
Max Uplift 4=-19(LC 4), 3=-29(LC 8)  
Max Grav 4=126(LC 1), 3=126(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 3.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J29	Jack-Closed Girder	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 40550481**  
**04/06/2021**

J45162731

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. S9CxBvDr6mXqZ?Ppi?ZR5jzbkqT

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-AP25gpBGUew18NjyS9CxBvDr6mXqZ?Ppi?ZR5jzbkqT



Scale = 1:14.1




Plate Offsets (X, Y)--	[3:0-3-8,0-2-5], [8:0-5-6,0-1-8]
------------------------	----------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.32	Vert(LL)	-0.01	7	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	-0.01	6-7	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.03	Horz(CT)	0.00	6	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S	Wind(LL)	0.00	7	>999	Weight: 19 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x3 SPF No.2 *Except* 2-8: 2x4 SPF No.2	


**REACTIONS.** (size) 8=0-3-8, 6=Mechanical  
 Max Horz 8=78(LC 5)  
 Max Uplift 8=-166(LC 4), 6=-52(LC 8)  
 Max Grav 8=364(LC 1), 6=170(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-8=-313/160

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Provide adequate drainage to prevent water ponding.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6 except (jt=lb) 8=166.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
  - 9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 59 lb down and 126 lb up at 2-0-0 on top chord, and 29 lb down and 60 lb up at 2-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-5=-70, 6-8=-20
Concentrated Loads (lb)
Vert: 3=35(B)



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J30	Jack-Closed	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFT SUMMIT WBS COURT**

J45162732

04/06/2021

Scale = 1:15.1

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068140250481  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-6nAr5VDW?FAIngsLZaFPMKIBECu1v559J2XAbzbkqR




Plate Offsets (X, Y)-- [3:0-3-8,0-2-5], [7:0-5-6,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	VERTICAL	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	in (loc) l/defl L/d	Vert(LL) -0.01 6-7 >999 360	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.14	Vert(CT) -0.03 6-7 >999 240	Horz(CT) 0.00 5 n/a n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.02	Wind(LL) 0.01 6-7 >999 240		Weight: 17 lb	FT = 10%
BCDL 10.0	Rep Stress Incr YES	Matrix-R				
	Code IRC2018/TPI2014					


**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2 \*Except\*  
 2-7: 2x4 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 7=0-3-8, 5=Mechanical  
 Max Horz 7=95(LC 5)  
 Max Uplift 7=-137(LC 4), 5=-32(LC 5)  
 Max Grav 7=385(LC 1), 5=184(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-7=-326/156

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Provide adequate drainage to prevent water ponding.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5 except (jt=lb) 7=137.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss J31	Truss Type Jack-Closed	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	---------------------------	----------	----------	------------

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW**

J45162733

**DEVELOPMENT SERVICES**

**LEFT SUBMIT TO SOURCE**

**04/06/2021**

Scale = 1:17.2

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No. 21061140550481

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-6nAr5VDW?FAINgsLZaFPMKIBEZCP1vK59J2XAbzkbqR




Plate Offsets (X,Y)-- [5:0-5-6,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.28	Vert(LL)	-0.02	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.17	Vert(CT)	-0.04	4-5	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.01	4-5	>999		
								Weight: 16 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2 \*Except\*  
3-4: 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
Max Horz 5=108(LC 5)  
Max Uplift 5=-134(LC 4), 4=-40(LC 8)  
Max Grav 5=385(LC 1), 4=184(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-340/166

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=134.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss J32	Truss Type Jack-Closed	Qty 6	Ply 1	Lot 102 RR
---------------	--------------	---------------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE H SUMMIT, MISSOURI**  
**04/06/2021**

J45162734

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21061140550181

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70-2AicWBEmXtQTc\_0jh?HtSINS1NqgVpqOddXeEUzkbqP



Scale = 1:19.1

Plate Offsets (X, Y)--	[4:Edge,0-2-8], [5:0-5-6,0-1-8]
------------------------	---------------------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.58	Vert(LL)	-0.08	4-5	>985	360	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.38	Vert(CT)	-0.17	4-5	>472	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.03	4-5	>999	240		
									Weight: 21 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 3-4: 2x3 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 4=Mechanical  
 Max Horz 5=137(LC 5)  
 Max Uplift 5=-144(LC 4), 4=-62(LC 8)  
 Max Grav 5=466(LC 1), 4=283(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-412/192

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=144.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J33	Diagonal Hip Girder	1	1	

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUBMITTALS DEPT  
 04/06/2021

J45162735

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 160000149050481

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-WMs\_kWFOIAYKE8bwEio6\_zwdMnCYEG3YrHGcmwzbnkqO

-2-7-13  
2-7-13

2-8-7  
2-8-7

Scale = 1:10.6




Plate Offsets (X,Y)--	[5:0-5-5,0-1-8]
-----------------------	-----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 2-0-0	TC 0.61	Vert(LL) 0.01	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.21	Vert(CT) 0.01	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT) -0.01	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.01	4-5	>999	240		
							Weight: 10 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-8-7 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	


**REACTIONS.** (size) 5=0-4-9, 3=Mechanical, 4=Mechanical  
 Max Horz 5=52(LC 7)  
 Max Uplift 5=-158(LC 4), 3=-42(LC 17), 4=-26(LC 1)  
 Max Grav 5=276(LC 1), 3=23(LC 4), 4=28(LC 4)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 5=158.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 46 lb down and 16 lb up at -2-7-13, and 46 lb down and 16 lb up at -2-7-13 on top chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Concentrated Loads (lb)  
 Vert: 1=-71(F=-36, B=-36)  
 Trapezoidal Loads (plf)  
 Vert: 1=0(F=35, B=35)-to-2=-49(F=11, B=11), 2=-5(F=33, B=33)-to-3=-49(F=10, B=10), 5=0(F=10, B=10)-to-4=-14(F=3, B=3)



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J34	Diagonal Hip Girder	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMIT 5050481**  
**04/06/2021**

J45162736

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70\_ZPMxsG13UgBsiA6oQJLXATI?AXYZjH4x0lJmZbkqN




Plate Offsets (X, Y)-- [3:Edge,0-2-8], [4:Edge,0-2-8], [5:0-3-10,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.81	Vert(LL)	-0.04	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.29	Vert(CT)	-0.08	4-5	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.02	4-5	>999	Weight: 27 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x6 SPF No.2  
WEBS 2x6 SPF No.2 \*Except\*  
3-4: 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-14, 4=Mechanical  
Max Horz 5=115(LC 22)  
Max Uplift 5=-191(LC 4), 4=-91(LC 8)  
Max Grav 5=553(LC 1), 4=380(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-501/250, 3-4=-261/131

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=191.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 38 lb up at 2-6-8, 77 lb down and 29 lb up at 3-4-9, and 89 lb down and 71 lb up at 5-1-4, and 101 lb down and 78 lb up at 6-6-15 on top chord, and 4 lb down at 2-6-8, 10 lb down and 8 lb up at 3-4-9, and 20 lb down at 5-1-4, and 39 lb down at 6-6-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)  
Vert: 1-2=-70, 2-3=-70, 4-5=-20

Concentrated Loads (lb)  
Vert: 8=-23(F) 9=-52(B) 11=8(B) 12=-10(F) 13=-24(B)



March 12, 2021

Job 210331	Truss J35	Truss Type Jack-Open	Qty 10	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	-----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEVO SUMMIT, MISSOURI**  
**04/06/2021**

J45162737

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 13068150255081

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-\_ZPMxSG13UgBslA6oQLXATq8AXHzjJh4x0IJMzkbqN




Plate Offsets (X, Y)--	[5:0-5-6,0-1-8]
------------------------	-----------------


LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.48	Vert(LL)	-0.05	4-5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.31	Vert(CT)	-0.11	4-5	>632		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.03	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	0.04	4-5	>999	Weight: 17 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=106(LC 4)  
 Max Uplift 5=-127(LC 4), 3=-82(LC 8)  
 Max Grav 5=427(LC 1), 3=173(LC 1), 4=107(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-374/174

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 5=127.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J36	Jack-Open	1	1	


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS**  
**04/06/2021**

J45162738

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-Tlzk8CHfqqo2TRIIM7qa3O?2eau5IAZrJblIrpzkbqM



Scale = 1:16.3

Plate Offsets (X,Y)-- [5:0-5-6,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.30	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.20	Vert(LL) -0.03 4-5 >999 360		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) -0.05 4-5 >999 240		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Horz(CT) 0.02 3 n/a n/a		
	Code IRC2018/TPI2014		Wind(LL) 0.02 4-5 >999 240	Weight: 15 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x4 SPF No.2


**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 5-0-12 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=93(LC 4)  
Max Uplift 5=-124(LC 4), 3=-68(LC 8)  
Max Grav 5=389(LC 1), 3=140(LC 1), 4=89(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-341/162

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 5=124.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job 210331	Truss J37	Truss Type Jack-Open	Qty 2	Ply 1	Lot 102 RR	<b>RELEASE FOR CONSTRUCTION</b> <b>AS NOTED ON PLANS REVIEW</b> <b>DEVELOPMENT SERVICES</b> <b>LEED SUBMITTALS SOURCE</b> <b>04/06/2021</b>
Wheeler Lumber, Waverly, KS - 66871,	8.430 s Feb 12 2021 MiTek Industries, Inc. L. H. Ma 20068152050481		Job Reference (optional) ID:Ej7EWovY_94Pzt7UVy1gWaz_t70-xxX7MYHH-b5wv5bKVvrLpcbYDj_GLRdp_YFVsNFzkbqL		Scale = 1:11.3	





Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]				
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.28	Vert(LL) 0.00 4-5 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.07	Vert(CT) -0.00 4-5 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00 3 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.00 4-5 >999 240	Weight: 9 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-6-12 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=59(LC 4)  
 Max Uplift 5=-126(LC 4), 3=-26(LC 8)  
 Max Grav 5=308(LC 1), 3=39(LC 1), 4=38(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-267/137

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3 except (jt=lb) 5=126.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J38	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE H SUMMIT MISSOURI**  
**04/06/2021**

J45162740

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-520350-01

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-xxX7MYHHb5wv5bKVvrLpcbYF8\_GcRdp\_YFVsNFzbkqL



<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.19	Vert(LL)	-0.01	2-4	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.12	Vert(CT)	-0.02	2-4	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.00	2	****	Weight: 10 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEDGE  
Left: 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 3-8-10 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 3=Mechanical, 2=0-3-8, 4=Mechanical  
Max Horz 2=77(LC 8)  
Max Uplift 3=66(LC 8), 2=37(LC 8)  
Max Grav 3=113(LC 1), 2=240(LC 1), 4=70(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss J39	Truss Type Jack-Open	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------


**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS**  
**04/06/2021**

J451627741

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068153050181

ID: Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-P85VZulvMP2jlvhTYt29p5RqOdEA437mvEPvzbkqK



Scale = 1:10.2

<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.06	Vert(LL)	-0.00	2	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	-0.00	2-4	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.00	2	****	Weight: 7 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEDGE  
Left: 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 2-1-7 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 3=Mechanical, 2=0-3-8, 4=Mechanical  
Max Horz 2=49(LC 8)  
Max Uplift 3=-35(LC 8), 2=-35(LC 4)  
Max Grav 3=48(LC 1), 2=177(LC 1), 4=38(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**  
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60  
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.  
3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.  
4) Refer to girder(s) for truss to truss connections.  
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.  
6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J40	Jack-Closed Girder	2	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162742

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 21068154050481  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_170-tKfnEJX7jBcKvTt1FOHh0dRLoYrvX\_H?Z\_zS7zbkqJ




Plate Offsets (X, Y)-- [2:0-2-1,0-2-0], [4:Edge,0-4-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.78	Vert(LL)	-0.00	5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.01	Vert(CT)	-0.00	5	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.02	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P	Wind(LL)	0.00	5	****	Weight: 15 lb	FT = 10%



LUMBER-	BRACING-
TOP CHORD 2x6 SPF 1650F 1.4E	TOP CHORD Structural wood sheathing directly applied or 1-7-4 oc purlins, except end verticals.
BOT CHORD 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 5=0-4-11, 4=Mechanical  
 Max Horz 5=92(LC 5)  
 Max Uplift 5=-278(LC 4), 4=-734(LC 21)  
 Max Grav 5=1327(LC 21), 4=123(LC 4)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-1313/286, 3-4=-142/748

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=278, 4=734.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Load case(s) 21 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard Except:  
 21) User defined: Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70(F), 2-3=-70(F), 4-5=-20(F)  
 Concentrated Loads (lb)  
 Vert: 1=-250



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017


Job 210331	Truss J41	Truss Type Jack-Open	Qty 2	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUBMITTALS**  
**04/06/2021**

J45162743

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-50000001



Scale = 1:15.3

<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.27	Vert(LL)	0.00	5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	-0.00	5	>999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.02	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R					Weight: 8 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 1-10-4 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
Max Horz 5=64(LC 5)  
Max Uplift 5=-107(LC 4), 3=-23(LC 5), 4=-12(LC 5)  
Max Grav 5=296(LC 1), 3=6(LC 19), 4=32(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-5=-270/132

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 5=107.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



Job 210331	Truss J42	Truss Type JACK-CLOSED GIRDER	Qty 1	Ply 1	Lot 102 RR
---------------	--------------	----------------------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUBMIT MISSOURI**  
**04/06/2021**

J45162744

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. H-11-150-01150-011

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-pjndCwKofKRKaDdG9gQlmRjn7bb6NqoaStT3W0zbkqH





Plate Offsets (X,Y)-- [3:Edge,0-2-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.83	Vert(LL)	0.00	5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.21	Vert(CT)	0.00	4-5	>999		
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	-0.00	5	>999		
								Weight: 12 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x6 SPF 1650F 1.4E	TOP CHORD Structural wood sheathing directly applied or 1-7-9 oc purlins, except end verticals.
BOT CHORD 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x6 SPF No.2 *Except* 3-4: 2x3 SPF No.2	

**REACTIONS.** (size) 5=0-4-11, 4=Mechanical  
 Max Horz 5=66(LC 7)  
 Max Uplift 5=-314(LC 4), 4=-846(LC 21)  
 Max Grav 5=1438(LC 21), 4=155(LC 4)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-1210/287, 3-4=-112/643

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=314, 4=846.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Load case(s) 21 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard Except:  
 21) User defined: Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70(F), 2-3=-70(F), 4-5=-20(F)  
 Concentrated Loads (lb)  
 Vert: 1=-250



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J44	Diagonal Hip Girder	1	1	

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 MISSOURI  
 04/06/2021

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)  
 ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-HvK0PGLQeZBBMCSI0x\_JfFys?wR6t2jhXCd2SzbkqG  
 Scale = 1:12.2




Plate Offsets (X, Y)--	[4:Edge,0-2-8]
------------------------	----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.83	Vert(LL) 0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.27	Vert(CT) 0.01	4-5	>999	240		
BCLL 0.0 *	Rep Stress Incr NO	WB 0.00	Horz(CT) -0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.00	4-5	>999	240		
							Weight: 19 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x6 SPF 1650F 1.4E  
 BOT CHORD 2x6 SPF No.2  
 WEBS 2x6 SPF No.2 \*Except\*  
 3-4: 2x3 SPF No.2



**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 3-4-1 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

**REACTIONS.** (size) 5=0-4-11, 4=Mechanical  
 Max Horz 5=85(LC 7)  
 Max Uplift 5=-231(LC 4), 4=-261(LC 37)  
 Max Grav 5=1000(LC 37), 4=100(LC 21)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-857/233

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=231, 4=261.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 7) Load case(s) 37 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 55 lb down and 28 lb up at 2-8-7 on top chord, and 14 lb down and 8 lb up at 2-8-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
  - 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard Except:  
 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70, 2-3=-70, 4-5=-20  
 Concentrated Loads (lb)  
 Vert: 7=8(F)



March 12, 2021

Continued on page 2

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J44	Diagonal Hip Girder	1	1	

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File Path: \\m157055018

ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-HvK0PGLQeZBBMCSiOx\_JfFys?wR6t2jhXCd2SzbkqG

**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEWIS & CLARK MISSOURI  
04/06/2021**

**LOAD CASE(S)**

37) User defined: Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70(F), 2-3=-70(F), 4-5=-20(F)

Concentrated Loads (lb)

Vert: 1=-250 7=8(F)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017



Job 210331	Truss J46	Truss Type Jack-Open	Qty 5	Ply 1	Lot 102 RR	<b>RELEASE FOR CONSTRUCTION</b> <b>AS NOTED ON PLANS REVIEW</b> <b>DEVELOPMENT SERVICES</b> <b>LEED SUBMITTALS ONLY</b> <b>04/06/2021</b>
Wheeler Lumber, Waverly, KS - 66871,		8.430 s Feb 12 2021 MiTek Industries, Inc. 151627748			Job Reference (optional) ID:Ej7EWovY_94Pzt7UVy1gWaz_t70-l5uOcbM2Bxh2pWneG5SDssoFDPJvrKlswByAbvzbkqF	





Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]							
<b>LOADING</b> (psf)	<b>SPACING-</b>	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	2-0-0	TC 0.28	Vert(LL) -0.00	4-5	>999	360	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.06	Vert(CT) -0.01	4-5	>999	240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT) -0.00	3	n/a	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Wind(LL) -0.00	4-5	>999	240	Weight: 10 lb	FT = 10%
	Code IRC2018/TPI2014							

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-2-8 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-3-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=49(LC 4)  
 Max Uplift 5=-76(LC 4), 3=-23(LC 8)  
 Max Grav 5=324(LC 1), 3=69(LC 1), 4=52(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-283/94

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 4) Refer to girder(s) for truss to truss connections.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	J47	Jack-Closed Girder	2	1	

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUBMITTALS SOURCE  
 04/06/2021

J45162749


Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. 1066158205081

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-l5uOcbM2Bxh2pWneG5SDsso7cPHurKlswByAbvzbkqF



Scale = 1:10.3



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.83	Vert(LL)	0.00	5	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	0.00	5	>999	MT18HS	197/144
BCLL 0.0 *	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-R	Wind(LL)	-0.00	5	>999		
								Weight: 13 lb	FT = 10%


LUMBER-	BRACING-
TOP CHORD 2x6 SPF 1650F 1.4E	TOP CHORD Structural wood sheathing directly applied or 1-10-2 oc purlins, except end verticals.
BOT CHORD 2x6 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x6 SPF No.2 *Except*	
3-4: 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-4-11, 4=Mechanical  
 Max Horz 5=68(LC 7)  
 Max Uplift 5=-295(LC 4), 4=-731(LC 21)  
 Max Grav 5=1340(LC 21), 4=134(LC 4)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-1121/271, 3-4=-92/542

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) All plates are MT20 plates unless otherwise indicated.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Refer to girder(s) for truss to truss connections.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 5=295, 4=731.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 8) Load case(s) 21 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
  - 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

**LOAD CASE(S)** Standard Except:  
 21) User defined: Lumber Increase=1.15, Plate Increase=1.15  
 Uniform Loads (plf)  
 Vert: 1-2=-70(F), 2-3=-70(F), 4-5=-20(F)  
 Concentrated Loads (lb)  
 Vert: 1=-250



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss J48	Truss Type Jack-Open	Qty 4	Ply 1	Lot 102 RR
---------------	--------------	-------------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE H SUMMIT MISSOURI**  
**04/06/2021**

J45162750

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210681502550481

ID: Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-EISmqxNgyFpvRgMrqzSO4KQypfsanY09rhj7LzbkqE



Scale = 1:10.4

Plate Offsets (X,Y)--	[5:0-5-6,0-1-8]				
<b>LOADING</b> (psf)	<b>SPACING-</b> 2-0-0	<b>CSI.</b>	<b>DEFL.</b> in (loc) l/defl L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL 1.15	TC 0.28	Vert(LL) 0.00 4-5 >999 360	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.08	Vert(CT) 0.00 4-5 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.00	Horz(CT) -0.00 3 n/a n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-R	Wind(LL) -0.00 5 >999 240	Weight: 8 lb	FT = 10%


<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 2-0-8 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	

**REACTIONS.** (size) 5=0-5-8, 3=Mechanical, 4=Mechanical  
 Max Horz 5=52(LC 4)  
 Max Uplift 5=-133(LC 4), 3=-15(LC 8), 4=-5(LC 1)  
 Max Grav 5=302(LC 1), 3=10(LC 1), 4=27(LC 3)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-5=-260/137

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 4 except (jt=lb) 5=133.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss LAY1	Truss Type GABLE	Qty 1	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE SUMMIT MISSOURI**  
**04/06/2021**

J45162751

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331-01-0001

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-63iHgJQB?UJLwHfc3e2OZwV7mQ04Wa?c3TfxG6zbnkqA



Scale = 1:36.3


<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.16	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.10	Horz(CT)	-0.00	8	n/a		
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-S						
								Weight: 46 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-9, 6-7.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 8-9.
WEBS 2x4 SPF No.2 *Except* 5-9: 2x3 SPF No.2	
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 9-2-9.  
 (lb) - Max Horz 1=277(LC 8)  
 Max Uplift All uplift 100 lb or less at joint(s) 1, 9, 8, 11, 10 except 12=-135(LC 8)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 9, 8, 11, 10 except 12=277(LC 15)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-364/211

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
  - 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 3) Provide adequate drainage to prevent water ponding.
  - 4) All plates are 2x4 MT20 unless otherwise indicated.
  - 5) Gable requires continuous bottom chord bearing.
  - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 7) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 9, 8, 11, 10 except (jt=lb) 12=135.
  - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss LAY2	Truss Type GABLE	Qty 1	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------


Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. L. P. No. 12068204250481

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162752

Scale = 1:33.4




<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 25 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except: 6-0-0 oc bracing: 5-6.
WEBS 2x4 SPF No.2	
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 6-7-9.  
 (lb) - Max Horz 1=175(LC 8)  
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5, 8, 6 except 7=121(LC 8)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 8, 6 except 7=271(LC 15)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Gable requires continuous bottom chord bearing.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5, 8, 6 except (jt=lb) 7=121.
  - 6) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 5, 7, 6.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	LAY3	GABLE	2	1	

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)


**RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW**

J45162753

**DEVELOPMENT SERVICES**

**LEFLO SUMMIT, MISSOURI**

**04/06/2021**




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.29	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.06	Horz(CT)	-0.00	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 31 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-3-12 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 5-3-12.  
 (lb) - Max Horz 1=254(LC 5)  
 Max Uplift All uplift 100 lb or less at joint(s) except 1=-125(LC 6), 5=-115(LC 7), 7=-197(LC 8), 6=-138(LC 8)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7, 6

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 1-2=-301/225

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Gable requires continuous bottom chord bearing.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 125 lb uplift at joint 1, 115 lb uplift at joint 5, 197 lb uplift at joint 7 and 138 lb uplift at joint 6.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss LAY4	Truss Type GABLE	Qty 2	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUMMIT, MISSOURI  
 04/06/2021

J45162754

Scale = 1:25.8

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)




Plate Offsets (X,Y)--	[3:0-1-3,Edge]
-----------------------	----------------


<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.04	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	-0.00	6	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 29 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 7-5-13.  
 (lb) - Max Horz 1=160(LC 8)  
 Max Uplift All uplift 100 lb or less at joint(s) 1, 6, 8, 9, 7 except 10=159(LC 8)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 6, 8, 10, 9, 7

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Provide adequate drainage to prevent water ponding.
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 6, 8, 9, 7 except (jt=lb) 10=159.
  - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 6, 7.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021

Job 210331	Truss LAY5	Truss Type GABLE	Qty 1	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK UNIVERSITY**  
**04/06/2021**

J45162755

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 2006200255-001

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-XeNPIKS3IPhvnIOBknc5AY7ICd18iwy2mRubtRzkbq7



Scale = 1:71.7

<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.15	Horz(CT)	0.01	7	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S					Weight: 99 lb	FT = 10%

**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x6 SPF No.2  
OTHERS 2x4 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
WEBS 1 Row at midpt 1-13, 2-12, 3-11

**REACTIONS.** All bearings 11-6-8.  
(lb) - Max Horz 13=592(LC 9)  
Max Uplift All uplift 100 lb or less at joint(s) 13 except 7=290(LC 7), 12=165(LC 9), 11=180(LC 9), 10=174(LC 9), 9=179(LC 9), 8=158(LC 9)  
Max Grav All reactions 250 lb or less at joint(s) 13, 12, 11, 10, 9, 8 except 7=743(LC 9)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
TOP CHORD 2-3=-252/120, 3-4=-433/193, 4-5=-609/266, 5-6=-791/343, 6-7=-940/404  
BOT CHORD 12-13=-247/591, 11-12=-247/591, 10-11=-247/591, 9-10=-247/591, 8-9=-247/591, 7-8=-247/591

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) All plates are 2x4 MT20 unless otherwise indicated.
  - 3) Gable requires continuous bottom chord bearing.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 13 except (jt=lb) 7=290, 12=165, 11=180, 10=174, 9=179, 8=158.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	LAY6	GABLE	1	1	


Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162756

Scale = 1:101.8




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.10	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.26	Horz(CT)	0.01	8	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 87 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 5-9: 2x3 SPF No.2	WEBS 1 Row at midpt 1-14, 2-13
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 8-5-15.  
 (lb) - Max Horz 14=387(LC 9)  
 Max Uplift All uplift 100 lb or less at joint(s) 14, 8 except 7=493(LC 7), 12=548(LC 9), 10=770(LC 7), 13=164(LC 9), 11=169(LC 9), 9=1288(LC 9)  
 Max Grav All reactions 250 lb or less at joint(s) 14, 8, 11 except 7=1068(LC 9), 12=373(LC 7), 10=1019(LC 9), 13=262(LC 16), 9=787(LC 7)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-261/124, 3-4=-450/202, 4-5=-596/256  
 BOT CHORD 13-14=-293/387, 12-13=-293/387, 11-12=-506/667, 10-11=-501/635, 9-10=-498/643  
 WEBS 5-7=-843/451, 5-9=-431/753

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Gable requires continuous bottom chord bearing.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14, 8 except (jt=lb) 7=493, 12=548, 10=770, 13=164, 11=169, 9=1288.
  - 6) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 10, 11, 9.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss LAY7	Truss Type GABLE	Qty 1	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**

J45162757  
 8.430 s Feb 12 2021 MiTek Industries, Inc.  
 ID:Ej7EWovY\_94Pz7UVy1gWAZ\_t70-T0VAj0UJq0xd03YZsCeZFzC?mRjzAqhLDkNixKzkbq5

Scale = 1:63.4





<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.08	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.13	Horz(CT)	0.01	6	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						
								Weight: 64 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	WEBS 1 Row at midpt 1-11, 2-10
OTHERS 2x4 SPF No.2	
WEDGE	
Right: 2x4 SPF No.2	

**REACTIONS.** All bearings 8-9-1.  
 (lb) - Max Horz 11=-477(LC 9)  
 Max Uplift All uplift 100 lb or less at joint(s) 11 except 10=-186(LC 9), 9=-172(LC 9), 6=-337(LC 7), 8=-185(LC 9), 7=-348(LC 9)  
 Max Grav All reactions 250 lb or less at joint(s) 11, 10, 9, 8, 7 except 6=812(LC 9)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 2-3=-264/126, 3-4=-439/195, 4-5=-626/275, 5-6=-940/406  
 BOT CHORD 10-11=-199/477, 9-10=-199/477, 8-9=-199/477, 7-8=-199/477, 6-7=-199/477  
 WEBS 5-7=-216/368

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) All plates are 2x4 MT20 unless otherwise indicated.
  - 3) Gable requires continuous bottom chord bearing.
  - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 5) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11 except (jt=lb) 10=186, 9=172, 6=337, 8=185, 7=348.
  - 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss LAY8	Truss Type GABLE	Qty 1	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEE'S SUMMIT MISSOURI  
 04/06/2021

J45162758

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 2018020205081




Plate Offsets (X, Y)--	[2:0-4-8,Edge], [4:0-2-3,Edge]
------------------------	--------------------------------


LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.08	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.08	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.14	Vert(CT) n/a - n/a 999		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.01 8 n/a n/a		
	Code IRC2018/TPI2014			Weight: 79 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 2-4.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	WEBS 1 Row at midpt 1-14, 2-13, 3-12
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 11-3-11.  
 (lb) - Max Horz 14=-477(LC 9)  
 Max Uplift All uplift 100 lb or less at joint(s) 14 except 8=-243(LC 7), 12=-227(LC 9), 11=-192(LC 9), 10=-173(LC 9), 9=-152(LC 9)  
 Max Grav All reactions 250 lb or less at joint(s) 14, 13, 12, 11, 10, 9 except 8=606(LC 9)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 TOP CHORD 4-5=-251/112, 5-6=-444/201, 6-7=-621/276, 7-8=-763/333  
 BOT CHORD 13-14=-201/476, 12-13=-201/476, 11-12=-201/476, 10-11=-201/476, 9-10=-201/476, 8-9=-201/476  
 WEBS 3-12=-156/250

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Provide adequate drainage to prevent water ponding.
  - 3) All plates are 2x4 MT20 unless otherwise indicated.
  - 4) Gable requires continuous bottom chord bearing.
  - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 6) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14 except (j=lb) 8=243, 12=227, 11=192, 10=173, 9=152.
  - 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
  - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



March 12, 2021


Job 210331	Truss LAY9	Truss Type GABLE	Qty 1	Ply 1	Lot 102 RR
---------------	---------------	---------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
 AS NOTED ON PLANS REVIEW  
**DEVELOPMENT SERVICES**  
 LEFF SUMMIT, MISSOURI  
 04/06/2021

J45162759

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File No: 210331; 10350181



Scale = 1:27.3




Plate Offsets (X,Y)--	[3:Edge,0-3-2]
-----------------------	----------------


<b>LOADING</b> (psf)	<b>SPACING-</b>	2-0-0	<b>CSI.</b>	<b>DEFL.</b>	in (loc)	l/defl	L/d	<b>PLATES</b>	<b>GRIP</b>
TCLL 25.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.03	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.03	Horz(CT)	0.00	5	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 23 lb	FT = 10%

<b>LUMBER-</b>	<b>BRACING-</b>
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SPF No.2	

**REACTIONS.** All bearings 6-1-8.  
 (lb) - Max Horz 1=103(LC 4)  
 Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 7=149(LC 8), 6=148(LC 9)  
 Max Grav All reactions 250 lb or less at joint(s) 1, 5, 7, 6

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
  - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - Gable requires continuous bottom chord bearing.
  - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 7=149, 6=148.
  - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017



Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	R1	Half Hip Girder	1	2	

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SILVER WISE CERT**  
**04/06/2021**

J4516Z760

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. File Path: \\mst101\0181210331\0181210331.dwg  
 ID:Ej7EWovY\_94Pzt7UVy1gWAz\_t70-p\_l3mkYSeYaw6qQXelEky1whGSD5ruf4N04TdXzkbq0

**NOTES-**

11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 754 lb down and 153 lb up at 1-7-12, 347 lb down and 24 lb up at 1-7-12, 1123 lb down and 185 lb up at 3-7-12, 754 lb down and 182 lb up at 3-7-12, 967 lb down and 31 lb up at 5-7-12, 754 lb down and 94 lb up at 5-7-12, 967 lb down and 70 lb up at 7-7-12, 754 lb down and 109 lb up at 7-7-12, 1051 lb down and 190 lb up at 9-7-12, 754 lb down and 109 lb up at 9-7-12, 1057 lb down and 163 lb up at 11-7-12, 754 lb down and 109 lb up at 11-7-12, 1057 lb down and 23 lb up at 13-7-12, 754 lb down and 109 lb up at 13-7-12, 1057 lb down and 163 lb down and 109 lb up at 15-7-12, 1053 lb down and 109 lb up at 17-7-12, 754 lb down and 109 lb up at 17-7-12, and 1062 lb down at 19-7-12, and 759 lb down and 104 lb up at 19-7-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

**LOAD CASE(S)** Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-70, 2-4=-70, 1-5=-20

Concentrated Loads (lb)

Vert: 7=-1812(F=-754, B=-1057) 9=-1101(F=-754, B=-347) 10=-1878(F=-754, B=-1123) 11=-1721(F=-754, B=-967) 12=-1721(F=-754, B=-967) 13=-1805(F=-754, B=-1051) 14=-1812(F=-754, B=-1057) 15=-1812(F=-754, B=-1057) 16=-1807(F=-754, B=-1053) 17=-1821(F=-759, B=-1062)

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017




Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	V2	Valley	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**

J45162762

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. ID: Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-mNqpBPZiAAqeM7avmAGC2S?AFF6JJ0gNqKZahQzbkq\_




LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.19	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.05	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P						
	Code IRC2018/TPI2014						Weight: 20 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	
OTHERS 2x3 SPF No.2	

**REACTIONS.** (size) 1=7-5-14, 4=7-5-14, 5=7-5-14  
 Max Horz 1=122(LC 5)  
 Max Uplift 4=-26(LC 8), 5=-102(LC 8)  
 Max Grav 1=81(LC 16), 4=141(LC 1), 5=384(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
 WEBS 2-5=-299/153

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Gable requires continuous bottom chord bearing.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=102.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021


Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	V3	Valley	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEWIS & CLARK MISSOURI**  
**04/06/2021**

J45162763

Scale = 1:14.7

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID: Ej7EWovY\_94Pzt7UVy1gWAz\_t70-EZ\_B0laKxTyVzH96KtnRafYIWFQb2TIW3\_J7Cszbkpz



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 25.0	Plate Grip DOL	1.15	TC 0.42	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.23	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 14 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-6-8 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 1=5-5-14, 3=5-5-14  
 Max Horz 1=86(LC 5)  
 Max Uplift 1=31(LC 8), 3=48(LC 8)  
 Max Grav 1=211(LC 1), 3=211(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021


Job 210331	Truss V4	Truss Type Valley	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEEO SUMMIT, MISSOURI**  
**04/06/2021**

J45162764

Scale = 1:10.1

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94PztUVy1gWAZ\_t70-iYZc5bzin4MbRkltb1g7i4Xq3oJnw?fle2gllzbpky



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.13	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.07	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Vert(CT) n/a - n/a 999		
BCDL 10.0	Rep Stress Incr YES	Matrix-P	Horz(CT) -0.00 3 n/a n/a		
	Code IRC2018/TPI2014			Weight: 8 lb	FT = 10%


LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 3-6-8 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 1=3-5-14, 3=3-5-14  
Max Horz 1=49(LC 5)  
Max Uplift 1=-18(LC 8), 3=-28(LC 8)  
Max Grav 1=121(LC 1), 3=121(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

Job 210331	Truss V5	Truss Type Valley	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------	----------	----------	------------

**RELEASE FOR**  
**CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**


J45162765

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. L. H. No. 1206821805081

ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-Ax6ypRbbT5CCDbJURlPv4dhOT8RWNFPWloEHkzbpX  
 3-8-0  
 3-8-0

Scale = 1:10.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
TCLL 25.0	Plate Grip DOL	1.15	TC 0.14	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 8 lb	FT = 10%

**LUMBER-**  
 TOP CHORD 2x4 SPF No.2  
 BOT CHORD 2x4 SPF No.2  
 WEBS 2x3 SPF No.2

**BRACING-**  
 TOP CHORD Structural wood sheathing directly applied or 3-8-0 oc purlins, except end verticals.  
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 1=3-7-6, 3=3-7-6  
 Max Horz 1=52(LC 5)  
 Max Uplift 1=-18(LC 8), 3=-29(LC 8)  
 Max Grav 1=126(LC 1), 3=126(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

**Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd  
 Chesterfield, MO 63017


Job 210331	Truss V6	Truss Type Valley	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------	----------	----------	------------

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**

J45162766

Scale = 1:15.0

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_i70-Ax6ypRbbT5CCDbJURlpvf4dddT6sWNFpWloEHkzbpX



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.44	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.24	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P					Weight: 14 lb	FT = 10%
	Code IRC2018/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-8-0 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 1=5-7-6, 3=5-7-6  
 Max Horz 1=88(LC 5)  
 Max Uplift 1=32(LC 8), 3=49(LC 8)  
 Max Grav 1=216(LC 1), 3=216(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021


Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	V7	Valley	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEFLO SUMMIT, MISSOURI**  
**04/06/2021**

J45162767

Wheeler Lumber, Waverly, KS - 66871,

8.430 s Feb 12 2021 MiTek Industries, Inc. ID:Ej7EWovY\_94Pzt7UVy1gWaz\_t70-e8gK1ncDEOK3qluh?0K8CH9rAtTEFfylyXnpBzbpw



Scale = 1:19.0

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.20	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.05	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P						
	Code IRC2018/TPI2014						Weight: 20 lb	FT = 10%


**LUMBER-**  
TOP CHORD 2x4 SPF No.2  
BOT CHORD 2x4 SPF No.2  
WEBS 2x3 SPF No.2  
OTHERS 2x3 SPF No.2

**BRACING-**  
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS.** (size) 1=7-7-6, 4=7-7-6, 5=7-7-6  
Max Horz 1=124(LC 5)  
Max Uplift 4=-25(LC 8), 5=-103(LC 8)  
Max Grav 1=86(LC 16), 4=140(LC 1), 5=389(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.  
WEBS 2-5=-303/155

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Gable requires continuous bottom chord bearing.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 5=103.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


16023 Swingley Ridge Rd  
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Lot 102 RR
210331	V8	Valley	1	1	

**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEE'S SUMMIT, MISSOURI**  
**04/06/2021**

J45162768

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. File Name: 210331.dwg  
 ID:Ej7EWovY\_94Pzt7UVy1gWAZ\_t70-6KDIE7dr?iSwSvTzjsNIV?ifGpc\_HE6\_cHLLdzbkpv  
 5-8-8 5-8-8




LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.28	Vert(LL)	0.01	1	n/r	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.09	Vert(CT)	-0.01	1	n/r		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.03	Horz(CT)	-0.00	5	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-R						
	Code IRC2018/TPI2014						Weight: 19 lb	FT = 10%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-8-8 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* 4-5: 2x3 SPF No.2	
OTHERS 2x3 SPF No.2	

**REACTIONS.** (size) 7=5-8-8, 5=5-8-8, 6=5-8-8  
 Max Horz 7=124(LC 5)  
 Max Uplift 7=-102(LC 4), 5=-28(LC 4), 6=-76(LC 8)  
 Max Grav 7=248(LC 1), 5=153(LC 1), 6=232(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
  - 2) Gable requires continuous bottom chord bearing.
  - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
  - 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
  - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 6 except (jt=lb) 7=102.
  - 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**  
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
 16023 Swingley Ridge Rd  
 Chesterfield, MO 63017

Job 210331	Truss V9	Truss Type Valley	Qty 1	Ply 1	Lot 102 RR
---------------	-------------	----------------------	----------	----------	------------


**RELEASE FOR CONSTRUCTION**  
**AS NOTED ON PLANS REVIEW**  
**DEVELOPMENT SERVICES**  
**LEED SUMMIT MISSOURI**

J45162769

04/06/2021

Scale = 1:13.9

Wheeler Lumber, Waverly, KS - 66871, 8.430 s Feb 12 2021 MiTek Industries, Inc. Job Reference (optional)  
 ID:Ej7EWovY\_94PztUVy1gWAZ\_t70-6KDE7dr?ISwSvTtZjsNIVix?Gmi\_Hl6\_cHLLdzbkpv



LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	2-0-0	TC 0.51	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.28	Vert(CT)	n/a	-	n/a		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.00	Horz(CT)	-0.00	3	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P					Weight: 15 lb	FT = 10%
	Code IRC2018/TPI2014							

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-2-8 oc purlins, except end verticals.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x3 SPF No.2	

**REACTIONS.** (size) 1=6-1-12, 3=6-1-12  
 Max Horz 1=77(LC 5)  
 Max Uplift 1=38(LC 4), 3=49(LC 8)  
 Max Grav 1=232(LC 1), 3=232(LC 1)

**FORCES.** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

**NOTES-**

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) \* This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



March 12, 2021

# Symbols

**RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI**



**PLATE LOCATION AND ORIENTATION**  
Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.

For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in **MITek 20/20 software or upon request.**

## PLATE SIZE


**4 X 4**  
The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

## LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

## BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

## Industry Standards:

- ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
- DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.
- BCSI:

# Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



**JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.**

**CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.**

## PRODUCT CODE APPROVALS

- ICC-ES Reports:  
ESR-1311, ESR-1352, ESR1988  
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved

# General Safety Notes

**Failure to Follow Could Cause Property Damage or Personal Injury**

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative T or I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020