

## **DEVELOPMENT SERVICES**

Building Permit - Commercial	Permit No: PRCOM20210969
Project Title: MILAN LASER HAIR REMOVAL	Date Issued: April 12, 2021
Work Desc: CHANGE OF TENANT	

Project Address: Permit Holder:

1728 NW CHIPMAN RD, LEES SUMMIT, MO 64081 Goebel and Company DBA Goebel Mitts Construction

6600 College Blvd. Suite 320 Overland Park , KS 66211

**Legal Description**: CHIPMAN HWY 50--- LOT 12

Parcel No: 51700031300000000

County: JACKSON

# **Activities Included for this Project:**

zChange of Tenant, License Tax, License Tax Credit, Alarm Permit, Sprinkler Permit,

THIS PERMIT IS ISSUED IN RELIANCE UPON INFORMATION SUBMITED BY THE APPLICANT. THE BUILDING OFFICIAL MAY SUSPEND OR REVOKE WHENEVER THE PERMIT IS ISSUED IN ERROR, OR ON THE BASIS OF INCORRECT INFORMATION SUPPLIED, OR IN VIOLATION OF ANY ADOPTED CODE, CITY ORDINANCE OR REGULATIONS.

NOTICE: THE DISPOSAL OF DEMOLITION WASTE IS REGULATED BY THE DEPARTMENT OF NATURAL RESOURCES UNDER CHAPTER 260 RSMO. SUCH WASTE, IN TYPES AND QUANTITIES ESTABLISHED BY THE DEPARTMENT, SHALL BE TAKEN TO A DEMOLITION LANDFILL OR A SANITARY LANDFILL FOR DISPOSAL.

## **CONDITIONS**

One or more divisions have conditions that have not been addressed during the review period. The outstanding conditions provided below shall be met as indicated during the construction period.

## Fire Plan Review

- 2018 IFC 907.1.1- Construction documents. Construction documents for fire alarm systems shall be submitted for review and approval prior to system installation. Construction documents shall include, but not be limited to, all of the following: 1. A floor plan which indicates the use of all rooms. 2. Locations of alarm-initiating and notification appliances.
- 3. Alarm control and trouble signaling equipment. 4. Annunciation. 5. Power connection. 6. Battery calculations. 7. Conductor type and sizes. 8. Voltage drop calculations. 9. Manufacturers, model numbers and listing information for equipment, devices and materials. 10. Details of ceiling height and construction. 11. The interface of fire safety control functions.

(Action Required)

Any modifications to the fire alarm system, provide PE stamped electronic shop drawings to mike.weissenbach@cityofls.net

#### 3/22/2021

Deferred submittal

2 2018 IFC 901.2- Construction documents. The fire code official shall have the authority to require construction documents and calculations for all fire protection systems and to require permits be issued for the installation, rehabilitation or modification of any fire protection system. Construction documents for fire protection systems shall be submitted for review and approval prior to system installation. (Action Required)

Any modifications to the fire sprinkler system, provide PE stamped electronic shop drawings to mike.weissenbach@cityofls.net

3/22/2021 Deferred Submittal

2018 IFC 901.5- Installation acceptance testing. Fire detection and alarm systems, fire-extinguishing systems, fire hydrant systems, fire standpipe systems, fire pump systems, private fire service mains and all other fire protection systems and appurtenances thereto shall be subject to acceptance tests as contained in the installation standards and as approved by the fire code official. The fire code official shall be notified before any required acceptance testing. The fire code official shall be notified 48 hours before any required acceptance test.

(Informational Purposes)
Call (816)969-1300 to schedule testing.

Building Plan R	eview	
Licensed Contr	actors	
Licensed Conti	actors	
Signature of		
Applicant:		Date:
Print name:		Company Name: