

BUILDER/CONTRACTOR IS RESPONSIBLE TO CHECK ALL DIMENSIONS FOR ACCURACY BETWEEN FLOORS, FOUNDATION, AND ELEVATIONS. ALSO VERIFY ALL BEAM, HEADERS, PAD LOCATIONS, AND COLUMN SIZES.


FRONT ELEVATION

1/4" = 1'0"

NOTE:
ACTUAL ELEVATIONS MAY VARY FROM ARCHITECTURAL DRAWINGS, DUE TO TERRAIN/BACKFILL PROCESS
FRONT ELEVATION IS ARCHITECTURAL DRAWING AND MAY VARY DUE TO MATERIALS AVAILABILITY


ALL NOTES, SECTIONS, AND DRAWINGS SHALL BE IN ACCORDANCE WITH THE 2018 IRC

LOT 134 NAPA
1523 SW BLACKSTONE
LEES SUMMIT MO.




LEFT ELEVATION

1/8" = 1'0"



RIGHT ELEVATION

1/8" = 1'0"



REAR ELEVATION

1/8" = 1'0"

THE "WHITE TAIL"

KH-6107 (WHITE TAIL)

RELEASE FOR
CONSTRUCTION
AS NOTED ON PLANS REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
05/12/2021



SQUARE FOOTAGE

LIVING AREA
FIRST FLOOR = 1735
BASEMENT = 1248
UNFINISHED AREA
STORAGE BASEMENT = 328
GARAGE = 787

BUILDER/CONTRACTOR IS RESPONSIBLE TO CHECK ALL DIMENSIONS FOR ACCURACY BETWEEN FLOORS, FOUNDATION, AND ELEVATIONS. ALSO VERIFY ALL BEAM, HEADERS, PAD LOCATIONS, AND COLUMN SIZES. BUILDER/CONTRACTOR SHALL CHECK FOR CONFORMANCE WITH ALL APPLICABLE CODES AND REGULATIONS. BUILDER/CONTRACTOR ACCEPTS ALL RESPONSIBILITY FOR LOT PLACEMENT, SET BACKS, AND FLOOR PLANS. BUILDER/CONTRACTOR AND HOME OWNER ACCEPTS RESPONSIBILITY FOR ANY AND ALL COPYRIGHT INFRINGEMENTS OR RESUBMITTANCES TO OTHER COPYRIGHTED PLANS. BUILDER/CONTRACTOR ACCEPTS RESPONSIBILITY FOR ANY ON SITE CHANGES MADE TO STRUCTURE.

HOME BUYER:	PHONE:	DATE DRAWN:	PLAN NO.	SHEET NO.
BUILDER:	PHONE:	DATE REVISED:	KH-6107	1
SUB-DIVISION:	LOT NO.	DESIGNER:	FILE NAME:	APPROX. SQ.FT.
			6107 FRNT	6107 FRNT



S.D.
 = SMOKE DETECTOR

Diagram of a Grade Pad showing dimensions and materials:

- Width: 16"
- Materials: 4" CONCRETE, 4" ROCK
- Rebar: (2) #4 REBAR CONTINUOUS
- Scale: $1/2" = 1'0"$



Diagram illustrating the components and dimensions of a typical foundation wall:

- 3/4" STUDS
- FLOOR JOIST
- 1/2" ANCHOR ROD @ 36" O.C. (MIN. 7')
- TOP REBAR WITH 12" OF TOP OF WALL
- #4 REBAR @ 24" O.C. HORIZONTAL REBAR
- SEE FOUNDATION NOTES FOR VERTICAL REBAR
- 8" THICK FOUNDATION WALL
- CLEARANCE 1/2" FROM INSIDE WALL
- SOFT SLAB
- (2) #4 CONTINUOUS REBAR

TYPICAL FOUNDATION WALL

[illegible]

BASEMENT PLAN

HOME BUYER:	PHONE:	DATE DRAWN:	PLAN NO.	SHEET NO. 2
BUILDER:	PHONE:	DATE REVISED:	KH-6107	
SUB-DIVISION:	LOT NO.	DESIGNER:	FILE NAME:	APPROX. SQ.FT.
			6107 B5MT	

BUILDER/CONTRACTOR ACCEPTS RESPONSIBILITY FOR ANY ON SITE CHANGES MADE TO STRUCTURE.

BUILDER/CONTRACTOR ACCEPTS RESPONSIBILITY FOR ANY AND ALL COPYRIGHT INFRINGEMENTS OR RESIMILANCES TO THEIR COPYRIGHTED PLANS.

BUILDER/CONTRACTOR AND HOME OWNER ACCEPTS RESPONSIBILITY FOR ANY AND ALL COMPLIANCE WITH CONTRACTS, CITY, AND NATIONAL CODES. BUILDER/CONTRACTOR ACCEPTS ALL RESPONSIBILITY FOR SET BACKS, LOT SIZES, BUILDERS/CONTRACTOR TO CHECK FOR FLOOD LOCATIONS, AND COLUMN SIZES. BUILDER/CONTRACTOR ALSO VERIFY ALL BEAM, HEADERS, FOUNDATION, ELEVATIONS, AND SPACINGS.



RELEASE FOR
CONSTRUCTION
NOTED ON PLANS REVIEW
EVELOPMENT SERVICES
EE'S SUMMIT, MISSOURI

12/2021

SEE ELEVATION FOR WALL HEIGHTS

NOTE.. ELECTRICAL SERVICE TO BE 200 AMP.

NOTE.. DOUBLE JOIST UNDER ALL PARALLEL WALLS ABOVE UNLESS NOTED

S.D.
☐ = SMOKE DETECTOR

GENERAL HEADER SPECIFICATIONS:	
REQUIRED AREAS NEEDING HEADERS:	HEADER DESCRIPTIONS:
WINDOWS/DOORS UP TO 38" R.O.	(2) #2 D-FIR 2X10'S
WINDOWS/DOORS 38" UP TO 72" R.O.	(2) #2 D-FIR 2X10'S W/1/2" GLUE PLY
WINDOWS/DOORS 72" UP TO 96" R.O.	(2) 9 1/2" L.V.L.
80" GARAGE DOORS W/CEILING & ROOF LOAD	(2) 9 1/2" L.V.L.
90" GARAGE DOORS W/CEILING & ROOF LOAD	(2) 9 1/2" L.V.L.
80" GARAGE DOORS W/SECOND FLOOR	(2) 9 1/2" L.V.L.
90" GARAGE DOORS W/SECOND FLOOR	(2) 11 7/8" L.V.L.
160" GARAGE DOOR W/NO SECOND FLOOR	(2) 11 7/8" L.V.L.
160" GARAGE DOORS W/SECOND FLOOR	(2) 14" L.V.L.
USE HEADERS FOR OPENINGS ABOVE UNLESS SPECIFIED OTHERWISE.	

R312.2.1 Window sills.
In dwelling units, where the opening of an operable window is located more than 72 inches (1829 mm) above the finished grade or surface below, the lowest part of the clear opening of the window shall be a minimum of 24 inches (610 mm) above the finished floor of the room in which the window is located. Operable sections of windows shall not permit openings that allow passage of a 4-inch-diameter (102 mm) sphere where such openings are located within 24 inches (610 mm) of the finished floor.


Exceptions:
1. Windows whose openings will not allow a 4-inch-diameter (102 mm) sphere to pass through the opening when the opening is in its largest opened position.
2. Openings that are provided with window fall prevention devices that comply with ASTM F 2090.
3. Windows that are provided with window opening control devices that comply with Section R312.2.2.

R312.2.2 Window opening control devices.
Window opening control devices shall comply with ASTM F 2090. The window opening control device, after operation to release the control device allowing the window to fully open, shall not reduce the minimum net clear opening area of the window unit to less than the area required by Section R310.1.1.

Bathrooms, water closet compartments and other similar rooms shall be provided with aggregate glazing area in windows of not less than 3 square feet, one-half of which must be operable.

Exception:
The glazed areas shall not be required where artificial light and a local exhaust system are provided. The minimum local exhaust rates shall be determined in accordance with Section M1507. Exhaust air from the space shall be exhausted directly to the outdoors.

LOT 134 NAPA
1523 SW BLACKSTONE
LEES SUMMIT MO.



KH-6107 (WHITE TAIL)

ALL NOTES, SECTIONS, AND DRAWINGS SHALL BE IN ACCORDANCE WITH THE 2018 IRC

FIRST FLOOR PLAN
1/4" = 1'0"

HOME BUYER:	PHONE:	DATE DRAWN:	PLAN NO.	SHEET NO.
BUILDER:	PHONE:	DATE REVISED:	KH-6107	3
SUB-DIVISION:	LOT NO.	DESIGNER:	FILE NAME:	APPROX. SQ.FT.
			6107 FLR1	

BUILDER/CONTRACTOR IS RESPONSIBLE TO CHECK ALL DIMENSIONS FOR ACCURACY BETWEEN FLOORS, FOUNDATION AND ELEVATIONS. ALSO VERIFY ALL BEAM, HEADERS, COLUMNS, AND COLUMN SIZES. BUILDER/CONTRACTOR TO CHECK FOR CONFLICTS WITH EXISTING STRUCTURE. BUILDER/CONTRACTOR TO CHECK FOR CONFLICTS WITH EXISTING UTILITIES. BUILDER/CONTRACTOR TO CHECK FOR CONFLICTS WITH EXISTING LOT PLACEMENT, SET BACKS, AND FLOOD PLANS. BUILDER/CONTRACTOR AND HOME OWNER ACCEPTS RESPONSIBILITY FOR ANY AND ALL COPYRIGHT INFRINGEMENTS OR RESEMBLANCES TO OTHER COPYRIGHTED PLANS. BUILDER/CONTRACTOR ACCEPTS RESPONSIBILITY FOR ANY ON SITE CHANGES MADE TO STRUCTURE.



Foundation Wall Reinforcement Schedule - Table 2


Vertical reinforcement spacing 60 psf soil						
Concrete strength/Grade	8 inch thick wall			10 inch thick wall		
Reinforcement #4 bar	8'	9'	10'	8'	9'	10'
3,000 psi / Grade 40	16	12	NP	24	16	12
3,500 psi / Grade 40	16	12	NP	24	24	12
3,000 psi / Grade 60	24	16	NP	24	20	16
3,500 psi / Grade 60	24	16	NP	24	24	16
Horizontal reinforcement – Minimum Grade 40 steel #4 bar						
One bar 12" from top of wall; maximum spacing 24" o.c.	4-#4	5-#4	6-#4	4-#4	5-#4	6-#4

- Footnotes:
- Wall height is measured from the top of the wall to the top of the floor slab.
 - Vertical reinforcement for concrete walls that are not full height and for reinforcement spaced 24 inch on center may be placed in the middle of the wall. Other walls shall have vertical reinforcement place as follows:
 - 8-inch wall - Minimum 5 inches from the outside face.
 - 10-inch wall - Minimum 6.75 inches from the outside face.
 - Extend bars to within 8 inches of the top of the wall.
 - Reinforcement clearances:
 - Concrete exposed to earth – minimum 1-1/2 inches.
 - Not exposed to weather (interior side of walls) – minimum 3/4 inch.
 - Concrete exposed to weather (top clearance in garage and driveway slabs) - 1-1/2 inches.
 - Horizontal reinforcement:
 - One bar shall be placed within 12 inches of the top of the wall.
 - Other bars shall be equally spaced with spacing not to exceed 24 inches on center.
 - Horizontal bars should be as close to the tension face as possible (interior) and behind the vertical reinforcement (i.e.2" towards the inside).
 - Supplemental reinforcement at corners - Place 1 #4 bar 48 inches long at 45 degree angle at corners of openings per Figure 4a. Place reinforcement within 6" of the edge of inside corners
 - Reinforcement shall be lapped a minimum 24 inches at ends, splices, and around corners.
 - At masonry ledges the minimum wall thickness shall be 3-1/2 inches. Ledges shall not exceed a depth of more than 24 inches below the top of the wall. For wall thicknesses less than 4 inches provide #4 bars at maximum 24 inches on center to within 8 inches of the top of the wall.
 - Straight walls more than 5 feet tall and more than 16 feet long shall be provided with exterior braced return walls. Wall length shall be measured using inside the shortest dimension between intersecting walls (See 7/S2).


TABLE PB02.1C(3) FASTENER SCHEDULE FOR STRUCTURAL MEMBERS

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENERS ^{a, b, c}	SPACING OF FASTENERS
Roof			
1	Blocking between joists or rafters to top plate, toe nail	3-8d (2 1/2" x 0.133")	---
2	Ceiling joists to plate, toe nail	3-8d (2 1/2" x 0.133")	---
3	Ceiling joists not attached to parallel rafter, laps over partitions, face nail	3-10d	---
4	Collar tie to rafter, face nail or 1 1/4" x 20 gage ridge strap	3-10d (3" x 0.125")	---
5	Rafter or roof truss to plate, toe nail	3-16d box nails (3/4" x 0.125") or 3-16d common (3" x 0.148")	2 toe nails on one side and 1 toe nail on opposite side of each rafter or truss
6	Roof rafters to ridge, valley or hip rafters: toe nail face nail	4-16d (3 1/2" x 0.135") 3-16d (3 1/2" x 0.135")	---
Wall			
7	Build-up studs-face nail	10d (3" x 0.128")	24" o.c.
8	Blocking studs at intersecting wall corners, face nail	16d (3 1/2" x 0.135")	12" o.c.
9	Build-up header, two pieces with 1/2" spacer	16d (3 1/2" x 0.135")	16" o.c. along each edge
10	Continued header, two pieces	16d (3 1/2" x 0.135")	16" o.c. along each edge
11	Continuous header to stud, toe nail	4-8d (2 1/2" x 0.125")	---
12	Double study, face nail	10d (3" x 0.128")	24" o.c.
13	Double top plates, face nail	10d (3" x 0.128")	24" o.c.
14	Double top plates, minimum 24-inch offset of end joints, face nail in lapped area	8-16d (3 1/2" x 0.135")	---
15	Sole plate to joist or blocking, face nail	16d (3 1/2" x 0.135")	16" o.c.
16	Sole plate to joist or blocking at braced wall panels	3-16d (3 1/2" x 0.135")	16" o.c.
17	Stud to sole plate, toe nail	3-8d (2 1/2" x 0.133") or 3-16d (3 1/2" x 0.135")	---
18	Top or sole plate to stud, end nail	2-16d (3 1/2" x 0.135")	---
19	Top plates, laps at corners and intersections, face nail	2-10d (3" x 0.125")	---
20	1" brace to each stud and plate, face nail	2-8d (2 1/2" x 0.125") 2 staples 1 3/4" x 1"	---
21	1" x 6" sheathing to each bearing, face nail	2-8d (2 1/2" x 0.125") 2 staples 1 3/4" x 1"	---
22	1" x 8" sheathing to each bearing, face nail	2-8d (2 1/2" x 0.125") 3 staples 1 3/4" x 1"	---
23	Wider than 1" x 8" sheathing to each bearing, face nail	3-8d (2 1/2" x 0.125") 4 staples 1 3/4" x 1"	---
Floor			
24	Joist to sill or girder, toe nail	3-8d (2 1/2" x 0.125")	---
25	Rim joist to top plate, toe nail (roof applications also)	8d (2 1/2" x 0.125")	6" o.c.
26	Rim joist or blocking to sill plate, toe nail	8d (2 1/2" x 0.125")	6" o.c.
27	1" x 6" subfloor or less to each joist, face nail	2-8d (2 1/2" x 0.125") 2 staples 1 3/4" x 1"	---
28	2" subfloor to joist or girder, blind and face nail	2-16d (3 1/2" x 0.135")	---
29	2" planks (plank & beam - floor & roof)	2-16d (3 1/2" x 0.135")	at each bearing
30	Build-up girders and beams, 2-inch lumber layers	10d (3" x 0.128")	Nail each layer as follows: 32" o.c. at top and bottom and staggered. Two nails at ends and at each splice.
31	Ledger strip supporting joists or rafters	3-16d (3 1/2" x 0.135")	At each joist or rafter


OVER CONCRETE OR MASONRY BLOCK FOUNDATION



OVER RAISED WOOD FLOORS OR SECOND FLOOR – FRAMING ANCHOR OPTION



OVER RAISED WOOD FLOORS OR SECOND FLOOR – WOOD STRUCTURAL PANEL OVERLAP OPTION



CF-PF WALL BRACING SECTION

LOT 134 NAPA
1523 SW BLACKSTONE
LEES SUMMIT MO.

NOTE... HIP RIDGE FOR THE MAIN ROOF AS:
2X8 FOR UNBRACED LENGTH UP TO 9'0"
2X10 FOR UNBRACED LENGTH UP TO 10'0"
2X12 FOR UNBRACED LENGTH UP TO 12'0"

ALL RAFTERS TO BE #2 2X6 D-FIR 16" O.C.
UNLESS OTHERWISE NOTED

PURLING RAFTERS TO BEARING WALL LINES

CONNECT RAFTERS TO CEILING JOIST W (4) 16d GALV. NAILS
CONNECT RAFTERS TO RIDGE, VALLEY, AND HIP RIDGE
WITH (4) 16d GALV. NAILS

VERT. RIDGE AND RAFTER SUPPORTS TO BE EQUAL TO OR GREATER
THAN THE DEPTH OF RAFTERS



ROOF ELEVATION


1/4" = 1'0"

ROOF DESIGNED WITH:
LIVE LOAD = 20 PSF
DEAD LOAD = 10 PSF

ALL NOTES, SECTIONS, AND DRAWINGS SHALL
BE IN ACCORDANCE WITH THE 2018 IRC




BUILDER/CONTRACTOR IS RESPONSIBLE TO CHECK ALL DIMENSIONS FOR ACCURACY
BETWEEN FLOORS, FOUNDATION AND ELEVATIONS ALSO VERIFY ALL BEAM, HEADERS,
PAIL LOCATIONS, AND COLUMN SIZES. BUILDER/CONTRACTOR TO CHECK FOR
COMPLIANCE WITH CONTRACTS CITY, AND NATIONAL CODES. BUILDER/CONTRACTOR
RESPECTOR AND MUST PROVIDE PERMITS, SETBACKS, AND FLOOD PLANS.
BUILDER/CONTRACTOR AND MUST PROVIDE PERMITS, SETBACKS, AND FLOOD PLANS.
BUILDER/CONTRACTOR ACCEPTS RESPONSIBILITY FOR ANY ON SITE CHANGES MADE
TO STRUCTURE.



OPTION-1
FRONT ELEVATION
1/4" = 1'0"

LOT 134 NAPA
1523 SW BLACKSTONE
LEES SUMMIT MO.



OPTION-2
FRONT ELEVATION
1/4" = 1'0"

THE "WHITE TAIL"

KH-6107 (WHITE TAIL)

HOME BUYER:	PHONE:	DATE DRAWN:	PLAN NO.	SHEET NO.
BUILDER:	PHONE:	DATE REVISED:	KH-6107	8
SUB-DIVISION:	LOT NO.	DESIGNER:	FILE NAME:	APPROX. SQ.FT.
			6107 FRN2	

BUILDER/CONTRACTOR IS RESPONSIBLE TO CHECK ALL DIMENSIONS FOR ACCURACY BETWEEN FLOORS, FOUNDATION, AND ELEVATIONS. ALSO VERIFY ALL BEAM, HEADERS, JOIST LOCATIONS, AND COLUMN SIZES. BUILDER/CONTRACTOR SHALL CHECK FOR CONFLICTS WITH EXISTING UTILITIES AND STRUCTURES. BUILDER/CONTRACTOR ACCEPTS ALL RESPONSIBILITY FOR LOT PLACEMENT, SET BACKS, AND FLOOR PLANS. BUILDER/CONTRACTOR AND HOME OWNER ACCEPTS RESPONSIBILITY FOR ANY AND ALL COPYRIGHT INFRINGEMENTS OR RESUBMITTALS TO OTHER COPYRIGHTED PLANS. BUILDER/CONTRACTOR ACCEPTS RESPONSIBILITY FOR ANY ON SITE CHANGES MADE TO STRUCTURE.

