



MiTek USA, Inc.
16023 Swingley Ridge Rd
Chesterfield, MO 63017
314-434-1200

Re: 2765833
Summit/#8 Osage

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Builders FirstSource (Valley Center).

Pages or sheets covered by this seal: I45804333 thru I45804396

My license renewal date for the state of Missouri is December 31, 2021.

Missouri COA: Engineering 001193



April 23, 2021

Johnson, Andrew ,Engineer

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804333
2765833	A1	GABLE	2	1		
Job Reference (optional)						

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:32 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-Bnkg6CXelsWfJ3T90ZZ7MQsRc5GWem7KzGCqG2zNtez

18-1-11 18-1-11 19-4-8 1-2-13 38-10-8 19-6-0 39-9-0 0-10-8

6.00 12 5x5 =

Scale = 1:70.6




Plate Offsets (X,Y)--	[12:0-3-0,Edge], [21:0-1-9,Edge], [24:0-3-8,Edge]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.43	Vert(LL)	-0.00	25	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.23	Vert(CT)	-0.00	25	n/r	120		
BCLL 0.0	Rep Stress Incr	YES	WB 0.16	Horz(CT)	0.02	24	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 257 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-12.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2	WEBS 1 Row at midpt 1-47, 13-36, 11-37, 10-39, 9-40, 7-41, 6-42, 5-43, 4-44, 3-45, 2-46, 14-35
OTHERS 2x4 SPF No.2	
WEDGE	
Right: 2x4 SPF No.2	

REACTIONS.	
All bearings 38-10-8.	
(lb) - Max Horz 47=315(LC 10)	
Max Uplift All uplift 100 lb or less at joint(s) 47, 36, 37, 39, 40, 41, 42, 43, 44, 45, 46, 35, 33, 32, 31, 30, 29, 28, 27, 26, 24	
Max Grav All reactions 250 lb or less at joint(s) 47, 36, 37, 39, 40, 41, 42, 43, 44, 45, 46, 35, 33, 32, 31, 30, 29, 28, 27, 26, 24	

FORCES.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD 17-18=281/179, 18-19=331/196, 19-20=382/214, 20-22=432/231, 22-23=484/250, 23-24=580/289	
BOT CHORD 46-47=240/502, 45-46=240/502, 44-45=240/502, 43-44=240/502, 42-43=240/502, 41-42=240/502, 40-41=240/502, 39-40=240/502, 37-39=240/502, 36-37=240/502, 35-36=240/502, 33-35=240/502, 32-33=240/502, 31-32=240/502, 30-31=240/502, 29-30=240/502, 28-29=240/502, 27-28=240/502, 26-27=240/502, 24-26=240/502	

NOTES-	
1) Unbalanced roof live loads have been considered for this design.	
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Corner(3E) 0-1-12 to 4-0-6, Exterior(2N) 4-0-6 to 19-4-8, Corner(3R) 19-4-8 to 23-4-8, Exterior(2N) 23-4-8 to 39-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.	
4) Provide adequate drainage to prevent water ponding.	
5) All plates are 2x4 MT20 unless otherwise indicated.	
6) Gable requires continuous bottom chord bearing.	
7) Gable studs spaced at 2-0-0 oc.	
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 47, 36, 37, 39, 40, 41, 42, 43, 44, 45, 46, 35, 33, 32, 31, 30, 29, 28, 27, 26, 24.	
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.	
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.	



April 23,2021

<p>WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.</p> <p>Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601</p>	<p>MiTek</p> <p>16023 Swingley Ridge Rd Chesterfield, MO 63017</p>
--	---

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804334
2765833	A3	ROOF SPECIAL	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:07 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-fWLVSAybVcwi0ReuaQhLHppJkC7rLSbT0DAA?WzNteQ

8-0-5	15-9-3	19-4-8	25-10-6	32-4-5	38-10-8	39-9-0
8-0-5	7-8-13	3-7-5	6-5-14	6-5-14	6-6-3	0-10-8

Scale = 1:71.2




Plate Offsets (X,Y)-- [3:0-5-8,0-3-0]											
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-0.11 15-16	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.54	Vert(CT)	-0.22 15-16	>846	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.75	Horz(CT)	0.02 8	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 191 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-2-2 oc purlins, except end verticals, and 2-0-0 oc purlins (5-7-10 max.): 1-3.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 1-16, 1-15, 4-13, 3-13

REACTIONS.

(size) 16=Mechanical, 13=0-3-8, 8=0-3-8
Max Horz 16=-363(LC 8)
Max Uplift 16=-206(LC 8), 13=-259(LC 13), 8=-205(LC 13)
Max Grav 16=535(LC 25), 13=2164(LC 1), 8=959(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-16=-464/228, 3-4=0/571, 4-5=-531/262, 5-7=-1245/362, 7-8=-1407/294
BOT CHORD 15-16=-200/354, 13-15=-496/320, 10-12=0/616, 8-10=-168/1147
WEBS 1-15=-196/329, 2-15=-641/274, 3-15=-156/926, 4-13=-1304/216, 4-12=-261/908, 5-12=-730/329, 5-10=-194/665, 7-10=-371/227, 3-13=-813/282

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 4-0-6, Interior(1) 4-0-6 to 19-4-8, Exterior(2R) 19-4-8 to 23-3-2, Interior(1) 23-3-2 to 39-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 16=206, 13=259, 8=205.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:08 2021 Page 1

ID:Slx.lxd784vT GMBI ZatyrsZzbhoN-8ivHfWzDGw2YdbD477Dag0l ZXbQE4_5dEtwiXzzNteP



TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-3.	
BOT CHORD	Rigid ceiling directly applied. Except: 4-1-0 oc bracing: 4-14	
WEBS	1 Row at midpt	5-13, 6-13



(size) 19=Mechanical, 14=0-3-8, 9=0-3-8
 max Horz 19=-307(LC 8)
 max Uplift 19=-243(LC 8), 14=-180(LC 12), 9=-283(LC 13)
 max Grav 19=589(LC 25), 14=1954(LC 1), 9=1035(LC 1)


TOP CHORD 1-19=531/257, 1-2=403/200, 2-3=405/201, 3-4=0/398, 4-5=288/348, 5-6=346/319,
6-8=1229/442, 8-9=1532/471

BOT CHORD 18-19=149/287, 14-16=1870/229, 4-16=1300/88, 13-14=250/85, 11-13=133/772,
9-11=322/1295


WEBS 1-18=274/504, 2-18=517/220, 3-16=587/177, 3-18=0/537, 4-13=12/1009,
6-13=819/313, 6-11=83/569, 8-11=412/222

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 4-0-6, Interior(1) 4-0-6 to 19-4-8, Exterior(2R) 19-4-8 to 23-3-2, Interior(1) 23-3-2 to 39-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 19=243, 14=180, 9=283.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.





Scale = 1:81.2



5-4-5	13-3-0	15-4-12	19-4-8	29-1-5	38-10-8
5-4-5	7-10-11	2-1-12	3-11-12	9-8-13	9-9-3

Plate Offsets (X,Y)-- [3:0-6-0,0-1-14], [16:0-3-0,0-3-4]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.22	16-17	>837	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.72	Vert(CT)	-0.43	16-17	>421	180	MT18HS	197/144
BCLL	0.0	Rep Stress Incr	YES	WB	0.49	Horz(CT)	0.03	14	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 183 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-3.
BOT CHORD	Rigid ceiling directly applied. Except: 1 Row at midpt 4-16 3-11-0 oc bracing: 14-16
WEBS	1 Row at midpt 5-13, 6-13

REACTIONS.

(size) 18=Mechanical, 14=0-3-8, 9=0-3-8
 Max Horz 18=-268(LC 8)
 Max Uplift 18=-224(LC 8), 14=-172(LC 12), 9=-290(LC 13)
 Max Grav 18=584(LC 25), 14=2001(LC 1), 9=1032(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-484/191, 3-4=0/449, 4-5=-290/366, 5-6=-340/335, 6-8=-1222/457, 8-9=-1525/487
BOT CHORD 17-18=-83/482, 16-17=-135/274, 14-16=-1957/203, 4-16=-1445/123, 13-14=-287/61,
11-13=-147/767, 9-11=-335/1289
WEBS 2-18=-610/257, 3-17=0/400, 3-16=-613/196, 6-13=-820/313, 6-11=-82/569,
8-11=-412/221, 4-13=0/1001

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDF=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 4-0-6, Interior(1) 4-0-6 to 19-4-8, Exterior(2R) 19-4-8 to 23-3-2, Interior(1) 23-3-2 to 39-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 18=224, 14=172, 9=290.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021



WARNING – Velly design parameters are listed below and included with the key reference to AISC M14-15 16f, 17f, 18f, 19f, 20f, 21f, 22f, 23f, 24f, 25f, 26f, 27f, 28f, 29f, 30f, 31f, 32f, 33f, 34f, 35f, 36f, 37f, 38f, 39f, 40f, 41f, 42f, 43f, 44f, 45f, 46f, 47f, 48f, 49f, 50f, 51f, 52f, 53f, 54f, 55f, 56f, 57f, 58f, 59f, 60f, 61f, 62f, 63f, 64f, 65f, 66f, 67f, 68f, 69f, 70f, 71f, 72f, 73f, 74f, 75f, 76f, 77f, 78f, 79f, 80f, 81f, 82f, 83f, 84f, 85f, 86f, 87f, 88f, 89f, 90f, 91f, 92f, 93f, 94f, 95f, 96f, 97f, 98f, 99f, 100f, 101f, 102f, 103f, 104f, 105f, 106f, 107f, 108f, 109f, 110f, 111f, 112f, 113f, 114f, 115f, 116f, 117f, 118f, 119f, 120f, 121f, 122f, 123f, 124f, 125f, 126f, 127f, 128f, 129f, 130f, 131f, 132f, 133f, 134f, 135f, 136f, 137f, 138f, 139f, 140f, 141f, 142f, 143f, 144f, 145f, 146f, 147f, 148f, 149f, 150f, 151f, 152f, 153f, 154f, 155f, 156f, 157f, 158f, 159f, 160f, 161f, 162f, 163f, 164f, 165f, 166f, 167f, 168f, 169f, 170f, 171f, 172f, 173f, 174f, 175f, 176f, 177f, 178f, 179f, 180f, 181f, 182f, 183f, 184f, 185f, 186f, 187f, 188f, 189f, 190f, 191f, 192f, 193f, 194f, 195f, 196f, 197f, 198f, 199f, 200f, 201f, 202f, 203f, 204f, 205f, 206f, 207f, 208f, 209f, 210f, 211f, 212f, 213f, 214f, 215f, 216f, 217f, 218f, 219f, 220f, 221f, 222f, 223f, 224f, 225f, 226f, 227f, 228f, 229f, 230f, 231f, 232f, 233f, 234f, 235f, 236f, 237f, 238f, 239f, 240f, 241f, 242f, 243f, 244f, 245f, 246f, 247f, 248f, 249f, 250f, 251f, 252f, 253f, 254f, 255f, 256f, 257f, 258f, 259f, 260f, 261f, 262f, 263f, 264f, 265f, 266f, 267f, 268f, 269f, 270f, 271f, 272f, 273f, 274f, 275f, 276f, 277f, 278f, 279f, 280f, 281f, 282f, 283f, 284f, 285f, 286f, 287f, 288f, 289f, 290f, 291f, 292f, 293f, 294f, 295f, 296f, 297f, 298f, 299f, 300f, 301f, 302f, 303f, 304f, 305f, 306f, 307f, 308f, 309f, 310f, 311f, 312f, 313f, 314f, 315f, 316f, 317f, 318f, 319f, 320f, 321f, 322f, 323f, 324f, 325f, 326f, 327f, 328f, 329f, 330f, 331f, 332f, 333f, 334f, 335f, 336f, 337f, 338f, 339f, 340f, 341f, 342f, 343f, 344f, 345f, 346f, 347f, 348f, 349f, 350f, 351f, 352f, 353f, 354f, 355f, 356f, 357f, 358f, 359f, 360f, 361f, 362f, 363f, 364f, 365f, 366f, 367f, 368f, 369f, 370f, 371f, 372f, 373f, 374f, 375f, 376f, 377f, 378f, 379f, 380f, 381f, 382f, 383f, 384f, 385f, 386f, 387f, 388f, 389f, 390f, 391f, 392f, 393f, 394f, 395f, 396f, 397f, 398f, 399f, 400f, 401f, 402f, 403f, 404f, 405f, 406f, 407f, 408f, 409f, 410f, 411f, 412f, 413f, 414f, 415f, 416f, 417f, 418f, 419f, 420f, 421f, 422f, 423f, 424f, 425f, 426f, 427f, 428f, 429f, 430f, 431f, 432f, 433f, 434f, 435f, 436f, 437f, 438f, 439f, 440f, 441f, 442f, 443f, 444f, 445f, 446f, 447f, 448f, 449f, 450f, 451f, 452f, 453f, 454f, 455f, 456f, 457f, 458f, 459f, 460f, 461f, 462f, 463f, 464f, 465f, 466f, 467f, 468f, 469f, 470f, 471f, 472f, 473f, 474f, 475f, 476f, 477f, 478f, 479f, 480f, 481f, 482f, 483f, 484f, 485f, 486f, 487f, 488f, 489f, 490f, 491f, 492f, 493f, 494f, 495f, 496f, 497f, 498f, 499f, 500f, 501f, 502f, 503f, 504f, 505f, 506f, 507f, 508f, 509f, 510f, 511f, 512f, 513f, 514f, 515f, 516f, 517f, 518f, 519f, 520f, 521f, 522f, 523f, 524f, 525f, 526f, 527f, 528f, 529f, 530f, 531f, 532f, 533f, 534f, 535f, 536f, 537f, 538f, 539f, 540f, 541f, 542f, 543f, 544f, 545f, 546f, 547f, 548f, 549f, 550f, 551f, 552f, 553f, 554f, 555f, 556f, 557f, 558f, 559f, 560f, 561f, 562f, 563f, 564f, 565f, 566f, 567f, 568f, 569f, 570f, 571f, 572f, 573f, 574f, 575f, 576f, 577f, 578f, 579f, 580f, 581f, 582f, 583f, 584f, 585f, 586f, 587f, 588f, 589f, 590f, 591f, 592f, 593f, 594f, 595f, 596f, 597f, 598f, 599f, 600f, 601f, 602f, 603f, 604f, 605f, 606f, 607f, 608f, 609f, 610f, 611f, 612f, 613f, 614f, 615f, 616f, 617f, 618f, 619f, 620f, 621f, 622f, 623f, 624f, 625f, 626f, 627f, 628f, 629f, 630f, 631f, 632f, 633f, 634f, 635f, 636f, 637f, 638f, 639f, 640f, 641f, 642f, 643f, 644f, 645f, 646f, 647f, 648f, 649f, 650f, 651f, 652f, 653f, 654f, 655f, 656f, 657f, 658f, 659f, 660f, 661f, 662f, 663f, 664f, 665f, 666f, 667f, 668f, 669f, 670f, 671f, 672f, 673f, 674f, 675f, 676f, 677f, 678f, 679f, 680f, 681f, 682f, 683f, 684f, 685f, 686f, 687f, 688f, 689f, 690f, 691f, 692f, 693f, 694f, 695f, 696f, 697f, 698f, 699f, 700f, 701f, 702f, 703f, 704f, 705f, 706f, 707f,



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804337
2765833	A6	ROOF SPECIAL	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:11 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-YHaQHY?5ZrQ7U3xpFmHRfz?cpRnHJA3xr8O8IzNteM

7-9-3	13-3-0	18-2-8	20-6-8	26-7-12	32-8-15	38-10-8	39-9-0
7-9-3	5-5-13	4-11-8	2-4-0	6-1-4	6-1-4	6-1-9	0-10-8

Scale = 1:78.7




Plate Offsets (X,Y)-- [2:0-8-0,0-1-14]		7-9-3 7-9-3		13-3-0 5-5-13	15-4-12 2-1-12	18-2-8 2-9-12	20-6-8 2-4-0	29-8-5 9-1-13	38-10-8 9-2-3
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.89	Vert(LL)	-0.16	9-11	>999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.73	Vert(CT)	-0.34	9-11	>819	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.52	Horz(CT)	0.03	14	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						
				Weight: 185 lb		FT = 20%			

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-2-3 oc purlins, except end verticals, and 2-0-0 oc purlins (2-8-10 max.): 1-2, 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 13-14.
5-11-0 oc bracing: 3-14
WEBS 1 Row at midpt 2-16, 5-13, 6-13, 4-14

REACTIONS.

(size) 19=Mechanical, 14=0-3-8, 9=0-3-8
Max Horz 19=223(LC 8)
Max Uplift 19=162(LC 8), 14=248(LC 12), 9=269(LC 13)
Max Grav 19=522(LC 25), 14=2068(LC 1), 9=1023(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-19=451/185, 1-2=521/207, 2-3=0/530, 3-4=0/453, 4-5=286/311, 5-6=421/301,
6-8=1232/413, 8-9=1509/437
BOT CHORD 17-18=136/521, 16-17=136/521, 14-16=902/354, 3-16=510/273, 11-13=118/796,
9-11=298/1260
WEBS 1-18=207/484, 2-16=873/224, 6-13=756/287, 6-11=80/527, 8-11=357/211,
4-13=152/954, 4-14=1146/27

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 4-0-6, Interior(1) 4-0-6 to 18-2-8, Exterior(2E) 18-2-8 to 20-6-8, Exterior(2R) 20-6-8 to 24-5-2, Interior(1) 24-5-2 to 39-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 19=162, 14=248, 9=269.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017



Scale = 1:73.3




Plate Offsets (X,Y)-- [2:0-4-0-0-1-14], [18:0-0-0-0-2-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	-0.13	12-14	>999	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.69	Vert(CT)	-0.29	12-14	>972	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.55	Horz(CT)	0.03	15	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 186 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (5-10-9 max.): 1-2, 4-5.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 4-15, 5-14, 6-14, 7-14

REACTIONS.

(size) 21=Mechanical, 15=0-3-8, 10=0-3-8
 Max Horz 21=192(LC 13)
 Max Uplift 21=117(LC 12), 15=322(LC 12), 10=249(LC 13)
 Max Grav 21=516(LC 25), 15=2098(LC 1), 10=988(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-21=466/134, 1-2=845/190, 2-3=286/153, 3-4=0/531, 4-5=186/260, 5-6=207/290,
6-7=-317/242, 7-9=1137/356, 9-10=1458/410

BOT CHORD 19-20=232/857, 17-18=135/436, 15-16=311/125, 14-15=369/156, 12-14=99/797,
10-12=274/1237

WEBS 1-20=197/813, 15-17=1976/332, 4-17=1530/208, 4-14=162/1126, 7-14=787/280,
7-12=48/510, 9-12=384/205, 3-19=0/324, 2-19=709/185, 3-17=670/213

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCFL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 4-0-6, Interior(1) 4-0-6 to 15-6-8, Exterior(2E) 15-6-8 to 19-6-8, Interior(1) 19-6-8 to 21-4-8, Exterior(2R) 21-4-8 to 25-3-2, Interior(1) 25-3-2 to 39-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 21=117, 15=322, 10=249.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021



WARNING – Velly design parameters are listed below and included with the key reference to AISC M14-15 16f, 17f, 18f, 19f, 20f, 21f, 22f, 23f, 24f, 25f, 26f, 27f, 28f, 29f, 30f, 31f, 32f, 33f, 34f, 35f, 36f, 37f, 38f, 39f, 40f, 41f, 42f, 43f, 44f, 45f, 46f, 47f, 48f, 49f, 50f, 51f, 52f, 53f, 54f, 55f, 56f, 57f, 58f, 59f, 60f, 61f, 62f, 63f, 64f, 65f, 66f, 67f, 68f, 69f, 70f, 71f, 72f, 73f, 74f, 75f, 76f, 77f, 78f, 79f, 80f, 81f, 82f, 83f, 84f, 85f, 86f, 87f, 88f, 89f, 90f, 91f, 92f, 93f, 94f, 95f, 96f, 97f, 98f, 99f, 100f, 101f, 102f, 103f, 104f, 105f, 106f, 107f, 108f, 109f, 110f, 111f, 112f, 113f, 114f, 115f, 116f, 117f, 118f, 119f, 120f, 121f, 122f, 123f, 124f, 125f, 126f, 127f, 128f, 129f, 130f, 131f, 132f, 133f, 134f, 135f, 136f, 137f, 138f, 139f, 140f, 141f, 142f, 143f, 144f, 145f, 146f, 147f, 148f, 149f, 150f, 151f, 152f, 153f, 154f, 155f, 156f, 157f, 158f, 159f, 160f, 161f, 162f, 163f, 164f, 165f, 166f, 167f, 168f, 169f, 170f, 171f, 172f, 173f, 174f, 175f, 176f, 177f, 178f, 179f, 180f, 181f, 182f, 183f, 184f, 185f, 186f, 187f, 188f, 189f, 190f, 191f, 192f, 193f, 194f, 195f, 196f, 197f, 198f, 199f, 200f, 201f, 202f, 203f, 204f, 205f, 206f, 207f, 208f, 209f, 210f, 211f, 212f, 213f, 214f, 215f, 216f, 217f, 218f, 219f, 220f, 221f, 222f, 223f, 224f, 225f, 226f, 227f, 228f, 229f, 230f, 231f, 232f, 233f, 234f, 235f, 236f, 237f, 238f, 239f, 240f, 241f, 242f, 243f, 244f, 245f, 246f, 247f, 248f, 249f, 250f, 251f, 252f, 253f, 254f, 255f, 256f, 257f, 258f, 259f, 260f, 261f, 262f, 263f, 264f, 265f, 266f, 267f, 268f, 269f, 270f, 271f, 272f, 273f, 274f, 275f, 276f, 277f, 278f, 279f, 280f, 281f, 282f, 283f, 284f, 285f, 286f, 287f, 288f, 289f, 290f, 291f, 292f, 293f, 294f, 295f, 296f, 297f, 298f, 299f, 300f, 301f, 302f, 303f, 304f, 305f, 306f, 307f, 308f, 309f, 310f, 311f, 312f, 313f, 314f, 315f, 316f, 317f, 318f, 319f, 320f, 321f, 322f, 323f, 324f, 325f, 326f, 327f, 328f, 329f, 330f, 331f, 332f, 333f, 334f, 335f, 336f, 337f, 338f, 339f, 340f, 341f, 342f, 343f, 344f, 345f, 346f, 347f, 348f, 349f, 350f, 351f, 352f, 353f, 354f, 355f, 356f, 357f, 358f, 359f, 360f, 361f, 362f, 363f, 364f, 365f, 366f, 367f, 368f, 369f, 370f, 371f, 372f, 373f, 374f, 375f, 376f, 377f, 378f, 379f, 380f, 381f, 382f, 383f, 384f, 385f, 386f, 387f, 388f, 389f, 390f, 391f, 392f, 393f, 394f, 395f, 396f, 397f, 398f, 399f, 400f, 401f, 402f, 403f, 404f, 405f, 406f, 407f, 408f, 409f, 410f, 411f, 412f, 413f, 414f, 415f, 416f, 417f, 418f, 419f, 420f, 421f, 422f, 423f, 424f, 425f, 426f, 427f, 428f, 429f, 430f, 431f, 432f, 433f, 434f, 435f, 436f, 437f, 438f, 439f, 440f, 441f, 442f, 443f, 444f, 445f, 446f, 447f, 448f, 449f, 450f, 451f, 452f, 453f, 454f, 455f, 456f, 457f, 458f, 459f, 460f, 461f, 462f, 463f, 464f, 465f, 466f, 467f, 468f, 469f, 470f, 471f, 472f, 473f, 474f, 475f, 476f, 477f, 478f, 479f, 480f, 481f, 482f, 483f, 484f, 485f, 486f, 487f, 488f, 489f, 490f, 491f, 492f, 493f, 494f, 495f, 496f, 497f, 498f, 499f, 500f, 501f, 502f, 503f, 504f, 505f, 506f, 507f, 508f, 509f, 510f, 511f, 512f, 513f, 514f, 515f, 516f, 517f, 518f, 519f, 520f, 521f, 522f, 523f, 524f, 525f, 526f, 527f, 528f, 529f, 530f, 531f, 532f, 533f, 534f, 535f, 536f, 537f, 538f, 539f, 540f, 541f, 542f, 543f, 544f, 545f, 546f, 547f, 548f, 549f, 550f, 551f, 552f, 553f, 554f, 555f, 556f, 557f, 558f, 559f, 560f, 561f, 562f, 563f, 564f, 565f, 566f, 567f, 568f, 569f, 570f, 571f, 572f, 573f, 574f, 575f, 576f, 577f, 578f, 579f, 580f, 581f, 582f, 583f, 584f, 585f, 586f, 587f, 588f, 589f, 590f, 591f, 592f, 593f, 594f, 595f, 596f, 597f, 598f, 599f, 600f, 601f, 602f, 603f, 604f, 605f, 606f, 607f, 608f, 609f, 610f, 611f, 612f, 613f, 614f, 615f, 616f, 617f, 618f, 619f, 620f, 621f, 622f, 623f, 624f, 625f, 626f, 627f, 628f, 629f, 630f, 631f, 632f, 633f, 634f, 635f, 636f, 637f, 638f, 639f, 640f, 641f, 642f, 643f, 644f, 645f, 646f, 647f, 648f, 649f, 650f, 651f, 652f, 653f, 654f, 655f, 656f, 657f, 658f, 659f, 660f, 661f, 662f, 663f, 664f, 665f, 666f, 667f, 668f, 669f, 670f, 671f, 672f, 673f, 674f, 675f, 676f, 677f, 678f, 679f, 680f, 681f, 682f, 683f, 684f, 685f, 686f, 687f, 688f, 689f, 690f, 691f, 692f, 693f, 694f, 695f, 696f, 697f, 698f, 699f, 700f, 701f, 702f, 703f, 704f, 705f, 706f, 707f,



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804339
2765833	A8	ROOF SPECIAL	1	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:14 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-ysGZwZ2_smpilWgEU0J_3HbdH0VvUbEVdpN2lczNteJ

2-5-3	7-7-13	12-10-8	16-10-8	21-4-8	27-2-6	33-0-5	38-10-8	39-9-0
2-5-3	5-2-11	5-2-11	4-0-0	4-6-0	5-9-14	5-9-14	5-10-3	0-10-8

Scale = 1:68.7




Plate Offsets (X,Y)-- [5:0-4-0,0-1-14]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP
TCLL	25.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	-0.10 12-14 >999	240	MT20 197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.58	Vert(CT)	-0.22 12-14 >999	180	
BCLL	0.0	Rep Stress Incr	YES	WB	0.88	Horz(CT)	0.02 10 n/a	n/a	
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS					
Weight: 181 lb									FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2, 4-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-16, 6-14, 7-14

REACTIONS.

(size) 21=Mechanical, 16=0-3-8, 10=0-3-8
Max Horz 21=171(LC 17)
Max Uplift 21=78(LC 12), 16=380(LC 12), 10=205(LC 13)
Max Grav 21=484(LC 25), 16=2246(LC 1), 10=929(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-442/146, 3-4=-24/450, 4-5=-51/693, 6-7=-297/175, 7-9=-1079/289, 9-10=-1346/317
BOT CHORD 20-21=-215/593, 19-20=-106/328, 16-19=-350/264, 14-16=-421/235, 12-14=-19/678, 10-12=-193/1136
WEBS 2-20=-306/141, 3-20=0/323, 3-19=-627/203, 4-19=-103/442, 4-16=-976/245, 5-16=-1266/255, 5-14=-106/1043, 7-14=-732/284, 7-12=-81/498, 9-12=-365/202, 2-21=-643/175

NOTES-

- 1) 2x4 SPF No.2 bearing block 12" long at jt. 16 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be SPF No.2.
- 2) Unbalanced roof live loads have been considered for this design.
- 3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 2-5-3, Interior(1) 2-5-3 to 12-10-8, Exterior(2E) 12-10-8 to 16-10-8, Interior(1) 16-10-8 to 21-4-8, Exterior(2R) 21-4-8 to 25-3-2, Interior(1) 25-3-2 to 39-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 4) Provide adequate drainage to prevent water ponding.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 21 except (jt=lb) 16=380, 10=205.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804340
2765833	A9	ROOF SPECIAL	2	1		
Job Reference (optional)						

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:16 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-vEOJLF3ENN3QbqqcbpMS8ihq0q6dySvo46s9pVzNteH

-0-10-8 4-3-12 8-4-0 8-11-0 11-5-8 12-4-0 19-6-0 25-3-14 31-1-13 37-0-0 37-10-8
0-10-8 4-3-12 4-0-4 0-7-0 2-6-8 0-10-8 7-2-0 5-9-14 5-9-14 5-10-3 0-10-8

Scale = 1:66.7




Plate Offsets (X,Y)--												[5:0-3-0,Edge], [6:0-9-12,0-2-12], [10:Edge,0-3-1], [17:0-4-12,Edge], [18:0-8-4,0-3-8]											
LOADING (psf)				SPACING- 2-0-0				CSI.				DEFL. in (loc) l/defl L/d				PLATES				GRIP			
TCLL 25.0				Plate Grip DOL 1.15				TC 0.91				Vert(LL) -0.42 16 >999 240				MT20				197/144			
TCDL 10.0				Lumber DOL 1.15				BC 0.95				Vert(CT) -0.75 14-15 >587 180											
BCLL 0.0				Rep Stress Incr YES				WB 1.00				Horz(CT) 0.37 10 n/a n/a											
BCDL 10.0				Code IRC2018/TPI2014				Matrix-S								Weight: 186 lb				FT = 20%			

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
5-6: 2x6 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
5-15: 2x4 SPF 1650F 1.5E
WEDGE
Right: 2x6 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
2-2-0 oc bracing: 17-18
9-11-10 oc bracing: 10-12.
WEBS 1 Row at midpt 5-15, 6-14, 7-14, 6-17

REACTIONS.

(size) 22=0-3-8, 10=0-3-8
Max Horz 22=-159(LC 13)
Max Uplift 22=-298(LC 12), 10=-285(LC 13)
Max Grav 22=1746(LC 1), 10=1732(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2095/366, 3-4=-4335/755, 4-5=-4798/801, 5-6=-5405/990, 6-7=-2025/448,
7-9=-2729/489, 9-10=-2960/489, 2-22=-1700/332
BOT CHORD 17-18=-638/3823, 12-14=-241/2166, 10-12=-345/2521
WEBS 4-18=-159/929, 5-17=-2838/615, 3-21=-1689/362, 4-17=-212/1205, 6-14=-135/257,
9-12=-273/196, 2-21=-252/1827, 7-14=-666/272, 7-12=-83/444, 18-21=-433/2151,
3-18=-284/2080, 14-17=-147/1761, 6-17=-783/4064

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-9-14, Interior(1) 2-9-14 to 8-4-0, Exterior(2E) 8-4-0 to 12-4-0, Interior(1) 12-4-0 to 19-6-0, Exterior(2R) 19-6-0 to 23-2-6, Interior(1) 23-2-6 to 37-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 22=298, 10=285.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804341
2765833	A10	Roof Special	2	1	Job Reference (optional)	


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:34 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-79rRWuZuGTmNYNcY8_bbRrxk1umM6aKdQahwKxzNtex

-0-10-8	5-8-0	9-8-0	14-7-0	19-6-0	24-5-0	25-3-14	31-1-13	37-0-0	37-10-8
0-10-8	5-8-0	4-0-0	4-11-0	4-11-0	4-11-0	0-10-14	5-9-14	5-10-3	0-10-8

Scale = 1:67.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.63	Vert(LL)	-0.23 14-16	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.91	Vert(CT)	-0.53 14-16	>832	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.56	Horz(CT)	0.12 10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 165 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x6 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (3-2-12 max.): 3-4.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-14, 7-14

REACTIONS.

(size) 18=0-3-8, 10=0-3-8
Max Horz 18=162(LC 17)
Max Uplift 18=308(LC 12), 10=287(LC 13)
Max Grav 18=1730(LC 1), 10=1719(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=2233/398, 3-4=2946/535, 4-5=3310/642, 5-6=1999/439, 6-7=2006/439,
7-9=2763/494, 9-10=2970/486, 2-18=1665/356
BOT CHORD 16-17=386/1939, 14-16=339/2217, 12-14=229/2104, 10-12=345/2567
WEBS 3-16=203/1408, 4-16=1759/392, 5-16=259/1135, 5-14=844/313, 6-14=263/1418,
7-14=675/289, 7-12=124/520, 9-12=343/215, 3-17=379/95, 2-17=255/1816

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-8-0, Exterior(2R) 5-8-0 to 8-8-0, Interior(1) 8-8-0 to 19-6-0, Exterior(2R) 19-6-0 to 22-6-0, Interior(1) 22-6-0 to 37-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 18=308, 10=287.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.




April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.76	Vert(LL) -0.21 12-14	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.81	Vert(CT) -0.42 16-17	>999	180		
BCLL 0.0	Rep Stress Incr NO	WB 0.93	Horz(CT) 0.14 10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-MS				Weight: 159 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
4-6,6-8: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF 1650F 1.5E *Except*
13-15: 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD	Structural wood sheathing directly applied or 2-8-11 oc purlins, except end verticals, and 2-0-0 oc purlins (4-4-5 max.): 3-4.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	1 Row at midpt 5-14, 7-14

REACTIONS.

(size) 18=0-3-8, 10=0-3-8
 Max Horz 18=-162(LC 13)
 Max Uplift 18=-326(LC 8), 10=-291(LC 9)
 Max Grav 18=1729(LC 1), 10=1719(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-1813/316, 3-4=-1566/304, 4-5=-2944/497, 5-6=-2039/382, 6-7=-2039/389,
7-9=-2661/442, 9-10=-2933/497, 2-18=-1737/314

BOT CHORD 16-17=-656/3331, 14-16=-438/2588, 12-14=-228/2348, 10-12=-354/2533

WEBS 6-14=-178/1220, 5-14=-1073/337, 7-14=-811/286, 7-12=0/381, 5-16=-45/589,
4-16=-847/248, 3-17=-41/523, 2-17=-255/1767, 4-17=-2116/374

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 18=326, 10=291.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 8) "NAILED" indicates 2-12d (0.148"x3.25") toe-nails per NDS guidelines.
- 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-70, 2-3=-70, 3-4=-70, 4-6=-70, 6-11=-70, 18-19=-20



April 23, 2021

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804342
2765833	A11	Roof Special Girder	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:35 2021 Page 2
ID:SlsJxd784vT_GMBLZatvrSzbhoN-bMPpkEaW1nuEAXBkih7q_3Utkl86rxqmfEQUtNzNtew

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 17=1(B)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2765833	Truss A12	Truss Type Common	Qty 6	Ply 1	Summit/#8 Osage	145804343
----------------	--------------	----------------------	----------	----------	-----------------	-----------

Builders FirstSource (Valley Center),


Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:37 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-YkXZ9wbNzO8yPqL7p69l3UZGG6p7J?J36YvaxGzNteu

-0-10-8	5-10-3	11-8-2	17-6-0	23-3-14	29-1-13	35-0-0	35-10-8
0-10-8	5-10-3	5-9-14	5-9-14	5-9-14	5-9-14	5-10-3	0-10-8

Scale = 1:61.1



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.57	Vert(LL)	-0.19 12-14	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.84	Vert(CT)	-0.40 12-14	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.29	Horz(CT)	0.13 10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 143 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x6 SPF No.2 , Right: 2x6 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-14, 5-14

REACTIONS.

(size) 2=0-3-8, 10=0-3-8
Max Horz 2=162(LC 12)
Max Uplift 2=280(LC 12), 10=280(LC 13)
Max Grav 2=1636(LC 1), 10=1636(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-2778/469, 3-5=-2530/444, 5-6=-1834/397, 6-7=-1834/397, 7-9=-2530/444, 9-10=-2778/469
BOT CHORD 2-16=-488/2395, 14-16=-323/2019, 12-14=-208/2019, 10-12=-327/2395
WEBS 6-14=-197/1178, 7-14=-701/281, 7-12=-73/433, 9-12=-316/194, 5-14=-701/280, 5-16=-73/433, 3-16=-316/194

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0, Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=280, 10=280.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2765833	Truss A13	Truss Type GABLE	Qty 4	Ply 1	Summit/#8 Osage 145804344
----------------	--------------	---------------------	----------	----------	------------------------------

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:39 2021 Page 1

ID:SlSjxd784vT_GMBLZatvSzboN-U7fKabd15?Ogf8VVxxBm8vejYvhlngwMasOh08zNtes

17-6-0
17-6-0

35-0-0
17-6-0

35-10-8
0-10-8

Scale = 1:61.1




Plate Offsets (X,Y)--		[1:0-3-8,Edge], [21:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07
TCDL 10.0	Lumber DOL	1.15	BC 0.03
BCLL 0.0	Rep Stress Incr	YES	WB 0.17
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-S
			DEFL. in (loc) l/defl L/d
			Vert(LL) -0.00 22 n/r 120
			Vert(CT) -0.00 22 n/r 120
			Horz(CT) 0.01 21 n/a n/a
			PLATES MT20
			GRIP 197/144
			Weight: 176 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

WEDGE

Left: 2x4 SPF No.2, Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 11-32

REACTIONS.

All bearings 35-0-0.

(lb) - Max Horz 1=-164(LC 13)

Max Uplift All uplift 100 lb or less at joint(s) 1, 33, 35, 36, 37, 38, 39, 40, 41, 31, 29, 28, 27, 26, 25, 24, 23, 21

Max Grav All reactions 250 lb or less at joint(s) 1, 32, 33, 35, 36, 37, 38, 39, 40, 41, 31, 29, 28, 27, 26, 25, 24, 23, 21

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 10-11=-111/295, 11-12=-111/295

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) 0-0-0 to 3-0-0, Exterior(2N) 3-0-0 to 17-6-0, Corner(3R) 17-6-0 to 20-6-0, Exterior(2N) 20-6-0 to 35-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 33, 35, 36, 37, 38, 39, 40, 41, 31, 29, 28, 27, 26, 25, 24, 23, 21.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804345
2765833	A14	Roof Special	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:41 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-QVm4?HeHddfOuSfu2yEEDKkuHjGDFn9f1Ato41zNteq

3-0-0	10-3-0	11-6-4	17-6-0	23-4-0	29-1-13	35-0-0	35-10-8
3-0-0	7-3-0	1-3-4	5-11-12	5-10-0	5-9-13	5-10-3	0-10-8

4x6 =

Scale = 1:65.4



3-0-0	11-6-4	17-6-0	23-4-0	27-1-14	29-1-13	35-0-0
3-0-0	8-6-4	5-11-12	5-10-0	3-9-14	1-11-15	5-10-3

Plate Offsets (X,Y)-- [2:0-6-0,0-2-6], [3:0-4-0,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.76	Vert(LL)	-0.11 16-17	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.45	Vert(CT)	-0.22 16-17	>610	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.36	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 155 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2.
 BOT CHORD Rigid ceiling directly applied.
 WEBS 1 Row at midpt 5-14, 4-16, 6-14, 2-16

REACTIONS.

(size) 18=Mechanical, 9=0-3-8, 16=0-3-8
 Max Horz 18=-172(LC 17)
 Max Uplift 18=-59(LC 12), 9=-216(LC 13), 16=-298(LC 12)
 Max Grav 18=331(LC 25), 9=987(LC 1), 16=1972(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-18=-339/49, 1-2=-487/73, 2-4=-88/618, 4-5=-430/227, 5-6=-416/200, 6-8=-997/269, 8-9=-1479/325
 BOT CHORD 16-17=-172/501, 14-16=-423/225, 12-14=-37/818, 11-12=-200/1247, 9-11=-200/1247
 WEBS 4-16=-1648/315, 4-14=-104/1002, 6-12=-41/410, 6-14=-771/269, 8-12=-494/187, 1-17=-105/592, 2-16=-795/231

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-0-0, Interior(1) 3-0-0 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0, Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 18 except (jt=lb) 9=216, 16=298.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804346
2765833	A15	Roof Special	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:42 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-ukSCdfvOwnFWbE4cglTmXG6R7a?_DAOgqLcTzNtep

5-8-0	9-4-8	11-6-4	13-5-4	17-6-0	23-3-14	26-0-15	29-1-13	35-0-0	35-10-8
5-8-0	3-8-8	2-1-12	1-11-0	4-0-12	5-9-14	2-9-1	3-0-14	5-10-3	0-10-8

4x6 =

Scale = 1:70.1



5-8-0	9-4-8	11-6-4	17-6-0	26-0-15	35-0-0
5-8-0	3-8-8	2-1-12	5-11-12	8-6-15	8-11-1

Plate Offsets (X,Y)--		[2:0-6-0,0-1-14], [16:0-8-8,0-2-0]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL 1.15		TC	0.54	Vert(LL)	-0.19 15-16	>725	240	MT20	197/144
TCDL	10.0	Lumber DOL 1.15		BC	0.61	Vert(CT)	-0.38 15-16	>364	180		
BCLL	0.0	Rep Stress Incr YES		WB	0.44	Horz(CT)	-0.03 13	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 159 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 15-16: 2x6 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and
 2-0-0 oc purlins (6-0-0 max.): 1-2.
 BOT CHORD Rigid ceiling directly applied.
 WEBS 1 Row at midpt 3-13, 5-12

REACTIONS.

(size) 8=0-3-8, 13=0-3-8, 16=Mechanical
 Max Horz 16=194(LC 13)
 Max Uplift 8=263(LC 13), 13=231(LC 12), 16=133(LC 8)
 Max Grav 8=1090(LC 1), 13=1696(LC 1), 16=467(LC 25)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-56/301, 3-4=-649/325, 4-5=-644/302, 5-7=-1396/406, 7-8=-1669/437
 BOT CHORD 15-16=-224/560, 10-12=-130/981, 8-10=-298/1421
 WEBS 2-15=-643/261, 2-16=-433/360, 13-15=-1602/271, 3-15=-1298/230, 3-12=0/788,
 5-12=-727/279, 5-10=-69/483, 7-10=-354/197

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed;
 MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0
 , Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces
 & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)
 8=263, 13=231, 16=133.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and
 referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum
 sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804347
2765833	A16	Roof Special	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:43 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-MuurPzgX9Ev67loGANGiJpK3XwpjY_xVUMv9vzNteo

4-3-12	8-4-0	9-4-8	11-6-4	13-5-4	23-3-14	25-4-11	29-1-13	35-0-0	35-10-8
4-3-12	4-0-4	1-0-8	2-1-12	1-11-0	9-10-10	2-0-12	3-9-2	5-10-3	0-10-8

4x6 =

Scale = 1:69.3



4-3-12	8-4-0	9-4-8	11-6-4	17-6-0	25-4-11	27-1-14	35-0-0
4-3-12	4-0-4	1-0-8	2-1-12	5-11-12	7-10-11	1-9-3	7-10-2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.36	Vert(LL)	-0.13 11-22	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.63	Vert(CT)	-0.27 11-22	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.92	Horz(CT)	-0.03 14	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 159 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-3.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-14, 6-13

REACTIONS.

(size) 18=Mechanical, 9=0-3-8, 14=0-3-8
Max Horz 18=-224(LC 8)
Max Uplift 18=-174(LC 8), 9=-265(LC 13), 14=-205(LC 12)
Max Grav 18=476(LC 25), 9=1093(LC 1), 14=1685(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-18=-454/178, 1-2=-425/145, 2-3=-427/147, 3-4=-51/281, 4-5=-649/328, 5-6=-650/306,
6-8=-1353/393, 8-9=-1668/444
BOT CHORD 11-13=-130/993, 9-11=-304/1423
WEBS 14-16=-1588/246, 4-16=-1224/189, 3-16=-419/111, 4-13=0/793, 2-17=-332/140,
1-17=-204/523, 3-17=0/296, 6-13=-738/274, 6-11=-54/470, 8-11=-376/202

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0, Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 18=174, 9=265, 14=205.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804348
2765833	A17	Roof Special	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:45 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-JH0bqfho9pN3yH0IA0AufhKcaBSYeyor0DozNtem

4-10-0	5-10-0	9-4-8	11-0-0	17-6-0	23-4-0	29-1-13	35-0-0	35-10-8
4-10-0	1-0-0	3-6-8	1-7-8	6-6-0	5-10-0	5-9-13	5-10-3	0-10-8

Scale = 1:69.3




Plate Offsets (X,Y)--	[3:0-6-0,0-5-4]
-----------------------	-----------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.41	Vert(LL)	-0.17 11-13	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.61	Vert(CT)	-0.35 11-13	>798	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.91	Horz(CT)	0.02 14	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 162 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-4.
 BOT CHORD Rigid ceiling directly applied.
 WEBS 1 Row at midpt 5-13, 4-14, 6-13

REACTIONS.

(size) 19=Mechanical, 9=0-3-8, 14=0-3-8
 Max Horz 19=-252(LC 8)
 Max Uplift 19=-153(LC 8), 9=-242(LC 13), 14=-213(LC 12)
 Max Grav 19=430(LC 25), 9=1059(LC 1), 14=1750(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-19=-372/166, 1-2=-264/130, 2-3=0/252, 3-4=-12/291, 4-5=-579/277, 5-6=-583/254,
 6-8=-1409/388, 8-9=-1622/386
 BOT CHORD 17-18=-24/286, 16-17=-26/374, 11-13=-93/917, 9-11=-255/1377
 WEBS 14-16=-1631/246, 4-16=-1272/232, 4-13=-37/904, 6-13=-714/286, 6-11=-97/519,
 8-11=-335/194, 1-18=-159/307, 2-16=-542/52

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0, Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 19=153, 9=242, 14=213.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804349
2765833	A18	Roof Special	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:47 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-Ff8LFKj2CTPXcN62PDKeTb_H8GOfMLXP6K6lhZNtek

5-10-0	9-4-8	13-8-0	17-6-0	23-3-14	29-1-13	35-0-0	35-10-8
5-10-0	3-6-8	4-3-8	3-10-0	5-9-14	5-9-14	5-10-3	0-10-8

6.00 | 12 4x6 =

Scale = 1:73.8




Plate Offsets (X,Y)--	[18:0-4-8,0-1-8]
-----------------------	------------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.47	Vert(LL)	-0.29 17-18	>465	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.66	Vert(CT)	-0.57 17-18	>239	180	MT20HS	148/108
BCLL 0.0	Rep Stress Incr	YES	WB 0.96	Horz(CT)	0.03 14	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 168 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 OTHERS 2x4 SPF No.2
 WEDGE
 Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
 2-0-0 oc purlins (6-0-0 max.): 1-4.
 BOT CHORD Rigid ceiling directly applied. Except:
 6-0-0 oc bracing: 3-14
 WEBS 1 Row at midpt 2-18, 2-16, 5-13, 6-13

REACTIONS.

(size) 14=0-3-8, 9=0-3-8, 18=Mechanical
 Max Horz 18=300(LC 8)
 Max Uplift 14=92(LC 12), 9=281(LC 13), 18=266(LC 8)
 Max Grav 14=1872(LC 1), 9=1019(LC 1), 18=355(LC 25)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=0/406, 3-4=0/418, 4-5=447/366, 5-6=493/341, 6-8=1264/445, 8-9=1529/470
 BOT CHORD 14-16=716/99, 3-16=305/139, 11-13=164/848, 9-11=328/1297
 WEBS 2-18=131/351, 2-16=547/0, 6-13=728/278, 6-11=69/502, 8-11=357/195,
 4-14=1031/120, 4-13=0/753

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0, Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14 except (jt=lb) 9=281, 18=266.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804350
2765833	A19	Common	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:48 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-jshkTgkgzmXOEWhEywst0oWAsYdbOpmgem4gq7zNtej

5-9-5	11-6-4	17-6-0	23-3-14	29-1-13	35-0-0	35-10-8
5-9-5	5-8-15	5-11-12	5-9-14	5-9-14	5-10-3	0-10-8

4x6 =

Scale = 1:63.2



5-9-5	11-6-4	17-6-0	26-2-13	35-0-0
5-9-5	5-8-15	5-11-12	8-8-13	8-9-3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.42	Vert(LL)	-0.11 11-13	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.59	Vert(CT)	-0.24 11-13	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.95	Horz(CT)	0.03 9	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 145 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x4 SPF No.2 , Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
 BOT CHORD Rigid ceiling directly applied.
 WEBS 1 Row at midpt 5-13, 6-13

REACTIONS.

(size) 1=Mechanical, 15=0-3-8, 9=0-3-8
 Max Horz 1=170(LC 13)
 Max Uplift 1=67(LC 12), 15=287(LC 12), 9=217(LC 13)
 Max Grav 1=407(LC 25), 15=1869(LC 1), 9=1022(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-462/97, 2-4=-33/461, 4-5=-500/224, 5-6=-498/209, 6-8=-1269/315, 8-9=-1534/342
 BOT CHORD 1-16=-139/354, 15-16=-139/354, 13-15=-332/223, 11-13=-44/851, 9-11=-215/1302
 WEBS 2-15=-611/210, 4-15=-1469/248, 4-13=-102/982, 6-13=-728/282, 6-11=-79/493,
 8-11=-357/201

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 17-6-0, Exterior(2R) 17-6-0 to 20-6-0, Interior(1) 20-6-0 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 15=287, 9=217.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804351
2765833	A20	HIP	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:50 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-fEpUtMlwVOn6Tqrd4LuM5DcOpLE0sjLz64Zmv?zNteh

3-11-0	6-11-0	9-5-8	16-2-0	18-10-0	24-2-9	29-7-2	35-0-0	35-10-8
3-11-0	3-0-0	2-6-8	6-8-8	2-8-0	5-4-9	5-4-9	5-4-14	0-10-8

Scale: 3/16"=1'




Plate Offsets (X,Y)-- [1:Edge,0-2-9], [2:0-5-8,0-2-4], [6:0-0-12,Edge], [7:0-2-12,0-0-12], [21:0-1-12,0-2-0]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	-0.51 18 >817 240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.92	Vert(CT)	-0.92 18 >457 180	MT20HS	148/108
BCLL	0.0	Rep Stress Incr	YES	WB	0.94	Horz(CT)	0.52 11 n/a n/a	MT18HS	197/144
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS				Weight: 181 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
4-6: 2x4 SP 2400F 2.0E, 6-7: 2x6 SPF No.2, 1-4: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2 *Except*
1-20: 2x4 SPF 1650F 1.5E, 18-19: 2x6 SPF 2100F 1.8E
WEBS 2x4 SPF No.2 *Except*
2-19: 2x4 SPF 1650F 1.5E

WEDGE
Left: 2x4 SPF No.2 , Right: 2x6 SPF No.2

REACTIONS. (size) 1=Mechanical, 11=0-3-8
Max Horz 1=-156(LC 13)
Max Uplift 1=-263(LC 12), 11=-283(LC 13)
Max Grav 1=1574(LC 1), 11=1637(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-2743/460, 2-3=-8218/1483, 3-5=-4903/856, 5-6=-4937/993, 6-7=-1674/405,
7-8=-1958/412, 8-10=-2571/455, 10-11=-2791/477
BOT CHORD 1-21=-490/2377, 3-19=-476/2561, 18-19=-1326/7313, 5-18=-393/230, 15-16=-137/1667,
13-15=-242/2086, 11-13=-338/2409
WEBS 3-18=-3125/622, 16-18=-175/1683, 6-18=-764/3554, 6-16=-630/217, 7-15=-139/575,
8-15=-619/251, 8-13=-61/393, 10-13=-272/176, 2-21=-2010/445, 19-21=-586/2816,
2-19=-876/5049

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-6-0, Interior(1) 3-6-0 to 16-2-0, Exterior(2E) 16-2-0 to 18-10-0, Exterior(2R) 18-10-0 to 23-9-6, Interior(1) 23-9-6 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) All plates are MT20 plates unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=263, 11=283.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Builders FirstSource (Valley Center), Valley Center, KS - 67147, 8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:51 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-7RNs5imZGhVz5_Qpe3PbdR8YzIb4bF87KklKR5SzNteg

6-9-3 13-6-0 17-6-0 21-6-0 28-2-13 35-0-0 35-10-8
6-9-3 6-8-13 4-0-0 4-0-0 6-8-13 6-9-3 0-10-8

Scale = 1:60




Plate Offsets (X,Y)-- [4:0-4-6,Edge]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.96	Vert(LL)	-0.15 11-12 >999 240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.86	Vert(CT)	-0.35 11-12 >999 180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.59	Horz(CT)	0.13 7 n/a n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S				Weight: 143 lb	FT = 20%

LUMBER-	
TOP CHORD	2x4 SPF No.2 *Except*
	3-4: 2x6 SPF No.2
BOT CHORD	2x4 SPF No.2
WEBS	2x4 SPF No.2
WEDGE	
Left: 2x4 SPF No.2 , Right: 2x4 SPF No.2	

BRACING-	
TOP CHORD	Structural wood sheathing directly applied, except 2-0-0 oc purlins (4-4-3 max.): 3-4.
BOT CHORD	Rigid ceiling directly applied or 8-8-9 oc bracing.
WEBS	1 Row at midpt 4-12

REACTIONS. (size) 1=Mechanical, 7=0-3-8
 Max Horz 1=-127(LC 17)
 Max Uplift 1=-268(LC 12), 7=-287(LC 13)
 Max Grav 1=1565(LC 1), 7=1638(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-281/473, 2-3=-2228/418, 3-4=-1895/414, 4-6=-2221/415, 6-7=-2811/460
BOT CHORD	1-14=-455/2408, 12-14=-453/3202, 11-12=-176/1888, 9-11=-313/2371, 7-9=-313/2371
WEBS	2-14=0/278, 2-12=-594/245, 3-12=-42/479, 4-11=-51/474, 6-11=-562/239, 6-9=0/274

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCFL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-12 to 3-0-12, Interior(1) 3-0-12 to 13-6-0, Exterior(2R) 13-6-0 to 17-8-15, Interior(1) 17-8-15 to 21-6-0, Exterior(2R) 21-6-0 to 25-8-15, Interior(1) 25-8-15 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=268, 7=287.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021



WARNING - Velly design parameters and READ NOTES ON THIS AND INCLUDED WITHIN KEY EXERCISE 1 AGE MH-475 (Rev. 3/19/2020) BEFORE USE. Design valid for use only with MITEK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804353
2765833	A22	Hip	2	1	Job Reference (optional)	


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:53 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrsZbhoN-4pVdWOopoJ9hKIZBITR3jsE_6ZGq3EvQo1nRVKzNtee

7-3-6	10-10-0	17-6-0	24-2-0	27-8-10	35-0-0	35-10-8
7-3-6	3-6-10	6-8-0	6-8-0	3-6-10	7-3-6	0-10-8

Scale = 1:60.4



10-10-0	17-6-0	24-2-0	35-0-0
10-10-0	6-8-0	6-8-0	10-10-0

Plate Offsets (X,Y)-- [1:Edge,0-2-9], [7:Edge,0-2-9]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.64	Vert(LL)	-0.22 13-16	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.85	Vert(CT)	-0.48 13-16	>872	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.31	Horz(CT)	0.12 7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 134 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE

Left: 2x4 SPF No.2 , Right: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
2-0-0 oc purlins (2-11-1 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 1=Mechanical, 7=0-3-8
Max Horz 1=-108(LC 13)
Max Uplift 1=-272(LC 12), 7=-292(LC 13)
Max Grav 1=1574(LC 1), 7=1637(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-2711/481, 2-3=-2431/450, 3-4=-2534/485, 4-5=-2534/485, 5-6=-2427/449,
6-7=-2707/479
BOT CHORD 1-13=-418/2325, 11-13=-295/2131, 9-11=-218/2128, 7-9=-316/2319
WEBS 2-13=-287/182, 3-13=-63/431, 3-11=-183/655, 4-11=-567/223, 5-11=-183/657,
5-9=-62/430, 6-9=-282/181

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 10-10-0, Exterior(2R) 10-10-0 to 15-0-15, Interior(1) 15-0-15 to 24-2-0, Exterior(2R) 24-2-0 to 28-4-15, Interior(1) 28-4-15 to 35-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=272, 7=292.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804354
2765833	A23	Hip Girder	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:55 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-0CcNx4p3KwPPZbjatuUXoHJFaM0yX46iFLGXaDzNtec

-0-10-8	3-7-15	4-1-3	8-2-0	12-9-2	17-6-0	22-2-14	26-10-0	30-10-13	35-0-0	35-10-8
0-10-8	3-7-15	0-5-4	4-0-13	4-7-2	4-8-14	4-8-14	4-7-2	4-0-13	4-1-3	0-10-8

Scale = 1:62.1




Plate Offsets (X,Y)--		[2:0-1-11,0-3-7], [4:0-3-4,0-2-8], [7:0-4-0,Edge], [9:0-3-4,0-2-8], [10:0-0-0,0-0-0], [11:0-1-11,0-3-7]	
LOADING (psf)	SPACING-	CSI.	DEFL.
TCLL 25.0	Plate Grip DOL 1.15	TC 0.90	in (loc) l/defl L/d
TCDL 10.0	Lumber DOL 1.15	BC 0.61	Vert(LL) 0.40 17 >999 240
BCLL 0.0	Rep Stress Incr NO	WB 0.52	Vert(CT) -0.68 17 >615 180
BCDL 10.0	Code IRC2018/TPI2014	Matrix-MS	Horz(CT) 0.13 11 n/a n/a
			PLATES MT20
			GRIP 197/144
			Weight: 185 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF 1650F 1.5E
 BOT CHORD 2x6 SP 2400F 2.0E *Except*
 15-19: 2x6 SPF 2100F 1.8E
 WEBS 2x4 SPF No.2
 WEDGE
 Left: 2x6 SP No.2 , Right: 2x6 SP No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-5-1 oc purlins, except
 2-0-0 oc purlins (2-2-10 max.): 4-9.
 BOT CHORD Rigid ceiling directly applied or 6-8-8 oc bracing.

REACTIONS.

(size) 2=0-3-8, 11=0-3-8
 Max Horz 2=-78(LC 34)
 Max Uplift 2=-1067(LC 8), 11=-1067(LC 9)
 Max Grav 2=3132(LC 1), 11=3132(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-5656/1960, 3-4=-5364/1939, 4-5=-6056/2275, 5-6=-6493/2396, 6-8=-6493/2396,
 8-9=-6056/2275, 9-10=-5364/1939, 10-11=-5656/1961
 BOT CHORD 2-21=-1764/4995, 20-21=-1764/4995, 18-20=-1671/4748, 17-18=-2174/6054,
 16-17=-2133/6054, 14-16=-1592/4748, 13-14=-1687/4995, 11-13=-1687/4995
 WEBS 3-20=-253/190, 4-20=-216/779, 4-18=-792/1859, 5-18=-1030/497, 5-17=-293/654,
 6-17=-505/273, 8-17=-294/654, 8-16=-1030/497, 9-16=-792/1859, 9-14=-215/779,
 10-14=-253/191

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=1067, 11=1067.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss, Single Ply Girder) or equivalent spaced at 20-0-0 oc max. starting at 3-6-0 from the left end to 31-6-0 to connect truss(es) to front face of bottom chord.
- Fill all nail holes where hanger is in contact with lumber.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

Continued on page 2



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	A23	Hip Girder	2	1	I45804354
Job Reference (optional)					

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:56 2021 Page 2
ID:SlSjxd784vT_GMBLZatvrSzbhoN-UOAI8Pqh5EXFBllmQc?mKUsQKmMBGXMsU?056fzNteb

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-4=-70, 4-9=-70, 9-12=-70, 22-25=-20

Concentrated Loads (lb)

Vert: 17=-79(F) 6=-79(F) 13=-316(F) 21=-316(F) 28=-79(F) 29=-79(F) 30=-79(F) 31=-79(F) 32=-79(F) 33=-79(F) 34=-79(F) 35=-79(F) 36=-233(F) 37=-233(F) 38=-79(F) 39=-79(F) 40=-79(F) 41=-79(F) 42=-79(F) 43=-79(F) 44=-79(F) 45=-79(F) 46=-233(F) 47=-233(F)

 **WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**
Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	A24	Common	1	1	145804355

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:57 2021 Page 1

ID:SlSjxd784vT_GMBLZatvSzbbhoN-yak7LrJsXg6pvtz_JW?tiOgrAko?VT?jfllee5zNtea

5-10-2	6-7-13	12-4-12	13-0-3	19-4-8	25-10-6	26-4-4	32-4-5	32-10-14	38-10-8	39-9-0
5-10-2	0-9-11	5-8-15	0-7-7	6-4-5	6-5-14	0-5-14	6-0-1	0-6-9	5-11-10	0-10-8

7x8 ||

Scale = 1:70.0




Plate Offsets (X,Y)--	[1:0-4-1,Edge]
-----------------------	----------------

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.53	Vert(LL)	-0.06 14-15	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.46	Vert(CT)	-0.14 12-24	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.79	Horz(CT)	0.02 10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS					Weight: 164 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Right: 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 -t 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-15

REACTIONS.

(size) 1=0-2-0, 15=0-3-8, 10=0-3-8
Max Horz 1=-189(LC 13)
Max Uplift 1=-84(LC 12), 15=-337(LC 12), 10=-213(LC 13)
Max Grav 1=528(LC 25), 15=2176(LC 1), 10=970(LC 26)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-3=-601/114, 3-5=-462/128, 5-6=0/661, 6-7=-561/273, 7-9=-1228/344, 9-10=-1433/331
BOT CHORD 1-17=-193/537, 15-17=-261/245, 12-14=-15/699, 10-12=-205/1211
WEBS 6-15=-1445/221, 6-14=-247/887, 7-14=-735/325, 5-15=-751/330, 5-17=-150/611,
7-12=-137/560, 3-17=-403/214, 9-12=-371/207

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 19-4-8, Exterior(2R) 19-4-8 to 22-4-8, Interior(1) 22-4-8 to 39-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 1.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1 except (jt=lb) 15=337, 10=213.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804356
2765833	A25	Roof Special	2	1	Job Reference (optional)	


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:16:58 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzbhoN-QnlWZ5rydrozQ3S9Y11EQvxmyayHkMM9xJVCByZnTeZ

2-2-0	7-8-8	13-3-0	15-4-12	19-4-8	25-10-6	32-4-5	38-10-8	39-9-0
2-2-0	5-6-8	5-6-8	2-1-12	3-11-12	6-5-14	6-5-14	6-6-3	0-10-8

Scale = 1:80.5



2-2-0	7-8-8	13-3-0	15-4-12	19-4-8	23-2-9	25-10-6	31-0-6	32-4-5	38-10-8
2-2-0	5-6-8	5-6-8	2-1-12	3-11-12	3-10-1	2-7-13	5-2-0	1-3-15	6-6-3

Plate Offsets (X,Y)-- [1:Edge,0-3-8], [2:0-0-0,0-0-5], [2:0-2-0,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.89	Vert(LL)	0.28	20	>668	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.96	Vert(CT)	-0.47	20	>391	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.81	Horz(CT)	0.07	10	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 175 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except*	TOP CHORD Structural wood sheathing directly applied.
1-4: 2x4 SPF 1650F 1.5E	BOT CHORD Rigid ceiling directly applied.
BOT CHORD 2x4 SPF No.2 *Except*	WEBS 1 Row at midpt 3-18, 6-15, 5-16, 7-15
1-20: 2x6 SPF No.2	
WEBS 2x4 SPF No.2 *Except*	
5-16: 2x4 SPF 1650F 1.5E	
WEDGE	
Left: 2x4 SPF No.2, Right: 2x4 SPF No.2	

REACTIONS. (size) 1=0-2-0, 10=0-3-8, 16=0-3-8
Max Horz 1=-189(LC 13)
Max Uplift 1=-129(LC 13), 10=-292(LC 13), 16=-309(LC 12)
Max Grav 1=545(LC 25), 10=1042(LC 26), 16=2083(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-730/296, 3-5=-63/575, 5-6=-251/376, 6-7=-352/342, 7-9=-997/413,
9-10=-1571/476
BOT CHORD 2-19=-200/639, 18-19=-200/639, 15-16=-300/102, 13-15=-142/806, 12-13=-326/1323,
10-12=-326/1323
WEBS 3-19=0/392, 3-18=-1036/342, 16-18=-1999/343, 5-18=-1548/242, 7-15=-863/297,
7-13=-43/467, 9-13=-595/210, 5-15=-5/984

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 19-4-8, Exterior(2R) 19-4-8 to 22-4-8, Interior(1) 22-4-8 to 39-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate at joint(s) 1.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=129, 10=292, 16=309.
 - This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.




April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017



Scale = 1:79.9



2-2-0	7-8-8	13-3-0	15-4-12	18-2-8	20-6-8	29-8-5	38-10-8
2-2-0	5-6-8	5-6-8	2-1-12	2-9-12	2-4-0	9-1-13	9-2-3

Plate Offsets (X,Y)-- [1:Edge,0-3-8], [2:0-0-0,0-0-5], [2:0-2-0,0-1-8], [7:0-4-6,Edge]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	25.0	Plate Grip DOL	1.15	TC	0.90	Vert(LL)	0.28	19	>662	240	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.97	Vert(CT)	-0.48	19	>387	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.06	15	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS							Weight: 172 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
1-4: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2 *Except*
1-19: 2x6 SPF No.2
WEBS 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2 , Right: 2x4 SPF No.2

BRACING-

TOP CHORD	Structural wood sheathing directly applied, except 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 3-17, 7-14, 5-15, 6-15, 9-14

REACTIONS.

(size) 1=0-2-0, 10=0-3-8, 15=0-3-8
 Max Horz 1=177(LC 13)
 Max Uplift 1=128(LC 13), 10=297(LC 13), 15=300(LC 12)
 Max Grav 1=552(LC 25), 10=1058(LC 26), 15=2063(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-748/298, 3-5=-44/549, 5-6=-46/449, 6-7=-378/377, 7-9=-574/351, 9-10=-1493/468
BOT CHORD 2-18=-206/655, 17-18=-206/655, 12-14=-290/1230, 10-12=-290/1230
WEBS 3-18=0/393, 3-17=-1038/347, 7-14=-333/88, 15-17=-938/358, 5-17=-489/256,
6-15=-1081/0, 6-14=-167/985, 9-14=-988/344, 9-12=0/387

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 18-2-8, Exterior(2E) 18-2-8 to 20-6-8, Exterior(2R) 20-6-8 to 24-9-7, Interior(1) 24-9-7 to 39-9-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 1.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=128, 10=297, 15=300.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021



WARNING – Velly design parameters are listed below and included with the key reference to AISC M14-15 16f, 17f, 18f, 19f, 20f, 21f, 22f, 23f, 24f, 25f, 26f, 27f, 28f, 29f, 30f, 31f, 32f, 33f, 34f, 35f, 36f, 37f, 38f, 39f, 40f, 41f, 42f, 43f, 44f, 45f, 46f, 47f, 48f, 49f, 50f, 51f, 52f, 53f, 54f, 55f, 56f, 57f, 58f, 59f, 60f, 61f, 62f, 63f, 64f, 65f, 66f, 67f, 68f, 69f, 70f, 71f, 72f, 73f, 74f, 75f, 76f, 77f, 78f, 79f, 80f, 81f, 82f, 83f, 84f, 85f, 86f, 87f, 88f, 89f, 90f, 91f, 92f, 93f, 94f, 95f, 96f, 97f, 98f, 99f, 100f, 101f, 102f, 103f, 104f, 105f, 106f, 107f, 108f, 109f, 110f, 111f, 112f, 113f, 114f, 115f, 116f, 117f, 118f, 119f, 120f, 121f, 122f, 123f, 124f, 125f, 126f, 127f, 128f, 129f, 130f, 131f, 132f, 133f, 134f, 135f, 136f, 137f, 138f, 139f, 140f, 141f, 142f, 143f, 144f, 145f, 146f, 147f, 148f, 149f, 150f, 151f, 152f, 153f, 154f, 155f, 156f, 157f, 158f, 159f, 160f, 161f, 162f, 163f, 164f, 165f, 166f, 167f, 168f, 169f, 170f, 171f, 172f, 173f, 174f, 175f, 176f, 177f, 178f, 179f, 180f, 181f, 182f, 183f, 184f, 185f, 186f, 187f, 188f, 189f, 190f, 191f, 192f, 193f, 194f, 195f, 196f, 197f, 198f, 199f, 200f, 201f, 202f, 203f, 204f, 205f, 206f, 207f, 208f, 209f, 210f, 211f, 212f, 213f, 214f, 215f, 216f, 217f, 218f, 219f, 220f, 221f, 222f, 223f, 224f, 225f, 226f, 227f, 228f, 229f, 230f, 231f, 232f, 233f, 234f, 235f, 236f, 237f, 238f, 239f, 240f, 241f, 242f, 243f, 244f, 245f, 246f, 247f, 248f, 249f, 250f, 251f, 252f, 253f, 254f, 255f, 256f, 257f, 258f, 259f, 260f, 261f, 262f, 263f, 264f, 265f, 266f, 267f, 268f, 269f, 270f, 271f, 272f, 273f, 274f, 275f, 276f, 277f, 278f, 279f, 280f, 281f, 282f, 283f, 284f, 285f, 286f, 287f, 288f, 289f, 290f, 291f, 292f, 293f, 294f, 295f, 296f, 297f, 298f, 299f, 300f, 301f, 302f, 303f, 304f, 305f, 306f, 307f, 308f, 309f, 310f, 311f, 312f, 313f, 314f, 315f, 316f, 317f, 318f, 319f, 320f, 321f, 322f, 323f, 324f, 325f, 326f, 327f, 328f, 329f, 330f, 331f, 332f, 333f, 334f, 335f, 336f, 337f, 338f, 339f, 340f, 341f, 342f, 343f, 344f, 345f, 346f, 347f, 348f, 349f, 350f, 351f, 352f, 353f, 354f, 355f, 356f, 357f, 358f, 359f, 360f, 361f, 362f, 363f, 364f, 365f, 366f, 367f, 368f, 369f, 370f, 371f, 372f, 373f, 374f, 375f, 376f, 377f, 378f, 379f, 380f, 381f, 382f, 383f, 384f, 385f, 386f, 387f, 388f, 389f, 390f, 391f, 392f, 393f, 394f, 395f, 396f, 397f, 398f, 399f, 400f, 401f, 402f, 403f, 404f, 405f, 406f, 407f, 408f, 409f, 410f, 411f, 412f, 413f, 414f, 415f, 416f, 417f, 418f, 419f, 420f, 421f, 422f, 423f, 424f, 425f, 426f, 427f, 428f, 429f, 430f, 431f, 432f, 433f, 434f, 435f, 436f, 437f, 438f, 439f, 440f, 441f, 442f, 443f, 444f, 445f, 446f, 447f, 448f, 449f, 450f, 451f, 452f, 453f, 454f, 455f, 456f, 457f, 458f, 459f, 460f, 461f, 462f, 463f, 464f, 465f, 466f, 467f, 468f, 469f, 470f, 471f, 472f, 473f, 474f, 475f, 476f, 477f, 478f, 479f, 480f, 481f, 482f, 483f, 484f, 485f, 486f, 487f, 488f, 489f, 490f, 491f, 492f, 493f, 494f, 495f, 496f, 497f, 498f, 499f, 500f, 501f, 502f, 503f, 504f, 505f, 506f, 507f, 508f, 509f, 510f, 511f, 512f, 513f, 514f, 515f, 516f, 517f, 518f, 519f, 520f, 521f, 522f, 523f, 524f, 525f, 526f, 527f, 528f, 529f, 530f, 531f, 532f, 533f, 534f, 535f, 536f, 537f, 538f, 539f, 540f, 541f, 542f, 543f, 544f, 545f, 546f, 547f, 548f, 549f, 550f, 551f, 552f, 553f, 554f, 555f, 556f, 557f, 558f, 559f, 560f, 561f, 562f, 563f, 564f, 565f, 566f, 567f, 568f, 569f, 570f, 571f, 572f, 573f, 574f, 575f, 576f, 577f, 578f, 579f, 580f, 581f, 582f, 583f, 584f, 585f, 586f, 587f, 588f, 589f, 590f, 591f, 592f, 593f, 594f, 595f, 596f, 597f, 598f, 599f, 600f, 601f, 602f, 603f, 604f, 605f, 606f, 607f, 608f, 609f, 610f, 611f, 612f, 613f, 614f, 615f, 616f, 617f, 618f, 619f, 620f, 621f, 622f, 623f, 624f, 625f, 626f, 627f, 628f, 629f, 630f, 631f, 632f, 633f, 634f, 635f, 636f, 637f, 638f, 639f, 640f, 641f, 642f, 643f, 644f, 645f, 646f, 647f, 648f, 649f, 650f, 651f, 652f, 653f, 654f, 655f, 656f, 657f, 658f, 659f, 660f, 661f, 662f, 663f, 664f, 665f, 666f, 667f, 668f, 669f, 670f, 671f, 672f, 673f, 674f, 675f, 676f, 677f, 678f, 679f, 680f, 681f, 682f, 683f, 684f, 685f, 686f, 687f, 688f, 689f, 690f, 691f, 692f, 693f, 694f, 695f, 696f, 697f, 698f, 699f, 700f, 701f, 702f, 703f, 704f, 705f, 706f, 707f,



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804358
2765833	A27	Roof Special	1	1	Job Reference (optional)	


Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:03 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-nk5Pcpv4RNQGXqK6LadP7zedyaiPPapu5bCzslzNteU

2-2-0	8-8-8	13-3-0	15-6-8	19-6-8	21-4-8	27-2-6	29-2-5	33-0-5	38-10-8	39-9-0
2-2-0	6-6-8	4-6-8	2-3-8	4-0-0	1-10-0	5-9-14	1-11-15	3-9-15	5-10-3	0-10-8

Scale = 1:74.0



Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804359
2765833	A28	Roof Special	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:05 2021 Page 1

ID:SlSjxd784vT_GMBLZatvSzboN-j7D91UxLz?g_m8UUVS?ftCOj__OPntVCBYvh3xezNteS

6-7-0	12-10-8	15-4-12	16-10-8	21-4-8	27-2-6	29-6-4	33-0-5	38-10-8	39-9-0
6-7-0	6-3-8	2-6-4	1-5-12	4-6-0	5-9-14	2-3-14	3-6-1	5-10-3	0-10-8

Scale = 1:68.1




Plate Offsets (X,Y)--		[1:0-3-8,Edge], [5:0-4-0,0-1-14]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc)		l/defl		L/d		PLATES		GRIP	
TCLL	25.0	Plate Grip DOL 1.15		TC	0.77	Vert(LL) 0.13 11-23		>999		240		MT20		197/144	
TCDL	10.0	Lumber DOL 1.15		BC	0.65	Vert(CT) -0.29 11-23		>975		180					
BCLL	0.0	Rep Stress Incr YES		WB	0.93	Horz(CT) 0.01 1		n/a		n/a					
BCDL	10.0	Code IRC2018/TPI2014		Matrix-AS								Weight: 162 lb		FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 WEDGE
 Right: 2x4 SPF No.2
 SLIDER Left 2x4 SPF No.2 -t 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied, except
 2-0-0 oc purlins (10-0-0 max.): 4-5.
 BOT CHORD Rigid ceiling directly applied.
 WEBS 1 Row at midpt 6-13, 8-13

REACTIONS.

(size) 1=0-2-0, 9=0-3-8, 14=0-3-8
 Max Horz 1=-171(LC 13)
 Max Uplift 1=-122(LC 12), 9=-239(LC 13), 14=-309(LC 12)
 Max Grav 1=560(LC 25), 9=1001(LC 1), 14=2044(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-3=-659/169, 3-4=-755/322, 4-5=0/400, 5-6=-419/275, 6-8=-502/240, 8-9=-1365/347
 BOT CHORD 1-16=-216/583, 11-13=-180/1114, 9-11=-180/1114
 WEBS 3-16=-475/270, 5-14=-1152/216, 4-14=-817/236, 4-16=-291/899, 5-13=-39/846,
 8-13=-939/334, 8-11=0/377

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 12-10-8, Exterior(2R) 12-10-8 to 15-10-8, Interior(1) 15-10-8 to 21-4-8, Exterior(2R) 21-4-8 to 24-4-8, Interior(1) 24-4-8 to 39-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate at joint(s) 1.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=122, 9=239, 14=309.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804360
2765833	B1	GABLE	2	1		

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:17 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-NRyYb4s8hBHC_Pp9WthhwD9CEVyh45yJmbiMxzNteG

0-10-8 5-6-4 10-9-0 15-2-12 15-11-12 20-0-0 20-10-8
0-10-8 5-6-4 5-2-12 4-5-12 0-9-0 4-0-4 0-10-8

4x6 =

Scale = 1:49.7




Plate Offsets (X,Y)--	[2:Edge,0-0-0]								
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.31	Vert(LL)	-0.22 17-32	>732	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.69	Vert(CT)	-0.45 17-32	>361	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.30	Horz(CT)	0.03 2	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						
								Weight: 122 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 - t 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

All bearings 6-7-0 except (jt=length) 2=0-3-8, 16=0-3-8, 16=0-3-8.
(lb) - Max Horz 2=231(LC 11)
Max Uplift All uplift 100 lb or less at joint(s) 11, 13, 12, 16 except 2=140(LC 12), 14=131(LC 13), 16=155(LC 3)
Max Grav All reactions 250 lb or less at joint(s) 11, 15, 13, 12 except 2=780(LC 1), 14=891(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-4=-915/185, 4-5=-549/170, 5-6=-545/168
BOT CHORD 2-17=-168/708
WEBS 4-17=-385/230, 5-17=-48/299, 6-17=-20/489, 6-14=-871/142

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 10-9-0, Exterior(2R) 10-9-0 to 13-9-0, Interior(1) 13-9-0 to 20-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) Gable studs spaced at 1-4-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 13, 12 except (jt=lb) 2=140, 14=131, 16=155.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804361
2765833	B2	ROOF SPECIAL GIRDER	2	2	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:19 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-Jp3SzH67glR?SHZBHxv9mLIPm1CG9w7Fm44pQqzNteE

2-3-8	6-0-10	10-9-0	11-4-8	13-2-15	16-0-2	20-0-0	20-10-8
2-3-8	3-9-2	4-8-6	0-7-8	1-10-7	2-9-3	3-11-14	0-10-8

Scale = 1:51.0




Plate Offsets (X,Y)-- [2:0-8-0,0-6-5], [3:0-3-4,0-3-0], [9:0-5-8,Edge], [14:0-5-8,0-3-0], [15:0-3-0,0-0-0]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES		GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	-0.14	2-17	>999	240	MT20	197/144	
TCDL	10.0	Lumber DOL	1.15	BC	0.63	Vert(CT)	-0.23	2-17	>999	180	MT18HS	197/144	
BCLL	0.0	Rep Stress Incr	NO	WB	0.52	Horz(CT)	0.19	9	n/a	n/a			
BCDL	10.0	Code IRC2018/TPI2014		Matrix-MS							Weight: 270 lb	FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2 *Except*
1-3: 2x8 SP 2400F 2.0E
BOT CHORD 2x4 SPF No.2 *Except*
2-14: 2x6 SPF 2100F 1.8E, 9-13: 2x6 SPF No.2
WEBS 2x4 SPF No.2 *Except*
7-9: 2x6 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-4-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 1-18.

REACTIONS.

(size) 9=(0-3-8 + bearing block) (req. 0-4-6), 1=0-3-8
Max Horz 1=222(LC 7)
Max Uplift 9=-1169(LC 9), 1=-844(LC 8)
Max Grav 9=-5575(LC 1), 1=3225(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-20=-1767/532, 2-3=-5555/1550, 3-4=-3917/1065, 4-5=-3826/1091, 5-6=-4948/1211,
6-7=-5216/1134, 7-9=-4751/1037
BOT CHORD 2-18=-149/623, 2-17=-1390/4896, 16-17=-1413/4961, 15-16=-879/4089, 14-15=-728/3326,
12-13=-157/764, 11-12=-169/818, 9-11=-95/372
WEBS 4-16=-1101/3963, 3-16=-2172/807, 12-14=-110/834, 5-14=-362/2284, 5-16=-2056/396,
6-11=-280/292, 7-11=-869/4230, 11-14=-747/3640, 6-14=-337/97, 3-17=-434/1307

NOTES-

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x8 - 2 rows staggered at 0-9-0 oc, 2x4 - 1 row at 0-7-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-6-0 oc, 2x6 - 2 rows staggered at 0-5-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 2x6 SPF No.2 bearing block 12" long at jt. 9 attached to each face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners per block. Bearing is assumed to be SPF No.2.
- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are MT20 plates unless otherwise indicated.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 9=1169, 1=844.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and Conference signed and ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**
Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804361
2765833	B2	ROOF SPECIAL GIRDER	2	2	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:20 2021 Page 2

ID:SlSjxd784vT_GMBLZatvrszboN-n0dqAd6lRcZs3R7OqeQOJYraWRYVuNNO?kqMyGzNteD

NOTES-

- 10) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 2-1-12 from the left end to 8-0-12 to connect truss(es) to back face of bottom chord.
- 11) Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent at 12-0-12 from the left end to connect truss(es) to back face of bottom chord.
- 12) Use Simpson Strong-Tie HUS26 (14-10d Girder, 6-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 14-0-12 from the left end to 18-0-12 to connect truss(es) to back face of bottom chord.
- 13) Fill all nail holes where hanger is in contact with lumber.
- 14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 335 lb down and 286 lb up at 10-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
 - Uniform Loads (plf)
 - Vert: 1-2=-70, 2-4=-70, 4-7=-70, 7-8=-70, 18-19=-20, 2-15=-20, 9-13=-20
 - Concentrated Loads (lb)
 - Vert: 18=-311(B) 11=-1545(B) 17=-456(B) 23=-447(B) 24=-343(B) 25=-335(B) 26=-387(B) 28=-1554(B) 29=-1554(B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804362
2765833	B3	COMMON SUPPORTED GAB	3	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:21 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-FCBCOz7NCvhibiaOMxdrmOvHr1EdyxXEOZvVizNteC



Scale: 3/8"=1'

Plate Offsets (X,Y)--		[12:Edge,0-4-0]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.05
TCDL 10.0	Lumber DOL	1.15	BC 0.02
BCLL 0.0	Rep Stress Incr	YES	WB 0.05
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-S
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) -0.00 12 n/r 120
			Vert(CT) -0.00 13 n/r 120
			Horz(CT) 0.00 12 n/a n/a
			PLATES
			MT20
			GRIP
			197/144
			Weight: 70 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF No.2
 SLIDER Left 2x4 SPF No.2 -t 1-8-11, Right 2x4 SPF No.2 -t 1-8-1

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 13-8-8.
 (lb) - Max Horz 2=134(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 2, 12, 19, 20, 21, 22, 17, 16, 15, 14
 Max Grav All reactions 250 lb or less at joint(s) 2, 12, 18, 19, 20, 21, 22, 17, 16, 15, 14

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 6-10-0, Corner(3R) 6-10-0 to 9-10-0, Exterior(2N) 9-10-0 to 14-6-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 1-4-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 12, 19, 20, 21, 22, 17, 16, 15, 14.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804363
2765833	B4	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:23 2021 Page 2
ID:SlSjxd784vT_GMBLZatvrSzbhoN-BbJype9dkXxQwvsyWn_5wBT8QeY75j8qhi20ZbzNteA

NOTES-

- 13) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 537 lb down and 217 lb up at 2-0-10 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 14) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-7=-70, 11-14=-20, 13-16=-20, 9-13=-20, 9-26=-20
Concentrated Loads (lb)
Vert: 14=-537(B) 29=-569(B) 30=-564(B) 31=-532(B) 32=-490(B) 37=-460(B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**
Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804364
2765833	B5	GABLE	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:24 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-gntL0_AfVq3HY2R93UVKTO0QW224qlr_wMoa51zNte9



Scale = 1:47.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.05	Vert(LL)	0.00	1	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.01	Vert(CT)	-0.00	1	n/r	120		
BCLL 0.0	Rep Stress Incr	YES	WB 0.10	Horz(CT)	-0.00	14	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 98 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 OTHERS 2x4 SPF No.2
 SLIDER Left 2x4 SPF No.2 - 1-9-7

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 13-14, 12-15

REACTIONS.

All bearings 13-6-14.
 (lb) - Max Horz 2=388(LC 12)
 Max Uplift All uplift 100 lb or less at joint(s) 14, 2, 15, 16, 17, 18, 19, 20, 21, 22 except 23=160(LC 12)
 Max Grav All reactions 250 lb or less at joint(s) 14, 15, 16, 17, 18, 19, 20, 21, 22, 23 except 2=297(LC 12)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-642/311, 3-4=-490/231, 4-5=-433/204, 5-6=-379/178, 6-7=-324/151, 7-9=-269/124

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 13-5-2 zone; cantilever left and right exposed; end vertical left exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 1-4-0 oc.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14, 2, 15, 16, 17, 18, 19, 20, 21, 22 except (jt=lb) 23=160.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
 Chesterfield, MO 63017

Job 2765833	Truss CJ1	Truss Type Jack-Closed Girder	Qty 4	Ply 1	Summit/#8 Osage I45804365
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:25 2021 Page 1
ID:SlSjXd784vT_GMBLZatvrSzbhoN-8zQjEKAuG8B8AC0ldC0Z0cYYwSNLZmi790X7eUzNte8



Scale = 1:14.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.20	Vert(LL)	-0.00	6-7	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.08	Vert(CT)	-0.01	6-7	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.00	Horz(CT)	-0.00	6	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MR						Weight: 13 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-9-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 7=0-4-13, 6=Mechanical
Max Horz 7=95(LC 5)
Max Uplift 7=-86(LC 4), 6=-65(LC 5)
Max Grav 7=291(LC 1), 6=146(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-7=-256/99

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 6.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) "NAILED" indicates 2-12d (0.148"x3.25") toe-nails per NDS guidelines.
- 8) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-70, 2-3=-70, 3-4=-20, 5-7=-20
Concentrated Loads (lb)
Vert: 8=-1(B) 9=-13(B)



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component**
Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	CJ2	Jack-Open	2	1	I45804366
Job Reference (optional)					

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:26 2021 Page 1

ID:SlSjXd784vT_GMBLZatvSzbhoN-cA_5RgBW1SJ?nMbXBvXoYp5jksiolDyGNgHgAwzNte7



Scale = 1:18.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.19	Vert(LL)	0.01	4-5	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	-0.01	4-5	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.04	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MR						Weight: 11 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 5=0-4-13, 3=Mechanical, 4=Mechanical
Max Horz 5=79(LC 9)
Max Uplift 5=-55(LC 8), 3=-54(LC 12), 4=-6(LC 9)
Max Grav 5=276(LC 1), 3=77(LC 1), 4=55(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -1-5-8 to 2-9-7, Exterior(2R) 2-9-7 to 3-1-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 3, 4.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	J1	Jack-Open	18	1	I45804367

Builders FirstSource (Valley Center),


Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:26 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzbhoN-ca_5RgBW1SJ?nMbXBvXoYp5i_se9lDbGNgHgAwzNte7



Scale = 1:26.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.31	Vert(LL)	0.11	6	>603	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.42	Vert(CT)	-0.14	6	>494	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.02	Horz(CT)	0.04	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 19 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 4=Mechanical, 5=Mechanical, 7=0-3-8
Max Horz 7=170(LC 12)
Max Uplift 4=-91(LC 12), 5=-31(LC 12), 7=-17(LC 12)
Max Grav 4=158(LC 19), 5=105(LC 19), 7=333(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-9-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 5, 7.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	J2	Half Hip	4	1	145804368

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:27 2021 Page 1

ID:SlSjXd784vT_GMBLZatvSzboN-4MYTe0C8oIRsPWAKlc2151eskG0V1gCQcK0EiMzNte6

-0-10-8 5-3-15 5-10-8
0-10-8 5-3-15 0-6-9

Scale = 1:28.0




Plate Offsets (X,Y)--		[4:0-5-12,Edge], [6:Edge,0-1-8]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.37
TCDL 10.0	Lumber DOL	1.15	BC 0.29
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-AS
			DEFL.
			in (loc) l/defl L/d
			Vert(LL) 0.03 6-9 >999 240
			Vert(CT) -0.05 6-9 >999 180
			Horz(CT) 0.02 2 n/a n/a
			PLATES
			MT20
			GRIP
			197/144
			Weight: 22 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 -t 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 6=Mechanical, 2=0-3-8
Max Horz 2=159(LC 11)
Max Uplift 6=78(LC 12), 2=52(LC 12)
Max Grav 6=262(LC 19), 2=324(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-3-15, Exterior(2E) 5-3-15 to 5-8-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Provide adequate drainage to prevent water ponding.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6, 2.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804370
2765833	J4	Half Hip Girder	4	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:29 2021 Page 1
ID:SlSjxd784vT_GMBLZatvrSzbhoN-0kgE3iDOJNiafqJ6s15VASjCR3kkVZGj3eVlnFzNte4



Scale = 1:15.1

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.29	Vert(LL)	-0.01	6-7	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.18	Vert(CT)	-0.02	6-7	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.09	Horz(CT)	0.00	6	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-MP						Weight: 26 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
SLIDER Left 2x4 SPF No.2 -t 2-0-0

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-10-8 oc purlins, except end verticals, and 2-0-0 oc purlins: 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 2=0-3-8, 6=Mechanical
Max Horz 2=81(LC 7)
Max Uplift 2=119(LC 8), 6=115(LC 5)
Max Grav 2=416(LC 1), 6=336(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-4=-373/124
BOT CHORD 2-7=-128/296, 6-7=-124/282
WEBS 4-6=-325/125

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Refer to girder(s) for truss to truss connections.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=119, 6=115.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.
- In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-4=-70, 4-5=-70, 6-8=-20
Concentrated Loads (lb)
Vert: 7=-121(B) 12=-27(B) 13=-27(B)



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	J5	Jack-Open	4	1	145804371
Job Reference (optional)					

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:30 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-UxEch1E04gqRGzuJQlckjGPeT4wE1yslIFuJhzNte3



Scale = 1:14.5

Plate Offsets (X,Y)--		[2:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.14
TCDL 10.0	Lumber DOL	1.15	BC 0.11
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-MP
			DEFL. in (loc) l/defl L/d
			Vert(LL) -0.01 4-7 >999 240
			Vert(CT) -0.01 4-7 >999 180
			Horz(CT) 0.00 2 n/a n/a
			PLATES GRIP
			MT20 197/144
			Weight: 10 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2

BOT CHORD 2x4 SPF No.2

WEDGE

Left: 2x4 SPF No.2

BRACING-

TOP CHORD

Structural wood sheathing directly applied or 3-5-4 oc purlins.

BOT CHORD

Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 3=Mechanical, 2=0-3-8, 4=Mechanical

Max Horz 2=84(LC 12)

Max Uplift 3=52(LC 12), 2=34(LC 12), 4=3(LC 12)

Max Grav 3=97(LC 1), 2=221(LC 1), 4=61(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2765833	Truss J6	Truss Type Jack-Open	Qty 4	Ply 1	Summit/#8 Osage I45804372
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:31 2021 Page 1
ID:SlSjxd784vT_GMBLZatvrSzbhoN-y7o_UNFer_ylu7TV_S7zFtobLtQuzUC0Xy_Rr7zNte2



Scale = 1:12.7

Plate Offsets (X,Y)--		[2:0-3-8,Edge]	
LOADING (psf)	SPACING-	2-0-0	CSI.
TCLL 25.0	Plate Grip DOL	1.15	TC 0.07
TCDL 10.0	Lumber DOL	1.15	BC 0.07
BCLL 0.0	Rep Stress Incr	YES	WB 0.00
BCDL 10.0	Code	IRC2018/TPI2014	Matrix-MP
			DEFL. in (loc) l/defl L/d
			Vert(LL) -0.00 7 >999 240
			Vert(CT) -0.01 4-7 >999 180
			Horz(CT) 0.00 3 n/a n/a
			PLATES GRIP
			MT20 197/144
			Weight: 9 lb FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEDGE
Left: 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 2-8-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 3=Mechanical, 2=0-3-8, 4=Mechanical
Max Horz 2=70(LC 12)
Max Uplift 3=40(LC 12), 2=30(LC 12), 4=4(LC 12)
Max Grav 3=74(LC 1), 2=191(LC 1), 4=47(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 2-8-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2, 4.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804373
2765833	LG1	GABLE	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,


8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:32 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-RJMMijGHcl49WH2hXAeCo4LmtHnQivf9mck?OazNte1



4x4 =

Scale = 1:50.4



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	n/a	-	n/a	999	MT20
TCDL 10.0	Lumber DOL	1.15	BC 0.05	Vert(CT)	n/a	-	n/a	999	197/144
BCLL 0.0	Rep Stress Incr	YES	WB 0.18	Horz(CT)	0.01	9	n/a	n/a	
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						
								Weight: 84 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 18-3-4.
(lb) - Max Horz 1=-206(LC 8)
Max Uplift All uplift 100 lb or less at joint(s) 1, 9, 16, 11 except 14=-112(LC 12), 17=-153(LC 12), 12=-110(LC 13), 10=-153(LC 13)
Max Grav All reactions 250 lb or less at joint(s) 1, 9, 13, 14, 16, 12, 11 except 17=280(LC 19), 10=279(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-4-9 to 3-1-10, Interior(1) 3-1-10 to 9-1-10, Exterior(2R) 9-1-10 to 12-1-10, Interior(1) 12-1-10 to 17-10-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 9, 16, 11 except (jt=lb) 14=112, 17=153, 12=110, 10=153.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017



Scale: 3/16"=1'

Plate Offsets (X,Y)-- [11:0-2-8,0-0-4]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	10	n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S							Weight: 113 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2	TOP CHORD	2-0-0 oc purlins (6-0-0 max.): 1-9, except end verticals.
BOT CHORD	2x4 SPF No.2	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SPF No.2	WEBS	1 Row at midpt 1-17, 2-16, 3-15, 4-14
OTHERS	2x4 SPF No.2		

REACTIONS. All bearings 16-2-3.
(lb) - Max Uplift All uplift 100 lb or less at joint(s) 17, 9, 11, 16, 15, 14, 13, 12, 10
Max Grav All reactions 250 lb or less at joint(s) 17, 9, 11, 16, 15, 14, 13, 12, 10

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TC DL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed ; end vertical right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Bearing at joint(s) 17, 9, 11, 16, 15, 14, 13, 12, 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula.
Building designer should verify capacity of bearing surface.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 17, 9, 11, 16, 15, 14, 13, 12, 10.
- 8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 9, 11, 16, 15, 14, 13, 12, 10.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTEK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personnel injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Code**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	LG3	GABLE	2	1	I45804375
Job Reference (optional)					

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:34 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzbhoN-NiT76PHX8vKslbC4fbggtVQ_M4PNAoxSDwD5SSzNte?



Scale = 1:59.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.60	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.27	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.13	Horz(CT)	0.01	7	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S					Weight: 73 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD 2-0-0 oc purlins (6-0-0 max.): 1-7, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 1 Row at midpt 1-14, 2-12

REACTIONS.

All bearings 12-5-1.

(lb) - Max Horz 14=-286(LC 10)

Max Uplift All uplift 100 lb or less at joint(s) 13, 11, 10, 9, 8 except 14=-134(LC 10), 7=-113(LC 9), 12=-113(LC 8)

Max Grav All reactions 250 lb or less at joint(s) 14, 7, 13, 12, 11, 10, 9, 8

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

BOT CHORD 11-12=-259/246, 10-11=-257/243, 9-10=-258/243, 8-9=-258/244, 7-8=-256/238

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Provide adequate drainage to prevent water ponding.
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 13, 11, 10, 9, 8 except (jt=lb) 14=134, 7=113, 12=113.
- 7) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 7, 12, 11, 10, 9, 8.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component



16023 Swingley Ridge Rd
Chesterfield, MO 63017



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.15	Vert(LL) -0.00	1	n/r	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.09	Vert(CT) 0.00	1	n/r		
BCLL 0.0	Rep Stress Incr YES	WB 0.05	Horz(CT) 0.00	8	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-P				Weight: 33 lb	FT = 20%

LUMBER-		BRACING-	
TOP CHORD	2x4 SPF No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. Rigid ceiling directly applied or 10-0-0 oc bracing.
BOT CHORD	2x4 SPF No.2	BOT CHORD	
WEBS	2x4 SPF No.2		
OTHERS	2x4 SPF No.2		

REACTIONS. All bearings 8-11-8.
(b) - Max Horz 2=137(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 8, 2, 9, 10, 11, 12
Max Grav All reactions 250 lb or less at joint(s) 8, 2, 9, 10, 11 except 12=328(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-257/126
 WEBS 3-12=-249/294

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCdL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 8-9-5 zone; cantilever left and right exposed; and vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) All plates are 2x4 MT20 unless otherwise indicated.
- 4) Gable requires continuous bottom chord bearing.
- 5) Gable studs spaced at 1'-4" o.c.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 8, 2, 9, 10, 11, 12.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021



Design valid for use only with MiTEK® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personnel injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Code**

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804377
2765833	M2	Monopitch	3	1	Job Reference (optional)	

Builders FirstSource (Valley Center),


Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:36 2021 Page 1

ID:SlSjXd784vT_GMBLZatvSzboN-J5btX5JngWaa_vMSm7j8yWwKmu2hekalhEiCWLzNtdz



Scale = 1:19.8



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.61	Vert(LL)	-0.12	6-9	>733	240	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.48	Vert(CT)	-0.24	6-9	>360	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.06	Horz(CT)	0.00	2	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-AS						Weight: 24 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied.
BOT CHORD Rigid ceiling directly applied.

REACTIONS.

(size) 2=0-3-8, 6=0-3-8
Max Horz 2=133(LC 8)
Max Uplift 2=-86(LC 8), 6=-121(LC 12)
Max Grav 2=370(LC 1), 6=488(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 3-6=-356/306

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-9-14 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 6=121.
- 4) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 5) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL 1.15	TC 0.29	Vert(LL) -0.03 4-7	>999	240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.24	Vert(CT) -0.06 4-7	>988	180		
BCLL 0.0	Rep Stress Incr YES	WB 0.00	Horz(CT) 0.00 2	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014	Matrix-AS				Weight: 14 lb	FT = 20%

LUMBER-

TOP CHORD	2x4 SPF No.2
BOT CHORD	2x4 SPF No.2
WEBS	2x4 SPF No.2

BRACING-

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS.

(size) 4=Mechanical, 2=0-3-8
Max Horz 2=79(LC 11)
Max Uplift 4=-53(LC 12), 2=-85(LC 8)
Max Grav 4=211(LC 1), 2=283(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCFL=6.0psf; BCLD=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 4-9-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and braced & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 3) Refer to girder(s) for truss to truss connections.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4, 2.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.



April 23, 2021

 WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804379
2765833	M4	GABLE	4	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:37 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-nH9FIRKPRqIRc2xfKjENV82cgIT?NaguVuRm2nzNtdy



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.15	Vert(LL)	-0.00	1	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.09	Vert(CT)	0.00	1	n/r	120		
BCLL 0.0	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 15 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-11-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

(size) 5=4-11-8, 2=4-11-8, 6=4-11-8
Max Horz 2=78(LC 9)
Max Uplift 5=-37(LC 1), 2=-64(LC 8), 6=-89(LC 12)
Max Grav 5=15(LC 12), 2=203(LC 1), 6=326(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 3-6=-249/372

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 4-9-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) Gable requires continuous bottom chord bearing.
- 4) Gable studs spaced at 1-4-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5, 2, 6.
- 7) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2765833	Truss M5	Truss Type GABLE	Qty 3	Ply 1	Summit/#8 Osage	I45804380
Builders FirstSource (Valley Center), Valley Center, KS - 67147,						Job Reference (optional)

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:38 2021 Page 1
ID:SlSjxd784vT_GMBLZatvrSzbhoN-FTjdynK1C8qIECWruQlc1LboKhqj6eD18YBjaDzNtdx



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	L/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	-0.00	1	n/r	120	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	0.00	1	n/r	120		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	7	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 24 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 6-11-8.
(lb) - Max Horz 2=108(LC 9)
Max Uplift All uplift 100 lb or less at joint(s) 7, 2, 8, 9, 10
Max Grav All reactions 250 lb or less at joint(s) 7, 2, 8, 9 except 10=252(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 3-10=-191/258

NOTES-

- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) -0-10-8 to 2-1-8, Exterior(2N) 2-1-8 to 6-9-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 1-4-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 7, 2, 8, 9, 10.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	V1	Valley	1	1	I45804382
Job Reference (optional)					

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:40 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzboN-CsqONSMik40TWIE?rn47mg4bVUVaWdKbrgQf6zNtdv



Scale = 1:46.1

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.36	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.16	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.14	Horz(CT)	-0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 46 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-5

REACTIONS.

All bearings 12-0-12.

(lb) - Max Horz 1=304(LC 9)

Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 6=164(LC 12), 7=161(LC 12)

Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 6=396(LC 19), 7=392(LC 19)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-448/348, 2-3=-317/265

WEBS 3-6=-321/232, 2-7=-298/207

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 11-11-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 6=164, 7=161.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804383
2765833	V2	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:46 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-00CfeWR3Jbr9BR7NM6uUM1w6FwYV_FRD_n7ksmzNtdp



Scale = 1:40.5

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.29	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.13	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.09	Horz(CT)	-0.00	5	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 39 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 10-6-12.

(lb) - Max Horz 1=265(LC 9)

Max Uplift All uplift 100 lb or less at joint(s) 1, 5 except 6=122(LC 12), 7=137(LC 12)

Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 6=412(LC 19), 7=315(LC 19)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-404/272, 2-3=-319/228

WEBS 3-6=-330/240

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 10-5-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 5 except (jt=lb) 6=122, 7=137.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	V3	Valley	1	1	I45804384
Job Reference (optional)					

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:47 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-UCm1rrRh4vz0pbawpPjvFTH5KtNji5MCRsIPczNtdo



Scale = 1:36.1

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.28	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.15	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.07	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S					Weight: 32 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=9-0-12, 4=9-0-12, 5=9-0-12
Max Horz 1=225(LC 9)
Max Uplift 1=6(LC 8), 4=50(LC 9), 5=179(LC 12)
Max Grav 1=192(LC 20), 4=143(LC 19), 5=489(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-333/236
WEBS 2-5=-377/276

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 8-11-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 4 except (jt=lb) 5=179.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804385
2765833	V4	Valley	1	1	Job Reference (optional)	

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:48 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzbhoN-zOJP2BSJrC5tQIGmTXwyRS?T_jEHSAiWR5crxezNtdn



Scale = 1:30.0

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.21	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 26 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=7-6-12, 4=7-6-12, 5=7-6-12
Max Horz 1=185(LC 9)
Max Uplift 1=16(LC 8), 4=46(LC 9), 5=162(LC 12)
Max Grav 1=128(LC 20), 4=154(LC 19), 5=410(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-313/216
WEBS 2-5=-322/259

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-7-2, Interior(1) 3-7-2 to 7-5-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 4 except (jt=lb) 5=162.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2765833	Truss V5	Truss Type Valley	Qty 1	Ply 1	Summit/#8 Osage I45804386
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:49 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzboN-RbtngXTxcWDk2ury1ESB_gYfz7a9Bd1fgLOT5zNtdm



Scale = 1:24.4

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.13	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.04	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 20 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=6-0-12, 4=6-0-12, 5=6-0-12
Max Horz 1=145(LC 9)
Max Uplift 1=6(LC 8), 4=32(LC 9), 5=131(LC 12)
Max Grav 1=120(LC 20), 4=95(LC 19), 5=320(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-255/175
WEBS 2-5=-251/230

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-4-10, Interior(1) 3-4-10 to 5-11-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 4 except (jt=lb) 5=131.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2765833	Truss V6	Truss Type Valley	Qty 1	Ply 1	Summit/#8 Osage I45804387
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:49 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzboN-RbtrnGXTxcWDk2ury1ESB_gYdL7YgBdffglLOT5zNtdm



Scale = 1:18.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.30	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.16	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 14 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2

BOT CHORD 2x4 SPF No.2

WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-7-2 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=4-6-12, 3=4-6-12

Max Horz 1=105(LC 9)

Max Uplift 1=-22(LC 12), 3=-59(LC 12)

Max Grav 1=179(LC 1), 3=192(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 4-5-6 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2765833	Truss V7	Truss Type Valley	Qty 1	Ply 1	Summit/#8 Osage I45804388
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:50 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-vnRATtUZNqLbg2Q9byzQWt5r2XwVw4vpvP5y?XzNtdl



Scale = 1:13.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.11	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.06	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 9 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-1-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=3-0-12, 3=3-0-12
Max Horz 1=66(LC 9)
Max Uplift 1=-14(LC 12), 3=-37(LC 12)
Max Grav 1=111(LC 1), 3=119(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage
2765833	V9	Valley	2	1	I45804389
Job Reference (optional)					

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:51 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-Nz?YhDUB87TSHC?L9fUf35dzYxE3fVwy73qVYzzNtdk



Scale = 1:37.3

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.31	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.16	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.08	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S					Weight: 33 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=9-4-6, 4=9-4-6, 5=9-4-6
Max Horz 1=233(LC 9)
Max Uplift 1=-4(LC 8), 4=-50(LC 9), 5=-183(LC 12)
Max Grav 1=203(LC 20), 4=138(LC 19), 5=511(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-339/242
WEBS 2-5=-393/281

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 9-3-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 4 except (jt=lb) 5=183.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2765833	Truss V10	Truss Type Valley	Qty 2	Ply 1	Summit/#8 Osage I45804390
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:40 2021 Page 1

ID:SlSjXd784vT_GMBLZatvSzboN-CsqONSMikI40TWfE?m47mg6oVVJaYhKbrgQf6zNtdv



Scale = 1:31.1

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.22	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.11	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	-0.00	4	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 27 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=7-10-6, 4=7-10-6, 5=7-10-6
Max Horz 1=193(LC 9)
Max Uplift 1=-14(LC 8), 4=-46(LC 9), 5=-165(LC 12)
Max Grav 1=142(LC 20), 4=152(LC 19), 5=425(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-318/221
WEBS 2-5=-334/262

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 7-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 4 except (jt=lb) 5=165.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2765833	Truss V11	Truss Type Valley	Qty 2	Ply 1	Summit/#8 Osage I45804391
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:41 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzbhoN-g2OmaoNwV3Ct5gEQZZIjf_DI6vriJ?zUqVPzBYzNtdu



Scale = 1:25.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.18	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.10	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	4	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P						Weight: 21 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=6-4-6, 4=6-4-6, 5=6-4-6
Max Horz 1=153(LC 9)
Max Uplift 1=-36(LC 10), 4=-42(LC 9), 5=-153(LC 12)
Max Grav 1=78(LC 9), 4=156(LC 19), 5=371(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-300/200
WEBS 2-5=-291/259

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 6-3-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 4 except (jt=lb) 5=153.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job 2765833	Truss V12	Truss Type Valley	Qty 2	Ply 1	Summit/#8 Osage I45804392
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:42 2021 Page 1

ID:SlSjxd784vt_GMBLZatvrSzbhoN-8Fy8o8NYGMKkiqpc7GqYCBiQJJAd2Swd399Xj?zNtdt



Scale = 1:19.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.35	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.19	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 15 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2

BOT CHORD 2x4 SPF No.2

WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-10-12 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=4-10-6, 3=4-10-6

Max Horz 1=113(LC 9)

Max Uplift 1=-24(LC 12), 3=-63(LC 12)

Max Grav 1=192(LC 1), 3=206(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-5-12 to 3-5-12, Interior(1) 3-5-12 to 4-9-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017


Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	145804393
2765833	V13	Valley	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:42 2021 Page 1

ID:SlSjXd784vT_GMBLZatvSzboN-8Fy8o8NYGMKkiqpc7GqYCBITcJBO2Swd399Xj?zNtdt



Scale = 1:14.2

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.14	Vert(LL)	n/a	-	n/a	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.07	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	3	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-P					Weight: 10 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2

BOT CHORD 2x4 SPF No.2

WEBS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-4-12 oc purlins, except end verticals.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=3-4-6, 3=3-4-6

Max Horz 1=74(LC 9)

Max Uplift 1=-15(LC 12), 3=-41(LC 12)

Max Grav 1=125(LC 1), 3=134(LC 19)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 5) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2765833	Truss V15	Truss Type Valley	Qty 2	Ply 1	Summit/#8 Osage I45804394
----------------	--------------	----------------------	----------	----------	------------------------------

Builders FirstSource (Valley Center),

Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:44 2021 Page 1

ID:SlSjXd784vT_GMBLZatvrSzbhoN-4d4uQdPon_bSy7z?Ehs0HcrrS6tXWM0wWTedotzNtdr

Job Reference (optional)




Plate Offsets (X,Y)--		[20:0-3-0,0-1-4]								
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES	GRIP	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.05	Vert(LL)	n/a - n/a	999	MT20	197/144
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a - n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00 11 n/a	n/a		
BCDL	10.0	Code IRC2018/TPI2014		Matrix-S					Weight: 59 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

All bearings 16-3-14.
(lb) - Max Horz 1=66(LC 12)
Max Uplift All uplift 100 lb or less at joint(s) 1, 17, 18, 19, 21, 15, 14, 13, 12
Max Grav All reactions 250 lb or less at joint(s) 1, 11, 16, 17, 18, 19, 21, 15, 14, 13, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3E) 0-7-7 to 3-7-7, Exterior(2N) 3-7-7 to 8-1-15, Corner(3R) 8-1-15 to 11-1-15, Exterior(2N) 11-1-15 to 15-8-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable studs spaced at 1-4-0 oc.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 17, 18, 19, 21, 15, 14, 13, 12.
- Non Standard bearing condition. Review required.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job	Truss	Truss Type	Qty	Ply	Summit/#8 Osage	I45804395
2765833	V16	Valley	2	1	Job Reference (optional)	

Builders FirstSource (Valley Center), Valley Center, KS - 67147,

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:45 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-YpeHQAQQYHjIIZHYBoONFpqNwpWA8Fps3I7NBKJzNtdq



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 25.0	Plate Grip DOL	1.15	TC 0.33	Vert(LL)	n/a	-	n/a	999	MT20	197/144
TCDL 10.0	Lumber DOL	1.15	BC 0.20	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code IRC2018/TPI2014		Matrix-S						Weight: 27 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=10-10-14, 3=10-10-14, 4=10-10-14
Max Horz 1=43(LC 12)
Max Uplift 1=47(LC 12), 3=55(LC 13), 4=51(LC 12)
Max Grav 1=202(LC 25), 3=202(LC 26), 4=477(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

WEBS 2-4=-330/192

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-7-9 to 3-7-9, Interior(1) 3-7-9 to 5-5-15, Exterior(2R) 5-5-15 to 8-5-15, Interior(1) 8-5-15 to 10-4-5 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Gable requires continuous bottom chord bearing.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3, 4.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Job 2765833	Truss V17	Truss Type Valley	Qty 2	Ply 1	Summit/#8 Osage 145804396
Builders FirstSource (Valley Center), Valley Center, KS - 67147,					Job Reference (optional)

8.430 s Mar 22 2021 MiTek Industries, Inc. Fri Apr 23 09:17:45 2021 Page 1

ID:SlSjxd784vT_GMBLZatvrSzbhoN-YpeHQAQQYHjZHYBoONFpqN_KWA?Fpf3I7NBKJzNtdq



3x6 =

Scale = 1:11.6




Plate Offsets (X,Y)-- [2:0-3-0,Edge]		5-7-14		5-7-6	
LOADING (psf)		SPACING-		CSI.	
TCLL	25.0	Plate Grip DOL	1.15	TC	0.11
TCDL	10.0	Lumber DOL	1.15	BC	0.21
BCLL	0.0	Rep Stress Incr	YES	WB	0.00
BCDL	10.0	Code	IRC2018/TPI2014	Matrix-P	
				DEFL.	
				in (loc) l/defl L/d	
				Vert(LL) n/a - n/a 999	
				Vert(CT) n/a - n/a 999	
				Horz(CT) 0.00 3 n/a n/a	
				PLATES	
				MT20	
				GRIP	
				197/144	
				Weight: 12 lb	
				FT = 20%	

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-

TOP CHORD Structural wood sheathing directly applied or 5-7-14 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS.

(size) 1=5-6-14, 3=5-6-14
Max Horz 1=19(LC 16)
Max Uplift 1=33(LC 12), 3=33(LC 13)
Max Grav 1=198(LC 1), 3=198(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=4.2psf; h=25ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Gable requires continuous bottom chord bearing.
- 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
- 6) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.



April 23, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see

ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component


Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601




16023 Swingley Ridge Rd
Chesterfield, MO 63017

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MiTek 20/20** software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MiTek® All Rights Reserved



MiTek Engineering Reference Sheet: MII-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.