


# Saint Luke's East Hospital

## Rockhill Orthopedics X-Ray Renovations 120 NE Saint Luke's Blvd, Suite 200 Lee's Summit, MO 64086



7/1/2021 11:46:41 AM  
Samuel K. Beckman - Architect  
License - Missouri WA-2011012130



1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

### MEP Engineers

IMEG Corp.  
1600 Baltimore Suite 300  
Kansas City MO 64108  
816.842.8347

## ROCKHILL X-RAY RENOVATION

**ARCHITECT**  
ACI BOLAND, INC.

1710 WYANDOTTE STREET  
KANSAS CITY, MO 64108  
PHONE 816.763.9600  
FAX 816.763.9757


**ENGINEER**  
IMEG Corp.

1600 BALTIMORE  
SUITE 300  
KANSAS CITY, MO 64108  
PHONE 816.842.8437


### ABBREVIATIONS

AC.	ACOUSTIC/ACOUSTICAL	FLOR.	FLUORESCENT	PTD.	PAINTED
ADD.	ADDENDUM	FTG.	FOOTING	PG.	PAGE
ADDN.	ADDITION	FND.	FOUNDATION	PLAM.	PLASTIC LAMINATE
ABC.	AGGREGATE BASE COURSE	FR.	FRAME	PK.	PAIR
AFF.	ABOVE FINISH FLOOR	F.H.C.	FIRE HOSE CAB.	PNL.	PANEL
AGG.	AGGREGATE	FV.	FIELD VERIFY	PTN.	PARTITION
ANC.	AIR CONDITIONING	GA.	GAUGE	PL.	PLATE
AL.	ALUMINUM	GL.	GLASS / GLAZING	PLBG.	PLUMBING
ALT.	ALTERNATE	GD.	GRADE	PLYWD.	PLYWOOD
A.B.	ANCHOR BOLT	G.	GRADE	PT.	POINT
AND	AND	G.	GRADE	GRAM.	GRAM
ARCH.	ARCHITECT	GRL.	GRILLE	P.S.I.	POUNDS PER SQ. IN.
ASP.	ASPHALT	GRD.	GRID	P.S.F.	POUNDS PER SQ. FT.
@	AT	GND.	GROUND	P.C.	PRECAST
ACT.	ACOUSTIC CEILING TILE/PANEL	GYP.	GYPSUM	P.L.	PROPERTY LINE
ANGLE	ANGLE	GYP.B.	GYPSUM BOARD	R.	RISER, RISERS
BLKG.	BLOCKING	H.R.	HAND RAIL	RAD.	RADIUS
BSMT.	BASEMENT	HDN.	HARDENER	R.D.	ROOF DRAIN
BM.	BEAM	HDW.	HARDWARE	RB.	RESILIENT BASE
B.M.	BENCHMARK	HDWD.	HARDWOOD	RE.	REFER TO
BOARD	BOARD	HTR.	HEATER	REG.	REGISTER
B.O.	BOTTOM OF	HT.	HEIGHT	REGD.	REQUIRED
BLDG.	BUILDING	H.P.	HIGH POINT	REV.	REVISION
CABT.	CABINET	H.M.	HOLLOW METAL	RFG.	ROOFING
C.I.P.	CAST IN PLACE	HORIZ.	HORIZONTAL	RGL.	ROUGH
C.B.	CATCH BASIN	H.S.	HOSE BIB	RM.	ROOM
C.C.	CEILING	H.W.	HOT WATER	RND.	ROUND
CEM.	CEMENT/CEMENTITIOUS	C.L.	CLEAR	R.O.	ROUGH OPENING
CG.	CENTRIGRAM	IN.	INCH / INCHES	SCHED.	SCHEDULE
CM.	CENTRIMETER	CM.	CENTRIMETER	S.C.	SEALED CONCRETE
CL.	CENTER LINE	INSUL.	INSULATION	SCR.	SCREW
CER.	CERAMIC	INT.	INTERIOR	SECT.	SECTION
C.F.	CERAMIC TILE	INV.	INVERT	SEL.	SELECT
CHAN.	CHANNEL	JAN.	JANITOR	SEL.	SELECT
CH.	CHANNEL	JT.	JOINT	SHG.	SHEATHING
CLR.	CLEAR	JST.	JOIST	SHT.	SHEET
C.O.	CLEAN OUT	K.P.	KICK PLATE	SDG.	SIDING
CLOS.	CLOSET	LAM.	LAMINATED	SIM.	SIMILAR
COL.	COLUMN	LB.	POUND	SLDG.	SLIDING
CONC.	CONCRETE	LDG.	LANDING	SM.	SMOOTH
CONN.	CONNECTION	LTH.	LATH	SPEC.	SPECIFICATION
CONST.	CONSTRUCTION	LAV.	LAVATORY	SQ.	SQUARE
C.J.	CONTROL JOINT	LG.	LENGTH	STD.	STANDARD
CONTR.	CONTRIBUTUS	LOC.	LOCATION	STD.	STANDARD
CONTR.	CONTRACTOR	LOC.	LOCATION	S.S. /	S.S. /
CORR.	CORRUGATED	LOC.	LOCATION	ST.STL.	STAINLESS STEEL
CTR.	COUNTER	LT.	LIGHT	STRUC.	STRUCTURE
CTSK.	COUNTERSUNK	L.W.C.	LIGHT WEIGHT CONCRETE	SUSP.	SUSPENDED
C.M.U.	CONCRETE MASONRY UNIT	LVR.	LOUVER	SW.BD.	SWITCHBOARD
		LOC.	LOCATION	SYS.	SYSTEM
D.P.	DAMP PROOFING	M.O.	MASONRY OPENING	T.	TREAD
DIAG.	DIAGONAL	MATL.	MATERIAL	T.C.	TOP OF CURB
DIAM.	DIAMETER	MFR.	MANUFACTURER	T.G.	TEMPERED GLASS
DM.	DIMENSION	MR.	MARKER BOARD	T.O.	TOP OF
DISP.	DISPENSER	MB.	MARKER BOARD	T.S.D.	TOP OF STEEL DECK
DWL.	DOWEL	MAX.	MAXIMUM	T.W.	TEACHERS WARDROBE
DN.	DOWN	MECH.	MECHANICAL	TYP.	TYPICAL
D.S.	DOWNSPOUT	M.L.	METAL LATH	U.O.N.	UNLESS OTHERWISE NOTED
DWG.	DRAWING	M.	METER	V.	VENT
		MIN.	MINIMUM	VERT.	VERTICAL
EA.	EACH	MLDG.	MOLDING	V.G.	VERTICAL GRAIN
ELEC.	ELECTRIC	MULL.	MULLION	VEST.	VESTIBULE
E.W.C.	ELECTRIC WATER COOLER	N.G.	NATURAL GRADE	V.C.T.	VINYL COMPOSITION TILE
ELEV.	ELEVATOR	NOM.	NOMINAL	VCP.	VITREOUS CLAY PIPE
ELEV.	ELEVATOR	N.I.C.	NOT IN CONTRACT	W.W.M.	WELDED WIRE MESH
EQ.	EQUAL	N.T.S.	NOT TO SCALE	W.C.	WATER CLOSET
EQUIP.	EQUIPMENT	NO. / #	NUMBER	W.H.	WATER HEATER
EXH.	EXHAUST	ONS.	OBSOLETE	W.F.	WIDE FLANGE
EXPAN.	EXPANSION	OPNG.	OPENING	W.	WITH
E.J.	EXPANSION JOINT	O.A.	OVERALL	W/O.	WITHOUT
EXT.	EXISTING	O.D.	OUTSIDE DIAMETER	W.	WOOD
EXT.	EXTERIOR	O.F.S.	OVERFLOW SCUPPER	WDW.	WINDOW
FT.	FEET / FOOT	O.F.D.	OVERFLOW DRAIN	W.W.	WINDOW WALL
FL.	FLOOR	O.H.D.	OVERHEAD DOOR		
F.D.	FLOOR DRAIN				

### LOCATION PLAN



### AREA OF CONSTRUCTION



### GENERAL NOTES

- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH A.D.A. REQUIREMENTS AND ALL APPLICABLE LOCAL, STATE, AND FEDERAL BUILDING CODES AND REGULATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY BUILDING PERMITS.
- THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL FIELD VERIFY EXISTING CONDITIONS AND NOTIFY THE ARCHITECT OF ANY INCONSISTENCIES OR DISCREPANCIES WITH THE PROJECT DOCUMENTS. ACCESS TO THE SITE AND/OR SPACE UNDER CONSTRUCTION DURING BIDDING AND CONSTRUCTION SHALL BE COORDINATED WITH THE OWNER.
- DO NOT SCALE DRAWINGS.
- THE WORD "ALIGN" AS USED IN THESE DOCUMENTS SHALL SUPERSEDE ANY DIMENSIONAL INFORMATION GIVEN.
- TYPICAL DIMENSIONS ARE TO FACE OF CONCRETE, DRYWALL, CURTAIN WALL, ETC., OR TO COLUMN CENTERLINE. DIMENSIONS AT WINDOWS ARE TYPICALLY TO FACE OF FRAME. REFER TO PLAN DETAILS FOR ADDITIONAL INFORMATION.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING AND CONFIRMING ALL SUBSTRATE CONDITIONS WHERE NEW MATERIALS ARE APPLIED. THE SUBSTRATE SHALL BE SMOOTH AND FREE OF DEFECTS AND SHALL CONFORM TO THE REQUIREMENTS OF THE FINISHED MATERIAL MANUFACTURERS.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR CLEAN-UP.
- THE GENERAL CONTRACTOR SHALL INSPECT AND CHECK THE ADEQUACY AND INSTALLATION OF THROUGH-WALL FLASHING PRIOR TO COVERING WITH FINISH MATERIALS. THIS SHALL INCLUDE, BUT IS NOT LIMITED TO, INSPECTION AGAINST HOLES OR PENETRATIONS, APPROPRIATE LAPPING AND SEALING, AND OVERALL WORKMANSHIP IN CONFORMANCE WITH THE SPECIFICATIONS.
- ANY OBJECTS PROJECTING MORE THAN 4 INCHES FROM THE FINISHED FACE OF WALL INTO A CIRCULATION PATH SHALL NOT HAVE A HEAD CLEARANCE OF LESS THAN 80" (6'-8").
- GENERAL CONTRACTOR TO INSTALL FIRE RETARDANT WOOD BLOCKING FOR ALL EQUIPMENT OVER RULERS AND FIRE RETARDANT FLYWOOD FOR EQUIPMENT UNDER 50 LBS. AS REQUIRED FOR THE MOUNTING OF ALL EQUIPMENT.

### SHEET INDEX

SHEET NUMBER	SHEET NAME	DISCIPLINE	DISCIPLINE ORDER	SHEET ORDER
ARCHITECTURE				
A0.1	COVER SHEET	ARCHITECTURE	4	
A0.2	CODE FOOTPRINT PLAN AND WALL PARTITIONS	ARCHITECTURE	4	
A2.1	FIRST FLOOR DEMO, DIMENSION, AND RCP PLAN	ARCHITECTURE	4	
A4.1	DOOR & FRAME SCHEDULE, OVERALL FLOOR FINISH PLAN, ROOM FINISH SCHEDULE, & LEGEND	ARCHITECTURE	4	
MECHANICAL				
M00	MECHANICAL COVERSHEET	MECHANICAL	6	1
M102	SECOND FLOOR DEMOLITION - PIPING	MECHANICAL	6	2
M112	SECOND FLOOR DEMOLITION - VENTILATION	MECHANICAL	6	3
M202	SECOND FLOOR - PIPING	MECHANICAL	6	4
M212	SECOND FLOOR - VENTILATION	MECHANICAL	6	5
M410	VENTILATION AND PIPING DETAILS	MECHANICAL	6	6
M610	VENTILATION SCHEDULES AND CONTROL DIAGRAMS	MECHANICAL	6	7
PLUMBING				
P000	PLUMBING COVERSHEET	PLUMBING	7	
P202	SECOND FLOOR - PLUMBING	PLUMBING	7	
ELECTRICAL				
E000	ELECTRICAL SYMBOLS LISTS	ELECTRICAL	8	
E001	ELECTRICAL GENERAL NOTES AND DETAILS	ELECTRICAL	8	
E002	SECOND FLOOR OVERALL PLAN	ELECTRICAL	8	
E102	SECOND FLOOR DEMOLITION - LIGHTING	ELECTRICAL	8	
E112	SECOND FLOOR DEMOLITION - POWER	ELECTRICAL	8	
E122	SECOND FLOOR DEMOLITION - SYSTEMS	ELECTRICAL	8	
E202	SECOND FLOOR - LIGHTING	ELECTRICAL	8	
E212	SECOND FLOOR - POWER	ELECTRICAL	8	
E222	SECOND FLOOR - SYSTEMS	ELECTRICAL	8	
GENERAL				
GE X-RAY	GE OPTIMA XR840 X-RAY VENDOR PACKAGE	GENERAL	9	
RAD X-RAY	GE OPTIMA XR840	GENERAL	9	
SAMSUNG X-RAY	SAMSUNG GC35 X-RAY VENDOR PACKAGE	GENERAL	9	

Saint Luke's East Hospital  
ROCKHILL ORTHOPAEDIC X-RAY RENOVATION  
120 NE SAINT LUKE'S BLVD, SUITE 200  
LEE'S SUMMIT MO 64086

Date 07.02.2021  
Job Number 3-21014  
Drawn By BRD  
Checked By GS

Revision  
Number Date Description



### PARTITION GENERAL NOTES

- UNLESS NOTED OTHERWISE, ALL INTERIOR METAL STUDS ARE 3/8" THICK. REFER TO SUFFIX SCHEDULE BELOW FOR LOCATIONS OF METAL STUDS OTHER THAN 3/8" THICK. NOTE: STUD THICKNESS (GAUGE) MUST CONFORM TO MANUFACTURER'S RECOMMENDATIONS FOR SPAN (HEIGHT OF STUD).
- WHERE THE PARTITION TYPE INDICATION IS SHOWN WITH A NUMERICAL SUFFIX, THE METAL STUD THICKNESS SHALL BE AS SCHEDULED BELOW.
 

SUFFIX	MTL. STUD THICKNESS
1	1-5/8" MTL. STUDS
2	2-1/2" MTL. STUDS
3	6" MTL. STUDS
4	8" MTL. STUDS
- UNLESS NOTED OTHERWISE, ALL INTERIOR DRYWALL PARTITIONS INDICATED ON THE FLOOR PLAN DRAWING ARE TYPE 'A' PARTITIONS, WHERE OCCURS, RATINGS ARE AS INDICATED ON THE LIFE SAFETY PLANS.
- ALL STUDS ARE CONTINUOUS FROM FLOOR STRUCTURE TO CEILING STRUCTURE UNLESS NOTED OTHERWISE.
- METAL STUDS ARE SPACED @ 16" O.C. MAX., UNLESS NOTED OTHERWISE.
- UNLESS NOTED OTHERWISE, ALL GYPSUM BOARD IS TO BE 5/8" THICK 'FIRCODE'.
- THE LOCATION OF A CHANGE IN THE PARTITION TYPE IS INDICATED BY A WALL TAG.
- THE CORRESPONDING RATED ASSEMBLIES ARE INDICATED BELOW THE PARTITION TYPES.
- PARTITION TYPE DESIGNATIONS ARE INDICATED ON THE FLOOR PLAN DRAWINGS.
- PARTITION TYPES DO NOT INCLUDE APPLIED FINISHES CALLED FOR IN THE ROOM FINISH SCHEDULE.
- AT PARTITION TYPES WHERE MTL. STUDS ARE EXPOSED ON ONE OR BOTH SIDES, CUT STUD 1/4" SHORT AND SCREW BOTH SIDES TO MTL. RUNNER TRACK.

### CODE SUMMARY

**Project Construction Purpose:** Interior replacement and addition of x-ray equipment and new x-ray room.

**Project Address:** Rockhill Orthopaedic, 100 NE Saint Luke's Boulevard

**Code Information:** 2018 International Building Code, 2018 International Plumbing Code, 2018 International Mechanical Code, 2018 International Fuel Gas Code, 2018 International Fire Code, 2017 National Electrical Code, 2009 ICC/ANSI A117.1 as amended and adopted by the City of Lee's Summit

**State of Missouri Dept. of Health & Environment references the following codes:** 2012 NFPA 101 Life Safety Code (LSC), 2014 FGI Guidelines for Design & Construction of Hospitals & Outpatient Facilities

**Owner Information:** Saint Luke's Lee's Summit, 100 NW Saint Luke's Blvd, Lee's Summit, MO 64093

**Designer Information:** ACI Boland Architects, 1710 Wyandotte St., Kansas City, MO 64108, Phone: (816) 763-9600, Fax: (816) 763-9757

**Local Authority:** Responding Life Service: Lee's Summit Fire Department, Local Building Inspection: Lee's Summit, MO Codes Administration Department

**Type of Construction:** Type 1-A - Section 602.2 (Type 1 - 332 Sprinklered - Section 18.1.6.1), 755+- SF

**Area of Renovation:** 755+- SF

**Occupancy Group:** B - Business - professional services - Section 304

**Occupant Load:** Total 2nd floor Square Footage = 19,000SF / 100, Total Number of Occupants = 190

**Required Fire Resistance Ratings (in hours) per NFPA 101 A.2.2.2:**

Exterior Bearing Walls	3 HR
Interior Bearing Walls	3 HR
Primary Structural Frame	3 HR
Floor Construction	2 HR
Roof Construction	1 1/2 HR
Interior non-bearing walls	0 HR

**Active Fire Safety Features:**

- Fire Alarm System:** The fire alarm system is specified as an addressable type system. The device type and locations are per the applicable codes as well as ADA requirements.
- Smoke Control System:** All ductwork penetrating smoke rated walls will have a smoke or combination fire/smoke damper as indicated on construction documents. These dampers will close upon detection of smoke by the area smoke detectors or duct smoke detectors in the air handling units.
- Fire Sprinkler System:** Specified to be per NFPA 13. The sprinkler heads are specified to be quick response type.
- Emergency Lighting and Power:** Emergency lighting, life safety and critical loads will receive power from a backup generator located outside the main electrical room.
- Illuminated Exit Signs**

**Passive Fire Safety Features:**

- Smoke Compartments no greater than 22,500 SF

### CODE FOOTPRINT LEGEND

**PARTITION TYPES**




- 0 HR SMOKE PARTITION (SMOKE RESISTIVE)
- 1 HR SMOKE BARRIER
- 1 HR FIRE BARRIER
- 2 HR FIRE BARRIER
- 2 HR FIRE SMOKE BARRIER

**AREA DESIGNATIONS**

- HAZARDOUS ROOM
- EXIT ENCLOSURE
- SHAFT
- NOT IN ARCHITECTURAL SCOPE

**SYMBOLS**

- FIRE EXIT
- OCCUPANT LOAD
- EXIT WIDTH PROVIDED
- EXIT WIDTH REQUIRED
- TRAVEL DISTANCE



### GENERAL NOTES

- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH A.D.A. REQUIREMENTS AND ALL APPLICABLE LOCAL, STATE, AND FEDERAL BUILDING CODES AND REGULATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY BUILDING PERMITS.
- THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL FIELD VERIFY EXISTING CONDITIONS AND NOTIFY THE ARCHITECT OF ANY INCONSISTENCIES OR DISCREPANCIES WITH THE PROJECT DOCUMENTS. ACCESS TO THE SITE AND/OR SPACE UNDER CONSTRUCTION DURING BIDDING AND CONSTRUCTION SHALL BE COORDINATED WITH THE OWNER.
- DO NOT SCALE DRAWINGS.
- THE WORD "ALIGN" AS USED IN THESE DOCUMENTS SHALL SUPERSEDE ANY DIMENSIONAL INFORMATION GIVEN.
- TYPICAL DIMENSIONS ARE TO FACE OF CONCRETE, DRYWALL, CURTAIN WALL, ETC., OR TO COLUMN CENTERLINE. DIMENSIONS AT WINDOWS ARE TYPICALLY TO FACE OF FRAME. REFER TO PLAN DETAILS FOR ADDITIONAL INFORMATION.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING AND CONFIRMING ALL SUBSTRATE CONDITIONS WHERE NEW MATERIALS ARE APPLIED. THE SUBSTRATE SHALL BE SMOOTH AND FREE OF DEFECTS AND SHALL CONFORM TO THE REQUIREMENTS OF THE FINISHED MATERIAL MANUFACTURER'S RECOMMENDATIONS.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR CLEAN-UP.
- THE GENERAL CONTRACTOR SHALL INSPECT AND CHECK THE ADEQUACY AND INSTALLATION OF THROUGH-WALL FLASHING PRIOR TO COVERING WITH FINISH MATERIALS. THIS SHALL INCLUDE, BUT IS NOT LIMITED TO, INSPECTION AGAINST HOLES OR PENETRATIONS, APPROPRIATE LAPPING AND SEALING, AND OVERALL WORKMANSHIP IN CONFORMANCE WITH THE SPECIFICATIONS.
- ANY OBJECTS PROJECTING MORE THAN 4 INCHES FROM THE FINISHED FACE OF WALL INTO A CIRCULATION PATH SHALL NOT HAVE A HEAD CLEARANCE OF LESS THAN 80" (6'-8").
- GENERAL CONTRACTOR TO INSTALL FIRE RETARDANT WOOD BLOCKING FOR ALL EQUIPMENT OVER SLEBS AND FIRE RETARDANT PLYWOOD FOR EQUIPMENT UNDER SLEBS, AS REQUIRED FOR THE MOUNTING OF ALL EQUIPMENT.

### EQUIPMENT MOUNTING HEIGHTS

1/4" = 1'-0"

### ELECTRICAL DEVICE MOUNTING HEIGHTS

1/4" = 1'-0"


### SYMBOLS

1/4" = 1'-0"

\*THIS DRAWING IS INTENDED TO BE PRINTED IN COLOR. USE BLACK AND WHITE COPIES AT YOUR OWN RISK.




- ### REFLECTED CEILING NOTES
- EXISTING MEPP DEVICES SHOWN ARE BASED ON EXISTING DRAWINGS AND/OR FIELD OBSERVATIONS. THE OWNER/ARCHITECT DOES NOT GUARANTEE THE ACCURACY/LOCATION OR QUANTITY OF EXISTING DEVICES.
  - CONTRACTOR TO PROVIDE ALL REQUIRED LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO MEET AND COMPLETE THE REQUIREMENTS OF THE NEW CONSTRUCTION.
  - ALL EXISTING CONSTRUCTION TO REMAIN SHALL BE PATCHED, REPAIRED, AND PREP AS REQUIRED FOR NEW FINISH APPLICATION.
  - SEE FINISH SCHEDULE FOR FINISH LOCATION AND SPECIFICATIONS.
  - PAINT THE UNDERSIDE OF ALL GYPSUM BOARD CEILINGS, BULKHEADS AND SOFFITS (PT-4) UNLESS NOTED OTHERWISE.
  - HIS PLAN SHALL BE USED TO COORDINATE THE CEILING LAYOUT WITH MECHANICAL AND ELECTRICAL WORK. VERIFY THE EXACT QUANTITY REQUIRED.
  - CONTRACTOR TO REFER TO THE ELECTRICAL PLANS FOR ACTUAL LIGHTING SIZES AND FIXTURE TYPES.
  - SEE SPECIFICATIONS FOR CEILING TYPES.
  - REFER TO ARCHITECTURAL FLOOR PLANS FOR MATERIAL LEGEND OF ALL TYPES.
  - ALL CEILINGS SHALL BE 9'-0" AFF UNLESS OTHERWISE NOTED.



### KEYNOTES - RCP

Number	Comments
1	MATCH ORIGINAL CEILING HEIGHT
2	EQUIPMENT RAIS SUPPORTED WITH NEW UNISTRUT STRUCTURE ABOVE CEILING. PROVIDE DRAWINGS FROM UNISTRUT, SIGNED AND SEALED BY AN ENGINEER IN THE STATE OF MISSOURI VERIFYING SUPPORT OF NEW LOADS TO EXISTING STRUCTURE. RE: VENDOR DRAWINGS.
3	ADJUST EXISTING SPRINKLER HEADS TO MATCH NEW CEILING HEIGHT
4	NEW LIGHTS, RE: ELECT. COORDINATE LAYOUT WITH CEILING MOUNTED EQUIPMENT

- ### GENERAL PLAN NOTES
- ALL NOTES ARE SUBJECT TO THE GENERAL NOTES AND SPECIFICATIONS.
  - DO NOT SCALE DRAWINGS.
  - THE WORD "ALUM" AS USED IN THESE DOCUMENTS SHALL SUPERSEDE ANY DIMENSIONAL INFORMATION GIVEN.
  - TYPICAL DIMENSIONS ARE TO FACE OF CONCRETE, DRYWALL, CURTAIN WALL, ETC., OR TO COLUMN CENTERLINE. DIMENSIONS AT WINDOWS ARE TYPICALLY TO FACE OF FRAME. REFER TO PLAN DETAILS FOR ADDITIONAL INFORMATION.
  - ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH A.D.A. REQUIREMENTS AND ALL APPLICABLE LOCAL, STATE, AND FEDERAL BUILDING CODES AND REGULATIONS.
  - THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY BUILDING PERMITS.
  - THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL FIELD VERIFY EXISTING CONDITIONS AND NOTIFY THE ARCHITECT OF ANY INCONSISTENCIES OR DISCREPANCIES WITH THE PROJECT DOCUMENTS. ACCESS TO THE SITE AND SPACE UNDER CONSTRUCTION DURING BIDDING AND CONSTRUCTION SHALL BE COORDINATED WITH THE OWNER.
  - THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING AND CONFIRMING ALL SUBSTRATE CONDITIONS WHERE NEW MATERIALS ARE APPLIED. THE SUBSTRATE SHALL BE SMOOTH AND FREE OF DEFECTS AND SHALL CONFORM TO THE REQUIREMENTS OF THE FINISHED MATERIAL MANUFACTURERS RECOMMENDATIONS.
  - CONTRACTOR TO PROVIDE ALL REQUIRED LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO MEET AND COMPLETE THE REQUIREMENTS OF THE NEW CONSTRUCTION.
  - ALL EXISTING CONSTRUCTION TO REMAIN SHALL BE PATCHED, REPAIRED, AND PREP AS REQUIRED FOR NEW FINISH APPLICATION.
  - DO NOT CLOSE OR OBSTRUCT WALKWAYS, EXITS, OR OTHER FACILITIES USED BY OCCUPANTS OF BUILDINGS WITHOUT WRITTEN PERMISSION FROM AUTHORITIES HAVING JURISDICTION.
  - CONDUCT ALL OPERATIONS IN A SAFE WORKING MANNER TO PREVENT DAMAGE OR INJURY TO ADJACENT SPACES, BUILDING, STRUCTURE, OTHER FACILITIES, AND PERSONS.
  - IF MATERIAL SUSPECTED OF CONTAINING HAZARDOUS MATERIALS ARE ENCOUNTERED, DO NOT DISTURB. IMMEDIATELY NOTIFY ARCHITECT AND OWNER. OWNER SHALL COORDINATE WITH CONTRACTOR ON THE REMOVAL OF SUCH ITEMS. WORK MAY PROCEED AFTER HAZARDOUS MATERIAL HAS BEEN REMOVED.
  - CONTRACTOR SHALL FURNISH AND INSTALL CONCEALED FIRE-TREATED WOOD BLOCKING BEHIND ALL CABINETS, TOILET ACCESSORIES, PLUMBING FIXTURES, AND OTHER WALL MOUNTED ITEMS AS REQUIRED FOR ADEQUATE SUPPORT.
  - UPON VERIFICATION OF THE EXISTING CONDITIONS, THE CONTRACTOR SHALL DETERMINE AND RECOMMEND THE BEST ACTION TO MINIMIZE THE EXTENT OF REMOVAL WORK FOR INSTALLATION OF NEW WORK.
  - SEE FINISH SCHEDULE FOR FINISH LOCATION AND SPECIFICATIONS.
  - SEE DOOR SCHEDULE FOR DOOR SPECIFICATIONS.
  - CONFIRM FINAL MOUNTING LOCATION OF ALL OFCI EQUIPMENT.
  - SLAB MUST BE THICK ENOUGH TO EMBED GE PROVIDED ANCHORS TO 3.5". IF THIS THICKNESS ISN'T POSSIBLE, CONTRACTOR MUST PROVIDE ANCHORS SOLUTION.
  - VERIFY FLOOR LEVELNESS NOT TO EXCEED .2" OVER 10 FOOT.
  - CONTRACTOR MUST VERIFY THAT THERE ARE NO ANCHORING CONFLICTS PRIOR TO INSTALL BEGINNING OF X-RAY EQUIPMENT.



### FFE SCHEDULE

TYPE MARK	DESCRIPTION	RESPONSIBILITY	COMMENTS
A5077	HAND SANITIZER	OF/CI	
M1801	Computer Monitor	OF/CI	NEW CONSTRUCTION





### KEYNOTES - FLOOR PLAN

Number	Comments
1	NEW WALL INFILL, PATCH AND PAINT CORRIDOR SIDE TO MATCH ADJACENT FINISH. RE: FINISH SCHEDULE
2	NEW LEAD LINED DOOR AND FRAME AT EXISTING OPENING. RE: DOOR SCHEDULE
3	UPPER AND LOWER CASEWORK BY FURNITURE SUPPLIER
4	NEW 30" CASED OPENING WITH 7'-0" HEADER RE: FRAME TYPE 7
6	MODIFY EXISTING WALL TO MEET WALL TYPE "N" CONSTRUCTION - LEAD LINED WALL PARTITION
7	INSTALL NEW X-RAY EQUIPMENT GE OPTIMA XRAY. RE: VENDOR PLANS
8	INSTALL EXISTING X-RAY EQUIPMENT SAMSUNG GC8. RE: VENDOR PLANS
9	REINSTALL SALVAGED EQUIPMENT ACCESSORIES, SIGNAGE, ETC AS DIRECTED BY OWNER. ENSURE IN-WALL FIRE BLOCKING IS PROVIDED AS REQUIRED.
10	NEW SOLID SURFACE TECH DESK. VERIFY WITH OWNER GROMMET LOCATION
11	X-RAY IN USE SIGNAGE

- ### GENERAL DEMOLITION NOTES
- THE OWNER SHALL VACATE THE EXISTING ROOMS AS INDICATED ON THE PLAN AND BE RESPONSIBLE FOR THE REMOVAL OF ANY EQUIPMENT WHICH IS TO REMAIN THE PROPERTY OF THE OWNER PRIOR TO ANY WORK DONE BY THE CONTRACTOR FOR THIS PORTION OF THE SEQUENCE.
  - INSTALL TEMPORARY DUST PARTITION AND/OR BARRIERS AND OTHER METHODS AS MAY BE REQUIRED NECESSARY AS INDICATED ON THE PLAN AND AS NECESSARY TO CONTAIN DEMOLITION CONSTRUCTION DUST AND DEBRIS WITHIN THE AREA OF CONSTRUCTION. REFER TO DUST PARTITION 'DP' ON THIS SHEET AND THE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
  - IT IS THE INTENT OF THIS DEMOLITION TO REMOVE ALL EXISTING CONSTRUCTION WHICH CONFLICTS WITH THE INTENT OF THE NEW CONSTRUCTION. EVERY DEMOLITION DETAIL MAY NOT NECESSARILY BE COVERED ON THESE DRAWINGS. FIELD VERIFY THE EXTENT OF ALL DEMOLITION.
  - THE CONTRACTOR SHALL USE EXTREME CARE IN THE PROTECTION OF ALL ADJACENT AREAS FOR IT IS IMPERATIVE TO PROVIDE CONTINUOUS OPERATION OF ALL OCCUPIED AREAS DURING THE DEMOLITION, CONSTRUCTION AND RENOVATION.
  - THE CONTRACTOR SHALL COORDINATE ALL DEMOLITION WORK WITH OCCUPIED SPACES ABOVE, BELOW AND ADJACENT TO THE WORK. THE CONTRACTOR SHALL NOTIFY THE OWNER AND THE MANAGEMENT OF THE OCCUPIED SPACES ABOVE, BELOW AND ADJACENT TO THE WORK. TWO WEEKS PRIOR TO COMMENCING WORK, SUCH SPACES ARE TO REMAIN OCCUPIED DURING DEMOLITION AND ALL WORK SHALL BE PERFORMED IN SUCH A MANNER TO MINIMIZE DISRUPTION TO OCCUPIED SPACES. EXISTING FLOOR, WALL AND CEILING FINISHES TO REMAIN SHALL BE PROTECTED AND ANY DAMAGE DONE AS A RESULT OF DEMOLITION WORK SHALL BE REPAIRED.
  - IN AREAS SCHEDULED FOR DEMOLITION, THE CONTRACTOR SHALL REMOVE ALL ACCESSORIES, GRAB BARS, MIRRORS, SOAP AND PAPER TOWEL DISPENSERS, SHELVES, BULLETIN BOARDS, ETC., SHALL BE TURNED OVER TO THE OWNER, EXCEPT FOR RELOCATED ITEMS.
  - WHERE NEW FINISHES ARE CALLED FOR, REMOVE AND DISCARD EXISTING FLOORING, CEILING AND WALL COVERING THROUGH-OUT AREA DESIGNATED FOR NEW CONSTRUCTION AND PREP EXISTING FLOOR AND WALL SUBSTRATE TO RECEIVE THE INSTALLATION OF NEW FINISH AS SCHEDULED.
  - SEE NEW WORK PLAN FOR REPAIR AND PREPARATION OF ADJACENT SURFACES.
  - WHERE CEILING IS TO REMAIN, REMOVE ALL DAMAGED CEILING PANELS/ TILES AND REPLACE WITH NEW TO MATCH EXISTING.
  - REMOVE AND RETURN TO THE OWNER ALL EXISTING PLUMBING FIXTURES. CAP ALL SUPPLY AND WASTE LINES AS REQUIRED. REFER TO PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.
  - THE CONTRACTOR SHALL PATCH TO MATCH ADJACENT SURFACES OF EXISTING WALLS, FLOOR, AND CEILING IN ALL AREAS THAT REQUIRE THE REMOVAL OF GENERAL MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION WORK AND OF EQUIPMENT AND FIXTURES.
  - THE CONTRACTOR SHALL PROVIDE FOR ALL NECESSARY TEMPORARY RELOCATION AND MAINTENANCE OF ALL EXISTING UTILITIES WHICH ARE CURRENTLY IN USE AND WHICH MUST BE TEMPORARILY RELOCATED DURING CONSTRUCTION OF NEW AREAS AND RENOVATION OF EXISTING AREAS.
  - REFER TO MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION DRAWINGS FOR WORK REQUIRED FOR NEW CONSTRUCTION.
  - WHERE REMOVAL OF EXISTING PARTITIONS, EQUIPMENT, ETC. DISTURBS EXISTING MECHANICAL, PLUMBING OR ELECTRICAL SERVICES, THE CONTRACTOR SHALL MAKE PERMANENT REVISIONS/PROVISIONS AS REQUIRED TO MAINTAIN SERVICES AND IF NECESSARY PROVIDE TEMPORARY SERVICES TO AREAS NOT SCHEDULED FOR DEMOLITION, RENOVATION, AND/OR NEW CONSTRUCTION.
  - WHERE EXISTING WALLS, CEILING, OR FLOORS ARE DAMAGED BY THE CONTRACTOR FOR ACCESS TO SERVICES AND NEW CONSTRUCTION WHICH MAY NOT BE INDICATED IN THE CONTRACT DOCUMENTS, THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH TO MATCH MATERIAL AND FINISHES TO ORIGINAL CONDITIONS. IF EXISTING FINISHES CANNOT BE MATCHED, THE ENTIRE WALL, CEILING, OR FLOOR SHALL BE REFINISHED TO THE NEAREST CORNER OR POSITIVE BREAKING POINT.
  - WHEN DEMOLITION CAUSES DAMAGE TO FLOOR SLAB, WALL, OR CEILING SURFACES WHICH WILL REMAIN EXPOSED IN THE FINISHED WORK, SUCH CONDITIONS SHALL BE REPAIRED AND LEVELLED AS REQUIRED TO RECEIVE NEW FINISHES.
  - WHEN DEMOLITION EXPOSES DAMAGE TO FLOOR SLAB, WALL, OR CEILING SURFACES WHICH WILL REMAIN EXPOSED IN THE FINISHED WORK, SUCH CONDITIONS SHALL BE REPORTED TO THE ARCHITECT AND OWNER WITH A RECOMMENDATION FOR RESOLUTION OF THE CONDITIONS.
  - CLEAN AIR GRILLES AND LIGHT FIXTURES THROUGHOUT PROJECT AREA UPON COMPLETION OF WORK.
  - WHERE EXISTING PHONE, DATA, OR PHONE/DATA OUTLETS ARE REMOVED, THE CONTRACTOR SHALL USE EXTREME CARE IN PULLING WIRE THROUGH THE EXISTING CONDUITS, COIL AND WRAP ABOVE EXISTING CEILING FOR REUSE.
  - WHERE EXTERIOR WALLS, WINDOWS, AND/OR DOORS ARE BEING REMOVED, THE CONTRACTOR SHALL BE RESPONSIBLE TO CONSTRUCT TEMPORARY PARTITIONS AS REQUIRED TO ENSURE THAT THE EXISTING BUILDINGS REMAIN WATER TIGHT, SECURE, AND WITHOUT DRAFTS DURING DEMOLITION WORK. THESE PARTITIONS SHALL REMAIN IN PLACE DURING THE NEW CONSTRUCTION WORK, OR AS REQUIRED TO MAINTAIN THIS SEPARATION.
  - PROVIDE SHORING AND BRACING AS REQUIRED DURING DEMOLITION AND NEW CONSTRUCTION.

### KEYNOTES - DEMO PLAN

NUMBER	COMMENTS
1	REMOVE EXISTING X-RAY ROOM 2E81 IN ITS ENTIRETY
2	REMOVE EXISTING DOOR AND FRAME
3	REMOVE EXISTING X-RAY ROOM 2E83 IN ITS ENTIRETY. SAVE ALL WALL MOUNTED ACCESSORIES
4	REMOVE AND SAVE EXISTING X-RAY EQUIPMENT
5	REMOVE EXISTING STORAGE ROOM AND TECH ROOM. SAVE FURNITURE AND ACCESSORIES
6	REMOVE EXAM ROOM 6 AND DOC 6 IN ITS ENTIRETY
7	REMOVE EXISTING TECH DESK AND UPPER CABINETS. SALVAGE EXISTING BASE FILE CABINET
8	REMOVE EXISTING WINDOW AND PORTION OF EXISTING WALL
9	REMOVE EXISTING FLOOR, BASE, AND CEILING TO COORDINATE WITH NEW CONSTRUCTION. PREP SUB FLOOR TO RECEIVE NEW FLOORING
10	PREP EXISTING WALLS FOR PAINT
11	REMOVE AND SALVAGE ALL WALL MOUNTED ACCESSORIES
12	REMOVE PORTION OF EXISTING WALL TO COORDINATE WITH NEW CONSTRUCTION
13	REMOVE EXISTING TECH DESK, CASEWORK AND UPPER CABINETS.
14	TEMPORARY DUST PARTITION CONSTRUCTION DOOR. LOCATE AS NEEDED TO PROVIDE SAFE AND SECURE ENTRY TO SITE
15	REMOVE EXISTING DOOR AND FRAME. SALVAGE DOOR AND HARDWARE FOR NEW LOCATION





### GENERAL FINISH NOTES

- SUBMIT SAMPLES OF ALL FINISHES TO ARCHITECT FOR REVIEW PRIOR TO THE ORDERING OF MATERIAL.
- NO IRREGULARITIES OR IMPERFECTIONS SHALL BE PRESENT IN ANY OF THE MATERIAL BEING INSTALLED. IF SUCH ITEMS ARE IDENTIFIED DURING APPLICATION, WORK SHALL BE STOPPED AND THE ARCHITECT NOTIFIED.
- PROVIDE ALL MAINTENANCE MANUALS AND WARRANTY INFORMATION FOR EACH FINISH MATERIAL TO OWNER AT COMPLETION OF THE PROJECT.
- PAINT THE UNDERSIDE OF ALL GYPSUM BOARD CEILINGS, BULKHEADS AND SOFFITS (PT-4) UNLESS NOTED OTHERWISE.
- FURNISH ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO COMPLETE WORK OF FINISH APPLICATIONS.
- ALL FINISHES SHALL BE INSTALLED AND MAINTAINED PER MANUFACTURER'S RECOMMENDATION AND INDUSTRY STANDARDS.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING AND CONFIRMING ALL SUBSTRATE CONDITIONS WHERE NEW MATERIALS ARE APPLIED. SUBSTRATE SHALL BE SMOOTH, FREE OF DEFECTS AND SHALL CONFORM TO THE REQUIREMENTS OF THE FINISHED MATERIAL MANUFACTURER'S RECOMMENDATIONS.
- ALL MATERIAL TO COMPLY WITH FLAME SPREAD CLASSIFICATION EITHER CLASS (1) ONE OR CLASS A DEPENDING ON GOVERNING CODE IN EFFECT.
- SMOKE DEVELOPMENT RATING < 450 FOR ALL FINISHES.

### INTERIOR FINISH LEGEND

MARK	ITEM	MANUFACTURER	MODEL/PATTERN	COLOR	SIZE	REMARKS
<b>FLOOR</b>						
LVT-1	LUXURY VINYL TILE	MANNINGTON	AMTICO WOOD	REGENCY WALNUT AROUNDWOOD	4-1/2" X 36"	STRAIGHT EDGE ONLY. RANDOM INSTALLATION
RSF-1	RESILIENT SHEET FLOORING	ARMSTRONG	MEDINTONE, DIAMOND 10	#H5311-NATURAL WHITE	6'-0" ROLL	WELD ROD W5288. HOMOGENEOUS FLOORING
<b>BASE</b>						
IB-1	INTEGRAL BASE	ARMSTRONG	MEDINTONE, DIAMOND 10	#H5311-NATURAL WHITE	6" COVE	J MOLD SCHLUTTER STRIP AT THE TOP. TO BE USED WITH RSF-1
RB-2	RESILIENT BASE	ROPPE	PINNACLE	#129 DOLPHIN	4" COVE	ALL CAMPUSES- SUPPORT SERVICES SPACES
<b>WALL</b>						
CG-2	CORNER GUARD	C/S ACROVYN	SM-20AN-ACROVYN-4000	#858 PLUMICE	3"	90 DEGREE. ABOVE BASE TO CEILING INCLUDE ALL TRIM AND ACCESSORIES PIECES
CG-3	CORNER GUARD	C/S ACROVYN	SSM-25AN-ACROVYN-4000	#858 PLUMICE	2"	END WALL. ABOVE BASE TO CEILING INCLUDE ALL TRIM AND ACCESSORIES PIECES
CG-4	CORNER GUARD	C/S ACROVYN	SSM-20MN-ACROVYN-4000	#858 PLUMICE	3"x3	SURFACE. 135 DEGREE. ABOVE BASE TO CEILING INCLUDE ALL TRIM AND ACCESSORIES PIECES
PT-1PT-1A	PAINT / EPOXY PAINT	SHERWIN WILLIAMS	SW7036	ACCESSIBLE BEIGE	---	FIELD PAINT. EGGSHELL FINISH/ EPOXY FINISH
PT-4	PAINT	SHERWIN WILLIAMS	SW7509	TRO HUT	---	DOOR FRAME PAINT. SEMI-GLOSS FINISH
PT-ART-8A	PAINT / EPOXY PAINT	SHERWIN WILLIAMS	SW7021	SILVERMAST	---	ACCENT PAINT. EGGSHELL FINISH/ EPOXY FINISH
WP-2	WALL PROTECTION	C/S ACROVYN	ACROVYN-4000	#858 PLUMICE	4" X 10' SHEETS, 040" THICK	TYPICAL OVERALL WALL PROTECTION UNLESS OTHERWISE NOTED
<b>CASEWORK</b>						
PLAM-1	PLASTIC LAMINATE	WILSONART	#7865K-12	WALNUT HEIGHTS	---	CUSTOM 3MM PVC DOBLENEN WALNUT HEIGHTS 870'S. RUN VERTICALLY
RSF-1	SOLID SURFACE	CORIAN	---	CLAM SHELL	1/2" X 30" X 144" SHEET, 36" X 144" SHEET	---
<b>CEILING</b>						
ACT-1	ACOUSTIC CEILING TILE	USG	RADAR CLMA PLUS #2210	WHITE	2' X 2'	SQUARE EDGE, DOWN DX TEE. 15/16" GRID SYSTEM

### ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	WALLS								BASE	WALL CASEWORK	CEILING	NOTES			
		FLOOR FINISH	NORTH	EAST	SOUTH	WEST	CABINETS	COUNTERTOPS	SINKS							
2E51	SAMSUNG X-RAY	RSF-1	IB-1	PT-1	PT-1	PT-1	PT-1	PT-1	PT-1	---	---	---	---	---	---	---
2E52	TECH	LVT-1	IB-1	PT-1	PT-1	PT-1	PT-1	PT-1	PT-1	---	---	---	---	---	---	---
2E83	GE X-RAY	RSF-1	IB-1	PT-1	PT-1	PT-1	PT-1	PT-1	PT-1	---	---	---	---	---	---	---

### GENERAL ROOM FINISH SCHEDULE NOTES

- REFER TO FINISH PLAN AND INTERIOR ELEVATIONS FOR WALL FINISHES, WALL PROTECTION, CORNER GUARDS, WINDOW TREATMENTS, FLOOR FINISH APPLICATION AND LOCATIONS
- ALL SOLID WOOD, WOOD VENEER, AND PLASTIC LAMINATE GRAIN SHALL BE VERTICALLY ORIENTED UNLESS OTHERWISE NOTED
- DOOR FRAMES, HOLLOW METAL WINDOW FRAMES TO BE PT-1 UNLESS OTHERWISE NOTED
- ALL FACES AND UNDERSIDES OF SOFFITS AND HEADERS TO BE PT-1 UNLESS OTHERWISE NOTED
- WALL EXPANSION JOINTS TO BE PT-1 UNLESS OTHERWISE NOTED
- ALL ELECTRICAL PANELS AND METAL GRILLES SHALL BE PT-1 TO MATCH ADJACENT WALL SURFACE UNLESS OTHERWISE NOTED
- ALL COLUMN SURROUND FINISHES TO MATCH ADJACENT WALL SURFACE UNLESS OTHERWISE NOTED
- WHERE A WALL IS INDICATED TO HAVE PARTIAL OR FULL HT WALL PROTECTION, THE ENTIRE WALL IS TO BE PT-1 PRIOR TO WALL PROTECTION INSTALLATION
- EXTEND ALL FINISHES BENEATH, BEHIND, AROUND ALL CASEWORK, EQUIPMENT, SIGNAGE, ETC

### DOOR SCHEDULE

DOOR #	ROOM NAME	DOOR INFORMATION	FRAME INFORMATION	GLAZING	LABEL	HARDWARE SET	OPENING DETAIL	REMARKS	REV #
2E51	SAMSUNG X-RAY	3'-6" F	7'-0" W	1	HM	NA	AS	LEAD LINED, NO LOCKS	---
2E52	TECH	3'-0" F	7'-0" W	1	HM	NA	AS	REUSE EXISTING DOOR AND HARDWARE. NEW FRAME	---
2E83	GE X-RAY	3'-6" F	7'-0" W	1	HM	NA	AS	LEAD LINED, NO LOCKS	---


#### DOOR & FRAME MAT'L LEGEND:

HM = HOLLOW METAL  
WD = SOLID CORE WOOD




#### DOOR HARDWARE

HARDWARE SET 1 DOOR NUMBER: 2E51, 2E83				HARDWARE SET 2 DOOR NUMBER: 2E52					
QTY	DESCRIPTION	CATALOG NUMBER	FINISH	MFR	QTY	DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1 EA	DOOR HINGE	13180	NA	WE	3 EA	HINGE	ETR	ETR	ETR
1 EA	PUSH/PULL	H4L-A (LEAD LINED)	US300	OL	1 EA	PASSAGE SET	ETR	ETR	ETR
1 EA	CLIP	401 (RED)	US300	LD	1 EA	WALL STOP	409	USD	RO
1 EA	KICK PLATE	K1050 17"X47"	US300	RD	---	---	---	---	---
1 EA	WALL STOP	409	USD	RO	---	---	---	---	---
1 EA	SEALS	2528	BRN	NSP	---	---	---	---	---

### X-RAY TECH WINDOW ELEVATIONS:





### DOOR & FRAME ELEVATIONS:





**D4** CEILING DETAIL  
3" = 1'-0"

**C4** LEAD-LINED H.M. DOOR FRAME JAMB / HEAD  
6" = 1'-0"





**D3** TYPICAL DOUBLE VINYL CORNER GUARD  
3" = 1'-0"

**C3** TYPICAL SINGLE VINYL CORNER GUARD  
3" = 1'-0"



**D2** TYPICAL ANGLED VINYL CORNER GUARD  
3" = 1'-0"

**C2** SECTION DTL. AT SUPPORT BRACKET / KNEE SPACE  
1 1/2" = 1'-0"




**D1** SECTION DETAIL AT SOLID SURFACE BACKSPLASH  
3" = 1'-0"

**C1** SECTION DETAIL AT CORNER GUARD  
1" = 1'-0"

### GENERAL CASEWORK NOTES

- GENERAL CASEWORK NOTES APPLY TO ALL INTERIOR ELEVATIONS.
- PROVIDE 3 MM PVC EDGE BANDING ON COUNTERTOP EDGE AND (018 MIN.) VINYL EDGING ON DRAWER AND DOOR EDGES UNLESS NOTED OTHERWISE. EDGE BANDING TO MATCH ADJACENT P. LAM. SURFACE.
- ALL EXPOSED FACES AND SHELVES TO BE WRAPPED WITH P. LAM. UNLESS NOTED OTHERWISE.
- ALL INTERIOR SURFACES TO BE WHITE MELAMINE U.N.O.
- PROVIDE WOOD BLOCKING OR 12" HIGH X 16 GA. CONTINUOUS SHEET METAL BRIDGING IN WALL AS REQUIRED FOR ADEQUATE SUPPORT OF ALL CASEWORK..
- WALL BASE TO BE INSTALLED ON ALL CASEWORK UNLESS NOTED OTHERWISE. REFER TO FINISH SCHEDULE FOR TYPE.
- "F" INDICATES FILLER PANEL, 1-1/2" MIN.
- PROVIDE FINISHED ENDS AT ALL EXPOSED ENDS OF CASEWORK.
- ALL ELECTRICAL, MECHANICAL, AND PLUMBING ITEMS SHOWN IN ELEVATION ARE FOR REFERENCE AND LOCATION ONLY. REFER TO MEP DRAWINGS FOR SIZES, TYPES AND QUANTITIES.
- ALL SOFFITS ABOVE CASEWORK TO BE P. LAM. UNLESS NOTES OTHERWISE.

FINISH FLOOR PLAN LEGEND	
(Symbol)	WALL TREATMENT
(Symbol)	FLOOR TRANSITION
(Symbol)	CORNER GUARD
(Symbol)	FLOOR FINISH DIRECTION



**A1** FINISH FLOOR PLAN  
1/4" = 1'-0"

RELEASE FOR CONSTRUCTION  
7/1/2021 11:39:34 AM  
Samuel K. Beckman - Architect  
License - Missouri WA-2011012130

**ACI BOLAND ARCHITECTS**  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

**MEP CONSULTANT**  
IMEG CORP.  
1600 BALTIMORE ST, SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437

**Saint Luke's East Hospital**  
ROCKHILL ORTHOPAEDIC X-RAY RENOVATION  
120 NE SAINT LUKE'S BLVD., SUITE 200  
LEE'S SUMMIT MO 64086

Date	07.02.2021
Job Number	3-21014
Drawn By	BRD
Checked By	GS

Revision	Number	Date	Description

**A4.1**  
DOOR & FRAME SCHEDULE, OVERALL FLOOR FINISH PLAN, ROOM FINISH SCHEDULE, & LEGEND



MECHANICAL SYMBOL LIST	
NOT ALL SYMBOLS MAY APPLY.	
SYMBOL:	DESCRIPTION:
	ACTUATOR
	DOOR SWITCH
	DIFFERENTIAL PRESSURE SWITCH
	CURRENT SWITCH
	VIBRATION SWITCH
	FLOW METER
	FAN
	MOTOR
	CONTACTOR
	PUMP
	NORMALLY CLOSED CONTACT
	NORMALLY OPEN CONTACT
	ANALOG INPUT
	ANALOG OUTPUT
	DIGITAL INPUT
	DIGITAL OUTPUT
	FLOW METER
	FLOW SWITCH
	FLOW SENSOR
	AIR FLOW SWITCH
	DUCT FLOW METER
	PRESSURE SENSOR (FURNISHED WITH BALL VALVE)
	PRESSURE GAUGE (FURNISHED WITH BALL VALVE)
	DIFFERENTIAL PRESSURE SENSOR
	PRESSURE SENSOR (DUCT MOUNTED)
	AVERAGING TEMPERATURE SENSOR
	LOW LIMIT TEMPERATURE SWITCH
	PROBE TEMPERATURE SENSOR
	HUMIDISTAT SENSOR
	HUMIDISTAT / SENSOR
	HUMIDITY SENSOR (DUCT MOUNTED)
	CARBON MONOXIDE SENSOR
	CARBON DIOXIDE SENSOR
	CARBON MONOXIDE SENSOR (DUCT MOUNTED)
	CARBON DIOXIDE SENSOR (DUCT MOUNTED)
	FILTER
	DUCT SMOKE DETECTOR
	HEATING / COOLING COIL
	AIR BLENDER
	MANUAL MOTOR STARTER WITH THERMAL OVERLOAD

MECHANICAL SYMBOL LIST	
NOT ALL SYMBOLS MAY APPLY.	
SYMBOL:	DESCRIPTION:
	BOILER BLOW DOWN
	BOILER FEED WATER
	COMPRESSED AIR
	CHILLED BEAM RETURN
	CHILLED BEAM SUPPLY
	CONDENSER WATER RETURN
	CONDENSER WATER SUPPLY
	CLEAN STEAM - NUMBER INDICATES PRESSURE IN PSIG.
	CHILLED WATER RETURN
	CHILLED WATER SUPPLY
	DRAIN
	NATURAL GAS
	GAS REGULATOR VENT
	GLYCOL WATER RETURN
	GLYCOL WATER SUPPLY
	HEATING/CHILLED WATER RETURN
	HEATING/CHILLED WATER SUPPLY
	REFRIGERANT HOT GAS
	HIGH PRESSURE CONDENSATE
	HIGH PRESSURE STEAM
	HEATING WATER RETURN
	HEATING WATER SUPPLY
	LOW PRESSURE CLEAN STEAM
	REFRIGERANT LIQUID
	LOW PRESSURE CONDENSATE
	LOW PRESSURE STEAM
	LOOP WATER RETURN
	LOOP WATER SUPPLY
	MEDICAL VACUUM
	OIL RETURN
	OIL SUPPLY
	PUMPED CONDENSATE
	PUMPED DISCHARGE
	RADIANT COOLING RETURN
	RADIANT COOLING SUPPLY
	REHEAT WATER RETURN
	REHEAT WATER SUPPLY
	REFRIGERANT SUCTION
	SAFETY RELIEF VENT
	LAB VACUUM
	PIPE CAP
	PIPE DOWN
	PIPE UP OR UP/DOWN
	PITCH PIPE IN DIRECTION
	DIRECTION OF FLOW IN PIPE
	DIELECTRIC CONNECTION
	UNION/FLANGE
	SHUTOFF VALVE NORMALLY OPEN
	SHUTOFF VALVE NORMALLY CLOSED
	THROTTLING VALVE
	BALANCING VALVE (NUMBER INDICATES GPM)
	AUTOMATIC BALANCING VALVE
	MIXING VALVE
	CONTROL VALVE (THREE-WAY)
	CONTROL VALVE (TWO-WAY)
	SOLENOID VALVE
	CHECK VALVE
	BACKFLOW PREVENTER
	SAFETY/RELIEF VALVE
	PRESSURE REDUCING VALVE (LIQUID/GAS)
	PRESSURE REDUCING VALVE (STEAM)
	TRIPLE DUTY VALVE (ANGLE TYPE)
	TRIPLE DUTY VALVE (IN-LINE TYPE)
	PUMP
	VACUUM BREAKER
	WYE - STRAINER
	WYE - STRAINER W/SHUTOFF VALVE AND HOSE CONNECTION WITH CAP
	BASKET STRAINER
	FLEXIBLE CONNECTION
	NORMALLY CLOSED
	NOT IN CONTRACT
	NORMALLY OPEN
	OUTSIDE AIR
	PRESSURE SWITCH
	RETURN AIR
	SUPPLY AIR
	SHORT CIRCUIT CURRENT RATING
	SMOKE DAMPER
	TERMINAL AIR BOX
	TRANSFER DUCT
	TYPICAL
	DOOR UNDERCUT BY OTHERS (1" TYPICAL)
	UNLESS NOTED OTHERWISE
	STATIC SWITCH
	FLOW METER
	FLOW SWITCH
	FLOW SENSOR
	STEAM TRAP (REFER TO SCHEDULE)
	F&T STEAM TRAP (REFER TO SCHEDULE)
	INVERTED BUCKET STEAM TRAP (REFER TO SCHEDULE)
	ALIGNMENT GUIDE
	PIPE ANCHOR
	EXPANSION JOINT
	#.# IS THE EXPANSION TRAVEL INCHES
	METER


MECHANICAL SYMBOL LIST	
NOT ALL SYMBOLS MAY APPLY.	
SYMBOL:	DESCRIPTION:
	DIRECTION OF AIR FLOW
	FLEXIBLE DUCT
	MANUAL VOLUME DAMPER
	RISE IN DIRECTION OF AIR FLOW
	DROP IN DIRECTION OF AIR FLOW
	DUCT GAP
	DUCT DOWN
	DUCT UP
	SUPPLY/OUTSIDE AIR DUCT SECTION
	RETURN AIR DUCT SECTION
	EXHAUST/RELIEF AIR DUCT SECTION
	4-WAY DIFFUSER WITH BLANKOFF IN ONE DIRECTION
	AIR TERMINAL PROPERTIES SYMBOL
	NECK SIZE/CFM
	TERMINAL AIR BOX (REFER TO SCHEDULE)
	TERMINAL AIR BOX W/REHEAT COIL (REFER TO SCHEDULE)
	FAN POWERED TERMINAL AIR BOX W/REHEAT COIL (REFER TO SCHEDULE)
	HUMIDIFIER
	OPPOSED BLADE DAMPER (REFER TO SCHEDULE)
	PARALLEL BLADE DAMPER (REFER TO SCHEDULE)
	DIFFERENTIAL PRESSURE SENSOR
	HUMIDISTAT SENSOR
	HUMIDISTAT / SENSOR
	CARBON MONOXIDE SENSOR
	CARBON DIOXIDE SENSOR
	OCCUPANCY SENSOR
	PRESSURE SENSOR/MONITOR
	PRESSURE SENSOR (DUCT MOUNTED)
	THERMOSTAT/SENSOR
	TEMPERATURE SENSOR
	THERMOSTAT/SENSOR WITH HEAVY DUTY ENCLOSURE
	TEMPERATURE SENSOR WITH WELL
	THERMOMETER WITH WELL (DIAL TYPE)
	THERMOMETER WITH WELL (FILLED TYPE)
	AIRFLOW MEASUREMENT SYMBOL
	XX - AHU SYMBOL
	Y - SEQUENTIAL NUMBER

MECHANICAL ABBREVIATION KEY	
ABBR:	DESCRIPTION:
AD	ACCESS DOOR
AFF	ABOVE FINISHED FLOOR
C	COMMON
CO	CLEANOUT
CFSD	CONTROL/FIRE/SMOKE DAMPER
DPG (0-2")	DIFFERENTIAL PRESSURE GAUGE (RANGE)
DPS	DIFFERENTIAL PRESSURE SWITCH
EA	EXHAUST/RELIEF AIR
ECFSD	EXISTING CONTROL FIRE SMOKE DAMPER
EFD	EXISTING FIRE DAMPER
EPSD	EXISTING FIRE SMOKE DAMPER
EPD	ELECTRICAL TO PNEUMATIC VALVE
ESD	EXISTING SMOKE DAMPER
FD	FIRE DAMPER
FOB	FLAT ON BOTTOM
FOT	FLAT ON TOP
FSD	FIRE/STRAKER DAMPER
MA	MIXED AIR
MV	MIXING VALVE
N.C.	NORMALLY CLOSED
NIC	NOT IN CONTRACT
N.O.	NORMALLY OPEN
OA	OUTSIDE AIR
PS	PRESSURE SWITCH
RA	RETURN AIR
SA	SUPPLY AIR
SCCR	SHORT CIRCUIT CURRENT RATING
SD	SMOKE DAMPER
TAB	TERMINAL AIR BOX
TD	TRANSFER DUCT
TYP	TYPICAL
UC-1	DOOR UNDERCUT BY OTHERS (1" TYPICAL)
UNO	UNLESS NOTED OTHERWISE

TAB PRE-DEMOLITION NOTES:	
1.	BEFORE ANY DEMOLITION WORK IS BEGUN A COMPLETE AIR BALANCE TEST SHALL BE PERFORMED BY THE TESTING, ADJUSTING AND BALANCING (TAB) CONTRACTOR ON EXISTING AIR HANDLERS AND EXHAUST FANS SERVING THE AREAS AFFECTED BY CONSTRUCTION. EQUIPMENT TO BE DEMOLISHED DOES NOT REQUIRE TESTING. PROVIDE AIR BALANCE TESTING ONLY ON EQUIPMENT THAT WILL CONTINUE TO BE USED TO SERVE RENOVATED AREAS AFTER THE CONSTRUCTION PHASE IS COMPLETED.
2.	PROVIDE DUCT TRAVERSE READINGS AT LOCATIONS DESIGNATED ON THE DRAWINGS BY THE AIRFLOW MEASUREMENT SYMBOL. THOSE MEASUREMENTS SHALL BE INCLUDED IN THE PRE-DEMOLITION REPORT AND SHALL BE DESIGNATED WITH THE IDENTIFIER AS MARKED ON THE DRAWINGS. READINGS SHALL BE DESIGNATED WITH THE ROOM NAME AND NUMBER AS MARKED ON THE DRAWINGS. IF FLOOR PLANS DO NOT HAVE UNIQUE ROOM NAMES AND NUMBERS, TAB CONTRACTOR SHALL INCLUDE FLOOR PLAN WITH UNIQUE NUMBER DESIGNATIONS ASSIGNED TO READINGS THAT MATCH THOSE USED IN THE FINAL PRE-DEMOLITION REPORT. DRAWINGS THAT ARE HAND-MARKED WITH RED INK ARE ACCEPTABLE PROVIDED THEY ARE LEGIBLE.
3.	IN THE EVENT A DUCT TRAVERSE LOCATION AS MARKED ON THIS PLAN IS INACCESSIBLE FOR MEASUREMENT, THE TAB CONTRACTOR SHALL PERFORM THE TRAVERSE AT AN ALTERNATE LOCATION OR SHALL TAKE MULTIPLE DUCT TRAVERSES AND/OR READINGS AS REQUIRED TO DETERMINE THE AIRFLOW READING WHERE THE DUCT TRAVERSE SYMBOL IS SHOWN. IN THE EVENT TRAVERSES ARE TAKEN AT ALTERNATE LOCATIONS, TAB CONTRACTOR SHALL INCLUDE A DRAWING THAT SHOWS THE LOCATIONS WHERE THE ACTUAL MEASUREMENTS WERE TAKEN.
4.	TAKE A DUCT STATIC PRESSURE READING AT EACH LOCATION WHERE A DUCT TRAVERSE READING IS TAKEN AND INCLUDE IN THE FINAL PRE-DEMOLITION TAB REPORT.
5.	TAB CONTRACTOR SHALL COMPLETE AND SUBMIT FOUR COPIES OF THE FINAL PRE-DEMOLITION REPORT WITHIN 10 WORKING DAYS AFTER THE FIELD MEASUREMENTS ARE COMPLETED. FINAL TAB REPORT SHALL BE SUBMITTED FOR REVIEW TO THE ARCHITECT/ENGINEER. TESTING SHALL INCLUDE ALL ITEMS REQUIRED IN THE SPECIFICATIONS.

TAB POST-CONSTRUCTION NOTES:	
1.	AFTER CONSTRUCTION ACTIVITIES ARE COMPLETE, TESTING, ADJUSTING (TAB) AND BALANCING CONTRACTOR SHALL REBALANCE AIR HANDLING UNITS AND EXHAUST FANS AS REQUIRED TO ACHIEVE THE NEW AIRFLOW VALUES SHOWN ON THE CONSTRUCTION DRAWINGS.
2.	AREAS SERVED BY THIS EQUIPMENT WHICH WERE NOT RENOVATED SHALL BE RE-BALANCED TO THE AIRFLOW RATES MEASURED BEFORE THE RENOVATION OCCURRED (REFER TO THE FINAL PRE-DEMOLITION REPORT).
3.	IF DUCT TRAVERSE LOCATION AS MARKED ON THE DRAWINGS IS INACCESSIBLE FOR MEASUREMENT, THE TAB CONTRACTOR SHALL PERFORM THE TRAVERSE AT AN ALTERNATE LOCATION OR SHALL TAKE MULTIPLE DUCT TRAVERSES AND/OR GRILLE READINGS AS REQUIRED TO DETERMINE THE FLOW RATE. IN THE EVENT TRAVERSES ARE TAKEN AT AN ALTERNATE LOCATION(S), TAB CONTRACTOR SHALL INCLUDE A DRAWING THAT SHOWS THE LOCATIONS WHERE THE ACTUAL MEASUREMENTS WERE TAKEN.
4.	A DUCT STATIC PRESSURE READING SHALL BE TAKEN AT EACH LOCATION WHERE A DUCT TRAVERSE READING IS TAKEN AND SHALL BE INCLUDED IN THE FINAL POST-CONSTRUCTION TAB REPORT.
5.	TAB CONTRACTOR SHALL COMPLETE AND SUBMIT COPIES OF THE FINAL POST-CONSTRUCTION TAB REPORT AS REQUIRED BY SECTION 23 05 93.
6.	THE FINAL POST CONSTRUCTION REPORT SHALL INCLUDE ALL ITEMS REQUIRED IN THE SPECIFICATIONS.

CONTRACTOR ABBREVIATION KEY	
ABBR:	DESCRIPTION:
A.C.	ASBESTOS ABATEMENT CONTRACTOR
A.V.C.	AUDIOVISUAL CONTRACTOR
C.C.	CIVIL CONTRACTOR
C.M.	CONSTRUCTION MANAGER
E.C.	ELECTRICAL CONTRACTOR
F.P.C.	FIRE PROTECTION CONTRACTOR
F.S.C.	FOOD SERVICE CONTRACTOR
G.C.	GENERAL CONTRACTOR
H.C.	HEATING CONTRACTOR
M.C.	MECHANICAL CONTRACTOR
N.C.C.	NURSE CALL CONTRACTOR
P.C.	PLUMBING CONTRACTOR
S.C.	SECURITY CONTRACTOR
T.C.	TECHNOLOGY CONTRACTOR
T.C.C.	TEMPERATURE CONTROLS CONTRACTOR
V.C.	VENTILATION CONTRACTOR




MECHANICAL PHASING NOTES:	
1.	REFER TO ARCHITECTURAL DRAWINGS FOR GENERAL DESCRIPTION OF PHASES. REFER TO GENERAL CONTRACTOR FOR PHASING DETAILS AND PHASING SCHEDULES AND FOR CONCURRENT WORK. MECHANICAL, ELECTRICAL AND TECHNOLOGY DRAWINGS DEPICT THE INTENT OF THE FINAL DESIGN. THE MECHANICAL, ELECTRICAL, AND TECHNOLOGY DRAWINGS DO NOT DEPICT THE MEANS AND METHODS TO MEET THE REQUIREMENTS OF THE PHASING CRITERIA.
2.	REVIEW PROJECT PHASING PLANS TO COORDINATE DEMOLITION WORK, OUTAGES, ETC.
3.	PROVIDE TEMPORARY DUCTWORK, PIPING, SHUTOFF VALVES, ZONE VALVES, ZONE ALARMS, ETC. AS NEEDED TO MAINTAIN SERVICE TO ALL AREAS DURING ALL PHASES OF PROJECT.
4.	INSTALL TEMPORARY DUCTWORK, PIPING, SHUTOFF VALVES, ETC. AS NECESSARY TO KEEP ALL OCCUPIED SPACES OPERATIONAL THROUGHOUT ALL PHASES OF THE PROJECT.
5.	PHASE DEMOLITION WORK TO MINIMIZE DOWNTIME.

PIPING GENERAL NOTES:	
1.	THE SIZE OF BRANCH PIPING TO TERMINAL HEATING DEVICES AND COILS SHALL BE 3/4" UNLESS NOTED OTHERWISE.
2.	PIPE DRAIN LINES FROM EQUIPMENT TO NEAREST FLOOR DRAIN.
3.	INSTALL ALL REFRIGERANT LIQUID AND SUCTION PIPING SIZED PER EQUIPMENT MANUFACTURER RECOMMENDATIONS.

VENTILATION GENERAL NOTES:	
1.	UNLESS NOTED OTHERWISE, THE SIZE OF EACH BRANCH DUCT TO A TERMINAL AIR BOX (TAB) SHALL MATCH THE INLET SIZE UNLESS THE BRANCH IS GREATER THAN PEEET IN LENGTH, IN WHICH CASE THE BRANCH DUCT SHALL BE SIZED AT A PRESSURE DROP OF 0.07"W.C. PER 100' OF DUCTWORK.
2.	UNLESS NOTED OTHERWISE, THE SIZE OF EACH BRANCH DUCT TO AN AIR TERMINAL SHALL MATCH THE INLET SIZE.
3.	ALIGN TEMPERATURE SENSORS WITH LIGHT SWITCHES AND WHEN IN CLOSE PROXIMITY TO EACH OTHER.
4.	PROVIDE ACCESS DOORS AT ALL DUCT MOUNTED EQUIPMENT.
5.	EXISTING AIR INLET AND OUTLET CFM SHOWN ON DRAWINGS ARE FROM EXISTING DRAWINGS, AND ARE FOR REFERENCE ONLY. CONTRACTOR SHALL USE PRE-BALANCE VALUES, AND NOT EXISTING CFM SHOWN ON DRAWINGS.
6.	CONTRACTOR MAY REUSE PORTIONS OF EXISTING DUCT PROVIDED SIZES AND PRESSURE CLASSES ARE CORRECT. DUCT IS THOROUGHLY CLEANED AND FREE OF DEFECTS, AND ALL TRANSVERSE JOINTS, LONGITUDINAL SEAMS, AND DUCT WALL PENETRATIONS ARE SEALED AS SPECIFIED FOR NEW DUCTWORK.

MECHANICAL GENERAL NOTES:	
THESE NOTES APPLY TO ALL MECHANICAL SHEETS AND TRADES, INCLUDING BUT NOT LIMITED TO: FIRE PROTECTION, PLUMBING, MEDICAL GAS, VENTILATION, PIPING AND TEMPERATURE CONTROL.	
1.	DRAWINGS SHOWING LOCATIONS OF EQUIPMENT, DUCTWORK, PIPING, ETC. ARE DIAGRAMMATIC AND MAY NOT ALWAYS REFLECT EXACT INSTALLATION CONDITIONS. CONTRACTOR SHALL VERIFY ALL DRAWINGS, INCLUDING THOSE OF OTHER TRADES, AND MAY NOT INCLUDE ALL OFFSETS AND FITTINGS REQUIRED FOR COMPLETE INSTALLATION. THE DRAWINGS SHALL BE FOLLOWED AS CLOSELY AS ACTUAL BUILDING CONSTRUCTION AND THE WORK OF OTHERS WILL PERMIT.
2.	DO NOT SCALE DRAWINGS. VERIFY ALL DIMENSIONS AND CLEARANCES FROM ARCHITECTURAL, STRUCTURAL, SUBMITTALS, AND OTHER APPROPRIATE DRAWINGS OR FIELD SURVEYS. VERIFY ALL DIMENSIONS AND CLEARANCES FROM OTHER TRADES.
3.	COORDINATE ALL WORK WITH ALL OTHER TRADES PRIOR TO INSTALLATION TO PROVIDE CLEARANCES REQUIRED FOR OPERATION, MAINTENANCE, CODE COMPLIANCE, AND TO VERIFY NON-INTERFERENCE WITH OTHER TRADES. VERIFY ALL CLEARANCES PRIOR TO VERIFICATION OF NECESSARY CLEARANCES FOR ALL TRADES. BRING ANY INTERFERENCES OR CONFLICTS TO THE ATTENTION OF THE ARCHITECT/ENGINEER BEFORE PROCEEDING WITH ANY WORK.
4.	REVIEW SPACE REQUIREMENTS OF EQUIPMENT SPECIFIED OR SUBSTITUTED AND MAKE REASONABLE ACCOMMODATIONS IN LAYOUT AND POSITIONING TO PROVIDE PROPER ACCESS.
5.	ANY CHANGES REQUIRED TO ELIMINATE CONFLICTS OR THAT RESULT FROM A FAILURE TO COORDINATE SHALL BE MADE BY THE CONTRACTOR WITHOUT ADDITIONAL COST OR EXPENSE TO OTHERS.
6.	EACH CONTRACTOR IS RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH ELECTRICAL CHANGES REQUIRED FOR EQUIPMENT PROPOSED THAT DIFFERS FROM THE BASIS OF DESIGN.
7.	REFER TO ARCHITECTURAL REFLECTED CEILING PLAN, ELECTRICAL, TECHNOLOGY AUDIOVISUAL, AND OTHER MECHANICAL PLANS FOR EXACT LOCATIONS OF ALL CEILING MOUNTED DEVICES, OTHER THAN SPRINKLERS.
8.	EACH CONTRACTOR IS RESPONSIBLE FOR DAMAGE CAUSED BY THEIR ACTIONS TO WALLS, FLOORS, CEILING, AND ROOFS. THE CONTRACTOR WHOSE WORK CAUSES DAMAGE IS RESPONSIBLE FOR REPAIRS TO MATCH ORIGINAL CONSTRUCTION, FIRE RATING, AND FINISH.
9.	IN AREAS WITH DRYWALL CEILINGS COORDINATE LOCATIONS OF ACCESS PANELS WITH THE GC FOR ACCESS TO VALVES, DUCTWORK ACCESSORIES, DAMPERS, ETC. COORDINATE PANEL TYPE AND COLOR WITH ARCHITECT. NOTIFY THE GC OF THE REQUIRED ACCESS PANELS PRIOR TO BIDDING.
10.	SEAL ALL FLOOR AND WALL PENETRATIONS AIRTIGHT WHERE CONDUITS, PIPING, AND DUCTS PENETRATE.
11.	CAULK ALL PIPE AND DUCT PENETRATIONS OF FULL HEIGHT NON-FIRE RATED WALL, PARTITION, FLOOR, AND ROOF ASSEMBLIES. THIS IS ESSENTIAL TO PREVENT NOISE TRANSMISSION FROM ONE ROOM TO ANOTHER AND TO PROVIDE THE DESIRED NC LEVELS WITHIN ROOMS.
12.	WHERE PIPES AND DUCTS ARE SHOWN TO PENETRATE FLOORS, PROVIDE SLEEVED OPENINGS WITH THE TOP EDGE RAISED ABOVE FLOOR SURFACE IN ACCORDANCE WITH ALL RELEVANT SPEC SECTIONS. SEAL SLEEVE PERIMETER TO BE WATERTIGHT.
13.	EQUIPMENT SIZES AND SERVICE CLEARANCE REQUIREMENTS VARY AMONG DIFFERENT MANUFACTURERS. CONSULT APPROVED SHOP DRAWINGS FOR EQUIPMENT SIZES AND REQUIRED SERVICE CLEARANCES. COORDINATE WITH LAYOUT OF EQUIPMENT PADS, PIPING, DUCTWORK, ETC.
14.	DO NOT BLOCK TUBE PULL OR EQUIPMENT SERVICE CLEARANCES.
15.	MAINTAIN MINIMUM 3'-6" CLEARANCE IN FRONT OF ALL ELECTRICAL PANELS, MOTOR STARTERS, SWITCHES, AND DISCONNECTS.
16.	PROVIDE CONCRETE EQUIPMENT PAD FOR ALL FLOOR MOUNTED EQUIPMENT. PAD SHALL EXTEND MINIMUM 6" BEYOND ALL SIDES OF EQUIPMENT.
17.	DO NOT SUPPORT EQUIPMENT, PIPING, OR DUCTWORK FROM METAL DECKING OR OTHER NON-STRUCTURAL BUILDING ELEMENTS. ANCHORS EMBEDDED IN CONCRETE SHALL BE CRACKED CONCRETE APPROVED IN ACCORDANCE WITH SPECIFICATIONS.



RELEASE FOR CONSTRUCTION DEVELOPMENT SERVICES OF MISSOURI  
 BRUCE ELTON HART  
 NUMBER 22041  
 PROFESSIONAL ENGINEER  
 07-07-21  
 Bruce E. Hart - Engineer  
 License - Missouri #E-22817

**ACI BOLAND ARCHITECTS**  
 1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600

ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**  
 IMEG CORP.  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

ROCKHILL ORTHOPAEDIC X-RAY RENOVATION  
 120 NE SAINT LUKE'S BLVD., SUITE 200  
 LEE'S SUMMIT MO 64086

Date	07/07/21	
Job Number	3-21014	
Drawn By	MJL	
Checked By	DWD	
Revision		
Number	Date	Description

**M000**  
 © 2021 ACI/BOLAND, Inc.  
 MECHANICAL COVERSHEET - PP, V




**SHEET NOTES:**

- REFER TO GENERAL NOTES ON SHEET M000.
- ACCORDING TO EXISTING BUILDING DOCUMENTS, EACH TERMINAL AIR BOX INCLUDES A THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) IN A NURSE STATION AREA, BUT MOST BOXES ALSO HAVE A TEMPERATURE SENSOR (WITH BLANK COVER) IN THE SPACE SERVED BY THE BOX. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND COORDINATE WITH ENGINEER IF CONDITIONS DIFFER.
- TERMINAL AIR BOX TAGS ARE BASED ON ROOM NUMBERS SERVED AND MAY NOT MATCH THE BOX TAGS IN THE BUILDING MANAGEMENT SYSTEM.

**KEYNOTES:**

- CUT 3/4" HWS AND HWR AND REMOVE PIPING TO BOX THAT IS BEING REMOVED, INCLUDING ACCESSORIES. PROTECT REMAINING PIPING FOR NEW CONNECTION. RE: SHEET M202. ALSO DISCONNECT DDC CONTROLLER ASSOCIATED WITH THIS BOX AND SALVAGE IT FOR RELOCATION AND RE-USE.
- FIELD VERIFY LOCATION OF TEMPERATURE SENSOR (WITH BLANK COVER). DISCONNECT AND SALVAGE SENSOR FOR RELOCATION AND RE-USE. REMOVE ANY CONTROL WIRING THAT CANNOT BE RE-USED.
- FIELD VERIFY LOCATION OF THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) ASSOCIATED WITH TERMINAL AIR BOX E3-2E83. THE BOX IS BEING REMOVED, BUT THE THERMOSTAT SHALL REMAIN AND WILL BE RE-USED WITH A NEW BOX. THE NEW BOX IS SHOWN WITH SAME TAG. RE: SHEET M202.
- CUT AND CAP 3/4" HWS AND HWR AND REMOVE PIPING TO BOX THAT IS BEING REMOVED, INCLUDING ACCESSORIES. THIS PIPING WILL NOT BE RE-USED. ALSO DISCONNECT DDC CONTROLLER ASSOCIATED WITH THIS BOX AND SALVAGE IT FOR RELOCATION AND RE-USE.
- FIELD VERIFY LOCATION OF THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) ASSOCIATED WITH TERMINAL AIR BOX E2-2E81. THE BOX IS BEING REMOVED, BUT THE THERMOSTAT SHALL REMAIN AND WILL BE RE-USED WITH A NEW BOX. THE NEW BOX IS SHOWN WITH A DIFFERENT TAG. RE: SHEET M202.
- TERMINAL BOX THAT SERVES X-RAY ROOM 2E79 SHALL REMAIN. IF THE BOX OR ITS PIPING WOULD INTERFERE WITH THE NEW G.E. X-RAY EQUIPMENT, OR NEEDS TO MOVE BECAUSE THE ASSOCIATED DUCTWORK WOULD INTERFERE, THEN CONTRACTOR SHALL DISCONNECT AND RELOCATE THE PIPING AS REQUIRED TO CLEAR SPACE FOR THE NEW WORK. MODIFY CONTROL WIRING OR PROVIDE NEW WIRING AS REQUIRED.
- EXISTING BUILDING DOCUMENTS SHOWED A TEMPERATURE SENSOR (WITH BLANK COVER) IN THIS LOCATION; HOWEVER, IT APPEARS THE SENSOR WAS PREVIOUSLY REMOVED. FIELD VERIFY LOCATION. IF SENSOR IS FOUND, DISCONNECT AND SALVAGE IT FOR RELOCATION AND RE-USE. REMOVE ANY CONTROL WIRING THAT CANNOT BE RE-USED.
- FIELD VERIFY LOCATION OF THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) ASSOCIATED WITH TERMINAL AIR BOX E3-2E69. THE BOX AND THERMOSTAT SHALL REMAIN, BUT WILL NOT BE USED FOR TEMPERATURE FEEDBACK, ONLY FOR SETPOINT ADJUSTMENT.



**1 SECOND FLOOR DEMOLITION - PIPING**  
 1/4" = 1'-0"


**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 PROJECT # 21014-00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. SAVED DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 1/4" = 1'-0"



**RELEASE FOR CONSTRUCTION**  
 AS SHOWN ON THESE DRAWINGS  
 DEVELOPMENT SERVICES  
 OF MISSOURI  
 MISSOURI  
 07/02/21  
 BRUCE E. HART  
 HART  
 NUMBER  
 22817  
 PROFESSIONAL ENGINEER  
 07-07-21  
 Bruce E. Hart - Engineer  
 License - Missouri #E-22817

- SHEET NOTES:**
- REFER TO GENERAL NOTES ON SHEET M000.
  - TERMINAL AIR BOX TAGS ARE BASED ON ROOM NUMBERS SERVED AND MAY NOT MATCH THE BOX TAGS IN THE BUILDING MANAGEMENT SYSTEM.

- KEYNOTES:**
- TAKE PRE-DEMOLITION AIRFLOW READINGS AT EXISTING TERMINAL AIR BOX AND AT ALL SUPPLY AIR TERMINALS SERVED BY THE BOX, INCLUDING THOSE OUTSIDE OF THE PROJECT AREA.
  - CUT AND CAP SUPPLY AIR DUCT AND REMOVE DOWNSTREAM DUCTWORK AND AIR TERMINALS SHOWN DARK AND DASHED.
  - CUT AND CAP SUPPLY AIR DUCT AND REMOVE DOWNSTREAM DUCTWORK, 6" TERMINAL AIR BOX, AND AIR TERMINAL SHOWN DARK AND DASHED. SALVAGE THE DDC CONTROLLER FROM THE TERMINAL AIR BOX AND PROTECT IT FOR RE-USE WITH A NEW TERMINAL AIR BOX. RE: SHEET M212. REMOVE ANY CONTROL WIRING THAT CANNOT BE USED.
  - DISCONNECT AND REMOVE A PORTION OF 10" x8" SUPPLY AIR DUCTWORK AS INDICATED. PROTECT REMAINING DUCTWORK FOR NEW CONNECTIONS. RE: SHEET M212.
  - DISCONNECT AND SALVAGE RETURN AIR TERMINAL WITH SOUND BOOT. CLEAN THE GRILLE AND PROTECT THE GRILLE AND BOOT FOR RE-USE. RE: SHEET M212.
  - TERMINAL AIR BOX THAT SERVED X-RAY ROOM 2E79 SHALL REMAIN. IF THE BOX, OR THE SUPPLY AIR DUCTWORK ON EITHER SIDE OF THE BOX, WOULD INTERFERE WITH THE NEW G.E. X-RAY EQUIPMENT (OR STRUCTURAL SUPPORTS FOR SAME), THEN CONTRACTOR SHALL DISCONNECT AND RELOCATE THE BOX AND/OR DUCTWORK AS REQUIRED TO CLEAR SPACE FOR THE NEW WORK. COORDINATE WITH NEW WORK TO ENSURE THE BOX IS ACCESSIBLE FOR MAINTENANCE. MODIFY CONTROL WIRING OR PROVIDE NEW WIRING AS REQUIRED.
  - CUT AND CAP THE (PREVIOUSLY ABANDONED) EXHAUST DUCT AND REMOVE DUCTWORK ABOVE X-RAY ROOM.



**ACI**  
**BOLAND**  
 ARCHITECTS

1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600  
 ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**  
 IMEG CORP.  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's**  
**East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD. SUITE 200**  
**LEE'S SUMMIT MO 64086**

Date 07/07/21  
 Job Number 3-21014  
 Drawn By MJL  
 Checked By DWD


Revision  
 Number Date Description

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 2101484.00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 1/4" = 1'-0"

**M112**  
 © 2021 ACI/BOLAND, Inc  
 SECOND FLOOR DEMOLITION - VENTILATION

**1 SECOND FLOOR DEMOLITION - VENTILATION**  
 1/4" = 1'-0"





**SHEET NOTES:**

- REFER TO GENERAL NOTES ON SHEET M000.
- ACCORDING TO EXISTING BUILDING DOCUMENTS, EACH TERMINAL AIR BOX INCLUDES A THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) IN A NURSE STATION AREA, BUT MOST BOXES ALSO HAVE A TEMPERATURE SENSOR (WITH BLANK COVER) IN THE SPACE SERVED BY THE BOX. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND COORDINATE WITH ENGINEER IF CONDITIONS DIFFER.
- TERMINAL AIR BOX TAGS ARE BASED ON ROOM NUMBERS SERVED AND MAY NOT MATCH THE BOX TAGS IN THE BUILDING MANAGEMENT SYSTEM.

**KEYNOTES:** (1-5)

- IF POSSIBLE, INSTALL DDC CONTROLLER THAT WAS SALVAGED DURING DEMOLITION AND INSTALL IT ON THE NEW TERMINAL AIR BOX. IF NOT POSSIBLE, THEN PROVIDE AND INSTALL A NEW DDC CONTROLLER. PROVIDE NEW CONTROL WIRING AND CONNECT TO EXISTING BUILDING MANAGEMENT SYSTEM (BMS). UPDATE SOFTWARE AND GRAPHICS ON BMS AS REQUIRED.
- NEW LOCATION FOR TEMPERATURE SENSOR (WITH BLANK COVER) THAT WAS SALVAGED DURING DEMOLITION. CONNECT TO TERMINAL AIR BOX CONTROLLER AS REQUIRED. TEST SENSOR FOR ACCURACY AND CALIBRATE OR REPLACE AS REQUIRED.
- CONNECT EXISTING THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) TO TERMINAL AIR BOX CONTROLLER AS REQUIRED. UPDATE THE LABEL ON THE DEVICE TO INDICATE WHAT IT SERVES.
- NEW TEMPERATURE SENSOR (WITH BLANK COVER). CONNECT TO TERMINAL AIR BOX CONTROLLER AS REQUIRED. IF AN EXISTING SENSOR WAS FOUND DURING DEMOLITION, IT CAN BE RE-USED AND SHALL BE RE-INSTALLED IN THIS LOCATION. TEST SENSOR FOR ACCURACY AND CALIBRATE OR REPLACE AS REQUIRED.)
- UPDATE LABEL ON EXISTING THERMOSTAT (WITH TEMPERATURE ADJUSTMENT KNOB) TO REFLECT THE ROOMS IT SERVES (E.E. BOTH TECH RM. 2E67 AND NURSE STATION).

RELEASE FOR CONSTRUCTION  
 DEVELOPMENT SERVICES  
 OF MISSOURI  
 BRUCE E. HART  
 LICENSE NUMBER 22817  
 PROFESSIONAL ENGINEER  
 07-07-21  
 Bruce E. Hart - Engineer  
 License - Missouri #E-22817

**ACI BOLAND ARCHITECTS**  
 1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600  
 ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**  
 IMEG CORP.  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
 120 NE SAINT LUKE'S BLVD, SUITE 200  
 LEE'S SUMMIT MO 64086

Date	07/07/21
Job Number	3-21014
Drawn By	MJL
Checked By	DWD

Revision		
Number	Date	Description

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 21014-00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. SAVED DRAWINGS AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 1" = 1'-0"

**1 SECOND FLOOR - PIPING**  
 1/4" = 1'-0"



**SHEET NOTES:**

- REFER TO GENERAL NOTES ON SHEET M000.
- TERMINAL AIR BOX TAGS ARE BASED ON ROOM NUMBERS SERVED AND MAY NOT MATCH THE BOX TAGS IN THE BUILDING MANAGEMENT SYSTEM.

**KEYNOTES:**

- ADJUST SETTINGS FOR EXISTING TERMINAL AIR BOX AND TEST. ADJUST AND BALANCE ALL AIR TERMINALS IN THIS ZONE TO THE NEW AIR FLOW RATES (CFM) INDICATED.
- COORDINATE ROUTING OF NEW SUPPLY DUCTWORK AND EXACT LOCATIONS OF NEW TERMINAL AIR BOXES WITH EXISTING WORK. MODIFY EXISTING WORK AS REQUIRED TO CLEAR A PATCH FOR NEW WORK.
- COORDINATE ROUTING OF DUCTWORK AND LOCATIONS OF AIR TERMINALS IN NEW X-RAY ROOM WITH THE X-RAY EQUIPMENT DRAWINGS. AVOID INSTALLING THESE ITEMS WHERE THEY COULD INTERFERE WITH NEW STRUCTURAL SUPPORTS OR NEW MEDICAL EQUIPMENT.
- EXISTING 18"x12" RETURN AIR TRANSFER DUCT SLEEVE OPENING IN WALL ABOVE CEILING TO REMAIN. IF NECESSARY, RAISE THE SLEEVE TO BE ABOVE THE NEW CEILING HEIGHT.

# ACI BOLAND ARCHITECTS


1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600  
 ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**  
**IMEG CORP.**  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD. SUITE 200**  
**LEE'S SUMMIT MO 64086**

Date 07/07/21  
 Job Number 3-21014  
 Drawn By MJL  
 Checked By DWD


Revision		
Number	Date	Description



**1 SECOND FLOOR - VENTILATION**  
 1/4" = 1'-0"


**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 21014-00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. SAYS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 © 2021 IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 0 1 2 3






**NOTES:**  
1. THIS DETAIL APPLIES TO ALL RETURN GRILLES.

**1 CEILING RETURN GRILLE**  
NO SCALE




**NOTES:**  
1. TO ATTACH FLEX DUCT TO THE HARD DUCT, TAPE THE INNER LINER TO THE HARD DUCT THEN ATTACH WITH TWO NYLON TIE WRAPS, ONE FOR THE INNER LINER AND ONE FOR THE OUTER SHELL. FOLD THE OUTER SHELL INSIDE ITSELF SO IT HAS NEAT EDGES PRIOR TO THE WRAPPING.  
2. DURABLE ELBOW SUPPORT ACCEPTABLE MANUFACTURER AND MODEL: HART AND COOLEY - SMARTFLOW, THERMAFLEX - FLEXFLOW, TITUS - FLEXRIGHT, OR APPROVED EQUAL.

**2 DIFFUSER CONNECTION DETAIL (W/ RADIUS FORMING ELBOW)**  
NO SCALE




**NOTES:**  
1. THIS DETAIL APPLIES ONLY TO TAPS OFF UNLINED DUCTS.  
2. TAP DOES NOT NEED TO BE CONICAL IF THE TAP IS NOT LOCATED BETWEEN FANS AND TERMINAL AIR BOXES. DUCT IS NOT OVER 2" PRESSURE CLASS, AND ROUND DUCT IS NOT OVER 12" DIAMETER.

**3 FLEX DUCT CONNECTION (CONICAL/WRAPPED)**  
NO SCALE




**NOTES:**  
1. THIS DETAIL APPLIES ONLY TO TAPS OFF UNLINED DUCTS.  
2. TAP DOES NOT NEED TO BE CONICAL IF THE TAP IS NOT LOCATED BETWEEN FANS AND TERMINAL AIR BOXES. DUCT IS NOT OVER 2" PRESSURE CLASS, AND ROUND DUCT IS NOT OVER 12" DIAMETER.  
3. MANUFACTURED TAP/DAMPER COMBINATIONS WITH LESS THAN 1/2 DUCT DIAMETER SPACING BETWEEN THE DAMP DUCT AND THE DAMPER SHAFT ARE ACCEPTABLE ONLY IF THE DAMPER SHAFT IS INSTALLED PARALLEL TO THE AIR FLOW IN THE MAIN DUCT.

**4 ROUND DUCT TAP CONNECTION (CONICAL/WRAPPED)**  
NO SCALE



**5 HOT WATER COIL PIPING**  
NO SCALE



**NOTES:**  
1. THIS DETAIL APPLIES ONLY TO TAPS OFF WRAPPED DUCTS.  
2. THIS DETAIL APPLIES TO TERMINAL AIR BOXES WITH ROUND INLETS AND RECTANGULAR OUTLETS.  
3. DUCT LEADING TO TAB INLET MUST BE STRAIGHT FOR 1.5 DIAMETER UPSTREAM.  
4. MAINTAIN VAPOR BARRIER FROM MAIN TO BRANCH DUCT.

**6 TERMINAL AIR BOX DETAIL (WRAPPED MAIN)**  
NO SCALE

Date	07/07/21
Job Number	3-21014
Drawn By	MJL
Checked By	DWD

Number	Date	Description
Revision		

7/2/2021 1:58:39 PM  
C:\Revit Local Files\MEPT21\_21001694\_00\_SLE Rockhill X-ray\_C\_Brent.W.Curp.rvt



**AIR TERMINAL SCHEDULE**


NOTES:  
 1.CONTRACTOR SHALL DETERMINE PROPER BORDER TYPE TO MATCH CEILING CONSTRUCTION.  
 2.REFER TO DRAWINGS FOR NECK SIZE. ALL BRANCH DUCTWORK TO AIR TERMINALS SHALL BE NECK SIZE UNLESS NOTED OTHERWISE.

TAG NAME	FACE SIZE (IN.) (NOTE 2)	TYPE	BORDER (NOTE 1)	MATERIAL	FINISH	VOLUME DAMPER REQUIRED	MANUFACTURER	MODEL	NOTES
RA	24x12	HORIZONTAL FACE 45° DEFLECTION	LAY-IN	STEEL	WHITE	NO	TITUS	23RL	OMIT SCREW HOLES IN LAY-IN CEILING
SD-1	24x24	SQUARE PLAQUE	LAY-IN	STEEL	WHITE	NO	TITUS	OMNI	

**TERMINAL AIR BOX SCHEDULE - SINGLE DUCT**

NOTES:  
 1.NEITHER RADIATED NOR DISCHARGE SOUND LEVELS SHALL EXCEED NC 35 AT 1.5' INLET STATIC PRESSURE WHEN TESTED PER AHRI STANDARD 885-2008 USING 5/8" 20-LB DENSITY MINERAL FIBER CEILING TILE.  
 2.TOTAL AIR PRESSURE DROP OF TAB AND REHEAT COIL SHALL NOT EXCEED 0.50" WC.  
 3.HEATING COIL IS BASED ON HEATING AIR FLOW. WATER PRESSURE DROP OF REHEAT COILS SHALL NOT EXCEED 5'. PROVIDE REHEAT COILS SEPARATE FROM BOXES IF REQUIRED TO MEET WATER PRESSURE DROP REQUIREMENTS. WHEN LAT °F, EWT °F, AND GPM VALUES ARE BLANK, HEATING COIL IS NOT REQUIRED FOR TAB.  
 4.HEATING COIL SELECTION SHALL BE BASED ON A FIXED LEAVING AIR TEMPERATURE AND VARIABLE FLOW (GPM). PROVIDE FINAL MAXIMUM FLOW RATE (GPM) TO TEST & BALANCE TEMPERATURE CONTROLS CONTRACTORS.

TAG NAME	CFM		HEATING COIL (NOTES 3, 4)				MIN. INLET SIZE (IN.) DIA.	MANUFACTURER	MODEL (NOTES 1, 2)	NOTES	
	COOLING MAX.	HEATING MAX.	MIN.	EAT °F	EWAT °F	MAX GPM					
E3-2E51	500	500	500	55.0	85.0	180	1.1	8"	TITUS	DESV	NOTES 1, 2, 3, 4
E3-2E83	600	600	600	55.0	85.0	180	1.3	8"	TITUS	DESV	NOTES 1, 2, 3, 4



**SEQUENCE OF OPERATION:**

- FMCS TAB CONTROLLER SHALL MODULATE THE TAB DAMPER AND TAB HW REHEAT COIL CONTROL VALVE TO MAINTAIN SPACE SET POINT BASED ON A SIGNAL FROM A WALL MOUNTED TEMPERATURE SENSOR. SEE DRAWINGS FOR TEMPERATURE SENSOR REQUIREMENTS.
- AT FULL COOLING, THE TAB SHALL BE OPEN TO MAXIMUM CFM POSITION. THE REHEAT COIL CONTROL VALVE SHALL BE CLOSED.
- UPON A FALL IN SPACE TEMPERATURE, THE TAB SHALL MODULATE CLOSED UNTIL SPACE SETPOINT IS MAINTAINED, OR UNTIL IT REACHES ITS MINIMUM SCHEDULED CFM POSITION PER THE TAB SCHEDULE. THE REHEAT COIL CONTROL VALVE SHALL BE CLOSED.
- UPON A FURTHER FALL IN SPACE TEMPERATURE, THE REHEAT COIL CONTROL VALVE SHALL MODULATE OPEN TO MAINTAIN SPACE SETPOINT UNTIL THE SUPPLY AIR TEMPERATURE IS 20°F ABOVE ROOM TEMPERATURE SETPOINT.
- UPON A FURTHER FALL IN SPACE TEMPERATURE, TAB SHALL OPEN TO MAINTAIN SETPOINT UNTIL TAB AIRFLOW REACHES ITS MAXIMUM HEATING SETTING. THE REHEAT CONTROL VALVE SHALL CONTINUE TO MODULATE OPEN TO MAINTAIN MAXIMUM DELTA T LISTED ABOVE.
- THE FMCS OPERATOR SHALL HAVE THE ABILITY TO ADJUST, OVERRIDE AND DISPLAY TEMPERATURES AND SET POINTS FROM THE EXISTING FMCS WORKSTATION.

**ALARMS, INTERLOCKS & SAFETIES:**  
 SEND AN ALARM TO THE FMCS OPERATOR INTERFACE IF THE SPACE TEMPERATURE IS MORE THAN 10°F (ADJ.) ABOVE OR BELOW SETPOINT.

**1 TAB CONTROL W/ HOT WATER REHEAT - TAB-X**  
 NO SCALE

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 2101634.00  
 Missouri State Certificate of Authority E-2017008530  
 IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 © 2021 IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 0 1 2 3

**Saint Luke's East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD, SUITE 200**  
**LEE'S SUMMIT MO 64086**

Date 07/07/21  
 Job Number 3-21014  
 Drawn By MJL  
 Checked By DWD

Revision  
 Number Date Description



### PLUMBING SYMBOL LIST

NOT ALL SYMBOLS MAY APPLY.	
SYMBOL:	DESCRIPTION:
AV	ACID VENT
AW	ACID WASTE
CA	COMPRESSED AIR
CW	COLD WATER - POTABLE
D	DRAIN
DI	DEIONIZED WATER
DT	DRAIN TILE
G	NATURAL GAS
GRV	GAS REGULATOR VENT
GSAN	SANITARY DRAINAGE (GREASE SANITARY DRAINAGE)
GV	GREASE VENT
HW	HOT WATER - POTABLE
HW-C	HOT WATER CIRCULATING - POTABLE
HW140	HOT WATER - POTABLE NUMBER INDICATES TEMP
HW140-C	HOT WATER CIRC. - POTABLE NUMBER INDICATES TEMP
IA	INSTRUMENT AIR
MA	MEDICAL AIR
MPG	MEDIUM PRESSURE GAS
MV	MEDICAL VACUUM
N	NITROGEN
NCW	NON-POTABLE COLD WATER
NHW	NON-POTABLE HOT WATER
NO	NITROUS OXIDE
OR	OIL RETURN
OS	OIL SUPPLY
O	OXYGEN
P	PROPANE GAS
PD	PUMPED DISCHARGE
PW	PURE WATER
RO	REVERSE OSMOSIS WATER
SAN	SANITARY DRAINAGE
SCW	SOFT COLD WATER
SHW	SOFT HOT WATER
ST(1,000)	STORM DRAINAGE (ROOF SQUARE FOOTAGE)
STS	STORM DRAINAGE (SECONDARY)
STW	SOFT TEMPERED WATER
TW	TEMPERED WATER
V	VENT
VAC	LAB VACUUM
W	SERVICE WATER - POTABLE
WAGD	WASTE ANESTHESIA GAS DISPOSAL
→	PIPE CONTINUATION
→	PIPE CAP
→	PIPE DOWN
→	PIPE UP OR UP/DOWN
→	PIPE SERVING FIXTURE ON FLOOR ABOVE (EXAMPLE: FD = FLOOR DRAIN)
→	PITCH PIPE IN DIRECTION
→	DIRECTION OF FLOW IN PIPE
→	ROUTE TO DRAIN
→	ROOF DRAIN PROPERTIES (SYMBOL SIZE (ROOF SQ. FT.))
→	DIELECTRIC CONNECTION
→	UNION/FLANGE
→	SHUTOFF VALVE NORMALLY OPEN
→	SHUTOFF VALVE NORMALLY CLOSED
→	BALANCING VALVE (NUMBER INDICATES GPM)
→	CHECK VALVE
→	BACKFLOW PREVENTER
→	SOLENOID VALVE
→	SAFETY/RELIEF VALVE
→	VACUUM BREAKER
→	PRESSURE GAUGE (FURNISHED WITH BALL VALVE)
→	PRESSURE SENSOR (FURNISHED WITH BALL VALVE)
→	TEMPERATURE SENSOR WITH WELL
→	THERMOMETER WITH WELL (DIAL TYPE)
→	THERMOMETER WITH WELL (FILLED TYPE)
→	REDUCER - REFERENCE SPECIFICATION FOR CONCENTRIC/ECCENTRIC AND FOTFOB
→	PRESSURE REDUCING VALVE (LIQUID/GAS)
→	PUMP
→	METER
→	ALIGNMENT GUIDE
→	PIPE ANCHOR
→	EXPANSION JOINT

### PLUMBING ABBREVIATION KEY

ABBR:	DESCRIPTION:
AD	ACCESS DOOR
AFB	ABOVE FINISHED FLOOR
BFP	BACKFLOW PREVENTER
BT	BATHTUB
CB	CATCH BASIN
CI	CAST IRON
CO	CLEANOUT
CS	CLINICAL SINK
DB	DIALYSIS BOX
DF	DRINKING FOUNTAIN
DI	DUCTILE IRON
E	EXISTING
EE	EMERGENCY EYEWASH
ES	EMERGENCY SHOWER
ESE	EMERGENCY SHOWER/EYEWASH
EW	ELECTRIC WATER COOLER
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FM	FLOW METER
FS	FLOOR SINK
GD	GARBAGE DISPOSER
GI	GREASE INTERCEPTOR
HB	HOSE BIBB
I.E.	INVERT ELEVATION (FOR REFERENCE ONLY)
LAV	LAVATORY
MB	MOP BASIN
MH	MANHOLE
MV	MIXING VALVE
NC	NOT IN CONTRACT
NT	NEUTRALIZATION TANK
OS	OIL SEPARATOR
RD	ROOF DRAIN
SCCR	SHORT CIRCUIT CURRENT RATING
SH	SHOWER
SK	SINK
SS	SERVICE SINK
TD	TRENCH DRAIN
TP	TRAP PRIMER
TYP	TYPICAL
UR	URINAL
VTR	VENT THROUGH ROOF
WC	WATER CLOSET
WCO	WALL CLEANOUT
WF	WASH FOUNTAIN
WH	WATER HEATER
WMF	WASHING MACHINE FIXTURE
WM	WATER METER
WS	WATER SOFTENER
UB	UTILITY BOX
UNO	UNLESS NOTED OTHERWISE
YCO	YARD CLEANOUT

### CONTRACTOR ABBREVIATION KEY

ABBR:	DESCRIPTION:
A.C.	ASBESTOS ABATEMENT CONTRACTOR
A.V.C.	AUDIOVISUAL CONTRACTOR
C.C.	CIVIL CONTRACTOR
C.M.	CONSTRUCTION MANAGER
E.C.	ELECTRICAL CONTRACTOR
F.P.C.	FIRE PROTECTION CONTRACTOR
F.S.C.	FOOD SERVICE CONTRACTOR
G.C.	GENERAL CONTRACTOR
H.C.	HEATING CONTRACTOR
M.C.	MECHANICAL CONTRACTOR
N.C.C.	NURSE CALL CONTRACTOR
P.C.	PLUMBING CONTRACTOR
S.C.	SECURITY CONTRACTOR
T.C.	TECHNOLOGY CONTRACTOR
T.C.C.	TEMPERATURE CONTROLS CONTRACTOR
V.C.	VENTILATION CONTRACTOR

### VIEW KEY

NAME → LEVEL NAME  
10' - 0" → HEIGHT ABOVE PROJECT 0' - 0"

INDICATES DIRECTION OF TRUE NORTH  
PLAN OR DETAIL NUMBER  
PLAN OR DETAIL NAME  
1/8" = 1'-0"  
PLAN OR DETAIL SCALE

INDICATES SIMILAR DETAIL REFERENCED IN MULTIPLE LOCATIONS  
DETAIL REFERRED TO BY SECTION CUT  
SHEET DETAIL IS LOCATED ON T101

LINE TYPE AND TAG KEY:  
NEW WORK BY THIS CONTRACTOR (WIDE LINE)  
NEW  
EXISTING TO BE REMOVED (SHORT DASHED PATTERN)  
NEW UNDERFLOOR OR UNDERGROUND (LONG DASHED PATTERN)  
EXISTING TO REMAIN OR WORK BY OTHERS (NARROW LINE)  
EXISTING  
EXISTING TO BE REMOVED BY OTHERS (SHORT DASHED PATTERN)  
EXISTING UNDERFLOOR OR UNDERGROUND (LONG DASHED PATTERN)

HALFTONING DOES NOT MODIFY SCOPE.

TAG-E TAGS WITH DASH 'E' INDICATES THE REFERENCED OBJECT IS EXISTING ELSEWHERE IN A SCHEDULE, MATERIAL LIST, OR SYMBOL LIST

TAG-1 UNDERLINED TEXT INDICATES ADDITIONAL INFORMATION CAN BE FOUND ELSEWHERE IN A SCHEDULE, MATERIAL LIST, OR SYMBOL LIST

INDICATES AN EXISTING SYSTEM'S POINT OF CONNECTION/REMOVAL

### PLUMBING GENERAL NOTES:

- THE SYMBOLS AND THE MATERIAL LIST ARE FOR THE CONVENIENCE OF THE CONTRACTOR. CONTRACTOR SHALL VERIFY QUANTITIES AND FURNISH ALL MATERIALS REQUIRED FOR FULLY OPERATIONAL SYSTEMS, WHETHER SPECIFIED OR NOT.
- CATALOG NUMBERS SHALL NOT BE CONSIDERED COMPLETE, BUT ARE GIVEN AS AN AID TO THE CONTRACTOR AND TO INDICATE THE QUALITY REQUIRED. CONTRACTOR IS RESPONSIBLE FOR A COMPLETE DESCRIPTION OF MATERIAL ON THESE DRAWINGS AND IN THE SPECIFICATIONS BEFORE ORDERING. THE DESCRIPTION OF THE MATERIAL TAKES PRECEDENCE OVER THE CATALOG NUMBER. THE FIRST MANUFACTURER LISTED IS THE BASIS OF DESIGN.
- CONTRACTOR SHALL VERIFY THAT FIXTURES SUPPLIED ARE APPROVED PER ALL APPLICABLE STATE, LOCAL, AND GOVERNING AUTHORITIES.
- ALL FIXTURES SHALL CONFORM TO FEDERAL ACT 5, 874.
- INVERT ELEVATIONS ARE FROM EXISTING DRAWINGS AND MAY NOT BE ACCURATE. VERIFY ALL ELEVATIONS BEFORE BEGINNING WORK.
- VERIFY UNDERGROUND PIPE SIZES, INVERT ELEVATIONS, AND LOCATIONS PRIOR TO BEGINNING ANY WORK.
- REFER TO THE PLUMBING ROUGH-IN SCHEDULE FOR THE SIZES OF BRANCH PIPES TO PLUMBING FIXTURES.
- FOR CLARITY, NOT ALL VALVES HAVE BEEN SHOWN. VERIFY SHUTOFF VALVES IN DOMESTIC WATER PIPING SERVING EACH ROOM WITH FIXTURES. ANGLE STOPS SHALL NOT BE CONSIDERED SHUTOFF VALVES.
- EXISTING CONDITIONS ON DEMOLITION PLANS ARE PROVIDED TO INDICATE THE GENERAL SCOPE OF ITEMS TO BE REMOVED. REFER TO SPECIFICATION SECTION 22 05 05 FOR ADDITIONAL DEMOLITION INFORMATION.
- P.C. SHALL CUT AND PATCH EXISTING AS REQUIRED FOR NEW OR DEMOLITION WORK UNLESS NOTED OTHERWISE. REFER TO SPECIFICATION SECTION 22 05 05 FOR ADDITIONAL INFORMATION.

### MECHANICAL GENERAL NOTES:


- THESE NOTES APPLY TO ALL MECHANICAL SHEETS AND TRADES, INCLUDING BUT NOT LIMITED TO, FIRE PROTECTION, PLUMBING, MEDICAL GAS, VENTILATION, PIPING AND TEMPERATURE CONTROL.
- DRAWINGS SHOWING LOCATIONS OF EQUIPMENT, DUCTWORK, PIPING, ETC. ARE DIAGRAMMATIC AND MAY NOT ALWAYS REFLECT EXACT INSTALLATION CONDITIONS. DRAWINGS SHOW THE GENERAL ARRANGEMENT OF DUCTWORK, PIPING, EQUIPMENT, ETC., AND MAY NOT INCLUDE ALL OFFSETS AND FITTINGS REQUIRED FOR COMPLETE INSTALLATION. THE DRAWINGS SHALL BE FOLLOWED AS CLOSELY AS ACTUAL BUILDING CONSTRUCTION AND THE WORK OF OTHERS WILL PERMIT.
  - DO NOT SCALE DRAWINGS. VERIFY ALL DIMENSIONS AND CLEARANCES FROM ARCHITECTURAL, STRUCTURAL, SUBMITTALS, AND OTHER APPROPRIATE DRAWINGS OR PHYSICALLY AT SITE. REVIEW ALL DRAWINGS, INCLUDING THOSE OF OTHER TRADES.
  - COORDINATE ALL WORK WITH ALL OTHER TRADES PRIOR TO INSTALLATION TO PROVIDE CLEARANCES REQUIRED FOR OPERATION, MAINTENANCE, CODE COMPLIANCE, AND TO VERIFY NON-INTERFERENCE WITH OTHER WORK. DO NOT FABRICATE PRIOR TO VERIFICATION OF NECESSARY CLEARANCES FOR ALL TRADES. BRING ANY INTERFERENCES OR CONFLICTS TO THE ATTENTION OF THE ARCHITECT/ENGINEER BEFORE PROCEEDING WITH FABRICATION OR EQUIPMENT ORDERS.
  - REVIEW SPACE REQUIREMENTS OF EQUIPMENT SPECIFIED OR SUBSTITUTED AND MAKE REASONABLE ACCOMMODATIONS IN LAYOUT AND POSITIONING TO PROVIDE PROPER ACCESS.
  - ANY CHANGES REQUIRED TO ELIMINATE CONFLICTS OR THAT RESULT FROM A FAILURE TO COORDINATE SHALL BE MADE BY THE CONTRACTOR WITHOUT ADDITIONAL COST OR EXPENSE TO OTHERS.
  - EACH CONTRACTOR IS RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH ELECTRICAL CHANGES REQUIRED FOR EQUIPMENT PROPOSED THAT DIFFERS FROM THE BASIS OF DESIGN.
  - REFER TO ARCHITECTURAL REFLECTED CEILING PLAN, ELECTRICAL, TECHNOLOGY AUDIOVISUAL, AND OTHER MECHANICAL PLANS FOR EXACT LOCATIONS OF ALL CEILING MOUNTED DEVICES, OTHER THAN SPRINKLERS.
  - EACH CONTRACTOR IS RESPONSIBLE FOR DAMAGE CAUSED BY THEIR ACTIONS TO WALLS, FLOORS, CEILINGS, AND ROOFS. THE CONTRACTOR WHOSE WORK CAUSES DAMAGE IS RESPONSIBLE FOR PATCHING TO MATCH ORIGINAL CONSTRUCTION, FIRE RATING, AND FINISH.
  - IN AREAS WITH DRYWALL CEILINGS COORDINATE LOCATIONS OF ACCESS PANELS WITH THE GC FOR ACCESS TO VALVES, DUCTWORK ACCESSORIES, DAMPERS, ETC. COORDINATE PANEL TYPE AND COLOR WITH ARCHITECT. NOTIFY THE GC OF THE REQUIRED ACCESS PANELS PRIOR TO BIDDING.
  - SEAL ALL FLOOR AND WALL PENETRATIONS AIRTIGHT WHERE CONDUITS, PIPING, AND DUCTS PENETRATE.
  - CAULK ALL PIPE AND DUCT PENETRATIONS OF FULL HEIGHT NON-FIRE RATED WALL, PARTITION, FLOOR, AND ROOF ASSEMBLIES. THIS IS ESSENTIAL TO PREVENT NOISE TRANSMISSION FROM ONE ROOM TO ANOTHER AND TO PROVIDE THE DESIRED NC LEVELS WITHIN ROOMS.
  - WHERE PIPES AND DUCTS ARE SHOWN TO PENETRATE FLOORS, PROVIDE SLEEVED OPENINGS WITH THE TOP EDGE RAISED ABOVE FLOOR SURFACE IN ACCORDANCE WITH ALL RELEVANT SPEC SECTIONS. SEAL SLEEVE PERIMETER TO BE WATERTIGHT.
  - EQUIPMENT SIZES AND SERVICE CLEARANCE REQUIREMENTS VARY AMONG DIFFERENT MANUFACTURERS. CONSULT APPROVED SHOP DRAWINGS OR EQUIPMENT SIZES AND REQUIRED SERVICE CLEARANCES, COORDINATE WITH LAYOUT OF EQUIPMENT PADS, PIPING, DUCTWORK, ETC.
  - DO NOT BLOCK TUBE FULL OR EQUIPMENT SERVICE CLEARANCES.
  - MAINTAIN MINIMUM 3'-6" CLEARANCE IN FRONT OF ALL ELECTRICAL PANELS, MOTOR STARTERS, SWITCHES, AND DISCONNECTS.
  - PROVIDE CONCRETE EQUIPMENT PAD FOR ALL FLOOR MOUNTED EQUIPMENT. PAD SHALL EXTEND MINIMUM 6" BEYOND ALL SIDES OF EQUIPMENT.
  - DO NOT SUPPORT EQUIPMENT, PIPING, OR DUCTWORK FROM METAL DECKING OR OTHER NON-STRUCTURAL BUILDING ELEMENTS. ANCHORS EMBEDDED IN CONCRETE SHALL BE CRACKED CONCRETE APPROVED IN ACCORDANCE WITH SPECIFICATIONS.

### MECHANICAL RENOVATION NOTES:

- THESE NOTES APPLY TO ALL MECHANICAL SHEETS AND TRADES, INCLUDING BUT NOT LIMITED TO, FIRE PROTECTION, PLUMBING, MEDICAL GAS, VENTILATION, PIPING AND TEMPERATURE CONTROL.
- EXISTING CONDITIONS ARE SHOWN BASED ON INFORMATION OBTAINED FROM FIELD SURVEYS, EXISTING BUILDING DOCUMENTS, AND STAFF. VERIFY EXISTING CONDITIONS AND REPORT ANY CONFLICTS BEFORE PROCEEDING.
  - NOT ALL EXISTING DUCTWORK AND PIPING IS SHOWN. VERIFY EXISTING CONDITIONS BEFORE STARTING WORK. NOTIFY ENGINEER OF ANY CONFLICTS WITH NEW WORK.
  - FIELD VERIFY THE AVAILABLE CLEARANCES FOR DUCTWORK AND PIPING BEFORE FABRICATION. RISES AND DROPS MAY BE NECESSARY BECAUSE OF EXISTING FIELD CONDITIONS.
  - EACH CONTRACTOR SHALL FIELD VERIFY ACCESSIBILITY TO THE AREA OF HIS/HER WORK AND SHALL NOTIFY THE ARCHITECT/ENGINEER PRIOR TO BIDDING IF OTHER UTILITIES ARE REQUIRED TO BE REMOVED OR RELOCATED TO ALLOW ACCESS TO HIS/HER AREA OF WORK.
  - THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CUTTING, REMOVAL AND PATCHING OF ROOFS, WALLS, AND FLOORS ASSOCIATED WITH WORK BY ALL CONTRACTORS. CONTRACTORS SHALL NOTIFY THE GC OF AFFECTED AREAS PRIOR TO BIDDING.
  - THE GENERAL CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF CEILINGS, CEILING TILES, AND CEILING GRIDS ASSOCIATED WITH AREAS OF WORK BY ALL CONTRACTORS. NOTIFY THE GENERAL CONTRACTOR OF AFFECTED AREAS PRIOR TO BIDDING.
  - WHERE EXISTING MECHANICAL SYSTEMS ARE LOCATED IN AREAS THAT CONFLICT WITH NEW EQUIPMENT, PIPING, OR DUCTWORK TO BE INSTALLED, EACH CONTRACTOR SHALL EITHER ARRANGE NEW EQUIPMENT, PIPING, OR DUCTWORK IN SUCH A FASHION THAT IT DOES NOT CONFLICT WITH EXISTING SYSTEMS, OR REWORK EXISTING MECHANICAL SYSTEMS TO ALLOW FOR INSTALLATION OF NEW EQUIPMENT, PIPING, OR DUCTWORK.
  - PROVIDE TEMPORARY CONNECTIONS TO MAINTAIN EXISTING SYSTEMS IN SERVICE DURING CONSTRUCTION. MAINTAIN ACCESS TO EXISTING MECHANICAL INSTALLATIONS THAT REMAIN ACTIVE.
  - OBTAIN PERMISSION FROM OWNER BEFORE SHUTTING DOWN ANY SYSTEM FOR ANY REASON. MAINTAIN SERVICE TO ALL COMPONENTS THAT ARE TO REMAIN UNTIL NEW SYSTEMS ARE INSTALLED.
  - MAINTAIN EXISTING SYSTEM IN SERVICE UNTIL NEW SYSTEM IS COMPLETE AND READY FOR TIE IN AND SWITCHOVER. DRAIN SYSTEM ONLY TO MAKE SWITCHOVERS AND CONNECTIONS. OBTAIN PERMISSION FROM OWNER BEFORE PARTIALLY OR COMPLETELY DRAINING SYSTEM. MAKE CHANGEOVER TO NEW SYSTEMS WITH MINIMUM OUTAGE.
  - DISCONNECT AND REMOVE MECHANICAL DEVICES AND EQUIPMENT SERVING EQUIPMENT THAT HAS BEEN REMOVED.

### MECHANICAL PHASING NOTES:

- THESE NOTES APPLY TO ALL MECHANICAL SHEETS AND TRADES, INCLUDING BUT NOT LIMITED TO, FIRE PROTECTION, PLUMBING, MEDICAL GAS, VENTILATION, PIPING AND TEMPERATURE CONTROL.
- REFER TO ARCHITECTURAL DRAWINGS FOR GENERAL DESCRIPTION OF PHASES. REFER TO GENERAL CONTRACTOR'S INSTRUCTIONS FOR MORE DETAILS AND PHASING SCHEDULES AND FOR CONCURRENT WORK. MECHANICAL, ELECTRICAL AND TECHNOLOGY DRAWINGS DEPICT THE INTENT OF THE FINAL DESIGN. THE MECHANICAL, ELECTRICAL AND TECHNOLOGY DRAWINGS DO NOT DEPICT THE MEANS AND METHODS TO MEET THE REQUIREMENTS OF THE PHASING CRITERIA.
  - REVIEW PROJECT PHASING PLANS TO COORDINATE DEMOLITION WORK, OUTAGES, ETC. WITH AFFECTED ADJACENT AREAS.
  - PROVIDE TEMPORARY DUCTWORK, PIPING, SHUTOFF VALVES, ZONE VALVES, ZONE ALARMS, ETC. AS NEEDED TO MAINTAIN SERVICE TO ALL AREAS DURING ALL PHASES OF PROJECT.
  - INSTALL TEMPORARY DUCTWORK, PIPING, SHUTOFF VALVES, ETC. AS NECESSARY TO KEEP ALL OCCUPIED SPACES OPERATIONAL THROUGHOUT ALL PHASES OF THE PROJECT.
  - PHASE DEMOLITION WORK TO MINIMIZE DOWNTIME.



Bruce E. Hart - Engineer  
License - Missouri #E-22817

# ACI BOLAND ARCHITECTS

1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

### MEP CONSULTANT

IMEG CORP.  
1600 BALTIMORE ST, SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437

**Saint Luke's East Hospital**

**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**

**120 NE SAINT LUKE'S BLVD. SUITE 200**

**LEE'S SUMMIT MO 64086**

Date	07/07/21
Job Number	3-21014
Drawn By	MJL
Checked By	DWD

Revision	Date	Description

**IMEG**

1600 BALTIMORE SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437  
www.imegcorp.com  
PROJECT # 21014-00

Missouri State Certificate of Authority E-201700850

IMEG CORP. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.

REFERENCE SCALE IN INCHES

0 1 2 3


**P000**

© 2021 ACI/BOLAND, Inc  
PLUMBING COVERSHEET



**SHEET NOTES:**  
 1. REFER TO GENERAL NOTES ON SHEET P000.

**SPRINKLER NOTE:**  
 SPRINKLER CONTRACTOR SHALL DISCONNECT, REMOVE AND RELOCATE ANY AND/OR ALL SPRINKLER PIPING AND SPRINKLER HEADS AS REQUIRED BY MECHANICAL, ELECTRICAL AND GENERAL CONTRACTORS. AFTER ALL LARGER DUCTWORK AND PIPING HAVE BEEN INSTALLED, SPRINKLER CONTRACTOR SHALL REINSTALL SPRINKLER PIPING AND HEADS REQUIRED TO SPRINKLER REMODELED SPACE. SPRINKLER CONTRACTOR SHALL ALSO INSTALL NEW SPRINKLER HEADS AND/OR PIPING AS REQUIRED BY REMODEL OF SPACE. ALL SPRINKLER HEADS SHALL BE CONCEALED TYPE. SPRINKLERS MAY NOT BE ALLOWED IN CERTAIN AREAS OF THE CEILING, WHERE RESTRICTED IN THE X-RAY EQUIPMENT DRAWINGS.



**1 SECOND FLOOR - PLUMBING**  
 1/4" = 1'-0"

**Saint Luke's**  
**East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD. SUITE 200**  
**LEE'S SUMMIT MO 64086**

Date 07/07/21  
 Job Number 3-21014  
 Drawn By MJL  
 Checked By DWD

Revision  
 Number Date Description

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 2101484.00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. SAYS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 1" = 1'-0"



AV SYMBOL LIST			
SYMBOL:	EQUIPMENT LIST ABBREVIATION:	DESCRIPTION:	NOTE:
(S)	PA-S1-C	FACILITY PAGING SPEAKER (CEILING) TYPE 1	
(S)	PA-S1-W	FACILITY PAGING SPEAKER (WALL) TYPE 1	
(H)	PA-H1-W	FACILITY PAGING LOUD SPEAKER HORN (WALL) TYPE 1	
(CR)	N/A	SECURITY CREDENTIAL READER (WALL) EXISTING	
(CR1)	AC-CR1-W	SECURITY CREDENTIAL READER (WALL) TYPE 1	
(DC)	AC-DC-W	SECURITY DOOR CONTACT SWITCH (WALL)	
(DR)	AC-DR-S	SECURITY DURESS/PANIC BUTTON (SURFACE)	
(DR)	AC-DR-W	SECURITY DURESS/PANIC BUTTON (WALL)	
(EDR)	AC-EDR-UC	SECURITY ELECTRONIC DOOR RELEASE (UNDERCOUNTER)	
(EDR)	AC-EDR-W	SECURITY ELECTRONIC DOOR RELEASE (WALL)	
(KP)	N/A	SECURITY KEYPAD (WALL) EXISTING	
(KP1)	AC-KP1-W	SECURITY KEYPAD (WALL) TYPE 1	
(PP)		PUSH PAD/PUSH TO EXIT	
(C#)	SC-ID-FB	ELECTRICAL FLOOR BOX WITH TECHNOLOGY	1.2
(C#)	SC-ID-C	INFORMATION OUTLET (CEILING)	1.2
(C#)	N/A	INFORMATION OUTLET (CEILING) EXISTING	
(C#)	SC-ID-F	INFORMATION OUTLET (FLOOR)	1.2
(C#)	N/A	INFORMATION OUTLET (FLOOR) EXISTING	
(C#)	SC-ID-W	INFORMATION OUTLET (WALL)	1.2
(C#)	N/A	INFORMATION OUTLET (WALL) EXISTING	
(C#)	AV-RL-AV#	INFORMATION OUTLET AV ROUGH-IN (WALL)	1.2
(C#)	N/A	INFORMATION OUTLET AV ROUGH-IN (WALL) EXISTING	
(C#)	SC-RL-C	INFORMATION OUTLET ROUGH-IN (CEILING)	
(C#)	N/A	INFORMATION OUTLET ROUGH-IN (CEILING) EXISTING	
(C#)	SC-RL-F	INFORMATION OUTLET ROUGH-IN (FLOOR)	
(C#)	N/A	INFORMATION OUTLET ROUGH-IN (FLOOR) EXISTING	
(C#)	SC-RL-W	INFORMATION OUTLET ROUGH-IN (WALL)	
(C#)	SC-ID-W	INFORMATION OUTLET WALL PHONE (WALL)	2
(C#)	N/A	INFORMATION OUTLET WALL PHONE (WALL) EXISTING	
(C#)	SC-WAP-C	WIRELESS ACCESS POINT WITH ENCLOSURE (CEILING)	
(C#)	SC-WAP-W	WIRELESS ACCESS WITH POINT ENCLOSURE (WALL)	

AV SYMBOL LIST			
SYMBOL:	EQUIPMENT LIST ABBREVIATION:	DESCRIPTION:	NOTE:
(AA)	ID-AA-W	INTRUSION DETECTION AUDIBLE ALARM (WALL)	
(DC)	ID-DC-W	INTRUSION DETECTION DOOR CONTACT SWITCH (WALL)	
(DR)	ID-DR-UC	INTRUSION DETECTION DURESS/PANIC BUTTON (UNDER COUNTER)	
(DR)	ID-DR-W	INTRUSION DETECTION DURESS/PANIC BUTTON (WALL)	
(MD)	ID-MD-C	INTRUSION DETECTION MOTION DETECTOR (CEILING)	
(MD)	ID-MD-W	INTRUSION DETECTION MOTION DETECTOR (WALL)	
(SP)	N/A	AV PERFORMANCE AUDIO SPEAKER (CEILING) EXISTING	
(SP1)	AV-SP1-C	AV PERFORMANCE AUDIO SPEAKER (CEILING) TYPE 1	
(#-#-#)	N/A	VIDEO SURVEILLANCE DOME CAMERA	
(#-#-#)	N/A	VIDEO SURVEILLANCE LINEAR CAMERA	
(#-#-#)	N/A	VIDEO SURVEILLANCE PANORAMIC 180 CAMERA	
(#-#-#)	N/A	VIDEO SURVEILLANCE PANORAMIC 360 CAMERA	
(#-#-#)	N/A	VIDEO SURVEILLANCE PTZ PANORAMIC CAMERA	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA 180° FOV (CEILING/HORIZONTAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA 180° FOV (WALL/VERTICAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA 270° FOV (CEILING/HORIZONTAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA 270° FOV (WALL/VERTICAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA 360° FOV (CEILING/HORIZONTAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA 360° FOV (WALL/VERTICAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA DUAL LENS FOV (CEILING/HORIZONTAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA DUAL LENS FOV (WALL/VERTICAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA SINGLE LENS FOV (CEILING/HORIZONTAL SURFACE)	
(#-#-#)	VS-CM-#	VIDEO SURVEILLANCE CAMERA SINGLE LENS FOV (WALL/VERTICAL SURFACE)	
(CAM)	VS-CAM-W	CLOSED CIRCUIT TELEVISION (CCTV) WALL CAMERA	
(CAM)	VS-CAM-C	CLOSED CIRCUIT TELEVISION (CCTV) CEILING CAMERA	

**GENERAL NOTES:**

- ALL SYMBOLS AND ABBREVIATIONS LISTED MAY NOT BE APPLICABLE TO THIS PROJECT. REFER TO THE GENERAL TECHNOLOGY EQUIPMENT SCHEDULE FOR MORE COMPLETE DESCRIPTION AND ITEMS.
- ALL SYMBOLS AND ABBREVIATIONS REFER TO TECHNOLOGY SHEETS ONLY AS DEFINED ON THE SHEET INDEX. REFER TO THE GENERAL TECHNOLOGY NOTES FOR ADDITIONAL INFORMATION.
- ALL SYMBOLS LISTED ABOVE ARE FOR REFERENCE ONLY. REFER TO PLAN AND LINE TYPE KEY FOR NEW, EXISTING TO REMAIN AND TO BE REMOVED ITEMS FOR ADDITIONAL INFORMATION.

**TECHNOLOGY SYMBOL NOTES:**

- "#"  
INDICATES NUMBER OF DATA CABLES FOR INFORMATION OUTLET FACEPLATE CONFIGURATION. REFER TO CABLE LABELING STANDARD DETAIL ON THIS SHEET FOR ADDITIONAL INFORMATION.

ELECTRICAL SYMBOL LIST		
SYMBOL:	TAG:	DESCRIPTION:
(GB)	GB	GROUND BUS
(IBT)	IBT	INTERSYSTEM BONDING TERMINATION
(ECONN)	ECONN	ELECTRICAL CONNECTION
(JB)	JB	JUNCTION BOX
(FB-#)	FB-#	FLOOR POKE-THRU - DUPLEX RECEPTACLE
(FB-#)	FB-#	FLOOR POKE-THRU - DUAL COMPARTMENT
(FB-#)	FB-#	FLOOR BOX - MULTI SERVICE
(F-SV)	F-SV	FLOOR - SERVICE FITTING
(RI-TV)	RI-TV	TV ANTENNA OUTLET ROUGH-IN
(WM-#)	WM-#	MULTI OUTLET SYSTEM
(ELECTRICAL WIREWAY w/ DEVICES SHOWN)		ELECTRICAL WIREWAY w/ DEVICES SHOWN
(PANEL-###)	PANEL-###	PANELBOARD - RECESS MOUNT
(PANEL-###)	PANEL-###	PANELBOARD - SURFACE MOUNT
(MX-#/MS-# /CB-#/CS-#)		MANUAL SWITCH / STARTER / COMBINATION STARTER/ CIRCUIT BREAKER.
(DS-#)	DS-#	DISCONNECT

ELECTRICAL SYMBOL LIST		
SYMBOL:	TAG:	DESCRIPTION:
(REC-DUP)	REC-DUP	DUPLEX RECEPTACLE, 125V
(REC-DUP-GFI)	REC-DUP-GFI	DUPLEX GFI RECEPTACLE, 125V
(REC-USB)	REC-USB	DUPLEX RECEPTACLE, USB CHARGING
(REC-SIM-520R)	REC-SIM-520R	SIMPLEX RECEPTACLE, 125V
(REC-SIM-530R)	REC-SIM-530R	RECEPTACLE, 125V
(REC-SIM-550R)	REC-SIM-550R	RECEPTACLE 125V, 50A, 125V
(REC-SIM-620R)	REC-SIM-620R	RECEPTACLE, 6-20R, 250V
(REC-SIM-630R)	REC-SIM-630R	RECEPTACLE, 6-30R, 250V
(REC-SIM-650R)	REC-SIM-650R	RECEPTACLE, 6-50R, 250V
(REC-SIM-1420R)	REC-SIM-1420R	RECEPTACLE, 14-20R, 125/250V
(REC-SIM-1430R)	REC-SIM-1430R	RECEPTACLE, 14-30R, 125/250V
(REC-SIM-1450R)	REC-SIM-1450R	RECEPTACLE, 14-50R, 125/250V
(REC-SIM-L520R)	REC-SIM-L520R	RECEPTACLE, LOCKING TYPE, L5-20R, 125V
(REC-SIM-L530R)	REC-SIM-L530R	RECEPTACLE, LOCKING TYPE, L5-30R, 125V
(REC-SIM-L620R)	REC-SIM-L620R	RECEPTACLE, LOCKING L6-20R, 250V
(REC-SIM-L630R)	REC-SIM-L630R	RECEPTACLE, LOCKING L6-30R, 250V
(REC-SIM-L1420R)	REC-SIM-L1420R	RECEPTACLE, LOCKING L14-20R, 125/250V
(REC-SIM-L1430R)	REC-SIM-L1430R	RECEPTACLE, LOCKING L14-30R, 125/250V
(REC-TAMP)	REC-TAMP	DUPLEX RECEPTACLE, TAMPER RESISTANT, 125V
(REC-TAMP-GFI)	REC-TAMP-GFI	GFI DUPLEX RECEPTACLE, TAMPER RESISTANT, 125V
(REC-TAMP-QUAD)	REC-TAMP-QUAD	QUAD RECEPTACLE, TAMPER RESISTANT, 125V
(REC-QUAD)	REC-QUAD	QUAD RECEPTACLE, 125V
(REC-QUAD-GFI)	REC-QUAD-GFI	QUAD GFI RECEPTACLE, 125V
(REC-QUAD-USB)	REC-QUAD-USB	QUAD RECEPTACLE, USB 125V
(PP#)	PP#	POWER POLE



ELECTRICAL SYMBOL LIST			
SYMBOL:	TAG:	SPEC SECTION:	DESCRIPTION:
(LUMINAIRE)			LINEAR LUMINAIRE
(TROFFER)			TROFFER
(WALL SCONCE LUMINAIRE)			WALL SCONCE LUMINAIRE
(DOWNLIGHT LUMINAIRE)			DOWNLIGHT LUMINAIRE
(AIMABLE OR WALL WASH LUMINAIRE)			AIMABLE OR WALL WASH LUMINAIRE
(INDUSTRIAL LUMINAIRE)			INDUSTRIAL LUMINAIRE
(WALL BRACKET LUMINAIRE)			WALL BRACKET LUMINAIRE
(POLE MOUNTED LUMINAIRE)			POLE MOUNTED LUMINAIRE
(SINGLE FACE EXIT SIGN)			SINGLE FACE EXIT SIGN
(DOUBLE FACE EXIT SIGN)			DOUBLE FACE EXIT SIGN
(WALL/CEILING EMERGENCY EXIT SIGN)			WALL/CEILING EMERGENCY EXIT SIGN
(EMERGENCY UNIT)			EMERGENCY UNIT

ELECTRICAL SYMBOL LIST		
SYMBOL:	TAG:	DESCRIPTION:
(S)	SW-1P	SWITCH - SINGLE POLE
(S <sub>M</sub> )	SW-1P-M	SWITCH - MOMENTARY CONTACT
(S <sub>2</sub> )	SW-2P	SWITCH - TWO POLE
(S <sub>3</sub> )	SW-3W	SWITCH - THREE WAY
(S <sub>4</sub> )	SW-4W	SWITCH - FOUR WAY
(D <sub>D</sub> )	SW-D-LED	DIMMER - LED, COMPATIBLE WITH FIXTURE DRIVER
(D <sub>D3</sub> )	SW-D3-LED	DIMMER - LED - 3-WAY, COMPATIBLE WITH FIXTURE DRIVER
(OC <sub>D</sub> )	SW-OC-D-W	OCCUPANCY SENSOR - DUAL TECHNOLOGY - WALL MOUNTED
(S <sub>O2</sub> )	SW-OC-P-O2	SWITCH - OCCUPANCY SENSOR AND DUAL SWITCH
(OC <sub>P</sub> )	SW-OC-P-P	OCCUPANCY SENSOR - PASSIVE INFRARED 90 DEGREE COVERAGE
(OC <sub>P2</sub> )	SW-OC-P-P2	OCCUPANCY SENSOR - PASSIVE INFRARED 100 DEGREE COVERAGE
(OC <sub>P</sub> )	SW-OC-P-W	OCCUPANCY SENSOR - PASSIVE INFRARED - WALL MOUNTED
(OC <sub>U</sub> )	SW-OC-U	OCCUPANCY SENSOR - ULTRASONIC 360 DEGREE COVERAGE
(OC <sub>U2</sub> )	SW-OC-U2	OCCUPANCY SENSOR - ULTRASONIC 35X30° HAND MOTION COVERAGE
(OC <sub>U</sub> A)	SW-OC-U-A	OCCUPANCY SENSOR - ULTRASONIC TWO SIDED CORRIDOR COVERAGE
(OC <sub>U</sub> )	SW-OC-U-W	OCCUPANCY SENSOR - ULTRASONIC - WALL MOUNTED
(SW)	SW	WALL CONTROL STATION
(TC)	TC#	TIME SWITCH
(#B#P)	SW-LCS	DIMMER CONTROL STATION WITH FADERS
(S <sub>LV</sub> )	SW-LV	LOW-VOLTAGE CONTROL SWITCH
(S <sub>O</sub> )	SW-OC-P-O	WATTSTOPPER DSW-301 SERIES DUAL TECHNOLOGY WALL SWITCH WITH MOTION SENSOR
(D <sub>O</sub> )	SW-OD	WATTSTOPPER DW-311 SERIES 0-10V DIMMABLE WALL SWITCH WITH DUAL TECHNOLOGY MOTION SENSOR
(S <sub>T</sub> )	SW-1P-ADJ	WATTSTOPPER TS-400 SERIES DIGITAL TIME SWITCH
(#B#XX)	SW-DCS	WATTSTOPPER DIGITAL LIGHTING MANAGEMENT CONTROL STATION KEYPAD WITH PROGRAMMABLE FUNCTION BUTTONS. REFER TO DETAILS FOR ADDITIONAL REQUIREMENTS. XX INDICATES TYPE: S1: ONE BUTTON KEYPAD S2: TWO BUTTON KEYPAD S3: THREE BUTTON KEYPAD S4: FOUR BUTTON KEYPAD S5: FIVE BUTTON KEYPAD S8: EIGHT BUTTON KEYPAD D1: ONE ROCKER BUTTON KEYPAD
(R <sub>X</sub> )		WATTSTOPPER DIGITAL LIGHTING MANAGEMENT ROOM CONTROLLER. REFER TO DETAILS FOR SYSTEM INTERCONNECTION REQUIREMENTS. X INDICATES TYPE: A. ONE RELAY SWITCHING CONTROLLER: LMR-102 B. TWO RELAY SWITCHING CONTROLLER: LMR-211 C. ONE RELAY SWITCHING OR 0-10V DIMMING CONTROLLER: LMR-212 D. TWO RELAY SWITCHING OR 0-10V DIMMING CONTROLLER: LMR-212 E. THREE RELAY SWITCHING OR 0-10V DIMMING CONTROLLER: LMR-213
(R <sub>BMS</sub> )		WATTSTOPPER DIGITAL LIGHTING MANAGEMENT INPUT/OUTPUT INTERFACE FOR BMS CONTROL OF LIGHTING. PROVIDE ALL LOW VOLTAGE CABLING AS REQUIRED. LM10-101.
(OC <sub>D</sub> )	SW-OC-D	WATTSTOPPER DIGITAL LIGHTING MANAGEMENT LMDC-100 SERIES DUAL TECHNOLOGY CEILING MOUNT OCCUPANCY SENSOR. OCCUPANCY SENSOR SHALL TURN OFF LIGHTS AFTER 20 MINUTES OF INACTIVITY. PROVIDE ALL LOW VOLTAGE CABLING AS REQUIRED.
(S <sub>WLS</sub> )	SWLS	WATTSTOPPER DIGITAL LIGHTING MANAGEMENT LMLS-105 SERIES PHOTOCELL. PROVIDE ALL LOW VOLTAGE CABLING AS REQUIRED.
(ALCR)		WATTSTOPPER ELCLU-200 SERIES EMERGENCY LIGHTING CONTROL UNIT. UPON LOSS OF NORMAL POWER, EMERGENCY LIGHTING SHALL TURN ON REGARDLESS OF SWITCH POSITION.

ELECTRICAL SYMBOL LIST		
SYMBOL:	TAG:	DESCRIPTION:
(FA-110)	FA-110	FIRE FIGHTERS PHONE
(FA-120)	FA-120	FIRE ALARM SMOKE DETECTOR - CEILING MOUNTED
(FA-122)	FA-122	FIRE ALARM DUCT SMOKE DETECTOR
(FA-123)	FA-123	FIRE ALARM IN DUCT SMOKE DETECTOR
(FA-130)	FA-130	FIRE ALARM MANUAL PULL STATION
(FA-140)	FA-140	FIRE ALARM HEAT DETECTOR
(FA-150)	FA-150	FIRE ALARM CARBON MONOXIDE/HEAT/SMOKE DETECTOR
(FA-160)	FA-160	FIRE ALARM ADDRESSABLE MONITOR MODULE
(FA-161)	FA-161	FIRE ALARM RELAY
(FA-170)	FA-170	SMOKE DETECTOR - STAND ALONE
(FA-171)	FA-171	SMOKE DETECTOR - STAND ALONE 177 CANDELA
(FA-200)	FA-200	FIRE ALARM VISUAL NOTIFICATION DEVICE - WALL MOUNTED
(FA-201)	FA-201	FIRE ALARM VISUAL NOTIFICATION DEVICE - CEILING MOUNTED
(FA-202)	FA-202	EMERGENCY NOTIFICATION - VISUAL - WALL MOUNTED
(FA-210)	FA-210	FIRE ALARM AUDIO NOTIFICATION DEVICE - WALL MOUNTED
(FA-211)	FA-211	FIRE ALARM AUDIO/VISUAL NOTIFICATION DEVICE - WALL MOUNTED
(FA-220)	FA-220	EMERGENCY NOTIFICATION - AUDIO/VISUAL - WALL MOUNTED
(FA-221)	FA-221	EMERGENCY NOTIFICATION - AUDIO/VISUAL - CEILING MOUNTED
(FA-222)	FA-222	EMERGENCY NOTIFICATION - VISUAL ONLY - CEILING MOUNTED
(FA-230)	FA-230	FIRE ALARM AUDIO NOTIFICATION DEVICE - CEILING MOUNTED
(FA-231)	FA-231	FIRE ALARM AUDIO/VISUAL NOTIFICATION DEVICE - CEILING MOUNTED
(FA-232)	FA-232	FIRE ALARM CM LOUD SPEAKER
(FA-233)	FA-233	FIRE ALARM AUDIO NOTIFICATION DEVICE - WALL MOUNTED - MINI-HORN
(FA-242)	FA-242	FIRE ALARM REMOTE INDICATOR AND TEST SWITCH
(FA-241)	FA-241	FIRE ALARM REMOTE INDICATOR
(FA-250)	FA-250	FIRE ALARM SMOKE DAMPER
(FA-251)	FA-251	SMOKE OR FIRE DAMPER CONTROLLER
(FA-253)	FA-253	FIRE ALARM HOISTWAY DAMPER SWITCH
(FA-254)	FA-254	FIRE ALARM SMOKE DAMPER WITH DUCT DETECTOR AND ADDRESSABLE RELAY
(FA-260)	FA-260	FIRE ALARM FLOW SWITCH TO MONITOR FIRE PROTECTION SYSTEM
(FA-261)	FA-261	FIRE ALARM MONITOR SWITCH TO MONITOR FIRE PROTECTION SYSTEM
(FA-262)	FA-262	FIRE ALARM POST INDICATOR VALVE CONNECTION
(FA-263)	FA-263	FIRE ALARM ELECTRONIC BELL FOR SPRINKLER SYSTEM
(FA-270)	FA-270	FIRE ALARM ELECTROMAGNETIC DOOR HOLD DEVICE
(FA-272)	FA-272	FIRE ALARM HOLD OPEN OVERRIDE CONNECTION
(FA-280)	FA-280	ISOLATION MODULE
(DB)	DB	DOOR BELL
(HD)	HD	HAND DRYER
(PP)	PP	PUSH PAD
(PB-EPO)		"EMERGENCY POWER OFF" PUSHBUTTON
(NC-D-C)	NC-D-C	NURSE CALL DOME LIGHT (CEILING)
(NC-NE-W)	NC-NE-W	NURSE CALL EMERGENCY CALL STATION (WALL)

ELECTRICAL ABBREVIATION KEY	
ABBR:	DESCRIPTION:
AFF	ABOVE FINISHED FLOOR
C	CONDUIT
EM	INDICATES LIGHT OR DEVICE CONNECTED TO EMERGENCY POWER OR FURNISHED WITH A BATTERY PACK CONNECTED TO A NON-SWITCHED HOT WIRE
GFI	GROUND FAULT INTERRUPTER
N.C.	NORMALLY CLOSED
NIC	NOT IN CONTRACT
N.O.	NORMALLY OPEN
RL	EXISTING DEVICE OR LIGHT RELOCATED
SV	SOLENOID VALVE
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE

LUMINAIRE SYMBOL KEY	
SYMBOL:	DESCRIPTION:
(□)	NORMAL BRANCH LUMINAIRE
(○)	CRITICAL BRANCH LUMINAIRE
(◐)	EMERGENCY LIFE SAFETY BRANCH LUMINAIRE



ACI  
BOLAND  
ARCHITECTS

1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

MEP CONSULTANT


IMEG CORP.  
1600 BALTIMORE ST, SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437

Saint Luke's  
East Hospital

ROCKHILL ORTHOPAEDIC X-RAY RENOVATION  
120 NE SAINT LUKE'S BLVD., SUITE 200  
LEE'S SUMMIT MO 64086

Date 07/07/21  
Job Number 3-21014  
Drawn By MSA  
Checked By BEH

Revision  
Number Date Description




E000

© 2021 ACI/BOLAND, Inc

ELECTRICAL SYMBOL LISTS



7/2/2021 1:58:17 PM



**LMRC-211**  
SEQUENCE OF OPERATION: IN THIS CONFIGURATION THE LMRC-211 DEFAULTS TO MANUAL-ON/AUTOMATIC OFF.


**LMRC-212**  
SEQUENCE OF OPERATION: IN THIS CONFIGURATION THE LMRC-212 DEFAULTS TO MULTI-LEVEL AUTOMATIC-ON/AUTOMATIC OFF. LOAD (A) TURNS ON AUTOMATICALLY AND LOAD (B) DEFAULTS TO MANUAL-ON CONTROL. BOTH LOADS TURN AUTOMATICALLY OFF.

**LMRC-213**  
SEQUENCE OF OPERATION: IN THIS CONFIGURATION THE LMRC-213 SEQUENCE OF OPERATION. DEFAULTS TO MULTI-LEVEL AUTOMATIC-ON/AUTOMATIC OFF. LOAD (A) ON THE LMRC-213 TURNS ON AUTOMATICALLY. WHILE LOAD (B) AND (C) DEFAULTS ENHANCED ROOM TO MANUAL-ON CONTROL. ALL RELAYS TURN OFF AUTOMATICALLY.

**NOTE:**  
-FINISH WITH TWO (2) LMCT-100 DIGITAL WIRELESS CONFIGURATION TOOLS.  
-PROVIDE COMMISSIONING AND TRAINING FOR ALL INSTALLATIONS.  
-PROVIDE ENGRAVING FOR BUTTONS ON ALL INSTALLATIONS.  
-ALL SHIELDING FOR OCCUPANCY SENSORS SHALL BE TURNED OVER TO OWNER.

### DETAIL OF LMRC-211, LMRC-212 AND LMRC-213 ROOM CONTROLLER CABLING

C:\Revit Local Files\MEPT21\_21001664\_00\_SLE Rockhill X-ray\_C\_Brent.W.Cump.vrt



- RISER KEYNOTES:**
- AS-BUILT DRAWING INDICATES EXISTING DISTRIBUTION PANEL DP-E2-10-XRAY HAS TWO (2) SPARE FUSIBLE 100AMP, 3-POLE DISCONNECT SWITCHES AVAILABLE FOR NEW WORK. EXISTING PANEL IS RATED 400AMP MAIN SWITCH, 277/480 VOLT, 3PH, 4 WIRE. VERIFY EXISTING CONDITIONS.
  - ROUTE TO 80AMP, 3-POLE MAIN DISCONNECT IN XRAY EXAM ROOM 2E51. PROVIDE 4 #2 W, 1 #2 GROUND IN 2" CONDUIT. (G.E. XRAY).
  - ROUTE TO 100AMP, 3-POLE MAIN DISCONNECT IN XRAY EXAM ROOM 2E51. PROVIDE 4 #10 W, 1 #10 GROUND IN 2.5" CONDUIT. (SAMSUNG XRAY).
  - PROVIDE THREE (3) - 100AMP FUSES IN EXISTING 100AMP, 3-POLE 'SPARE' FUSIBLE SWITCH. LABEL SWITCH XRAY 2E51.
  - PROVIDE THREE (3) - 80AMP FUSES IN EXISTING 100AMP, 3-POLE 'SPARE' FUSIBLE SWITCH. LABEL SWITCH XRAY 2E83.
  - EXISTING PANEL IS UTILIZED IN NEW WORK. TRACE AND VERIFY BRANCH CIRCUITS AS REQUIRED.
  - VERIFY FUSE, CONDUIT AND WIRE SIZING WITH FINAL XRAY VENDOR DRAWING REQUIREMENTS.

### PARTIAL ELECTRICAL RISER DIAGRAM

### LUMINAIRE SCHEDULE

<b>(DESC) DOOR:</b> FA - FLAT ALUMINUM FS - FLAT STEEL RA - REGRESSED ALUMINUM RS - REGRESSED STEEL <b>FINISH:</b> PAF - PAINT AFTER FABRICATION CFSA - COLOR-FINISH SELECTION BY ARCHITECT	<b>DISTRIBUTION:</b> II - ANSIES TYPE 2 DISTRIBUTION III - ANSIES TYPE 3 DISTRIBUTION IV - ANSIES TYPE 4 DISTRIBUTION V - ANSIES TYPE 5 DISTRIBUTION	<b>BEAMWIDTH:</b> NSP - VERY NARROW SPOT SP - SPOT MD - MEDIUM WD - WIDE VWD - VERY WIDE WW - WALL WASH	<b>(L) LENS/OUVER:</b> A - 125° ACRYLIC B - BAFFLE/OUVER C - CLEAR ALZAK F - FROSTED ACRYLIC G - TEMPERED GLASS K - KSH12 125° ACRYLIC	K19 - KSH19 156° ACRYLIC N - MATTE DIFFUSE CLEAR NONE P - POLYCARBONATE SS - SEMI-SPECULAR CLEAR O - OTHER (SEE DESCRIPTION) [DESIGN SPECIFIC BLANKS]
<b>(TYPE) LIGHT SOURCE TECHNOLOGY:</b> DL - DYNAMIC TUNABLE LED LED - LIGHT EMITTING DIODE OLED - ORGANIC LED RGB - COLOR CHANGING LED RGBW - COLOR CHANGING + AMBER LED RGBW - COLOR CHANGING + WHITE LED RLED - RETROFIT LED TLED - TUBULAR LED LAMP WLED - WARM DIM LED O - OTHER (SEE DESCRIPTION)	FL - FLUORESCENT CF - COMPACT FLUORESCENT HL - HALOGEN HIR - HALOGEN INFRARED IN - INCANDESCENT HS - HIGH PRESSURE SODIUM MH - METAL HALIDE SMH - SUPER METAL HALIDE FSMH - PULSE START METAL HALIDE CMH - CERAMIC METAL HALIDE XL - EXTENDED LIFE FLUORESCENT XLP - EXTENDED LIFE & OUTPUT FLUORESCENT	CC - COLD CATHODE IND - INDUCTION O - OTHER (SEE DESC)	<b>(MTG) MOUNTING:</b> CL - CEILING SURFACE CV - COVE FR - FLANGED RECESSED O - OTHER (SEE DESCRIPTION) P - PERIMETER <b>(WATT) PER:</b> FIX - FIXTURE, FT - FOOT, LAMP	FL - POLE RE - RECESSED SU - SUSPENDED SU - SURFACE UC - UNDER CABINET WL - WALL
<b>(TYPE) BALLAST/DRIVER:</b> HBF - BALLAST FACTOR D-10V - 0-10V DIMMING TO 1% DALI - DIGITAL ADDRESSABLE DMX - DIGITAL MULTIPLEX ELV - ELECTRONIC ELV - ELECTRONIC LOW VOLTAGE EM - EMERGENCY BATTERY				

ITEM	DESCRIPTION	L/L	MTG	DIMENSIONS				WATT	LIGHT SOURCE TECHNOLOGY	BALLAST/DRIVER	APPROVED MANUFACTURER
				L	W	H	DIA.				
A	SHALLOW PLENUM TROFFER WITH DIFFUSE LINEAR RIBBED ACRYLIC LENS IN CENTER. WHITE FINISH. STEEL HOUSING.	F	RE	4'-0"	2'-0"	2"		45 W	FIX	LED 1	WILLIAMS - PT SERIES
B	SHALLOW PLENUM TROFFER WITH DIFFUSE LINEAR RIBBED ACRYLIC LENS IN CENTER. WHITE FINISH. STEEL HOUSING.	F	RE	2'-0"	2'-0"	2"		29 W	FIX	LED 1	WILLIAMS - PT SERIES
D	OPEN RECESSED DOWNLIGHT, CLEAR SEMI-SPECULAR PARABOLIC SELF FLANGE REFLECTOR, DAMP LABEL, WIDE DISTRIB. SPRING-RETENTION REFLECTOR, TOP LENS	O	RE	6 1/2"	6"	16 W		16 W	FIX	LED 1	WILLIAMS - 6DR
X	LED "IN USE" SIGN, CAST ALUMINUM HOUSING WITH RED LETTERING, WHITE FINISH. PROVIDE NECESSARY HARDWARE FOR CEILING OR WALL MOUNTING.	O	CL	11"	2"	8"		2 W	FIX	LED 1	PROVIDE FROM XRAY VENDOR

### ELECTRICAL GENERAL NOTES:

- REFER TO DRAWINGS CONTAINING ELECTRICAL SCHEDULES. PERMANENT NAMEPLATE SHALL MATCH FINAL EQUIPMENT NOMENCLATURE. NOT ELECTRICAL EQUIPMENT TAG NAME. REFER TO SPECIFICATIONS.
- "N.I." INDICATES LUMINAIRE IS UNSWITCHED FOR NIGHT LIGHT.
- "SIE" INDICATES LUMINAIRE IS SWITCHED/CONTROLLED DURING NORMAL OPERATION AND OPERATES FROM EMERGENCY CIRCUIT UPON LOSS OF POWER.
- SHADED LUMINAIRE OR DEVICE INDICATES LUMINAIRE OR DEVICE IS CONNECTED TO AN EMERGENCY CIRCUIT.
- REFER TO THIS SHEET FOR LIGHTING CONTROL DETAILS.
- REFER TO SHEET E2 FOR LUMINAIRE SCHEDULE.
- (E) PUSH BUTTON REFERS TO SCENE QUANTITY. CONTROL STATION SHALL BE CAPABLE OF RAISE/LOWER AND SWITCHING ON/OFF FOR MULTIPLE SCENES AS INDICATED ON SHEETS. COORDINATE QUANTITIES OF BUTTONS FOR CONTROL STATIONS WITH LIGHTING CONTROL MANUFACTURER. REFER TO DETAILS THIS SHEET.
- VACUANCY/OCCUPANCY SENSOR LAYOUT. SENSORS ARE SHOWN ON THE PLANS FOR DESIGN INTENT AND MAY NOT REPRESENT EVERY DEVICE. PROVIDE MANUFACTURER SPECIFIC FLOOR PLAN LAYOUTS, ORIENTATION, AND COVERAGE AREA OF EACH CONTROL DEVICE, SENSOR, AND CONTROLLER/INTERFACE. AREAS REQUIRING MULTIPLE SENSOR DEVICES FOR APPROPRIATE COVERAGE, SUBMIT SPECIFIC MANUFACTURER-APPROVED SENSOR LAYOUT AS AN OVERLAY DIRECTLY ON THE PROJECT DRAWINGS, EITHER IN PRINT OR APPROVED ELECTRONIC FORM.

**LUMINAIRE KEY:**  
F1 = FIXTURE TAG  
1 = CIRCUIT NUMBER  
a = SWITCH DESIGNATION  
NL = SUBSCRIPT (IF APPLICABLE)  
Z = ZONE DESIGNATION

"IF LABEL IS ORIENTED HORIZONTALLY A SLASH WILL SEPARATE THIS INFORMATION. EX: F11 / a / NL"

**DEVICE KEY:**  
A = INFORMATION (IF APPLICABLE)  
1 = CIRCUIT NUMBER

"IF LABEL IS ORIENTED HORIZONTALLY A SLASH WILL SEPARATE THIS INFORMATION. EX: A / 1"

**ELECTRICAL MOUNTING SUBSCRIPT KEY:**  
MOUNT AT 48" TO CENTERLINE ABOVE COUNTER OR BACKSPLASH  
C MOUNT AT CEILING  
H MOUNT ORIENTED HORIZONTALLY  
L MOUNT IN CASEWORK  
M MOUNT IN MODULAR FURNITURE  
R MOUNT IN SURFACE RACEWAY  
EWC ELECTRIC WATER COOLER

### ELECTRICAL INSTALLATION NOTES:

- THE COMPLETE INSTALLATION SHALL BE IN ACCORDANCE WITH THE ADA STANDARDS FOR ACCESSIBLE DESIGN. REFER TO THE ADA GUIDELINES FOR ALL CONFIGURATION DETAILS ON THIS PAGE FOR ADDITIONAL INFORMATION.
- CIRCUIT NUMBERS ARE SHOWN FOR CIRCUIT IDENTIFICATION. CIRCUITING SHALL AGREE WITH NUMBERING ON THE PANEL PROVIDED. COMMON NEUTRALS MAY NOT BE USED FOR BRANCH CIRCUITS. BALANCE THE LOAD ON PANEL AS EVENLY AS POSSIBLE BETWEEN EACH PHASE.
- EMERGENCY LIFE SAFETY AND CRITICAL EQUIPMENT** BRANCH WIRING FOR FEEDERS AND BRANCH CIRCUITS SHALL BE ROUTED IN SEPARATE RACEWAY, JUNCTION BOXES, PULL BOXES, AND CABINETS. WIRING FOR EACH BRANCH SHALL BE INDEPENDENT FROM OTHER BRANCHES, INCLUDING THE NORMAL BRANCH.
- FLUSH MOUNT ALL LIGHTING CONTROL DEVICES AT +42" FROM FLOOR (CENTERLINE DIMENSION), EXCEPT WHERE OTHERWISE NOTED. DEVICES MAY BE SURFACE MOUNTED WHEN CONDUIT IS SPECIFICALLY EXPOSED.
- FLUSH MOUNT ALL DUPLEX RECEPTACLES AND TECHNOLOGY OUTLETS AT +18" FROM FLOOR (CENTERLINE DIMENSION), EXCEPT WHERE OTHERWISE NOTED. RECEPTACLES AND OUTLETS MAY BE SURFACE MOUNTED WHEN CONDUIT IS SPECIFICALLY EXPOSED.
- ALL MATERIALS USED TO SEAL PENETRATIONS OF FIRE RATED WALLS AND FLOORS SHALL BE TESTED AND CERTIFIED AS A SYSTEM PER ASTM E814 STANDARDS FOR FIRE TESTS OF THROUGH-PENETRATION FIRESTOPPING. REFER TO ARCHITECTURAL SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS SPECIFIC TO FIRESTOPPING.
- CONNECTION FOR ELECTRIC WATER COOLERS (EWC) SHALL BE A JUNCTION BOX CONCEALED BEHIND WATER COOLER ACCESS PLATE OR BE A GFI RECEPTACLE LOCATED DIRECTLY BELOW AND CENTERED ON EWC. CONTRACTOR SHALL VERIFY TYPE OF EWC TO BE INSTALLED.
- MOUNT ALL FIRE ALARM PULL STATIONS AT +42" FROM FLOOR (CENTERLINE DIMENSION) EXCEPT WHERE OTHERWISE NOTED.
- INSTALL ALL WALL MOUNTED FIRE ALARM NOTIFICATION DEVICES AT 90" ABOVE FINISHED FLOOR OR 6" BELOW THE CEILING, WHICHEVER IS LOWER, EXCEPT WHERE OTHERWISE NOTED. HEIGHT SHALL BE MEASURED TO THE TOP OF THE DEVICE.
- CONTRACTOR SHALL COORDINATE THE LOCATION OF ALL CEILING MOUNTED DEVICES AND EQUIPMENT WITH LUMINAIRES, SPRINKLER, AND CEILING DIFFUSERS. CENTER ALL DEVICES IN CEILING TILE PATTERN. SMOKE DETECTORS AND OCCUPANCY/VACANCY SENSORS SHALL BE LOCATED NO CLOSER THAN 3 FEET TO AN AIR SUPPLY DIFFUSER OR RETURN GRILLE.
- CONTRACTOR SHALL VERIFY ALL FURNITURE, MODULAR FURNITURE, AND EQUIPMENT LOCATIONS WITH ARCHITECTURAL PLANS, ELEVATIONS, AND REVIEWED SHOP DRAWINGS. PRIOR TO MAKING THE ACTUAL ELECTRICAL INSTALLATION, THIS CONTRACTOR SHALL ADJUST RECEPTACLES, OUTLETS, OR CONNECTION LOCATIONS TO ACCOMMODATE FURNITURE AND/OR EQUIPMENT.
- ELECTRICAL AND TECHNOLOGY EQUIPMENT SHALL BE MOUNTED TO AVOID IMPEDANCE OF OPERATION OF AND/OR ACCESS TO ELECTRICAL AND MECHANICAL EQUIPMENT. ALL MOUNTING OF ELECTRICAL AND TELECOMMUNICATIONS EQUIPMENT, ON EQUIPMENT SUPPLIED BY ANOTHER CONTRACTOR, SHALL BE APPROVED IN ADVANCE BY THE OTHER CONTRACTOR.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ALL OPENINGS REQUIRED IN WALLS. ALL OPENINGS SHALL BE REPAIRED TO MATCH EXISTING BY A QUALIFIED CONTRACTOR AT THE EXPENSE OF THIS CONTRACTOR. ALL CONDUITS THROUGH WALLS SHALL BE GROUDED OR SEALED INTO OPENINGS.
- ALL WELDING SHALL BE ACCORDING TO AMERICAN WELDING SOCIETY STANDARDS. CONTRACTOR SHALL FURNISH TO THE ARCHITECT/ENGINEER CERTIFICATES QUALIFYING EACH WELDER, PRIOR TO START OF WORK. THE ARCHITECT/ENGINEER RESERVES THE RIGHT TO REQUIRE QUALIFYING DEMONSTRATION, AT THE CONTRACTOR'S EXPENSE, OF ANY WELDERS ASSIGNED TO THE JOB.
- CONTRACTOR SHALL REMOVE AND REINSTALL ALL CEILING TILES AS REQUIRED FOR THE EXECUTION OF ELECTRICAL WORK. CONTRACTOR SHALL REPLACE CEILING TILES WITH IDENTICAL MATERIALS WHERE DAMAGED BY THIS CONTRACTOR.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLAN, ELECTRICAL, TECHNOLOGY AUDIOVISUAL, AND OTHER ELECTRICAL PLANS FOR EXACT LOCATIONS OF ALL CEILING MOUNTED DEVICES, OTHER THAN SPRINKLERS.
- ALL EXISTING BRANCH CIRCUITS REQUIRE FIELD VERIFICATION AND SHALL BE TRACED FROM SOURCE PANEL TO DEVICES. LIGHT FIXTURES AND EQUIPMENT REQUIRED TO REMAIN OR RELOCATE. UTILIZE INFORMATION TO PROVIDE ACCURATE UPDATED TYPE-WRITTEN PANEL SCHEDULES.
- ALL ELECTRICAL WORK SHALL COMPLY WITH NEC 2017 ARTICLE 517 FOR HEALTHCARE FACILITIES.

### ELECTRICAL PHASING NOTES:

- THESE NOTES APPLY TO ALL ELECTRICAL SHEETS AND TRADES, INCLUDING BUT NOT LIMITED TO LIGHTING, POWER, AND SYSTEMS.
- REFER TO ARCHITECTURAL DRAWINGS FOR GENERAL DESCRIPTION OF PHASES. REFER TO CONSTRUCTION MANAGERS/GENERAL CONTRACTORS/ARCHITECTS INSTRUCTIONS FOR MORE DETAILS AND PHASING SCHEDULES AND FOR CONCURRENT WORK. MECHANICAL, ELECTRICAL AND TECHNOLOGY DRAWINGS DEPICT THE INTENT OF THE FINAL DESIGN. THE MECHANICAL, ELECTRICAL, AND TECHNOLOGY DRAWINGS DO NOT DEPICT THE MEANS AND METHODS TO MEET THE REQUIREMENTS OF THE PHASING CRITERIA.
  - REVIEW PROJECT PHASING PLANS TO COORDINATE DEMOLITION WORK, OUTAGES, ETC. WITH AFFECTED ADJACENT AREAS.
  - PROVIDE TEMPORARY LIGHTING, POWER, SYSTEMS, ETC. AS NEEDED TO MAINTAIN SERVICE TO ALL AREAS DURING ALL PHASES OF PROJECT.
  - INSTALL TEMPORARY LIGHTING, CIRCUITS, ETC. AS NECESSARY TO KEEP ALL OCCUPIED SPACES OPERATIONAL THROUGHOUT ALL PHASES OF THE PROJECT.
  - PHASE DEMOLITION WORK TO MINIMIZE DOWNTIME.

### TYPICAL NEW CONSTRUCTION:

- HALF-SHADED FIXTURES INDICATE EMERGENCY LUMINAIRES THAT ARE TO BE CONNECTED VIA AN EMERGENCY TRANSFER DEVICE (ALCR) TO TURN LIGHTS ON UPON LOSS OF POWER. THE THIRD LEG OF THE ETD IS CONNECTED TO THE EMERGENCY LIGHTING PANEL. WHERE LUMINAIRE QUANTITIES OR LAYOUT DIFFER BETWEEN ELECTRICAL LIGHTING PLANS AND ARCHITECTURAL REFLECTED CEILING PLANS, HIGHER QUANTITY SHALL TAKE PRECEDENCE. CONTRACTOR SHALL CONFIRM QUANTITY AND LAYOUT WITH DESIGN TEAM.
- #B PUSH BUTTON REFERS TO SCENE QUANTITY. COORDINATE NUMBER OF BUTTONS FOR CONTROL STATIONS WITH LIGHTING CONTROL MANUFACTURER. CONTROL SHALL BE CAPABLE OF DIMMING UP/DOWN AND SWITCHING ON/OFF FOR MULTIPLE ZONES AS INDICATED.
- COORDINATE LUMINAIRE IN MECHANICAL ROOMS WITH DUCTWORK, PIPING AND ANY MECHANICAL EQUIPMENT. PROVIDE LUMINAIRE WITH CHAINS OR HANGAR KIT WHERE REQUIRED. BOTTOM OF FIXTURE TO ALIGN WITH BOTTOM OF NEAREST BEAM TRUSS. COORDINATE MOUNTING PRIOR TO ORDERING LUMINAIRES.

RELEASE FOR CONSTRUCTION  
ACI/BOLAND ARCHITECTS  
BRUCE E. HART, ENGINEER  
LICENSE - MISSOURI #E-22817

**ACI/BOLAND ARCHITECTS**  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

**MEP CONSULTANT**  
IMEG CORP.  
1600 BALTIMORE ST, SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437

**Saint Luke's East Hospital**  
ROCKHILL ORTHOPAEDIC X-RAY RENOVATION  
120 NE SAINT LUKE'S BLVD., SUITE 200  
LEE'S SUMMIT MO 64086

Date	07/07/21
Job Number	3-21014
Drawn By	MSA
Checked By	BEH

Revision	Description
Number	Date

**IMEG**  
1600 BALTIMORE SUITE 300  
KANSAS CITY, MO 64108  
www.imegcorp.com  
PROJECT # 16101664-00  
Missouri State Certificate of Authority E-2017008530  
IMEG CORP. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
© 2021 IMEG CORP.  
REFERENCE SCALE IN INCHES  
1" = 1'





**1 SECOND FLOOR PLAN**  
 1/16" = 1'-0"


**Saint Luke's**  
**East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD. SUITE 200**  
**LEE'S SUMMIT MO 64086**

Date 07/07/21  
 Job Number 3-21014  
 Drawn By MSA  
 Checked By BEH

Revision  
 Number Date Description

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 21014-00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. SAID DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 0 1 2 3





- SHEET NOTES:**
1. REFER TO SHEETS E000 AND E001 FOR SYMBOLS AND ELECTRICAL GENERAL NOTES. NOT ALL NOTES MAY APPLY TO THIS SHEET.
  2. EXISTING LIGHTING BRANCH CIRCUITS ARE SERVED FROM 277VOLT NORMAL SOURCE PANELBOARD 'E2-1-HN'. REFER TO SHEET E002 FOR PANEL LOCATION.
  3. DEVICES AND LIGHTS TO BE DEMO'D ARE SHOWN DARK AND DASHED. ALL EXISTING TO REMAIN DEVICES AND LIGHTS ARE SHOWN LIGHTLY.
  4. NOT ALL DEVICES AND LIGHTS TO BE DEMO'D ARE SHOWN. CONTRACTOR SHALL COMPLETELY REMOVE ALL DEVICES AND LIGHTS NO LONGER REQUIRED TO REMAIN.

- KEYNOTES: (#)**
1. MAINTAIN EXISTING BRANCH CIRCUIT(S). ADAPT/EXTEND/MODIFY EXISTING CIRCUIT(S) FOR NEW WORK INDICATED. VERIFY EXISTING CONDITIONS.
  2. EXISTING BRANCH CIRCUITS WITHIN DESIGNATED ROOM TO REMAIN. VERIFY EXISTING CONDITIONS.

**1 SECOND FLOOR DEMOLITION - LIGHTING**  
1/4" = 1'-0"

RELEASE FOR CONSTRUCTION  
AS SHOWN ON DRAWING  
DEVELOPMENT SERVICES  
OF MISSOURI  
BRUCE ELDON, P.E.  
HART  
NUMBER  
2-2817  
PROFESSIONAL ENGINEER  
07-07-21  
Bruce E. Hart - Engineer  
License - Missouri #E-22817

**ACI  
BOLAND  
ARCHITECTS**

1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

**MEP CONSULTANT**  
**IMEG CORP.**  
1600 BALTIMORE ST, SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437

**Saint Luke's  
East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD. SUITE 200**  
**LEE'S SUMMIT MO 64086**


Date 07/07/21  
Job Number 3-21014  
Drawn By MSA  
Checked By BEH

Number	Date	Description

**IMEG**  
1600 BALTIMORE SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437  
www.imegcorp.com  
PROJECT # 2101484.00  
Missouri State Certificate of Authority E-201708530  
IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
© 2021 IMEG CORP.  
REFERENCE SCALE IN INCHES  
1" = 1'-0"

**E102**  
© 2021 ACI/BOLAND, Inc.  
SECOND FLOOR DEMOLITION -  
LIGHTING





**1** SECOND FLOOR DEMOLITION - POWER  
1/4" = 1'-0"

- SHEET NOTES:**
- REFER TO SHEET E000 AND E001 FOR SYMBOLS AND ELECTRICAL GENERAL NOTES. NOT ALL NOTES MAY APPLY TO THIS SHEET.
  - PROVIDE NEW BREAKERS TO MATCH WITH EXISTING PANEL RATINGS AND MATE WITH EXISTING SIZE, IF REQUIRED.
  - FOR PURPOSES OF VOLTAGE DROP, PROVIDE #10 WIRE FOR 120 VOLT BRANCH CIRCUIT HOMERUN BEYOND 70FT FROM SOURCE PANEL AND #8 WIRE FOR 120 VOLT BRANCH CIRCUIT HOMERUNS BEYOND 120FT FROM SOURCE PANEL.
  - UPON COMPLETION OF DEMOLITION WORK, CONFIRM QUANTITIES, SIZES, RATING AND POLES OF 'SPARE' BREAKERS IN EXISTING PANELS FOR RE-USE IN NEW WORK. PROVIDE LIST TO ARCHITECT AND ENGINEER FOR REVIEW, PRIOR TO ROUGH-IN.
  - EXISTING RECEPTACLES BRANCH CIRCUITS ARE SERVED FROM 120 VOLT NORMAL SOURCE PANELBOARD 'E2-7-LN/A'. REFER TO OVERALL PLAN ON SHEET E002 FOR PANEL LOCATION.
  - EXISTING X-RAY EQUIPMENT CIRCUITS ARE SERVED FROM 277/480 VOLT NORMAL SOURCE DISTRIBUTION PANEL 'DP-E2-10-XRAY'. REFER TO OVERALL PLAN ON SHEET E002 FOR PANEL LOCATION.
  - DEVICES TO BE DEMO'D ARE SHOWN DARK AND DASHED. ALL EXISTING TO REMAIN DEVICES ARE SHOWN LIGHTLY.
  - NOT ALL DEVICES TO BE DEMO'D ARE SHOWN. CONTRACTOR SHALL COMPLETELY REMOVE ALL DEVICES NO LONGER REQUIRED TO REMAIN.

- KEYNOTES: (#)**
- MAINTAIN EXISTING BRANCH CIRCUIT(S). ADAPT/EXTEND/MODIFY EXISTING CIRCUIT(S) FOR NEW WORK INDICATED. VERIFY EXISTING CONDITIONS.
  - EXISTING RECEPTACLE CIRCUIT(S) WITHIN DESIGNATED ROOM TO REMAIN. VERIFY EXISTING CONDITIONS.
  - EXISTING X-RAY EQUIPMENT, ASSOCIATED ACCESSORIES AND CABLING TO BE REMOVED BY XRAY VENDORS.
  - EXISTING DISCONNECT, PANEL, DEVICES, CONDUIT, WIRE AND RACEWAYS WITHIN XRAY ROOM TO BE REMOVED. VERIFY EXISTING CONDITIONS.

RELEASE FOR CONSTRUCTION  
ACI/BOLAND ARCHITECTS  
DEVELOPMENT SERVICES  
OF MISSOURI  
BRUCE E. HART  
HART  
NUMBER  
E-22817  
PROFESSIONAL ENGINEER  
07-07-21  
Bruce E. Hart - Engineer  
License - Missouri #E-22817

**ACI  
BOLAND  
ARCHITECTS**  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
ACI/Boland, Inc.  
Kansas City | St. Louis  
Licensee's Certificate of Authority Number:  
Missouri: #000958

**MEP CONSULTANT**  
**IMEG CORP.**  
1600 BALTIMORE ST, SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437


**Saint Luke's  
East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
120 NE SAINT LUKE'S BLVD. SUITE 200  
LEE'S SUMMIT MO 64086

Date	07/07/21
Job Number	3-21014
Drawn By	MSA
Checked By	BEH

Number	Date	Description

**IMEG**  
1600 BALTIMORE SUITE 300  
KANSAS CITY, MO 64108  
816.842.8437  
www.imegcorp.com  
PROJECT # 2101484.00  
Missouri State Certificate of Authority E-201708530  
IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
© 2021 IMEG CORP.  
REFERENCE SCALE IN INCHES  
0 1 2 3





**1 SECOND FLOOR DEMOLITION - SYSTEMS**  
 1/4" = 1'-0"  
 NORTH

- SHEET NOTES:**
- REFER TO SHEET E000 AND E001 FOR SYMBOLS AND ELECTRICAL GENERAL NOTES. NOT ALL NOTES MAY APPLY TO THIS SHEET.
  - RELOCATED FIRE ALARM DEVICES SHALL BE INTERCONNECTED TO EXISTING FIRE ALARM SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS AND PANEL REQUIRED IN EXISTING FIRE ALARM SYSTEM TO SERVE NEW DEVICES. ALL DEVICES, PANEL, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - RELOCATED OVERHEAD PAGING DEVICES SHALL BE INTERCONNECTED TO EXISTING SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS REQUIRED IN EXISTING PAGING SYSTEM TO SERVE DEVICES. ALL DEVICES, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - NEW DOOR SECURITY DEVICES SHALL BE INTERCONNECTED TO EXISTING DOOR SECURITY SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS REQUIRED IN EXISTING DOOR SECURITY SYSTEM TO SERVE NEW DEVICES. ALL DEVICES, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - CABLES FOR FIRE ALARM VOICE, DATA, PAGING, SECURITY AND TV SHALL BE PLENUM - RATED.
  - SUBMIT SHOP DRAWINGS SHOWING THE LOCATION OF NEW OPENING/CORED HOLES ON THE FLOOR FOR REVIEW. DO NOT CORE ANY HOLES UNTIL SHOP DRAWINGS ARE REVIEWED AND APPROVED BY THE STRUCTURAL ENGINEER.
  - BEFORE CORE DRILLING ANY HOLES, LOCATE REBAR IN THE SLAB BY X-RAY OR WITH R-METER. IF REBAR IS ENCOUNTERED WITHIN THE PROPOSED LOCATION OF THE HOLE, THEN EITHER RELOCATE THE HOLE TO MISS REBAR OR IF THE HOLE CANNOT BE RELOCATED, CONTACT STRUCTURAL ENGINEER FOR APPROVAL PRIOR TO CORING/DRILLING. DO NOT CORE ANY HOLES THROUGH THE BEAM WITHOUT APPROVAL OF STRUCTURAL ENGINEER.
  - DEVICES TO BE DEMO'D ARE SHOWN DARK AND DASHED. ALL EXISTING TO REMAIN DEVICES ARE SHOWN LIGHTLY.
  - NOT ALL DEVICES TO BE DEMO'D ARE SHOWN. CONTRACTOR SHALL COMPLETELY REMOVE ALL DEVICES NO LONGER REQUIRED TO REMAIN.
  - RELOCATED NURSE CALL DEVICES SHALL BE INTERCONNECTED TO EXISTING SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS REQUIRED IN EXISTING SYSTEM TO SERVE DEVICES. ALL DEVICES, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.

- KEYNOTES: (E)**
- ALL LOCATIONS AND TYPES OF DEVICES WITHIN DESIGNATED ROOMS/AREAS ARE BASED UPON AS-BUILT DRAWINGS. VERIFY EXISTING CONDITIONS.

RELEASE FOR CONSTRUCTION  
 DEVELOPMENT SERVICES  
 MISSOURI  
 BRUCE E. HART  
 ENGINEER  
 LICENSE NUMBER  
 MISSOURI  
 07-07-21  
 Bruce E. Hart - Engineer  
 License - Missouri #E-22817

**ACI BOLAND ARCHITECTS**  
 1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600

ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**  
 IMEG CORP.  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
 120 NE SAINT LUKE'S BLVD. SUITE 200  
 LEE'S SUMMIT MO 64086


Date	07/07/21
Job Number	3-21014
Drawn By	MSA
Checked By	BEH

Revision	Date	Description

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 2101484.00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 © 2021 IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 1" = 1'-0"

**E122**  
 © 2021 ACI/BOLAND, Inc.  
 SECOND FLOOR DEMOLITION - SYSTEMS






**1 SECOND FLOOR - LIGHTING**  
 1/4" = 1'-0"

**SHEET NOTES:**

- REFER TO SHEETS E000 AND E001 FOR SYMBOLS AND ELECTRICAL GENERAL NOTES. NOT ALL NOTES MAY APPLY TO THIS SHEET.
- EXISTING LIGHTING BRANCH CIRCUITS ARE SERVED FROM 277VOLT NORMAL SOURCE PANELBOARD 'E2-1-H'. REFER TO SHEET E002 FOR PANEL LOCATION.
- AS-BUILT DRAWINGS INDICATES EXISTING PANEL 'E2-1-H' AS HAVING SIX (6) 1P 20AMP SPARES AND EIGHTEEN (18) 1-POLE SPACES. PANEL IS RATED 225AMP, 277/480 VOLT, 3-PHASE, 4 WIRE, 42 CIRCUIT. VERIFY EXISTING CONDITIONS.

**KEYNOTES: ( # )**

- WATTSTOPPER DLM DIMMING ROOM CONTROLLER - ALRMC-212, 0-10 VOLT UNIT. REFER TO DETAIL.
- WATTSTOPPER DLM #LMSW-105 SERIES DIMMABLE WALL SWITCH WITH 2 UP/2 DN 5-BUTTON CONTROL WITH ONE BUTTON MASTER ON/OFF CONTROL. REFER TO DETAIL.
- INTERCEPT, EXTEND AND CONNECT LIGHTING TO EXISTING 277 VOLT BRANCH CIRCUIT(S) IN X-RAY ROOM AREA. TAKE READINGS TO ENSURE CIRCUIT(S) WILL NOT BECOME OVERLOADED. TRACE AND VERIFY EXISTING CONDITIONS AND LOADS PRIOR TO ROUGH-IN.
- PROVIDE NEW "IN-USE" SIGN, INTERCONNECT WITH X-RAY EQUIPMENT AS DIRECTED BY VENDOR.



**ACI BOLAND ARCHITECTS**

1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600

ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**

**IMEG CORP.**  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's East Hospital**

**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
**120 NE SAINT LUKE'S BLVD. SUITE 200**  
**LEE'S SUMMIT MO 64086**

Date 07/07/21  
 Job Number 3-21014  
 Drawn By MSA  
 Checked By BEH

Revision

Number	Date	Description

**IMEG** 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 2101424.00

Missouri State Certificate of Authority E-201708530

IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.

REFERENCE SCALE IN INCHES

**E202**

© 2021 ACI/BOLAND, Inc  
 SECOND FLOOR - LIGHTING



**ACI BOLAND ARCHITECTS**  
 1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600

ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**  
**IMEG CORP.**  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's East Hospital**  
**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
 120 NE SAINT LUKE'S BLVD. SUITE 200  
 LEE'S SUMMIT MO 64086

Date	07/07/21
Job Number	3-21014
Drawn By	MSA
Checked By	BEH

Revision		
Number	Date	Description

**IMEG**  
 1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 21014-00  
 Missouri State Certificate of Authority E-201708530  
 IMEG CORP RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.  
 REFERENCE SCALE IN INCHES  
 1" = 1'-0"


**E212**  
 SECOND FLOOR - POWER

**SHEET NOTES:**

- REFER TO SHEET E000 AND E001 FOR SYMBOLS AND ELECTRICAL GENERAL NOTES. NOT ALL NOTES MAY APPLY TO THIS SHEET.
- PROVIDE NEW BREAKERS TO MATCH WITH EXISTING PANEL RATINGS AND MATE WITH EXISTING SIZE, IF REQUIRED.
- FOR PURPOSES OF VOLTAGE DROP, PROVIDE #10 WIRE FOR 120 VOLT BRANCH CIRCUIT HOMERUN BEYOND 70FT FROM SOURCE PANEL AND #8 WIRE FOR 120 VOLT BRANCH CIRCUIT HOMERUNS BEYOND 120FT FROM SOURCE PANEL.
- UPON COMPLETION OF DEMOLITION WORK, CONFIRM QUANTITIES, SIZES, RATING AND POLES OF 'SPARE' BREAKERS IN EXISTING PANELS FOR RE-USE IN NEW WORK. PROVIDE LIST TO ARCHITECT AND ENGINEER FOR REVIEW, PRIOR TO ROUGH-IN.
- EXISTING RECEPTACLES BRANCH CIRCUITS ARE SERVED FROM 120 VOLT NORMAL SOURCE PANELBOARD 'E2-7-LN(A)'. REFER TO OVERALL PLAN ON SHEET E002 FOR PANEL LOCATION.
- EXISTING X-RAY EQUIPMENT CIRCUITS ARE SERVED FROM 277/480VOLT NORMAL SOURCE DISTRIBUTION PANEL 'DP-E2-10-XRAY'. REFER TO OVERALL PLAN ON SHEET E002 FOR PANEL LOCATION.
- AS-BUILT DRAWING INDICATES EXISTING PANEL 'E2-7-GN(A)' AS HAVING THIRTEEN (13) - 1P 20AMP SPARES AND NO SPACES. PANEL IS RATED 225 AMP MAIN BREAKING, 120/208 VOLT, 3-PHASE, 4 WIRE, 84 CIRCUIT. VERIFY EXISTING CONDITIONS.
- REFER TO RADSOURCE IMAGING TECHNOLOGIES - SAMSUNG VENDOR DRAWINGS - SITE SPECIFIC - "SAMSUNG GC85", FOR ALL INTERCONNECTING CABLING, CONDUIT AND WIRING. DESCRIPTION OF ITEMS TO BE PROVIDED BY THE ELECTRICAL CONTRACTOR. IN ADDITION, REFER TO MANUFACTURER INSTALLATION MANUAL FOR ADDITIONAL REFERENCE MATERIAL ASSOCIATED WITH THIS INSTALLATION.
- NOT ALL ELECTRICAL WORK IS SHOWN. REFER TO FINAL SAMSUNG AND G.E. HEALTHCARE SITE SPECIFIC DRAWINGS FOR ALL INTERCONNECTING CABLING, CONDUIT, J-BOXES, ELECTRICAL DEVICES AND DESCRIPTION OF SYMBOLS WHICH APPLY TO THIS PROJECT. DESIGN INDICATED ON THIS PROJECT IS SHOWN FOR BIDDING PURPOSES AND MAY NOT BE FINAL SITE SPECIFIC.
- NOT ALL DEVICES, J-BOXES, RACEWAYS, CABLING, ETC ARE SHOWN. CONTRACTOR SHALL REFER TO ATTACHED FINAL SAMSUNG AND G.E. HEALTHCARE DRAWINGS FOR ADDITIONAL REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK INDICATED ON SAMSUNG AND G.E. HEALTHCARE DRAWINGS AS OWNER OR CONTRACTOR FURNISHED AND/OR INSTALLED.
- CONTRACTOR SHALL CAREFULLY COORDINATE EXACT LOCATION OF ALL DEVICES AND EQUIPMENT WITH FINAL SAMSUNG AND GE HEALTHCARE PRIOR TO INSTALLATION.
- PROVIDE NEW CIRCUIT BREAKERS TO MATE WITH EXISTING PANELBOARDS SIZE AND MATCH PANEL RATINGS, IF REQUIRED.
- REFER TO GE HEALTHCARE VENDOR DRAWINGS TITLED "1-150" TYPICAL FINAL-RAD SITE PLANNING/READINESS-OPTIMA XR846". IN ADDITION, REFER TO PREINSTALLATION MANUAL #5843854-1EN FOR ADDITIONAL MATERIAL ASSOCIATED WITH RELOCATION INSTALLATION. ALL INTERCONNECTING CABLING, CONDUIT AND WIRING, DESCRIPTION OF ITEMS TO BE PROVIDED BY THE ELECTRICAL CONTRACTOR.
- ALL CONDUIT RUNS MUST TAKE THE MOST DIRECT ROUTE AND SHALL BE FURNISHED WITH PULL STRINGS.


**KEYNOTES: (#)**

- REFERENCE VENDOR DRAWINGS FOR DIMENSIONED EQUIPMENT LOCATIONS, ALL INTERCONNECTING CABLING, CONDUIT AND WIRING. DESCRIPTION OF ITEMS TO BE FURNISHED BY ELECTRICAL CONTRACTOR AND DESCRIPTION OF THE SYMBOLS WHICH APPLY TO THIS PROJECT, BUT ARE NOT SHOWN ON ELECTRICAL DRAWINGS. ELECTRICAL CONTRACTOR SHALL VERIFY THAT VENDOR DRAWINGS USED FOR CONSTRUCTION ARE OF THE LATEST REVISIONS. ANY DEVIATIONS FROM VENDOR DRAWINGS REQUIRED ARE NOT SHOWN ON THE ELECTRICAL DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING ALL CRITERIA LISTED IN THE NOTES, DETAILS AND DIAGRAMS SHOWN ON THE VENDOR DRAWINGS.
- INTERCEPT, EXTEND AND CONNECT RECEPTACLE(S) TO EXISTING 120 VOLT BRANCH CIRCUIT(S) IN X-RAY ROOM AREA. TAKE READINGS TO ENSURE CIRCUIT(S) WILL NOT BECOME OVERLOADED. TRACE AND VERIFY EXISTING CONDITIONS AND LOADS PRIOR TO ROUGH-IN.
- AS-BUILT DRAWING INDICATES EXISTING PANEL 'E2-7-LN(A)' CIRCUITS #18, 25, 27, 29, 35, 37, 58 AND 60 SERVES EXISTING RECEPTACLES WITHIN REMODELED XRAY AREA. VERIFY EXISTING CONDITIONS.
- DESIGNATED GROUP OF DUPLX RECEPTACLES TO BE PROVIDED AND CONNECTED TOGETHER ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 4. DESIGNATED GROUP OF DUPLX RECEPTACLES TO BE PROVIDED AND CONNECTED TOGETHER ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 5. DESIGNATED GROUP OF DUPLX RECEPTACLES TO BE PROVIDED AND CONNECTED TOGETHER ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 6. DESIGNATED GROUP OF FOURPLEX RECEPTACLES TO BE PROVIDED AND CONNECTED TOGETHER ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 7. DESIGNATED GROUP OF FOURPLEX RECEPTACLES TO BE PROVIDED AND CONNECTED TOGETHER ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 8. DESIGNATED GROUP OF FOURPLEX RECEPTACLES TO BE PROVIDED AND CONNECTED TOGETHER ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 9. INTERCEPT, EXTEND AND CONNECT TO EXISTING CIRCUIT.
- CORE EXISTING CONCRETE SLAB AND PATCH CONCRETE TO MATCH ADJACENT SURFACES AS DIRECTED BY ARCHITECT.
- PROVIDE 3 #3W, 1 #3 GROUND IN 1.25" CONDUIT.
- HOME RUN TO DESIGNATED PANEL. REFER TO ELECTRICAL RISER DIAGRAM FOR CONDUIT AND WIRE SIZE TO XRAY MAIN BREAKER.
- PROVIDE FLUSH MOUNT 100AMP, 3-POLE ENCLOSED MAIN BREAKER WITH SHUNT TRIP AS DIRECTED BY XRAY VENDOR. (480V, 3PH).
- PROVIDE 6"x6"x4" J-BOX FLUSH MOUNTED AS DIRECTED BY X-RAY VENDOR.
- PROVIDE 12"x12"x4" J-BOX FLUSH MOUNTED AS DIRECTED BY X-RAY VENDOR.
- PROVIDE 12"x12"x4" J-BOX FLUSH MOUNTED WITH 850P AS DIRECTED BY X-RAY VENDOR.
- PROVIDE WARNING LIGHT AT 12-24V DC AS DIRECTED BY XRAY VENDOR.
- PROVIDE PROTECTIVE COVER TO PREVENT ACCIDENTAL ACTIVATION.
- PROVIDE ONE (1) 14.5x12x4 FLUSH J-BOX, ONE (1) 18x3x4 FLUSH WALL DUCT AND ONE (1) 10x10x10 SURFACE J-BOX AT CEILING AS DIRECTED BY XRAY VENDOR.
- PROVIDE FLUSH MOUNT 80 AMP, 3-POLE ENCLOSED MAIN BREAKER WITH SHUNT TRIP AS DIRECTED BY XRAY VENDOR. (480V, 3PH).
- PROVIDE 8x8x4 J-BOX BELOW FLOOR AND ASSOCIATED CONDUITS AS DIRECTED BY XRAY VENDOR.
- PROVIDE 3 #2W, 1 #2 GROUND IN 1.25" CONDUIT.
- PROVIDE ONE (1) 18x18x4 FLUSH MOUNT J-BOX, ONE (1) 18x18x6 J-BOX ABOVE CEILING AND ONE (1) 18x3.5" FLUSH WALL DUCT AS DIRECTED BY XRAY VENDOR.
- PROVIDE 12x8x4 FLUSH MOUNT J-BOX AS DIRECTED BY XRAY VENDOR.
- DESIGNATED DEVICE TO BE CONNECTED ON ONE(1) 20AMP, 120 VOLT BRANCH CIRCUIT ROUTED TO EXISTING PANEL 'E2-7-LN(A)'.  
 26. PROVIDE 8x8x4 FLUSH MOUNT J-BOX WITH DIVIDER AND ASSOCIATED CONDUITS AS DIRECTED BY XRAY VENDOR.



**1 SECOND FLOOR - POWER**  
 1/4" = 1'-0"





**1 SECOND FLOOR - SYSTEMS**  
 1/4" = 1'-0"  
 NORTH

- SHEET NOTES:**
- REFER TO SHEET E000 AND E001 FOR SYMBOLS AND ELECTRICAL GENERAL NOTES. NOT ALL NOTES MAY APPLY TO THIS SHEET.
  - RELOCATED FIRE ALARM DEVICES SHALL BE INTERCONNECTED TO EXISTING FIRE ALARM SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS AND PANEL REQUIRED IN EXISTING FIRE ALARM SYSTEM TO SERVE DEVICES. ALL DEVICES, PANEL, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - RELOCATED OVERHEAD PAGING DEVICES SHALL BE INTERCONNECTED TO EXISTING SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS REQUIRED IN EXISTING PAGING SYSTEM TO SERVE DEVICES. ALL DEVICES, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - NEW DOOR SECURITY DEVICES SHALL BE INTERCONNECTED TO EXISTING DOOR SECURITY SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS REQUIRED IN EXISTING DOOR SECURITY SYSTEM TO SERVE NEW DEVICES. ALL DEVICES, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - CABLES FOR FIRE ALARM, VOICE, DATA, PAGING, SECURITY AND NURSE CALL SHALL BE PLENUM - RATED.
  - SUBMIT SHOP DRAWINGS SHOWING THE LOCATION OF NEW OPENING/CORED HOLES ON THE FLOOR FOR REVIEW. DO NOT CORE ANY HOLES UNTIL SHOP DRAWINGS ARE REVIEWED AND APPROVED BY THE STRUCTURAL ENGINEER.
  - BEFORE CORE DRILLING ANY HOLES, LOCATE REBAR IN THE SLAB BY X-RAY OR WITH R-METER. IF REBAR IS ENCOUNTERED WITHIN THE PROPOSED LOCATION OF THE HOLE, THEN EITHER RELOCATE THE HOLE TO MISS REBAR OR IF THE HOLE CANNOT BE RELOCATED, CONTACT STRUCTURAL ENGINEER FOR APPROVAL PRIOR TO CORING/DRILLING. DO NOT CORE ANY HOLES THROUGH THE BEAM WITHOUT APPROVAL OF STRUCTURAL ENGINEER.
  - RELOCATED NURSE CALL DEVICES SHALL BE INTERCONNECTED TO EXISTING SYSTEM SERVING CAMPUS. PROVIDE ANY NEW COMPONENTS REQUIRED IN EXISTING SYSTEM TO SERVE DEVICES. ALL DEVICES, COMPONENTS AND CABLING SHALL BE FURNISHED AND INSTALLED PER APPLICABLE PORTIONS OF PROJECT SPECIFICATIONS.
  - EXTEND ALL NEW I.T. CABLE TO EXISTING DATA NETWORK CLOSET AND PROVIDE PATCH PANEL(S) AS REQUIRED, UNLESS DIRECTED OTHERWISE BY OWNER.

- KEYNOTES: (#)**
- UTILIZE EXISTING NETWORK CLOSET FOR NEW CABLING. REFER TO SHEET E002 FOR CLOSET LOCATION.

**RELEASE FOR CONSTRUCTION**  
 AS SHOWN ON THESE DRAWINGS  
 DEVELOPMENT SERVICES  
 OF MISSOURI

BRUCE E. HART  
 HART  
 NUMBER  
 22817  
 PROFESSIONAL ENGINEER

07-07-21

Bruce E. Hart - Engineer  
 License - Missouri #E-22817

**ACI BOLAND ARCHITECTS**

1710 Wyandotte  
 Kansas City, MO 64108  
 T: 816.763.9600

ACI/Boland, Inc.  
 Kansas City | St. Louis  
 Licensee's Certificate of Authority Number:  
 Missouri: #000958

**MEP CONSULTANT**

**IMEG CORP.**  
 1600 BALTIMORE ST, SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437

**Saint Luke's East Hospital**

**ROCKHILL ORTHOPAEDIC X-RAY RENOVATION**  
 120 NE SAINT LUKE'S BLVD. SUITE 200  
 LEE'S SUMMIT MO 64086

Date	07/07/21
Job Number	3-21014
Drawn By	MSA
Checked By	BEH

Number	Date	Description

**IMEG**

1600 BALTIMORE SUITE 300  
 KANSAS CITY, MO 64108  
 816.842.8437  
 www.imegcorp.com  
 PROJECT # 21014-00

Missouri State Certificate of Authority E-201708530

IMEG CORP. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THIS DRAWING AND THE DATA SHOWN THEREON. SAID DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF IMEG CORP. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF IMEG CORP.

© 2021 IMEG CORP.  
 REFERENCE SCALE IN INCHES

**E222**

© 2021 ACI/BOLAND, Inc  
 SECOND FLOOR - SYSTEMS



# Drawing Index

These sheets are a document set and should not be separated. Electrical information and references are contained on all sheets.

SITE READINESS	C1
EQUIPMENT LAYOUT (Equipment locations, heat loads, component weights, environmental specs)	A1
STRUCTURAL LAYOUT (Structural support/mounting locations for floor/wall/ceiling, wall support elevations)	S1
STRUCTURAL DETAILS (Floor and Ceiling loading information)	S2
ELECTRICAL LAYOUT (Contractor supplied wiring, interconnect methods, junction point locations and descriptions)	E1
ELECTRICAL SPECIFICATIONS (Maximum wiring run lengths, interconnect diagram, system power specifications)	E2
ELECTRICAL DETAILS	E3 THRU E4
EQUIPMENT DETAILS	D1 THRU D2

These drawings indicate the placement and interconnection of the listed equipment components. These drawings are not construction or site preparation drawings. Customer remains ultimately responsible for preparing the site to accommodate the operation of such equipment in compliance with GE Healthcare's written specifications and all applicable federal, state, and/or local requirements.

## \* REQUIRED REFERENCE \*

Optima XR646  
Pre Installation Manual  
5643854-1EN

A mandatory component of this drawing set is the GE Healthcare Pre Installation manual. Failure to reference the Pre Installation manual will result in incomplete documentation required for site design and preparation.

Pre Installation documents for GE Healthcare products can be accessed on the web at:

[www.gehealthcare.com/siteplanning](http://www.gehealthcare.com/siteplanning)

# GE Healthcare



## RAD Site Planning



imagination at work

## Customer Site Readiness Requirements

- Any deviation from these drawings must be communicated in writing to and reviewed by your local GE Healthcare Installation Project Manager prior to making changes.
- Make arrangements for any rigging, special handling, or facility modifications that must be made to deliver the equipment to the installation site. If desired, your local GE Healthcare Installation Project Manager can supply a reference list of rigging contractors.
- New construction requires the following; 1. Secure area for equipment, 2. Power for drills and other test equipment, 3. Capability for image analysis, 4. Restrooms.
- Provide for refuse removal and disposal (e.g. crates, cartons, packing)
- Contact a radiation physicist or consultant to specify radiation containment requirements.

## GE Equipment Delivery Requirements

The items on the GE Healthcare Site Readiness Checklist are REQUIRED to facilitate equipment delivery to the IS site. Equipment will not be delivered if these requirements are not satisfied.

GE Healthcare Site Readiness Checklist Rev 21				
Before using this document ensure you have the latest Rev from MyWorkshop on D0C0422752				
GEHC Global Order # : _____		Customer: _____		
GEHC PMI Name : _____		FE / DOS Name: _____		
The customer is responsible for proper site preparation regardless of any GEHC measurements/inspections/assessments				
Escalate Site Readiness issues to the Zone ISL: East- Dan Pruent 352 255 7052, Central- Todd Rogers 940 453 9425, West- Randy Williams 360 606 2129				
Inspection Date: _____				
GEHC Minimum Requirements	Storage is item ready?	PMI is item ready?	FE is item ready?	Comments if "N", enter comments or action plan
1 MR Magnet Delivery Requirements: Ensure cryogen venting system is available for magnet connection as defined by GEHC Pre-Installation Manual (PIM) requirements, exhaust fan system is installed and operational, 480V power, and chilled water supply is oval				
2 MR RF Screen Room Requirements: RF Screen Room is tested with copy of Test Report that it is compliant with GEHC specifications. Dock Bolt and magnet anchors (if applicable) installed using 2 part anchor. For HDx systems, blower box mount bolts installed				
3 State Regulatory Requirements: Facility registration number provided for states of IL, KY, HI, RI, SC, TX, X-ray shielding plan and state acknowledgment letter provided to installer for AR, DC, NC, SC, CO & WA. Site Drawing Requirements: Final version o				
4 Surface Penetration Requirements: Customer/Contractor scheduled to provide required drilling or cutting into floors, ceilings, and walls; OR surface penetration permit available and posted in the room when GEHC will perform the work.				
5 Pre-Delivery Route Requirements: The equipment delivery route from the truck to the final destination within the facility has been reviewed with all key stakeholders to safely meet the minimum requirements for equipment access, and all communications/notes				
6 Finished Room Requirements: Rooms that will contain equipment, including storage areas not in scan suite, are dust free. Provisions taken to maintain a dust free room. Precautions must be taken to prevent dust from entering rooms containing equipment wh				
7 Electrical Requirements: Lockable (LOTO) Main Disconnect Panel (MDPI) is installed per GE guidelines and system power is available. Conduits, electrical cable ducting/dividers/cable trays, and access flooring is installed in proper location and height. S				
8 Power and Ground Audit: Workflow created				
9 HVAC Requirements: The HVAC/Chilled Water systems designed to maintain the environment per spec/PMI is at running state and appears to provide the desired environmental conditions including location of vents, temperature and humidity for system operation.				
10 Flooring Requirements: Floor is clean and prepared for final floor covering. Floor levelness/flatness is measured and within tolerance, and there are no visible defects per GEHC specifications. Confirm customer anchoring plan aligns with designed floor				
11 Ceiling Requirements: Unistrut (or equivalent) location, levelness and spacing is measured (or vendor confirmed) and consistent with the requirement of the installation drawings. Ensure unistrut and rails are not used as mounting surfaces. Ceiling grid				
12 Staging Requirements: Space has been identified to support the active installation process only. This area meets PIM/project book requirements. Storage space has been identified, if needed. This secured space would be used to store equipment indefinitely				
13 Network Connectivity: Hardwire for network connectivity(network drop) is in place prior to delivery with specified network firewall configuration where required. Site Surveys for wireless mobile XR units have been completed.				
14 Insite Readiness: Confirmation of VPN tunnel requested.				
15 Medical Gases Requirements: Systems (hard piped or portable) in place to allow testing and calibration of equipment (anesthesia), including ventilation.				

RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI

07/28/2021

Wisconsin  
Healthcare Project Implementation - Design Center  
Milwaukee, Copyright © 2009 General Electric Company - Proprietary to GE

**GE Healthcare**

SHEET TITLE: SITE READINESS  
MODALITY TYPE: OPTIMA XR646

THIS PLAN IS SUBMITTED TO SURVEY LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE LATEST REVISED DRAWINGS AND THE COMPANY CANNOT ACCEPT ANY LIABILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
1-150f  
TYPICAL FINAL

PROJECT	REVISION
1-150f	03
DATE:	09.Sep.16
DRAWN BY:	JDR
CHECKED BY:	REK

REVISION HISTORY:


SHEET  
C1

PIM R5 RQ - 163687



GE EQUIPMENT LISTING


EQUIPMENT ON ORDER FROM GE HEALTHCARE, INSTALLED BY GE HEALTHCARE, PER NEITHER A QUOTE OR GON WAS ISSUED AT THE DATE OF THESE DWGS		EQUIPMENT CROSS REFERENCE CHART		SEISMIC STATUS					
NOTE: LOCAL CONDITIONS MAY DICTATE THAT ITEMS IDENTIFIED IN THIS CATEGORY BE INSTALLED BY OTHERS.		P = PREAPPROVAL C = CALCULATIONS/ PENDING APPROVAL		S = SPECIFICATIONS ONLY					
ITEM NO.	QUANTITY ORDERED	REFER TO SHEET "D"	ITEM DESCRIPTION (* = EXISTING/REINSTALL)	WEIGHT	HEAT OUTPUT (PER HOUR)	DETAIL NO.	STRC PLAN	ELEC PLAN	
1	1		SYSTEM CABINET	705 lbs	2440 btu	B8125	-	SKL S	
2	1		XR656 G2/646 DIGITAL ELEVATING TABLE	970 lbs	372 btu	B0557V	B0558N	RT S	
3	1		TETHER INTERFACE BOX	15 lbs	10 btu	B8126	-	TIB -	
4	1		CABLE DRAPE RAIL	182 lbs			B20079	-	
5	1		XT RADIOGRAPHIC SUSPENSION WITH INBOARD MOUNTING	764 lbs	105 btu	B2020	B20041	XTS1 C	
6	2		LONGITUDINAL STATIONARY RAIL FOR XT SUSPENSION	68 lbs			B20041	-	
7	1		OPERATORS CONSOLE	61 lbs	604 btu	CG10CB B6566E B6566F B8138B	-	WBC1 -	
8	1		DIGITAL CHEST UNIT	595 lbs	136 btu	B0557F	B0557G	WLS C	
9	1		DONGLE	4 lbs		B8137	-	D -	
10	1		GRID HOLDER (FIELD VERIFY IDEAL LOCATION)	30 lbs		B0557W	B0557K	S -	
--- OPTIONAL ---									
11	1		PARTIAL SYSTEM UNINTERRUPTIBLE POWER SUPPLY	77 lbs	30 btu			UPS -	
12	1		IMAGE PASTING BARRIER	121 lbs		B0557Y	-	-	
13	1		DETECTOR BIN (WALL MOUNT)	33 lbs		B8127	-	-	
14	1		DETECTOR BIN (FLOOR MOUNT)	33 lbs		B8127	-	-	
15	1		FLEXI DT MOBILE TABLE	683 lbs		B0557L	-	-	
16	1		MOBILE TABLE	224 lbs		B0557K	-	S -	
17	1		CARBON FIBER TABLE	70 lbs		B5000A	-	-	
18	1		DIGITAL CHEST UNIT WITH EXTENDED RECEPTOR	617 lbs	136 btu	B0557Z	B0557G	WLS C	

SCALE: 1/4" = 1'-0"

EQUIPMENT LAYOUT

RECOMMENDED CEILING HEIGHT = 9'-6"

This equipment layout indicates the placement and interconnection of the indicated equipment components. There may be federal, state, and/or local requirements that could impact the placement of these components. It remains the Customer's responsibility for ensuring the site and final equipment placement complies with all applicable federal, state, and/or local requirements.



ANCILLARY ITEMS

CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS

ITEM NO.	ITEM DESCRIPTION (* INDICATES EXISTING)
60	MINIMUM DOOR OPENING FOR EQUIPMENT DELIVERY IS 37.5 IN. W x 75 IN. H (950mm x 1900mm), CONTINGENT ON A 98.5 IN. (2500mm) CORRIDOR WIDTH. NOTE: IMAGE PASTE OPTION REQUIRES AN 82 IN. H (2100mm) HIGH OPENING FOR ACCESS.
61	CONTROL WALL, 7 FT. HIGH WITH LEAD GLASS VIEWING WINDOW.
62	COUNTER TOP FOR EQUIPMENT - MINIMUM DEPTH 24 IN. AND ADDITIONAL SHELVING MAY BE REQUIRED BELOW COUNTER TOP FOR PC TOWER. PROVIDE GROMMETED OPENINGS AS REQUIRED TO ROUTE CABLES.
63	X-RAY ON WARNING LIGHT - AVAILABLE FROM GE SUPPLY CALL: 800-200-9760 GE CAT. NO. WX1ABW-DF-XIU
64	DOOR LIMIT SWITCH (NEEDED ONLY IF REQUIRED BY STATE/LOCAL CODES)

THE FOLLOWING ITEMS ARE AVAILABLE FROM GE HEALTHCARE TECHNOLOGIES. CONTACT YOUR LOCAL GE HEALTHCARE SERVICE REPRESENTATIVE FOR PRICING AND AVAILABILITY.

90	X-RAY ROOM WARNING LIGHT CONTROL PANEL REFERENCE JUNCTION POINT 'XRLC' ON SHEET 'E1' FOR DETAILED DESCRIPTION -E4502RL FOR WARNING LIGHT CONTROL ONLY.
91	EMERGENCY OFF SWITCH (NEEDED ONLY IF REQUIRED BY STATE/LOCAL CODES)
92	MAIN DISCONNECT, REFERENCE JUNCTION POINT 'A' ON SHEET E1: <16" W x 24" H x 6" D>

GENERAL SPECIFICATIONS

- THE REQUIRED CEILING HEIGHT INDICATED ON THESE PLANS IS TO ENSURE EQUIPMENT FUNCTION IS NOT INHIBITED. CONSULT WITH YOUR LOCAL GEHC SPECIALIST REGARDING ACCEPTABILITY OF OTHER CEILING HEIGHTS.
- CHECK ALL DOOR OPENINGS AND HALLWAYS FROM DELIVERY LOCATION TO WHERE EQUIPMENT IS TO BE INSTALLED TO ENSURE THE ROUTE PHYSICALLY AND STRUCTURALLY WILL ACCOMMODATE THE EQUIPMENT AS SHIPPED.
- RADIATION PROTECTION REQUIREMENTS ARE NOT INDICATED ON THIS PLAN. WHERE NEEDED PER NATIONAL OR LOCAL CODE THEY SHALL BE SPECIFIED BY A QUALIFIED RADIOLOGICAL PHYSICIST.
- THE DEVELOPMENT OF THE EQUIPMENT LAYOUT, ROOM DIMENSIONS, MECHANICAL AND ELECTRICAL SUGGESTIONS IS PREDICATED UPON THE BEST INFORMATION OBTAINABLE FROM THE SITE, COUPLED WITH THE CUSTOMER'S KNOWN DESIRES. ARCHITECTURAL OR ELECTRICAL CHANGES INCLUDING RELOCATION OF EQUIPMENT ILLUSTRATED ON THIS DRAWING IS ALLOWED ONLY WITH NOTIFICATION, IN WRITING, AND REVIEW BY GEHC SERVICE DEPARTMENT. EQUIPMENT OPERATION, SERVICEABILITY, AND RESTRICTING CABLE LENGTHS, ETC., MAKE THIS ESSENTIAL FOR A PROPER IS. GEHC RESERVES THE RIGHT TO MAKE ON THE JOB CHANGES BECAUSE OF CUSTOMER REQUIREMENTS AND/OR OBSTACLES IN CONSTRUCTION, ETC..
- ALL WORK TO BE IN COMPLIANCE WITH NATIONAL AND LOCAL BUILDING SAFETY CODES.
- DIMENSIONS ARE TO FINISHED SURFACES OF ROOM.

SITE ENVIRONMENT SPECIFICATIONS

- AMBIENT OPERATING TEMPERATURE: 59 TO 95 DEGREES (F), MAXIMUM ALLOWABLE TEMPERATURE CHANGE OF 10 DEGREES (C)/HOUR.
- HUMIDITY: REFER TO PREINSTALLATION MANUAL FOR THE EQUIPMENT ILLUSTRATED ON THIS DRAWING.
- REFER TO PREINSTALLATION MANUAL FOR THE EQUIPMENT ILLUSTRATED ON THIS DRAWING.
- THE ENVIRONMENT FOR THE ELECTRONICS CABINET MUST BE CONTROLLED SO THE ABOVE RESTRICTIONS ARE NOT EXCEEDED.
- DO NOT RESTRICT THE AIR INTAKE AT THE LOWER FRONT OR AIR EXHAUST AT THE TOP OF THE ELECTRONICS CABINETS.

MAGNETIC INTERFERENCE SPECIFICATIONS

DIGITAL FLAT PANEL MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 1 GAUSS TO GUARANTEE SPECIFIED IMAGING PERFORMANCE.  
 X-RAY TUBES MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 10 GAUSS TO GUARANTEE SPECIFIED PERFORMANCE.  
 SYSTEM ELECTRONICS MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 10 GAUSS TO GUARANTEE DATA INTEGRITY.  
 OPERATORS CONSOLE EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 10 GAUSS TO OBTAIN SPECIFIED GEOMETRIC LINEARITY.

THE FOLLOWING ITEMS, WHICH HAVE BEEN ORDERED FROM GE HEALTHCARE, ARE TO BE INSTALLED BY THE CUSTOMER OR HIS CONTRACTOR.

SHEET TITLE: EQUIPMENT LAYOUT  
 MODALITY TYPE: OPTIMA XR646

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO ALL APPLICABLE CODES AND REGULATIONS. GE HEALTHCARE DOES NOT ACCEPT LIABILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
 1-150f  
 TYPICAL FINAL

PROJECT	REVISION
1-150f	03

DATE: 09.Sep.16  
 DRAWN BY: JDR  
 CHECKED BY: REK

REVISION HISTORY:


SHEET  
 A1




STRUCTURAL SUPPORT METHODS	
CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS	
ITEM NO.	ITEM DESCRIPTION (* INDICATES EXISTING)
1	SUPPORT BACKING, LOCATE AS SHOWN, REFER TO ELEVATION DETAIL S130, FOR SYSTEMS CABINET
2	FLOOR CONTACT AREA FOR TABLE
3	UNISTRUT OR EQUIVALENT SUPPORT IN CEILING FOR FASTENING CABLE DRAPE RAIL SUPPORTS TO RUN CONTINUOUS WITH NO FITTINGS EXTENDING BELOW FACE OF UNISTRUT CHANNEL, RUN WALL TO WALL, BE PARALLEL, SQUARE, AND IN THE SAME HORIZONTAL PLANE, FLUSH WITH THE FINISHED CEILING. RAILS ARE MOUNTED TO THESE SUPPORTS EVERY 2'-2" AND REQUIRE 90 LBS. PER BOLT LOAD. METHODS OF SUPPORT THAT PERMIT ATTACHMENT TO STRUCTURAL STEEL OR THROUGH BOLTS IN CONCRETE SHOULD BE FAVORED. DO NOT USE SCREW ANCHORS IN DIRECT TENSION.
4	UNISTRUT OR EQUIVALENT SUPPORT IN CEILING FOR FASTENING CABLE DRAPE RAIL SUPPORTS TO RUN CONTINUOUS WITH NO FITTINGS EXTENDING BELOW FACE OF UNISTRUT CHANNEL, RUN WALL TO WALL, BE PARALLEL, SQUARE, AND IN THE SAME HORIZONTAL PLANE, FLUSH WITH THE FINISHED CEILING. RAILS ARE MOUNTED TO THESE SUPPORTS EVERY 2'-2" AND REQUIRE 90 LBS. PER BOLT LOAD. METHODS OF SUPPORT THAT PERMIT ATTACHMENT TO STRUCTURAL STEEL OR THROUGH BOLTS IN CONCRETE SHOULD BE FAVORED. DO NOT USE SCREW ANCHORS IN DIRECT TENSION.
5	FLOOR CONTACT AREA FOR CHEST READER
6	SUPPORT BACKING, REFER TO ELEVATION DETAIL S107, FOR GRID HOLDER
7	SUPPORT BACKING, LOCATE AS SHOWN, REFER TO ELEVATION DETAIL S129


**STRUCTURAL NOTES**

- ALL STEEL WORK AND PARTS NECESSARY TO SUPPORT CEILING MOUNTED TUBE HANGER OR OTHER EQUIPMENT ARE TO BE SUPPLIED BY THE CUSTOMER OR HIS CONTRACTORS. THE UNISTRUT OR EQUIVALENT STRUCTURE SHOULD RUN CONTINUOUS WITH NO FITTINGS EXTENDING BELOW FACE OF UNISTRUT CHANNEL, RUN WALL TO WALL, BE PARALLEL, SQUARE AND IN THE SAME HORIZONTAL PLANE FLUSH WITH FINISHED CEILING. THE SYSTEM IS TO BE CROSS BRACED VERTICALLY, HORIZONTALLY AND DIAGONALLY TO ALLOW NO MOVEMENT AND A MAXIMUM OF 1.58mm(1/16") DEFLECTION. CLOSURE STRIPS SHALL BE PROVIDED FOR AREAS OF UNISTRUT EXPOSED AND WITHOUT MOUNTING UNITS.
- METHODS OF SUPPORT FOR THE STEELWORK THAT WILL PERMIT ATTACHMENT TO STRUCTURAL STEEL OR THROUGH BOLTS IN CONCRETE CONSTRUCTION SHOULD BE FAVORED. DO NOT USE CONCRETE OR MASONRY ANCHORS IN DIRECT TENSION.
- ALL UNITS THAT ARE WALL MOUNTED OR WALL SUPPORTED ARE TO BE PROVIDED WITH SUPPORTS WHERE NECESSARY. WALL SUPPORTS ARE TO BE SUPPLIED AND INSTALLED BY THE CUSTOMER OR HIS CONTRACTORS. SEE PLAN AND DETAIL SHEETS FOR SUGGESTED LOCATIONS AND MOUNTING HOLE LOCATIONS.
- ALL CEILING MOUNTED FIXTURES, AIR VENTS, SPRINKLERS, ETC. TO BE FLUSH MOUNTED, OR SHALL NOT EXTEND MORE THAN 6.35mm (1/4") BELOW THE FINISHED CEILING.
- CONTROL WALLS, WITH TUBE HANGER PASSAGE ABOVE SHALL BE CONSTRUCTED TO 2130mm (7'-0") HIGH.
- FLOOR SLABS ON WHICH EQUIPMENT IS TO BE INSTALLED MUST BE LEVEL TO 3,17mm (1/8") IN 3050mm (10'-0")
- DIMENSIONS ARE TO FINISHED SURFACES OF ROOM.
- CUSTOMERS CONTRACTOR MUST PROVIDE ALL PENETRATIONS IN POST TENSION FLOORS.
- CUSTOMERS CONTRACTOR MUST PROVIDE AND INSTALL ANY NON-STANDARD ANCHORING. DOCUMENTS FOR STANDARD ANCHORING METHODS ARE INCLUDED WITH GE EQUIPMENT DRAWINGS FOR GEOGRAPHIC AREAS THAT REQUIRE SUCH DOCUMENTATION.
- CUSTOMERS CONTRACTOR MUST PROVIDE AND INSTALL HARDWARE FOR "THROUGH THE FLOOR" ANCHORING AND/OR ANY BRACING UNDER ACCESS FLOORS. THIS CONTRACTOR MUST ALSO PROVIDE FLOOR DRILLING THAT CANNOT BE COMPLETED BECAUSE OF AN OBSTRUCTION ENCOUNTERED WHILE DRILLING BY THE GE INSTALLER SUCH AS REBAR ETC.
- IT IS THE CUSTOMER'S RESPONSIBILITY TO PERFORM ANY FLOOR OR WALL PENETRATIONS THAT MAY BE REQUIRED. THE CUSTOMER IS ALSO RESPONSIBLE FOR ENSURING THAT NO SUBSURFACE UTILITIES (E.G., ELECTRICAL OR ANY OTHER FORM OF WIRING, CONDUITS, PIPING, DUCT WORK OR STRUCTURAL SUPPORTS (I.E. POST TENSION CABLES OR REBAR)) WILL INTERFERE OR COME IN CONTACT WITH SUBSURFACE PENETRATION OPERATIONS (E.G. DRILLING AND INSTALLATION OF ANCHORS/SCREWS) PERFORMED DURING THE INSTALLATION PROCESS. TO ENSURE WORKER SAFETY, GE INSTALLERS WILL PERFORM SURFACE PENETRATION OPERATIONS ONLY AFTER THE CUSTOMER'S VALIDATION AND COMPLETION OF THE "GE SURFACE PENETRATION PERMIT"

SCALE: 1/4" = 1'-0"      STRUCTURAL LAYOUT      RECOMMENDED CEILING HEIGHT = 9'-6"



TYPICAL WALL SUPPORT ELEVATIONS



(FINISHED CEILING)

(FINISHED FLOOR)

(FINISHED CEILING)

(FINISHED FLOOR)

(FINISHED CEILING)

(FINISHED FLOOR)


(FINISHED CEILING)

(FINISHED FLOOR)




STRUCTURAL DETAIL  
SYSTEM CABINET

B5032  
REV. DATE: 05.Dec.11




SUPPORT DETAIL  
XT RADIOGRAPHIC SUSPENSION, INBOARD MOUNTING

B20-041  
REV. DATE: 02.Feb.15




SUPPORT DETAIL  
XT RADIOGRAPHIC SUSPENSION, INBOARD MOUNTING

B20-079  
REV. DATE: 11.Jun.12




SUPPORT DETAIL  
GRID HOLDER WALL MOUNT PANEL

B0557K  
REV. DATE: 05/24/10




FLOOR MOUNTING DETAIL: DIGITAL ELEVATING TABLE INSTALLATION METHODS

B0558N  
REV. DATE: 09.Jan.15



FLOOR MOUNTING DETAIL: DIGITAL CHEST READER

B0557G  
REV. DATE: 01.Oct.13



CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI

07/28/2021

Design Center

GE Healthcare

Healthcare Project Implementation - Design Center

Missouri, Milwaukee

SHEET TITLE: STRUCTURAL DETAILS

MODALITY TYPE: OPTIMA XR646

THIS PLAN IS SUBMITTED TO SURVEY LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM TO THE ACTUAL CONSTRUCTION PURPOSES AND THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:

1-150f

TYPICAL FINAL

PROJECT	REVISION
1-150f	03

DATE: 09.Sep.16

DRAWN BY: JDR

CHECKED BY: REK

REVISION HISTORY:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

SHEET






S2



SCALE: 1/4" = 1'-0"


ELECTRICAL PLAN

RECOMMENDED CEILING HEIGHT = 9'-6"



**JUNCTION POINT NOTES**

- ALL JUNCTION BOXES, CONDUIT, DUCT, DUCT DIVIDERS, SWITCHES, CIRCUIT BREAKERS, CABLE TRAY, ETC., ARE TO BE SUPPLIED AND INSTALLED BY CUSTOMERS ELECTRICAL CONTRACTOR.
- CONDUIT AND DUCT RUNS SHALL HAVE SWEEP RADIUS BENDS
- CONDUITS AND DUCT ABOVE CEILING OR BELOW FINISHED FLOOR MUST BE INSTALLED AS NEAR TO CEILING OR FLOOR AS POSSIBLE TO REDUCE RUN LENGTH.
- CEILING MOUNTED JUNCTION BOXES ILLUSTRATED ON THIS PLAN MUST BE INSTALLED FLUSH WITH FINISHED CEILING.
- ALL DUCTWORK MUST MEET THE FOLLOWING REQUIREMENTS:
  - DUCTWORK SHALL BE METAL WITH DIVIDERS AND HAVE REMOVABLE, ACCESSIBLE COVERS.
  - DUCTWORK SHALL BE CERTIFIED/RATED FOR ELECTRICAL POWER PURPOSES.
  - DUCTWORK SHALL BE ELECTRICALLY AND MECHANICALLY BONDED TOGETHER IN AN APPROVED MANNER.
  - PVC AS A SUBSTITUTE MUST BE USED IN ACCORDANCE WITH ALL LOCAL AND NATIONAL CODES.
- ALL OPENINGS IN ACCESS FLOORING ARE TO BE CUT OUT AND FINISHED OFF WITH GROMMET MATERIAL BY THE CUSTOMERS CONTRACTOR.
- GENERAL CONTRACTOR TO INSERT PULL CORDS FOR ALL CABLE RUN CONDUITS BETWEEN THE EQUIPMENT ROOM AND THE OPERATORS CONTROL ROOM.
- 10 FOOT PIGTAILS AT ALL JUNCTION POINTS.
- ALL WIRING MUST BE THHN OR TFFN STRANDED COPPER THERMOPLASTIC 600 VOLT OR EQUIVALENT INSULATION. **ALUMINUM OR SOLID WIRES ARE NOT ALLOWED.**
- GROUNDING IS CRITICAL TO EQUIPMENT FUNCTION AND PATIENT SAFETY. SITE MUST CONFORM TO WIRING SPECIFICATIONS SHOWN ON THIS PLAN.



PLEASE SEE BELOW FOR ADDITIONAL REQUIRED CONDUIT RUNS AND SIZES.

JEDI 80kW SYSTEMS CABINET REV. DATE: 03.FEB.15

- CALCULATIONS BASED UPON NOMINAL VOLTAGE, WIRE SIZE IN AWG.
- RECOMMENDED FEEDER SIZES FROM DISTRIBUTION TRANSFORMER TO THE POWER CABINET
- NEUTRAL MUST BE TERMINATED INSIDE THE MAIN DISCONNECT PANEL AND NOT AT ANY GE CABINET.
- THE GROUNDING CONDUCTOR WILL BE OF SAME SIZE AS THE FEEDER. THIS GROUND WILL RUN FROM THE EQUIPMENT BACK TO THE FACILITY POWER SOURCE/MAIN GROUNDING POINT AND ALWAYS TRAVEL IN THE SAME CONDUIT WITH THE FEEDERS AND NEUTRAL.
- MINIMUM WIRE SIZE FOR CIRCUIT BREAKER, BASED ON RECOMMENDED OVERCURRENT PROTECTION.
- FOR A FULL SYSTEM UPS, REFER TO ELECTRICAL DETAILS FOR UPS FEEDER WIRES.

RUN LENGTH IN FEET	POWER SUPPLY VOLTAGE					
	342-418 380	360-440 400	373-456 420	396-484 440	414-506 460	432-528 480
50	2	2	2	2	2	2
100	2	2	2	2	2	2
150	1/0	1	1	2	2	2
200	2/0	2/0	1/0	1/0	1	1
250	3/0	3/0	2/0	2/0	1/0	1/0
300	4/0	4/0	3/0	3/0	2/0	2/0
350	300M	250M	4/0	4/0	3/0	3/0
400	350M	300M	250M	4/0	4/0	3/0
450	400M	350M	300M	250M	250M	4/0

SIZE OF FEEDERS AND GROUND WIRES (AWG)

ADDITIONAL CONDUIT RUNS FOR DISCOVERY XR656, XR656 PLUS AND OPTIMA XR646

CONDUITS REQUIRED FOR BASE SYSTEM (CONDUITS ARE LOCATED ABOVE CEILING)

REV DATE: 25.Sep.15

XRLC TO	XRL1	ONE 1/2" CND.
XRLC TO SKL	ONE 1/2" CND.	
XRLC TO 120-V 1Ø POWER	CND. AS REQ'D	
A TO SKL	ONE CND. AS REQ'D	
A TO SEO	ONE 1/2" CND.	
A TO FEEDER	ONE CND. AS REQ'D	
DLK1 TO SKL	ONE 1/2" CND.	
SKL TO TIB	ONE 2" CND.	
WBC1 TO TIB	ONE 1" CND.	
SKL TO D	ONE 1" CND.	
WBC1 TO D	ONE 2" CND.	

NOTE: SEE E2 PAGE FOR MAXIMUM RUN LENGTHS

ELECTRICAL OUTLET LEGEND

CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS. HEIGHT ABOVE FLOOR DETERMINED BY LOCAL CODES UNLESS OTHERWISE SPECIFIED.

- Ⓜ DUPLEX HOSPITAL GRADE, DEDICATED OUTLET 120-V, SINGLE PHASE POWER
- Ⓛ DEDICATED TELEPHONE LINE(S) (SEE ELECTRICAL DETAIL ELEC-1 OR ELEC-67)
- Ⓝ NETWORK OUTLET (SEE ELECTRICAL DETAILS ELEC-83 AND ELEC-84 OR ELEC-87)

**JUNCTION POINT DESCRIPTIONS**

THE FOLLOWING MATERIALS ARE TO BE SUPPLIED AND INSTALLED BY THE CUSTOMER'S ELECTRICAL CONTRACTOR

POINT	DESCRIPTION	QTY.	HARDWARE	DETAIL NO., SHT. E3
A	MAIN DISCONNECT # AVAILABLE FROM GEHC CALL 800-279-7525 OR LOCAL GE INSTALLATION PROJECT MGR.	1	MAIN DISCONNECT PANEL SEE SHEET E2. POWER SPECS FOR THE APPROPRIATE CATALOG NUMBER. ONE REMOTE EMERGENCY OFF (SEO) PUSHBUTTON AND STAINLESS STEEL GROUNDING PLATE STATION ARE WITH EACH MAIN DISCONNECT	ELEC-15
D	DONGLE	1	COVERPLATE 1 1/2 IN. DIA. CHASE NIPPLE 16 X 6 X 4 IN. BOX	ELEC-8
DLK1	DOOR SWITCH (NEEDED ONLY IF REQUIRED BY STATE/LOCAL CODES)	1	ROOM DOOR INTERLOCK LIMIT SWITCH IN FRAME - NORMALLY OPEN (24V) 1 SINGLE GANG BOX	ELEC-48
RT	TABLE	1	SUITABLE BUSHING & LOCKNUT 3/4 IN. CONDUIT STUBBED 2 IN. ABOVE FLOOR 8 X 8 X 4 IN. BOX BELOW FLOOR	ELEC-48
SEO	EMERGENCY OFF	1	PROVIDE A SINGLE GANG, 2 1/2 IN. DEEP, FLUSH MTD. WALL BOX.	ELEC-16 ELEC-167
SKL	SYSTEMS CABINET	1	SPLIT COVERPLATE 2 1/2 IN. DIA. CHASE NIPPLE 18 X 18 X 4 IN. BOX	ELEC-7 ELEC-2
TIB	TETHER INTERFACE BOX	1	COVERPLATE 1 1/2 IN. DIA. CHASE NIPPLE 16 X 6 X 4 IN. BOX	ELEC-8
UPS	UNINTERRUPTIBLE POWER SUPPLY	1	EXTERNAL CONNECTION	
WBC1	OPERATORS CONSOLE	1	12 X 6 X 4 IN. BOX	ELEC-173
WLS	CHEST UNIT	1	SPLIT COVERPLATE 1 1/2 IN. DIA. CHASE NIPPLE 18 X 8 X 4 IN. BOX WITH DIVIDER	ELEC-79
XRL1	WARNING LIGHT	1	SINGLE GANG BOX X-RAY ON-INCANDESCENT LIGHT FIXTURE. 24V, 8 AMP OR LESS LOW VOLTAGE SOURCE. DO NOT USE FLUORESCENT FIXTURES.	
XRLC	WARNING LIGHT CONTROLLER (AVAILABLE FROM GEHC CALL 800-279-7525 OR LOCAL GE INSTALLATION PROJECT MGR.)	1	E4502RL WARNING LIGHT CONTROL OR EQUIVALENT MAX 24V CONTROLLER	ELEC-72
XTS1	X-RAY TUBE HANGER	1	3/2 IN. OF GROMMET MATERIAL FOR AN 8 X 8 IN. OPENING IN DUCT COVER	ELEC-6

**CONTRACTOR SUPPLIED AND INSTALLED WIRING**

ELECTRICAL CONTRACTOR SHALL RING OUT, TAG AND TERMINATE ALL WIRES AT BOTH ENDS.

WIRE RUN, FROM - TO	QUANTITY, WIRE SIZE/COLOR
XRLC > 1 PHASE	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
A > SEO	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
SKL > XRLC	2-ND. 14 BLACK, 1-ND. 14 RED, 1-ND. 14 WHITE
SKL > DLK1	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
SKL > XRLC	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
A > XRL1	3-BLACK, 1-GREEN - REFER TO FEEDER TABLE
480-V > A	3-BLACK, 1-WHITE, 1-GREEN - REFER TO FEEDER TABLE

RECONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LLC'S SUMMIT, MISSOURI

07/28/2021

Healthcare Project Implementation - Design Center

GE Healthcare

SHEET TITLE: ELECTRICAL LAYOUT  
MODALITY TYPE: OPTIMA XR646

THIS PLAN IS SUBMITTED TO SURVEY LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS. ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM TO DETAILS AND REQUIREMENTS OF THE PROJECT. THE USER OF THIS PLAN SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION OF ALL EQUIPMENT AND ROOMS. THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE: 1-150f  
TYPICAL FINAL

PROJECT: 1-150f  
REVISION: 03

DATE: 09.Sep.16  
DRAWN BY: JDR  
CHECKED BY: REK

REVISION HISTORY:

SHEET E1

THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED








PROJECT	REVISION
1-150f	03
DATE: 09.Sep.16	
DRAWN BY: JDR	
CHECKED BY: REK	


REVISION HISTORY:


ELECTRICAL DETAIL  
HORIZONTAL WALL DUCT (TYPICAL) ELEC-5  
REV. DATE: 03/19/04




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
TABLE INTERCONNECTION - BOX BELOW FLOOR ELEC-48  
REV. DATE: 01/04/96




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
J.B. / WALL DUCT DETAIL (TYPICAL) ELEC-2  
REV. DATE: 02.Jan.15




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
BOX WITH SPLIT COVERPLATE (TYPICAL) ELEC-7  
REV. DATE: 09/30/94




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
BOX WITH COVERPLATE AND NETWORK JACK ELEC-83  
REV. DATE: 10/06/98




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
INSITE CONNECTION (TYPICAL) ELEC-1  
REV. DATE: 04/24/02




DETAIL NOT TO SCALE

EQUIPMENT DETAIL  
WALL PLATE ELEC-173  
REV. DATE: 11.Aug.14




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
WARNING LIGHT DIAGRAM ELEC-72  
REV. DATE: 05/14/09




UNLESS SPECIFIED ON SHEET A1 AS BEING INCLUDED ON EQUIPMENT ORDER, ALL ITEMS ILLUSTRATED ARE TO BE FURNISHED AND INSTALLED BY CUSTOMER'S CONTRACTOR  
DRAWING NOT TO SCALE

ELECTRICAL DETAIL  
BOX WITH COVERPLATE (TYPICAL) ELEC-8  
REV. DATE: 09/30/94




DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
BOX WITH DIVIDER AND SPLIT COVERPLATE (TYPICAL) ELEC-79  
REV. DATE: 04/06/04



DETAIL NOT TO SCALE

ELECTRICAL DETAIL  
NETWORK CONNECTION (TYPICAL) ELEC-84  
REV. DATE: 17.Jun.16




DETAIL NOT TO SCALE




ELECTRICAL DETAIL  
EMERGENCY OFF BUTTON

ELEC-16  
REV. DATE: 05/14/09




ELECTRICAL DETAIL  
ROOM POWER SUPPLY

ELEC-167  
REV. DATE: 04-08-10



ELECTRICAL DETAIL  
X-RAY MAIN DISCONNECT PANEL

ELEC-15  
REV. DATE: 09.Mar.15



RELEASE FOR CONSTRUCTION AS NOTED ON PLANS REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI

07/28/2021

Healthcare Project Implementation - Design Center  
Milwaukee, Wisconsin



GE Healthcare

SHEET TITLE: ELECTRICAL DETAILS  
MODALITY TYPE: OPTIMA XR646

THIS PLAN IS SUBMITTED TO SURVEY LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS. ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM TO THE LOCAL, STATE AND FEDERAL REGULATIONS AND STANDARDS. THE USER OF THIS PLAN SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:

1-150f  
TYPICAL FINAL

PROJECT	REVISION
1-150f	03

DATE: 09.Sep.16  
DRAWN BY: JDR  
CHECKED BY: REK

REVISION HISTORY:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

SHEET  
E4

PIM R5  
RQ - 163687





PROJECT	REVISION
1-150f	03

DATE: 09.Sep.16  
DRAWN BY: JDR  
CHECKED BY: REK

REVISION HISTORY:


SHEET  
D1

PIM R5  
RQ - 163687

### EQUIPMENT DETAIL

#### XT RADIOGRAPHIC SUSPENSION, INBOARD MOUNTING

**B2020**  
REV. DATE: 18.Nov.14

TOP BOLTS ONLY CAN BE USED ON INBOARD SYSTEM.  
.75" [19mm] DIA. HOLES  
1.06" [27mm]  
2.5" [64mm]  
3.3" [84mm] 5mm PLATE  
4" MAX. [102mm]  
26" - TYPICAL [660mm]  
162" TO 228" (\* see note) [4115mm]  
2.16" [55mm]  
THE STATIONARY RAIL CAN BE CUT TO SUIT CONDITIONS AT THE SITE. WHEN CUTTING THE RAIL THE LAST BOLT HOLE MUST NOT BE MORE THAN FOUR INCHES FROM THE END OF THE RAIL. A NEW HOLE SHOULD BE DRILLED IF NECESSARY.

2M MIN. 18.5" [470mm]  
3M MIN. 34.75" [883mm] (\* see note)  
3M REC. 37.4" [950mm]  
4" MIN. [102mm]  
1.19" [30mm]  
56" (\* see note) [1422mm]  
162" TO 228" (\* see note) [4115mm]  
5791mm  
2" MIN. [51mm]  
2" MIN. [51mm]  
5mm PLATE ON EACH SIDE OF THE RAIL, USED FOR BUMPERS

\* STANDARD DIMENSION, REFER TO GE SITE SPECIFIC PREINSTALLATION DRAWINGS (IF AVAILABLE) FOR ACTUAL DIMENSION.

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### XR656 G2(PLUS)/XR646 IMAGE PASTE BARRIER

**B05-57Y**  
REV. DATE: 29.JAN.15

43.72" [1110.4mm]  
6.7" [170mm]  
10.5" [267mm] WITH STEP  
81.5" [2070mm]

PLAN VIEW  
FRONT VIEW  
SIDE VIEW

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### DIGITAL ELEVATING RADIOGRAPHIC TABLE

**B0557V**  
REV. DATE: 28.Oct.14

94.5" [2400mm]  
70.1" [1780mm]  
36.7" [933mm]  
28.1" [713mm]  
36.4" [923mm]  
13.2" [335mm]  
22.8" [580mm]  
121.26" [3080mm]  
47.7" [1212mm]

FRONT VIEW  
SIDE VIEW  
PLAN VIEW

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### SYSTEM CABINET

**B8125**  
REV. DATE: 05.Dec.11

9.86" [250.5mm]  
3.86" [98mm]  
9.17" [232.9mm]  
26" [662.2mm]  
9.45" [240mm]  
8.73" [221.72mm]  
6.1" [155mm]  
58" [1475mm]  
55.1" [1400mm]  
10.76" [273.4mm]  
6.1" [155mm]  
8.6" [217.9mm]  
3.27" [83mm]  
3.27" [83mm]  
23.57" [598.8mm]  
8.7" [220mm]  
27.83" [707mm]  
8.7" [220mm]  
8.7" [220mm]  
23.57" [598.8mm]

PLAN VIEW  
RIGHT SIDE VIEW  
FRONT VIEW  
LEFT SIDE VIEW

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### XR646 HEAT OUTPUTS BY COMPONENT

**B8138B**  
REV. DATE: 03.Nov.14

PRODUCT OR COMPONENT	HEAT OUTPUT			
	STANDBY		IN-USE	
	BTU/h	Kilowatt	BTU/h	Kilowatt
Wall Stand Detector power	56	0.017	56	0.017
Wall Stand / Extended Wall Stand	79	0.023	321	0.094
Table Detector Power	56	0.017	56	0.017
Table	315	0.092	2272	0.666
OTS & Collimator	105	0.031	105	0.031
Tube Rotor	0	0	544	0.160
System Cabinet	2437	0.714	4869	1.427
2420 PC + Monitor	601	0.176	863	0.253
TIB	6.75	0.002	68	0.020
UPS	31.61	0.009	45.45	0.013

### EQUIPMENT DETAIL

#### EQUIPMENT SHIPPING DETAIL

**B6566F**  
REV. DATE: 03.Nov.14

SHIPPING DIMENSIONS AND WEIGHTS - DOMESTIC SHIPMENTS				
LENGTH IN [MM]	WIDTH IN [MM]	HEIGHT IN [MM]	lbs [kg]	
SHIPPING DIMENSIONS (APPROX) - DETECTOR ASSEMBLY				
41 [1042]	47 [1194]	29 [737]	194 [88]	CRATE/SKID
SHIPPING DIMENSIONS (APPROX) - TABLE ASSEMBLY				
95 [2400]	44 [1100]	51 [1300]	882 [400]	BOX/SKID
SHIPPING DIMENSIONS (APPROX) - TABLE ASSEMBLY IN TRANSIT				
95 [2400]	44 [1100]	24.8 [630]	NA	DOLLY
SHIPPING DIMENSIONS (APPROX) - STRETCHER NON-ELEVATING				
91 [2312]	41 [1042]	37 [940]	360 [164]	BOX/SKID
SHIPPING DIMENSIONS (APPROX) - STRETCHER CARBON FIBER NON-ELEVATING				
90.5 [2300]	30 [770]	9 [230]	154 [70]	CRATE
SHIPPING DIMENSIONS (APPROX) - STRETCHER ELEVATING				
99 [2515]	37 [920]	32 [810]	772 [350]	CRATE/SKID
SHIPPING DIMENSIONS (APPROX) - EXAM ROOM LEAN CART				
84 [2134]	30 [762]	60 [1524]	VARIES	WHEELED CART
SHIPPING DIMENSIONS (APPROX) - CONTROL & OPTIONS LEAN CART				
51.5 [1308]	30 [762]	55 [1397]	VARIES	WHEELED CART
SHIPPING DIMENSIONS (APPROX) - DETECTOR BIN				
21.3 [540]	14.2 [360]	4.7 [120]	33 [15]	BOX
SHIPPING DIMENSIONS (APPROX) - OVERHEAD TUBE SUSPENSION (OTS)				
34 [864]	41 [1039]	53.4 [1355]	635 [288]	CRATE

### EQUIPMENT DETAIL

#### EQUIPMENT SHIPPING DETAIL

**B6566E**  
REV. DATE: 03.Nov.14

SHIPPING DIMENSIONS AND WEIGHTS - DOMESTIC SHIPMENTS				
LENGTH IN [MM]	WIDTH IN [MM]	HEIGHT IN [MM]	lbs [kg]	
SHIPPING DIMENSIONS (APPROX) - 4 METER RAIL, SET OF TWO				
173.23 [4400]	2.46 [62.5]	3.2 [84.3]	106 [48]	BOX
SHIPPING DIMENSIONS (APPROX) - 12 METER RAIL, SET OF TWO (3 X 4M RAIL)				
173.23 [4400]	2.46 [62.5]	9.96 [253]	318 [144]	BOX
SHIPPING DIMENSIONS (APPROX) - 2 METER BRIDGE WITH OTS				
87 [2210]	29 [737]	7 [178]	701.1 [318]	BOX/CRATE/SKID
SHIPPING DIMENSIONS (APPROX) - 3 METER BRIDGE WITH OTS				
122 [3099]	29 [737]	7 [178]	726.9 [329.7]	BOX
SHIPPING DIMENSIONS (APPROX) - CABLE DRAPE RAIL AND SUPPORT				
32 [813]	23 [584]	9 [229]	182 [82.5]	BOX/SKID
SHIPPING DIMENSIONS (APPROX) - SYSTEM CABINET				
35.8 [910]	30.7 [780]	65 [1650]	705 [320]	BOX
SHIPPING DIMENSIONS (APPROX) - SYSTEM CABINET IN TRANSIT				
34.65 [880]	30 [760]	65.4 [1660]	NA	SKID
SHIPPING DIMENSIONS (APPROX) - SYSTEM CABINET HARDWARE				
27.8 [707]	26 [662]	58 [1475]	672.4 [305]	BOX/SKID
SHIPPING DIMENSIONS (APPROX) - WALL STAND				
96 [2440]	37 [940]	50 [1270]	1023 [464]	CRATE/SKID
SHIPPING DIMENSIONS (APPROX) - EXTENDED WALL STAND				
96 [2440]	37 [940]	65 [1651]	1087 [493]	CRATE/SKID

### EQUIPMENT DETAIL

#### OPERATORS CONSOLE

**CG10CB**  
REV. DATE: 12.Apr.11

6.6" [167.9mm]  
15.2" [387mm]  
7.1" [180mm]  
17.7" [450.2mm]  
19.9" [504mm]  
17.9" [455.3mm]  
17.8" [451mm]  
5.3" [135mm]  
RCIM  
KEYBOARD  
MOUSE

PC TOWER HP Z400  
FLAT PANEL MONITOR

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### DONGLE

**B8137**  
REV. DATE: 03/31/11

5.24" [133mm]  
3.82" [97mm]  
0.79" [20mm]  
2.46" [62.5mm]  
1.89" [48mm]

FRONT VIEW  
SIDE VIEW  
PLAN VIEW

WALL ANCHORS

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### TIB

**B8126**  
REV. DATE: 03/30/11

8.77" [223mm]  
1.96" [50mm]  
5.7" [145mm]  
10.03" [255mm]  
12.2" [310mm]  
10.86" [276mm]

PLAN VIEW  
FRONT VIEW  
SIDE VIEW

WALL ANCHOR, TYP.

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### DIGITAL CHEST READER WITH EXTENDED RECEPTOR

**B05-57Z**  
REV. DATE: 10.DEC.14

49.61" [1260mm]  
11.54" [293mm]  
91.54" [2325mm]  
10.47" [266mm]  
1.34" [34mm]  
18.58" [472mm]  
51.89" [1318mm]  
41.65" [1058mm]  
59.06" [1500mm]  
24.26" [612mm]  
20.48" [520mm]  
15.81" [400mm]  
19.21" [488mm]  
10.24" [260mm]  
19.21" [488mm]

PLAN VIEW  
FRONT VIEW  
SIDE VIEW

MAXIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 70.26" [1785mm]  
MAXIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 70.28" [1785mm]  
MINIMUM HEIGHT TO THE TOP OF DETECTOR HOUSING 78.27" [1988mm]  
MINIMUM HEIGHT TO THE TOP OF DETECTOR HOUSING 78.27" [1988mm]  
MINIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 11.2" [285mm]  
MINIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 11.2" [285mm]

DETAIL NOT TO SCALE

### EQUIPMENT DETAIL

#### DIGITAL CHEST READER

**B05-57F**  
REV. DATE: 10.DEC.14

36.85" [936mm]  
11.54" [293mm]  
91.54" [2325mm]  
10.47" [266mm]  
1.34" [34mm]  
18.58" [472mm]  
39.13" [994mm]  
28.9" [734mm]  
59.06" [1500mm]  
24.26" [612mm]  
20.48" [520mm]  
15.81" [400mm]  
19.21" [488mm]

PLAN VIEW  
FRONT VIEW  
SIDE VIEW

MAXIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 70.26" [1785mm]  
MINIMUM HEIGHT TO THE TOP OF DETECTOR HOUSING 78.27" [1988mm]  
MINIMUM HEIGHT TO THE TOP OF DETECTOR HOUSING 78.27" [1988mm]  
MINIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 11.2" [285mm]  
MINIMUM HEIGHT TO THE CENTER OF DETECTOR HOUSING 11.2" [285mm]


DETAIL NOT TO SCALE





EQUIPMENT DETAIL  
 GRID HOLDER


B05-57W  
 REV. DATE: 05/26/10



DETAIL NOT TO SCALE

EQUIPMENT DETAIL  
 DETECTOR BIN


B8127  
 REV. DATE: 03/30/11



DETAIL NOT TO SCALE

EQUIPMENT DETAIL  
 SUINSA FLEXI-DT MOBILE TABLE


B0557L  
 REV. DATE: 17.DEC.14



DETAIL NOT TO SCALE

EQUIPMENT DETAIL  
 MOBILE TABLE


B05-57K  
 REV. DATE: 06/07/10



DETAIL NOT TO SCALE

EQUIPMENT DETAIL  
 CARBON FIBER TABLE

B5000A  
 REV. DATE: 02/12/07



DETAIL NOT TO SCALE

SHEET TITLE: EQUIPMENT DETAILS

MODALITY TYPE: OPTIMA XR646

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE MANUFACTURER'S DRAWINGS AND TO THE USER'S REQUIREMENTS. GE HEALTHCARE ACCEPTS NO LIABILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:

1-150f  
 TYPICAL FINAL

PROJECT	REVISION
1-150f	03
DATE:	09.Sep.16
DRAWN BY:	JDR
CHECKED BY:	REK

REVISION HISTORY:

SHEET  
 D2

RQ - 163687 PIM R5





**St Lukes Hospital of Kansas City  
Kansas City, Missouri  
USA**

A	30/Jun/2021	Final drawing based on DC-304460; Original GON 4760566
REV	DATE	MODIFICATIONS

- 01 - C1 - Cover Sheet
- 02 - C2 - Disclaimer - Site Readiness
- 03 - A1 - General Notes
- 04 - A2 - Equipment Layout
- 05 - A3 - Section Views
- 06 - A4 - Equipment Details & Delivery
- 07 - S1 - Structural Notes
- 08 - S2 - Structural Layout
- 09 - S3 - Structural Details (1)

- 10 - S4 - Structural Details (2)
- 11 - M1 - HVAC
- 12 - E1 - Electrical Notes
- 13 - E2 - Electrical Layout
- 14 - E3 - Electrical Elevations
- 15 - E4 - Details-Interconnections
- 16 - E5 - Power Requirements



**GE Healthcare**

Cody Ayers  
913-251-0235  
Cody.ayers@ge.com

**OPTIMA XR646  
FINAL STUDY**

A mandatory component of this drawing set is the GE Healthcare Pre Installation manual. Failure to reference the Pre Installation manual will result in incomplete documentation required for site design and preparation.  
Pre Installation documents for GE Healthcare products can be accessed on the web at: [www.gehealthcare.com/siteplanning](http://www.gehealthcare.com/siteplanning)

GE does not take responsibility for any damages resulting from changes on drawings made by others. Errors may occur by not referring to the complete set of final issue drawing. GE cannot accept responsibility for any damage due to the partial use of GE final issue drawings, however caused. All dimensions are in millimeters unless otherwise specified. Do not scale from printed pdf files. GE accepts no responsibility or liability for defective work due to scaling from these drawings.

Drawn by	Verified by	Concession	S.O. (GON)	PIM Manual	Rev
ENW	ENW	-	Room Move	5643854-1EN	9
Format	Scale	File Name		Date	Sheet
A3	1/4"=1'-0"	RAD-M244849-FIN-00-A.DWG		30/Jun/2021	01/16



## DISCLAIMER

### GENERAL SPECIFICATIONS

- GE is not responsible for the installation of developers and associated equipment, lighting, cassette trays and protective screens or derivatives not mentioned in the order.
- The final study contains recommendations for the location of GE equipment and associated devices, electrical wiring and room arrangements. When preparing the study, every effort has been made to consider every aspect of the actual equipment expected to be installed.
- The layout of the equipment offered by GE, the dimensions given for the premises, the details provided for the pre-installation work and electrical power supply are given according to the information noted during on-site study and the wishes expressed by the customer.
- The room dimensions used to create the equipment layout may originate from a previous layout and may not be accurate as they may not have been verified on site. GE cannot take any responsibility for errors due to lack of information.
- Dimensions apply to finished surfaces of the room.
- Actual configuration may differ from options presented in some typical views or tables.
- If this set of final drawings has been approved by the customer, any subsequent modification of the site must be subject to further investigation by GE about the feasibility of installing the equipment. Any reservations must be noted.
- The equipment layout indicates the placement and interconnection of the indicated equipment components. There may be local requirements that could impact the placement of these components. It remains the customer's responsibility to ensure that the site and final equipment placement complies with all applicable local requirements.
- All work required to install GE equipment must be carried out in compliance with the building regulations and the safety standards of legal force in the country concerned.
- These drawings are not to be used for actual construction purposes. The company cannot take responsibility for any damage resulting therefrom.

### CUSTOMER RESPONSIBILITIES

- It is the responsibility of the customer to prepare the site in accordance with the specifications stated in the final study. A detailed site readiness checklist is provided by GE. It is the responsibility of the customer to ensure all requirements are fulfilled and that the site conforms to all specifications defined in the checklist and final study. The GE Project Manager of Installation (PMI) will work in cooperation with the customer to follow up and ensure that actions in the checklist are complete, and if necessary, will aid in the rescheduling of the delivery and installation date.
- Prior to installation, a structural engineer of record must ensure that the floor and ceiling is designed in such a way that the loads of the installed system can be securely borne and transferred. The layout of additional structural elements, dimensioning and the selection of appropriate installation methods are the sole responsibility of the structural engineer. Execution of load bearing structures supporting equipment on the ceiling, floor or walls are the customer's responsibility.

### RADIO-PROTECTION

- Suitable radiological protection must be determined by a qualified radiological physicist in conformation with local regulations. GE does not take responsibility for the specification or provision of radio-protection.

<b>THE UNDERSIGNED, HEREBY CERTIFIES THAT I HAVE READ AND APPROVED THE PLANS IN THIS DOCUMENT.</b>		
<b>DATE</b>	<b>NAME</b>	<b>SIGNATURE</b>

## GLOBAL SITE READINESS CHECKLIST (DI)

DOC1809666 Rev. 7

RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

07/08/2021

Site Ready Checks at Installation
EHS Site Requirements
Overall access route to the scan room free from obstruction / high hazards.
Enough space to store tools, equipment, parts, install waste and the general area free from obstruction and trip hazards.
Enough necessary facilities for the GE employees available.
No 3rd parties working in the area that may affect the safety of the installation activity.
Area free from any chemical, gas, dust, welding fume exposure and has painting been completed and dry.
All emergency routes identified, signed and clear from obstruction.
Accessible single source lockable panel that LOTO can be applied to for GE equipment installation (MDP and/or PDU).
There are no other conditions or hazards that you have observed or have been made aware of by the customer or contractors on site.
Required for Mechanical Install start
Room dimensions, including ceiling height, for all Exam, Equipment/Technical & Control rooms meets GE specifications.
Ceiling support structure, if indicated on the GE drawing, is in the correct location and at the correct height according to the Original Equipment Manufacturer specifications.
Levelness and spacing has been measured, and is ready for the installation of any GE supplied components.
Overhead support Structure (unistrut) has been confirmed with customer/contractor to meet required GE provided criteria.
Finished ceiling is installed. If applicable ceiling tiles installed per PMI discretion.
Floor levelness/flatness is measured and within tolerance, and there are no visible defects per GEHC specifications.
Entry door threshold meets PIM requirement.
Rooms that will contain equipment, including staging areas if applicable, are construction debris free. Precautions must be taken to prevent debris from entering rooms containing equipment.
Cable ways (floor/wall/ceiling/Access Flooring) are available for installation of GE cables are of correct length and diameter.
Cable ways routes per GE Final drawings and cable access openings areas installed at a time determined by GEHC PM. Surface floor duct can be installed at time of system installation.
Adequate room illumination installed and working.
Customer supplied countertops where GE equipment will be installed are in place.
Required for Calibration Start
HVAC systems Installed, and the site meets minimum environmental operational system requirements.
System power & grounding (PDB/MDP) is available as per GE specifications.
System power & grounding (PDB/MDP) is installed at point of final connection and ready to use. Lock Out Tag Out is available.
PMI to confirm all feeder wires and breaker are size appropriately. EPO installed if needed.
PMI to confirm with electrician all power and signal cables are well terminated ensuring there are no loose connections.
Network outlets installed.
Computer network available and working.
Lead doors and windows complete or scheduled to be installed. If applicable, radiation protection (shielding) finished & radioprotection regulatory approval for installation obtained.

Note: The details shown here are only an extract from DOC1809666. For the complete document please contact your PMI.



## CUSTOMER SITE READINESS REQUIREMENTS

- Any deviation from these drawings must be communicated in writing to and reviewed by your local GE healthcare installation project manager prior to making changes.
- Make arrangements for any rigging, special handling, or facility modifications that must be made to deliver the equipment to the installation site. If desired, your local GE healthcare installation project manager can supply a reference list of rigging contractors.
- New construction requires the following;
  1. Secure area for equipment,
  2. Power for drills and other test equipment,
  3. Capability for image analysis,
  4. Restrooms.
- Provide for refuse removal and disposal (e.g. crates, cartons, packing)
- It is the customer's responsibility to contract a vibration consultant/engineer to implement site design modifications to meet the GE vibration specification. Refer to the system preinstallation manual for the vibration specification.

## ENVIRONMENTAL SPECIFICATIONS

### MAGNETIC INTERFERENCE

In order to avoid interference on the system, static field limits from the surrounding environment must be less than <1 Gauss around the unit.

### LIGHT REQUIREMENTS

For the electronic ballast of fluorescent lamp in exam room, the operating frequency should be above 42 kHz.

### ACOUSTIC OUTPUT

Measured 1 m [3.28 ft] from any point in system.


In-use: less than 55 dBA

Stand-by: less than 55 dBA

RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

07/08/2021





LEGEND

A	GE Supplied	D	Available from GE
B	GE Supplied/contractor installed	E	Equipment existing in room
C	Customer/contractor supplied and installed	*	Item to be reinstalled from another site

BY	ITEM	DESCRIPTION	MAX HEAT OUTPUT (btu)	WEIGHT (lbs)
*A	1	Standard Table	2272	680
*A	2	Systems Cabinet	4869	705
*A	3	Manual Wall Stand	321	530
*A	4	Tether Interface Box	68	15.4
*A	5	Dongle	-	1.76
*A	6	Grid Holder	-	30.5
*A	7	Operators Console	863	43.2
*A	8	Partial UPS	350	26
*A	9	Wall Box	-	-
*A	10	Cable Drape Rail	-	65
*A	11	Longitudinal Stationary Rail for OTS	-	138
*A	12	OTS with 3m Bridge	1500	900
*B	13	Main Disconnect Panel	-	-
C	14	Minimum opening for equipment delivery is 36 in. w x 66.9 in. h, contingent on a 96 in. corridor width (Note: Image Paste option requires an 80.9 in H opening)		
C	15	Counter top for equipment- provide grommeted openings as required to route cables		
C	16	Control wall to ceiling with lead glass viewing window		

The following shots are NOT available in this layout

Rear to front cross table shot

Exam room height

Finished floor to slab height	-
Recommended finished ceiling height	9'-6"


Room Move Note:

Equipment shown on drawing is being relocated/ reinstalled from another location. All equipment must be verified for accuracy by GE PMI or Field Engineer.



07/08/2021

**SIDE VIEW A-A'**




**EXAM ROOM CEILING HEIGHTS**

**RECOMMENDED AND MINIMUM ROOM HEIGHTS**

CONFIGURATION	SPECIFICATIONS	CEILING HEIGHT	
2M or 3M Bridge	Recommended	2986 mm	117.6 in
2M or 3M Bridge	Minimum	2686 mm	105.75 in
2M or 3M Bridge with Extended Wallstand at Foot Position	Minimum	2750 mm	108.27 in

Note : measured from the floor to the top of the longitudinal rails


**FRONT VIEW B-B'**





## CLEARANCE AREAS

### MANUAL WALLSTAND WITH STANDARD TABLE



SCALE 1:50

## DELIVERY

### THE CUSTOMER/CONTRACTOR SHOULD:

- Provide an area adjacent to the installation site for delivery and unloading of the GE equipment.
- Ensure that the dimensions of all doors, corridors, ceiling heights are sufficient to accommodate the movement of GE equipment from the delivery area into the definitive installation room.
- Ensure that access routes for equipment will accommodate the weights of the equipment and any transportation, lifting and rigging equipment.
- Ensure that all necessary arrangements for stopping and unloading on public or private property not belonging to the customer have been made.

### DIMENSIONS OF DELIVERY IN TRANSIT


EQUIPMENT	DIMENSIONS			WEIGHT	
	LENGTH	WIDTH	HEIGHT		
MANUAL WALLSTAND	LENGTH	1999 mm	78.7 in	240 kg + dolly	530 lbs + dolly
	WIDTH	911 mm	35.9 in		
	HEIGHT	1840 mm	72.4 in		
STANDARD TABLE	LENGTH	1319 mm	51.9 in	267.5 kg + dolly	589.7 lbs + dolly
	WIDTH	833 mm	32.8 in		
	HEIGHT	570 mm	24.5 in		

Pay attention to the lengths of the rails! They can also be 5.79 m [19 ft] and have a shipping dimension of 5.92 m x 178 mm x 76 mm [16'-10" x 7" x 3"].

## DONGLE POSITIONING

### DONGLE DEFAULT LOCATION AND ADJUSTING RANGE:

- Dongle shall be positioned at the wall of detector insertion direction.
- B is the best position which is in the middle of the wall.
- The height requirement of dongle is 30 cm [11.8 in] lower than the ceiling.
- Position "A" to "C" (around  $\pm 1$  m [ $\pm 39.4$  in]) are acceptable locations for dongle.
- There shall be no obstructions in the path between dongle and detector applications.





## STRUCTURAL NOTES

- Methods of support for the steelwork that will permit attachment to structural steel or through bolts in concrete construction should be favored. Do not use concrete or masonry anchors in direct tension.
- All units that are wall mounted or wall supported are to be provided with supports where necessary. Wall supports are to be supplied and installed by the customer or his contractors. See plan for suggested locations.
- Control walls shall be constructed to minimum 2130mm (7'-0") high.
- Dimensions are to finished surfaces of room.
- Customers contractor must provide all penetrations in post tension floors.
- Customers contractor must provide and install any non-standard anchoring. Documents for standard anchoring methods are included with GE equipment drawings for geographic areas that require such documentation.
- Customers contractor must provide and install hardware for "through the floor" anchoring and/or any bracing under access floors. This contractor must also provide floor drilling that cannot be completed because of an obstruction encountered while drilling by the GE installer such as rebar etc.
- It is the customer's responsibility to perform any floor or wall penetrations that may be required. The customer is also responsible for ensuring that no subsurface utilities (e.g., electrical or any other form of wiring, conduits, piping, duct work or structural supports (i.e. post tension cables or rebar)) will interfere or come in contact with subsurface penetration operations (e.g. drilling and installation of anchors/screws) performed during the installation process. To ensure worker safety, GE installers will perform surface penetration operations only after the customer's validation and completion of the "GE surface penetration permit".
- Different anchor types are used to install the components of the system. Refer to Structural Requirements Section(s) of the Pre-Installation Manual for each anchor requirement.
- Refer to the Structural Requirements Section for the required minimum embedment.
- The ground surface must be flat and leveled, maximum tolerance for leveling is  $\pm 1.5$  mm per 1 m (0.2 in per 10 feet). A grout pad provided by the contractor is required to meet this specification. The maximum pad thickness is 6.3 mm (0.25 in).

## CEILING REQUIREMENTS

To allow installation of the stationary rail cross-members, clearance is required between the ends of the stationary rails and the walls.

It is recommended that sprinkler heads not be placed between the stationary rails. All sprinkler heads should be mounted so they do not extend downward more than 6.35 mm [1/4 in] from the ceiling while in the 'resting' position.

In addition, there should not be anything mounted in the ceiling (i.e. lights, A/C returns, etc) between the stationary rails. This is because the OTS longitudinal drive belt assembly is located on the movable bridge, approximately centered between the two stationary rails, and may come into contact with those ceiling-mounted items during normal use.


Stationary rails are designed for top (ceiling) mounting. Rails can be ordered and are supplied in the following sizes:

- |                         |                         |
|-------------------------|-------------------------|
| - 4115 mm [13 ft 6 in]  | - 5131 mm [16 ft 10 in] |
| - 4318 mm [14 ft 2 in]  | - 5334 mm [17 ft 6 in]  |
| - 4521 mm [14 ft 10 in] | - 5537 mm [18 ft 2 in]  |
| - 4724 mm [15 ft 6 in]  | - 5791 mm [19 ft]       |
| - 4928 mm [16 ft 2 in]  |                         |

The choice of length depends on room size, configuration and the possible presence of obstructions.



ITEM	DESCRIPTION
(GE SUPPLIED / CONTRACTOR INSTALLED)	
1	Area occupied by GE supplied table baseplate
2	Area occupied by GE supplied wall stand baseplate
(CONTRACTOR SUPPLIED & INSTALLED)	
3	Support backing, locate as shown.
4	Structural support in ceiling for fastening ceiling supported equipment. Supports to run continuous with no fittings extending below face of channel, run wall to wall, be parallel, square, and in the same horizontal plane, flush with the finished ceiling. Rails are mounted to these supports every 2'-2" and require 350 lbs. (597 lbs. In seismic regions) per bolt load. Methods of support that permit attachment to structural steel or through bolts in concrete should be favored. Do not use screw anchors in direct tension.
5	Structural support in ceiling for fastening cable drape rail. Supports to run continuous with no fittings extending below face of channel, run wall to wall, be parallel, square, and in the same horizontal plane, flush with the finished ceiling. Rails are mounted to these supports every 2'-2" and require 50 lbs. Per bolt load. Methods of support that permit attachment to structural steel or through bolts in concrete should be favored. Do not use screw anchors in direct tension.






07/08/2021

## TABLE ANCHORING

### STANDARD TABLE STAND



The floor bearing the system is recommended to be concrete and the thickness to be determined by a Structural Engineer to properly support the equipment loads. The supplied anchors require a minimum embedment of 90 mm [3.5 in] into the concrete. If the floor thickness is less than 95 mm [3.7 in], it is recommended that the unit be secured using a through-bolt method with a reinforcement plate on the back side.

SCALE 1:20

## OTS SUSPENSION RAILS MOUNTING SPECIFICATIONS

### 3 m BRIDGE

When a 22.7 kg [50 lb] force is applied vertically upward, downward or horizontally at any support rail mounting point, the attachment interface must not deflect more than 1.5 mm [1/16 in]


When a 136 kg [330 lb] load is applied vertically downward or horizontally at any stationary rail mounting point, the attachment interface must not deflect more than 1.5 mm [1/16 in]

660.4 ±1.5 mm [26 ±1/16 in]

Cable takeup support rail mounting points

Stationary rail mounting points must be parallel within ±3 mm [±1/8 in]


When a 45.4 kg [100 lb] force is applied vertically upward at any stationary rail mounting point, the attachment interface must not deflect more than 1.5 mm [1/16 in]



Distance between holes axis 660.4 mm [26 in], Maximum load per screw is 160 kg [353 lb], however each mounting screw must not "PULL OUT" or otherwise fail under a vertically downward dead load of 635 kg [1400 lb]. Bolts for mounting stationary rails on Unistrut or equivalent supplied by GE (1/2" - 13 headed bolts)

## WALLSTAND ANCHORING


### WALLSTAND BASE



Concrete area for wall stand installation should be 1 m<sup>2</sup> [39.37 ft<sup>2</sup>].

SCALE 1:10

## FOCAL SPOT TRAVEL WITH 3M BRIDGE




NOT TO SCALE Note: Focal Spot Travel depends on the length of the bridge, rails and position of bridge.



# XT RADIOGRAPHIC SUSPENSION, INBOARD MOUNTING


RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

07/08/2021




Structural Support system is not supplied or installed by GE Healthcare

## DETAIL 1



## DETAIL 2





# TEMPERATURE AND HUMIDITY SPECIFICATIONS

**RELEASE FOR  
CONSTRUCTION**  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

07/08/2021

## IN-USE CONDITIONS

	EXAM ROOM		CONTROL ROOM	
	Min	Max	Min	Max
Temperature	15°C [59°F]	35°C [95°F]	15°C [59°F]	35°C [95°F]
Temperature gradient	< 10°C/h [< 50°F/h]		< 10°C/h [< 50°F/h]	
Relative humidity (1)	30% to 60%		30% to 60%	
Humidity gradient	< 30%/h		< 30%/h	

## STORAGE CONDITIONS

Temperature	-5°C [23°F] to +50°C [122°F]
Temperature gradient	< 20°C/h [< 68°F/h]
Relative humidity (1)	10% to 85%
Humidity gradient	< 30%/h

Storage longer than 90 days is not recommended.

(1) Non-condensing

## AIR RENEWAL

According to local standards.

### NOTE

In case of using air conditioning systems that have a risk of water leakage it is recommended not to install it above electric equipment or to take measures to protect the equipment from dropping water.

# HEAT DISSIPATION DETAILS

ROOM	DESCRIPTION	HEAT DISSIPATION (kW)		HEAT DISSIPATION (BTU/hr)	
		STANDBY	IN-USE	STANDBY	IN-USE
Exam Room	Table (Standard/G2)	0.092	0.666	315	2272
	Table Detector power	0.017	0.017	56	56
	Wall Stand (Standard/Extended/Manual)	0.023	0.094	79	321
	WS Detector power	0.017	0.017	56	56
	System Cabinet	0.714	1.427	2437	4869
	OTS & Collimator	0.031	0.031	106	106
	Tube Rotor	0	0.160	0	544
	TIB	0.002	0.020	6.75	68
	<b>TOTAL</b>	<b>0.896</b>	<b>2.432</b>	<b>3055.8</b>	<b>8292.0</b>
Control Room	PC and Monitor	0.176	0.253	601	863
	UPS	0.009	0.013	31.61	45.45
	<b>TOTAL</b>	<b>0.185</b>	<b>0.266</b>	<b>632.6</b>	<b>908.5</b>



## CONNECTIVITY REQUIREMENTS

Broadband Connections are necessary during the installation process and going forward to ensure full support from the Engineering Teams for the customers system. Maximum performance and availability for the customers system is maintained and closely monitored during the lifetime of the system. Proactive and reactive maintenance is available utilising the wide range of digital tools using the connectivity solutions listed below:

- Site-to-Site VPN/GE Solution
- Site-to-Site VPN/Customer Solution
- Connection through Dedicated Service Network
- Internet Access - connectivity for InSite 2.0

The requirements for these connectivity solutions are explained in the broadband solutions catalogue (separate document).

## ELECTRICAL NOTES

RELEASE FOR  
CONSTRUCTION  
AS NOTED ON PLANS REVIEW  
DEVELOPMENT SERVICES  
LEE'S SUMMIT, MISSOURI

07/08/2021

1. All wires specified shall be copper stranded, flexible, thermo-plastic, color coded, cut 10 foot long at outlet boxes, duct termination points or stubbed conduit ends. All conductors, power, signal and ground, must be run in a conduit or duct system. Electrical contractor shall ring out and tag all wires at both ends. Wire runs must be continuous copper stranded and free from splices.
  - 1.1. Aluminum or solid wires are not allowed.
2. Wire sizes given are for use of equipment. Larger sizes may be required by local codes.
3. It is recommended that all wires be color coded, as required in accordance with national and local electrical codes.
4. Conduit sizes shall be verified by the architect, electrical engineer or contractor, in accordance with local or national codes.
5. Convenience outlets are not illustrated. Their number and location are to be specified by others. Locate at least one convenience outlet close to the system control, the power distribution unit and one on each wall of the procedure room. Use hospital approved outlet or equivalent.
6. General room illumination is not illustrated. Caution should be taken to avoid excessive heat from overhead spotlights. Damage can occur to ceiling mounting components and wiring if high wattage bulbs are used. Recommend low wattage bulbs no higher than 75 watts and use dimmer controls (except MR). Do not mount lights directly above areas where ceiling mounted accessories will be parked.
7. Routing of cable ductwork, conduits, etc., must run direct as possible otherwise may result in the need for greater than standard cable lengths (refer to the interconnection diagram for maximum usable lengths point to point).
8. Conduit turns to have large, sweeping bends with minimum radius in accordance with national and local electrical codes.
9. A special grounding system is required in all procedure rooms by some national and local codes. It is recommended in areas where patients might be examined or treated under present, future, or emergency conditions. Consult the governing electrical code and confer with appropriate customer administrative personnel to determine the areas requiring this type of grounding system.
10. The maximum point to point distances illustrated on this drawing must not be exceeded.
11. Physical connection of primary power to GE equipment is to be made by customers electrical contractor with the supervision of a GE representative. The GE representative would be required to identify the physical connection location, and insure proper handling of GE equipment.
12. GEHC conducts power audits to verify quality of power being delivered to the system. The customer's electrical contractor is required to be available to support this activity.

- All junction boxes, conduit, duct, duct dividers, switches, circuit breakers, cable tray, etc., are to be supplied and installed by customers electrical contractor.
- Conduit and duct runs shall have sweep radius bends
- Conduits and duct above ceiling or below finished floor must be installed as near to ceiling or floor as possible to reduce run length.
- Ceiling mounted junction boxes illustrated on this plan must be installed flush with finished ceiling.
- All ductwork must meet the following requirements:
  1. Ductwork shall be metal with dividers and have removable, accessible covers.
  2. Ductwork shall be certified/rated for electrical power purposes.
  3. Ductwork shall be electrically and mechanically bonded together in an approved manner.
  4. PVC as a substitute must be used in accordance with all local and national codes.
- All openings in raceway and access flooring are to be cut out and finished off with grommet material by the customers contractor.
- General contractor to insert pull cords for all cable run conduits between the equipment room and the operators control room.
- 10 foot pigtails at all junction points.
- Grounding is critical to equipment function and patient safety. Site must conform to wiring specifications shown on this plan.




**ELECTRICAL LAYOUT ITEM LIST**

1	Main Disconnect Panel
2	Flush box for Control, size per local code
3	Flush box for Chest Unit, size per local code
4	Flush box for Dongle, size per local code
5	Flush box for TIB, size per local code
6	Flush box for Generator, size per local code
7	Box below floor for Table, size per local code with 3" conduit stubbed up thru and cut flush with floor
8	Flush vertical duct, 18" x 3 1/2" with minimum 2 dividers
9	Box above ceiling, size per local code
10	One 2" conduit below floor
11	One 2 1/2" conduit below floor
12	One 1" conduit above ceiling
13	One 1 1/2" conduit above ceiling
14	One 2 1/2" conduit above ceiling


**Room Move Cables Note:**  
 Cable lengths listed may differ from what is included with reinstalled system. Contact the local field engineer for actual lengths to be delivered. Run all conduits straight as possible.

ITEM	QTY	Outlet Legend for GE Equipment
		System emergency off (SEO), (recommended height 1.2m [48"] above floor)
		X-Ray room warning light control panel
		X-Ray ON lamp (L1) - 24V
		Door interlock switch (needed only if required by state/local codes)
		Duplex hospital grade, dedicated wall outlet 120-v, single phase power
		Dedicated telephone line(s)
		Network outlet


Additional Conduit Runs (Contractor Supplied and Installed)				
From	To	Qty	Size	
			In.	mm
3 phase power	Main disconnect	1	AS REQ'D	AS REQ'D
Main disconnect	Emergency off	1	1/2	16
	Systems Cabinet	1	AS REQ'D	AS REQ'D
Warning light	Warning light control	1	1/2	16
1 phase power		1	AS REQ'D	AS REQ'D
Systems Cabinet	Door Switch	1	1/2	16
	TIB	1	2	53
	Dongle	1	1	27
	Operators Console	TIB	1	1
	Dongle	1	2	53









A



C




B



D



## INTERCONNECTIONS




Measured from the front of the bridge


.....m [.....ft] - Long usable length  
 .....m [.....ft] - Standard usable length

## TYPICAL CABLE MANAGEMENT

### CONDUIT BELOW FLOOR



### VERTICAL DUCT ON WALL



NOT TO SCALE



## POWER REQUIREMENTS

POWER SUPPLY	<b>380/400/415/440/460/480V ±10%, THREE-PHASE + G</b>
FREQUENCIES	<b>50/60Hz ± 3Hz</b>
POWER DEMAND	<b>97kVA</b>
MAXIMUM LINE RESISTANCE PER 2 PHASES (Ohm)	<b>380V : 0.118 / 400V : 0.131 / 415V : 0.138 440V : 0.154 / 480V : 0.185</b>

- Power supply should come into a main disconnect panel (MDP) containing the protective units and controls.
- The section of the supply cable should be calculated in accordance with its length and the maximum permissible voltage drops.
- There must be discrimination between supply cable protective material at the beginning of the installation (main low-voltage transformer side) and the protective devices in the MDP.

### SUPPLY CHARACTERISTICS

- Power input must be separated from any others which may generate transients (elevators, air conditioning, radiology rooms equipped with high speed film changers...)
- All equipment (lighting, power outlets, etc...) installed with GE system components must be powered separately.

### GROUND SYSTEM

- Equipotential : the equipotential link will be by means of an equipotential bar. This equipotential bar should be connected to the protective earth conductors in the ducts of the non GE cableways and to additional equipotential connections linking up all the conducting units in the rooms where GE units are located.

### CABLES

- Power and cable installation must comply with the distribution diagram below.
  - All cables must be isolated and flexible.
  - Cable color codes must comply with standards for electrical installation.
- Case MDP furnished by GE : The cables for signals and remote control (SEO, XRL1...) will go to MDP with a pigtail length of 1.5 m (4.9 ft), and will be connected during installation. Each conductor will be identified and isolated (screw connector).

### CABLEWAYS

- The general rules for laying cableways should meet the conditions laid down in current standards and regulations, with regard to:
- Protecting cables against water (cableways should be waterproof)
  - Protecting cables against abnormal temperatures (proximity to heating pipes or ducts)
  - Protecting cables against temperature shocks
  - Replacing cables (cableways should be large enough for cables to be replaced) metal cableways should be grounded.


### FEEDER TABLE

MIN. FEEDER WIRE SIZE, AWG OR MCM (sq. mm)/VAC	MINIMUM FEEDER WIRE LENGTH - ft (m)								
	50 (15)	100 (30)	150 (46)	200 (61)	250 (76)	300 (91)	350 (107)	400 (122)	450 (137)
480 VAC	4 (21)	4 (21)	4 (21)	2 (34)	1 (45)	1/0 (54)	1/0 (54)	2/0 (68)	3/0 (85)

#### GENERAL NOTES

- In all cases qualified personnel must verify that the feeder (at the point of take-off) and the run to the GE system meet all the requirements stated in the PIM
- For a single unit installation, the minimum transformer size is 112.5 kVA, Synthesized power feed is not acceptable
- Grounding conductor will be of the same size as the feeder. This ground will run from the equipment back to the power source/main grounding point and always travel in the same conduit with the feeders

## POWER DISTRIBUTION



- MDP Main Disconnect Panel
- SKL Generator (System Cabinet/VCP Cabinet)
- SEO Emergency OFF button (Control Room), located 1.50m (4.9') above floor
- XRLC Warning Light Control
- XRL1 Warning Light
- DLK1 Door Interlock Switch (needed only if required by state/local codes)






# SAMSUNG GC 85

## S LUKES ROCKHILL

120 NE SAINT LUKE'S BLVD SUITE 200, LEE'S SUMMIT, MO 64086



**CUSTOMER**  
 ALL REQUIREMENTS FOR THIS EQUIPMENT ARE NOT NOTED ON THIS SHEET. IT IS SUGGESTED THAT THESE DRAWINGS BE REVIEWED BY QUALIFIED PROFESSIONALS WHO CAN ASSIST WITH MAKING DECISIONS REGARDING RADIATION CONTAINMENT, MAGNETIC FIELD CONTAINMENT, ELECTRICAL, STRUCTURAL AND MECHANICAL REQUIREMENTS. ALTHOUGH THE EQUIPMENT MAY BE INSTALLED IN AN EXISTING ROOM OF SIMILAR FUNCTION, REQUIREMENTS STILL NEED TO BE CHECKED.

**SITE VISIT**  
 NORMAL PROCEDURE IS TO ATTEND AN INITIAL CONSTRUCTION MEETING AND THEN PERFORM AN INSPECTION OF THE ELECTRICAL BUILD OUT AT OR ABOUT THE SAME TIME AS THE ELECTRICAL ROUGH IN (PRIOR TO SHEETROCK OR LEAD BEING INSTALLED), ADDITIONAL VISITS MAY BE REQUIRED

**RECEIPT OF DRAWING** FINAL/REVIEW  
 THIS SIGNATURE PRINTED OR OTHERWISE REPRESENTS RECEIPT OF THIS SET OF PLANS, IT IS UNDERSTOOD THAT ANY DEVIATION FROM THESE DRAWINGS, DETAILS AND SPECIFICATIONS MAY ENCROACH UPON THE EQUIPMENT OPERATION, SERVICEABILITY, OR SAFETY GUIDELINES. ALSO I AM AWARE THAT ANY CHANGES MADE AFTER 7 June 2021 COULD RESULT IN ADDITIONAL EXPENSES BEING INCURRED IF RADSOURCE IS NOT NOTIFIED IN WRITING i.e. E-MAIL ETC... NEW SHEETS WILL BE ISSUED AS ADDITIONS AND REVISIONS WILL HAVE CURRENT DATES ADDED.

NAME: \_\_\_\_\_ DATE: \_\_\_\_\_  
 PRINTED: \_\_\_\_\_  
 COMPANY: \_\_\_\_\_

NAME: \_\_\_\_\_ DATE: \_\_\_\_\_  
 PRINTED: \_\_\_\_\_  
 COMPANY: \_\_\_\_\_

NAME: \_\_\_\_\_ DATE: \_\_\_\_\_  
 PRINTED: \_\_\_\_\_  
 COMPANY: \_\_\_\_\_

**GENE NOWACZYK**  
 MEP  
 SITE PLANNING &  
 PROJECT DEVELOPMENT  
 OFFICE: 816-741-5558  
 CELL: 816-223-6378  
 FAX: 816-587-2423  
 EMAIL: GNOWACZYK@RADSOURCE.NET  
 8121 N.W. 97TH TERR  
 KANSAS CITY, MISSOURI 64153

**PROJECT**  
**SAMSUNG GC 85**  
 S LUKES ROCKHILL  
 120 NE SAINT LUKE'S BLVD SUITE 200, LEE'S SUMMIT,  
 MO 64086

**ARCHITECT:**  
**BRIAN DOSTAL**  
 p.816.728.1999  
 BDOSTAL@ACIBOLAND.COM  
**ELECTRICAL CONTRACTOR:**  
 p.---  
 m.XXX-XXX-XXXX  
 ---  
**GENERAL CONTRACTOR:**  
 ---  
 p.---  
 m.---  
 ---  
**PROJECT MANAGER FOR CUSTOMER:**  
 ---  
 p.---  
 ---  
**IT MANAGER**  
 XXX  
 p. XXX  
 XXX  
**RADIOLOGY DIRECTOR**  
 ---  
 p.---  
 ---

REVISION:	DATE:

**DRAWN BY:** GENE N.  
**CHKD BY:** A.W.  
**CUSTOMER :**  
**SCALE:** NOTED  
**DATE:** 5/19/2021 9:22:12 AM


**FILE NAME:**  
 Rockhill 2021 Samsung GC85.dwg

**DRAWING SHEET #**  
**COVER**

~ DRAWING INDEX ~

AQ	EQUIPMENT LAYOUT
AN	NOTES
E1	ELECTRICAL LAYOUT GC85
E1.1	ELECTRICAL DETAILS
E1.3	MAIN PANEL DETAILS (OPTIONAL)
S1	OVERHEAD STRUCTURAL LAYOUT
S2	STRUCTURAL NOTES GENERAL CONNECTION DETAILS
S3	STRUCTURAL NOTES
Q1	EQUIPMENT DETAILS GC85
QE1	EQUIPMENT CABLE LENGTH GC85

**PROJECT MANAGER:** GENE NOWACZYK  
 8121 N.W. 97TH TERR  
 KANSAS CITY, MISSOURI  
 64153  
**OFFICE PHONE** 816.741.5558  
**CELL PHONE** 816.223.6378  
**E-MAIL** GNOWACZYK@RADSOURCE.NET



INSTALL LOCATION MAP

- SITE PROGRESS CHECKLIST -

- REVIEW EQUIPMENT ORDER FOR EXACT ITEMS PURCHASED. OPTIONAL/- FUTURE ITEMS NOT ON ORDER MAY BE INDICATED ON THESE PLANS.
- ALL ROOM DIMENSIONS ARE CRITICAL! IMMEDIATELY CONTACT GENE NOWACZYK AT RADSOURCE IF CHANGES OCCUR OR DIMENSIONS ARE NOT CORRECT.
- CONTACT A RADIATION PHYSICIST OR CONSULTANT TO SPECIFY REQUIREMENTS FOR RADIATION CONTAINMENT.
- PROVIDE A LOCKABLE EQUIPMENT HOLDING AREA CLOSE TO THE INSTALLATION FOR STORING TOOLS AND TEST EQUIPMENT.
- MAKE ARRANGEMENTS FOR ANY RIGGING, SPECIAL HANDLING, OR FACILITY MODIFICATIONS THAT MUST BE MADE IN ORDER FOR THE EQUIPMENT TO BE DELIVERED TO THE INSTALLATION SITE. IF DESIRED, YOUR LOCAL RADSOURCE TEAM REPRESENTATIVE CAN SUPPLY A REFERENCE LIST OF RIGGERS.
- MAKE SURE A DUST FREE, TEMPERATURE AND HUMIDITY CONTROLLED ENVIRONMENT IS AVAILABLE FOR STORING THE EQUIPMENT IF YOUR SITE IS NOT READY FOR INSTALLATION AT THE TIME OF DELIVERY. ONCE THE SITE IS PREPARED, YOU ARE THEN RESPONSIBLE FOR DELIVERING THE EQUIPMENT TO THE SITE.

WITHIN THE NOTES, DETAILS AND SPECIFICATION CONTAINED IN THIS SET OF DOCUMENTS, THE SINGLE TERM "RADSOURCE" IS USED FOR INDICATING "RADSOURCE IMAGING TECHNOLOGIES INC."

LAST PLOT DATE: 7 June 2021  
 LAST REVIEW: 6/7/2021 1:23:34 PM



**07/08/2021**  
**GNOWACZYK**  
 SITE PLANNING &  
 PROJECT DEVELOPMENT  
 OFFICE: 816-741-5558  
 CELL: 816-223-6378  
 FAX: 816-587-2423  
 EMAIL: GNOWACZYK@RADSOURCE.NET  
 8121 N.W. 97TH TERR  
 KANSAS CITY, MISSOURI 64153

**PROJECT**

**SAMSUNG GC 85**

S LUKES ROCKHILL

120 NE SAINT LUKES BLVD SUITE 200, LEE'S  
 SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
 p.816.728.1999  
 BDOSTAL@ACIBOLAND.COM

ELECTRICAL CONTRACTOR:  
 p. ....  
 m.XXX-XXX-XXXX  
 ....

GENERAL CONTRACTOR:  
 p. ....  
 m. ....  
 ....

PROJECT MANAGER FOR CUSTOMER:  
 p. ....  
 ....

IT  
 XXX  
 p. XXX  
 XXX

RADIOLOGY DIRECTOR  
 p. ....  
 ....


REVISION:	DATE:

DRAWN BY: \_\_\_\_\_ GENE N.  
 CHK'D BY: \_\_\_\_\_ A.W.  
 CUSTOMER: \_\_\_\_\_

SCALE: \_\_\_\_\_ NOTED  
 DATE: **6/7/2021 1:23:34 PM**

FILE NAME:  
 Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #  
**AQ1- X-RAY**



NOTE:  
 THIS SAMSUNG ROOM CONFIGURATION UTILIZES 3 METER TRANSVERSE BRIDGE AND 4 METER LONGITUDE RAILS

COUNTER TOP IN OPERATORS AREA SHOULD BE 40"-42" A.F.F. COUNTER TOP HEIGHT NEEDS APPROVAL BY S LUKES ROCKHILL

CONTROL WALL DOES NOT GO ALL THE WAY TO CEILING

THIS SYSTEM REQUIRES 480 VAC 3 PHASE POWER AND RECONFIGURING OF THE ABOVE CEILING SUPER STRUCTURE

NOTE:  
 ARCHITECT / CONTRACTOR IS TO VERIFY ALL DIMENSIONS ON THIS DRAWING AGAINST AS-BUILT. DIMENSIONS ILLUSTRATED WITHIN HAVE BEEN USED FOR PROPER EQUIPMENT PLACEMENT AND MAY BE USED IN THE FUTURE FOR RADIATION SHIELDING PROTECTION BY THE CUSTOMERS SELECTED PHYSICIST.

EACH RESPECTIVE ROOM WILL HAVE AN ENLARGED VIEW ILLUSTRATING THE PLACEMENT OF THE RADIOLOGY EQUIPMENT FOR THE ASSOCIATED ROOM IDENTIFICATION AS SHOWN ON SHEETS LABELED WITH THE LETTER 'AQ-?'

SUPPLEMENTAL NOTES:  
 ALL ITEMS LISTED BELOW ARE TO BE PROVIDED / DESIGNED BY THE ARCHITECT ACI. THE ARCHITECT ACI SHALL CONSULT WITH S LUKES ROCKHILL FOR ANY ADDITIONAL INFORMATION.


- ALL DIAGNOSTIC ROOMS INCLUDING X-RAY, MAMMO, R/F, CT, ETC., SHALL HAVE " LED" CAN LIGHTING AND/OR FLORESCENT LIGHT FIXTURES. THE LED FIXTURES ARE TO BE DISTRIBUTED AROUND THE ROOM AND SHOULD BE PROVIDED WITH DIMMER CONTROLS. THE DIMMER CONTROLS SHOULD BE LOCATED NEAR THE ENTRANCES AND IN THE CONTROL AREAS.
- IT IS RECOMMENDED THAT ALL DIAGNOSTIC ROOMS SHOULD HAVE TILE OR VINYL FLOORING.
- A TILE DROP CEILING IS RECOMMENDED FOR ANY DIAGNOSTIC ROOMS. MINIMUM CEILING HEIGHT 9'-4"
- ALL CABINERY WORK IS TO BE DESIGNED BY THE ARCHITECT AND PROVIDED BY S LUKES ROCKHILL AND OR ---- . RECOMMEND ALL COUNTERS SHALL HAVE ROUNDED CORNERS.
- PROVIDE FOR REFUSE REMOVAL AND DISPOSAL (E.G. CRATES, CARTONS, PACKING)
- PROVIDE A WORKING RESTROOM WITH SUPPLIES WITHIN THE FACILITY

**ROOM LAYOUT - X-RAY**  
 SCALE: 1/2" = 1'-0"  
 MINIMUM CEILING HEIGHT: 9'-4"  
 MAXIMUM CEILING HEIGHT: 9'-6"

EQUIPMENT LEGEND SAMSUNG XGEO-GC85						
OWNER: S LUKES ROCKHILL						
ITEM	QUANTITY	DESCRIPTION	WEIGHT	HEAT OUTPUT	PROVIDED BY	INSTALLED BY
1	1	PATIENT TABLE	440LBS	2,046 BTU	OWNER	RADSOURCE
2	1	WALL / CHEST STAND	330 LBS	511 BTU	OWNER	RADSOURCE
3	1	GENERATOR CABINET	220 LBS	5,968 BTU	OWNER	RADSOURCE
4	1	CEILING RAIL	140 LBS	N/A	OWNER	RADSOURCE
5	1	CEILING MOUNTED TUBE HEAD	616 LBS	1,909 BTU	OWNER	RADSOURCE
6	1	WORK STATION	35 LBS	1,364 BTU	OWNER	RADSOURCE
7	1	STITCHING STAND	235 LBS	N/A BTU	OWNER	RADSOURCE

ENVIRONMENT

AMBIENT OPERATION TEMPERATURE: 55-75° (F)  
 ALLOWABLE TEMPERATURE CHANGE: 15° (F) PER HOUR  
 HUMIDITY: 20-80 PERCENT NON CONDENSING  
 ALLOWABLE HUMIDITY CHANGE: 10 PERCENT PER HOUR



NOTE:  
 SPECIAL DELIVERY TO BUILDING NOT COVERED BY RADSOURCE IMAGING TECHNOLOGIES INC. TO BE COORDINATED BETWEEN "S LUKES ROCKHILL AND/OR ----" AND RADSOURCE IMAGING TECHNOLOGIES INC.





**GENE NOWACZYK**  
MEP  
SITE PLANNING &  
PROJECT DEVELOPMENT

OFFICE: 816-741-5558  
CELL: 816-223-6378  
FAX: 816-587-2423  
EMAIL: GNOWACZYK@RADSOURCE.NET  
8121 N.W. 97TH TERR  
KANSAS CITY, MISSOURI 64153

**PROJECT**

**SAMSUNG GC 85**

**S LUKES ROCKHILL**

120 NE SAINT LUKE'S BLVD SUITE 200, LEE'S  
SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
p.816.728.1999  
BDOSTAL@ACIBOLAND.COM

ELECTRICAL CONTRACTOR:  
---  
p.---  
m.XXX-XXX-XXXX  
---

GENERAL CONTRACTOR:  
---  
p.---  
m.---  
---

PROJECT MANAGER FOR CUSTOMER:  
---  
p.---  
---

IT  
XXX  
p. XXX  
XXX

RADIOLOGY DIRECTOR  
---  
p.---  
---

REVISION:	DATE:

DRAWN BY: GENE N.  
CHKD BY: A.W.  
CUSTOMER :  
SCALE: NOTED  
DATE: 6/7/2021 1:23:34 PM

FILE NAME:  
Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #  
**AN**

**MINIMUM SITE PREPARATION REQUIREMENTS**

WALLS TO BE PAINTED OR COVERED, BASEBOARDS INSTALLED, FLOORS TO BE TILED AND/OR COVERED, CEILING SHALL HAVE GRID TILES AND LIGHTING FIXTURES INSTALLED.

DOORS AND WINDOWS, ESPECIALLY RADIATION PROTECTION BARRIERS, INSTALLED AND FINISHED WITH LOCK SETS OPERATIONAL.

ALL ELECTRICAL CONVENIENCE, CONDUIT, RACEWAY AND JUNCTION BOXES INSTALLED.

INCOMING MAINS POWER OPERATIONAL AND CONNECTED TO X-RAY ROOM BREAKER.

115 VOLTS CONVENIENCE OUTLETS OPERATIONAL.

ALL SUPPORT STRUCTURES CORRECTLY INSTALLED.

ALL CHANNELS, PIPES, BEAM'S AND OR OTHER SUPPORTING DEVICES SHOULD BE LEVEL, PARALLEL AND FREE OF LATERAL OR LONGITUDINAL MOVEMENTS.

ALL CONTRACTOR SUPPLIED CABLES PULLED AND TERMINATED.

A DUST FREE ENVIRONMENT IN AND AROUND THE PROCEDURE ROOM.

ALL HEATING AND VENTILATION / AIR-CONDITIONING INSTALLED AND OPERATIONAL.

A CLEAR DOOR OPENING FOR MOVING EQUIPMENT INTO THE BUILDING MUST BE 42 IN. X 82 IN. OR LARGER CONTINGENT ON AN 8' CORRIDOR WIDTH.

**NOTICE:**  
THIS DRAWING SET IS THE SOLE PROPERTY OF RADSOURCE IMAGING TECHNOLOGIES, INC.

ITS USE IS AUTHORIZED ONLY FOR THE CUSTOMER S LUKES ROCKHILL/CONTRACTOR ---- TO DESIGN AND INCORPORATE OUR CONCEPT INTO CONSTRUCTION AND PREPARATION FOR IMAGING EQUIPMENT INSTALLATION. THESE DRAWINGS SHALL NOT BE USED FOR ANY PURPOSE OTHER THAN THE AGREED UPON DESIGN BETWEEN RADSOURCE IMAGING AND THEIR CUSTOMER.

THE CUSTOMER S LUKES ROCKHILL IS RESPONSIBLE FOR ALL ROOM PREPARATION COSTS, FEES, PERMITS AND INSPECTIONS UNLESS OTHERWISE SPECIFIED IN THE GENERAL ORDER FOR THE EQUIPMENT PURCHASE.

RADIATION SHIELDING IS NOT SHOWN ON THESE PLANS. HOWEVER, THE CUSTOMER S LUKES ROCKHILL SHALL, AT THEIR OWN EXPENSE, HAVE SHIELDING CALCULATIONS FOR THE ROOM PREPARED BY A LICENSED RADIATION PHYSICIST.

**PREFACE**

THESE DRAWINGS HAVE BEEN PREPARED BY RADSOURCE IMAGING TECHNOLOGIES, INC. , THEIR PURPOSE IS TO PROVIDE THE SITING, ELECTRICAL, MECHANICAL AND ENVIRONMENTAL SPECIFICATIONS REQUIRED TO ACCOMMODATE THE INSTALLATION AND OPERATION OF THE DIAGNOSTIC IMAGING EQUIPMENT AND SUB-COMPONENTS ILLUSTRATED.

THE LAYOUT(S) PROVIDED FOR ALL COMPONENTS PURCHASED FROM AND/OR PROVIDED BY THE EQUIPMENT MANUFACTURER SHALL SERVE AS A GUIDE FOR INSTALLATION BY THE LOCAL SERVICE/INSTALLATION REPRESENTATIVES.

INFORMATION IN THESE DRAWINGS RELATING TO BUILDING/FACILITY SPECIFICATIONS THAT WILL SUPPORT IMAGING EQUIPMENT COMPONENTS SUCH AS ELECTRICAL, STRUCTURAL, MECHANICAL AND ENVIRONMENTAL REQUIREMENTS SHALL BE UTILIZED AS A GUIDE BY THE CUSTOMER'S ARCHITECT ACI AND/OR CONTRACTOR ----. FACILITY CONDITIONS MAY DICTATE ACTUAL CONSTRUCTION METHODS AND MATERIALS APPLIED. HOWEVER, ALL METHODS AND MATERIALS MUST COMPLY WITH EQUIPMENT MANUFACTURER SPECIFICATIONS, AS WELL AS LOCAL AND/OR NATIONAL BUILDING CODES.

THE REQUIRED CEILING HEIGHT OF 9'-4" INDICATED ON THESE PLANS IS TO INSURE EQUIPMENT FUNCTION IS NOT INHIBITED. CONSULT WITH YOUR EQUIPMENT INSTALLATION SPECIALIST REGARDING ACCEPTABILITY OF THE OTHER CEILING HEIGHTS. CHECK ALL DOOR OPENINGS FROM DELIVERY LOCATION TO WHERE EQUIPMENT IS TO BE INSTALLED.

THE QUALITY OF CONSTRUCTION METHODS, MATERIALS AND CONFORMANCE TO EQUIPMENT MANUFACTURER SPECIFICATIONS AND TOLERANCES, WILL AFFECT EQUIPMENT PERFORMANCE.

**MAGNETIC INTERFERENCE SPECIFICATIONS**

DIGITAL FLAT PANEL MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN ONE GAUSS TO GUARANTEE SPECIFIED IMAGING PERFORMANCE.

X-RAY TUBES AND EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN TEN GAUSS TO GUARANTEE SPECIFIED PERFORMANCE DATA INTEGRITY

SYSTEM ELECTRONICS / EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN TEN GAUSS TO GUARANTEE DATA INTEGRITY

CONSOLE EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN ONE GAUSS TO OBTAIN SPECIFIED GEOMETRIC LINEARITY.

**SITE ENVIRONMENT SPECIFICATIONS**

AMBIENT OPERATING TEMPERATURE: 60° TO 75° F (16° TO 24° C) MAXIMUM

ALLOWABLE TEMPERATURE CHANGE OF 5° F, (3° C) / HOUR MAXIMUM ROOM

TEMPERATURE GRADIENT 5° F, (3° C)

HUMIDITY: 30 TO 60 PERCENT NON-CONDENSING, MAXIMUM ALLOWABLE CHANGE OF 5 PERCENT / HOUR

ALTITUDE: NOT TO EXCEED 10,000 FT (3050M) ABOVE SEA LEVEL

THE ENVIRONMENT FOR THE ELECTRONICS CABINET MUST BE CONTROLLED SO THE ABOVE RESTRICTIONS ARE NOT EXCEEDED.

DO NOT RESTRICT THE AIR INTAKE OR AIR EXHAUST OF THE SYSTEM COMPONENTS.

ENVIRONMENTAL CONDITIONS LISTED ABOVE MUST BE MAINTAINED AT ALL TIMES, INCLUDING OVERNIGHT AND HOLIDAYS.

**RADSOURCE**  
 Imaging Technologies

**MSF**  
**07/06/2021**  
**GNOWACZYK**  
 MSP  
 SITE PLANNING &  
 PROJECT DEVELOPMENT

OFFICE: 816-741-5558  
 CELL: 816-223-6378  
 FAX: 816-587-2423  
 EMAIL: GNOWACZYK@RADSOURCE.NET  
 8121 N.W. 97TH TERR  
 KANSAS CITY, MISSOURI 64153

**PROJECT**

**SAMSUNG GC 85**

**S LUKES ROCKHILL**

120 NE SAINT LUKES BLVD SUITE 200, LEE'S  
 SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
 p.816.728.1999  
 BDOSTAL@ACIBOLAND.COM

ELECTRICAL CONTRACTOR:  
 ---  
 p.---  
 m.XXX-XXX-XXXX  
 ---

GENERAL CONTRACTOR:  
 ---  
 p.---  
 m.---  
 ---

PROJECT MANAGER FOR CUSTOMER:  
 ---  
 p.---  
 ---

IT  
 XXX  
 p. XXX  
 XXX

RADIOLOGY DIRECTOR  
 ---  
 p.---  
 ---

REVISION:	DATE:


DRAWN BY:	GENE N.
CHKD BY:	A.W.
CUSTOMER :	
SCALE:	NOTED
DATE:	6/7/2021 1:23:34 PM

FILE NAME:  
 Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #  
**E1-X-RAY**

**ELECTRICAL LEGEND**

- CBE1** MAIN DISCONNECT CONTRACTOR SUPPLIED, 480 VAC 3 PHASE @ 100 AMP FRAME, UL LISTED WITH MAGNETIC CONTACTOR, SEMI OR FLUSH MOUNTED IN X-RAY EXAM ROOM.
- UB** 1 @ 6 x 6 x 4 JUNCTION BOX PART, MOUNT BOTTOM OF BOX DIRECTLY A.F.F.  
 1 @ OVERSIZED COVER
- OC** 1 @ 12 x 12 x 4 JUNCTION BOX, MOUNT CENTER OF BOX TO 18.0" A.F.F.  
 1 @ OVERSIZE COVER  
 1 @ 2-1/2 CHASE NIPPLE WITH BUSHING AND LOCKNUT, INSTALLED BY CONTRACTOR (CENTER IN COVER)
- FB** 1 @ 12 x 12 x 4 JUNCTION BOX, MOUNT TOP OF BOX JUST BELOW FINISHED FLOOR, ALLOW FOR COVER TO FIT FLUSH TO FINISHED FLOOR  
 1 @ COVER  
 1 @ 2-1/2 CHASE NIPPLE WITH BUSHING AND LOCKNUT, INSTALLED BY CONTRACTOR (CENTER IN COVER)
- ST1** SINGLE GANG 2-1/2" DEEP FLUSH MOUNTED JUNCTION BOX, SUPPLY AND INSTALL MUSHROOM HEAD "EMERGENCY STOP BUTTON" 60.0" A.F.F. WIRE TO "CBE1" MAIN DISCONNECT MAGNETIC CONTACTOR PER N.E.C. SUPPLIED AND INSTALLED BY ELECTRICAL CONTRACTOR  
 IN THE EVENT THERE IS AN EXSISTING EMERGENCY/SHUNT TRIP ALREADY IN PLACE THE EXSISTING LOCATION CAN BE REUSED.
- WL** WARNING LIGHT (X-RAY ON), LED LIGHT FIXTURE SUPPLIED AND INSTALLED BY CONTRACTOR, LOW VOLTAGE (LED) 12-24VDC. RUN SWITCH LEG BACK TO "XG"
- XG** 1 @ 14.5 x 12 x 4 RECESSED MOUNTED JUNCTION BOX WITH SPLIT COVER AND DIVIDER, CONNECT TO "CBE1" PER N.E.C. MOUNT CENTER 18.0" A.F.F. SEE SHEET (E1.3)  
 INSTALL A 5.0' TAIL IN METAL FLEX ON SMALL SIDE OF SPLIT COVER LEAVING 3.0' OF EXPOSED CONDUCTOR OUTSIDE THE FLEX. ELECTRICAL CONTRACTOR TO SUPPLY AND INSTALL JUNCTION BOX, FLEX AND CONNECTORS AS REQUIRED, TERMINATE FLEX WITH A 90DEG BOTH ENDS.
- XT** 1 @ 10 x 3 x 4 RECESSED MOUNTED WALL DUCT WITH COVERS, MOUNT MOUNT ONTOP OF "XG" WITH SUPPLIED CONNECTORS IN KIT. SEE SHEET (E1.3)
- AC** 1 @ 10 x 10 x 10 JUNCTION BOX, SURFACE MOUNT AT FINISHED CEILING TO WALL DUCT (THIS WILL BE USED AS A PASS THROUGH, SEE SHEET (E1.3))



**REQUIRED CONDUIT RUNS FOR BASE SYSTEM BY CONTRACTOR**

ID	FROM	TO	DESCRIPTION
1	CBE1	TO XG	CONDUIT ABOVE CEILING PER N.E.C., PULL 3 @ #3AWG; PULSE 1 @ #3 AWG GROUND, CONNECT WIRE TO BREAKER AND LEAVE 6' TAILS AT "XG". LABEL "FOR X-RAY POWER"
2	CBE1	TO ST1	CONDUIT AS REQUIRED PER N.E.C. ABOVE CEILING, PULL 2 @ # _ CONNECT TO SHUNT TRIP EMERGENCY STOP DEVICE
3	XG	TO OC	2.0" CONDUIT, BELOW GRADE
4	CBE1	TO WL	NO CONDUIT REQUIRED WITH KIT, WITH OUT KIT USE 3/4" CND
5	CBE1	TO XG	1/2" CNDUIT ABOVE CEILING, PULL 18-2 AWG THEROMSTATE WIRE, LEAVE 3.0' AT CBE1 AND 12.0' AT XG. LABEL BOTH ENDS "FOR WARNING LIGHT"
6	XG	TO FB	2.5" CONDUIT, BELOW GRADE
7	FB	TO UB	2.0" CONDUIT, BELOW GRADE
8	INCOMING MAINS	TO CBE1	CONDUIT AS REQUIRED
9	UB	O OC	1.5" CND, ABOVE CEILING OR BELOW GRADE

**SYMBOLS LEGEND**

- GROUND FAULT INTERRUPT RECEPTACLE
- 110/115VAC 20 AMP
- PHONE / DATA
- PHONE
- DATA
- WALL MOUNTED PHONE 48"A.F.F.
- ABOVE CEILING CONDUIT
- BELOW GRAD CONDUIT
- 3 x 10 HORIZONTAL WALL DUCT
- 3 x 10 FLUSH TO FINISHED FLOOR DUCT
- 3 x 10 VERTICAL WALL DUCT
- CEILING MOUNTED JUNCTION BOX

**ELECTRICAL LAYOUT DRGEM PREMIUM**

SCALE: 3/8" = 1'-0"  
 MINIMUM CEILING HEIGHT: 9'-4"



07/09/2021



**RadsourcE**  
Imaging Technologies

MEP  
GNOWACZYK  
SITE PLANNING &  
PROJECT DEVELOPMENT

OFFICE: 816-741-5558  
CELL: 816-223-6378  
FAX: 816-587-2423  
EMAIL: GNOWACZYK@RADSOURCE.NET  
8121 N.W. 97TH TERR  
KANSAS CITY, MISSOURI 64153

**ELECTRICAL NOTES**

ALL WIRES SPECIFIED SHALL BE COPPER STRANDED FLEXIBLE, THERMO-PLASTIC, COLOR CODED, CUT 10 FOOT LONG AT OUTLET BOXES. DUCT TERMINATION POINTS OR STUBBED CONDUIT ENDS. ALL CONDUCTORS, POWER, SIGNAL AND GROUND, MUST BE RUN IN A CONDUIT OR DUCT SYSTEM. ELECTRICAL CONTRACTOR SHALL RING OUT AND TAG ALL WIRES AT BOTH ENDS. WIRE RUNS MUST BE CONTINUOUS COPPER STRANDED AND FREE FROM SPLICES. MIN 2 PULL STRINGS PER CONDUIT RUN.

WIRE SIZES GIVEN ARE FOR USE OF EQUIPMENT. LARGER SIZES MAY BE REQUIRED BY LOCAL CODES.

IT IS RECOMMENDED THAT ALL WIRES BE COLOR CODED, AS REQUIRED IN ACCORDANCE WITH NATIONAL AND LOCAL ELECTRICAL CODES.

LOCATE AT LEAST ONE CONVENIENCE OUTLET CLOSE TO THE SYSTEM CONTROL, THE POWER DISTRIBUTION UNIT AND ONE ON EACH WALL OF THE PROCEDURE ROOM. USE HOSPITAL APPROVED OUTLET OR EQUIVALENT.

GENERAL ROOM ILLUMINATION IS NOT ILLUSTRATED. CAUTION SHOULD BE TAKEN TO AVOID EXCESSIVE HEAT FROM OVERHEAD SPOTLIGHTS. DAMAGE CAN OCCUR TO CEILING MOUNTING COMPONENTS AND WIRING IF HIGH WATTAGE BULBS ARE USED. RECOMMEND LED BULBS, USE DIMMER CONTROLS (EXCEPT MR). DO NOT MOUNT LIGHTS DIRECTLY ABOVE AREAS WHERE CEILING MOUNTED ACCESSORIES WILL BE PARKED.

ROUTING OF CABLE DUCTWORK, CONDUITS, ETC., MUST RUN DIRECT AS POSSIBLE OTHERWISE MAY RESULT IN THE NEED FOR GREATER THAN STANDARD CABLE LENGTHS (REFER TO THE INTERCONNECTION DIAGRAM FOR MAXIMUM USABLE LENGTHS POINT TO POINT). SHEET QE1

CONDUIT TURNS TO HAVE LARGE, SWEEPING BENDS WITH MINIMUM RADIUS IN ACCORDANCE WITH NATIONAL AND LOCAL ELECTRICAL CODES.

PHYSICAL CONNECTION OF PRIMARY POWER TO SAMSUNG EQUIPMENT IS TO BE MADE BY CUSTOMERS ELECTRICAL CONTRACTOR WITH THE SUPERVISION OF A RADSOURCE IMAGING REPRESENTATIVE. THE RADSOURCE IMAGING REPRESENTATIVE WOULD BE REQUIRED TO IDENTIFY THE PHYSICAL CONNECTION LOCATION, AND INSURE PROPER HANDLING OF SAMSUNG EQUIPMENT.

ALL ELECTRICAL CONVEINCE, NETWORKING AND PHONE OUTLETS TO BE 18.0' A.F.F. UNLESS OTHER WISE NOTED

FEILD VERIFY EXACT LOCATIONS OF EXISTING ELECTRICAL PANELS, CONDUITS, JUNCTION BOXES ETC FOR NEW CONNECTIONS.

LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6FT

ALL CONDUITS & CONDUCTERS SHALL BE INSTALLED INSIDE WALLS OR ABOVE CEILING, NO EXPOSED CONDUIT OR CONDUCTORS WILL BE ALLOWED.

ALL WIRE RUNS WILL BE A MINIMUM OF FLEXIBLE METAL CONDUIT (FMC)

**PROJECT**

**SAMSUNG GC 85**

S LUKES ROCKHILL

120 NE SAINT LUKES BLVD SUITE 200, LEE'S  
SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
p.816.728.1999  
BDOSTAL@ACIBOLAND.COM

ELECTRICAL CONTRACTOR:  
---  
p.---  
m.XXX-XXX-XXXX  
---

GENERAL CONTRACTOR:  
---  
p.---  
m.---  
---

PROJECT MANAGER FOR CUSTOMER:  
---  
p.---  
---

IT  
XXX  
p. XXX  
XXX

RADIOLOGY DIRECTOR  
---  
p.---  
---

REVISION:	DATE:

DRAWN BY:	GENE N.
CHKD BY:	A.W.
CUSTOMER :	
SCALE:	NOTED
DATE:	6/7/2021 1:23:34 PM

FILE NAME:  
Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #  
**E1.3**



07/08/2021  
**RadSource**  
Imaging Technologies

GENE NOWACZYK  
MEP  
SITE PLANNING &  
PROJECT DEVELOPMENT

OFFICE: 816-741-5558  
CELL: 816-223-6378  
FAX: 816-587-2423  
EMAIL: GNOWACZYK@RADSOURCE.NET  
8121 N.W. 97TH TERR  
KANSAS CITY, MISSOURI 64153

**PROJECT**

**SAMSUNG GC 85**

S LUKES ROCKHILL

120 NE SAINT LUKE'S BLVD SUITE 200, LEE'S  
SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
p.816.728.1999  
BDOSTAL@ACIBOLAND.COM

ELECTRICAL CONTRACTOR:  
---  
p.---  
m.XXX-XXX-XXXX  
---

GENERAL CONTRACTOR:  
---  
p.---  
m.---  
---

PROJECT MANAGER FOR CUSTOMER:  
---  
p.---  
---

IT  
XXX  
p. XXX  
XXX

RADIOLOGY DIRECTOR  
---  
p.---  
---


REVISION:	DATE:

DRAWN BY:	GENE N.
CHKD BY:	A.W.
CUSTOMER :	
SCALE:	NOTED
DATE:	6/7/2021 1:23:34 PM


FILE NAME:  
Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #



**Q1**




FRONT VIEW




SIDE VIEW



FRONT VIEW




SIDE VIEW




TOP VIEW

**WALL STAND DETAIL DRAWING**




TOP VIEW


**TABLE DETAIL DRAWING**




FRONT VIEW




SIDE VIEW



FRONT VIEW



SIDE VIEW



TOP VIEW

**CABINET DETAIL DRAWING**





07/08/2021  
**RadSource**  
Imaging Technologies  
GENE NOWACZYK  
MEP  
SITE PLANNING &  
PROJECT DEVELOPMENT  
OFFICE: 816-741-5558  
CELL: 816-223-6378  
FAX: 816-587-2423  
EMAIL: GNOWACZYK@RADSOURCE.NET  
8121 N.W. 97TH TERR  
KANSAS CITY, MISSOURI 64153

**PROJECT**  
**SAMSUNG GC 85**  
S LUKES ROCKHILL  
120 NE SAINT LUKE'S BLVD SUITE 200, LEE'S  
SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
p.816.728.1999  
BDOSTAL@ACIBOLAND.COM  
ELECTRICAL CONTRACTOR:  
p.---  
m.XXX-XXX-XXXX  
---  
GENERAL CONTRACTOR:  
p.---  
m.---  
---  
PROJECT MANAGER FOR CUSTOMER:  
p.---  
---  
IT  
XXX  
p. XXX  
XXX  
RADIOLOGY DIRECTOR  
p.---  
---


REVISION:	DATE:

DRAWN BY: GENE N.  
CHKD BY: A.W.  
CUSTOMER :  
SCALE: NOTED  
DATE: 6/7/2021 1:23:34 PM

FILE NAME:  
Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #  
**Q2**

# INTERCONNECT OF XGEO GC80









07/08/2021  
**GENE NOWACZYK**  
 MEP  
 SITE PLANNING &  
 PROJECT DEVELOPMENT  
 OFFICE: 816-741-5558  
 CELL: 816-223-6378  
 FAX: 816-587-2423  
 EMAIL: GNOWACZYK@RADSOURCE.NET  
 8121 N.W. 97TH TERR  
 KANSAS CITY, MISSOURI 64153

**PROJECT**  
**SAMSUNG GC 85**  
**S LUKES ROCKHILL**  
 120 NE SAINT LUKE'S BLVD SUITE 200, LEE'S  
 SUMMIT, MO 64086

**ARCHITECT:**  
**BRIAN DOSTAL**  
 p.816.728.1999  
 BDOSTAL@ACIBOLAND.COM

**ELECTRICAL CONTRACTOR:**  
 ----  
 p.----  
 m.XXX-XXX-XXXX  
 ----

**GENERAL CONTRACTOR:**  
 ----  
 p.----  
 m.----  
 ----

**PROJECT MANAGER FOR CUSTOMER:**  
 ----  
 p.----  
 ----

**IT**  
 XXX  
 p. XXX  
 XXX

**RADIOLOGY DIRECTOR**  
 ----  
 p.----  
 ----

REVISION:	DATE:

**DRAWN BY:** GENE N.  
**CHK'D BY:** A.W.  
**CUSTOMER :**  
**SCALE:** NOTED  
**DATE:** 6/7/2021 1:23:34 PM

**FILE NAME:**  
 Rockhill 2021 Samsung GC85.dwg

**DRAWING SHEET #**  
**S2**

**STRUT CHANNEL SUPPORT FRAME NOTES**

RECOMMENDED UNIVERSAL STEEL STRUT CHANNEL SUPPORT FRAME.

ALLOWS FOR TRANSVERSE AND LONGITUDINAL ADJUSTMENT AT TIME OF EQUIPMENT INSTALLATION. DETERMINATION OF THE ACTUAL DESIGN SHALL BE COORDINATED AND APPROVED BY THE ENGINEER OF RECORD. ALL STEEL STRUT MEMBERS SHALL BE PROVIDED AND INSTALLED BY CUSTOMER / THEIR CONTRACTOR.

- 1 SPANNING MEMBERS: STEEL CHANNEL STRUT FLUSH WITH FINISHED CEILING. SPACED AS INDICATED ON SHEET "S1"
- 2 LONGITUDINAL EQUIPMENT RAILS: FASTENED TO UNDERSIDE OF SPANNING MEMBERS.
- 3 COLUMNS: STEEL CHANNEL STRUT ATTACHED TO SPANNING MEMBERS AS SHOWN ON GENERAL CEILING DETAIL. NUMBER AND LOCATION OF VERTICAL COLUMNS SHALL VARY DEPENDING ON BUILDING CONSTRUCTION.
- 4 BRACES: STEEL CHANNEL STRUT ATTACHED TO VERTICAL COLUMNS AS SHOWN ON DETAIL.

THE ATTACHED DRAWINGS ARE FOR LAYOUT PURPOSES AND GENERAL MEANS OF FABRICATION. THE CUSTOMER'S ENGINEER OF RECORD OR AGENT SHALL PREPARE CONSTRUCTION DOCUMENTS.

THESE DRAWINGS INDICATE PLACEMENT OF THE PURCHASED EQUIPMENT, AS WELL AS DESCRIBE THE STRUCTURAL REQUIREMENTS FOR THAT EQUIPMENT. RADSOURCE WILL NOT BE RESPONSIBLE FOR OTHER DESIGNS AND CONSTRUCTION.


EVERY EFFORT HAS BEEN MADE TO ASSURE THAT THE EQUIPMENT DEPICTED ON THE ATTACHED RECOMMENDED LAYOUT, CONFIGURES THE LAYOUT PLAN TO ALLOW OPTIMUM OPERATION OF THE EQUIPMENT. THE CUSTOMER'S ENGINEER OF RECORD AND / OR AGENT SHALL BEAR SOLE RESPONSIBILITY FOR COMPLIANCE WITH APPLICABLE CODES ..

---- SHALL PROVIDE AND INSTALL ALL MATERIALS ALONG WITH ANY OTHER FEATURES CALLED OUT IN THE PLANS.


THE CONTRACTOR ----IS RESPONSIBLE FOR ANY FINAL PAINT OR TOUCH-UP WORK WHICH SHALL BE COMPLETED AFTER THE INSTALLATION OF THE PURCHASED SYSTEM.

EXISTING SERVICES THAT WILL NOT BE USED (PLUMBING, JUNCTION BOXES, FLOOR DRAINS ETC.) MUST BE CAPPED OR COVERED PRIOR TO COMMENCEMENT OF EQUIPMENT INSTALLATION.


**MINIMUM CEILING HEIGHT: 9'-4"**



**SCHMATIC / ISOMETRIC - SUSPENSION STRUCTURE**  
 NO SCALE



**GENERAL CEILING DETAIL**  
 NO SCALE



**GENERAL CONNECTION DETAIL**  
 NO SCALE

**GENERAL STRUCTURAL CEILING SUPPORT REQUIREMENTS**

A WELDED OR FABRICATED STRUCTURAL SUPPORT IS REQUIRED FOR CEILING MOUNTED X-RAY UNITS. IT'S TOP MEMBER IS FASTENED TO THE FLOOR SLAB (OR BUILDING STEEL) ABOVE THE EXAM ROOM. THE BOTTOM OF IT'S LOWEST SPANNING MEMBER IS FLUSH WITH THE FINISHED CEILING TO WHICH THE STATIONARY CEILING TRACKS ARE FASTENED.

THE DETAILS PROVIDED HERE INDICATE A BASIC SUPPORT METHOD THAT PERMITS TRANSVERSE AND LONGITUDINAL ADJUSTMENT OF BOLT CENTERS AT THE INSTALLATION SITE. IT CAN BE ADAPTED TO ACCOMMODATE THE VARIOUS ARCHITECTURAL CIRCUMSTANCES ENCOUNTERED AT EACH INSTALLATION.

THE SUPPORT MUST BE RIGID, SECURELY BRACED AND LEVEL IN BOTH DIRECTIONS AT THE FINISHED CEILING LINE. LENGTH AND LOADING CAPACITY WILL DEPEND ON THE SELECTED CEILING UNIT AND NUMBER OF CARRIAGE ASSEMBLIES TO BE BORNE. ACTUAL EQUIPMENT LOADS FOR EACH ROOM ARE SPECIFIED ON SITE PLANNING DRAWINGS UNDER THE STRUCTURAL DETAIL SPECIFICATIONS.

IT IS SUGGESTED THAT THROUGH BOLTING THE SUPPORT STRUCTURE TO BUILDING STRUCTURE OCCUR WHENEVER POSSIBLE. APPLICABLE CONDITIONS WILL ALSO ACCEPT THE APPLICATION OF HILTI EXPANSION ANCHORS (OR EQUAL) IN LIEU OF THROUGH BOLTING. ACTUAL METHODS AND MATERIALS SHALL BE DETERMINED BY THE ENGINEER OF RECORD. ALL SUPPORT MEMBERS, ANCHOR BOLTS AND HARDWARE SHALL BE PROVIDED AND INSTALLED BY THE CUSTOMER/CONTRACTOR. THE LENGTH OF BOLTS SHALL BE DETERMINED TO MEET SPECIFIC SITE REQUIREMENTS BY THE ENGINEER OF RECORD.

CENTERLINES OF THE TWO LONGITUDINAL RAILS HOLDING THE SUSPENDED WEIGHTS ARE SHOWN. STEEL CHANNEL STRUT FLUSH FINISHED CEILING SHALL BE IDENTIFIED AS THE SPANNING MEMBERS. THESE MEMBERS MUST BE LEVEL IN BOTH DIRECTIONS TO WITHIN 1MM AND BRACED TO PREVENT MOVEMENT IN ANY DIRECTION. THEY MUST BE SECURED TO THE SLAB ABOVE AND/OR TO THE BUILDING STRUCTURE TO HOLD THE DEAD WEIGHTS INDICATED. see EQUIPMENT LEGEND "SHEET A1"

INSTALLATION OF THE SUPPORT MAY BE AFFECTED BY OTHER ARCHITECTURAL OR MECHANICAL PROVISIONS WHICH MAY BE LOCATED IN THE SAME AREA. IN THIS CASE, COORDINATION OF THE REPRESENTATIVE MUST BE CONSULTED BEFORE ANY DEVIATION FROM THE SITE PLANNING DRAWINGS IS UNDERTAKEN.

1. CUSTOMER S LUKES ROCKHILL CAN ALSO UTILIZE AN EXISTING SUPPORT STRUCTURE, ONLY IF THE STRUCTURE IS CERTIFIED BY A LICENSED/PROFESSIONAL STRUCTURAL ENGINEER.
2. SUPPORT STRUCTURE MUST MEET ALL REQUIRED EQUIPMENT SUPPORT NEEDS FOR WIDTH, DEPTH, STRENGTH, ETC.
3. CUSTOMER S LUKES ROCKHILL IS RESPONSIBLE FOR MEETING SITE CONDITIONS FOR STATIC LOADS, LEVELNESS, ETC.

**GENERAL STRUCTURAL NOTES**

FLOOR SLABS ON WHICH EQUIPMENT IS TO BE INSTALLED MUST BE LEVEL TO 1MM IN 10.0'.

DIMENSIONS ARE TO FINISHED SURFACES OF ROOM.

CUSTOMERS CONTRACTOR ---- MUST PROVIDE ALL PENETRATIONS IN POST TENSION FLOORS.

CUSTOMERS CONTRACTORS ----MUST PROVIDE AND INSTALL ALL HARDWARE FOR "THROUGH THE FLOOR" ANCHORING AND/OR ANY BRACING UNDER SLAB AND/OR ACCESS FLOORS. THE CONTRACTOR MUST ALSO PROVIDE FLOOR DRILLING THAT CAN NOT BE COMPLETED BECAUSE OF AN OBSTRUCTION ENCOUNTERED BY THE INSTALLER SUCH AS REBAR ETC...

IT IS THE RESPONSIBILITY OF THE CUSTOMER S LUKES ROCKHILL/CONTRACTOR ---- TO PERFORM ANY FLOOR OR WALL PENETRATIONS THAT MAY BE REQUIRED. THE CUSTOMER S LUKES ROCKHILL/CONTRACTOR ---- IS ALSO RESPONSIBLE FOR ENSURING THAT NO SUBSURFACE UTILITIES i.e. ELECTRICAL, PLUMBING OR ANY OTHER FORM OF WIRING, CONDUITS, PIPING, DUCT WORK OR STRUCTURAL SUPPORTS E.G. POST TENSION CABLES OR REBAR WILL INTERFERE OR COME IN CONTACT WITH SUBSURFACE PENETRATION OPERATIONS, E.G. DRILLING AND INSTALLATION OF ANCHORING PERFORMED DURING THE INSTALLATION PROCESS. TO ENSURE WORKERS SAFETY INSTALLERS WILL ONLY PERFORM SURFACE PENETRATION OPERATIONS ONLY AFTER THE CUSTOMERS CONTRACTOR HAS VALIDATED THE SURFACE TO BE PENETRATED.

**ALL CEILING MOUNTED FIXTURES SUCH AS AIR VENTS, SPRINKLERS etc. TO BE FLUSH MOUNTED OR NOT TO EXTEND MORE THEN 1/4" BELOW THE FINISHED CEILING.**

ALL STEEL WORK AND PARTS NECESSARY TO SUPPORT CEILING MOUNTED EQUIPMENT IS TO BE SUPPLIED BY THE CUSTOMER S LUKES ROCKHILL OR THEIR CONTRACTOR ----.

ALL UNITS THAT ARE WALL MOUNTED OR WALL SUPPORTED ARE TO BE PROVIDED WITH SUPPORTS WHERE NECESSARY. WALL SUPPORTS ARE TO BE SUPPLIED AND INSTALLED BY THE CUSTOMER S LUKES ROCKHILL OR THEIR CONTRACTOR ----.



**GENE NOWACZYK**  
 MEP  
 SITE PLANNING &  
 PROJECT DEVELOPMENT  
 OFFICE: 816-741-5558  
 CELL: 816-223-6378  
 FAX: 816-587-2423  
 EMAIL: GNOWACZYK@RADSOURCE.NET  
 8121 N.W. 97TH TERR  
 KANSAS CITY, MISSOURI 64153

**PROJECT**

**SAMSUNG GC 85**

S LUKES ROCKHILL

120 NE SAINT LUKES BLVD SUITE 200, LEE'S  
 SUMMIT, MO 64086

ARCHITECT:  
**BRIAN DOSTAL**  
 p.816.728.1999  
 BDOSTAL@ACIBOLAND.COM

ELECTRICAL CONTRACTOR:  
 ----  
 p.----  
 m.XXX-XXX-XXXX  
 ----

GENERAL CONTRACTOR:  
 ----  
 p.----  
 m.----  
 ----

PROJECT MANAGER FOR CUSTOMER:  
 ----  
 p.----  
 ----

IT  
 XXX  
 p. XXX  
 XXX

RADIOLOGY DIRECTOR  
 ----  
 p.----  
 ----

REVISION:	DATE:

DRAWN BY: GENE N.  
 CHK'D BY: A.W.  
 CUSTOMER :  
 SCALE: NOTED  
 DATE: 6/7/2021 1:23:34 PM

FILE NAME:  
 Rockhill 2021 Samsung GC85.dwg

DRAWING SHEET #  
**S3**