







FRONT ELEVATION
SCALE: 1/4" = 1'-0"



RIGHT ELEVATION
SCALE: 1/8" = 1'-0"



LEFT ELEVATION
SCALE: 1/8" = 1'-0"



REAR ELEVATION
SCALE: 1/8" = 1'-0"


These plans and specifications are protected under federal copyright laws.
Copyright A.D. 2021 Viewpoint Residential Design, LLC.
Care and effort have gone into the creation and design of this plan. However, the designer is not an architect or engineer and construction professional. Architect or engineer. Because of the complexity of the design, the designer does not warrant the accuracy of the plans, specifications, and details. The designer assumes no responsibility for any damages, including structural failures, due to any deficiencies, omissions or errors in the design of blueprints. Also, site conditions may vary from those portrayed on the plan. Designer does not warrant the suitability of these plans for your specific site and application.

"For God so loved the world, that he gave his only begotten Son, that whosoever should not perish, but have everlasting life" (John 3:16)

VIEWPOINT
RESIDENTIAL DESIGN LLC
Office: (816) 554-0400 Email: admin@viewpointdesign.net

Site Description:
Lot 11, The Townhomes of Chapel Ridge - 2nd Plat
Street Address:
805, 807, and 809 NE Algonquin St., Lee's Summit, Missouri


Project Title:
TCR011 Triplex
General Contractor:
Kevin Higdon Construction, LLC



Date: 8 - 20 - AD 2021
Rev. 1: 9 - 10 - AD 2021
Rev. 2: 9 - 17 - AD 2021
Rev. 3:

Sheet Title:
ELEVATIONS

Sheet No.:
A-1 of 4




HIGHER PERFORMANCE (RECOMMENDED)		
RAFTERS	SPACING	MAX HORIZONTAL CLEARSPAN
#2-2x6	#24" O.C.	8'-6"
#2-2x6	#16" O.C.	9'-9"
#2-2x8	#24" O.C.	11'-3"
#2-2x8	#16" O.C.	12'-9"
#2-2x10	#24" O.C.	14'-3"
#2-2x10	#16" O.C.	16'-3"

DEFLECTION = $L/360$ LIVE LOAD, $L/240$ TOTAL LOAD


- * VALUITS TO BE 2x10 DEPTH
 - RIDGE BOARDS ARE (UNLESS OTHERWISE NOTED)
 - 2x8 UP TO 10x12 PITCH
 - 2x10 OVER 10x12 PITCH
 - ALL HIP & VALLEY'S ARE (UNLESS OTHERWISE NOTED)
 - 4x8 UP TO 10x12 PITCH
 - 4x10 OVER 10x12 PITCH
 - * PURLINS ARE 2x6 MIN.
 - PURLIN STRUITS SHALL BE INSTALLED AT 4'-0" O.C.
 - ALL PURLIN STRUITS SHALL HAVE A MINIMUM UNLAPPED LENGTH OF 8'-0"
 - PURLIN STRUITS SHALL BE CONSTRUCTED IN A
 - 1" CONFIGURATION AND PER THE FOLLOWING CHART:
- * RIDGE BOARDS ARE SAME AS PURLIN BRACINGS-
SPACING, SIZE, CONFIGURATION, & INSTALLATION
(SEE PURLIN BRACE NOTES ABOVE)

* HIP & VALLEY BRACE ARE SAME AS PURLIN
SIZE, CONFIGURATION, & INSTALLATION
(SEE PURLIN BRACE NOTES ABOVE)


* VERTICAL BRACE IF NOT IS UNDER HIP OR VALLEY
SLASH IS TOP END OF BRACE (/),
DOT IS BOTTOM OF BRACE (.)




* IDENTITIES RIDGE BOARD



* IDENTITIES PURLIN



PURLIN STRUT	MAX PURLIN STRUT LENGTH
(2) 2x4	8'-0"
(1) 2x4 & (1) 2x6	12'-0"
(1) 2x6 & (1) 2x8	20'-0"
(2) 2x6 & (1) 2x8	30'-0"
CONSULT ARCH/ENGR.	30'-0"



9'-0" CEILING
MAIN LEVEL
SCALE: 1/4" = 1'-0"

JOIST SCHEDULE	
C	2" X 6" #3 CEILING JOIST @ 16' O.C.
D	2" X 6" #2 CEILING JOIST @ 16' O.C.

UNIT A: 1451 SQ. FT.
UNIT B: 1451 SQ. FT.
<u>UNIT C: 1451 SQ. FT.</u>
TOTAL: 4353 SQ. FT.

GARAGE A: 472 SQ. FT.
GARAGE B: 472 SQ. FT.
GARAGE C: 472 SQ. FT.
COV. OUT/LIV A: 171 SQ. FT.
COV. OUT/LIV B: 171 SQ. FT.
COV. OUT/LIV C: 171 SQ. FT.

+++++ = WALL BRACING PER FRAMING NOTE #1 AND PER CALCULATIONS ON SHEET S1.1

[illegible]

These plans and specifications are protected under federal copyright laws.
Copyright A.D. 2021 Viewpoint Residential Design, LLC.

"For God so loved the world, that he gave his only begotten Son, that whosoever believeth in him should not perish, but have everlasting life" (John 3:16).

VIEWPOINT
RESIDENTIAL DESIGN LLC
Office: (816) 554-0400 Email: admin@viewpointdesign.net

Site Description:
**Lot 11, The Townhomes of
Chapel Ridge - 2nd Plat**

Street Address:
**805, 807, and 809 NE Algonquin St.,
Local Summit, Missouri**

Project Title:
TCR011 Triplex


General Contractor:
Kevin Higdon Construction, LLC

STATE OF MISSOURI
DENNIS HEIER
NUMBER
PE-2010061772
PROFESSIONAL ENGINEER
9/30/21

Date: 8 - 20 - AD 2021
Rev. 1: 9 - 10 - AD 2021
Rev. 2: 9 - 17 - AD 2021
Rev. 3: _____

Sheet Title:
**MAIN LEVEL
PLAN**

Sheet No.:
A-3 of 4



2" X 10" FLOOR SYSTEM
FOUNDATION
SCALE: 1/4" = 1'-0"

9'-0" FOUNDATION WALLS
(UNLESS NOTED OTHERWISE)
ON 16" X 8" STRIP FOOTINGS
(STEP WHERE GRADE REQUIRES)

UNFINISHED A: 1333 SQ. FT.
UNFINISHED B: 1333 SQ. FT.
UNFINISHED C: 1329 SQ. FT.

STEEL COLUMN & PAD FOOTING SCHEDULE	
	3" X 11 GA. STEEL COLUMN (ON 36" X 36" X 12" PAD FOOTING W/ (4) #4 BARS EACH WAY (C2530))
	3 1/2" X 11 GA. STEEL COLUMN (ON 36" X 36" X 12" PAD FOOTING W/ (4) #4 BARS EACH WAY (C2530))
	3" SCH. 40 STEEL COLUMN (ON 42" X 42" X 12" PAD FOOTING W/ (5) #4 BARS EACH WAY (C24530))
	3 1/2" SCH. 40 STEEL COLUMN (ON 48" X 48" X 12" PAD FOOTING W/ (5) #4 BARS EACH WAY (C2530))
	3 1/2" SCH. 40 STEEL COLUMN (ON 54" X 54" X 14" PAD FOOTING W/ (7) #4 BARS EACH WAY (C46530))
	3 1/2" SCH. 40 STEEL COLUMN (ON 60" X 60" X 14" PAD FOOTING W/ (8) #4 BARS EACH WAY (C50030))

PIER FOOTING SCHEDULE	
	12" Ø PIER FTG.
	16" Ø PIER FTG.
	18" Ø PIER FTG.
	24" Ø PIER FTG.

JOIST SCHEDULE	
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.
	2" X 10" R2 FLOOR JOIST Ø 16" DC.

***** = WALL BRACING PER FRAMING NOTE #1 AND PER CALCULATIONS ON SHEET S11.

FOUNDING NOTES:
1. BASEMENT LEVEL EXTERIOR WOOD-FRAMED WALLS SHALL BE SHEATHED W/ 7/16" D.S.B. APA PANELS W/ 8d COMMON NAILS Ø 6" DC. AT EDGES & Ø 12" DC. IN THE FIELD. SMALT PANEL, OR EQUAL, INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
2. 1" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX FASTENED W/ NO. 6 - 1 1/4" TYPE W OR S DRYWALL SCREWS Ø 7" DC. EDGES & FIELD. MIN. 8'-0" SECTIONS ONE SIDE OF WALL. (OR MIN. 4'-0" SECTION FOR BOTH SIDES)
3. 1" MIN. GYPSUM BOARD OVER STUDS SPACED 24" MAX FASTENED W/ NO. 6 - 1 1/4" TYPE W OR S DRYWALL SCREWS Ø 7" DC. EDGES & FIELD. MIN. 8'-0" SECTIONS ONE SIDE OF WALL. (OR MIN. 4'-0" SECTION FOR BOTH SIDES)
4. 2" X 10" R2 FLOOR JOIST AT ALL EXTERIOR AND LOAD BEARING WALLS, UNLESS NOTED OTHERWISE.
5. LVL TIES Ø 4" DC. (TYPICAL)
6. RUM STUDS THE FULL HEIGHT OF RAISED PLATE WALLS.
7. BLOCK JOISTS ABOVE BEAMS, CANTILEVERS AND LOAD BEARING WALLS WITH JOIST MATERIAL (NOT REQUIRED WITH I-JOISTS).
8. PROVIDE MULTIPLE STUDS FOR SOLID BEARING BELOW ALL BEAMS.
9. ALL DESIGNATED 2" X 6" WALLS SHALL HAVE DOUBLE KING STUDS AT DOOR AND WINDOW OPENINGS.
10. ALL UNDESIGNED WALLS SHALL BE 4" UNLESS NOTED OTHERWISE.
11. ALL WALLS TO BE FRAMED W/ MIN. STUD GRADE 2" X 4" S OR 16" DC. UNLESS NOTED OTHERWISE.
12. 1/2" Ø ANCHOR BOLTS W/ MIN. 7" EMBEDMENT Ø 48" DC. MAX. & WITHIN 6" - 12" OF END OF EACH PLATE LENGTH.
13. LVL'S SHOWN ON PLANS MAY BE REPLACED WITH 16" OF GRADE 24K-V4 GULAN BEAMS OF THE SAME DEPTH, AND THE FOLLOWING WIDTHS:
Ø 1 3/4" LVL PILES = 3 1/2" GULAN
Ø 1 3/4" LVL PILES = 5 1/2" GULAN
14. NEW FOUNDATION SHALL BEAR ON ORIGINAL SOIL WITH MINIMUM BEARING CAPACITY OF 1500 PSF. A GEOTECHNICAL ENGINEER IS RECOMMENDED FOR VERIFICATION OF THESE CONDITIONS DURING THE EXCAVATION PHASE. ENGINEER OF RECORD ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION NOT VERIFIED TO BE FOUND ON ANYTHING SHORT OF THE AFORESAID REQUIREMENTS.
15. CONTRACTOR SHALL NOTIFY ENGINEER OF RECORD BEFORE CONSTRUCTION OF ANY DEFLECTION LIMITATIONS MORE STRINGENT THAN CODE. MINIMUMS ABOVE ANY OPENINGS.

These plans and specifications are protected under federal copyright laws.
Copyright A.D. 2021 Viewpoint Residential Design, LLC.
Care and effort have gone into the creation and design of this plan. However, the designer is not an architect or engineer and construction from these plans should not be undertaken without the assistance of a construction professional, architect or engineer. Because of the nature of the design, the designer does not assume any responsibility for any damages, including structural failures, due to any deficiencies, omissions or errors in the design of blueprints. Also, site conditions may vary from those portrayed on the plan. The designer does not warrant the suitability of these plans for your specific site and application.

"For God so loved the world, that he gave his only begotten Son, that whosoever should not perish, but have everlasting life" (John 3:16)

VIEWPOINT
RESIDENTIAL DESIGN LLC

Office: (816) 554-0400 Email: admin@viewpointdesign.net

Site Description:
Lot 11, The Townhomes of Chapel Ridge - 2nd Plat
Sheet Address:
805, 807, and 809 NE Algonquin St., Lee's Summit, Missouri

Project Title:
TCR011 Triplex
General Contractor:
Kevin Higdon Construction, LLC

DATE: 9-17-2021
Rev. 1: 9-10-AD 2021
Rev. 2: 9-17-AD 2021
Rev. 3:

Sheet Title:
FOUNDATION PLAN

Sheet No.:
A-4 of 4

RESIDENTIAL SEISMIC & WIND ANALYSIS

DETERMINE WEIGHT OF HOUSE:				INPUT
				CALCULATED VALUE
LOCATION		DEAD LOAD (psf)	AREA (ft²)	WEIGHT (lbs.)
ROOF		10	6349	63490
CEILING		10	6349	63490
FIRST FLOOR		10	6349	63490
		WALL LENGTH (ft)	WALL HEIGHT (ft)	WALL UNIT WT. (psf)
FIRST FLOOR EXT. WALL DL		354.66	10	35466
		DEAD LOAD (psf)	AREA (ft²)	WEIGHT (lbs)
FIRST FLOOR INT. PARTITION WALL DL		6	6349	38094

PROJECTED AREAS (WIND DESIGN PER 115 MPH 3-SECOND GUST, EXPOSURE C AND MEAN ROOF HEIGHT <= 30 FT ASSUMED)							
FRONT-TO-BACK				SIDE-TO-SIDE			
	AREA	LOAD			AREA	LOAD	
SLOPED ROOF	555	4515		SLOPED ROOF	708	6024	
VERT. ROOF	853	10129	CUMULATIVE	VERT. ROOF	30	373	CUMULATIVE
1ST	1287	15282	30007	1ST	663.63	8250	14728
				PRESSURE (PSF) - PER ASCE CH. 6			
	SLOPED ROOF	ZONE B	9.7		ZONE C	11.3	2a (FIG. 28.6-1, ASCE7)
	WALL/VERT. ROOF	ZONE A	14.2		ZONE D	7.7	12.068
	MEAN ROOF HT., h		24				

a) If there is a walkout wall to be sheathed, determine tributary wind area and enter here. If no walkout, enter 0 for area.
 $q_{L10}=0.00256K_zK_{xt}K_dV^2$ (ASCE7-10 Velocity Pressure) $q_{L10_ASD}=0.6q_{L10}$ (Design Velocity Pressure for ASD analysis under ASCE7-10 and IRC/IBC 2012)

1ST FLOOR TRIBUTARY WEIGHT	144713
S _s (SITE GROUND MOTION - %g - FROM ASCE7 SEISMIC MAP)	12.0%
F _s (from ASCE7 Table 11.4-1)	1.6
S _{DS} (= 2/3 * S _s * F _s)	0.128
R (from ASCE7 Table 12.2-1)	6.5

SEISMIC SHEAR		
LOCATION	From ASCE7 (Eq. 12.8-1):	V (= 1.2 * S _{DS} * W / R) (lbs.)
1ST FLOOR		3420

Sheathing Location	Min. Sheathing Schedule	Fastening Schedule	Allowable Shear (#/LF)	Code Reference
Exterior (Option #1)	7/16" APA Rated Plywood/OSB	1-1/2" 18ga. Staples w/ 1" penetration @ 8" O.C. Edges, 8" O.C. Field For 24" stud spacing, 12" O.C. Field For 16" stud spacing	155	per IBC, Table 2306.3(1)
Exterior (Option #2)	7/16" APA Rated Plywood/OSB	1-1/2" 18ga. Staples w/ 1" penetration @ 4" O.C. Edges, 8" O.C. Field For 24" stud spacing, 12" O.C. Field For 16" stud spacing	230	per IBC, Table 2306.3(1)
Exterior (Option #3)	7/16" APA Rated Plywood/OSB	1-1/2" 18ga. Staples w/ 1" penetration @ 3" O.C. Edges, 8" O.C. Field For 24" stud spacing, 12" O.C. Field For 16" stud spacing	310	per IBC, Table 2306.3(1)
Exterior (Option #4)	7/16" APA Rated Plywood/OSB or shiplap panel sheathing, or 3/8" shiplap panel sheathing with tighter nail spacing	8d Common Nails w/ 1-3/8" penetration @ 6" O.C. Edges, 12" O.C. Field for 7/16" APA-rated plywood/OSB or shiplap panel sheathing OR @ 4" O.C. Edges, 12" O.C. Field for 3/8" shiplap panel sheathing	220	AF&PA SDPWS Table 4.3A
Exterior (Option #5)	7/16" APA Rated Plywood/OSB or shiplap panel sheathing, or 3/8" shiplap panel sheathing with tighter nail spacing	8d Common Nails w/ 1-3/8" penetration @ 4" O.C. Edges, 12" O.C. Field for 7/16" APA-rated plywood/OSB or shiplap panel sheathing OR @ 3" O.C. Edges, 12" O.C. Field for 3/8" shiplap panel sheathing	320	AF&PA SDPWS Table 4.3A
Exterior (Option #6)	7/16" APA Rated Plywood/OSB or shiplap panel sheathing, or 3/8" shiplap panel sheathing with tighter nail spacing and double studs at each panel edge	8d Common Nails w/ 1-3/8" penetration @ 3" O.C. Edges, 12" O.C. Field	410	AF&PA SDPWS Table 4.3A
Interior	1/2" Gypsum Board	No. 6- 1 1/4" Type W or S Screws @ 8" O.C. Edges, 12" O.C. Field	60	per IBC, Table 2306.4.4
Interior	16 Ga. Simpson/USP Type WB Steel X-Brace (or equal)	(3) 16d @ end studs & (1) 8d @ intermediate studs (per manufacturer specifications - see detail on sheet S3)	325	

EXTERIOR SHEATHING OPTION FOR FIRST FLOOR	4	WIDTH OF 1ST STORY (FT.)	117	WIDTH OF 2ND STORY (FT.)	1
EXTERIOR SHEATHING OPTION FOR BASEMENT WALLS	4	DEPTH OF 1ST STORY (FT.)	60.33	DEPTH OF 2ND STORY (FT.)	1
		BACK WALL OF GARAGE (FT.)	0		
		GAR. WALL: 1=F-B, 2=S-S	2		

	SEISMIC				WIND			
	FRONT-TO-BACK	RESISTANCE (lbs.)	SIDE-TO-SIDE	RESISTANCE (lbs.)	FRONT-TO-BACK	RESISTANCE (lbs.)	SIDE-TO-SIDE	RESISTANCE (lbs.)
1ST FLOOR	114	31920	49.5	13860	114	44688	49.5	19404

1ST FLOOR FRONT-TO-BACK 1ST FLOOR SIDE-TO-SIDE BASEMENT FRONT-TO-BACK BASEMENT SIDE-TO-SIDE	ADDITIONAL RESISTANCE REQUIRED		Anchor Bolt Spacing (in.)		16d Nail Spacing req'd at bottom plate (in.)	
	SEISMIC	WIND	diameter (in.)	0.5	1st Floor F-B	11
	0	0	Shear value (per NDS)	944	1st Floor S-S	43
	0	0	Spacing F-B (inches)	72.9		
			spacing S-S (inches)	288.0		

RESISTANCE REQUIRED IN ADDITION TO RESISTANCE PROVIDED BY EXTERIOR WALLS**						
	ADDITIONAL RESISTANCE REQUIRED (POUNDS)	PORTAL FRAMES OR PERF. SHEAR WALL RESISTANCE	INTERIOR X-BRACES (325#/BRACE)	INTERIOR WALL LENGTH W/ 1/2" GYPSUM BOARD PER TABLE (FT.)	INT. WALL LENGTH SHEATHED W/ OSB (TOTAL LENGTH, ONE SIDE, FT.)	RESISTANCE PROVIDED BY ADDITIONAL METHODS (POUNDS)
1ST FLOOR FRONT-TO-BACK	0					0
1ST FLOOR SIDE-TO-SIDE	0					0

**NOTES: 1) SEE ATTACHED CALCULATIONS FOR PORTAL FRAME OR PERFORATED SHEAR WALL RESISTANCE CAPACITIES (IF APPLICABLE).
2) SEE SHEET S1 FOR INTERIOR STEEL X-BRACE INSTALLATION. 3) INTERIOR WALLS SHEATHED WITH OSB SHALL BE ATTACHED WITH SAME STAPLE/NAILING PATTERN AS EXTERIOR OSB ON SAME FLOOR (SEE TABLE ABOVE) AND ARE ONLY APPLICABLE FOR FULL-HEIGHT SECTIONS OF 2'-8" OR LONGER
ALL LATERAL BRACING ACHIEVED AT EXTERIOR WALLS AND WALLS DIRECTLY ON FOUNDATIONS; THEREFORE, NO INTERIOR BRACING PER 2012 IRC SECTION R502.2.1 IS REQUIRE!

WIND UPLIFT ANALYSIS							
	X/12	DEGREES					
ROOF PITCH (MAX)	12	45.0	PITCH OF 6 OR LESS: EOH -13.3, E -7.2, G -5.2				
		ASCE 7					
	LENGTH (FT.)	PRESSURE (PSF)	LINEAL FT. OF OH	UPLIFT PER FT* (LBS)			
OVERHANG	1	-1.08	356.66	-1.08			
	TOTAL AREA (FT²)	ZONE E AREA (FT²)	ZONE G AREA (FT²)	PRESSURE ZN. E (PSF)	PRESSURE ZN. G (PSF)	TOTAL FORCE (LBS)	FORCE PER LINEAL FT @ PERIMETER (LBS)
MAIN ROOF**	7058.61	-534.089424	7592.699424	-1.08	-0.36	-2157	-6.1
*ALONG PERIMETER	TOTAL UPLIFT PER LINEAL FOOT ALONG EXTERIOR (POUNDS)			-7.2	UPLIFT OK		
**INSIDE EXTERIOR WALLS	RESISTANCE DUE TO DEAD WEIGHT & (3) 16d TOENAILS			251.6			

NOTE FOR CONSTRUCTION:
THE CONTINUOUS STRUCTURAL PANEL SHEATHING BRACING METHOD REQUIRES USE OF THE ABOVE TABLE FOR SHEATHING OF THE ENTIRE STRUCTURE. IN ADDITION, FRAMING MEMBERS SHALL BE @ 16" O.C. MAX., UNBLOCKED, AND W/ SHEATHING APPLIED DIRECTLY TO FRAMING MEMBERS

NOTE FOR DESIGN:
ALL WALLS USED IN THE CALCULATION OF THE RESISTANCE FOR THIS STRUCTURE SHALL HAVE A MINIMUM UNINTERRUPTED HEIGHT OF 8'-0" AND LENGTH OF 2'-8". ALLOWABLE RESISTANCES HAVE BEEN #/FT AND INCREASED BY 40% FOR WIND LOADS, PER VALUES IN 2012 IBC SECTION 2306 AND AF&PA SDPWS TABLE 4.3A. FOR EXAMPLE, 7/16" APA-RATED SHEATHING WITH 8d @ 6" & 12" HAS A SEISMIC SHEAR VALUE OF 240 A WIND SHEAR VALUE OF 335#/FT - 40% GREATER THAN THAT OF SEISMIC)

NOTE: SOIL SITE CLASS ASSUMED TO BE CLASS D. IF SITE CONDITIONS ARE DETERMINED TO BE CLASS E OR F, CONSULT ENGINEER BEFORE PROCEEDING WITH CONSTRUCTION



14718 NW DELIA STREET * PORTLAND, OREGON 97229
OFFICE: 971.645.0901 * MOBILE: 971.645.0901 *
* DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM


CLIENT: KEVIN HIGDON CONSTRUCTION

JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES OF CHAPEL RIDGE
2ND PLAT

LOCATION: 805, 807, 809 NE ALCONQUIN ST.
LEE'S SUMMIT, MISSOURI




NO.	DATE	REVISION	BY
DRAWING TITLE			
STRUCTURAL CALCULATIONS			
ENGINEER: DMH		CHECKED BY: DMH	
JOB NO. 3812		DRAWN BY: DMH	
DATE: 09-17-21			
SHEET NUMBER			




1 DAYLIGHT WALL CONSTRUCTION
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)


DAYLIGHT BASEMENT WALL SCHEDULE						
A	B	C	D	E	F	G
4'-0"	1'-6"	0'-8"	0'-5"	(2) #4	#4 VERT. @ 12" O.C.	(2) #4 HORIZ.
5'-0"	2'-0"	0'-8"	0'-7"	(2) #4	#4 VERT. @ 12" O.C.	(3) #4 HORIZ.
6'-0"	2'-6"	0'-8"	0'-10"	(3) #4	#4 VERT. @ 12" O.C.	(3) #4 HORIZ.




3 CONCRETE WALL SECTION
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)



2 COLUMN AND BEARING PAD SCHEDULE
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




5 SOLID JUMP
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)



6 REINFORCEMENT AT OPENING CORNERS AND STEP CORNERS @ INSIDE CORNERS
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

NOTE: WHERE FLOOR JOIST RUNS PARALLEL TO FDN WALL, SOLID BLOCK OUTSIDE 3 JOIST SPACES @ 36" OC ALIGNING BLOCKING WITH THE ANCHOR BOLT




7 RETURN WALL DETAIL
S2.0 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

VERTICAL REINFORCEMENT SPACING						
CONCRETE STRENGTH/GRADE REINFORCEMENT (#4 BARS)	8" THICK WALL			10" THICK WALL		
	8'	9'	10'	8'	9'	10'
3,000 PSI/ GRADE 40	24	24	16	24	24	18
3,500 PSI/ GRADE 40	24	24	16	24	24	18
3,000 PSI/ GRADE 60	24	24	16	24	24	18
3,500 PSI/ GRADE 60	24	24	16	24	24	18
HORIZONTAL REINFORCEMENT - MINIMUM GRADE 40 STEEL						
ONE BAR 12" FROM TOP OF WALL; MAX. SPACING 24" OC	4-#4	5-#4	6-#4	4-#4	5-#4	6-#4

- FOOTNOTES:
1) WALL HEIGHT IS MEASURED FROM THE TOP OF THE WALL TO THE TOP OF THE FLOOR SLAB
2) VERTICAL REINFORCEMENT FOR CONCRETE WALLS THAT ARE NOT FULL HEIGHT, AND FOR REINFORCEMENT SPACING 24" OC, REINFORCEMENT MAY BE PLACED IN THE MIDDLE OF THE WALL. OTHER WALLS SHALL HAVE VERTICAL REINFORCEMENT AS FOLLOWS:
A) 8" WALL - MINIMUM 5" FROM THE OUTSIDE FACE
B) 10" WALL - MINIMUM 6 3/4" FROM THE OUTSIDE FACE
C) EXTEND BARS TO WITHIN 8" OF THE TOP OF THE WALL
3) REINFORCEMENT CLEARANCES:
A) CONCRETE EXPOSED TO EARTH - MINIMUM 1 1/2"
B) NOT EXPOSED TO WEATHER (INTERIOR SIDE OF WALLS) - 3/4"
C) CONCRETE EXPOSED TO WEATHER (TOP CLEARANCE IN GARAGE AND DRIVEWAY SLABS) - 1 1/2"
4) HORIZONTAL REINFORCEMENT:
A) ONE BAR SHALL BE PLACED WITHIN 12" OF THE TOP OF THE WALL
B) OTHER BARS SHALL BE EQUALLY SPACED WITH SPACING NOT TO EXCEED 24" OC
C) HORIZONTAL BARS SHOULD BE AS CLOSE TO THE TENSION FACE AS POSSIBLE (INTERIOR) AND BEHIND THE VERTICAL REINFORCEMENT (I.E. 2" TOWARD THE INSIDE)
D) SUPPLEMENTAL REINFORCEMENT AT CORNERS - PLACE (1) #4 BAR 48" LONG AT 45 DEGREE ANGLE AT CORNERS OF OPENINGS. PLACE REINFORCEMENT WITHIN 6" OF THE EDGE OF INSIDE CORNERS.
5) REINFORCEMENT SHALL BE LAPPED A MINIMUM 24" AT ENDS, SPLICES, AND AROUND CORNERS.
6) AT MASONRY LEDGES THE MINIMUM WALL THICKNESS SHALL BE 3 1/2". LEDGES SHALL NOT EXCEED A DEPTH OF MORE THAN 24" BELOW THE TOP OF THE WALL. FOR WALL THICKNESSES LESS THAN 4" PROVIDE #4 BARS AT MAX. 24" OC TO WITHIN 8" OF THE TOP OF THE WALL.
7) STRAIGHT WALLS MORE THAN 5' TALL AND MORE THAN 16 FEET LONG SHALL BE PROVIDED WITH EXTERIOR BRACED RETURN WALLS. WALL LENGTH SHALL BE MEASURED USING INSIDE THE SHORTEST DIMENSION BETWEEN INTERSECTING WALLS

4 FOUNDATION WALL REINFORCEMENT TABLE
S2.0 NO SCALE



8 CONCRETE GRADE BEAM
S2.0 SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)






14718 NW DELIA STREET * PORTLAND, OREGON 97229
OFFICE: 971.645.0901 * MOBILE: 971.645.0901 *
* DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM

CLIENT: KEVIN HIGDON CONSTRUCTION
JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES OF CHAPEL RIDGE
2ND PLAT
LOCATION: 805, 807, 809 NE ALCONQUIN ST.
LEE'S SUMMIT, MISSOURI




NO.	DATE	REVISION	BY
DRAWING TITLE			
FOUNDATION DETAILS			
ENGINEER: DMH		CHECKED BY: DMH	
JOB NO. 3812		DRAWN BY: DMH	
DATE: 09-17-21			
SHEET NUMBER			


S2.0



- NOTES:
- MAX. 3'-6" IN LENGTH
 - BARS SHALL EXTEND MIN. 2'-0" PAST OPENING ON EACH SIDE





- NOTES:
- MAX. 6'-0" IN LENGTH
 - BARS SHALL EXTEND MIN. 2'-0" PAST OPENING ON EACH SIDE




1 WALKOUT FOUNDATION DETAIL
S2.1 SCALE: 1/2" = 1'-0"

(ALTERNATE)




SECTION A-A

5 EGRESS WINDOW WELL ELEVATION AND PLAN DETAILS
S2.1 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)



- NOTES:
- LAP SPLICES MIN. 24"
 - GRADE 40 BARS
 - 3500 PSI CONCRETE



- NOTES
- 3500 PSI CONCRETE
 - 24" CLASS B LAP SPLICES
 - SLAB REINFORCEMENT SHALL BE PLACED ON CHAIRS
 - 5" BOTTOM REINFORCEMENT SHALL BE EMBEDDED 4" INTO WALLS
 - GRADE 40 REINFORCEMENT



1418 NW DELIA STREET * PORTLAND, OREGON 97229
OFFICE: 971.645.0901 * MOBILE: 971.645.0901 *
* DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM

CLIENT: KEVIN HIGDON CONSTRUCTION


JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES OF CHAPEL RIDGE
2ND PLAT

LOCATION: 805, 807, 809 NE ALCONQUIN ST.
LEE'S SUMMIT, MISSOURI



NO.	DATE	REVISION	BY
DRAWING TITLE			
FOUNDATION DETAILS			
ENGINEER: DMH		CHECKED BY: DMH	
JOB NO. 3812		DRAWN BY: DMH	
DATE: 09-17-21			
SHEET NUMBER			


S2.1



1 METHOD PFH (PORTAL FRAME WITH
S3.0/HOLD-DOWNS) - PER FIGURE IRC R602.10.6.2

SCALE: $\frac{1}{4}" = 1'-0"$ (18x24) OR $\frac{3}{8}" = 1'-0"$ (24x36)


MINIMUM PANEL LENGTH FOR DETAIL 1/S3. (INCHES)					
WALL HEIGHT					
	8 FEET	9 FEET	10 FEET	11 FEET	12 FEET
SUPPORTING ROOF ONLY	16	16	16	18	20
SUPPORTING ONE STORY AND ROOF	24	24	24	27	29




3 EXTERIOR WALL SHEATHING

S3.0 PANEL ATTACHMENT

SCALE: $\frac{1}{2}" = 1'-0"$ (18x24) OR $\frac{3}{4}" = 1'-0"$ (24x36)




SHEATHING EDGE AT TOP PLATE
(SINGLE ROW OF FASTENERS)



0 SHEATHING EDGE AT TOP
AND BOTTOM PLATES

SCALE: 1" = 1'-0" (18x24) OR 1½" = 1'-0" (24x36)




2 METHOD PFG (PORTAL FRAME AT GARAGE
S3.0 DOOR) - PER FIGURE IRC R602.10.6.3

SCALE: $\frac{1}{4}" = 1'-0"$ (18x24) OR $\frac{3}{8}" = 1'-0"$ (24x36)


MINIMUM PANEL LENGTH FOR DETAIL 2/S3.0 (INCHES)				
WALL HEIGHT				
8 FEET	9 FEET	10 FEET	11 FEET	12 FEET
24	27	30	33 ^a	36 ^a

a. Maximum opening height for PFG is 10 feet in accordance with Figure R602.10.6.3, but wall height may be increased to 12 feet with pony wall




5 SHEATHING EDGE AT HORIZONTAL S3.0 FRAMING MEMBER

SCALE: 1" = 1'-0" (18x24) OR 1½" = 1'-0" (24x36)



6 SHEATHING EDGE AT PANEL S3.0 SPLICE ACROSS STUDS


SCALE: 1" = 1'-0" (18x24) OR 1½" = 1'-0" (24x36)



*NOTE: NAILING INTO TOP AND BOTTOM LAP IS IN ADDITION TO NAILING REQUIRED INTO BOTTOM LAP. FOR EXAMPLE, IF PLAN CALLS FOR NAILS @ 6" O.C. AT EDGES, BOTTOM LAP SHALL BE FASTENED AT 6" O.C AND, IN ADDITION, NAILING SHALL ALSO BE INSTALLED THROUGH TOP AND BOTTOM LAP @ 6" O.C. STAGGERED 3" FROM BOTTOM LAP NAILING

7 FASTENING INSTRUCTIONS FOR S3.0 SHIPLAP PANEL SHEATHING

SCALE: 4" = 1'-0" (18x24) OR 6" = 1'-0" (24x36)



8 GARAGE HOLD-DOWN
S3.0 STRAP INSTALLATION


SCALE: $\frac{1}{2}" = 1'-0"$ (18x24) OR $\frac{3}{4}" = 1'-0"$ (24x36)



CLIENT: KEVIN HIGDON CONSTRUCTION

JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES OF CHAPEL RIDGE
2ND PLAT

LOCATION: 805, 807, 809 NE ALGONQUIN ST.
LEE'S SUMMIT, MISSOURI



NO.	DATE	REVISION	B


DRAWING TITLE

FRAMING DETAILS

ENGINEER: DMH	CHECKED BY: DMH
JOB NO. 3812	DRAWN BY: DMH

SHEET NUMBER


S3.0



1 EXTERIOR WALL SHEATHING PANEL ATTACHMENT

S3.1 PANEL SPLICE OVER HORIZONTAL FRAMING MEMBER


SCALE: $\frac{1}{2}" = 1'-0"$ (18x24) OR $\frac{3}{4}" = 1'-0"$ (24x36)



2 EXTERIOR WALL SHEATHING PANEL ATTACHMENT


S3.1 PANEL SPLICE OCCURRING ACROSS STUDS

SCALE: $\frac{1}{2}" = 1'-0"$ (18x24) OR $\frac{3}{4}" = 1'-0"$ (24x36)



3 EXTERIOR WALL SECTION
S3.1 SCALE: $\frac{3}{4}" = 1'-0"$

SCALE: $\frac{3}{4}" = 1'-0"$




VISTA
—**STRUCTURAL**—
ENGINEERING, LLC

14718 NW DELIA STREET * PORTLAND, OREGON 97229
OFFICE: 971.645.0901 * MOBILE: 971.645.0901 *
* DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM

CLIENT: KEVIN HIGDON CONSTRUCTION

JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES OF CHAPEL RIDGE
2ND PLAT


LOCATION: 805, 807, 809 NE ALGONQUIN ST.
LEE'S SUMMIT, MISSOURI

[illegible]


NUMBER

NUMBER


S3.1




1 RIDGE FRAMING DETAIL
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




2 TRUSS CONNECTION TO EXT. WALL BEARING
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




4 STAIR AND HANDRAIL/GUARDRAIL DETAIL
S3.2 SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




9 COPED I-JOIST REINFORCEMENT
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




10 HEADER/BEAM CONNECTION OPTIONS AT OUTDOOR/OPEN SPACE
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




5 RAFTER TIES AT CEILING JOISTS PERP. TO RAFTERS
S3.2 SCALE: 3/4" = 1'-0" (18x24) OR 3/8" = 1'-0" (24x36)



7 FLOOR JOIST TO FLUSH STEEL BEAM DETAIL
S3.2 SCALE: 1" = 1'-0" (18x24) OR 1/2" = 1'-0" (24x36)




8 MAXIMUM ALLOWABLE LENGTH OF WOOD WALL STUDS (IRC TABLE 602.3.1)
S3.2



3 VAULTED RAFTER INSULATION DETAILS
S3.2 SCALE: 3/4" = 1'-0"

HEIGHT (FT.)	SPACING (INCHES O.C.)			
	24	16	12	8
SUPPORTING A ROOF ONLY				
10 OR LESS	2x4	2x4	2x4	2x4
12	2x6	2x4	2x4	2x4
14	2x6	2x6	2x6	2x4
16	2x6	2x6	2x6	2x4
18	DR	2x6	2x6	2x6
20	DR	DR	2x6	2x6
SUPPORTING ONE FLOOR AND A ROOF				
10 OR LESS	2x6	2x4	2x4	2x4
12	2x6	2x6	2x6	2x4
14	2x6	2x6	2x6	2x6
16	DR	2x6	2x6	2x6
18	DR	2x6	2x6	2x6
20	DR	DR	2x6	2x6
SUPPORTING TWO FLOORS AND A ROOF				
10 OR LESS	2x6	2x6	2x4	2x4
12	2x6	2x6	2x6	2x6
14	2x6	2x6	2x6	2x6
16	DR	2x6	2x6	2x6
18	DR	DR	2x6	2x6
20	DR	DR	DR	2x6

NOTES:
1) DR = DESIGN REQUIRED
2) UTILITY, STANDARD, STUD AND #3 GRADE LUMBER OF ANY SPECIES ARE NOT PERMITTED
3) THIS TABLE DOES NOT APPLY FOR STUDS SUPPORTING MEMBERS WITH A TRIB. LENGTH GREATER THAN 6'-0"





DECK LEDGER ATTACHMENT GUIDE

DECK JOIST SPAN	1/2" Ø GALV. LAG OR 3/8" Ø LEDGER-LOK SPACING
10'-0" OR LESS	16" OC
10'-0" - 13'-11"	12" OC OR @ 16" OC DOUBLED EVERY OTHER
14'-0" - 18'-0"	8" OC OR @ 16" OC DOUBLED


1 LEDGER ATTACHMENT
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)




2 CANTILEVER WITH DECK ATTACHMENT
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)




5 LET-IN (COVERED) DECK BEAM CONNECTION
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)




7 ALTERNATE COVERED DECK/PORCH INTERSECTION
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



8 GUARDRAIL DETAIL
S3.3

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)




3 DECK POST BASE
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)


4 REINF. POST CONNECTIONS
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



6 GUARDRAIL CONNECTION
S3.3

SCALE: 1" = 1'-0" (18x24) OR 1 1/2" = 1'-0" (24x36)



9 STAIR STRINGER DETAIL (MAX. 5' STAIR WIDTH)
S3.3

SCALE: 1/2" = 1'-0" (18x24) OR 3/4" = 1'-0" (24x36)

VISTA
STRUCTURAL
ENGINEERING, LLC

14718 NW DELIA STREET * PORTLAND, OREGON 97229
OFFICE: 971.645.0901 * MOBILE: 971.645.0901 *
* DENNIS@VISTASTRUCTURAL.COM * VISTASTRUCTURAL.COM

CLIENT: KEVIN HIGDON CONSTRUCTION
JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES OF CHAPEL RIDGE
2ND PLAT
LOCATION: 805, 807, 809 NE ALCONQUIN ST.
LEE'S SUMMIT, MISSOURI

STATE OF MISSOURI
DENNIS HEIER
NUMBER
FE-2018001772
PROFESSIONAL ENGINEER
9-17-2021

NO. DATE REVISION BY


DRAWING TITLE
**FRAMING
DETAILS**

ENGINEER: DMH	CHECKED BY: DMH
JOB NO.: 3812	DRAWN BY: DMH
DATE: 09-17-21	
SHEET NUMBER	


S3.3



- A. TWO HOUR FIRE WALL PER UL DESIGN # U366 SHOWN IN THE UL FIRE RESISTANCE DIRECTORY.
- B. INSULATE STUD CAVITIES WITH 3½" BATT INSULATION
- C. PLUMBING OR ELECTRICAL ALLOWED IN ADJOINING WALLS
- D. A SEPARATE FIRE SEPARATION WALL INSPECTION WILL BE REQUIRED
- E. ANY SHAFT WALL PENETRATIONS IN EXCESS OF 3" BUT LESS THAN 3½" TO BE FILLED WITH APPROVED FIRE CAULK OR FIRE FOAM. PENETRATIONS IN EXCESS OF 3½" TO BE FIRE PROOFED WITH OVERLAPPING LAYER OF 5/8" TYPE X SHEET ROCK, PROPERLY NAILED AND GLUED. SEAL ADDITIONAL DRYWALL PATCH COMPLETELY WITH FIRE CAULK
- F. ATTIC FIRE SEPARATION WALL: (1)-2 HOUR SHAFT WALL FIRE TEST U366



TWO LAYERS OF 5/8" THICK TYPE X GYPSUM BOARD COVERED BY 3/8" MASONITE APPLIED AT RIGHT ANGLES W/ 3" LONG TYPE W SCREWS @ 8" OC



1 HOUR SOFFIT DETAIL

NTS

CLIENT: KEVIN HIGDON CONSTRUCTION
JOB TITLE: TCR011 TRIPLEX
LOT 111, THE TOWNHOMES C
2ND PLAT
LOCATION: 805, 807, 809 NE ALGONQUIN
LEE'S SUMMIT, MISSOURI



9-17-2021

NO.	DATE	REVISION	BY
DRAWING TITLE			
FRAMING DETAILS			
ENGINEER: DMH		CHECKED BY: DMH	
JOB NO. 3812	DRAWN BY: DMH		
DATE: 09-17-21			
SHEET NUMBER			

S3.4

AREA SEPARATION WALL: (MAX HEIGHT - 44 FT)

1. FLOOR, INTERMEDIATE OR TOP OF WALL - 2 IN. WIDE CHANNEL SHAPED WITH 1-IN LONG LEGS FORMED FROM NO. 25 MSG GALV STEEL, SECURED WITH SUITABLE FASTENERS SPACED @ 24 IN OC
2. STEEL STUDS - STEEL MEMBERS FORMED FROM NO. 25 MSG GALV STEEL HAVING "H" SHAPED FLANGE SPACED @ 24 IN OC; OVERALL DEPTH 2 IN AND FLANGE WIDTH 1-3/8 IN
3. GYPSUM BOARD - 2 LAYERS OF 1 IN THICK GYPSUM WALLBOARD LINER PANELS, SUPPLIED IN NOM 24 IN WIDTHS. VERTICAL EDGES OF PANELS FRICTION FITTED INTO "H" SHAPED STUDS.
(JAMES HARDIE GYPSUM INC-TYPE HARDLINER)

PROTECTED WALL: (BEARING OR NON-BEARING WALL)

4. WOOD STUDS - NOM 2 BY 4 IN. MAX SPACING @ 24 IN. OC. STUDS CROSS-BRACED AT MIDHEIGHT WHERE NECESSARY FOR CLIP ATTACHMENT. MIN. $\frac{3}{4}$ " SEPARATION BETWEEN WOOD FRAMING AND AREA SEPARATION WALL.
5. GYPSUM BOARD - CLASSIFIED OR UNCLASSIFIED - MIN. $\frac{1}{2}$ IN. THICK, 4FT WIDE, APPLIED EITHER HORIZONTALLY OR VERTICALLY. WALLBOARD ATTACHED TO STUDS WITH 1 $\frac{1}{2}$ IN. LONG STEEL DRYWALL NAILS SPACED @ 8 IN. OC. VERTICAL JOINTS LOCATED OVER STUDS. (OPTIONAL) JOINTS COVERED WITH PAPER TAPE AND JOINT COMPOUND. NAIL HEADS COVERED WITH JOINT COMPOUND.
6. ATTACHMENT CLIPS - ALUMINUM ANGLE, 0.063 IN. THICK, MIN 2 IN. WIDE WITH MIN 2 IN. AND 2 $\frac{1}{2}$ IN. LEGS. CLIPS SECURED WITH TYPE S SCREWS $\frac{3}{8}$ IN. LONG TO "H" STUDS AND WITH TYPE W SCREWS 1 $\frac{1}{2}$ IN. LONG TO WOOD FRAMING THROUGH HOLES PROVIDED IN CLIP. CLIPS SPACED A MAX OF 10 FT OC VERTICALLY BETWEEN WOOD FRAMING AND "H" STUDS FOR SEPARATION WALLS UP TO 23 FT HIGH. FOR SEPARATION WALLS UP TO 44FT HIGH, CLIPS SPACED AS DESCRIBED ABOVE FOR THE UPPER 24 FT AND THE REMAINING WALL AREA BELOW REQUIRES CLIPS A MAX 5 FT OC VERTICALLY BETWEEN WOOD FRAMING AND "H" STUDS.

*BEARING THE UL CLASSIFICATION MARK